Form 3160-5 (February 2005)

# UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT SUNDRY NOTICES AND REPORTS ON WELLS

OCD Artesia

FORM APROVED OMB NO. 1004-0135 EXPIRES: March 31, 2007

RN	

SUNDRY NOTICES AND REPORTS ON WELLS					5. Lease Serial	No.	
Do not use this form for proposals to drill or to re-enter an						NM-77046	
	abandoned well. Use	e Form 3160-3 (APD) tor			6. If Indian, Allot	tee or Tribe Name	
	SU	IBMIT IN TRIPLICATE	RECE	IVED	7 11=14 == CA A	reement Name and	No
4 - 7 10 (- 11		ш п П он			]7. UIII OI CA AL	preement Name and	NO.
1a. Type of Well	Oil Well Gas	s Well Other	APR 1.	<b>z</b> 2010	8 Well Name an	id No.	
Name of Operator	r		NMOOD		North	Pure Gold 9 Feder	al 19
· ·	ENERGY PRODUCT	ION COMPANY, LP	NMOCD A	RTESIA	9. API Well No.		
3. Address and Tele	phone No.				30.01	5.37617	
20 N. Bro	oadway, Oklah	oma City, Ok 73102-826	0 405-235-3611			ool, or Exploratory	
4. Location of Well (	Report location clear	ly and in accordance wit	n Federal requirements)*		]	Delaware	
38 FSL 1920' FWL	M SEC 9	T23S R31E			11. County or P	arish State	
110BHL:110			<del>.</del>		Eddy	NM	
	12. CHECK	APPROPRIATE BOX(	) TO INDICATE NATURE OF			DATA	
TYPE OS SI	UBMISSION			YPE OF ACTION	l		
☑ Notice of Inte	ent	Acidize	Deepen		on (Start/Resume)		
		☐ Alter Casing	Fracture Treat	☐ Reclama		☐ Well Integr ☐ Other	rity
Subsequent F	1	☐ Casing Repair☐ Change Plans	New Construction Plug and Abandor		ete Irily Abandon	□ Onler	
Final Abando		Convert to Inject	— · · · · · · · · · · · · · · · · · · ·	☐ Water Di	sposal		
interval, a Form 3160-4 sha determined that the site is r	all be filed once testing has l ready for final inspection)	been completed Final Abandor	0 days following completion of the invo- ment Notices shall be filed only after al- ts to deviate from the origin	ll requirement, includin	g reclamation, have be	en completed, and the ope	rator has
	• •	•	ts to deviate from the origin ures, C-102, Directional Sur	•			<u>ber Penn</u>
Casing Prograi	_	es. (Cementing Proced	ures, C-102, Directional Surv	vey, Geo Frog &	BOP Schematic)	•	
Hole Size	Hole Interv	al OD Csg	Casing Interva	I. Wt	Collar	Grade	
26"	0'500'	20"	Casing Interva See CoA 0' – 500'540	94#	BTC	H-40	ļ
17 ½"	<del>50</del> 0' - 4000	)' 13 3/8"	0' – 4000'	68#	BTC	HCK-55	
12 1/4"	4,000' - 11,1		0' - 11,100'	40#	BTC	HCP-110	11
8 1/2"	11,100' - 13,10		,				
8 1/2"	11,900' - 16,5		0-16,500'	23#	Vam Top	HEC-P110	
Design Parame	eter Factors:				•		
Casing Size	Collapse	Design Factor	Burst Design Fa	actor	Tension Des	ign Factor	
20"	2.7		8.18		15.4		
13 3/8"	1.28	EE ATTACH	ED FOR <sup>5</sup>	•	4.77		İ
13 3/8" 1.2SEE ATTACHED FOR 5 9 5/8" 1.68 CONDITIONS OF APPROVAL			_	1.91		i l	
5 ½"	1.63	OUDITIONS	OF APPROVAL		2.18		Ì
14. I hereby certify t	hat the foregoing is to						
			Name Judy A. Barn	ett X8699			
Signed	ede -		Title Regulatory		Date	3/18/2010	
(This space for Fede	ral or State Office us	e)				· · · · · · · · · · · · · · · · · · ·	
Approved by			Title		Date		
Conditions of approv	al, if any:		T KIO		_ Date	1 10 100 100	
			make any department or agency or the				

\*See Instruction on Reverse Side



March 18, 2010 Page 2 NORTH PURE GOLD 9 FED #19 SEC 09-T23S-R31E DRILLED W/ PILOT HOLE (PH)

The Collapse SF for the 9 5/8 is derived using a 9 lb fluid gradient behind the casing and a minimum of a 9 lb fluid gradient in the casing. This casing will not be evacuated.

#### Mud Program

<u>Depth</u>	Mud Wt.	<u>Visc</u>	Fluid Loss	Type System
0' - 500'	8.4 - 8.8	32 - 34	N/C	FW/Gel
500' – 4,000'	9.7 - 10.0	28 - 30	N/C	Brine
4,000' - 11,100'	9.0 - 9.3	28-30	NC -40	Fresh
11,100' - 13,100'PH	10.5 - 14.0	40 - 60	12 - 8cc	Fresh
12,000-16,500'	14.0-15.0	40-60		80/20 Oil Base

BOP DESIGN: Will consist of a (10M system) triple ram type (10M psi WP) preventor and a bag-type (Hydril) preventor (10M psi WP) and a rotation head. All units will be hydraulically operated and the ram type preventor will be equipped with blind rams on top and 5" drill pipe rams on bottom. A 3M Annular BOP will be installed on the 20" surface casing and utilized continuously until total depth (~4000') is reached. The mentioned 10M preventer will be installed on the 13 3/8" casing. All BOP's will be tested with independent testers before drilling out the associated casing shoes. Prior to drilling out the 13 3/8" casing shoe, the BOP's and Hydril will be tested as per BLM Drilling Operations Order #2.

Pipe rams will be operated and checked each 24-hour period and each time the drill pipe is out of the hole. These functional tests will be documented on the daily driller's log. A 2" kill line and 3" choke line will be incorporated in the drilling spool below the ram-type BOP. Other accessory BOP equipment will include a Kelly cock, floor safety valve, choke lines and choke manifold having 10000 psi WP rating.

#### CEMENTING PROGRAM and WHIPSTOCK PROGRAM

Cement plug for the Pilot Hole

Plug Geometry:

Plug ~12,100' to 13,100' 420 sx Cl H +R-3, Yld 1.18 ct/sx

An 8 3/4" Open Hole Whipstock with a packer type anchor will be set @ ~12,000' after the cement plug has been set. Directional tools will be run and KOP will be ~12,300'. The lateral will be drilled from ~12,700' MD to 16,500' MD.

20"	Surface	Lead: 745 sx Cl C w/2% CC + 4% gel Yld 1.75 cf/sx Tail: 300 sx Cl C w/2% CC + 0.125#/sx CF Yld: 1.35 cf/sx
13 3/8" I	ntermediate	Lead: 2360 sx (35:65) Poz (Fly Ash) Premium Plus C Cement + 5% bwow Sodium Yld: 2.04 cf/sx. TOC @ surface
		Tail: 430 sx Premium Plus C Cement + 2% bwoc Calcium Chloride + 0.125#/sx CF + 56.3% FW YId: 1.35 cf/sx.
9 5/8" 1	Intermediate	Lead. 1100 sx (35:65) Poz (Fly Ash):Premium Plus C Cement + 5% bwow Sodium Chloride + 0.125#/sx CF + 6% bwoc Bentonite + 107.8% FW, VId: 2.04 cf/sy

Tail 850 sx Premium Plus Super C Cement + 5% bwow Sodium Chloride + 0.125#/sx CF + 0.4% bwoc Sodium Metasilicate + 4% bwoc MPA-5 + 64.7% FW Yld: 1.56 cf/sx.

DV Tool @ 5500'

Stage 2: Lead:w/ 450 sx 35:65 Poz: Cl H w/ 6% gel and 2% SC Yld: 1.98 cf/sx Tail w/ 150 sx 60:40 Poz Cl C w/ 1% KCL +0.125#/sx Yld: 1.56 cf/sx

5 1/2" Production

1950 sx Premium Plus H + 0.35% bwoc R-3 + 0.4% bwoc CD-32 + 1.4% Yld: 1.13 cf/sx.

**TOC** for All Strings:

Surface: 0'
Intermediate: 0'
Intermediate: 3600'
Production: 3000'

Well Name:

Operator Name: Devon Energy Corp

Job Description: Surface Casing

North Pure Gold 9 Fed #19

Date:

January 14, 2010 -



**Proposal No: 215855599A** 

#### **JOB AT A GLANCE**

500 ft Depth (TVD)

500 ft Depth (MD)

**Hole Size** 26 in

20in, 94 lbs/ft Casing Size/Weight:

**Pump Via** 20" O.D. (19.124" .I.D) 94#

8,734 gals **Total Mix Water Required** 

**Spacer** 

10 bbls Fresh Water **Density** 8.3 ppg

**Lead Slurry** 

745 sacks Class C 13.5 ppg **Density** 1.75 cf/sack Yield

**Tail Slurry** 

300 sacks Class C **Density** 14.8 ppg 1.35 cf/sack Yield

Displacement

Mud 163 bbls **Density** 8.8 ppg

North Pure Gold 9 Fed #19 Well Name:

Job Description: Surface Casing Date:



January 14, 2010

#### **WELL DATA**

#### **ANNULAR GEOMETRY**

`	ANNULAR I.D.	DEP.	TH(ft)
* 5	(in)	MEASURED	TRUE VERTICAL
	26.000 HOLE	500	500

#### **SUSPENDED PIPES**

DIAMETE	ER (in)	WEIGHT	DEP.	TH(ft)
, <b>O.</b> D.	l.D.	(lbs/ft)	MEASURED	TRUE VERTICAL
20.000	19.124	94	500	500

460 ft Float Collar set @ **Mud Density** 8.80 ppg Water Based **Mud Type** 80 ° F Est. Static Temp. 80 ° F Est. Circ. Temp.

#### **VOLUME CALCULATIONS**

400 ft	Х	1.5053 cf/ft	with	115 % excess	=	1294.4 cf
100 ft	Х	1.5053 cf/ft	with	115 % excess	=	323.9 cf
40 ft	X	1.9947 cf/ft	with	0 % excess	=	79.8 cf (inside pipe)

TOTAL SLURRY VOLUME = 1698.0 cf

303 bbls

Operator Name: Devon Energy Corp Well Name:

North Pure Gold 9 Fed #19

Job Description: Surface Casing Date:

January 14, 2010



Proposal No: 215855599A

#### **FLUID SPECIFICATIONS**

Spacer

10.0 bbls Fresh Water @ 8.34 ppg

FLUID	VOLUME CU-FT	VOLUME FACTOR	AMOUNT AND TYPE OF CEMENT
Lead Slurry	1294	<i>I</i> 1.75 =	745 sacks Class C Cement + 0.25 lbs/sack Cello Flake + 4% bwoc Bentonite + 2% bwoc Calcium Chloride + 81.3% Fresh Water
Tail Slurry	404	<i>I</i> 1.35 =	300 sacks Class C Cement + 2% bwoc Calcium Chloride + 0.125 lbs/sack Cello Flake + 56.3% Fresh Water
Dionicachant		160.4	bbla Mud @ 9 9 ppg

Displacement

163.4 bbls Mud @ 8.8 ppg

#### **CEMENT PROPERTIES**

	SLURRY NO. 1	SLURRY NO. 2
Slurry Weight (ppg)	13.50	14.80
Slurry Yield (cf/sack)	1.75	1.35
Amount of Mix Water (gps)	9.17	6.35
Estimated Pumping Time - 70 BC (HH:MM)	3:30	2:30
COMPRESSIVE STRENGTH		
8 hrs @ 80 ° F (psi)		500
12 hrs @ 80 ° F (psi)	400	1150
15 hrs @ 80 ° F (psi)	500	
24 hrs @ 80 ° F (psi)	700	2100
72 hrs @ 80 ° F (psi)		2700

Well Name: North Pure Gold 9 Fed #19

Job Description: Intermediate Casing Date:

January 14, 2010



Proposal No: 215855599A

#### **JOB AT A GLANCE**

4,000 ft Depth (TVD)

4,000 ft Depth (MD)

17.5 in **Hole Size** 

13 3/8 in, 48 lbs/ft Casing Size/Weight:

13 3/8" O.D. (12.715" .I.D) 48 # Pump Via

**Total Mix Water Required** 29,290 gals

**Spacer** 

20 bbls Fresh Water **Density** 8.3 ppg

Lead Slurry

2,360 sacks 35:65:6 Poz:Class C **Density** 12.5 ppg 2.04 cf/sack Yield

**Tail Slurry** 

60:40 Poz:Class C (MPA) 430 sacks Density 13.8 ppg Yield 1.37 cf/sack

Displacement

622 bbls Mud **Density** 10.0 ppg

Well Name: North Pure Gold 9 Fed #19
Job Description: Intermediate Casing

Job Description Date:

January 14, 2010



Proposal No: 215855599A

#### **WELL DATA**

#### **ANNULAR GEOMETRY**

ANNULAR I.D.	DEI	PTH(ft)
(in)	MEASURED	TRUE VERTICAL
19.124 CASING	500	500
17.500 HOLE	4,000	4,000

#### **SUSPENDED PIPES**

DIAMETER (in)		DIAMETER (in)   WEIGHT		TH(ft)
O.D.	I.D.	(lbs/ft)	MEASURED	TRUE VERTICAL
13.375	12.715	48	4,000	4,000

Float Collar set @	3,960 ft
Mud Density	10.00 ppg
Est. Static Temp.	112 ° F
Est. Circ. Temp.	99 ° F

#### **VOLUME CALCULATIONS**

500 ft	x	1.0190 cf/ft	with	0 % excess	=	509.5 cf
3,100 ft	Х	0.6946 cf/ft	with	100 % excess	=	4310.4 cf
400 ft	Х	0.6946 cf/ft	with	100 % excess	=	555.7 cf
40 ft	X	0.8818 cf/ft	with	0 % excess	=	35.3 cf (inside pipe)

TOTAL SLURRY VOLUME = 5410.9 cf

= 965 bbls

Operator Name: Devon Energy Corp North Pure Gold 9 Fed #19 Well Name:

Job Description: Intermediate Casing Date:

January 14, 2010



Proposal No: 215855599A

#### **FLUID SPECIFICATIONS**

Spacer	
--------	--

20.0 bbls Fresh Water @ 8.34 ppg

FLUID	VOLUME CU-FT	VOLUME FACTOR AMOUNT AND TYPE OF CEMENT
Lead Slurry	4820	<ul> <li>I 2.04 = 2360 sacks (35:65) Poz (Fly Ash):Class C Cement</li> <li>+ 5% bwow Sodium Chloride + 0.125 lbs/sack</li> <li>Cello Flake + 6% bwoc Bentonite + 0.25% bwoc</li> <li>FL-52A + 107.7% Fresh Water</li> </ul>
Tail Slurry	591	<ul> <li>I 1.37 = 430 sacks (60:40) Poz (Fly Ash):Class C Cement + 5% bwow Sodium Chloride + 0.125 lbs/sack Cello Flake + 0.1% bwoc Sodium Metasilicate + 4% bwoc MPA-5 + 65.4% Fresh Water</li> </ul>

Displacement

621.9 bbls Mud @ 10 ppg

#### **CEMENT PROPERTIES**

	SLURRY NO. 1	SLURRY NO. 2
Slurry Weight (ppg)	12.50	13.80
Slurry Yield (cf/sack)	2.04	1.37
Amount of Mix Water (gps)	11.24	6.43
Estimated Pumping Time - 70 BC (HH:MM)	5:30	4:00
COMPRESSIVE STRENGTH		
8 hrs @ 107 ° F (psi)		500
12 hrs @ 107 ° F (psi)		1000
24 hrs @ 107 ° F (psi)		1900
72 hrs @ 107 ° F (psi)		2700
12 hrs @ 112 ° F (psi)	300	
24 hrs @ 112 ° F (psi)	650	
72 hrs @ 112 ° F (psi)	900	

ACTUAL CEMENT VOLUME MAY VARY BASED ON CALIPER.

Well Name: North Pure Gold 9 Fed #19
Job Description: 2nd Intermediate Casing

Date:

January 14, 2010



Proposal No: 215855599A

#### **JOB AT A GLANCE**

**Depth (TVD)** 11,100 ft

**Depth (MD)** 11,100 ft

Hole Size 12.25 in

Casing Size/Weight: 9 5/8 in, 53.5 lbs/ft

**Pump Via** 9 5/8" O.D. (8.535" .I.D) 53.5 #

Total Mix Water Required 24,481 gals

Stage No: 1 Float Collar set @ 11,060 ft

Spacer

Fresh Water 20 bbls
Density 8.3 ppg

**Spacer** 

Surebond III 1,000 gals
Density 9.4 ppg

**Spacer** 

Fresh Water 10 bbls
Density 8.3 ppg

**Lead Slurry** 

 35:65:6 Poz:Class H
 1,100 sacks

 Density
 12.5 ppg

 Yield
 1.98 cf/sack

**Tail Slurry** 

Super C Modified850 sacksDensity13.3 ppgYield1.56 cf/sack

**Displacement** 

Displacement Fluid 783 bbls

Well Name: North Pure Gold 9 Fed #19
Job Description: 2nd Intermediate Casing

Date:

January 14, 2010



Proposal No: 215855599A

#### **JOB AT A GLANCE** (Continued)

Stage No: 2	Stage Collar set @	5,500 ft
C		

**Spacer** 

Fresh Water 20 bbls
Density 8.3 ppg

**Lead Slurry** 

 35:65:6 Poz:Class C
 450 sacks

 Density
 12.5 ppg

 Yield
 2.04 cf/sack

**Tail Slurry** 

 60:40 Poz:Class C (MPA)
 150 sacks

 Density
 13.8 ppg

 Yield
 1.37 cf/sack

**Displacement** 

Displacement Fluid 389 bbls

Well Name: North Pure Gold 9 Fed #19
Job Description: 2nd Intermediate Casing

Date:

January 14, 2010



**Proposal No: 215855599A** 

#### **WELL DATA**

#### **ANNULAR GEOMETRY**

ANNULAR I.D.	DEPTH(ft)		
(in)	MEASURED	TRUE VERTICAL	
12.715 CASING	4,000	4,000	
12.250 HOLE	11,100	11,100	

#### **SUSPENDED PIPES**

DIAMETI		WEIGHT	DEPTH(ft)	
O.D.	I.D.	(ibs/ft)	MEASURED	TRUE VERTICAL
9.625	8.535	53.5	11,100	11,100

STAGE: 1 Float Collar set @

Mud Density9.10 ppgMud TypeWater BasedEst. Static Temp.163 ° FEst. Circ. Temp.136 ° F

#### **VOLUME CALCULATIONS**

3,500 ft	Х	0.3132 cf/ft	with	100 % excess	=	2192.3 cf
2,100 ft	Х	0.3132 cf/ft	with	100 % excess	=	1315.4 cf

40 ft x 0.3973 cf/ft with 0% excess = 15.9 cf (inside pipe)

TOTAL SLURRY VOLUME = 3523.6 cf

= 628 bbls

11,060 ft

STAGE: 2 Stage Collar set @ 5,500 ft

Mud Density9.10 ppgMud TypeWater BasedEst. Static Temp.121 ° F

Est. Circ. Temp. 107 ° F

#### **VOLUME CALCULATIONS**

500 ft	Х	0.3765 cf/ft	with	0 % excess	=	188.3 cf
1,171 ft	Х	0.3132 cf/ft	with	100 % excess	=	733.6 cf
329 ft	Х	0.3132 cf/ft	with	100 % excess	=	206.0 cf

TOTAL SLURRY VOLUME = 1127.8 cf

= 201 bbls

Well Name:

Operator Name: Devon Energy Corp

North Pure Gold 9 Fed #19 Job Description: 2nd Intermediate Casing

Date:

January 14, 2010



Proposal No: 215855599A

#### **FLUID SPECIFICATIONS**

STAGE NO.: 1

20.0 bbls Fresh Water @ 8.34 ppg Spacer

Spacer 1,000.0 gals Surebond III @ 9.35 ppg

Spacer 10.0 bbls Fresh Water @ 8.34 ppg

**VOLUME VOLUME** AMOUNT AND TYPE OF CEMENT **FACTOR FLUID** CU-FT Lead Slurry 2192 1 1.98 = 1100 sacks (35:65) Poz (Fly Ash): Class H Cement + 0.3% bwoc R-3 + 2% bwow Sodium Chloride + 0.125 lbs/sack Cello Flake + 0.4% bwoc FL-52A + 6% bwoc Bentonite + 104.2% Fresh Water Tail Slurry 1331 I 1.56 = 850 sacks (15:61:11) Poz (Fly Ash):Class C Cement: CSE-2 + 1% bwow Potassium Chloride + 0.75% bwoc EC-1 + 0.4% bwoc CD-32 + 2 lbs/sack LCM-1 + 0.6% bwoc FL-25 + 0.6% bwoc

FL-52A + 0.125 lbs/sack Cello Flake + 73.3%

Fresh Water

Displacement

782.7 bbls Displacement Fluid

#### **CEMENT PROPERTIES**

	SLURRY NO. 1	SLURRY NO. 2
Slurry Weight (ppg)	12.50	13.30
Slurry Yield (cf/sack)	1.98	1.56
Amount of Mix Water (gps)	10.87	7.65
Estimated Pumping Time - 70 BC (HH:MM)	5:30	4:00
Free Water (mls) @ ° F @ 90 ° angle		0.0
Fluid Loss (cc/30min) at 1000 psi and ° F		50.0
COMPRESSIVE STRENGTH		
12 hrs @ 167 ° F (psi)	350	900
24 hrs @ 167 ° F (psi)	700	2100
72 hrs @ 167 ° F (psi)	100	2600

Operator Name: Devon Energy Corp
Well Name: North Pure Gold 9 Fed #19
Job Description: 2nd Intermediate Casing

Date:

January 14, 2010



Proposal No: 215855599A

#### **FLUID SPECIFICATIONS (Continued)**

STAGE NO.: 2

Spacer 20.0 bbls Fresh Water @ 8.34 ppg

Lead Slurry 922 / 2.04 = 450 sacks (35:65) Poz (Fly Ash):Class C Cement +

6% bwoc Bentonite + 0.4% bwoc FL-52A + 5% bwow Sodium Chloride + 0.125 lbs/sack Cello

Flake + 107.7% Fresh Water

Tail Slurry 206 / 1.37 = 150 sacks (60:40) Poz (Fly Ash):Class C Cement +

5% bwow Sodium Chloride + 0.125 lbs/sack Cello

Flake + 0.1% bwoc Sodium Metasilicate + 4%

bwoc MPA-5 + 65.4% Fresh Water

Displacement Supplement Supplement Fluid

**CEMENT PROPERTIES** 

	SLURRY NO. 1	SLURRY NO. 2
Slurry Weight (ppg).	12.50	13.80
Slurry Yield (cf/sack)	2.04	1.37
Amount of Mix Water (gps)	11.24	6.43
Estimated Pumping Time - 70 BC (HH:MM)	4:00	3:30
Free Water (mls) @ ° F @ 90 ° angle		
Fluid Loss (cc/30min) at 1000 psi and ° F		
COMPRESSIVE STRENGTH		
12 hrs @ 106 ° F (psi)	400	
15 hrs @ 106 ° F (psi)	500	
24 hrs @ 106 ° F (psi)	750	
12 hrs @ 121 ° F (psi)		1700
24 hrs @ 121 ° F (psi)		2500

CEMENT VOLUMES WILL VARY BASED ON CALIPER.

North Pure Gold 9 Fed #19 Well Name:

Job Description: Long String

Date:

January 14, 2010



Proposal No: 215855599A

#### **JOB AT A GLANCE**

12,750 ft Depth (TVD)

16,500 ft Depth (MD)

8.5 in **Hole Size** 

5 1/2 in, 23 lbs/ft Casing Size/Weight:

5 1/2" O.D. (4.670" .I.D) 23 # **Pump Via** 

**Total Mix Water Required** 9,003 gals

**Spacer** 

50 bbls MCS-3 15.5 ppg **Density** 

**Cement Slurry** 

1,950 sacks Class H **Density** 16.0 ppg 1.13 cf/sack Yield

**Displacement** 

349 bbls **Displacement Fluid** 

North Pure Gold 9 Fed #19 Well Name:

Job Description: Long String Date:

January 14, 2010



Proposal No: 215855599A

#### **WELL DATA**

#### **ANNULAR GEOMETRY**

ANNULAR I.D.	DEPTH(ft)			
(in)	MEASURED	TRUE VERTICAL		
8.535 CASING	11,100	11,100		
8.500 HOLE	16,500	12,750		

#### **SUSPENDED PIPES**

DIAMET	ER (in)	WEIGHT	DEP.	ΓH(ft)
O.D.	I.D.	(lbs/ft)	MEASURED	TRUE VERTICAL
5.500	4.670	23	16,500	12,750

Float Collar set @ 16,460 ft 15.00 ppg **Mud Density** Oil Based **Mud Type** 182 ° F Est. Static Temp. 178 ° F Est. Circ. Temp.

#### **VOLUME CALCULATIONS**

500 ft	Х	0.2323 cf/ft	with	0 % excess	=	116.2 cf
5,400 ft	X	0.2291 cf/ft	with	70 % excess	=	2105.3 cf
40 ft	Х	0.1189 cf/ft	with	0 % excess	=	4.8 cf (inside pipe)

2226.2 cf TOTAL SLURRY VOLUME = 397 bbls Operator Name: Devon Energy Corp
Well Name: North Pure Gold 9 Fed #19

Job Description: Long String
Date: January 14, 2010

Proposal No: 215855599A

#### **FLUID SPECIFICATIONS**

Spacer 50.0 bbls MCS-3 + 383 lbs/bbl Barite, Bulk + 2 gal/bbl

SS-2 + 13.88 lbs/bbl Bentonite @ 15.5 ppg

**VOLUME VOLUME** 

FLUID CU-FT FACTOR AMOUNT AND TYPE OF CEMENT

Cement Slurry 2226 / 1.13 = 1950 sacks Premium Plus H Cement + 0.4% bwoc

R-21 + 1% bwoc CD-32 + 0.8% bwoc FL-63 +

0.5% bwoc BA-11 + 0.7% bwoc Sodium

Metasilicate + 41% Fresh Water

Displacement 348.7 bbls Displacement Fluid

**CEMENT PROPERTIES** 

	SLURRY NO. 1
Slurry Weight (ppg)	16.00
Slurry Yield (cf/sack)	1.13
Amount of Mix Water (gps)	, 4.62
Estimated Pumping Time - 70 BC (HH:MM)	5:00
Free Water (mls) @ 178 ° F @ 90 ° angle	0.0
Fluid Loss (cc/30min) at 1000 psi and 178 ° F	40.0
COMPRESSIVE STRENGTH	
12 hrs @ 187 ° F (psi)	1600
24 hrs @ 187 ° F (psi)	2400
72 hrs @ 187 ° F (psi)	3200

CEMENT VOLUMES WILL VARY BASED ON CALIPER.

TEST SPACER SYSTEM WITH OIL BASED MUD.

BATCH MIX SPACER SYSTEM.

Well Name: North Pure Gold 9 Fed #19

Job Description: Plug Back and Whipstock Plug

Date:

January 14, 2010



Proposal No: 215855599A

#### **JOB AT A GLANCE**

**Depth (TVD)** 13,100 ft

**Depth (MD)** 13,100 ft

Hole Size 8.5 in

Casing Size/Weight: 9 5/8 in, 53.5 lbs/ft

Pump Via Casing 4 1/2" O.D. (3.920" .l.D) 13.5 #

Total Mix Water Required 3,808 gals

Plug No: 1

Spacer

Mud Clean II 15 bbls

**Cement Slurry** 

Class H 550 sacks

Density 15.6 ppg

Yield 1.18 cf/sack

Plug No: 2

**Spacer** 

Mud Clean II15 bblsDensity8.3 ppg

**Cement Slurry** 

 Class H
 250 sacks

 Density
 17.0 ppg

 Yield
 0.99 cf/sack

Well Name:

Operator Name: Devon Energy Corp

North Pure Gold 9 Fed #19 Job Description: Plug Back and Whipstock Plug

Date:

January 14, 2010



Proposal No: 215855599A

#### **FLUID SPECIFICATIONS**

Spacer

= 15.0 bbls Mud Clean II

PLUG NO.	VOLUME CU-FT	_	VOLUME FACTOR	AMOUNT AND TYPE OF CEMENT
1	649	1	1.18	= 550 sacks Premium Plus H Cement + 0.15% bwoc R-3 + 46.4% Fresh Water
Spacer				= 15.0 bbls Mud Clean II @ 8.34 ppg
2	248	1	.99	= 250 sacks Premium Plus H Cement + 0.15% bwoc R-21 + 0.05% bwoc ASA-301 + 1% bwoc CD-32 + 33.1% Fresh Water

#### **CEMENT PROPERTIES**

	PLUG NO. 1	PLUG NO. 2
Slurry Weight (ppg)	15.60	17.00
Slurry Yield (cf/sack)	1.18	0.99
Amount of Mix Water (gps)	5.23	3.73
Estimated Pumping Time - 70 BC (HH:MM)	4:00	5:00
COMPRESSIVE STRENGTH		
12 hrs @ 185 ° F (psi)	1500	3300
24 hrs @ 185 ° F (psi)	2700	5500
72 hrs @ 185 ° F (psi)	3500	

#### **PLUG GEOMETRY**

	PLUG TOP		PLUG Bottom	
1	11750 ft	to	13100 ft	with 8.5 inch Open Hole PDSqT = 160 ° F PDST = 184.8 ° F
2	11250 ft	to	11750 ft	with 8.5 inch Open Hole PDSqT = 150 ° F

PLUG #1 - 11750' - 13100'

PUMP 550 SACK PLUG (20% EXCESS OVER TRUE HOLE).

PLUG #2 - 11250' - 11750'

PUMP 250 SACKS FOR WHIPSTOCK PLUG (20% EXCESS OVER TRUE HOLE)

DISTRICT I
1625 N. French Dr., Hobbs, NM 88240
DISTRICT II
1301 W. Grand Avenue, Artesia, NM 88210

1000 Rio Brazos Rd., Aztec, NM 87410

1220 S. St. Francis Dr., Santa Fe, NM 87505

DISTRICT III

DISTRICT IV

State of New Mexico
Energy, Minerals and Natural Resources Department

Form C-102 Revised October 15, 2009

Submit one copy to appropriate
District, Office

#### OIL CONSERVATION DIVISION

1220 South St. Francis Dr. Santa Fe, New Mexico 87505

WELL LOCATION AND ACREAGE DEDICATION PLAT


☐ AMENDED REPORT

API Number	Pool Code	Pool Name UPPER PENN S	SHALE
Property Code		ty Name DLD "9" FEDERAL	Well Number
ogrid No. 6137	-	Dr Name JCTION COMPANY, L.P.	Elevation 3349'
	Surface	Location	

#### UL or lot No. Section Township Range Lot Idn Feet from the North/South line Feet from the East/West line County

М	9	23 S	31 E		710	SOUTH	710	WEST	EDDY		
Bottom Hole Location If Different From Surface											
UL or lot No.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County		
D	9	23 S	31 E		660	NORTH	710	WEST	EDDY		
Dedicated Acre	s Joint o	r Infill Co	nsolidation	Code Or	der No.		· <u> </u>				
<u>,32</u> 0											

NO ALLOWABLE WILL BE ASSIGNED TO THIS COMPLETION UNTIL ALL INTERESTS HAVE BEEN CONSOLIDATED OR A NON-STANDARD UNIT HAS BEEN APPROVED BY THE DIVISION



DISTRICT I
1625 N. French Dr., Hobbs, NM 88240
DISTRICT II

1301 W. Grand Avenue, Artesia, NM 88210

State of New Mexico Energy, Minerals and Natural Resources Department

Form C-102 Revised October 15, 2009

Submit one copy to appropriate

District Office

#### OIL CONSERVATION DIVISION

1220 South St. Francis Dr. Santa Fe, New Mexico 87505

DISTRICT IV

DISTRICT III

1220 S. St. Francis Dr., Santa Fe, NM 87505

1000 Rio Brazos Rd., Aztec, NM 87410

#### WELL LOCATION AND ACREAGE DEDICATION PLAT

□ AMENDED REPORT

API Number	Pool Code	Pool Name UPPER PENN S			
Property Code	<u>-</u>	rty Name OLD "9" FEDERAL	Well Number 19H		
OGRID No. 6137:	-	tor Name OUCTION COMPANY, L.P.	Elevation 3349'		


#### Surface Location

1	UL or lot No.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
	М	9	23 S	31 E		710	SOUTH	710	WEST	EDDY


#### Bottom Hole Location If Different From Surface

UL or lot No.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
D	9	23 S	31 E		660	NORTH	710	WEST	EDDY
Dedicated Acres   Joint or Infill   Consolidation Code		Code Or	der No.						
,320									

NO ALLOWABLE WILL BE ASSIGNED TO THIS COMPLETION UNTIL ALL INTERESTS HAVE BEEN CONSOLIDATED OR A NON-STANDARD UNIT HAS BEEN APPROVED BY THE DIVISION



9, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M., SECTION EDDY COUNTY, NEW MEXICO.



Directions to Location:

FROM THE MILE MARKER 13 OF HWY 18; GO 100' WEST TO LEASE ROAD, ON LEASE ROAD GO NORTH 0.6 MILES TO THE NPG 17 #2 LOCATION, AND CONTINUE NORTH 0.7 MILES THENCE EAST 0.3 MILES TO PROPOSED LOCATION AT THE NPG 9 #2 LOCATION.

BASIN SURVEYS P.O. BOX 1786 -HOBBS, NEW MEXICO

W.O. Number: 21892 Drawn By: J. SMALL


11-02-2009 Disk: JMS 200 200 400 FEET HHHH SCALE: 1" = 200'

### DEVON ENERGY PRODUCTION COMPANY, L.P.

REF: NORTH PURE GOLD "9" FEDERAL #19H / WELL PAD TOPO THE NORTH PURE GOLD "9" FEDERAL #19H LOCATED 710' FROM THE SOUTH LINE AND 710' FROM THE WEST LINE OF SECTION 9, TOWNSHIP 23 SOUTH, RANGE 31 EAST,

N.M.P.M., EDDY COUNTY, NEW MEXICO.

Sheet Sheets Survey Date: 11-02-2009




NORTH PURE GOLD "9" FEDERAL #19H Located 710' FSL and 710' FWL Section 9, Township 23 South, Range 31 East, N.M.P.M., Eddy County, New Mexico.



P.O. Box 1786 1120 N. West County Rd. Hobbs, New Mexico 88241 (575) 393—7316 — Office (575) 392—2206 — Fax basinsurveys.com

W.O. 1	lumber:	JMS	21892 <sup>.</sup>	
Survey	/ Date:	10-3	30-2009	
Scale:	1" = 2	000,		ď
Date	11-02-	-2009		1

DEVON ENERGY PRODUCTION COMPANY, L.P.




NORTH PURE GOLD "9" FEDERAL #19H Located 710' FSL and 710' FWL Section 9, Township 23 South, Range 31 East, N.M.P.M., Eddy County, New Mexico.



P.O. Box 1786 1120 N. West County Rd. Hobbs, New Mexico 88241 (575) 393-7316 - Office (575) 392-2206 - Fax basinsurveys.com

W.O. Number:	JMS	21892	_
Survey Date:	10-3	30-2009	1
Scale: 1" = 2	Miles		T T
Date: 11-02-	-2009		7 /

DEVON ENERGY PRODUCTION COMPANY, L.P.



NORTH PURE GOLD "9" FEDERAL #19H Located 710' FSL and 710' FWL Section 9, Township 23 South, Range 31 East, N.M.P.M., Eddy County, New Mexico.



P.O. Box 1786 1120 N. West County Rd. Hobbs, New Mexico 88241 (575) 393-7316 — Office (575) 392-2206 — Fax basinsurveys.com W.O. Number: JMS 21892

Scale: 1" = 2000'

YELLOW TINT - USA LAND
BLUE TINT - STATE LAND
NATURAL COLOR - FEE LAND







Project: Eddy Co., New Mexico (Nad 83) Site: North Pure Gold 9 Fed #19H Well: North Pure Gold 9 Fed #19H Wellbore Lateral #1 Design: Design #1

SECTION DETAILS										
Sec 1 2 3 4	MD 0 00 12045 04 12945 04 16332.08	Inc 0 00 0 00 90 00 90 00	Azi 0 00 0 00 0 00 0 00	TVD 0 00 12045 04 12618 00 12618 00	+N/-S 0 00 0 00 572 96 3960 00	+E/-W 0.00 0.00 0.00 0.00	DLeg 0 00 0 00 10 00 0 00	TFace 0.00 0.00 0.00 0.00 0.00	VSec 0 00 0 00 572.96 3960 00	Target PBHL - TD (NPG9F19)

ANNOTATIONS MD 12045 00 12945 00 TVD 12045 00 12618,00 Annotation KOP - Build 10"/100" EOC - Hold I 90 0" @ A 0 0"

WELLBORE TARGET DETAILS (MAP CO-ORDINATES AND LATILONG)										
Name	TVD	+N/-\$	+E/-W	Northing	Easting	Latitude	Longitude	Shape		
PBHL - TD (NPG9F19)	1261800	3960 00	0 00	479355 63	723708 54	32° 18' 59 186 N	103° 44′ 34 746 W	Point		

WELL DETAILS North Pure Gold 9 Fed #19H Ground Level WELL @ 3369 00ft (Original Well Elev) +E/-W Easting Latittude 723708 54 32° 18' 20 000 N Longitude 103° 44' 35 000 W 000

PROJECT DETAILS: Eddy Co., New Mexico (Nad 83)

Geodetic System US State Plane 1983
Datum. North American Datum 1983
Ellipsold GRS 1980
Zone New Mexico Eastern Zone
System Datum: Mean Sea Level

Pfan Design#1 (North Pure Gold 9 Fed #19H/Lateral #1)										
Created By: Mike Starkey	Date 17.55, January 14 2010									
Checked	Date									
Reviewed										
Approved	Date									

3000

2200 2000 1800

> 1200 1000


> > EOC - Hold I 90 0° @ A0 0°

-800 -1400 -1200 -1000 -800

LEASE LINE West(-)/East(+) (200 f/in) Azimuths to Grid North True North -0 31° Magnetic North, 7,51° Magnetic Field Strength 48819 9snT Dip Angle 60 29° Date 1/14/2010 Modet IGRF200510

660' from LEASE LINE

PBHL - TD (NPG9F19)





## **Devon Energy**

Eddy Co., New Mexico (Nad 83) North Pure Gold 9 Fed #19H North Pure Gold 9 Fed #19H

Lateral #1

Plan: Design #1

# **Standard Planning Report**

14 January, 2010





Design #1

New Mexico Eastern Zone

Design:

Map Zone:

#### **CUDD Drilling & Measurement Services**

#### Planning Report



EDM 2003.21 Single User Db Site North Pure Gold 9 Fed #19H Database: Local Co-ordinate Reference: Company: Devon Energy WELL @ 3369 00ft (Original Well Élev) TVD Reference: , Eddy Co., New Mexico (Nad 83) Project: MD Reference: WELL @ 3369.00ft (Original Well Elev) North Pure Gold 9 Fed #19H Site: North Reference: Grid

Well: North Pure Gold 9 Fed #19H Survey Calculation Method: Minimum Curvature
Wellbore: Lateral #1

Project Eddy Co., New Mexico (Nad 83)

 Map System:
 US State Plane 1983
 System Datum:
 Mean Sea Level

 Geo Datum:
 North American Datum 1983

 Site
 North Pure Gold 9 Fed #19H, Sec 9, T-23S, R-31E

 Site Position:
 Northing:
 475,395.64 ft
 Latitude:
 32° 18' 20.000 N

 From:
 Lat/Long
 Easting:
 723,708.54 ft
 Longitude:
 103° 44' 35.000 W

Position Uncertainty: 0.00 ft Slot Radius: " Grid Convergence: 0.32 °

North Pure Gold 9 Fed #19H Well Well Position +N/-S 0 00 ft Northing: 475,395.64 ft Latitude: 32° 18' 20.000 N Easting: 723,708.54 ft Longitude: 103° 44' 35.000 W +E/-W 0.00 ft Wellhead Elevation: Position Uncertainty 0 00 ft 3,369.00 ft **Ground Level:** 3,349.00 ft

Lateral #1 Wellbore Declination Dip Angle Field Strength Magnetics Model Name Sample Date (°) (°) (nT) IGRF200510 60.29 1/14/2010 7.83 48.820

Design **Audit Notes:** 0.00 Version: Phase: PLAN Tie On Depth: Vertical Section: Depth From (TVD) +N/-S +E/-W Direction (ft) (ft) (ft) (°) 0.00 0.00 0.00 0.00

Measured			Vertical	i		Dogleg	Build	Turn		•
Depth	Inclination	Azimuth	Depth	+N/-S	+E/-W	Rate	Rate	Rate	TFO	
(ft)	(°)	(°)	(ft)	(ft)	(ft)	(°/100ft)	(°/100ft)	(º/100ft)	(°)	Target
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0 00	0.00	
12,045.04	0 00	0 00	12,045.04	0.00	0.00	0.00	0.00	0.00	0.00	
12,945.04	90.00	0.00	12,618.00	572.96	0.00	10.00	10.00	0.00	0.00	
16.332.08	90.00	0 00	12,618.00	3,960.00	0.00	0.00	0.00	0 00	0.00 PBI	HL - TD (NPG9



#### **CUDD Drilling & Measurement Services**

Planning Report



Database: Company: Project: Site:

Wellbore:

Design:

Well:

EDM 2003.21 Single User Db

Devon Energy

Design #1

Eddy Co , New Mèxico (Nad 83) North Pure Gold 9 Fed #19H North Pùre Gold 9 Fed #19H Lateral #1 Local Co-ordinate Reference:

TVD Reference: MD Reference:

North Reference: Survey Calculation Method:

the state of the s

Site North Pure Gold 9 Fed #19H

WELL @ 3369.00ft (Original Well Elev) WELL @ 3369 00ft (Original Well Elev)

Grid

Minimum Curvature

Planned Survey

Measured			Vertical	*	371. fe u	Vertical	Dogleg	Build	Turn
Depth   (ft)	nclination (°)	Azimuth · (°)	Depth (ft)	+N/-Ş (ft)	+E/-W (ft)	Section (ft)	Rate , (°/100ft)	Rate (°/100ft)	Rate (°/100ft)
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
11,245.00	0.00	0.00	11,245.00	0 00	0 00	0.00	0.00	0.00	. 0.00
Wolfcamp						•		-	
12,045.00	0.00	0.00	12,045.00	0.00	0.00	0.00	0.00	0.00	0.00
KOP - Build 10	//100'			•			*		,
12,045.04	0.00	0.00	12,045.04	0.00	0.00	0.00	0 00	0.00	0.00
12,142 47	9.74	0.00	12,142.00	8.26	0.00	8 26	10.00	10.00	0.00
Wolfcamp Hot	Shale Top		3	•	•			•	
12,248.23	20.32	0.00	12,244.00	35.65	0,00	35.65	10.00	10.00	0.00
Wolfcamp Hot	Shale Btm		2.0	·	•		,		•
12,601.40	55 64	0.00	12,518.00	249.55	0.00	249.55	10.00	. 10 00	0 00
Top Penn Shale	9					•			
12,945.00	90.00	0.00	12,618.00	572.92	0.00	572.92	10.00	10 00	0.00
EOC - Hold I:90	.0* @ A:0.0*								
12,945.04	90.00	0 00	12,618 00	572 96	0.00	572.96	10.00	10.00	0.00
16,332.08	90.00	0 00	12,618 00	3,960.00	0.00	3,960.00	0.00	0.00	0 00

Formations Measured	Vertical	این دهر د درمه هرچه همی این درستان و داشتان او اینان در	Dip
Depth (ft)	Depth (ft) Name	Lithology	Dip Direction (°) (°)
11,245 00	11,245.00 Wolfcamp	i nito de Bourre Noval de la destruir vitt una Entrada, deblockraftsdebustetsdebir demokration de volume et no	0.00
12,142 47	12,142.00 Wolfcamp Hot Shale Top		0.00
12,248 23	12,244.00 Wolfcamp Hot Shale Btm		0.00
12,601.40	12,518.00 Top Penn Shale		0.00
	12,924 00 Strawn		0.00

Plan Annotatio	ns	the dr. winds are agreed in a secondary					n service of the contract of the second of the contract of the	years an house, on on the order
	Measured	Vertical	Local Cool		talanta a ana sa	e er skodenkis e	an a a angangan ( pranama). P	The state of the s
	Depth (ft)	Depth (ft)	+N/-S (ft)	+E/-W (ft)	Comment		* - * * * * * * * * * * * * * * * * * *	* , * *
The state of the s	12,045.00 12,945.00	,	0.00 572.92	0.00 0.00	KOP - Build 10* EOC - Hold I:90		When a view to an out of bride is an	e one a erroren en en contenue de tre envenenmen

**GEOLOGIC PROGNOSIS** DATE: 2//1/2010 COMPANY. DEVON ENERGY API# POOL: NORTH PURE GOLD WELL NAME: North Pure Gold 9 Fed #19H SURFACE LOCATION Sec 09-23S-31E, 660 FSL & 710 FWL COUNTY: EDDY BOTTOM HOLE LOCATION Sec 09-23S-31E, 660 FNL & 710 FWL, STATE: NEW MEXICO PRIMARY OBJECTIVE · UPPER PENN SHALE KB(EST.) 3369 GL 3349 OTHER POTENTIAL ZONES. UPPER WOLFCAMP SHALE PILOT TD 13,100' LATERAL TD. 16,500' ESTIMATED BHP/BHT 9700 psi 180degF DEEPEST FORMATION STRAWN DEVON FIELD GEOLOGIST CHARLIE WILLEY CELLULAR: 405-388-5256 ADDRESS 20N BROADWAY, OKLAHOAM CITY, OK 73102 OFC. PHONE 405-552-7904 EMAIL charle willey@dvn com HM PHONE. DEVON GEOLOGIST JASON CURRIE CELLULAR 405-209-4610 ADDRESS: 20N\_BROADWAY, OKLAHOAM CITY, OK 73102 OFC PHONE. 405-552-3319 HM PHONE 405-728-5893 EMAIL: jason cur c@dvn com  ${\tt MUDLOOGING\ CO: \underline{DISCOVERY\ LOGGING\ INC\ (WEATHERFORD\ SURFACE\ LOGGING)}}$ OFC PHONE: 432-687-1823 ADDRESS: P.O BOX 80531 CITY: MIDLAND STATE: TEXAS ,79708 MUDLOGGING PROGRAM 2 MAN SERVICE CASING TO TD MORNING REPORT AT 8AM OKLAHOMA CITY TIME TO JASON CURRIE. Lithology(major and minor constituents), Shows, Hotwire, Chromatograph C1-C5 DRILL TIME 2' Drill Time From Geolograph or Pason SAMPLES: 10' intervals - Formation Cuttings caught by Mudloggers CORING. JUPE 2 ME NO. 89 ALM WHY-, THE CORE 2,600-12 97 OF (000.) DST PROGRAM. POSSIBLE LOGGING PROGRAM. SCHLUMBERGER 6 LOGGING RUNS (SEE PAGE 2) DEPTH TO WATER: MUD PROGRAM. NOVA MUD CO --- 'Cut Brine w/Nitrate Marker, Chlorides > 30,000ppm KNOWN OR POTENTIAL HAZARDS: REMARKS No known hazards GEOLOGIC MARKERS

K.3 3369 PROGNOSIS					MUDLOG							1	
							-	ŀ		E-LC		Г	
FORMATION ALLUVIUM	MD	Subsea	TVD	MD_	Subsoa	TVD	hi/lo	ŀ	MD	Subsea	TVD	hı/lo	NOTES
RUSTLER DOL.	0	3369		555	17.0	<del> </del>	1.5	ŀ	1 1 1	Service.		10.25	. 37 301 316 7 73 2000
	455	2914	455	\$ 13je4	١	o ' + '	1.4.4	ŀ		T. Take	, ", ",	1,1	13, 20 44 BALL
SALADO SALT	682	268/	682	ļ		ļ	-	ŀ	. 50.			l,	1 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2
CASTILE: \\ \\ \\ \\ \\ \\ \\ \\ \\ \\ \\ \\ \\	2799	570	2799	, · ·	13 6	',,	-	ļ	* ' ' '	5 9,7	,	10.5	AD41275,A86,38
BASE OF SALT	3900	-531	3900										
BELL CANYON CONTRACTOR	4146	-777	* 4146	31 × 31	43, 3	gr 🖔 2	÷ ;.	L	" " " Udg.	, Alv. 1	1. h.	٦,	The state of the s
CHERRY CANYON	5079	-1710	5079	ļ				ļ					
BRUSHY, CANYON TO THE POPULATION	6405	-3036	6405	1-3	* \\$	2 15 F	; 1	ı		1.45	, . t	1 244	
1ST BONE SPRINGS LM	8031	-4662	8031					ı					
AVALON SHALE LOWER TOP 💥 🖟 🗠	8637	-5268	8637	<u>.:</u> *	12.75	11 11 11	15.3		4.5	747,3	A., 81	ر\$,	19 5. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1.
AVALON SHALE LOWER BOTTOM	8769	-5400	8769	L				Į					
1ST BONE SPRINGS SS.	9088	-5719	9088	*5.5	1.	6, 1, 2			100			, ,4	をおりて ない ない こうかい
2NO BONE SPRINGS LM	9495	-6126	9495					ſ					
2NO BONE SPRINGS SS	9843	-6474	9843	11 3 3	\$ 5	( A )	15	ſ	F 1 3 1	14.1 1	7. 14	1,	
3RD BONE SPRINGS LM	10159	-6790	10159					ſ					
3RD BONE SPRINGS SS.	10862	-7493	10862	3.77	. 68	5 %		ſ	1	* '	1000	25	とうとなる が南に着る
WOLFCAMP	11327	7958	11327					Ì					
WOLFCAMP HOT SHALE TOP	12196	8827	12195	3 3, 5	130	31 4	` '	Ī	, k	1.4	625	11.	
WOLFCAMP HOT SHALE BOTTOM	12339	-8970	12339					Ī					
TOP PENN SHALE	12620	-9251	12620	. 100		2.5			٠ "		- N 1 ×	V*=,	cons tigata rapide site in the
STRAWN	13045	9678	13045					ı					
TO PILOT ( ) ( S C S C C C C C C C C C C C C C C C C	13100	-9731	13100	21.	. ';	٠,	, , ,		17, 34	" in a co	1 1 1	27	15 m. may 18 18 18 18 18 18 18 18 18 18 18 18 18
18 3 to 98 collecture	** . 264.		ξ, ` , 'ζ"	1,100	18, 18	C.,	`,`,`;	[	1 1	10	58. J.	4	40% TABPX WASTASE
KOP	12187	-8818	12187					ſ					
WOLFCAMP HOT SHALE BOTTOM	12342	-8970	12339	14. 75	0)	3, 4,	6.45	ſ	13.33	A 1			47.7 15th 13.7 10.7 10.0
TOP PENN SHALE	12706	-6251	12620					Ī					
HOLD 90 DEGREES (EST.)	13046	-9351	12720	1844	, 4.5	\$12° \$1.	100	Ī	1.2	8 1 5	. 1/2 7	w, '	これでは 後のと はっ
LATERAL TD	16500	-9351	12760					ſ			,		
State of the state	, v.a. j. Nga '		153,000	\$ 100 miles	±10 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1		3 ,	Ī	17.13	· 34	~ .	30	THE WAR THE STATE OF THE STATE

Devon Energy Confidential 2/12/2010 Page 1

Mail final copies of mudlogs to partners as directed in attached Interest Owner Data Distribution sheet.

#### **DEVON ENERGY**

WELL NAME:	North Pure Gold 9 Fed #	19H		API#:	0		
SURFACE LOCATION.	Sec 09-23S-31E, 660 FS	L & 710 F	WL,	COUNTY	EDDY		
<b>BOTTOM HOLE LOCATION</b>	Sec 09-23S-31E, 660 FN	IL & 710 F	WL,	STATE:	NEW MEXICO		
PRIMARY OBJECTIVE .:	UPPER PENN SHALE			KB (EST)	3369	GL:	3349
ESTIMATED BHP/BHT:	9700 psi 180degF	,		PILÔT TD.		LATERAL TD:	16,500'
RIG.	1600 HP			DÉEPEST FM.	STRAWN		
RIG CONTACT:				DEVON DRILL ENG.:	PAT BROWN	CELL PH. 4	405-213-5058
MUD PROGRAM.				DEVON FIELD GEOL.	CHARLIE WILLEY	CELL PH.	405-388-5256
CASING:	BONE SPRINGS			DEVON GEOLOGIST:	JASON CURRIE	CELL PH.	405-209-4610
	-		SURVEY COM	PANY			
COMPANY.	CUDD			CONTACT:			
LOGGING ENGINEER:							
23302 222					****		
	,						
Suface Location (NAD27)	)						
	Long	W	-103.7884860				
	Lat	N	32.3136148				
	Footage N/S	FSL	660				
	Footage E/W	FWL	710				
Entry Point (NAD27)	)						
	Formation	UPPER	R PENN SHALE				
	Depth	TVD	12620				
	Depth	MD	12706				
	Footage N/S	FSL	912				
	Footage E/W	FEL	710				
Bottom Hole (NAD27)	)						
	Long	W	-103.7884921				
	Lat	N	32.3247366				
	Footage N/S	FNL	660				
	Footage E/W	FWL.	710				

#### CONDITIONS OF APPROVAL

**OPERATOR'S NAME:** | Devon Energy Production Company

**LEASE NO.:** | NM-77046

WELL NAME & NO.: | North Pure Gold 9 Federal 19

SURFACE HOLE FOOTAGE: 710' FSL & 710' FWL BOTTOM HOLE FOOTAGE 660' FNL & 710' FWL

LOCATION: | Section 9, T. 23 S., R 31 E., NMPM

**COUNTY:** Eddy County, New Mexico

#### I. DRILLING

#### A. DRILLING OPERATIONS REQUIREMENTS

The BLM is to be notified a minimum of 4 hours in advance for a representative to witness:

- a. Spudding well
- b. Setting and/or Cementing of all casing strings
- c. BOPE tests

#### **Eddy County**

Call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220, (575) 361-2822

- 1. Due to recent H2S encounters in the salt formation, it is recommended that monitoring equipment be onsite for potential Hydrogen Sulfide prior to drilling out the surface shoe. If Hydrogen Sulfide is encountered, please report measurements and formations to the BLM.
- 2. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval.
- 3. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works are located, this does not include the dog house or stairway area.

4. The record of the drilling rate along with the CAL/GR/N well log run from TD to surface will be submitted to the BLM office as well as all other logs run on the borehole 30 days from completion. If available, a digital copy of the logs is to be submitted in addition to the paper copies. The Rustler top and top and bottom of Salt are to be recorded on the Completion Report.

#### B. CASING

Changes to the approved APD casing and cement program require submitting a sundry and receiving approval prior to work. Failure to obtain approval prior to work will result in an Incident of Non-Compliance being issued.

Centralizers required on surface casing per Onshore Order 2.III.B.1.f.

Wait on cement (WOC) time for a primary cement job will be a minimum 18 hours for a water basin, 24 hours in the potash area, or 500 pounds compressive strength, whichever is greater for all casing strings. Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. See individual casing strings for details regarding lead cement slurry requirements.

No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.

#### Secretary's Potash

Possible brine and water flows in the Salado, Castile, Delaware and Bone Spring. Possible lost circulation in the Delaware and Bone Springs.

- 1. The 20 inch surface casing shall be set at approximately 540 feet (a minimum of 25 feet into the Rustler Anhydrite and above the salt) and cemented to the surface.
  - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with a surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.
  - b. Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry.
  - c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.

- d. If cement falls back, remedial cementing will be done prior to drilling out that string.
- 2. The minimum required fill of cement behind the 13-3/8 inch intermediate casing is:
  - □ Cement to surface. If cement does not circulate see B.1.a, c-d above.
     Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to potash. Set intermediate casing in the Lamar Limestone.

Formation below the 13-3/8" shoe to be tested according to Onshore Order 2.III.B.1.i. Test to be done as a mud equivalency test using the mud weight necessary for the pore pressure of the formation below the shoe (not the mud weight required to prevent dissolving the salt formation) and the mud weight for the bottom of the hole. Report results to BLM office.

Casing is to be kept fluid filled while running into hole.

- 3. The minimum required fill of cement behind the 9-5/8 inch second intermediate casing is:
  - a. First stage to DV tool, cement shall:
  - Cement to circulate. If cement does not circulate, contact the appropriate BLM office before proceeding with second stage cement job.
  - b. Second stage above DV tool, cement shall:
  - Cement should tie-back at least 500 feet into previous casing string. Operator shall provide method of verification. Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to potash.

Pilot hole is required to have a 1,000' plug at the bottom of the hole and it must be tagged. Tag depth to be recorded and reported on subsequent sundry with casing information.

Formation below the 9-5/8" shoe to be tested according to Onshore Order 2.III.B.1.i. Test to be done as a mud equivalency test using the mud weight necessary for the pore pressure of the formation below the shoe (not the mud weight required to prevent dissolving the salt formation) and the mud weight for the bottom of the hole. Report results to BLM office.

Centralizers required on horizontal leg, must be type for horizontal service and minimum of one every other joint.

- 4. The minimum required fill of cement behind the 5-1/2 inch production casing is:
  - Cement should tie-back at least 7,500 feet into previous casing string.

    Operator shall provide method of verification. Additional cement may be required as the excess calculates to -34%.
- 5. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.

#### C. PRESSURE CONTROL

- 1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in Onshore Oil and Gas Order No. 2 and API RP 53 Sec. 17.
- 2. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be **2000 (2M)** psi.
  - a. **For surface casing only:** If the BOP/BOPE is to be tested against casing, the wait on cement (WOC) time for that casing is to be met (see WOC statement at start of casing section). Independent service company required.
- 3. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the 13-3/8 inch intermediate casing shoe shall be 10,000 (10M) psi. 10M system requires an HCR valve, remote kill line and annular to match. The remote kill line is to be installed prior to testing the system and tested to stack pressure.
- 4. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.
  - a. Casing cut-off and BOP installation will not be initiated until the cement has had a minimum of 8 hours setup time for a water basin. The casing shall remain stationary and under pressure for at least eight hours after the operator places the cement. In the potash area, the minimum time is 12 hours and the casing shall remain stationary and under pressure during this time period. Casing shall be under pressure if the operator uses some acceptable means of holding pressure or if the operator employs one or more float valves to hold the cement in place. Testing the BOP/BOPE against a plug can commence after meeting the above conditions plus the BOP installation time.
  - b. The tests shall be done by an independent service company utilizing a test plug.

- c. The results of the test shall be reported to the appropriate BLM office.
- d. All tests are required to be recorded on a calibrated test chart. A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.
- e. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug.
- f. BOP/BOPE must be tested by an independent service company within 500 feet of the top of the **Wolfcamp** formation if the time between the setting of the intermediate casing and reaching this depth exceeds 20 days. This test does not exclude the test prior to drilling out the casing shoe as per Onshore Order No. 2.

#### D. DRILLING MUD

Mud system monitoring equipment, with derrick floor indicators and visual and audio alarms, shall be operating before drilling into the **Wolfcamp** formation, and shall be used until production casing is run and cemented.

#### E. DRILL STEM TEST

If drill stem tests are performed, Onshore Order 2.III.D shall be followed.

CRW 033110