#### **UNITED STATES** DEPARTMENT OF THE INTERIOR **BUREAU OF LAND MANAGEMENT**

**OCD Artesia** 

FORM APPROVED OMB NO. 1004-0135 Expires: July 31, 2010

5.	Lease Serial No.
	NMLC028784C

SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill or to re-enter an abandoned well. Use form 3160-3 (APD) for such proposals. 6. If Indian, Allottee or Tribe Name If Unit or CA/Agreement, Name and/or No. SUBMIT IN TRIPLICATE - Other instructions on reverse side. NMNM88525X Well Name and No.
BURCH KEELY UNIT 415 913 Type of Well ☑ Oil Well ☐ Gas Well ☐ Other Name of Operator API Well No. Contact: ROBYN ODOM MARBOB ENERGY CORPORATION E-Mail: rodom@conchoresources.com 30-015-37131-00-X1 3b. Phone No. (include area code)
Ph: 432-685-4385 Field and Pool, or Exploratory GRAYBURG JACKSON SR-Q-GRE 3a. Address ARTESIA, NM 88211-0227 4. Location of Well (Footage, Sec., T., R., M., or Survey Description) 11. County or Parish, and State NOV 29 2010 Sec 25 T17S R29E NENE Lot A 150FNL 660FEL EDDY COUNTY, NM HOCD ARTESIA 12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA TYPE OF SUBMISSION TYPE OF ACTION ☐ Water Shut-Off □ Acidize Production (Start/Resume) □ Deepen Notice of Intent ☐ Alter Casing ☐ Fracture Treat ☐ Reclamation ☐ Well Integrity ☐ Subsequent Report Other Change to Original Casing Repair ■ New Construction □ Recomplete Final Abandonment Notice ☐ Change Plans Plug and Abandon Temporarily Abandon Convert to Injection □ Plug Back ■ Water Disposal 13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomplete horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.) COG Operating respectfully requests permission to change the casing program to: See Attached drilling plan \*\*COG-proposes to drill 17-1/2? hole to +/-300? w/fresh water\_mud\_system, wt. 8.5, vis 28, set 13-3/8? casing 48# J-55/H-40 & cement w/\_300sxs to surf. Drill 11? or 12-1/4" hole to +/-850? w/brine mud system, wt 10-vis 30. Set 8-5/8? intermediate casing 24# J-55 & cement w/ 400sxs to surface. Drill a Z-7/8? hole to +/-4800 w/-cut brine mud system, wt 9.1, vis 29-32. Test Yeso formation. Run 5-1/2" casing 17# J-55 & cement w/ 800sxs to surface. Note: On production string, a caliper will be run, COG will attempt to circulate cement. SEE ATTACHED FOR AUDITIONIS OF APPROVAI.

	COMPLITORS OF Y	TH T Y		
14. Thereby certify	that the foregoing is true and correct.  Electronic Submission #96217 verified For MARBOB ENERGY CORPO Committed to AFMSS for processing by KU	BRÁTIOI	N. sent to the Carlsbad	
Name (Printed/T	yped) ROBYN ODOM	Title	PERSON RESPONSIBLE	
Signature	(Electronic Submission)	Date	10/29/2010	
	THIS SPACE FOR FEDERA	L OR	STATE OFFICE USE	
Approved By CHRISTOPHER WALLS		TitleF	ETROLEUM ENGINEER	Date 11/22/20
Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.		Į.	Carlsbad	
Tide 10 H C C Contis	an 1001 and Title 42 U.S.C. Section 1212, make it a prime for any			and an annual of the United

ly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.



### 1. Casing Program

		OD					
Hole Size	Interval	Casing	Weight	Grade	Jt., Condition	Jt.	brst/clps/ten
17 1/2"	0-300'	13 3/8"	48#	H-40orJ-55	ST&C/New	ST&C	9.22/3.943/15.8
11"or12 ¼"	0-1000'	8 5/8"	24or32#	J-55	ST&C/New	ST&C	3.03/2.029/7.82
7 7/8"	0-5100'	5 1/2"	15.5or17#	J-55orL-80	LT&C/New	LT&C	1.88/1.731/2.42

# 2. Cement Program

13 3/8" Surface Casing:

Class C, 300 sx, yield 1.32, back to surface

8 5/8" Intermediate Casing:

11" Hole:

**Single Stage:** 50:50:10, 300 sx lead, yield-2.45 + Class C, 200 sx tail, yield-1.32, back to surface.

5 1/2" Production Casing:

**Single Stage:** 35:65:6, 500 sx Lead, yield-2.05 + 50:50:2, 300 sx Tail, yield-1.37, to 200' minimum tie back to intermediate casing.

### CONDITIONS OF APPROVAL

**OPERATOR'S NAME:** | COG Operating LLC

LEASE NO.: NMLC-028784C

WELL NAME & NO.: | Burch Keely Unit 415 SURFACE HOLE FOOTAGE: | 150' FNL & 660' FEL

LOCATION: Section 25, T. 17 S., R 29 E., NMPM

**COUNTY:** | Eddy County, New Mexico

### I. DRILLING

# A. DRILLING OPERATIONS REQUIREMENTS

The BLM is to be notified a minimum of 4 hours in advance for a representative to witness:

- a. Spudding well
- b. Setting and/or Cementing of all casing strings
- c. BOPE tests

# **Eddy County**

Call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220, (575) 361-2822

- 1. A Hydrogen Sulfide (H2S) Drilling Plan should be activated 500 feet prior to drilling into the Yates formation. As a result, the Hydrogen Sulfide area must meet Onshore Order 6 requirements, which includes equipment and personnel/public protection items. If Hydrogen Sulfide is encountered, please provide measured values and formations to the BLM.
- 2. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval. If the drilling rig is removed without approval an Incident of Non-Compliance will be written and will be a "Major" violation.
- 3. The record of the drilling rate along with the GR/N well log run from TD to surface (horizontal well vertical portion of hole) will be submitted to the BLM office as well as all other logs run on the borehole 30 days from completion. If available, a digital copy of the logs is to be submitted in addition to the paper copies. The Rustler top and top and bottom of Salt are to be recorded on the Completion Report.

### B. CASING

Changes to the approved APD casing and cement program require submitting a sundry and receiving approval prior to work. Failure to obtain approval prior to work will result in an Incident of Non-Compliance being issued.

Centralizers required on surface casing per Onshore Order 2.III.B.1.f.

Wait on cement (WOC) time prior to drilling out for a primary cement job will be a minimum 18 hours for a water basin, 24 hours in the potash area, or 500 pounds compressive strength, whichever is greater for all casing strings. DURING THIS WOC TIME, NO DRILL PIPE, ETC. SHALL BE RUN IN THE HOLE. Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. See individual casing strings for details regarding lead cement slurry requirements.

No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.

Possible lost circulation in the Grayburg and San Andres formations. Possible water flows in the Salado and Artesia Groups

- 1. The 13-3/8 inch surface casing shall be set at approximately 300 feet (a minimum of 25 feet into the Rustler Anhydrite and above the salt) and cemented to the surface.
  - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.
  - b. Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry.
  - c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.
  - d. If cement falls back, remedial cementing will be done prior to drilling out that string.

- 2. The minimum required fill of cement behind the 8-5/8 inch intermediate casing is:
  - Cement to surface. If cement does not circulate see B.1.a, c-d above.
- 3. The minimum required fill of cement behind the 5-1/2 inch production casing is:
  - Cement to surface. If cement does not circulate, contact the appropriate BLM office. Additional cement may be required, as the excess cement calculates to 16%.
- 4. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.

### C. PRESSURE CONTROL

- 1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in Onshore Oil and Gas Order No. 2 and API RP 53 Sec. 17.
- 2. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be **2000 (2M)** psi.
  - a. **For surface casing only:** If the BOP/BOPE is to be tested against casing, the wait on cement (WOC) time for that casing is to be met (see WOC statement at start of casing section). Independent service company required.
- 3. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.
  - a. In a water basin, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. The casing cut-off and BOP installation can be initiated four hours after installing the slips, which will be approximately six hours after bumping the plug. For those casing strings not using slips or where the float does not hold, the minimum wait time before cut-off is eight hours after bumping the plug or when the cement reaches 500 psi compressive strength (including lead when specified), whichever is greater. BOP/BOPE testing can begin after the above conditions are satisfied.

- b. The tests shall be done by an independent service company utilizing a test plug **not a cup or J-packer**. The operator also has the option of utilizing an independent tester to test without a plug (i.e. against the casing) pursuant to Onshore Order 2 with the pressure not to exceed 70% of the burst rating for the casing. Any test against the casing must meet the WOC time for water basin (18 hours) or potash (24 hours) prior to initiating the test.
- c. The results of the test shall be reported to the appropriate BLM office.
- d. All tests are required to be recorded on a calibrated test chart. A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.
- e. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug.
- f. Effective November 1, 2008, no variances will be granted on reduced pressure tests on the surface casing and BOP/BOPE. Onshore Order 2 requirements will be in effect.

### D. DRILL STEM TEST

If drill stem tests are performed, Onshore Order 2.III.D shall be followed.

### E. WASTE MATERIAL AND FLUIDS

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area.

**CRW 112210**