

ATS-10-752
10-1189

OCD Artesia

Form 3160-3
(February 2005)

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

APPLICATION FOR PERMIT TO DRILL OR REENTER

FORM APPROVED
OMB No. 1004-0137
Expires March 31, 2007

1a. Type of work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER		5. Lease Serial No. NMNM LC 00656860.
1b. Type of Well: <input checked="" type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Other <input checked="" type="checkbox"/> Single Zone <input type="checkbox"/> Multiple Zone		6. If Indian, Allottee or Tribe Name
2. Name of Operator Devon Energy Production Co., LP		7. If Unit or CA Agreement, Name and No.
3a. Address 20 North Broadway OKC, OK 73102		8. Lease Name and Well No. Serene Sisters 25 Federal 3H (38412)
3b. Phone No. (include area code) (405) 553-1100		9. API Well No. 30-015-38311
4. Location of Well (Report location clearly and in accordance with any State requirements*) At surface SESW 200' FSL & 1800' FWL Lot N At proposed prod. zone NENW 400' FNL & 2310' FWL Lot C		10. Field and Pool or Exploratory TAMAND; Bone Spring (58040)
14. Distance in miles and direction from nearest town or post office* Approximately 12 miles southeast of Loco Hills, NM.		11. Sec., T. R. M. or Blk. and Survey or Area Sec 25-T18S-R31E
15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) 200'	16. No. of acres in lease 640 acres	17. Spacing Unit dedicated to this well 160 acres
18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft. See Plat	19. Proposed Depth TVD 8,240' MD 12,770'	20. BLM/BIA Bond No. on file CO-1104
21. Elevations (Show whether DF, KDB, RT, GL, etc.) 3667.1' GL	22. Approximate date work will start* 09/15/2010	23. Estimated duration 45 days

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No.1, must be attached to this form:

- | | |
|--|---|
| 1. Well plat certified by a registered surveyor. | 4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above). |
| 2. A Drilling Plan. | 5. Operator certification |
| 3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO must be filed with the appropriate Forest Service Office). | 6. Such other site specific information and/or plans as may be required by the BLM. |

25. Signature 	Name (Printed/Typed) Stephanie A. Ysasaga	Date 08/04/2010
-------------------	--	--------------------

Title
Sr. Staff Engineering Technician

Approved by (Signature) Is/ Don Peterson	Name (Printed/Typed)	Date NOV 12 2010
---	----------------------	---------------------

Title FIELD MANAGER	Office CARLSBAD FIELD OFFICE
------------------------	---------------------------------

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.
Conditions of approval, if any, are attached.


APPROVAL FOR TWO YEARS

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*(Instructions on page 2)

SEE ATTACHED FOR
CONDITIONS OF APPROVAL

APPROVAL SUBJECT TO
GENERAL REQUIREMENTS
AND SPECIAL STIPULATIONS
ATTACHED



Capitan Controlled Water Basin

District I

1625 N. French Dr., Hobbs, NM 88240

District II

1301 W. Grand Avenue, Artesia, NM 88210

District III

1000 Rio Brazos Rd., Aztec, NM 87410

District IV

1220 S. St. Francis Dr., Santa Fe, NM 87505

State of New Mexico

Energy, Minerals & Natural Resources Department

OIL CONSERVATION DIVISION

1220 South St. Francis Dr.

Santa Fe, NM 87505

Form C-102

Revised October 15, 2009

Submit one copy to appropriate

District Office

☐ AMENDED REPORT

WELL LOCATION AND ACREAGE DEDICATION PLAT

¹ API Number 30-05-38311	² Pool Code 56040	³ Pool Name TAMANO; BONE SPRING
⁴ Property Code 38412	⁵ Property Name SERENE SISTERS 25 FEDERAL	
⁷ OGRID No. 6137	⁸ Operator Name DEVON ENERGY PRODUCTION COMPANY, L.P.	⁶ Well Number 3H
		⁹ Elevation 3667.1

¹⁰ Surface Location

UL or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
N	25	18 S	31 E		200	SOUTH	1800	WEST	EDDY

¹¹ Bottom Hole Location If Different From Surface

UL or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
C	25	18 S	31 E		400	NORTH	2310	WEST	EDDY

¹² Dedicated Acres 160	¹³ Joint or Infill	¹⁴ Consolidation Code	¹⁵ Order No.
---	-------------------------------	----------------------------------	-------------------------

No allowable will be assigned to this completion until all interests have been consolidated or a non-standard unit has been approved by the division.

<p>2310'</p> <p>NW CORNER SEC. 25 LAT. = 32°43'32.97"N LONG. = 103°49'54.03"W NMSP EAST (FT) N = 628142.55 E = 695610.97</p>	<p>BOTTOM OF HOLE</p> <p>400'</p> <p>BOTTOM OF HOLE LAT. = 32°43'29.06"N LONG. = 103°49'26.93"W NMSP EAST (FT) N = 627758.25 E = 697928.74</p>	<p>NE CORNER SEC. 25 LAT. = 32°43'33.11"N LONG. = 103°48'51.80"W NMSP EAST (FT) N = 628181.67 E = 700927.99</p>	<p>17 OPERATOR CERTIFICATION</p> <p>I hereby certify that the information contained herein is true and complete to the best of my knowledge and belief, and that this organization either owns a working interest or unleased mineral interest in the land including the proposed bottom hole location or has a right to drill this well at this location pursuant to a contract with an owner of such a mineral or working interest, or to a voluntary pooling agreement or a compulsory pooling order heretofore entered by the division.</p> <p>Signature: <i>[Signature]</i> Date: 06/04/2010</p> <p>Printed Name: STEPHANIE A. YSASAGA</p>
<p>SW CORNER SEC. 25 LAT. = 32°42'40.68"N LONG. = 103°49'53.55"W NMSP EAST (FT) N = 622856.67 E = 695677.43</p>	<p>SERENE SISTERS "25" FED. #3H ELEV. = 3667.1' LAT. = 32°42'42.721"N (NAD83) LONG. = 103°49'32.488"W NMSP EAST (FT) N = 623071.50 E = 697476.19</p>	<p>SE CORNER SEC. 25 LAT. = 32°42'40.84"N LONG. = 103°48'51.74"W NMSP EAST (FT) N = 622898.69 E = 700959.68</p>	

18 SURVEYOR CERTIFICATION

I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief.

JULY 8, 2010

Date of Survey

Signature and Seal of Professional Surveyor

Certificate Number

FILMON LARAMINO, PLS 12797

SURVEY NO. 148

PENETRATION POINT: 480' FSL & 2310' FWL

☐ PRODUCING AREA☒ PROJECT AREA

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0137
Expires: March 31, 2007

SUNDRY NOTICES AND REPORTS ON WELLS
Do not use this form for proposals to drill or to re-enter an abandoned well. Use Form 3160-3 (APD) for such proposals.

5. Lease Serial No.
NMNM LC-0065680

6. If Indian, Allottee or Tribe Name

SUBMIT IN TRIPLICATE - Other instructions on page 2.

1. Type of Well

☒ Oil Well ☐ Gas Well ☐ Other

2. Name of Operator
Devon Energy Production Co., LP

3a. Address
20 North Broadway
OKC, OK 73102

3b. Phone No. (include area code)
(405)-552-7802

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)
SL: 200' FSL & 1800' FWL BHL: 400' FSL & 2310' FWL
Sec 25-T18S-R31E, N

7. If Unit of CA/Agreement, Name and/or No.

8. Well Name and No.
Serene Sisters 25 Federal 3H

9. API Well No.

10. Field and Pool or Exploratory Area
Hackberry; Bone Springs, North

11. Country or Parish, State
Eddy County, NM

12. CHECK THE APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input checked="" type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other Use of co-flex hose
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	between the BOPE &
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	the choke manifold

13. Describe Proposed or Completed Operation: Clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomple horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports must be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recomple in a new interval, a Form 3160-4 must be filed once testing has been completed. Final Abandonment Notices must be filed only after all requirements, including reclamation, have been completed and the operator has determined that the site is ready for final inspection.)

Devon Energy Production Co., LP respectfully requests a variance to Onshore Order No. 2. If H&P rig is used to drill this well, co-flex hose may be used between the BOPE and the choke manifold. The hose will be kept as straight as possible with minimal turns.

Co-Flex Hose:

- * Manufacturer: Copper State Rubber, Inc.
- * Approximately ~ 37' 6" of co-flex line
- * 3" coupling with 4 1/16" flanges on each end - 10,000 psi
- * Quality Control Inspection & Test Certificate attached
- * See configuration schematic
- * Safety clamps are not required since the ends are flanged
- * Line to be kept as straight as possible.

Devon also respectfully submits the requested documentation, per BLM request, for Federal permits regarding lifting and safety equipment.

14. I hereby certify that the foregoing is true and correct.

Name (Printed/Typed)
Stephanie A. Ysasaga

Title Sr. Staff Engineering Technician

Signature

Date 08/30/2010

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved by

/s/ Don Peterson

Title

FIELD MANAGER

Date

NOV 21 2010

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office

CARLSBAD FIELD OFFICE

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on page 2)

COPPER STATE RUBBER
VISUAL INSPECTION / HYDROSTATIC TEST REPORT
CHOKE & KILL / CEMENTING HOSE
10,000 P.S.I. W/P X 15,000 P.S.I. T/P
SPEC: 090-1915 HS
H2S SUITABLE

SHOP ORDER NO.: 22162 SIZE: 3" I.D.

SERIAL NO.: 26547 LENGTH 37 FT. 6 IN.

CONNECTIONS: 4-1/16" 10,000 PSI API FLANGES

08C1 - 08D2 - HT-A080635

VISUAL INSPECTION

(A) END CAPS / SLEEVE RECESS: OK
(B) EXTERIOR / COVER / BRANDING: OK
(C) INTERIOR TUBE: OK

HYDROSTATIC TEST

5 MIN. @ 10,000 PSI

2 MIN. @ 0 PSI 37' - 11" OAL


15 MIN. @ 15,000 PSI

WITNESSED BY:

Phil Spider

DATE

June 16, 2010





Fluid Technology

ContiTech Beattie Corp.
Website: www.contitechbeattie.com

Monday, June 14, 2010

RE: Drilling & Production Hoses
Lifting & Safety Equipment

To Helmerich & Payne,

A Continental ContiTech hose assembly can perform as intended and suitable for the application regardless of whether the hose is secured or unsecured in its configuration. As a manufacturer of High Pressure Hose Assemblies for use in Drilling & Production, we do offer the corresponding lifting and safety equipment, this has the added benefit of easing the lifting and handling of each hose assembly whilst affording hose longevity by ensuring correct handling methods and procedures as well as securing the hose in the unlikely event of a failure; but in no way does the lifting and safety equipment affect the performance of the hoses providing the hoses have been handled and installed correctly. It is good practice to use lifting & safety equipment but not mandatory.


Should you have any questions or require any additional information/clarifications then please do not hesitate to contact us.

ContiTech Beattie is part of the Continental AG Corporation and can offer the full support resources associated with a global organization.

Best regards,

Robin Hodgson
Sales Manager
ContiTech Beattie Corp

ContiTech Beattie Corp,
11535 Brittmoores Park Drive,
Houston, TX 77041
Phone: +1 (832) 327-0141
Fax: +1 (832) 327-0148
www.contitechbeattie.com



SECTION 25, TOWNSHIP 18 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO

SERENE SISTERS "25" FED. #3H

ELEV. = 3667.1'


LAT. = 32°42'42.721"N (NAD83)

LONG. = 103°49'32.488"W

NMSP EAST (FT)

N = 623071.50

E = 697476.19



0 150 300 600

SCALE 1" = 300'

DIRECTIONS TO LOCATION

FROM STATE HWY. 82 AND CR# 222 GO SOUTH ON CR# 222 (PAVED) 4.0 MILES AND TURN LEFT ON CALICHE CR #249 AND GO SOUTHEAST 2.8 MILES BEND RIGHT ON CR #249 AND GO SOUTH 1.35 MILES, TURN LEFT ON CALICHE ROAD AND GO EAST 1.0 MILES, TURN RIGHT AND GO SOUTH 0.13 MILES TO A PROPOSED ROAD SURVEY AND FOLLOW FLAGS EAST 477' BEND LEFT AND FOLLOW FLAGS NE, 983', BEND LEFT AND FOLLOW FLAGS NORTH 110' TO THE SW COR. OF PROPOSED PAD FOR THIS LOCATION.


DEVON ENERGY PRODUCTION COMPANY, L.P.
SERENE SISTERS "25" FED. #3H & #4H
LOCATED 200 FT. FROM THE SOUTH LINE
AND 1800 FT. FROM THE WEST LINE OF
SECTION 25, TOWNSHIP 18 SOUTH,
RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO

SURVEY NO. 148

MADRON SURVEYING, INC. CARLSBAD, NEW MEXICO

JULY 8, 2010

SECTION 25, TOWNSHIP 18 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
LOCATION MAP



CONTOUR INTERVAL:
GREENWOOD LAKE

NOT TO SCALE

DIRECTIONS TO LOCATION

FROM STATE HWY. 82 AND CR# 222 GO SOUTH ON CR# 222
(PAVED) 4.0 MILES AND TURN LEFT ON CALICHE CR. #249 AND
GO SOUTHEAST 2.8 MILES BEND RIGHT ON CR. #249 AND GO
SOUTH 1.35 MILES, TURN LEFT ON CALICHE ROAD AND GO EAST
1.0 MILES, TURN RIGHT AND GO SOUTH 0.13 MILES TO A
PROPOSED ROAD SURVEY AND FOLLOW FLAGS EAST 477', BEND
LEFT AND FOLLOW FLAGS NE. 983', BEND LEFT AND FOLLOW
FLAGS NORTH 110' TO THE SW COR. OF PROPOSED PAD FOR
THIS LOCATION.

SEC. 25 TWP. 18-S RGE. 31-E
SURVEY N.M.P.M.
COUNTY EDDY STATE NEW MEXICO
DESCRIPTION 200' FSL & 1800' FWL
ELEVATION 3667.1'
OPERATOR DEVON ENERGY PRODUCTION COMPANY, LP
LEASE SERENE SISTERS


DEVON ENERGY PRODUCTION COMPANY, L.P.
SERENE SISTERS "25" FED. #3H
LOCATED 200 FT. FROM THE SOUTH LINE
AND 1800 FT. FROM THE WEST LINE OF
SECTION 25, TOWNSHIP 18 SOUTH,
RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO

JULY 8, 2010

SURVEY NO. 148

MADRON SURVEYING, INC. 301 SOUTH CANAL (575) 897-5810 CARLSBAD, NEW MEXICO

SECTION 25, TOWNSHIP 18 SOUTH, RANGE 31 EAST, N.M.P.M.
 EDDY COUNTY, STATE OF NEW MEXICO
VICINITY MAP



DIRECTIONS TO LOCATION

FROM STATE HWY. 82 AND CR# 222 GO SOUTH ON CR# 222 (PAVED) 4.0 MILES AND TURN LEFT ON CALICHE CR. #249 AND GO SOUTHEAST 2.8 MILES BEND RIGHT ON CR. #249 AND GO SOUTH 1.35 MILES, TURN LEFT ON CALICHE ROAD AND GO EAST 1.0 MILES, TURN RIGHT AND GO SOUTH 0.13 MILES TO A PROPOSED ROAD SURVEY AND FOLLOW FLAGS EAST 477', BEND LEFT AND FOLLOW FLAGS NE. 983', BEND LEFT AND FOLLOW FLAGS NORTH 110' TO THE SW COR. OF PROPOSED PAD FOR THIS LOCATION.

NOT TO SCALE

SEC. 25 TWP. 18-S RGE. 31-E
 SURVEY N.M.P.M.
 COUNTY EDDY STATE NEW MEXICO
 DESCRIPTION 200' FSL & 1800' FWL
 ELEVATION 3667.1'
 OPERATOR DEVON ENERGY PRODUCTION COMPANY, LP
 LEASE SERENE SISTERS


DEVON ENERGY PRODUCTION COMPANY, L.P.
 SERENE SISTERS "25" FED. #3H
 LOCATED 200 FT. FROM THE SOUTH LINE
 AND 1800 FT. FROM THE WEST LINE OF
 SECTION 25, TOWNSHIP 18 SOUTH,
 RANGE 31 EAST, N.M.P.M.
 EDDY COUNTY, STATE OF NEW MEXICO

JULY 8, 2010

SURVEY NO. 148

MADRON SURVEYING, INC. 301 SOUTH CANAL (575) 887-5830 CARLSBAD, NEW MEXICO


AERIAL PHOTO



DEVON ENERGY PRODUCTION COMPANY, L.P.
SERENE SISTERS "25" FED. #3H
LOCATED 200 FT. FROM THE SOUTH LINE
AND 1800 FT. FROM THE WEST LINE OF
SECTION 25, TOWNSHIP 18 SOUTH,
RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO

SURVEY NO. 148

301 SOUTH CANAL
(575) 887-5830



DRILLING PROGRAM

Devon Energy Production Company, LP

Serene Sisters 25 Federal 3H

Surface Location: 200' FSL & 1800' FWL, Unit N, Sec 25 T18S R31E, Eddy, NM

Bottom hole Location: 400' FNL & 2310' FWL, Unit C, Sec 25 T18S R31E, Eddy, NM

1. Geologic Name of Surface Formation

a. Permian

2. Estimated Tops of Geological Markers & Depths of Anticipated Fresh Water, Oil or Gas:

a. Rustler	825'	Barren
b. Salado	1020'	Barren
c. Salado Base	2210'	Barren
d. Tansil Dolomite	2300'	Barren
e. Yates	2530'	Oil
f. Seven Rivers	2875'	Oil
g. Queen	3540'	Oil
h. Penrose	3750'	Barren
i. San Andres	4175'	Barren
j. Delaware	4725'	Oil/Gas
k. Bone Springs	6565'	Oil/Gas
l. Avalon Shale	6910'	Oil/Gas
m. 1 st Bone Spring Ss	7980'	Oil/Gas
n. 1 st BS Upper Ss pay	8000'	Oil/Gas
o. 1 st BS Middle Ss pay	8090'	Oil/Gas
p. 1 st BS Middle "B" Ss pay	8145'	Oil/Gas
q. 1 st BS Lower Ss pay	8205'	Oil/Gas
r. 2 nd Bone Spring Lime	8270'	Oil/Gas
s. PTD (pilot hole)	8825'	
t. Total Depth	TVD 8240' MD 12771'	

No other formations are expected to yield oil, gas or fresh water in measurable volumes. The surface fresh water sands will be protected by setting 13 3/8" casing at ^{See COA}875' and circulating cement back to surface. The fresh water sands will be protected by setting 9 5/8" casing at 3500' and circulating cement to surface. The Delaware intervals will be isolated by setting 5 1/2" casing to total depth and circulating cement above the base of the 9 5/8" casing. All casing is new and API approved.

NOTE: THIS WELL WILL BE DRILLED WITH A PILOT HOLE (PH)

3. Casing Program: *See COA*

<u>Hole Size</u>	<u>Hole Interval</u>	<u>OD Csg</u>	<u>Casing Interval</u>	<u>Weight</u>	<u>Collar</u>	<u>Grade</u>
17 1/2"	0'-875' 430'	13 3/8"	0'-875'	48#	STC	H-40
12 1/4"	875'-3000'	9 5/8"	0'-3000'	36#	LTC	J-55
12 1/4"	3000'-3500'	9 5/8"	3000'-3500'	40#	LTC	J-55
8 3/4"	3500'-7600'	5 1/2"	0-7600'	17#	LTC	P-110HC
8 3/4"	7600'-12771'	5 1/2"	7600'-12771'	17#	BTC	P-110HC

Design Parameter Factors:

<u>Casing Size</u>	<u>Collapse Design Factor</u>	<u>Burst Design Factor</u>	<u>Tension Design Factor</u>
13 3/8"	1.69	3.79	6.88
9 5/8" 36# J-55	1.29	2.26	3.43
9 5/8" 40# J-55	1.37	2.11	21.67
5 1/2" 17# LTC	1.77	2.18	1.59
5 1/2" 17# BTC	1.84	2.27	4.95

4. Cement Program:

a. 13 3/8" Surface

Lead: 600 sacks Class C Cement + 2% bwoc Calcium Chloride + 0.125 lbs/sack Cello Flake + 4% bwoc Bentonite + 81.4% Fresh Water, 13.5 ppg. Yield: 1.75 cf/sk

Tail: 250 sacks Class C Cement + 2% bwoc Calcium Chloride + 0.125 lbs/sack Cello Flake + 56.3% Fresh Water, 14.8 ppg. Yield: 1.35 cf/sk. **TOC @ surface**

b. 9 5/8" Intermediate

Lead: 1,100 sacks (35:65) Poz (Fly Ash):Class C Cement + 5% bwow Sodium Chloride + 0.125 lbs/sack Cello Flake + 6% bwoc Bentonite + 107.8% Fresh Water, 12.5 ppg. Yield: 1.96 cf/sk

Tail: 300 sacks Class C Cement + 5% bwow Sodium Chloride + 0.125 lbs/sack Cello Flake + 0.4% bwoc Sodium Metasilicate + 4% bwoc MPA-5 + 52.7% Water, 14.8 ppg. Yield: 1.34 cf/sk. **TOC @ surface**

c. 5 1/2" Production

1st Stage

Lead: 900 sacks (35:65) Poz (Fly Ash):Class H Cement + 5% bwow Sodium Chloride + 0.3% bwoc CD-32 + 0.5% bwoc FL-25 + 2% bwoc Bentonite + 0.6% bwoc Sodium Metasilicate + 0.5% bwoc FL-52A + 102.5% Fresh Water, 12.5 ppg. Yield: 2.00 cf/sk

Tail: 1,300 sacks (50:50) Poz (Fly Ash):Class H Cement + 1% bwow Sodium Chloride + 0.2% bwoc R-3 + 0.125 lbs/sack Cello Flake + 0.5% bwoc BA-10A + 4% bwoc MPA-5 + 58.3% Fresh Water, 14.2 ppg. **Yield:** 1.28 cf/sk

DV TOOL at ~5,000 ft

2nd Stage

Lead: 350 sacks Class C Cement + 1% bwow Calcium Chloride + 0.125 lbs/sack Cello Flake + 157.8% Fresh Water, 11.4 ppg. **Yield:** 2.89 cf/sk

Tail: 150 sacks (60:40) Poz (Fly Ash):Class C Cement + 1% bwow Sodium Chloride + 0.2% bwoc R-3 + 0.125 lbs/sack Cello Flake + 0.5% bwoc BA-10A + 4% bwoc MPA-5 + 63.2% Fresh Water, 13.8 ppg. **Yield:** 1.37cf/sk. **TOC @ 3,000 ft**

8 3/4" Pilot Hole Plug

700 sxs Class H, 18.0 ppg, 0.89 cf/sk
Top of Plug 7,667' (KOP)
Bottom of Plug 8,825' (Pilot Hole TD)

TOC for All Strings:

Surface: 0'
Intermediate: 0'
Production: 3,000'

The above cement volumes could be revised pending the caliper measurement from the open hole logs. Actual cement volumes will be adjusted based on fluid caliper and caliper log data.

5. Pressure Control Equipment:

BOP DESIGN: The BOP system used to drill the intermediate hole will consist of a 13-5/8" 5M Double Ram and Annular preventer. The BOP system will be tested as per BLM Onshore Oil and Gas Order No. 2 as a 3M system prior to drilling out the surface casing shoe.

The BOP system used to drill the production hole will consist of a 13-5/8" 5M Double Ram and Annular preventer. The BOP system will be tested as per BLM Onshore Oil and Gas Order No. 2 as a 5M system prior to drilling out the intermediate casing shoe.

The pipe rams will be operated and checked each 24 hour period and each time the drill pipe is out of the hole. These tests will be logged in the daily driller's log. A 2" kill line and 3" choke line will be incorporated into the drilling spool below the ram BOP. In addition to the rams and annular preventer, additional BOP accessories include a kelly cock, floor safety valve, choke lines, and choke manifold rated at 5,000 psi WP.

6. **Proposed Mud Circulation System**

See COA

<u>Depth</u>	<u>Mud Wt.</u>	<u>Visc</u>	<u>Fluid Loss</u>	<u>Type System</u>
0' - 875' 130	8.4-9.0	30-34	NC	Fresh Water
875' - 3500'	9.8-10.0	28-32	NC	Brine
3500' - 12771'	8.6-9.0	28-32	NC-12	Fresh Water

The necessary mud products for weight addition and fluid loss control will be on location at all times.

7. **Auxiliary Well Control and Monitoring Equipment:**

- A Kelly cock will be in the drill string at all times.
- A full opening drill pipe stabbing valve having the appropriate connections will be on the rig floor at all times.
- Hydrogen Sulfide detection equipment will be in operation after drilling out the 13 3/8" casing shoe until the 5 1/2" casing is cemented. Breathing equipment will be on location upon drilling the 13 3/8" shoe until total depth is reached.

8. **Logging, Coring, and Testing Program:**

See COA

- Drill stem tests will be based on geological sample shows.
- If a drill stem test is anticipated; a procedure, equipment to be used and safety measures will be provided via sundry notice to the BLM.
- The open hole electrical logging program will be:
 - Total Depth to Intermediate Casing Dual Laterolog-Micro Laterolog with SP and Gamma Ray. Compensated Neutron - Z Density log with Gamma Ray and Caliper.
 - Total Depth to Surface Compensated Neutron with Gamma Ray
 - No coring program is planned
 - Additional testing will be initiated subsequent to setting the 5 1/2" production casing. Specific intervals will be targeted based on log evaluation, geological sample shows and drill stem tests.

9. **Potential Hazards:**

- No abnormal pressures or temperatures are expected. There is no known presence of H2S in this area. If H2S is encountered the operator will comply with the provisions of Onshore Oil and Gas Order No. 6 No lost circulation is expected to occur. All personnel will be familiar with all aspects of safe operation of equipment being used to drill this well. Estimated BHP 3600 psi and Estimated BHT 145°. No H2S is anticipated to be encountered.

10. **Anticipated Starting Date and Duration of Operations:**

- Road and location construction will begin after the BLM has approved the APD. Anticipated spud date will be as soon after BLM approval and as soon as a rig will be available. Move in operations and drilling is expected to take 32 days. If production casing is run then an additional 30 days will be needed to complete well and construct surface facilities and/or lay flow lines in order to place well on production.



Weatherford®

Drilling Services

Proposal



devon

SERENE SISTERS 25 FED 3H

EDDY COUNTY, NM

WELL FILE: PLAN 1

JULY 29, 2010

Weatherford International, Ltd.

P.O. Box 61028

Midland, TX 79711 USA

+1.432.561.8892 Main

+1.432.561.8895 Fax

www.weatherford.com



Weatherford International, Inc.

Directional Plan Report



Weatherford

Company: Devon Energy Date: 7/29/2010 Time: 12:37:24 Page: 1
Field: Eddy Co., NM (NAD 83) Co-ordinate(NE) Reference: Well: Serene Sisters 25 Fed 3H
Site: Serene Sisters 25 Fed 3H Vertical (TVD) Reference: SITE 3692.1
Well: Serene Sisters 25 Fed 3H Section (VS) Reference: Well (0.00N,0.00E,5.52Azi)
Wellpath: 1 Survey Calculation Method: Minimum Curvature Db: Sybase

Field: Eddy Co., NM (NAD 83)

Map System: US State Plane Coordinate System 1983
Geo Datum: GRS 1980
Sys Datum: Mean Sea Level

Map Zone: New Mexico, Eastern Zone
Coordinate System: Well Centre
Geomagnetic Model: IGRF2010

Site: Serene Sisters 25 Fed 3H

Site Position: Northing: 623071.50 ft Latitude: 32 42 42.601 N
From: Map Easting: 697476.19 ft Longitude: 103 49 32.473 W
Position Uncertainty: 0.00 ft North Reference: Grid
Ground Level: 3667.10 ft Grid Convergence: 0.27 deg

Well: Serene Sisters 25 Fed 3H

Slot Name:

Well Position: +N/-S 0.00 ft Northing: 623071.50 ft Latitude: 32 42 42.601 N
+E/-W 0.00 ft Easting: 697476.19 ft Longitude: 103 49 32.473 W
Position Uncertainty: 0.00 ft

Wellpath: 1

Current Datum: SITE Height 3692.10 ft
Magnetic Data: 7/29/2010
Field Strength: 48997 nT
Vertical Section: Depth From (TVD) +N/-S
ft ft
0.00 0.00 0.00 5.52

Drilled From: Surface
Tie-on Depth: 0.00 ft
Above System Datum: Mean Sea Level
Declination: 7.85 deg
Mag Dip Angle: 60.62 deg
+E/-W Direction
ft deg
0.00 5.52

Plan: Plan #1

Date Composed: 7/29/2010
Version: 1
Tied-to: From Surface

Principal: Yes

Plan Section Information

MD ft	Incl deg	Azim deg	TVD ft	+N/-S ft	+E/-W ft	DLS deg/100ft	Build deg/100ft	Turn deg/100ft	TFO deg	Target
0.00	0.00	26.34	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
7667.04	0.00	26.34	7667.04	0.00	0.00	0.00	0.00	0.00	26.34	
8567.04	90.00	26.34	8240.00	513.46	254.23	10.00	10.00	0.00	26.34	
9445.10	90.00	0.00	8240.00	1360.91	452.55	3.00	0.00	-3.00	-90.00	
12770.94	90.00	0.00	8240.00	4686.75	452.55	0.00	0.00	0.00	0.00	PBHL

Survey

MD ft	Incl deg	Azim deg	TVD ft	N/S ft	E/W ft	VS ft	DLS deg/100ft	MapN ft	MapE ft	Comment
7600.00	0.00	26.34	7600.00	0.00	0.00	0.00	0.00	623071.50	697476.19	
7667.04	0.00	26.34	7667.04	0.00	0.00	0.00	0.00	623071.50	697476.19	KOP
7700.00	3.30	26.34	7699.98	0.85	0.42	0.89	10.00	623072.35	697476.61	
7800.00	13.30	26.34	7798.81	13.76	6.81	14.35	10.00	623085.26	697483.00	
7900.00	23.30	26.34	7893.63	41.86	20.73	43.66	10.00	623113.36	697496.92	
8000.00	33.30	26.34	7981.57	84.29	41.73	87.91	10.00	623155.79	697517.92	
8100.00	43.30	26.34	8059.96	139.75	69.20	145.76	10.00	623211.25	697545.39	
8200.00	53.30	26.34	8126.40	206.57	102.28	215.45	10.00	623278.07	697578.47	
8300.00	63.30	26.34	8178.89	282.72	139.99	294.87	10.00	623354.22	697616.18	
8400.00	73.30	26.34	8215.82	365.88	181.16	381.60	10.00	623437.38	697657.35	
8500.00	83.30	26.34	8236.08	453.52	224.55	473.00	10.00	623525.02	697700.74	
8567.04	90.00	26.34	8240.00	513.46	254.23	535.52	10.00	623584.96	697730.42	Landing Pt/Turn
8600.00	90.00	25.35	8240.00	543.12	268.60	566.43	3.00	623614.62	697744.79	
8700.00	90.00	22.35	8240.00	634.57	309.04	661.34	3.00	623706.07	697785.23	
8800.00	90.00	19.35	8240.00	728.01	344.63	757.76	3.00	623799.51	697820.82	
8900.00	90.00	16.35	8240.00	823.19	375.28	855.44	3.00	623894.69	697851.47	



Weatherford International, Inc.

Directional Plan Report



Weatherford

Company: Devon Energy
Field: Eddy Co., NM (NAD 83)
Site: Serene Sisters 25 Fed 3H
Well: Serene Sisters 25 Fed 3H
Wellpath: 1

Date: 7/29/2010 Time: 12:37:24 Page: 2
Co-ordinate(NE) Reference: Well: Serene Sisters 25 Fed 3H
Vertical (TVD) Reference: SITE 3692.1
Section (VS) Reference: Well (0.00N,0.00E,5.52Azi)
Survey Calculation Method: Minimum Curvature Db: Sybase

Survey

MD ft	Incl deg	Azim deg	TVD ft	N/S ft	E/W ft	VS ft	DLS deg/100ft	MapN ft	MapE ft	Comment
9000.00	90.00	13.35	8240.00	919.83	400.92	954.11	3.00	623991.33	697877.11	
9100.00	90.00	10.35	8240.00	1017.69	421.45	1053.49	3.00	624089.19	697897.64	
9200.00	90.00	7.35	8240.00	1116.49	436.84	1153.30	3.00	624187.99	697913.03	
9300.00	90.00	4.35	8240.00	1215.95	447.04	1253.29	3.00	624287.45	697923.23	
9400.00	90.00	1.35	8240.00	1315.82	452.02	1353.17	3.00	624387.32	697928.21	
9445.10	90.00	0.00	8240.00	1360.91	452.55	1398.11	3.00	624432.41	697928.74	Hold
9500.00	90.00	0.00	8240.00	1415.81	452.55	1452.76	0.00	624487.31	697928.74	
9600.00	90.00	0.00	8240.00	1515.81	452.55	1552.29	0.00	624587.31	697928.74	
9700.00	90.00	0.00	8240.00	1615.81	452.55	1651.83	0.00	624687.31	697928.74	
9800.00	90.00	0.00	8240.00	1715.81	452.55	1751.37	0.00	624787.31	697928.74	
9900.00	90.00	0.00	8240.00	1815.81	452.55	1850.90	0.00	624887.31	697928.74	
10000.00	90.00	0.00	8240.00	1915.81	452.55	1950.44	0.00	624987.31	697928.74	
10100.00	90.00	0.00	8240.00	2015.81	452.55	2049.98	0.00	625087.31	697928.74	
10200.00	90.00	0.00	8240.00	2115.81	452.55	2149.51	0.00	625187.31	697928.74	
10300.00	90.00	0.00	8240.00	2215.81	452.55	2249.05	0.00	625287.31	697928.74	
10400.00	90.00	0.00	8240.00	2315.81	452.55	2348.59	0.00	625387.31	697928.74	
10500.00	90.00	0.00	8240.00	2415.81	452.55	2448.13	0.00	625487.31	697928.74	
10600.00	90.00	0.00	8240.00	2515.81	452.55	2547.66	0.00	625587.31	697928.74	
10700.00	90.00	0.00	8240.00	2615.81	452.55	2647.20	0.00	625687.31	697928.74	
10800.00	90.00	0.00	8240.00	2715.81	452.55	2746.74	0.00	625787.31	697928.74	
10900.00	90.00	0.00	8240.00	2815.81	452.55	2846.27	0.00	625887.31	697928.74	
11000.00	90.00	0.00	8240.00	2915.81	452.55	2945.81	0.00	625987.31	697928.74	
11100.00	90.00	0.00	8240.00	3015.81	452.55	3045.35	0.00	626087.31	697928.74	
11200.00	90.00	0.00	8240.00	3115.81	452.55	3144.89	0.00	626187.31	697928.74	
11300.00	90.00	0.00	8240.00	3215.81	452.55	3244.42	0.00	626287.31	697928.74	
11400.00	90.00	0.00	8240.00	3315.81	452.55	3343.96	0.00	626387.31	697928.74	
11500.00	90.00	0.00	8240.00	3415.81	452.55	3443.50	0.00	626487.31	697928.74	
11600.00	90.00	0.00	8240.00	3515.81	452.55	3543.03	0.00	626587.31	697928.74	
11700.00	90.00	0.00	8240.00	3615.81	452.55	3642.57	0.00	626687.31	697928.74	
11800.00	90.00	0.00	8240.00	3715.81	452.55	3742.11	0.00	626787.31	697928.74	
11900.00	90.00	0.00	8240.00	3815.81	452.55	3841.64	0.00	626887.31	697928.74	
12000.00	90.00	0.00	8240.00	3915.81	452.55	3941.18	0.00	626987.31	697928.74	
12100.00	90.00	0.00	8240.00	4015.81	452.55	4040.72	0.00	627087.31	697928.74	
12200.00	90.00	0.00	8240.00	4115.81	452.55	4140.26	0.00	627187.31	697928.74	
12300.00	90.00	0.00	8240.00	4215.81	452.55	4239.79	0.00	627287.31	697928.74	
12400.00	90.00	0.00	8240.00	4315.81	452.55	4339.33	0.00	627387.31	697928.74	
12500.00	90.00	0.00	8240.00	4415.81	452.55	4438.87	0.00	627487.31	697928.74	
12600.00	90.00	0.00	8240.00	4515.81	452.55	4538.40	0.00	627587.31	697928.74	
12700.00	90.00	0.00	8240.00	4615.81	452.55	4637.94	0.00	627687.31	697928.74	
12770.94	90.00	0.00	8240.00	4686.75	452.55	4708.55	0.00	627758.25	697928.74	PBHL

Targets

Name	Description Dip.	Dir.	TVD ft	+N/-S ft	+E/-W ft	Map Northing ft	Map Easting ft	<--- Latitude --->			<--- Longitude --->		
PBHL			8240.00	4686.75	452.55	627758.25	697928.74	32	43	28.954 N	103	49	26.913 W



Weatherford International, Inc.

Directional Plan Report



Weatherford

Company: Devon Energy	Date: 7/29/2010	Time: 12:37:24	Page: 3
Field: Eddy Co., NM (NAD 83)	Co-ordinate(NE) Reference:	Well: Serene Sisters 25 Fed 3H	
Site: Serene Sisters 25 Fed 3H	Vertical (TVD) Reference:	SITE 3692.1	
Well: Serene Sisters 25 Fed 3H	Section (VS) Reference:	Well (0.00N,0.00E,5.52Azi)	
Wellpath: 1	Survey Calculation Method:	Minimum Curvature	Db: Sybase

Casing Points

MD	TVD	Diameter	Hole Size	Name

Annotation

MD ft	TVD ft	
7667.04	7667.04	KOP
8567.04	8240.00	Landing Pt/Turn
9445.10	8240.00	Hold
12770.93	8240.00	PBHL

Formations


MD	TVD	Formations	Lithology	Dip Angle	Dip Direction




SERENE SISTERS 25 FED 3H
EDDY CO., NEW MEXICO



KH ELEV: 3692.1
GL ELEV: 3667.1



Vertical Section at 5.52° [200ft/in]



Vertical Section at 5.52° [500ft/in]

SECTION DETAILS									
Sec	MD	Inc	Azi	TVD	+N/-S	+E/-W	DLeg	TFace	VSec Target
1	0.00	0.00	26.34	0.00	0.00	0.00	0.00	0.00	0.00
2	7667.04	0.00	26.34	7667.04	0.00	0.00	0.00	26.34	0.00
3	8567.04	90.00	26.34	8240.00	513.00	252.23	10.00	26.34	535.52
4	9445.10	90.00	0.00	8240.00	1340.91	452.55	3.00	-90.00	1398.11
5	12770.94	90.00	0.00	8240.00	4686.75	452.55	0.00	0.00	4708.55

WELL DETAILS				
Name	+N/-S	+E/-W	Northing	Eastng
Serene Sisters 25 Fed 3H	0.00	0.00	623071.50	697476.19

Latitude	Longitude	Slot
32°42'42.60"N	103°49'32.47"W	N/A

TARGET DETAILS				
Name	TVD	+N/-S	+E/-W	Northing
PBHL	8240.00	4686.75	452.55	627758.25

Eastng	Shape	Point
697928.74		

FIELD DETAILS

Eddy Co., NM (NAD 83)

Geodetic System: US State Plane Coordinate System 1983

Ellipsoid: GRS 1980

Zone: North Mexico, Eastern Zone

Magnetic Model: IGRF2010

System Datum: Mean Sea Level

Local North: Grid North

SITE DETAILS

Serene Sisters 25 Fed 3H

Site Centre Northing: 623071.50

Eastng: 697476.19

Ground Level: 3667.10

Positional Uncertainty: 0.00

Convergence: 0.27

WELL DETAILS

KB ELEV: 3692.1

GL ELEV: 3667.1

FIELD DETAILS

Eddy Co., NM (NAD 83)

Geodetic System: US State Plane Coordinate System 1983

Ellipsoid: GRS 1980

Zone: North Mexico, Eastern Zone

Magnetic Model: IGRF2010

System Datum: Mean Sea Level

Local North: Grid North

SITE DETAILS

Serene Sisters 25 Fed 3H


Site Centre Northing: 623071.50

Eastng: 697476.19

Ground Level: 3667.10


Positional Uncertainty: 0.00


Convergence: 0.27



H&P Flex Rig Location Layout


2 Well Pad





DEVON ENERGY PRODUCTION COMPANY LP

General Production Facilities Diagram




Attachment to Exhibit #1
NOTES REGARDING BLOWOUT PREVENTERS
Devon Energy Production Company, LP
Serene Sisters 25 Federal 3H


Surface Location: 200' FSL & 1800' FWL, Unit N, Sec 25 T18S R31E, Eddy, NM
Bottom hole Location: 400' FNL & 2310' FWL, Unit C, Sec 25 T18S R31E, Eddy, NM


1. Drilling nipple will be constructed so it can be removed mechanically without the aid of a welder. The minimum internal diameter will equal BOP bore.
2. Wear ring will be properly installed in head.
3. Blowout preventer and all associated fittings will be in operable condition to withstand a minimum 5000 psi working pressure.
4. All fittings will be flanged.
5. A full bore safety valve tested to a minimum 5000 psi WP with proper thread connections will be available on the rotary rig floor at all times.
6. All choke lines will be anchored to prevent movement.
7. All BOP equipment will be equal to or larger in bore than the internal diameter of the last casing string.
8. Will maintain a kelly cock attached to the kelly.
9. Hand wheels and wrenches will be properly installed and tested for safe operation.
10. Hydraulic floor control for blowout preventer will be located as near in proximity to driller's controls as possible.
11. All BOP equipment will meet API standards and include a minimum 40 gallon accumulator having two independent means of power to initiate closing operation.

5,000 PSI CHOKE MANIFOLD



13-5/8" x 5,000 psi BOP Stack





**Devon Energy Corporation
20 North Broadway
Oklahoma City, Oklahoma 73102-8260**

Hydrogen Sulfide (H₂S) Contingency Plan

For



Serene Sisters "25" Federal # 3H

**200' FNL & 1800' FEL,
Sec-25, T-18S R-31E**

Eddy County NM

Serene Sisters "25" Federal # 3H

This is an open drilling site. H₂S monitoring equipment and emergency response equipment will be used within 500' of zones known to contain H₂S, including warning signs, wind indicators and H₂S monitor.



Assumed 100 ppm H₂S = 3000' (Radius of Exposure)
100 ppm H₂S concentration shall trigger activation of this plan.

Escape

Crews shall escape upwind of escaping gas in the event of an emergency release of gas. Escape can be facilitated West/SouthWest on lease road then North to on Westall Road CR249. Crews should then block entrance to the location from the lease road so as not to allow anyone traversing into a hazardous area. The blockade should be at a safe distance outside of the ROE There are no homes or buildings in or near the ROE.

Assumed 100 ppm ROE = 3000'

100 ppm H₂S concentration shall trigger activation of this plan.

Emergency Procedures

In the event of a release of gas containing H₂S, the first responder(s) must

- **Isolate the area and prevent entry by other persons into the 100 ppm ROE.**
- **Evacuate any public places encompassed by the 100 ppm ROE.**
- **Be equipped with H₂S monitors and air packs in order to control the release.**
- **Use the "buddy system" to ensure no injuries occur during the response**
- **Take precautions to avoid personal injury during this operation.**
- **Contact operator and/or local officials to aid in operation. See list of phone numbers attached.**
- **Have received training in the**
 - **Detection of H₂S, and**
 - **Measures for protection against the gas,**
 - **Equipment used for protection and emergency response.**

Ignition of Gas Source

Should control of the well be considered lost and ignition considered, take care to protect against exposure to Sulfur Dioxide (SO₂). Intentional ignition must be coordinated with the NMOCD and local officials. Additionally the NM State Police may become involved. NM State Police shall be the Incident Command on scene of any major release. Take care to protect downwind whenever there is an ignition of the gas

Characteristics of H₂S and SO₂

Common Name	Chemical Formula	Specific Gravity	Threshold Limit	Hazardous Limit	Lethal Concentration
Hydrogen Sulfide	H₂S	1.189 Air = 1	10 ppm	100 ppm/hr	600 ppm
Sulfur Dioxide	SO₂	2.21 Air = 1	2 ppm	N/A	1000 ppm

Contacting Authorities

Devon Energy Corp. personnel must liaison with local and state agencies to ensure a proper response to a major release. Additionally, the OCD must be notified of the release as soon as possible but no later than 4 hours. Agencies will ask for information such as type and volume of release, wind direction, location of release, etc. Be prepared with all information available. The following call list of essential and potential responders has been prepared for use during a release. Devon Energy Corp. Company response must be in coordination with the State of New Mexico's 'Hazardous Materials Emergency Response Plan' (HMER)

Devon Energy Corp. Company Call List

<u>Artesia (575)</u>	<u>Cellular</u>	<u>Office</u>	<u>Home</u>
Foreman – Robert Bell.....	748-7448	748-0178	746-2991
Asst. Foreman –Tommy Polly.....	748-5290	748-0165	748-2846
Don Mayberry.....	748-5235	748-0164	746-4945
Montral Walker.....	390-5182	748-0193	936-414-6246
Engineer – Marcos Ortiz.....	(405) 317-0666....	(405) 552-8152....	(405) 381-4350

Agency Call List

<u>Lea</u>	<u>Hobbs</u>
<u>County</u>	State Police
<u>(575)</u>	City Police
	Sheriff's Office
	Ambulance.....
	Fire Department.....
	LEPC (Local Emergency Planning Committee).....
	NMOCD
	US Bureau of Land Management
<u>Eddy</u>	<u>Carlsbad</u>
<u>County</u>	State Police
<u>(575)</u>	City Police
	Sheriff's Office
	Ambulance.....
	Fire Department.....
	LEPC (Local Emergency Planning Committee).....
	US Bureau of Land Management
	New Mexico Emergency Response Commission (Santa Fe) ...
	24 HR
	National Emergency Response Center (Washington, DC) ..


Emergency Services

	Boots & Coots IWC
	Cudd Pressure Control.....
	Halliburton
	B. J. Services.....
<i>Give</i>	Flight For Life - Lubbock, TX
<i>GPS</i>	Aerocare - Lubbock, TX
<i>position:</i>	Med Flight Air Amb - Albuquerque, NM
	Lifeguard Air Med Svc. Albuquerque, NM

Prepared in conjunction with
Wade Rohloff of;



Closed Loop Equipment Diagram



District I
1625 N. French Dr., Hobbs, NM 88240
District II
1301 W. Grand Avenue, Artesia, NM 88210
District III
1000 Rio Brazos Road, Aztec, NM 87410
District IV
1220 S. St. Francis Dr., Santa Fe, NM 87505

State of New Mexico
Energy Minerals and Natural Resources
Department
Oil Conservation Division
1220 South St. Francis Dr.
Santa Fe, NM 87505

Form C-144 CLEZ
July 21, 2008

For closed-loop systems that only use above ground steel tanks or haul-off bins and propose to implement waste removal for closure, submit to the appropriate NMOCD District Office.

Closed-Loop System Permit or Closure Plan Application

(that only use above ground steel tanks or haul-off bins and propose to implement waste removal for closure)

Type of action: ☒ Permit ☐ Closure

Instructions: Please submit one application (Form C-144 CLEZ) per individual closed-loop system request. For any application request other than for a closed-loop system that only use above ground steel tanks or haul-off bins and propose to implement waste removal for closure, please submit a Form C-144.

Please be advised that approval of this request does not relieve the operator of liability should operations result in pollution of surface water, ground water or the environment. Nor does approval relieve the operator of its responsibility to comply with any other applicable governmental authority's rules, regulations or ordinances.

1. Operator: Devon Energy Production Co., LP OGRID #: 6137
Address: 20 North Broadway OKC, OK 73102-8260
Facility or well name: Serene Sisters 25 Federal 3H
API Number: _____ OCD Permit Number: _____
U/L or Qtr/Qtr SESW Section 25 Township 18S Range 31E County: Eddy County, NM
Center of Proposed Design: Latitude _____ Longitude _____ NAD: ☐ 1927 ☐ 1983
Surface Owner: ☒ Federal ☐ State ☐ Private ☐ Tribal Trust or Indian Allotment



2. ☒ **Closed-loop System:** Subsection H of 19.15.17.11 NMAC
Operation: ☒ Drilling a new well ☐ Workover or Drilling (Applies to activities which require prior approval of a permit or notice of intent) ☐ P&A
☒ Above Ground Steel Tanks or ☒ Haul-off Bins

3. **Signs:** Subsection C of 19.15.17.11 NMAC
☐ 12"x 24", 2" lettering, providing Operator's name, site location, and emergency telephone numbers
☒ Signed in compliance with 19.15.3.103 NMAC

4. **Closed-loop Systems Permit Application Attachment Checklist:** Subsection B of 19.15.17.9 NMAC
Instructions: Each of the following items must be attached to the application. Please indicate, by a check mark in the box, that the documents are attached.
☒ Design Plan - based upon the appropriate requirements of 19.15.17.11 NMAC
☒ Operating and Maintenance Plan - based upon the appropriate requirements of 19.15.17.12 NMAC
☒ Closure Plan (Please complete Box 5) - based upon the appropriate requirements of Subsection C of 19.15.17.9 NMAC and 19.15.17.13 NMAC
☐ Previously Approved Design (attach copy of design) API Number: _____
☐ Previously Approved Operating and Maintenance Plan API Number: _____

5. **Waste Removal Closure For Closed-loop Systems That Utilize Above Ground Steel Tanks or Haul-off Bins Only:** (19.15.17.13.D NMAC)
Instructions: Please identify the facility or facilities for the disposal of liquids, drilling fluids and drill cuttings. Use attachment if more than two facilities are required.

Disposal Facility Name: CRI Disposal Facility Permit Number: R9166
Disposal Facility Name: _____ Disposal Facility Permit Number: _____

Will any of the proposed closed-loop system operations and associated activities occur on or in areas that will not be used for future service and operations?
☐ Yes (If yes, please provide the information below) ☒ No

Required for impacted areas which will not be used for future service and operations:

- ☐ Soil Backfill and Cover Design Specifications - based upon the appropriate requirements of Subsection H of 19.15.17.13 NMAC
☐ Re-vegetation Plan - based upon the appropriate requirements of Subsection I of 19.15.17.13 NMAC
☐ Site Reclamation Plan - based upon the appropriate requirements of Subsection G of 19.15.17.13 NMAC

6. **Operator Application Certification:**

I hereby certify that the information submitted with this application is true, accurate and complete to the best of my knowledge and belief.

Name (Print): Stephanie A. Ysasaga Title: Sr. Staff Engineering Technician

Signature: [Signature] Date: 08/02/2010

e-mail address: Stephanie.Ysasaga@dmn.com Telephone: (405)-552-7802

7. **OCD Approval:** ☐ Permit Application (including closure plan) ☐ Closure Plan (only)

OCD Representative Signature: _____ Approval Date: _____

Title: _____ OCD Permit Number: _____

8. **Closure Report (required within 60 days of closure completion):** Subsection K of 19.15.17.13 NMAC

Instructions: Operators are required to obtain an approved closure plan prior to implementing any closure activities and submitting the closure report. The closure report is required to be submitted to the division within 60 days of the completion of the closure activities. Please do not complete this section of the form until an approved closure plan has been obtained and the closure activities have been completed.

☐ Closure Completion Date: _____

9. **Closure Report Regarding Waste Removal Closure For Closed-loop Systems That Utilize Above Ground Steel Tanks or Haul-off Bins Only:**

Instructions: Please indentify the facility or facilities for where the liquids, drilling fluids and drill cuttings were disposed. Use attachment if more than two facilities were utilized.

Disposal Facility Name: _____ Disposal Facility Permit Number: _____

Disposal Facility Name: _____ Disposal Facility Permit Number: _____

Were the closed-loop system operations and associated activities performed on or in areas that *will not* be used for future service and operations?

☐ Yes (If yes, please demonstrate compliance to the items below) ☐ No

Required for impacted areas which will not be used for future service and operations:

☐ Site Reclamation (Photo Documentation)

☐ Soil Backfilling and Cover Installation

☐ Re-vegetation Application Rates and Seeding Technique

10. **Operator Closure Certification:**

I hereby certify that the information and attachments submitted with this closure report is true, accurate and complete to the best of my knowledge and belief. I also certify that the closure complies with all applicable closure requirements and conditions specified in the approved closure plan.


Name (Print): _____ Title: _____

Signature: _____ Date: _____

e-mail address: _____ Telephone: _____



Commitment Runs Deep



Design Plan
Operation and Maintenance Plan
Closure Plan

SENM - Closed Loop Systems
June 2008

I. Design Plan

Devon uses MI SWACO closed loop system (CLS). The MI SWACO CLS is designed to maintain drill solids at or below 5%. The equipment is arranged to progressively remove solids from the largest to the smallest size. Drilling fluids can thus be reused and savings is realized on mud and disposal costs. Dewatering may be required with the centrifuges to insure removal of ultra fine solids.

The drilling location is constructed to allow storm water to flow to a central sump normally the cellar. This insures no contamination leaves the drilling pad in the event of a spill. Storm water is reused in the mud system or stored in a reserve fluid tank farm until it can be reused. All lubricants, oils, or chemicals are removed immediately from the ground to prevent the contamination of storm water. An oil trap is normally installed on the sump if an oil spill occurs during a storm.

A tank farm is utilized to store drilling fluids including fresh water and brine fluids. The tank farm is constructed on a 20 ml plastic lined, bermed pad to prevent the contamination of the drilling site during a spill. Fluids from other sites may be stored in these tanks for processing by the solids control equipment and reused in the mud system. At the end of the well the fluids are transported from the tank farm to an adjoining well or to the next well for the rig.

Prior to installing a closed-loop system on site, the topsoil, if present, will be stripped and stockpiled for use as the final cover or fill at the time of closure.

Signs will be posted on the fence surrounding the closed-loop system unless the closed-loop system is located on a site where there is an existing well, that is operated by Devon.


II. Operations and Maintenance Plan

Primary Shakers: The primary shakers make the first removal of drill solids from the drilling mud as it leaves the well bore. The shakers are sized to handle maximum drilling rate at optimal screen size. The shakers normally remove solids down to 74 microns.

Mud Cleaner: The Mud Cleaner cleans the fluid after it leaves the shakers. A set of hydrocyclones are sized to handle 1.25 to 1.5 times the maximum circulating rate. This ensures all the fluid is being processed to an average cut point of 25 microns. The wet discharged is dewatered on a shaker equipped with ultra fine mesh screens and generally cut at 40 microns.

devon

Closed Loop Schematic



MISWACO

Centrifuges: The centrifuges can be one or two in number depending on the well geometry or depth of well. The centrifuges are sized to maintain low gravity solids at 5% or below. They may or may not need a dewatering system to enhance the removal rates. The centrifuges can make a cut point of 8-10 microns depending on bowl speed, feed rate, solids loading and other factors.

The centrifuge system is designed to work on the active system and be flexible to process incoming fluids from other locations. This set-up is also dependant on well factors.

Dewatering System: The dewatering system is a chemical mixing and dosing system designed to enhance the solids removal of the centrifuge. Not commonly used in shallow wells. It may contain pH adjustment, coagulant mixing and dosing, and polymer mixing and dosing. Chemical flocculation binds ultra fine solids into a mass that is within the centrifuge operating design. The

dewatering system improves the centrifuge cut point to infinity or allows for the return of clear water or brine fluid. This ability allows for the ultimate control of low gravity solids.

Cuttings Boxes: Cuttings boxes are utilized to capture drill solids that are discarded from the solids control equipment. These boxes are set upon a rail system that allows for the removal and replacement of a full box of cuttings with an empty one. They are equipped with a cover that insures no product is spilled into the environment during the transportation phase.

Process Tank: (Optional) The process tank allows for the holding and process of fluids that are being transferred into the mud system. Additionally, during times of lost circulation the process tank may hold active fluids that are removed for additional treatment. It can further be used as a mixing tank during well control conditions.

Sump and Sump Pump: The sump is used to collect storm water and the pump is used to transfer this fluid to the active system or to the tank for to hold in reserve. It can also be used to collect fluids that may escape during spills. The location contains drainage ditches that allow the location fluids to drain to the sump.

Reserve Fluids (Tank Farm): A series of frac tanks are used to replace the reserve pit. These are steel tanks that are equipped with a manifold system and a transfer pump. These tanks can contain any number of fluids used during the drilling process. These can include fresh water, cut brine, and saturated salt fluid. The fluid can be from the active well or reclaimed fluid from other locations. A 20 ml liner and berm system is employed to ensure the fluids do not migrate to the environment during a spill.

If a leak develops, the appropriate division district office will be notified within 48 hours of the discovery and the leak will be addressed. Spill prevention is accomplished by maintaining pump packing, hoses, and pipe fittings to insure no leaks are occurring. During an upset condition the source of the spill is isolated and repaired as soon as it is discovered. Free liquid is removed by a diaphragm pump and returned to the mud system. Loose topsoil may be used to stabilize the spill and the contaminated soil is excavated and placed in the cuttings boxes. After the well is finished and the rig has moved, the entire location is scrapped and testing will be performed to determine if a release has occurred.

All trash is kept in a wire mesh enclosure and removed to an approved landfill when full. All spent motor oils are kept in separate containers and they are removed and sent to an approved recycling center. Any spilled lubricants, pipe

dope, or regulated chemicals are removed from soil and sent to landfills approved for these products.

These operations are monitored by Mi Swaco service technicians. Daily logs are maintained to ensure optimal equipment operation and maintenance. Screen and chemical use is logged to maintain inventory control. Fluid properties are monitored and recorded and drilling mud volumes are accounted for in the mud storage farm. This data is kept for end of well review to insure performance goals are met. Lessons learned are logged and used to help with continuous improvement.

A MI SWACO field supervisor manages from 3-5 wells. They are responsible for training personnel, supervising installations, and inspecting sites for compliance of MI SWACO safety and operational policy.

III. Closure Plan

A maximum 340' X 340' caliche pad is built per well. All of the trucks and steel tanks fit on this pad. All fluid cuttings go to the steel tanks to be hauled by various trucking companies to an agency approved disposal.

SURFACE USE PLAN

Devon Energy Production Company, LP

Serene Sisters 25 Federal 3H

Surface Location: 200' FSL & 1800' FWL, Unit N, Sec 25 T18S R31E, Eddy, NM

Bottom hole Location: 400' FNL & 2310' FWL, Unit C, Sec 25 T18S R31E, Eddy, NM

1. Existing Roads:

- a. The well site and elevation plat for the proposed well are reflected on the well site layout; Form C-102. The well was staked by Basin Surveys.
- b. All roads into the location are depicted on the surveyor plats.
- c. Directions to Location: From State Hwy 82 and CR# 222 go south on CR# 222 (paved) 4.0 miles and turn left on caliche CR #249 and go south 1.3 miles, turn left on caliche road and to east 1.0 miles, turn right and go south 0.13 miles to a proposed road survey and follow flags east 477', bend left and follow flags NE 983', bend left and follow flags north 110' to the SW corner of proposed pad for this location. Routine grading and maintenance of existing roads will be conducted as necessary to maintain their condition as long as any operations continue on this lease.
- d. If existing road is shared with other operators, Devon will share in its cost to maintain the road as required by the BLM.

2. New or Reconstructed Access Roads:

- a. The well site layout, Form C-102 shows approximately 1570' of new access road will be constructed as follows:
- b. The maximum width of the road will be 14'. It will be crowned and made of 6" of rolled and compacted caliche. Water will be deflected, as necessary, to avoid accumulation and prevent surface erosion.
- c. Surface material will be native caliche. This material will be obtained from a BLM approved pit nearest in proximity to the location. The average grade will be approximately 2%.
- d. No cattle guards, grates or fence cuts will be required. No turnouts are planned.

3. Location of Existing Wells:

1 Mile Radius Plat shows all existing and proposed wells within a one-mile radius of the proposed location. See attached plat.

4. Location of Existing and/or Proposed Production Facilities:

- a. In the event the well is found productive, the Serene Sisters 25 Federal 3H/4H tank battery would be utilized and shared, and the necessary production equipment will be installed at the well site. The tank battery would be located at the Serene Sisters 25 Federal 3 and Serene Sisters 25 Federal 4 well pad located in Sec 25-T18S-R31E.
- b. If necessary, the well will be operated by means of an electric prime mover. Electric power poles will be set along side of the access road.
- c. All flowlines will adhere to API standards.
- d. If the well is productive, rehabilitation plans are as follows:
 - i. A closed loop system will be utilized.
 - ii. The original topsoil from the well site will be returned to the location. The drill site will then be contoured as close as possible to the original state.

4. Location and Types of Water Supply:

This location will be drilled using a combination of water mud systems (outlined in the Drilling Program). The water will be obtained from commercial water stations in the area and hauled to location by transport truck using the existing and proposed roads shown in the C-102. On occasion, water will be obtained from a pre-existing water well, running a pump directly to the drill rig. In these cases where a poly pipeline is used to transport water for drilling purposes, proper authorizations will be secured. If a poly pipeline is used, the size, distance, and map showing route will be provided to the BLM via sundry notice.

5. Construction Materials:

The caliche utilized for the drilling pad and proposed access road will be from minerals that are located onsite or will be used onsite. If minerals are not available onsite, then an established mineral pit will be used to build the location and stem road.

6. Methods of Handling Waste Material:

- a. Drill cuttings will be disposed of in a closed loop system.
- b. All trash, junk and other waste material will be contained in trash cages or trash bins to prevent scattering. When the job is completed all contents will be removed and disposed of in an approved sanitary landfill.
- c. The supplier, including broken sacks, will pick up salts remaining after completion of well.
- d. A Porto-john will be provided for the rig crews. This equipment will be properly maintained during the drilling and completion operations and will be removed when all operations are complete.
- e. Remaining drilling fluids will be sent to a closed loop system. Water produced during completion will be put into a closed loop system. Oil and condensate produced will be put into a storage tank and sold.
- f. Disposal of fluids to be transported by the following companies:
 - i. American Production Service Inc, Odessa TX
 - ii. Gandy Corporation, Lovington NM
 - iii. I & W Inc, Loco Hill NM
 - iv. Jims Water Service of Co Inc, Denver CO

7. Ancillary Facilities: No campsite or other facilities will be constructed as a result of this well.

8. Well Site Layout

- a. The rig layout diagram shows the proposed well site layout with dimensions of the pad layout.
- b. This exhibit indicated proposed location of reserve and sump pits and living facilities.
- c. A closed loop system will be utilized.
- d. If a pit or closed loop system will be utilized, Devon will comply with the NMOCD requirements 19.15.17 and submit form C-144 CLEZ to the appropriate NMOCD District Office. An unapproved copy is provided within the APD.
- e. Topsoil Stockpiling:
 - i. Standard practice is topsoil will be pushed to the high side of location to prevent water from running across location to control erosion. If a cut out is done and there are two or three high sides, we will use those there.

9. Plans for Surface Reclamation Include Both Final & Interim:

- a. After concluding the drilling and/or completion operations, if the well is found non-commercial, the caliche will be removed from the pad and used for other drilling locations, repair existing roads, repair existing locations, etc. The road will be reclaimed as directed by the BLM. The original top soil will again be returned to the pad and contoured, as close as possible, to the original topography. We will use a closed loop system.
- b. The location and road will be rehabilitated as recommended by the BLM.
- c. If the well is deemed commercially productive, caliche from areas of the pad site not required for operations will be reclaimed. The original top soil will be returned to the area of the drill pad not necessary to operate the well. These unused areas of the drill pad will be contoured, as close as possible, to match the original topography.
- d. All disturbed areas not needed for active support of production operations will undergo interim reclamation. The portions of the cleared well site not needed for operational and safety purposes will be recontoured to a final or intermediate contour that blends with the surrounding topography as much as possible. Topsoil will be respread over areas not needed for all-weather operations.

10. Surface Ownership

- a. The surface is owned by the US Government and is administered by the Bureau of Land Management. The surface is multiple use with the primary uses of the region for the grazing of livestock and the production of oil and gas.
- b. The proposed road routes and the surface location will be restored as directed by the BLM.

11. Other Information:

- a. The area surrounding the well site is grassland. The topsoil is very sandy in nature. The vegetation is moderately sparse with native prairie grass, sagebush, yucca and miscellaneous weeds. No wildlife was observed but it is likely that deer, rabbits, coyotes, and rodents traverse the area.
- b. There is no permanent or live water in the general proximity of the location.
- c. There are no dwellings within 2 miles of location.
- d. A Cultural Resources Examination will be completed by Southern New Mexico Archaeological Services, Inc. and forwarded to the BLM office in Carlsbad, New Mexico.

13. Bond Coverage:

Bond Coverage is Nationwide; Bond # is CO-1104

Operators Representative:

The Devon Energy Production Company, L.P. representatives responsible for ensuring compliance of the surface use plan are listed below.

Steven Jones
Operations Engineer Advisor

Don Mayberry
Superintendent

Devon Energy Production Company, L.P.
20 North Broadway, Suite 1500
Oklahoma City, OK 73102-8260

Devon Energy Production Company, L.P.
Post Office Box 250
Artesia, NM 88211-0250

(405) 552-7994 (office)
(405) 596-8041 (cell)

(505) 748-0164 (office)
(505) 748-5235 (cell)

Certification

I hereby certify that I, or persons under my direct supervision, have inspected the proposed drill site and access road proposed herein; that I am familiar with the conditions that presently exist; that I have full knowledge of State and Federal laws applicable to this operation; that the statements made in this APD package are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or Devon Energy Production Company, L.P. am responsible for the operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filing of false statements.

I hereby also certify that I, or Devon Energy Production Company, L.P. have made a good faith effort to provide the surface owner with a copy of the Surface Use Plan of Operations and any Conditions of Approval that are attached to the APD.

Executed this 4th day of August, 2010.

Printed Name: Stephanie A. Ysasaga

Signed Name: 

Position Title: Sr. Staff Engineering Technician

Address: 20 North Broadway, OKC OK 73102

Telephone: (405) 552-7802

Field Representative (if not above signatory): Don Mayberry (see above)

Address (if different from above):

Telephone (if different from above):

E-mail (optional):

PECOS DISTRICT CONDITIONS OF APPROVAL

OPERATOR'S NAME:	Devon Energy Prod Co
LEASE NO.:	LC065680
WELL NAME & NO.:	3H-Serene Sisters 25 Federal
SURFACE HOLE FOOTAGE:	200' FSL & 1800' FWL
BOTTOM HOLE FOOTAGE:	400' FNL & 2310' FWL
LOCATION:	Section 25, T. 18 S., R 31 E., NMPM
COUNTY:	Eddy County, New Mexico

TABLE OF CONTENTS

Standard Conditions of Approval (COA) apply to this APD. If any deviations to these standards exist or special COAs are required, the section with the deviation or requirement will be checked below.

- ☐ **General Provisions**
- ☐ **Permit Expiration**
- ☐ **Archaeology, Paleontology, and Historical Sites**
- ☐ **Noxious Weeds**
- ☒ **Special Requirements**
 - Lesser Prairie-Chicken Timing Stipulations
 - Ground-level Abandoned Well Marker
 - Access road
 - Pad restriction
- ☐ **Construction**
 - Notification
 - V-Door Direction
 - Topsoil
 - Closed Loop System
 - Federal Mineral Material Pits
 - Well Pads
 - Roads
- ☐ **Road Section Diagram**
- ☒ **Drilling**
 - Logging requirements
 - H₂S – Onshore Order #6
 - Waste Material and Fluids
- ☐ **Production (Post Drilling)**
 - Well Structures & Facilities
 - Pipelines
 - Electric Lines
- ☒ **Interim Reclamation**
- ☒ **Final Abandonment & Reclamation**

I. GENERAL PROVISIONS

The approval of the Application For Permit To Drill (APD) is in compliance with all applicable laws and regulations: 43 Code of Federal Regulations 3160, the lease terms, Onshore Oil and Gas Orders, Notices To Lessees, New Mexico Oil Conservation Division (NMOCD) Rules, National Historical Preservation Act As Amended, and instructions and orders of the Authorized Officer. Any request for a variance shall be submitted to the Authorized Officer on Form 3160-5, Sundry Notices and Report on Wells.

II. PERMIT EXPIRATION

If the permit terminates prior to drilling and drilling cannot be commenced within 60 days after expiration, an operator is required to submit Form 3160-5, Sundry Notices and Reports on Wells, requesting surface reclamation requirements for any surface disturbance. However, if the operator will be able to initiate drilling within 60 days after the expiration of the permit, the operator must have set the conductor pipe in order to allow for an extension of 60 days beyond the expiration date of the APD. (Filing of a Sundry Notice is required for this 60 day extension.)

III. ARCHAEOLOGICAL, PALEONTOLOGY & HISTORICAL SITES

Any cultural and/or paleontological resource discovered by the operator or by any person working on the operator's behalf shall immediately report such findings to the Authorized Officer. The operator is fully accountable for the actions of their contractors and subcontractors. The operator shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery shall be made by the Authorized Officer to determine the appropriate actions that shall be required to prevent the loss of significant cultural or scientific values of the discovery. The operator shall be held responsible for the cost of the proper mitigation measures that the Authorized Officer assesses after consultation with the operator on the evaluation and decisions of the discovery. Any unauthorized collection or disturbance of cultural or paleontological resources may result in a shutdown order by the Authorized Officer.

IV. NOXIOUS WEEDS

The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes the roads, pads, associated pipeline corridor, and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

V. SPECIAL REQUIREMENT(S)

Timing Limitation Stipulation / Condition of Approval for lesser prairie-chicken:
Oil and gas activities including 3-D geophysical exploration, and drilling will not be allowed in lesser prairie-chicken habitat during the period from March 1st through June 15th annually. During that period, other activities that produce noise or involve human activity, such as the maintenance of oil and gas facilities, pipeline, road, and well pad construction, will be allowed except between 3:00 am and 9:00 am. The 3:00 am to 9:00 am restriction will not apply to normal, around-the-clock operations, such as venting, flaring, or pumping, which do not require a human presence during this period. Additionally, no new drilling will be allowed within up to 200 meters of leks known at the time of permitting. Normal vehicle use on existing roads will not be restricted. Exhaust noise from pump jack engines must be muffled or otherwise controlled so as not to exceed 75 db measured at 30 feet from the source of the noise.

Ground-level Abandoned Well Marker to avoid raptor perching: Upon the plugging and subsequent abandonment of the well, the well marker will be installed at ground level on a plate containing the pertinent information for the plugged well. For more installation details, contact the Carlsbad Field Office at 575-234-5972.

Attention: The proposed action occurs within the Southpaw Lesser Prairie-Chicken Habitat Evaluation Area (HEA) as described in the 2008 Special Status Species Resource Management Plan Amendment. Therefore, according to the prescriptions set forth in the RMPA for management of HEAs, non-emergency exceptions to the Timing Limitation Condition-of-Approval will not be granted to afford the species protection during its breeding season.

Access road

The 1570 feet of access road exiting the well and traveling to the southwest shall be constructed on the east side of the buried pipeline.

Pad restriction

Limit pad to 190 feet east from Serene Sister 25 Federal 3H center hole to avoid archeological site

Limit pad to 150 feet north from center hole to avoid sand dunes

VI. CONSTRUCTION

A. NOTIFICATION

The BLM shall administer compliance and monitor construction of the access road and well pad. Notify the Carlsbad Field Office at (575) 234-5972 at least 3 working days prior to commencing construction of the access road and/or well pad.

When construction operations are being conducted on this well, the operator shall have the approved APD and Conditions of Approval (COA) on the well site and they shall be made available upon request by the Authorized Officer.

B. V-DOOR DIRECTION: west

C. TOPSOIL

The operator shall stockpile the topsoil in a low profile manner in order to prevent wind/water erosion of the topsoil. The topsoil to be stripped is approximately 6 inches in depth. The topsoil will be used for interim and final reclamation.

D. CLOSED LOOP SYSTEM

Tanks are required for drilling operations: No Pits.

The operator shall properly dispose of drilling contents at an authorized disposal site.

E. FEDERAL MINERAL MATERIALS PIT

Payment shall be made to the BLM prior to removal of any federal mineral materials. Call the Carlsbad Field Office at (575) 234-5972.

F. WELL PAD SURFACING

Surfacing of the well pad is not required.

If the operator elects to surface the well pad, the surfacing material may be required to be removed at the time of reclamation.

The well pad shall be constructed in a manner which creates the smallest possible surface disturbance, consistent with safety and operational needs.

G. ON LEASE ACCESS ROADS

Road Width

The access road shall have a driving surface that creates the smallest possible surface disturbance and does not exceed fourteen (14) feet in width. The maximum width of surface disturbance, when constructing the access road, shall not exceed thirty (30) feet.

Surfacing

Surfacing material is not required on the new access road driving surface. If the operator elects to surface the new access road or pad, the surfacing material may be required to be removed at the time of reclamation.

Where possible, no improvements should be made on the unsurfaced access road other than to remove vegetation as necessary, road irregularities, safety issues, or to fill low areas that may sustain standing water.

The Authorized Officer reserves the right to require surfacing of any portion of the access road at any time deemed necessary. Surfacing may be required in the event the road deteriorates, erodes, road traffic increases, or it is determined to be beneficial for future field development. The surfacing depth and type of material will be determined at the time of notification.

Crowning


Crowning shall be done on the access road driving surface. The road crown shall have a grade of approximately 2% (i.e., a 1" crown on a 14' wide road). The road shall conform to Figure 1; cross section and plans for typical road construction.

Ditching

Ditching shall be required on both sides of the road.

Turnouts

Vehicle turnouts shall be constructed on the road. Turnouts shall be intervisible with interval spacing distance less than 1000 feet. Turnouts shall be constructed on all blind curves. Turnouts shall conform to the following diagram:




Drainage

Drainage control systems shall be constructed on the entire length of road (e.g. ditches, sidehill outslowing and inslaping, lead-off ditches, culvert installation, and low water crossings).

A typical lead-off ditch has a minimum depth of 1 foot below and a berm of 6 inches above natural ground level. The berm shall be on the down-slope side of the lead-off ditch.

Cross Section of a Typical Lead-off Ditch



All lead-off ditches shall be graded to drain water with a 1 percent minimum to 3 percent maximum ditch slope. The spacing interval are variable for lead-off ditches and shall be determined according to the formula for spacing intervals of lead-off ditches, but may be amended depending upon existing soil types and centerline road slope (in %);

Formula for Spacing Interval of Lead-off Ditches

Example - On a 4% road slope that is 400 feet long, the water flow shall drain water into a lead-off ditch. Spacing interval shall be determined by the following formula:

$$400 \text{ foot road with } 4\% \text{ road slope: } \frac{400'}{4\%} + 100' = 200' \text{ lead-off ditch interval}$$

Culvert Installations

Appropriately sized culvert(s) shall be installed at the deep waterway channel flow crossing.

Cattleguards

An appropriately sized cattleguard(s) sufficient to carry out the project shall be installed and maintained at fence crossing(s).

Any existing cattleguard(s) on the access road shall be repaired or replaced if they are damaged or have deteriorated beyond practical use. The operator shall be responsible for the condition of the existing cattleguard(s) that are in place and are utilized during lease operations.

A gate shall be constructed and fastened securely to H-braces.

Fence Requirement


Where entry is required across a fence line, the fence shall be braced and tied off on both sides of the passageway prior to cutting.

The operator shall notify the private surface landowner or the grazing allotment holder prior to crossing any fence(s).

Public Access

Public access on this road shall not be restricted by the operator without specific written approval granted by the Authorized Officer.

Figure 1 – Cross Sections and Plans For Typical Road Sections



VII. DRILLING

A. DRILLING OPERATIONS REQUIREMENTS

The BLM is to be notified a minimum of 4 hours in advance for a representative to witness:

- a. Spudding well
- b. Setting and/or Cementing of all casing strings
- c. BOPE tests

☒ **Eddy County**

Call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220,
(575) 361-2822

1. A Hydrogen Sulfide (H₂S) Drilling Plan should be activated 500 feet prior to drilling into the Yates formation. **As a result, the Hydrogen Sulfide area must meet Onshore Order 6 requirements, which includes equipment and personnel/public protection items. If Hydrogen Sulfide is encountered, please provide measured values and formations to the BLM.**
2. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval. **If the drilling rig is removed without approval – an Incident of Non-Compliance will be written and will be a “Major” violation.**
3. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works are located, this does not include the dog house or stairway area.
4. **The record of the drilling rate along with the GR/N well log run from TD to surface (horizontal well – vertical portion of hole) will be submitted to the BLM office as well as all other logs run on the borehole 30 days from completion. If available, a digital copy of the logs is to be submitted in addition to the paper copies. The Rustler top and top and bottom of Salt are to be recorded on the Completion Report.**

B. CASING

Changes to the approved APD casing and cement program require submitting a sundry and receiving approval prior to work. Failure to obtain approval prior to work will result in an Incident of Non-Compliance being issued.

Centralizers required on surface casing per Onshore Order 2.III.B.1.f.

Wait on cement (WOC) time prior to drilling out for a primary cement job will be a minimum 18 hours for a water basin, 24 hours in the potash area, or 500 pounds compressive strength, whichever is greater for all casing strings. DURING THIS WOC TIME, NO DRILL PIPE, ETC. SHALL BE RUN IN THE HOLE. Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. See individual casing strings for details regarding lead cement slurry requirements.

No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.

Possible water and brine flows in the Salado and Artesia groups.

1. The 13-3/8 inch surface casing shall be set at **approximately 930 feet (a minimum of 25 feet into the Rustler Anhydrite and above the salt)** and cemented to the surface. **Fresh water mud to be used to setting depth.**
 - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.
 - b. **Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry.**
 - c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.
 - d. If cement falls back, remedial cementing will be done prior to drilling out that string.
2. The minimum required fill of cement behind the 9-5/8 inch intermediate casing is:
☒ Cement to surface. If cement does not circulate see B.1.a, c-d above.

Formation below the 9-5/8" shoe to be tested according to Onshore Order 2.III.B.1.i. Test to be done as a mud equivalency test using the mud weight necessary for the pore pressure of the formation below the shoe (not the mud weight required to prevent dissolving the salt formation) and the mud weight for the bottom of the hole. Report results to BLM office.

Centralizers required on horizontal leg, must be type for horizontal service and minimum of one every other joint.

3. The minimum required fill of cement behind the 5-1/2 inch production casing is:

a. First stage to DV tool, cement shall:

☒ Cement to circulate. If cement does not circulate, contact the appropriate BLM office before proceeding with second stage cement job. Operator should have plans as to how they will achieve circulation on the next stage.

b. Second stage above DV tool, cement shall:

☒ Cement should tie-back at least 500 feet into previous casing string. Operator shall provide method of verification.

4. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.

C. PRESSURE CONTROL

1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in Onshore Oil and Gas Order No. 2 and API RP 53 Sec. 17.

2. **Variance approved to use flex line (SN: 26547) from BOP to choke manifold. Check condition of 3" flexible line from BOP to choke manifold, replace if exterior is damaged or if line fails test. Line to be as straight as possible with no hard bends.**

3. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be **3000 (3M) psi. 5M tested as a 3M.**

4. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the 9-5/8 intermediate casing shoe shall be **5000 (5M) psi. 5M system requires an HCR valve, remote kill line and annular to match. The remote kill line is to be installed prior to testing the system and tested to stack pressure.**

5. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.
- a. In a water basin, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. The casing cut-off and BOP installation can be initiated four hours after installing the slips, which will be approximately six hours after bumping the plug. For those casing strings not using slips or where the float does not hold, the minimum wait time before cut-off is eight hours after bumping the plug or when the cement reaches 500 psi compressive strength (including lead when specified), whichever is greater. BOP/BOPE testing can begin after the above conditions are satisfied.
 - b. The tests shall be done by an independent service company utilizing a test plug **not a cup or J-packer**. The operator also has the option of utilizing an independent tester to test without a plug (i.e. against the casing) pursuant to Onshore Order 2 with the pressure not to exceed 70% of the burst rating for the casing. Any test against the casing must meet the WOC time for water basin (18 hours) or potash (24 hours) prior to initiating the test.
 - c. The results of the test shall be reported to the appropriate BLM office.
 - d. All tests are required to be recorded on a calibrated test chart. **A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.**
 - e. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug.

D. DRILL STEM TEST

If drill stem tests are performed, Onshore Order 2.III.D shall be followed.

E. WASTE MATERIAL AND FLUIDS

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area.

DHW 110810

VIII. PRODUCTION (POST DRILLING)

A. WELL STRUCTURES & FACILITIES

Placement of Production Facilities

Production facilities should be placed on the well pad to allow for maximum interim recontouring and revegetation of the well location.

Containment Structures

The containment structure shall be constructed to hold the capacity of the entire contents of the largest tank, plus 24 hour production, unless more stringent protective requirements are deemed necessary by the Authorized Officer.

Painting Requirement

All above-ground structures including meter housing that are not subject to safety requirements shall be painted a flat non-reflective paint color
Shale Green, Munsell Soil Color Chart # 5Y 4/2

B. PIPELINES (not applied for in APD)

C. ELECTRIC LINES (not applied for in APD)

IX. INTERIM RECLAMATION

During the life of the development, all disturbed areas not needed for active support of production operations should undergo interim reclamation in order to minimize the environmental impacts of development on other resources and uses.

Within six (6) months of well completion, operators should work with BLM surface management specialists (Jim Amos: 575-234-5909) to devise the best strategies to reduce the size of the location. Interim reclamation should allow for remedial well operations, as well as safe and efficient removal of oil and gas.

During reclamation, the removal of caliche is important to increasing the success of revegetating the site. Removed caliche that is free of contaminants may be used for road repairs, fire walls or for building other roads and locations. In order to operate the well or complete workover operations, it may be necessary to drive, park and operate on restored interim vegetation within the previously disturbed area. Disturbing revegetated areas for production or workover operations will be allowed. If there is significant disturbance and loss of vegetation, the area will need to be revegetated. Communicate with the appropriate BLM office for any exceptions/exemptions if needed.

All disturbed areas after they have been satisfactorily prepared need to be reseeded with the seed mixture provided below.

Upon completion of interim reclamation, the operator shall submit a Sundry Notices and Reports on Wells, Subsequent Report of Reclamation (Form 3160-5).

X. FINAL ABANDONMENT & RECLAMATION

At final abandonment, well locations, production facilities, and access roads must undergo "final" reclamation so that the character and productivity of the land are restored.

Earthwork for final reclamation must be completed within six (6) months of well plugging. All pads, pits, facility locations and roads must be reclaimed to a satisfactory revegetated, safe, and stable condition, unless an agreement is made with the landowner or BLM to keep the road and/or pad intact.

After all disturbed areas have been satisfactorily prepared, these areas need to be revegetated with the seed mixture provided below. Seeding should be accomplished by drilling on the contour whenever practical or by other approved methods. Seeding may need to be repeated until revegetation is successful, as determined by the BLM.

Operators shall contact a BLM surface protection specialist prior to surface abandonment operations for site specific objectives (Jim Amos: 575-234-5909).

Ground-level Abandoned Well Marker to avoid raptor perching: Upon the plugging and subsequent abandonment of the well, the well marker will be installed at ground level on a plate containing the pertinent information for the plugged well.

Seed Mixture for LPC Sand/Shinnery Sites

The holder shall seed all disturbed areas with the seed mixture listed below. The seed mixture shall be planted in the amounts specified in pounds of pure live seed (PLS)* per acre. There shall be no primary or secondary noxious weeds in the seed mixture. Seed will be tested and the viability testing of seed will be done in accordance with State law(s) and within nine (9) months prior to purchase. Commercial seed will be either certified or registered seed. The seed container will be tagged in accordance with State law(s) and available for inspection by the authorized officer.

Seed will be planted using a drill equipped with a depth regulator to ensure proper depth of planting where drilling is possible. The seed mixture will be evenly and uniformly planted over the disturbed area (smaller/heavier seeds have a tendency to drop the bottom of the drill and are planted first). The holder shall take appropriate measures to ensure this does not occur. Where drilling is not possible, seed will be broadcast and the area shall be raked or chained to cover the seed. When broadcasting the seed, the pounds per acre are to be doubled. The seeding will be repeated until a satisfactory stand is established as determined by the authorized officer. Evaluation of growth will not be made before completion of at least one full growing season after seeding.

Species to be planted in pounds of pure live seed* per acre:

<u>Species</u>	<u>lb/acre</u>
Plains Bristlegrass	5lbs/A
Sand Bluestem	5lbs/A
Little Bluestem	3lbs/A
Big Bluestem	6lbs/A
Plains Coreopsis	2lbs/A
Sand Dropseed	1lbs/A

**Four-winged Saltbush 5lbs/A

* This can be used around well pads and other areas where caliche cannot be removed.

*Pounds of pure live seed:

Pounds of seed x percent purity x percent germination = pounds pure live seed