

9. Abnormal Conditions, Pressures, Temperatures, & Potential Hazards:

No abnormal pressure and/or temperatures are anticipated. Maximum BHP is estimated at 5200 psig. Potential for lost circulation is anticipated in the surface hole and thru the Cisco Reef interval (8000'-9000'). No H<sub>2</sub>S expected during drilling operations. Reports of H<sub>2</sub>S from San Andres during production only. H<sub>2</sub>S operation plan and equipment to be installed as a precaution.

10. Anticipated Starting Date and Duration of Operations:

The anticipated start date will be October 15, 2000. Once commenced, drilling operations should be completed in approximately 45 days. If the well is productive, another 30 days will be required for completion work and facility installation.