

8115-1000
SUBMIT IN TRIPLICATE
ARTS (Other instructions on
reverse side)

FORM APPROVED
OMB NO. 1004-0136
Expires: February 28, 1995

CHK

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

APPLICATION FOR PERMIT TO DRILL OR DEEPEN

1. TYPE OF WORK
 DRILL DEEPEN

2. NAME OF OPERATOR
 Bass Enterprises Production Co. 1801

3. ADDRESS AND TELEPHONE NO.
 P.O. Box 2760, Midland, TX 79702-2760 915-683-2277

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements. *)
 At surface
 2310' FSL & 1815' FEL, SEC 31, T23S, R30E, UNIT LETTER J
 At proposed prod. zone
 SAME POTASH

5. LEASE DESIGNATION AND SERIAL NO.
 NM 02864

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

7. UNIT AGREEMENT NAME
 POKER LAKE UNIT

8. FARM OR LEASE NAME, WELL NO.
 POKER LAKE UNIT #145
 1796

9. API WELL NO.
 30-015-31006

10. FIELD AND POOL, OR WILDCAT
 FORTY-NINER RIDGE (DELAWARE),
 SW UNDES

11. SEC., T., R., M. OR BLK.
 AND SURVEY OR AREA
 SECTION 31, T23S, R30E

12. COUNTY OR PARISH
 EDDY

13. STATE
 NM

14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE*
 14.0 MILES EAST FROM MALAGA, NM

15. DISTANCE FROM PROPOSED*
 LOCATION TO NEAREST
 PROPERTY OR LEASE LINE, FT.
 (Also to nearest drilg. unit line, if any) 330'

16. NO. OF ACRES IN LEASE
 480

17. NO. OF ACRES ASSIGNED
 TO THIS WELL
 40

18. DISTANCE FROM PROPOSED LOCATION*
 TO NEAREST WELL, DRILLING, COMPLETED,
 OR APPLIED FOR, ON THIS LEASE, FT. 1005'

19. PROPOSED DEPTH
 7600'

20. ROTARY OR CABLE TOOLS
 ROTARY

21. ELEVATIONS (Show whether DF, RT, GR, etc.)
 3145' GR CARLSBAD CONTROLLED WATER BASIN

22. APPROX. DATE WORK WILL START*
 UPON APPROVAL

PROPOSED CASING AND CEMENTING PROGRAM

SIZE OF HOLE	GRADE, SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH	QUANTITY OF CEMENT
* 11"	8-5/8" WC-50	24#	460'	165 SX - CIRC TO SURFACE
** 7-7/8"	5-1/2" K-55	15.50#	7600'	785 SX - TOC @ 2964', 500' ABOVE THE TOP OF RAMSEY

THIS WELL IS INSIDE THE SECRETARY'S POTASH AREA AND OUTSIDE THE R-111-P POTASH AREA. THERE IS NO POTASH LEASES WITHIN 1 MILE OF THIS LOCATION.


*SURFACE CASING TO BE SET INTO RUSTLER BELOW ALL FRESH WATER SANDS.

** CEMENT WILL BE PLACED 500' ABOVE THE UPPER MOST HYDROCARBON BEARING ZONE (RAMSEY SAND @ 3464').

BLM ROW APPLICATION FOR ACCESS TO POKER LAKE UNIT WAS SUBMITTED UNDER SEPARATE COVER ON 12/28/99.

APPROVAL SUBJECT TO
GENERAL REQUIREMENTS AND
SPECIAL STIPULATIONS
ATTACHED

THE PROPOSED CEMENTING PROGRAM AS WRITTEN IS CORRECT,
Notify OCD at SPUD & TIME 3/9/2000
to witness cementing the casing
OCD



IN ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposed program is to be drilled in a productive zone and proposed new productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blowout preventer program, if any.

24. SIGNED William R. Dannels TITLE W. R. DANNELS DATE 1-17-00
DIVISION DRILLING SUPT.

(This space for Federal or State office use)

PERMIT NO. _____ APPROVAL DATE _____

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

CONDITIONS OF APPROVAL, IF ANY:

APPROVED BY (ORIG. SGD.) M. J. CHÁVEZ TITLE STATE DIRECTOR DATE 3-6-00

*See Instructions On Reverse Side

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

RECEIVED
JAN 18 2000
BLM
ROSWELL, NM