

Form 3160-3  
(June 2015)UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

## APPLICATION FOR PERMIT TO DRILL OR REENTER

FORM APPROVED  
OMB No. 1004-0137  
Expires: January 31, 2018

1a. Type of work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER		5. Lease Serial No. NMNM0012121
1b. Type of Well: <input checked="" type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Other		6. If Indian, Allottee or Tribe Name
1c. Type of Completion: <input type="checkbox"/> Hydraulic Fracturing <input checked="" type="checkbox"/> Single Zone <input type="checkbox"/> Multiple Zone		7. If Unit or CA Agreement, Name and No. COTTON DRAW / NMNM 070928X
2. Name of Operator DEVON ENERGY PRODUCTION COMPANY LP		8. Lease Name and Well No. COTTON DRAW UNIT 603H
3a. Address 333 West Sheridan Avenue, Oklahoma City, OK 73102	3b. Phone No. (include area code) (800) 583-3866	9. API Well No. 3001547301
4. Location of Well (Report location clearly and in accordance with any State requirements. *) At surface NWNW / 385 FNL / 1190 FWL / LAT 32.1945387 / LONG -103.7532823 At proposed prod. zone SWNW / 2314 FNL / 990 FWL / LAT 32.1747169 / LONG -103.7539395		10. Field and Pool, or Exploratory PURPLE SAGE-WOLFCAMP
14. Distance in miles and direction from nearest town or post office*		11. Sec., T. R. M. or Blk. and Survey or Area SEC 26/T24S/R31E/NMP
15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) 385 feet		12. County or Parish EDDY
16. No of acres in lease 1280		13. State NM
17. Spacing Unit dedicated to this well 480.0		
18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft. 478 feet		20. BLM/BIA Bond No. in file FED: NMB000801
21. Elevations (Show whether DF, KDB, RT, GL, etc.) 3536 feet		22. Approximate date work will start* 03/31/2021
		23. Estimated duration 45 days
24. Attachments		

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, and the Hydraulic Fracturing rule per 43 CFR 3162.3-3 (as applicable)

- |  |   |
|--|---|
| 1. Well plat certified by a registered surveyor.   | 4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above). |
| 2. A Drilling Plan.  | 5. Operator certification.  |
| 3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO must be filed with the appropriate Forest Service Office). | 6. Such other site specific information and/or plans as may be requested by the BLM.            |

25. Signature (Electronic Submission)	Name (Printed/Typed) JENNY HARMS / Ph: (800) 583-3866	Date 04/16/2020
Title Regulatory Compliance Professional		
Approved by (Signature) (Electronic Submission)	Name (Printed/Typed) Cody Layton / Ph: (575) 234-5959	Date 07/15/2020
Title Assistant Field Manager Lands & Minerals Carlsbad Field Office		

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

**APPROVED WITH CONDITIONS**

Approval Date: 07/15/2020

(Continued on page 2)

\*(Instructions on page 2)

Entered - KMS NMOC

District I  
1625 N. French Dr., Hobbs, NM 88240  
Phone: (575) 393-6161 Fax: (575) 393-0720  
District II  
811 S. First St., Artesia, NM 88210  
Phone: (575) 748-1283 Fax: (575) 748-9720  
District III  
1000 Rio Brazos Road, Aztec, NM 87410  
Phone: (505) 334-6178 Fax: (505) 334-6170  
District IV  
1220 S. St. Francis Dr., Santa Fe, NM 87505  
Phone: (505) 476-3460 Fax: (505) 476-3462

State of New Mexico  
Energy, Minerals & Natural Resources Department  
OIL CONSERVATION DIVISION  
1220 South St. Francis Dr.  
Santa Fe, NM 87505

Form C-102  
Revised August 1, 2011  
Submit one copy to appropriate  
District Office  
☐ AMENDED REPORT

WELL LOCATION AND ACREAGE DEDICATION PLAT


<sup>1</sup> API Number <b>3001547301</b>	<sup>2</sup> Pool Code <b>98220</b>	<sup>3</sup> Pool Name <b>Purple Sage Wolfcamp Gas 98220</b>
<sup>4</sup> Property Code <b>300635</b>	<sup>5</sup> Property Name <b>COTTON DRAW UNIT</b>	<sup>6</sup> Well Number <b>603H</b>
<sup>7</sup> OGRID No. <b>6137</b>	<sup>8</sup> Operator Name <b>DEVON ENERGY PRODUCTION COMPANY, L.P.</b>	<sup>9</sup> Elevation <b>3535.9</b>

<sup>10</sup> Surface Location									
UL or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
<b>D</b>	<b>26</b>	<b>24 S</b>	<b>31 E</b>		<b>385</b>	<b>NORTH</b>	<b>1190</b>	<b>WEST</b>	<b>EDDY</b>

<sup>11</sup> Bottom Hole Location If Different From Surface									
UL or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
<b>E</b>	<b>35</b>	<b>24 S</b>	<b>31 E</b>		<b>2314</b>	<b>NORTH</b>	<b>990</b>	<b>WEST</b>	<b>EDDY</b>

<sup>12</sup> Dedicated Acres <b>480</b>	<sup>13</sup> Joint or Infill	<sup>14</sup> Consolidation Code	<sup>15</sup> Order No.
---	-------------------------------	----------------------------------	-------------------------

No allowable will be assigned to this completion until all interests have been consolidated or a non-standard unit has been approved by the division.

		<p><b><sup>17</sup> OPERATOR CERTIFICATION</b></p> <p>I hereby certify that the information contained herein is true and complete to the best of my knowledge and belief, and that this organization either owns a working interest or unleased mineral interest in the land including the proposed bottom hole location or has a right to drill this well at this location pursuant to a contract with an owner of such a mineral or working interest, or to a voluntary pooling agreement or a compulsory pooling order heretofore entered by the division.</p> <p><i>Jenny Harms</i> 4-14-2020 Signature Date</p> <p><b>JENNY HARMS</b> Printed Name</p> <p><b>JENNY.HARMS@DVN.COM</b> E-mail Address</p> <p><b><sup>18</sup> SURVEYOR CERTIFICATION</b></p> <p>I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief.</p> <p>MARCH 3, 2020 Date of Survey</p> <p><i>[Signature]</i> Signature and Seal of Professional Surveyor:</p> <p>Certificate Number: <b>PL 12797</b> SURVEY NO. 79924</p>
---	--	---

Intent ☒ As Drilled ☐

API #		
Operator Name: DEVON ENERGY PRODUCTION COMPANY, L.P.	Property Name: COTTON DRAW UNIT	Well Number 603H

Kick Off Point (KOP)

UL D	Section 26	Township 24S	Range 31E	Lot	Feet 50 FNL	From N/S	Feet 990 FWL	From E/W	County EDDY
Latitude 32.19546300					Longitude -103.75392300				NAD 83

First Take Point (FTP)

UL D	Section 26	Township 24S	Range 31E	Lot	Feet 330	From N/S NORTH	Feet 990	From E/W WEST	County EDDY
Latitude 32.1946898					Longitude 103.7539287				NAD 83

Last Take Point (LTP)

UL E	Section 35	Township 24S	Range 31E	Lot	Feet 2314	From N/S NORTH	Feet 990	From E/W WEST	County EDDY
Latitude 32.1747169					Longitude 103.7539395				NAD 83

Is this well the defining well for the Horizontal Spacing Unit? ☐ NO

Is this well an infill well? ☐ YES

If infill is yes please provide API if available, Operator Name and well number for Defining well for Horizontal Spacing Unit.

API #		
Operator Name:	Property Name:	Well Number

KZ 06/29/2018

District I  
1625 N. French Dr., Hobbs, NM 88240  
District II  
811 S. First St., Artesia, NM 88210  
District III  
1000 Rio Brazos Road, Aztec, NM 87410  
District IV  
1220 S. St. Francis Dr., Santa Fe, NM 87505

State of New Mexico  
Energy, Minerals and Natural Resources Department  
Oil Conservation Division  
1220 South St. Francis Dr.  
Santa Fe, NM 87505

Submit Original  
to Appropriate  
District Office

## GAS CAPTURE PLAN

Date: April 13, 2020

☒ Original

Devon & OGRID No.: Devon Energy Production Co., L.P. 6137

☐ Amended - Reason for Amendment: \_\_\_\_\_

This Gas Capture Plan outlines actions to be taken by the Devon to reduce well/production facility flaring/venting for new completion (new drill, recomple to new zone, re-frac) activity.

*Note: Form C-129 must be submitted and approved prior to exceeding 60 days allowed by Rule (Subsection A of 19.15.18.12 NMAC).*

### Well(s)/Production Facility – Name of facility

The well(s) that will be located at the production facility are shown in the table below.

Well Name	API	Well Location	Footages	Expected MCF/D	Flared or Vented	Comments
COTTON DRAW UNIT 601H		LOT D, 26-24S-31E	385 FNL 1130 FWL			COTTON DRAW 26 CTB 2
COTTON DRAW UNIT 602H		LOT D, 26-24S-31E	385 FNL 1160 FWL			COTTON DRAW 26 CTB 2
COTTON DRAW UNIT 603H		LOT D, 26-24S-31E	385 FNL 1190 FWL			COTTON DRAW 26 CTB 2
COTTON DRAW UNIT 604H		LOT D, 26-24S-31E	385 FNL 1220 FWL			COTTON DRAW 26 CTB 2
COTTON DRAW UNIT 605H		LOT C, 26-24S-31E	385 FNL 2525 FWL			COTTON DRAW 26 CTB 2
COTTON DRAW UNIT 606H		LOT C, 26-24S-31E	385 FNL 2555 FWL			COTTON DRAW 26 CTB 2
COTTON DRAW UNIT 607H		LOT C, 26-24S-31E	385 FNL 2585 FWL			COTTON DRAW 26 CTB 2
COTTON DRAW UNIT 608H		LOT C, 26-24S-31E	385 FNL 2615 FWL			COTTON DRAW 26 CTB 2

### Gathering System and Pipeline Notification

Well(s) will be connected to a production facility after flowback operations are complete, if DCP system is in place. The gas produced from production facility is dedicated to DCP and will be connected to DCP low/high pressure gathering system located in Lea County, New Mexico. It will require 0' of pipeline to connect the facility to low/high pressure gathering system. Devon provides (periodically) to DCP a drilling, completion and estimated first production date for wells that are scheduled to be drilled in the foreseeable future. In addition, Devon and DCP have periodic conference calls to discuss changes to drilling and completion schedules. Gas from these wells will be processed at DCP Processing Plant located in the reference table. The actual flow of the gas will be based on compression operating parameters and gathering system pressures.

### Flowback Strategy

After the fracture treatment/completion operations, well(s) will be produced to temporary production tanks and gas will be flared or vented. During flowback, the fluids and sand content will be monitored. When the produced fluids contain minimal sand, the wells will be turned to production facilities. Gas sales should start as soon as the wells start flowing through the production facilities, unless there are operational issues on DCP system at that time. Based on current information, it is Devon's belief the system can take this gas upon completion of the well(s).

Safety requirements during cleanout operations from the use of underbalanced air cleanout systems may necessitate that sand and non-pipeline quality gas be vented and/or flared rather than sold on a temporary basis.

### Alternatives to Reduce Flaring

Below are alternatives considered from a conceptual standpoint to reduce the amount of gas flared.

- Power Generation – On lease

- Only a portion of gas is consumed operating the generator, remainder of gas will be flared
- Compressed Natural Gas – On lease
  - Gas flared would be minimal, but might be uneconomical to operate when gas volume declines
- NGL Removal – On lease
  - Plants are expensive, residue gas is still flared, and uneconomical to operate when gas volume declines

**Reference Table:**

DCP Plant locations

Artesia Sec. 7, T18S, R28E,

Eunice Sec. 5, T21S, R36E

Linam Sec. 6, T19S, R37E

Zia II Sec. 19, T19S, R32E

1. Geologic Formations

TVD of target	11955	Pilot hole depth	N/A
MD at TD:	19267	Deepest expected fresh water	

Basin

Formation	Depth (TVD) from KB	Water/Mineral Bearing/Target Zone?	Hazards*
Rustler	660		
Salt	1010		
Base of Salt	4400		
Delaware	4550		
Bone Spring 1st	9300		
Bone Spring 2nd	9920		
Bone Spring 3rd	11215		
Wolfcamp	11700		

\*H2S, water flows, loss of circulation, abnormal pressures, etc.

**2. Casing Program (Primary Design)**

Hole Size	Csg. Size	Wt (PPF)	Grade	Conn	Casing Interval		Casing Interval	
					From (MD)	To (MD)	From (TVD)	To (TVD)
17 1/2	13 3/8	48.0	H40	STC	0	685	0	685
9 7/8	8 5/8	32.0	P110	TLW	0	11215	0	11215
7 7/8	5 1/2	17.0	P110	BTC	0	19267	0	11955

• All casing strings will be tested in accordance with Onshore Oil and Gas Order #2 IILB.1.h Must have table for contingency casing.

**3. Cementing Program (Primary Design)**

Casing	# Sks	TOC	Wt. ppg	Yld (ft3/sack)	Slurry Description
Surface	534	Surf	13.2	1.44	Lead: Class C Cement + additives
Int 1	427	Surf	9	3.27	Lead: Class C Cement + additives
	465	4000' above	13.2	1.44	Tail: Class H / C + additives
Int 1 Intermediate Squeeze	As Needed	Surf	13.2	1.44	Squeeze Lead: Class C Cement + additives
	427	Surf	9	3.27	Lead: Class C Cement + additives
	465	4000' above	13.2	1.44	Tail: Class H / C + additives
Production	117	9392	9.0	3.3	Lead: Class H / C + additives
	1042	11392	13.2	1.4	Tail: Class H / C + additives

Casing String	% Excess
Surface	50%
Intermediate 1	30%
Intermediate 1 (Two Stage)	25%
Prod	10%

**4. Pressure Control Equipment (Three String Design)**

BOP installed and tested before drilling which hole?		Size?	Min. Required WP	Type		✓	Tested to:
Int 1		13-5/8"	5M	Annular		X	50% of rated working pressure
				Blind Ram		X	5M
				Pipe Ram			
				Double Ram		X	
				Other*			
Production		13-5/8"	5M	Annular (5M)		X	50% of rated working pressure
				Blind Ram		X	5M
				Pipe Ram			
				Double Ram		X	
				Other*			
				Annular (5M)			
				Blind Ram			
				Pipe Ram			
				Double Ram			
				Other*			
N	A variance is requested for the use of a diverter on the surface casing. See attached for schematic.						
Y	A variance is requested to run a 5 M annular on a 10M system						



**5. Mud Program (Three String Design)**

Section	Type	Weight (ppg)
Surface	FW Gel	8.5-9
Intermediate	DBE / Cut Brine	10-10.5
Production	OBM	10-10.5

Sufficient mud materials to maintain mud properties and meet minimum lost circulation and weight increase requirements will be kept on location at all times.

What will be used to monitor the loss or gain of fluid?	PVT/Pason/Visual Monitoring
---	-----------------------------

**6. Logging and Testing Procedures**

Logging, Coring and Testing	
X	Will run GR/CNL from TD to surface (horizontal well - vertical portion of hole). Stated logs run will be in the Completion Report and submitted to the BLM.
	No logs are planned based on well control or offset log information.
	Drill stem test? If yes, explain.
	Coring? If yes, explain.

Additional logs planned		Interval
	Resistivity	Int. shoe to KOP
	Density	Int. shoe to KOP
X	CBL	Production casing
X	Mud log	Intermediate shoe to TD
	PEX	

**7. Drilling Conditions**

Condition	Specify what type and where?
BH pressure at deepest TVD	6527
Abnormal temperature	No

Mitigation measure for abnormal conditions. Describe. Lost circulation material/sweeps/mud scavengers.

Hydrogen Sulfide (H<sub>2</sub>S) monitors will be installed prior to drilling out the surface shoe. If H<sub>2</sub>S is detected in concentrations greater than 100 ppm, the operator will comply with the provisions of Onshore Oil and Gas Order #6. If Hydrogen Sulfide is encountered measured values and formations will be provided to the BLM.

N	H <sub>2</sub> S is present
Y	H <sub>2</sub> S plan attached.

**8. Other facets of operation**

Is this a walking operation? Potentially

- 1 If operator elects, drilling rig will batch drill the surface holes and run/cement surface casing; walking the rig to next wells on the pad.
- 2 The drilling rig will then batch drill the intermediate sections and run/cement intermediate casing; the wellbore will be isolated with a blind flange and pressure gauge installed for monitoring the well before walking to the next well.
- 3 The drilling rig will then batch drill the production hole sections on the wells with OBM, run/cement production casing, and install TA caps or tubing heads for completions.

NOTE: During batch operations the drilling rig will be moved from well to well however, it will not be removed

## Cotton Draw Unit 603H

from the pad until all wells have production casing run/cemented.

Will be pre-setting casing? Potentially

- 1 Spudder rig will move in and batch drill surface hole.
  - a. Rig will utilize fresh water based mud to drill surface hole to TD. Solids control will be handled entirely on a closed loop basis.,
- 2 After drilling the surface hole section, the spudder rig will run casing and cement following all of the applicable rules and regulations (OnShore Order 2, all COAs and NMOCD regulations).
- 3 The wellhead will be installed and tested once the surface casing is cut off and the WOC time has been reached.
- 4 A blind flange with the same pressure rating as the wellhead will be installed to seal the wellbore. Pressure will be monitored with a pressure gauge installed on the wellhead.
- 5 Spudder rig operations is expected to take 4-5 days per well on a multi-well pa.
- 6 The NMOCD will be contacted and notified 24 hours prior to commencing spudder rig operations.
- 7 Drilling operations will be performed with drilling rig. A that time an approved BOP stack will be nipped up and tested on the wellhead before drilling operations commences on each well.
  - a. The NMOCD will be contacted / notified 24 hours before the drilling rig moves back on to the pad with the pre-set surface casing.

Attachments

X Directional Plan  
           Other, describe

# **WCDSC Permian NM**

**Eddy County (NAD 83 NM Eastern)**

**Sec 26-T24S-R31E**

**Cotton Draw Unit 603H**

**Wellbore #1**

**Plan: Permit Plan 1**

## **Standard Planning Report - Geographic**

**25 March, 2020**

# Planning Report - Geographic

<b>Database:</b>	EDM r5000.141_Prod US	<b>Local Co-ordinate Reference:</b>	Well Cotton Draw Unit 603H
<b>Company:</b>	WCDSC Permian NM	<b>TVD Reference:</b>	RKB @ 3560.90ft (Original Well Elev)
<b>Project:</b>	Eddy County (NAD 83 NM Eastern)	<b>MD Reference:</b>	RKB @ 3560.90ft (Original Well Elev)
<b>Site:</b>	Sec 26-T24S-R31E	<b>North Reference:</b>	Grid
<b>Well:</b>	Cotton Draw Unit 603H	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Wellbore:</b>	Wellbore #1		
<b>Design:</b>	Permit Plan 1		

<b>Project</b>	Eddy County (NAD 83 NM Eastern)		
<b>Map System:</b>	US State Plane 1983	<b>System Datum:</b>	Mean Sea Level
<b>Geo Datum:</b>	North American Datum 1983		
<b>Map Zone:</b>	New Mexico Eastern Zone		

Site		Sec 26-T24S-R31E			
Site Position:		Northing:	435,369.69 usft	Latitude:	32.195596
From:	Map	Easting:	719,574.99 usft	Longitude:	-103.757129
Position Uncertainty:	5.00 ft	Slot Radius:	13-3/16 "	Grid Convergence:	0.31 °

Well	Cotton Draw Unit 603H					
Well Position	+N/-S	0.00 ft	Northing:	434,991.51 usft	Latitude:	32.194539
	+E/-W	0.00 ft	Easting:	720,767.06 usft	Longitude:	-103.753283
Position Uncertainty		0.50 ft	Wellhead Elevation:		Ground Level:	3,535.90 ft

<b>Wellbore</b>	Wellbore #1				
<b>Magnetics</b>	<b>Model Name</b>	<b>Sample Date</b>	<b>Declination (°)</b>	<b>Dip Angle (°)</b>	<b>Field Strength (nT)</b>
	IGRF2015	3/23/2020	6.74	59.97	47,616.63942772

<b>Design</b>	Permit Plan 1			
<b>Audit Notes:</b>				
<b>Version:</b>	<b>Phase:</b>	PROTOTYPE	<b>Tie On Depth:</b>	0.00
<b>Vertical Section:</b>	<b>Depth From (TVD) (ft)</b>	<b>+N/-S (ft)</b>	<b>+E/-W (ft)</b>	<b>Direction (°)</b>
	0.00	0.00	0.00	181.31

<b>Plan Survey Tool Program</b>	<b>Date</b>	3/25/2020		
<b>Depth From (ft)</b>	<b>Depth To (ft)</b>	<b>Survey (Wellbore)</b>	<b>Tool Name</b>	<b>Remarks</b>
1	0.00	19,266.51 Permit Plan 1 (Wellbore #1)	MWD+HDGM OWSG MWD + HDGM	

<b>Plan Sections</b>										
<b>Measured Depth (ft)</b>	<b>Inclination (°)</b>	<b>Azimuth (°)</b>	<b>Vertical Depth (ft)</b>	<b>+N/-S (ft)</b>	<b>+E/-W (ft)</b>	<b>Dogleg Rate (°/100usft)</b>	<b>Build Rate (°/100usft)</b>	<b>Turn Rate (°/100usft)</b>	<b>TFO (°)</b>	<b>Target</b>
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
3,500.00	0.00	0.00	3,500.00	0.00	0.00	0.00	0.00	0.00	0.00	
3,806.94	3.07	329.16	3,806.79	7.06	-4.21	1.00	1.00	0.00	329.16	
10,837.71	3.07	329.16	10,827.47	330.30	-197.19	0.00	0.00	0.00	0.00	
11,042.33	0.00	0.00	11,032.00	335.00	-200.00	1.50	-1.50	0.00	180.00	
11,392.37	0.00	0.00	11,382.04	335.00	-200.00	0.00	0.00	0.00	0.00	
12,292.37	90.00	179.73	11,955.00	-237.95	-197.30	10.00	10.00	0.00	179.73	PBHL - Cotton Draw Unit 603H
19,266.51	90.00	179.73	11,955.00	-7,212.01	-164.48	0.00	0.00	0.00	0.00	PBHL - Cotton Draw Unit 603H

# Planning Report - Geographic

<b>Database:</b>	EDM r5000.141_Prod US	<b>Local Co-ordinate Reference:</b>	Well Cotton Draw Unit 603H
<b>Company:</b>	WCDSC Permian NM	<b>TVD Reference:</b>	RKB @ 3560.90ft (Original Well Elev)
<b>Project:</b>	Eddy County (NAD 83 NM Eastern)	<b>MD Reference:</b>	RKB @ 3560.90ft (Original Well Elev)
<b>Site:</b>	Sec 26-T24S-R31E	<b>North Reference:</b>	Grid
<b>Well:</b>	Cotton Draw Unit 603H	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Wellbore:</b>	Wellbore #1		
<b>Design:</b>	Permit Plan 1		

Planned Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Map Northing (usft)	Map Easting (usft)	Latitude	Longitude
0.00	0.00	0.00	0.00	0.00	0.00	434,991.51	720,767.06	32.194539	-103.753283
100.00	0.00	0.00	100.00	0.00	0.00	434,991.51	720,767.06	32.194539	-103.753283
200.00	0.00	0.00	200.00	0.00	0.00	434,991.51	720,767.06	32.194539	-103.753283
300.00	0.00	0.00	300.00	0.00	0.00	434,991.51	720,767.06	32.194539	-103.753283
400.00	0.00	0.00	400.00	0.00	0.00	434,991.51	720,767.06	32.194539	-103.753283
500.00	0.00	0.00	500.00	0.00	0.00	434,991.51	720,767.06	32.194539	-103.753283
600.00	0.00	0.00	600.00	0.00	0.00	434,991.51	720,767.06	32.194539	-103.753283
700.00	0.00	0.00	700.00	0.00	0.00	434,991.51	720,767.06	32.194539	-103.753283
800.00	0.00	0.00	800.00	0.00	0.00	434,991.51	720,767.06	32.194539	-103.753283
900.00	0.00	0.00	900.00	0.00	0.00	434,991.51	720,767.06	32.194539	-103.753283
1,000.00	0.00	0.00	1,000.00	0.00	0.00	434,991.51	720,767.06	32.194539	-103.753283
1,100.00	0.00	0.00	1,100.00	0.00	0.00	434,991.51	720,767.06	32.194539	-103.753283
1,200.00	0.00	0.00	1,200.00	0.00	0.00	434,991.51	720,767.06	32.194539	-103.753283
1,300.00	0.00	0.00	1,300.00	0.00	0.00	434,991.51	720,767.06	32.194539	-103.753283
1,400.00	0.00	0.00	1,400.00	0.00	0.00	434,991.51	720,767.06	32.194539	-103.753283
1,500.00	0.00	0.00	1,500.00	0.00	0.00	434,991.51	720,767.06	32.194539	-103.753283
1,600.00	0.00	0.00	1,600.00	0.00	0.00	434,991.51	720,767.06	32.194539	-103.753283
1,700.00	0.00	0.00	1,700.00	0.00	0.00	434,991.51	720,767.06	32.194539	-103.753283
1,800.00	0.00	0.00	1,800.00	0.00	0.00	434,991.51	720,767.06	32.194539	-103.753283
1,900.00	0.00	0.00	1,900.00	0.00	0.00	434,991.51	720,767.06	32.194539	-103.753283
2,000.00	0.00	0.00	2,000.00	0.00	0.00	434,991.51	720,767.06	32.194539	-103.753283
2,100.00	0.00	0.00	2,100.00	0.00	0.00	434,991.51	720,767.06	32.194539	-103.753283
2,200.00	0.00	0.00	2,200.00	0.00	0.00	434,991.51	720,767.06	32.194539	-103.753283
2,300.00	0.00	0.00	2,300.00	0.00	0.00	434,991.51	720,767.06	32.194539	-103.753283
2,400.00	0.00	0.00	2,400.00	0.00	0.00	434,991.51	720,767.06	32.194539	-103.753283
2,500.00	0.00	0.00	2,500.00	0.00	0.00	434,991.51	720,767.06	32.194539	-103.753283
2,600.00	0.00	0.00	2,600.00	0.00	0.00	434,991.51	720,767.06	32.194539	-103.753283
2,700.00	0.00	0.00	2,700.00	0.00	0.00	434,991.51	720,767.06	32.194539	-103.753283
2,800.00	0.00	0.00	2,800.00	0.00	0.00	434,991.51	720,767.06	32.194539	-103.753283
2,900.00	0.00	0.00	2,900.00	0.00	0.00	434,991.51	720,767.06	32.194539	-103.753283
3,000.00	0.00	0.00	3,000.00	0.00	0.00	434,991.51	720,767.06	32.194539	-103.753283
3,100.00	0.00	0.00	3,100.00	0.00	0.00	434,991.51	720,767.06	32.194539	-103.753283
3,200.00	0.00	0.00	3,200.00	0.00	0.00	434,991.51	720,767.06	32.194539	-103.753283
3,300.00	0.00	0.00	3,300.00	0.00	0.00	434,991.51	720,767.06	32.194539	-103.753283
3,400.00	0.00	0.00	3,400.00	0.00	0.00	434,991.51	720,767.06	32.194539	-103.753283
3,500.00	0.00	0.00	3,500.00	0.00	0.00	434,991.51	720,767.06	32.194539	-103.753283
3,600.00	1.00	329.16	3,600.00	0.75	-0.45	434,992.26	720,766.61	32.194541	-103.753284
3,700.00	2.00	329.16	3,699.96	3.00	-1.79	434,994.51	720,765.27	32.194547	-103.753288
3,800.00	3.00	329.16	3,799.86	6.74	-4.03	434,998.25	720,763.03	32.194557	-103.753295
3,806.94	3.07	329.16	3,806.79	7.06	-4.21	434,998.57	720,762.84	32.194558	-103.753296
3,900.00	3.07	329.16	3,899.72	11.34	-6.77	435,002.85	720,760.29	32.194570	-103.753304
4,000.00	3.07	329.16	3,999.58	15.93	-9.51	435,007.44	720,757.54	32.194583	-103.753313
4,100.00	3.07	329.16	4,099.43	20.53	-12.26	435,012.04	720,754.80	32.194595	-103.753322
4,200.00	3.07	329.16	4,199.29	25.13	-15.00	435,016.64	720,752.05	32.194608	-103.753331
4,300.00	3.07	329.16	4,299.15	29.73	-17.75	435,021.24	720,749.31	32.194621	-103.753339
4,400.00	3.07	329.16	4,399.00	34.32	-20.49	435,025.83	720,746.56	32.194633	-103.753348
4,500.00	3.07	329.16	4,498.86	38.92	-23.24	435,030.43	720,743.82	32.194646	-103.753357
4,600.00	3.07	329.16	4,598.72	43.52	-25.98	435,035.03	720,741.08	32.194659	-103.753366
4,700.00	3.07	329.16	4,698.57	48.12	-28.73	435,039.63	720,738.33	32.194671	-103.753375
4,800.00	3.07	329.16	4,798.43	52.71	-31.47	435,044.22	720,735.59	32.194684	-103.753383
4,900.00	3.07	329.16	4,898.29	57.31	-34.22	435,048.82	720,732.84	32.194697	-103.753392
5,000.00	3.07	329.16	4,998.14	61.91	-36.96	435,053.42	720,730.10	32.194710	-103.753401
5,100.00	3.07	329.16	5,098.00	66.51	-39.70	435,058.02	720,727.35	32.194722	-103.753410
5,200.00	3.07	329.16	5,197.85	71.10	-42.45	435,062.61	720,724.61	32.194735	-103.753419
5,300.00	3.07	329.16	5,297.71	75.70	-45.19	435,067.21	720,721.86	32.194748	-103.753427

# Planning Report - Geographic

<b>Database:</b>	EDM r5000.141_Prod US	<b>Local Co-ordinate Reference:</b>	Well Cotton Draw Unit 603H
<b>Company:</b>	WCDC Permian NM	<b>TVD Reference:</b>	RKB @ 3560.90ft (Original Well Elev)
<b>Project:</b>	Eddy County (NAD 83 NM Eastern)	<b>MD Reference:</b>	RKB @ 3560.90ft (Original Well Elev)
<b>Site:</b>	Sec 26-T24S-R31E	<b>North Reference:</b>	Grid
<b>Well:</b>	Cotton Draw Unit 603H	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Wellbore:</b>	Wellbore #1		
<b>Design:</b>	Permit Plan 1		

Planned Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Map Northing (usft)	Map Easting (usft)	Latitude	Longitude
5,400.00	3.07	329.16	5,397.57	80.30	-47.94	435,071.81	720,719.12	32.194760	-103.753436
5,500.00	3.07	329.16	5,497.42	84.90	-50.68	435,076.41	720,716.37	32.194773	-103.753445
5,600.00	3.07	329.16	5,597.28	89.49	-53.43	435,081.00	720,713.63	32.194786	-103.753454
5,700.00	3.07	329.16	5,697.14	94.09	-56.17	435,085.60	720,710.88	32.194798	-103.753462
5,800.00	3.07	329.16	5,796.99	98.69	-58.92	435,090.20	720,708.14	32.194811	-103.753471
5,900.00	3.07	329.16	5,896.85	103.29	-61.66	435,094.79	720,705.39	32.194824	-103.753480
6,000.00	3.07	329.16	5,996.71	107.88	-64.41	435,099.39	720,702.65	32.194836	-103.753489
6,100.00	3.07	329.16	6,096.56	112.48	-67.15	435,103.99	720,699.90	32.194849	-103.753498
6,200.00	3.07	329.16	6,196.42	117.08	-69.90	435,108.59	720,697.16	32.194862	-103.753506
6,300.00	3.07	329.16	6,296.28	121.68	-72.64	435,113.18	720,694.41	32.194874	-103.753515
6,400.00	3.07	329.16	6,396.13	126.27	-75.39	435,117.78	720,691.67	32.194887	-103.753524
6,500.00	3.07	329.16	6,495.99	130.87	-78.13	435,122.38	720,688.92	32.194900	-103.753533
6,600.00	3.07	329.16	6,595.85	135.47	-80.88	435,126.98	720,686.18	32.194912	-103.753542
6,700.00	3.07	329.16	6,695.70	140.07	-83.62	435,131.57	720,683.44	32.194925	-103.753550
6,800.00	3.07	329.16	6,795.56	144.66	-86.37	435,136.17	720,680.69	32.194938	-103.753559
6,900.00	3.07	329.16	6,895.42	149.26	-89.11	435,140.77	720,677.95	32.194950	-103.753568
7,000.00	3.07	329.16	6,995.27	153.86	-91.86	435,145.37	720,675.20	32.194963	-103.753577
7,100.00	3.07	329.16	7,095.13	158.46	-94.60	435,149.96	720,672.46	32.194976	-103.753586
7,200.00	3.07	329.16	7,194.99	163.05	-97.34	435,154.56	720,669.71	32.194988	-103.753594
7,300.00	3.07	329.16	7,294.84	167.65	-100.09	435,159.16	720,666.97	32.195001	-103.753603
7,400.00	3.07	329.16	7,394.70	172.25	-102.83	435,163.76	720,664.22	32.195014	-103.753612
7,500.00	3.07	329.16	7,494.56	176.84	-105.58	435,168.35	720,661.48	32.195026	-103.753621
7,600.00	3.07	329.16	7,594.41	181.44	-108.32	435,172.95	720,658.73	32.195039	-103.753630
7,700.00	3.07	329.16	7,694.27	186.04	-111.07	435,177.55	720,655.99	32.195052	-103.753638
7,800.00	3.07	329.16	7,794.13	190.64	-113.81	435,182.15	720,653.24	32.195064	-103.753647
7,900.00	3.07	329.16	7,893.98	195.23	-116.56	435,186.74	720,650.50	32.195077	-103.753656
8,000.00	3.07	329.16	7,993.84	199.83	-119.30	435,191.34	720,647.75	32.195090	-103.753665
8,100.00	3.07	329.16	8,093.69	204.43	-122.05	435,195.94	720,645.01	32.195103	-103.753673
8,200.00	3.07	329.16	8,193.55	209.03	-124.79	435,200.54	720,642.26	32.195115	-103.753682
8,300.00	3.07	329.16	8,293.41	213.62	-127.54	435,205.13	720,639.52	32.195128	-103.753691
8,400.00	3.07	329.16	8,393.26	218.22	-130.28	435,209.73	720,636.77	32.195141	-103.753700
8,500.00	3.07	329.16	8,493.12	222.82	-133.03	435,214.33	720,634.03	32.195153	-103.753709
8,600.00	3.07	329.16	8,592.98	227.42	-135.77	435,218.93	720,631.28	32.195166	-103.753717
8,700.00	3.07	329.16	8,692.83	232.01	-138.52	435,223.52	720,628.54	32.195179	-103.753726
8,800.00	3.07	329.16	8,792.69	236.61	-141.26	435,228.12	720,625.80	32.195191	-103.753735
8,900.00	3.07	329.16	8,892.55	241.21	-144.01	435,232.72	720,623.05	32.195204	-103.753744
9,000.00	3.07	329.16	8,992.40	245.81	-146.75	435,237.32	720,620.31	32.195217	-103.753753
9,100.00	3.07	329.16	9,092.26	250.40	-149.50	435,241.91	720,617.56	32.195229	-103.753761
9,200.00	3.07	329.16	9,192.12	255.00	-152.24	435,246.51	720,614.82	32.195242	-103.753770
9,300.00	3.07	329.16	9,291.97	259.60	-154.98	435,251.11	720,612.07	32.195255	-103.753779
9,400.00	3.07	329.16	9,391.83	264.20	-157.73	435,255.71	720,609.33	32.195267	-103.753788
9,500.00	3.07	329.16	9,491.69	268.79	-160.47	435,260.30	720,606.58	32.195280	-103.753797
9,600.00	3.07	329.16	9,591.54	273.39	-163.22	435,264.90	720,603.84	32.195293	-103.753805
9,700.00	3.07	329.16	9,691.40	277.99	-165.96	435,269.50	720,601.09	32.195305	-103.753814
9,800.00	3.07	329.16	9,791.26	282.59	-168.71	435,274.10	720,598.35	32.195318	-103.753823
9,900.00	3.07	329.16	9,891.11	287.18	-171.45	435,278.69	720,595.60	32.195331	-103.753832
10,000.00	3.07	329.16	9,990.97	291.78	-174.20	435,283.29	720,592.86	32.195343	-103.753841
10,100.00	3.07	329.16	10,090.83	296.38	-176.94	435,287.89	720,590.11	32.195356	-103.753849
10,200.00	3.07	329.16	10,190.68	300.98	-179.69	435,292.49	720,587.37	32.195369	-103.753858
10,300.00	3.07	329.16	10,290.54	305.57	-182.43	435,297.08	720,584.62	32.195381	-103.753867
10,400.00	3.07	329.16	10,390.40	310.17	-185.18	435,301.68	720,581.88	32.195394	-103.753876
10,500.00	3.07	329.16	10,490.25	314.77	-187.92	435,306.28	720,579.13	32.195407	-103.753885
10,600.00	3.07	329.16	10,590.11	319.37	-190.67	435,310.88	720,576.39	32.195419	-103.753893
10,700.00	3.07	329.16	10,689.96	323.96	-193.41	435,315.47	720,573.65	32.195432	-103.753902
10,800.00	3.07	329.16	10,789.82	328.56	-196.16	435,320.07	720,570.90	32.195445	-103.753911

# Planning Report - Geographic

<b>Database:</b>	EDM r5000.141_Prod US	<b>Local Co-ordinate Reference:</b>	Well Cotton Draw Unit 603H
<b>Company:</b>	WCDCS Permian NM	<b>TVD Reference:</b>	RKB @ 3560.90ft (Original Well Elev)
<b>Project:</b>	Eddy County (NAD 83 NM Eastern)	<b>MD Reference:</b>	RKB @ 3560.90ft (Original Well Elev)
<b>Site:</b>	Sec 26-T24S-R31E	<b>North Reference:</b>	Grid
<b>Well:</b>	Cotton Draw Unit 603H	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Wellbore:</b>	Wellbore #1		
<b>Design:</b>	Permit Plan 1		

Planned Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Map Northing (usft)	Map Easting (usft)	Latitude	Longitude
10,837.71	3.07	329.16	10,827.47	330.30	-197.19	435,321.80	720,569.87	32.195450	-103.753914
10,900.00	2.13	329.16	10,889.70	332.72	-198.64	435,324.23	720,568.42	32.195456	-103.753919
11,000.00	0.63	329.16	10,989.67	334.80	-199.88	435,326.31	720,567.18	32.195462	-103.753923
11,042.33	0.00	0.00	11,032.00	335.00	-200.00	435,326.51	720,567.06	32.195463	-103.753923
11,100.00	0.00	0.00	11,089.67	335.00	-200.00	435,326.51	720,567.06	32.195463	-103.753923
11,200.00	0.00	0.00	11,189.67	335.00	-200.00	435,326.51	720,567.06	32.195463	-103.753923
11,300.00	0.00	0.00	11,289.67	335.00	-200.00	435,326.51	720,567.06	32.195463	-103.753923
11,392.37	0.00	0.00	11,382.04	335.00	-200.00	435,326.51	720,567.06	32.195463	-103.753923
KOP @ 11392' MD, 50' FNL, 990' FWL									
11,400.00	0.76	179.73	11,389.67	334.95	-200.00	435,326.46	720,567.06	32.195462	-103.753923
11,500.00	10.76	179.73	11,489.04	324.92	-199.95	435,316.43	720,567.10	32.195435	-103.753923
11,600.00	20.76	179.73	11,585.16	297.79	-199.82	435,289.30	720,567.23	32.195360	-103.753923
11,700.00	30.76	179.73	11,675.10	254.38	-199.62	435,245.89	720,567.44	32.195241	-103.753923
11,800.00	40.76	179.73	11,756.14	196.01	-199.35	435,187.52	720,567.71	32.195081	-103.753924
11,900.00	50.76	179.73	11,825.82	124.46	-199.01	435,115.97	720,568.05	32.194884	-103.753924
11,985.00	59.26	179.73	11,874.51	54.88	-198.68	435,046.39	720,568.37	32.194693	-103.753924
FTP @ 11985' MD, 330' FNL, 990' FWL									
12,000.00	60.76	179.73	11,882.01	41.89	-198.62	435,033.40	720,568.44	32.194657	-103.753924
12,100.00	70.76	179.73	11,923.01	-49.18	-198.19	434,942.33	720,568.86	32.194407	-103.753924
12,200.00	80.76	179.73	11,947.57	-145.98	-197.74	434,845.53	720,569.32	32.194140	-103.753924
12,292.37	90.00	179.73	11,955.00	-237.95	-197.30	434,753.56	720,569.75	32.193888	-103.753924
12,300.00	90.00	179.73	11,955.00	-245.58	-197.27	434,745.93	720,569.79	32.193867	-103.753924
12,400.00	90.00	179.73	11,955.00	-345.58	-196.80	434,645.93	720,570.26	32.193592	-103.753925
12,500.00	90.00	179.73	11,955.00	-445.58	-196.33	434,545.93	720,570.73	32.193317	-103.753925
12,600.00	90.00	179.73	11,955.00	-545.58	-195.86	434,445.93	720,571.20	32.193042	-103.753925
12,700.00	90.00	179.73	11,955.00	-645.58	-195.38	434,345.94	720,571.67	32.192767	-103.753925
12,800.00	90.00	179.73	11,955.00	-745.57	-194.91	434,245.94	720,572.14	32.192492	-103.753926
12,900.00	90.00	179.73	11,955.00	-845.57	-194.44	434,145.94	720,572.61	32.192217	-103.753926
13,000.00	90.00	179.73	11,955.00	-945.57	-193.97	434,045.94	720,573.08	32.191942	-103.753926
13,100.00	90.00	179.73	11,955.00	-1,045.57	-193.50	433,945.94	720,573.55	32.191668	-103.753926
13,200.00	90.00	179.73	11,955.00	-1,145.57	-193.03	433,845.94	720,574.02	32.191393	-103.753926
13,300.00	90.00	179.73	11,955.00	-1,245.57	-192.56	433,745.94	720,574.50	32.191118	-103.753927
13,400.00	90.00	179.73	11,955.00	-1,345.57	-192.09	433,645.94	720,574.97	32.190843	-103.753927
13,500.00	90.00	179.73	11,955.00	-1,445.57	-191.62	433,545.95	720,575.44	32.190568	-103.753927
13,600.00	90.00	179.73	11,955.00	-1,545.57	-191.15	433,445.95	720,575.91	32.190293	-103.753927
13,700.00	90.00	179.73	11,955.00	-1,645.56	-190.68	433,345.95	720,576.38	32.190018	-103.753928
13,800.00	90.00	179.73	11,955.00	-1,745.56	-190.21	433,245.95	720,576.85	32.189743	-103.753928
13,900.00	90.00	179.73	11,955.00	-1,845.56	-189.74	433,145.95	720,577.32	32.189469	-103.753928
14,000.00	90.00	179.73	11,955.00	-1,945.56	-189.27	433,045.95	720,577.79	32.189194	-103.753928
14,100.00	90.00	179.73	11,955.00	-2,045.56	-188.80	432,945.95	720,578.26	32.188919	-103.753928
14,200.00	90.00	179.73	11,955.00	-2,145.56	-188.33	432,845.95	720,578.73	32.188644	-103.753929
14,300.00	90.00	179.73	11,955.00	-2,245.56	-187.85	432,745.96	720,579.20	32.188369	-103.753929
14,400.00	90.00	179.73	11,955.00	-2,345.56	-187.38	432,645.96	720,579.67	32.188094	-103.753929
14,500.00	90.00	179.73	11,955.00	-2,445.56	-186.91	432,545.96	720,580.14	32.187819	-103.753929
14,600.00	90.00	179.73	11,955.00	-2,545.55	-186.44	432,445.96	720,580.61	32.187544	-103.753930
14,700.00	90.00	179.73	11,955.00	-2,645.55	-185.97	432,345.96	720,581.08	32.187270	-103.753930
14,800.00	90.00	179.73	11,955.00	-2,745.55	-185.50	432,245.96	720,581.55	32.186995	-103.753930
14,900.00	90.00	179.73	11,955.00	-2,845.55	-185.03	432,145.96	720,582.03	32.186720	-103.753930
15,000.00	90.00	179.73	11,955.00	-2,945.55	-184.56	432,045.97	720,582.50	32.186445	-103.753930
15,100.00	90.00	179.73	11,955.00	-3,045.55	-184.09	431,945.97	720,582.97	32.186170	-103.753931
15,200.00	90.00	179.73	11,955.00	-3,145.55	-183.62	431,845.97	720,583.44	32.185895	-103.753931
15,300.00	90.00	179.73	11,955.00	-3,245.55	-183.15	431,745.97	720,583.91	32.185620	-103.753931
15,400.00	90.00	179.73	11,955.00	-3,345.55	-182.68	431,645.97	720,584.38	32.185345	-103.753931
15,500.00	90.00	179.73	11,955.00	-3,445.54	-182.21	431,545.97	720,584.85	32.185070	-103.753932

# Planning Report - Geographic

<b>Database:</b>	EDM r5000.141_Prod US	<b>Local Co-ordinate Reference:</b>	Well Cotton Draw Unit 603H
<b>Company:</b>	WCDSC Permian NM	<b>TVD Reference:</b>	RKB @ 3560.90ft (Original Well Elev)
<b>Project:</b>	Eddy County (NAD 83 NM Eastern)	<b>MD Reference:</b>	RKB @ 3560.90ft (Original Well Elev)
<b>Site:</b>	Sec 26-T24S-R31E	<b>North Reference:</b>	Grid
<b>Well:</b>	Cotton Draw Unit 603H	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Wellbore:</b>	Wellbore #1		
<b>Design:</b>	Permit Plan 1		

Planned Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Map Northing (usft)	Map Easting (usft)	Latitude	Longitude
15,600.00	90.00	179.73	11,955.00	-3,545.54	-181.74	431,445.97	720,585.32	32.184796	-103.753932
15,700.00	90.00	179.73	11,955.00	-3,645.54	-181.27	431,345.97	720,585.79	32.184521	-103.753932
15,800.00	90.00	179.73	11,955.00	-3,745.54	-180.80	431,245.98	720,586.26	32.184246	-103.753932
15,900.00	90.00	179.73	11,955.00	-3,845.54	-180.32	431,145.98	720,586.73	32.183971	-103.753932
16,000.00	90.00	179.73	11,955.00	-3,945.54	-179.85	431,045.98	720,587.20	32.183696	-103.753933
16,100.00	90.00	179.73	11,955.00	-4,045.54	-179.38	430,945.98	720,587.67	32.183421	-103.753933
16,200.00	90.00	179.73	11,955.00	-4,145.54	-178.91	430,845.98	720,588.14	32.183146	-103.753933
16,300.00	90.00	179.73	11,955.00	-4,245.54	-178.44	430,745.98	720,588.61	32.182871	-103.753933
16,400.00	90.00	179.73	11,955.00	-4,345.53	-177.97	430,645.98	720,589.09	32.182597	-103.753934
16,500.00	90.00	179.73	11,955.00	-4,445.53	-177.50	430,545.98	720,589.56	32.182322	-103.753934
16,600.00	90.00	179.73	11,955.00	-4,545.53	-177.03	430,445.99	720,590.03	32.182047	-103.753934
16,700.00	90.00	179.73	11,955.00	-4,645.53	-176.56	430,345.99	720,590.50	32.181772	-103.753934
16,800.00	90.00	179.73	11,955.00	-4,745.53	-176.09	430,245.99	720,590.97	32.181497	-103.753934
16,900.00	90.00	179.73	11,955.00	-4,845.53	-175.62	430,145.99	720,591.44	32.181222	-103.753935
16,954.00	90.00	179.73	11,955.00	-4,899.53	-175.36	430,091.99	720,591.69	32.181074	-103.753935
Cross section @ 16954' MD, 0' FNL, 990' FWL									
17,000.00	90.00	179.73	11,955.00	-4,945.53	-175.15	430,045.99	720,591.91	32.180947	-103.753935
17,100.00	90.00	179.73	11,955.00	-5,045.53	-174.68	429,945.99	720,592.38	32.180672	-103.753935
17,200.00	90.00	179.73	11,955.00	-5,145.53	-174.21	429,845.99	720,592.85	32.180397	-103.753935
17,300.00	90.00	179.73	11,955.00	-5,245.52	-173.74	429,746.00	720,593.32	32.180123	-103.753935
17,400.00	90.00	179.73	11,955.00	-5,345.52	-173.26	429,646.00	720,593.79	32.179848	-103.753936
17,500.00	90.00	179.73	11,955.00	-5,445.52	-172.79	429,546.00	720,594.26	32.179573	-103.753936
17,600.00	90.00	179.73	11,955.00	-5,545.52	-172.32	429,446.00	720,594.73	32.179298	-103.753936
17,700.00	90.00	179.73	11,955.00	-5,645.52	-171.85	429,346.00	720,595.20	32.179023	-103.753936
17,800.00	90.00	179.73	11,955.00	-5,745.52	-171.38	429,246.00	720,595.67	32.178748	-103.753937
17,900.00	90.00	179.73	11,955.00	-5,845.52	-170.91	429,146.00	720,596.14	32.178473	-103.753937
18,000.00	90.00	179.73	11,955.00	-5,945.52	-170.44	429,046.00	720,596.62	32.178198	-103.753937
18,100.00	90.00	179.73	11,955.00	-6,045.52	-169.97	428,946.01	720,597.09	32.177924	-103.753937
18,200.00	90.00	179.73	11,955.00	-6,145.51	-169.50	428,846.01	720,597.56	32.177649	-103.753937
18,300.00	90.00	179.73	11,955.00	-6,245.51	-169.03	428,746.01	720,598.03	32.177374	-103.753938
18,400.00	90.00	179.73	11,955.00	-6,345.51	-168.56	428,646.01	720,598.50	32.177099	-103.753938
18,500.00	90.00	179.73	11,955.00	-6,445.51	-168.09	428,546.01	720,598.97	32.176824	-103.753938
18,600.00	90.00	179.73	11,955.00	-6,545.51	-167.62	428,446.01	720,599.44	32.176549	-103.753938
18,700.00	90.00	179.73	11,955.00	-6,645.51	-167.15	428,346.01	720,599.91	32.176274	-103.753939
18,800.00	90.00	179.73	11,955.00	-6,745.51	-166.68	428,246.02	720,600.38	32.175999	-103.753939
18,900.00	90.00	179.73	11,955.00	-6,845.51	-166.21	428,146.02	720,600.85	32.175724	-103.753939
19,000.00	90.00	179.73	11,955.00	-6,945.51	-165.73	428,046.02	720,601.32	32.175450	-103.753939
19,100.00	90.00	179.73	11,955.00	-7,045.50	-165.26	427,946.02	720,601.79	32.175175	-103.753939
19,200.00	90.00	179.73	11,955.00	-7,145.50	-164.79	427,846.02	720,602.26	32.174900	-103.753940
19,266.50	90.00	179.73	11,955.00	-7,212.00	-164.48	427,779.52	720,602.58	32.174717	-103.753940
PBHL & LTP @ 19267' MD, 2314' FNL, 990' FWL									
19,266.51	90.00	179.73	11,955.00	-7,212.01	-164.48	427,779.51	720,602.58	32.174717	-103.753940

Design Targets									
Target Name	Dip Angle (°)	Dip Dir. (°)	TVD (ft)	+N/-S (ft)	+E/-W (ft)	Northing (usft)	Easting (usft)	Latitude	Longitude
PBHL - Cotton Draw Uni	0.00	0.00	0.00	-7,212.01	-164.48	427,779.51	720,602.58	32.174717	-103.753940
- hit/miss target									
- Shape									
PBHL - plan misses target center by 7213.89ft at 0.00ft MD (0.00 TVD, 0.00 N, 0.00 E)									
- Point									



## Planning Report - Geographic

<b>Database:</b>	EDM r5000.141_Prod US	<b>Local Co-ordinate Reference:</b>	Well Cotton Draw Unit 603H
<b>Company:</b>	WCDSC Permian NM	<b>TVD Reference:</b>	RKB @ 3560.90ft (Original Well Elev)
<b>Project:</b>	Eddy County (NAD 83 NM Eastern)	<b>MD Reference:</b>	RKB @ 3560.90ft (Original Well Elev)
<b>Site:</b>	Sec 26-T24S-R31E	<b>North Reference:</b>	Grid
<b>Well:</b>	Cotton Draw Unit 603H	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Wellbore:</b>	Wellbore #1		
<b>Design:</b>	Permit Plan 1		

Plan Annotations				
Measured Depth (ft)	Vertical Depth (ft)	Local Coordinates		Comment
		+N/-S (ft)	+E/-W (ft)	
11,392.37	11,382.04	335.00	-200.00	KOP @ 11392' MD, 50' FNL, 990' FWL
11,985.00	11,874.51	54.88	-198.68	FTP @ 11985' MD, 330' FNL, 990' FWL
16,954.00	11,955.00	-4,899.53	-175.36	Cross seciton @ 16954' MD, 0' FNL, 990' FWL
19,266.50	11,955.00	-7,212.00	-164.48	PBHL & LTP @ 19267' MD, 2314' FNL, 990' FWL

Devon Energy


WELL DETAILS: Cotton Draw Unit 603H

RKB @ 3560.90ft (Original Well Elev)  
3535.90



Northing 434991.51      Easting 720767.06      Latitude 32.194539      Longitude -103.753282

SECTION DETAILS      Permit Plan 1

MD	Inc	Azi	TVD	+N/-S	+E/-W	Dleg	VSect	Annotation
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
3500.00	0.00	0.00	3500.00	0.00	0.00	0.00	0.00	
3806.94	3.07	329.16	3806.79	7.06	-4.21	1.00	-6.96	
10837.71	3.07	329.16	10827.47	330.30	-197.19	0.00	-325.71	
11042.33	0.00	0.00	11032.00	335.00	-200.00	1.50	-330.35	
11392.37	0.00	0.00	11382.04	335.00	-200.00	0.00	-330.35	KOP @ 11392' MD, 50' FNL, 990' FWL
12292.37	90.00	179.73	11955.00	-237.95	-197.30	10.00	242.39	
19266.51	90.00	179.73	11955.00	-7212.01	-164.48	0.00	7213.89	PBHL & LTP @ 19267' MD, 2314' FNL, 990' FWL



Azimuths to Grid North  
True North: -0.31°  
Magnetic North: 6.43°  
  
Magnetic Field  
Strength: 47616.6snT  
Dip Angle: 59.97°  
Date: 3/23/2020  
Model: IGRF2015



**PECOS DISTRICT  
DRILLING CONDITIONS OF APPROVAL**

<b>OPERATOR'S NAME:</b>	<b>Devon Energy Production Company LP</b>
<b>LEASE NO.:</b>	<b>NMNM0012121</b>
<b>LOCATION:</b>	Section 26, T.24 S., R.31 E., NMPM
<b>COUNTY:</b>	Eddy County, New Mexico

<b>WELL NAME &amp; NO.:</b>	Cotton Draw Unit 601H
<b>SURFACE HOLE FOOTAGE:</b>	385'/N & 1130'/W
<b>BOTTOM HOLE FOOTAGE:</b>	2314'/N & 400'/W

<b>WELL NAME &amp; NO.:</b>	Cotton Draw Unit 602H
<b>SURFACE HOLE FOOTAGE:</b>	385'/N & 1160'/W
<b>BOTTOM HOLE FOOTAGE:</b>	2314'/N & 450'/W

<b>WELL NAME &amp; NO.:</b>	Cotton Draw Unit 603H
<b>SURFACE HOLE FOOTAGE:</b>	385'/N & 1190'/W
<b>BOTTOM HOLE FOOTAGE:</b>	2314'/N & 990'/W

<b>WELL NAME &amp; NO.:</b>	Cotton Draw Unit 604H
<b>SURFACE HOLE FOOTAGE:</b>	385'/N & 1220'/W
<b>BOTTOM HOLE FOOTAGE:</b>	2314'/N & 1650'/W

<b>WELL NAME &amp; NO.:</b>	Cotton Draw Unit 605H
<b>SURFACE HOLE FOOTAGE:</b>	385'/N & 2525'/W
<b>BOTTOM HOLE FOOTAGE:</b>	2310'/N & 1750'/W

<b>WELL NAME &amp; NO.:</b>	Cotton Draw Unit 606H
<b>SURFACE HOLE FOOTAGE:</b>	385'/N & 2555'/W
<b>BOTTOM HOLE FOOTAGE:</b>	2310'/N & 2300'/W

<b>WELL NAME &amp; NO.:</b>	Cotton Draw Unit 608H
<b>SURFACE HOLE FOOTAGE:</b>	385'/N & 2615'/W
<b>BOTTOM HOLE FOOTAGE:</b>	2310'/N & 2200'/E

COA

H2S	<input checked="" type="checkbox"/> Yes	<input type="checkbox"/> No	
Potash	<input checked="" type="checkbox"/> None	<input type="checkbox"/> Secretary	<input type="checkbox"/> R-111-P
Cave/Karst Potential	<input checked="" type="checkbox"/> Low	<input type="checkbox"/> Medium	<input type="checkbox"/> High
Cave/Karst Potential	<input type="checkbox"/> Critical		
Variance	<input type="checkbox"/> None	<input checked="" type="checkbox"/> Flex Hose	<input type="checkbox"/> Other
Wellhead	<input type="checkbox"/> Conventional	<input checked="" type="checkbox"/> Multibowl	<input type="checkbox"/> Both
Other	<input type="checkbox"/> 4 String Area	<input type="checkbox"/> Capitan Reef	<input type="checkbox"/> WIPP
Other	<input checked="" type="checkbox"/> Fluid Filled	<input checked="" type="checkbox"/> Cement Squeeze	<input type="checkbox"/> Pilot Hole
Special Requirements	<input type="checkbox"/> Water Disposal	<input type="checkbox"/> COM	<input checked="" type="checkbox"/> Unit

## A. HYDROGEN SULFIDE

A Hydrogen Sulfide (H2S) Drilling Plan shall be activated 500 feet prior to drilling into the **Cotton Draw** pool. As a result, the Hydrogen Sulfide area must meet Onshore Order 6 requirements, which includes equipment and personnel/public protection items. If Hydrogen Sulfide is encountered, please provide measured values and formations to the BLM.

## B. CASING

1. The **13-3/8** inch surface casing shall be set at approximately **775 feet** (a minimum of **70 feet (Eddy County)** into the Rustler Anhydrite and above the salt) and cemented to the surface.
  - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.
  - b. Wait on cement (WOC) time for a primary cement job will be a minimum of **8 hours** or 500 pounds compressive strength, whichever is greater. (This is to include the lead cement)
  - c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.
  - d. If cement falls back, remedial cementing will be done prior to drilling out that string.

**Intermediate casing must be kept fluid filled to meet BLM minimum collapse requirement.**

2. The minimum required fill of cement behind the **8-5/8** inch intermediate casing is:
  - **Cement to surface. If cement does not circulate see B.1.a, c-d above. Cement excess is less than 25%, more cement might be required.**

**Operator has proposed to pump down 13-3/8" X 8-5/8" annulus. Operator must run a CBL from TD of the 8-5/8" casing to surface. Submit results to BLM.**

**Production casing must be kept fluid filled to meet BLM minimum collapse requirement.**

3. The minimum required fill of cement behind the **5-1/2** inch production casing is:
  - Cement should tie-back at least **200 feet** into previous casing string. Operator shall provide method of verification.

### **C. PRESSURE CONTROL**

1. Variance approved to use flex line from BOP to choke manifold. Manufacturer's specification to be readily available. No external damage to flex line. Flex line to be installed as straight as possible (no hard bends).'
2. Operator has proposed a multi-bowl wellhead assembly. This assembly will only be tested when installed on the surface casing. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be **5000 (5M)** psi.
  - a. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
  - b. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
  - c. Manufacturer representative shall install the test plug for the initial BOP test.
  - d. If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
  - e. Whenever any seal subject to test pressure is broken, all the tests in OOGO2.III.A.2.i must be followed.

#### **D. SPECIAL REQUIREMENT (S)**

##### **Unit Wells**

The well sign for a unit well shall include the unit number in addition to the surface and bottom hole lease numbers. This also applies to participating area numbers. If a participating area has not been established, the operator can use the general unit designation, but will replace the unit number with the participating area number when the sign is replaced.

##### **Commercial Well Determination**

A commercial well determination shall be submitted after production has been established for at least six months.

## GENERAL REQUIREMENTS

The BLM is to be notified in advance for a representative to witness:

- a. Spudding well (minimum of 24 hours)
- b. Setting and/or Cementing of all casing strings (minimum of 4 hours)
- c. BOPE tests (minimum of 4 hours)

☒ Eddy County

Call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220,  
(575) 361-2822

☒ Lea County

Call the Hobbs Field Station, 414 West Taylor, Hobbs NM 88240, (575)  
393-3612

1. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval.
  - a. In the event the operator has proposed to drill multiple wells utilizing a skid/walking rig. Operator shall secure the wellbore on the current well, after installing and testing the wellhead, by installing a blind flange of like pressure rating to the wellhead and a pressure gauge that can be monitored while drilling is performed on the other well(s).
  - b. When the operator proposes to set surface casing with Spudder Rig
    - Notify the BLM when moving in and removing the Spudder Rig.
    - Notify the BLM when moving in the 2<sup>nd</sup> Rig. Rig to be moved in within 90 days of notification that Spudder Rig has left the location.
    - BOP/BOPE test to be conducted per Onshore Oil and Gas Order No. 2 as soon as 2nd Rig is rigged up on well.
2. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works are located, this does not include the dog house or stairway area.
3. The record of the drilling rate along with the GR/N well log run from TD to surface (horizontal well – vertical portion of hole) shall be submitted to the BLM office as well as all other logs run on the borehole 30 days from completion. If available, a digital copy of the logs is to be submitted in addition to the paper copies. The Rustler top and top and bottom of Salt are to be recorded on the Completion Report.

A. CASING

1. Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size or are Non-API. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.). The initial wellhead installed on the well will remain on the well with spools used as needed.
2. Wait on cement (WOC) for Potash Areas: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi for all cement blends, 2) until cement has been in place at least 24 hours. WOC time will be recorded in the driller's log. The casing integrity test can be done (prior to the cement setting up) immediately after bumping the plug.
3. Wait on cement (WOC) for Water Basin: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi at the shoe, 2) until cement has been in place at least 8 hours. WOC time will be recorded in the driller's log. See individual casing strings for details regarding lead cement slurry requirements. The casing integrity test can be done (prior to the cement setting up) immediately after bumping the plug.
4. Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. Have well specific cement details onsite prior to pumping the cement for each casing string.
5. No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.
6. On that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Formation at the shoe shall be tested to a minimum of the mud weight equivalent anticipated to control the formation pressure to the next casing depth or at total depth of the well. This test shall be performed before drilling more than 20 feet of new hole.
7. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.
8. Whenever a casing string is cemented in the R-111-P potash area, the NMOCD requirements shall be followed.

B. PRESSURE CONTROL



1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in Onshore Oil and Gas Order No. 2 and API RP 53 Sec. 17.
2. If a variance is approved for a flexible hose to be installed from the BOP to the choke manifold, the following requirements apply: The flex line must meet the requirements of API 16C. Check condition of flexible line from BOP to choke manifold, replace if exterior is damaged or if line fails test. Line to be as straight as possible with no hard bends and is to be anchored according to Manufacturer's requirements. The flexible hose can be exchanged with a hose of equal size and equal or greater pressure rating. Anchor requirements, specification sheet and hydrostatic pressure test certification matching the hose in service, to be onsite for review. These documents shall be posted in the company man's trailer and on the rig floor.
3. 5M or higher system requires an HCR valve, remote kill line and annular to match. The remote kill line is to be installed prior to testing the system and tested to stack pressure.
4. If the operator has proposed a multi-bowl wellhead assembly in the APD. The following requirements must be met:
  - a. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
  - b. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
  - c. Manufacturer representative shall install the test plug for the initial BOP test.
  - d. Whenever any seal subject to test pressure is broken, all the tests in OOGO2.III.A.2.i must be followed.
  - e. If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
5. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.
  - a. In a water basin, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. The casing cut-off and BOP installation can be initiated four hours after installing the slips, which will be approximately six hours after bumping the plug. For those casing strings not using slips, the minimum wait time before cut-off is eight hours after bumping the plug. BOP/BOPE testing can begin after cut-off or once cement reaches 500 psi compressive strength (including lead when specified), whichever is greater. However, if the float does not

hold, cut-off cannot be initiated until cement reaches 500 psi compressive strength (including lead when specified).

- b. In potash areas, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. For all casing strings, casing cut-off and BOP installation can be initiated at twelve hours after bumping the plug. However, **no tests** shall commence until the cement has had a minimum of 24 hours setup time, except the casing pressure test can be initiated immediately after bumping the plug (only applies to single stage cement jobs).
- c. The tests shall be done by an independent service company utilizing a test plug not a cup or J-packer. The operator also has the option of utilizing an independent tester to test without a plug (i.e. against the casing) pursuant to Onshore Order 2 with the pressure not to exceed 70% of the burst rating for the casing. Any test against the casing must meet the WOC time for water basin (8 hours) or potash (24 hours) or 500 pounds compressive strength, whichever is greater, prior to initiating the test (see casing segment as lead cement may be critical item).
- d. The test shall be run on a 5000 psi chart for a 2-3M BOP/BOP, on a 10000 psi chart for a 5M BOP/BOPE and on a 15000 psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one hour chart. A circular chart shall have a maximum 2 hour clock. If a twelve hour or twenty-four hour chart is used, tester shall make a notation that it is run with a two hour clock.
- e. The results of the test shall be reported to the appropriate BLM office.
- f. All tests are required to be recorded on a calibrated test chart. A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.
- g. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug. This test shall be performed prior to the test at full stack pressure.
- h. BOP/BOPE must be tested by an independent service company within 500 feet of the top of the Wolfcamp formation if the time between the setting of the intermediate casing and reaching this depth exceeds 20 days. This test does not exclude the test prior to drilling out the casing shoe as per Onshore Order No. 2.

C. DRILLING MUD

Mud system monitoring equipment, with derrick floor indicators and visual and audio alarms, shall be operating before drilling into the Wolfcamp formation, and shall be used until production casing is run and cemented.

**D. WASTE MATERIAL AND FLUIDS**

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area.

Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.



**Devon Energy Center  
333 West Sheridan Avenue  
Oklahoma City, Oklahoma 73102-5015**

# **Hydrogen Sulfide (H<sub>2</sub>S) Contingency Plan**

**For**



**Cotton Draw Unit 603H**

**Sec-26 T-24S R-31E  
385' FNL & 1190' FWL  
LAT. = 32.1945387' N (NAD83)  
LONG = 103.7532823' W**

**Eddy County NM**

## Cotton Draw Unit 603H

This is an open drilling site. H<sub>2</sub>S monitoring equipment and emergency response equipment will be used within 500' of zones known to contain H<sub>2</sub>S, including warning signs, wind indicators and H<sub>2</sub>S monitor.



Assumed 100 ppm ROE = 3000' (Radius of Exposure)  
100 ppm H<sub>2</sub>S concentration shall trigger activation of this plan.

### Escape

Crews shall escape upwind of escaping gas in the event of an emergency release of gas. Escape can be facilitated from the location entrance road. Crews should then block the entrance to the location from the lease road so as not to allow anyone traversing into a hazardous area. The blockade should be at a safe distance outside of the ROE. There are no homes or buildings in or near the ROE.

**Assumed 100 ppm ROE = 3000'**

**100 ppm H<sub>2</sub>S concentration shall trigger activation of this plan.**

### **Emergency Procedures**

In the event of a release of gas containing H<sub>2</sub>S, the first responder(s) must

- Isolate the area and prevent entry by other persons into the 100 ppm ROE.
- Evacuate any public places encompassed by the 100 ppm ROE.
- Be equipped with H<sub>2</sub>S monitors and air packs in order to control the release.
- Use the “buddy system” to ensure no injuries occur during the response
- Take precautions to avoid personal injury during this operation.
- Contact operator and/or local officials to aid in operation. See list of phone numbers attached.
- Have received training in the
  - Detection of H<sub>2</sub>S, and
  - Measures for protection against the gas,
  - Equipment used for protection and emergency response.

### **Ignition of Gas Source**

Should control of the well be considered lost and ignition considered, take care to protect against exposure to Sulfur Dioxide (SO<sub>2</sub>). Intentional ignition must be coordinated with the NMOCD and local officials. Additionally the NM State Police may become involved. NM State Police shall be the Incident Command on scene of any major release. Take care to protect downwind whenever there is an ignition of the gas

### **Characteristics of H<sub>2</sub>S and SO<sub>2</sub>**

<b>Common Name</b>	<b>Chemical Formula</b>	<b>Specific Gravity</b>	<b>Threshold Limit</b>	<b>Hazardous Limit</b>	<b>Lethal Concentration</b>
<b>Hydrogen Sulfide</b>	H <sub>2</sub> S	1.189 Air = 1	10 ppm	100 ppm/hr	600 ppm
<b>Sulfur Dioxide</b>	SO <sub>2</sub>	2.21 Air = 1	2 ppm	N/A	1000 ppm

### **Contacting Authorities**

Devon Energy Corp. personnel must liaison with local and state agencies to ensure a proper response to a major release. Additionally, the OCD must be notified of the release as soon as possible but no later than 4 hours. Agencies will ask for information such as type and volume of release, wind direction, location of release, etc. Be prepared with all information available. The following call list of essential and potential responders has been prepared for use during a release. Devon Energy Corp. Company response must be in coordination with the State of New Mexico’s ‘Hazardous Materials Emergency Response Plan’ (HMER)

# **Hydrogen Sulfide Drilling Operation Plan**

## **I. HYDROGEN SULFIDE (H<sub>2</sub>S) TRAINING**

All personnel, whether regularly assigned, contracted, or employed on an unscheduled basis, will receive training from a qualified instructor in the following areas prior to commencing drilling operations on this well:

1. The hazards and characteristics of hydrogen sulfide (H<sub>2</sub>S)
2. The proper use and maintenance of personal protective equipment and life support systems.
3. The proper use of H<sub>2</sub>S detectors, alarms, warning systems, briefing areas, evacuation procedures, and prevailing winds.
4. The proper techniques for first aid and rescue procedures.

In addition, supervisory personnel will be trained in the following areas:

1. The effects of H<sub>2</sub>S metal components. If high tensile tubulars are to be used, personnel will be trained in their special maintenance requirements.
2. Corrective action and shut-in procedures when drilling or reworking a well and blowout prevention and well control procedures.
3. The contents and requirements of the H<sub>2</sub>S Drilling Operations Plan and Public Protection Plan.

There will be an initial training session just prior to encountering a known or probable H<sub>2</sub>S zone (within 3 days or 500 feet) and weekly H<sub>2</sub>S and well control drills for all personnel in each crew. The initial training session shall include a review of the site specific H<sub>2</sub>S Drilling Operations Plan and the Public Protection Plan.

## **II. HYDROGEN SULFIDE TRAINING**

Note: All H<sub>2</sub>S safety equipment and systems will be installed, tested, and operational when drilling reaches a depth of 500 feet above, or three days prior to penetrating the first zone containing or reasonably expected to contain H<sub>2</sub>S.

## **1. Well Control Equipment**

- A. Flare line
- B. Choke manifold – Remotely Operated
- C. Blind rams and pipe rams to accommodate all pipe sizes with properly sized closing unit
- D. Auxiliary equipment may include if applicable: annular preventer and rotating head.
- E. Mud/Gas Separator

## **2. Protective equipment for essential personnel:**

30-minute SCBA units located at briefing areas, as indicated on well site diagram, with escape units available in the top doghouse. As it may be difficult to communicate audibly while wearing these units, hand signals shall be utilized.

## **3. H<sub>2</sub>S detection and monitoring equipment:**

Portable H<sub>2</sub>S monitors positioned on location for best coverage and response. These units have warning lights which activate when H<sub>2</sub>S levels reach 10 ppm and audible sirens which activate at 15 ppm. Sensor locations:

- Bell nipple
- Possum Belly/Shale shaker
- Rig floor
- Choke manifold
- Cellar

### **Visual warning systems:**

- A. Wind direction indicators as shown on well site diagram
- B. Caution/ Danger signs shall be posted on roads providing direct access to locations. Signs will be painted a high visibility yellow with black lettering of sufficient size to be reasonable distance from the immediate location. Bilingual signs will be used when appropriate.



#### **4. Mud program:**

The mud program has been designed to minimize the volume of H<sub>2</sub>S circulated to surface. Proper mud weight, safe drilling practices and the use of H<sub>2</sub>S scavengers will minimize hazards when penetrating H<sub>2</sub>S bearing zones.

#### **5. Metallurgy:**

- A. All drill strings, casings, tubing, wellhead, blowout preventer, drilling spool, kill lines, choke manifold lines, and valves shall be H<sub>2</sub>S trim.
- B. All elastomers used for packing and seals shall be H<sub>2</sub>S trim.

#### **6. Communication:**

- A. Company personnel have/use cellular telephones in the field.
- B. Land line (telephone) communications at Office

#### **7. Well testing:**

- A. Drill stem testing will be performed with a minimum number of personnel in the immediate vicinity, which are necessary to safety and adequately conduct the test. The drill stem testing will be conducted during daylight hours and formation fluids will not be flowed to the surface. All drill-stem-testing operations conducted in an H<sub>2</sub>S environment will use the closed chamber method of testing.
- B. There will be no drill stem testing.

<b><u>Devon Energy Corp. Company Call List</u></b>		
Drilling Supervisor – Basin – Mark Kramer		405-823-4796
EHS Professional – Laura Wright		405-439-8129
<b><u>Agency Call List</u></b>		
<b><u>Lea County (575)</u></b>	<b>Hobbs</b>	
	Lea County Communication Authority	393-3981
	State Police	392-5588
	City Police	397-9265
	Sheriff's Office	393-2515
	<b>Ambulance</b>	<b>911</b>
	Fire Department	397-9308
	LEPC (Local Emergency Planning Committee)	393-2870
	NMOCD	393-6161
	US Bureau of Land Management	393-3612
<b><u>Eddy County (575)</u></b>	<b>Carlsbad</b>	
	State Police	885-3137
	City Police	885-2111
	Sheriff's Office	887-7551
	<b>Ambulance</b>	<b>911</b>
	Fire Department	885-3125
	LEPC (Local Emergency Planning Committee)	887-3798
	US Bureau of Land Management	887-6544
	NM Emergency Response Commission (Santa Fe)	(505) 476-9600
	24 HR	(505) 827-9126
	National Emergency Response Center	(800) 424-8802
	National Pollution Control Center: Direct	(703) 872-6000
	For Oil Spills	(800) 280-7118
	<b>Emergency Services</b>	
	Wild Well Control	(281) 784-4700
	Cudd Pressure Control	(915) 699-0139 (915) 563-3356
	Halliburton	(575) 746-2757
	B. J. Services	(575) 746-3569
<b><u>Give GPS position:</u></b>	Native Air – Emergency Helicopter – Hobbs	(575) 392-6429
	Flight For Life - Lubbock, TX	(806) 743-9911
	Aerocare - Lubbock, TX	(806) 747-8923
	Med Flight Air Amb - Albuquerque, NM	(575) 842-4433
	Lifeguard Air Med Svc. Albuquerque, NM	(800) 222-1222
	Poison Control (24/7)	(575) 272-3115
	Oil & Gas Pipeline 24 Hour Service	(800) 364-4366
	NOAA – Website - <a href="http://www.nhc.noaa.gov">www.nhc.noaa.gov</a>	

Prepared in conjunction with  
Dave Small



# Devon Energy - Well Pad Rig Location Layout Safety Equipment Location

