DEPARTMENT OF THE BUREAU OF LAND MAN APPLICATION FOR PERMIT TO  Type of Well. Voil Well Gas Well Other  Name of Operator  BOPCO, L. P.  A Address P. O. Box 2760 Midland, TX 79702 At surface  MES W., ULX, 2365' FSL, 1980' FV.	INTERIOR NAGEMENT  DRILL OR REENTER  ER  Single Zone Multip  3b Phone No. (include area code) 432-683-2277  The State requirements.*)	Figure 1 September 2 September	otee or Tribe Name  Agreement, Name and No nch NMNM 70965X  and Well No. nch Unit #138H
DEPARTMENT OF THE BUREAU OF LAND MAN APPLICATION FOR PERMIT TO  a. Type of work.  DRILL  REENT  b. Type of Well.  Oil Well  Gas Well  Other  Name of Operator  BOPCO, L. P.  a. Address P. O. Box 2760  Midland, TX 79702  Location of Well (Report location cle. Land in accordance with an	INTERIOR NAGEMENT  DRILL OR REENTER  ER  Single Zone Multip  3b Phone No. (include area code) 432-683-2277  The State requirements.*)	5 Lease Serial 1 02952; 029: 6 If Indian, Allo 7 If Unit or CA A James Ran 8 Lease Name a James Ran 9 API Well No. 10 Field and Pool, Quahada F	No. 53* otee or Tribe Name  Agreement, Name and No nch NMNM 70965X and Well No. nch Unit #138H
APPLICATION FOR PERMIT TO  a. Type of work.  DRILL  REENT  b. Type of Well.  Oil Well  Gas Well  Other  Name of Operator  BOPCO, L. P.  a. Address P. O. Box 2760  Midland, TX 79702  Location of Well (Report location cle. Land in accordance with an	DRILL OR REENTER  PER  Single Zone Multip  Multip  3b Phone No. (include area code)  432-683-2277  The State requirements.*	7 If Unit or CA A  James Ran  8 Lease Name a  James Ran  9 API Well No.  10 Field and Pool,  Quahada F	Agreement, Name and No nich NMNM 70965X and Well No. nich Unit #138H
Type of Well. Oil Well Gas Well Other  Name of Operator  BOPCO, L. P.  Address P. O. Box 2760  Midland, TX 79702  Location of Well (Report location cle. K. and in accordance with an	Single Zone Multip    3b   Phone No. (include area code)     432-683-2277     25   27   27     27   27   27     27   27	James Ran  8 Lease Name a  James Ran  9 API Well No.  10 Field and Pool,  Quahada F	nch NMNM 70965X  and Well No.  nch Unit #138H  5-39766
Name of Operator  BOPCO, L. P.  Address P. O. Box 2760  Midland, TX 79702  Location of Well (Report location cle. K. and in accordance with an	3b Phone No. (mclude frea code) 432-683-2277  ny State requirements.*)	ge Zone James Ran  9 API Well No.  10 Field and Pool,  Quahada F	nch Unit #138H (3 5-39166
BOPCO, L. P.  Address P. O. Box 2760 Midland, TX 79702 Location of Well (Report location cle. L. and in accordance with an	432-683-2277  Try State requirements.*)	10 Field and Pool, Quahada F	5-39766
Midland, TX 79702 6120  Location of Well (Report location cle. K. and in accordance with an	432-683-2277  Try State requirements.*)	Quahada F	or Exploratory
Location of Well (Report location cle L'and in accordance with an			Ridge, SE (Delaware)
At surface NESW, ULE, 2365' FSL, 1980' FV	VL, Lat:N32.362247, Long:W103.		or Blk. and Survey or Area
At proposed prod zone 1980' FSL, 330' FWL, Sec 27, T22S	5,R30E,Lat:N32,361264,Lg:W103	Sec 25, T22	2S, R30E Mer NMP
Distance in miles and direction from nearest town or post office*  20 miles southeast of Malaga	<u> </u>	12 County or Pari Eddy	ish 13 State NM
Distance from proposed* 1980' location to nearest	16 No of acres in lease	17 Spacing Unit dedicated to the	hıs weli
property or lease line, ft (Also to nearest drig unit line, if any)	5121.84	320	
Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft  415'	19 Proposed Depth 19,531' MD, 7,304' TVD	20 BLM/BIA Bond No. on file COB 000050	e
Elevations (Show whether DF, KDB, RT, GL, etc)	22. Approximate date work will star	* 23 Estimated dur	ration
3,343' GL	. 11/01/2011	30 Days	
	24. Attachments		
e following, completed in accordance with the requirements of Onsho  Well plat certified by a registered surveyor  A Drilling Plan		ached to this form:  e operations unless covered by	y an existing bond on file (
A Surface Use Plan (if the location is on National Forest System SUPO shall be filed with the appropriate Forest Service Office).		pecific information and/or plan	ns as may be required by the
Signature	Name (Printed/Typed)  Jeremy Braden		Date 9-19-11
Engineering Assistant	occurry brauen		
proved by (Signature) /s/ Tony J. Herrell	Name (Printed/Typed)		DalDEC 1 2
STATE DIRECTOR	Office NM	STATE OFFICE	3
plication approval does not warrant or certify that the applicant hold induct operations thereon. Inditions of approval, if any, are attached.	ds legal or equitable title to those right		uld entitle the applicant to

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

\*(Instructions on page 2)

CARLSBAD CONTROLLED WATER BASIN

SEE ATTACHED FUR
CONDITIONS OF APPROVAL

APPROVAL SUBJECT TO ...
GENERAL REQUIREMENTS
AND SPECIAL STIPULATIONS
ATTACHED

dm

DISTRICT I 1625 N. French Dr., Hobbs, NM 88240 DISTRICT II 1301 W. Grand Avenue, Artesia, NM 88210

1000 Río Brazos Rd., Aztec, NM 87410

1220 S. St. Francis Dr., Santa Fe, NM 87505

DISTRICT III

DISTRICT IV

## State of New Mexico Energy, Minerals and Natural Resources Department

Form C-102 Revised July 16, 2010

Submit one copy to appropriate District Office


## OIL CONSERVATION DIVISION

1220 South St. Francis Dr. Santa Fe, New Mexico 87505


WELL LOCATION AND ACREAGE DEDICATION PLAT

☐ AMENDED REPORT

API	Number	11		Pool Code		Pool Name					
3/2-015	- 39%	lolo	تِ	50443	Quahada Ridge, SE (Delaware)						
Property (	Code		Property Name Well Num								
30640	7			J۵	MES RANCH	UNIT		138H	l		
OGRID No	ο.				Operator Nam	ne .	-	Elevat			
26073	7				BOPCO, L.	Р.		334	3'		
<u>-</u>					Surface Loca	ation					
UL or lot No.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County		
κ -	25	22 S	30 E		2365	SOUTH	1980	WEST	EDDY		
			Bottom	Hole Loc	ation If Diffe	rent From Sur	face	·			
UL or lot No.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County		
L	27	22 S	30 E		1980	SOUTH	330	WEST	EDDY		
Dedicated Acres Joint or Infill Consolidation Code Order No.											
NO ALLO	WABLE W					NTIL ALL INTER APPROVED BY		EEN CONSOLIDA	TED		



SECTION 25, TOWNSHIP 22 SOUTH, RANGE 30 EAST, N.M.P.M., EDDY COUNTY, WELL PAD LAYOUT NEW MEXICO.



Directions to Location:

FROM THE WIPP SITE, GO NORTH 10 MILES TO LEASE ROAD, ON LEASE ROAD GO SOUTHWESTERLY FOR 1.8 MILES TO LEASE ROAD, ON LEASE ROAD GO SOUTH 0 9 MILES TO LEASE ROAD, ON LEASE ROAD GO SOUTHWESTERLY FOR 0.3 MILES TO LEASE ROAD, ON LEASE ROAD GO NORTH 0 1 MILES TO PROPOSED WELL PAD

BASIN SURVEYS P.O BOX 1786-HOBBS, NEW MEXICO

W.O. Number. 25267 Drawn By. **J. SMALL**Date 09-07-2011 Disk: JMS 25267

200 0 200 400 FEET

SCALE: 1" = 200'

## BOPCO, L.P.


REF: JAMES RANCH UNIT #138H / WELL PAD TOPO

THE JAMES RANCH UNIT #138H LOCATED 2365'

FROM THE SOUTH LINE AND 1980' FROM THE WEST LINE OF SECTION 25, TOWNSHIP 22 SOUTH, RANGE 30 EAST,

N.M.P.M., EDDY COUNTY, NEW MEXICO.

Survey Date. 09-06-2011 | Sheet 1 of 6 Sheets






P.O. Box 1786 1120 N. West County Rd. Hobbs, New Mexico 88241 (575) 393-7316 — Office (575) 392-2206 — Fax basinsurveys.com

W O. Number: JMS 25267	
Survey Date: 09-06-2011	\$
Scale: 1" = 2000'	T
Date: 09-07-2011	4

BOPCO, L.P.

Sheet 2 of 6 Sheets






P O. Box 1786 1120 N. West County Rd. Hobbs, New Mexico 88241 (575) 393-7316 — Office (575) 392-2206 — Fax basinsurveys.com

W.O. Number: JMS 25267	
Survey Date: 09-06-2011	1
Scale: 1" = 2 Miles	4
Date: 09072011	

BOPCO, L.P.

Sheet 3 of 6 Sheets






P.O. Box 1786 1120 N. West County Rd. Hobbs, New Mexico 88241 (575) 393—7316 — Office (575) 392—2206 — Fax basinsurveys.com W.O Number, JMS 25267

Scale: 1" = 2000'

YELLOW TINT — USA LAND BLUE TINT — STATE LAND NATURAL COLOR — FEE LAND BOPCO, L.P.


Sheet 4 '

Sheets





P.O. Box 1786 1120 N. West County Rd. Hobbs, New Mexico 88241 (575) 393-7316 — Office (575) 392-2206 — Fax basinsurveys.com




BOPCO, L.P.

Sheet 5 of 6 Sheets

## James Ranch Unit #138H MOA Diagram 3





JAMES RANCH UNIT #138H Located 2365' FSL and 1980' FWL Section 25. Township 22 South, Range 30 East, N.M.P.M., Eddy County, New Mexico.

Surface casing is to be set into the Rustler below all fresh water sands at an approximate depth of 751' and cement circulated to surface.

7" casing will be set at approximately 9,498' MD, 7,344' TVD (thru curve) and cemented in two stages with DV Tool set at approximately 5,000'. Cement will be circulated to surface.

Drilling procedure, BOP diagram, and anticipated tops are attached.

This well is located inside the R111 Potash area and Secretary's Potash area.

The surface location is nonstandard and located outside the James Ranch Unit.

The bottom hole location is standard and located inside the James Ranch Unit

## Surface Lease Number's -This well is located off Unit

## Bottom Hole Lease Numbers - 02952, 02953

BOPCO, L.P., at P. O. Box 2760, Midland, TX, 79702 is a subsidiary of BOPCO, L.P., 201 Main Street, Ft. Worth, TX, 76102. Bond No. COB000050 (Nationwide).

## EIGHT POINT DRILLING PROGRAM BOPCO, L.P.

**ESTIMATED** 

+3,210

+ 2,997'

+ 2,604

SUB-SEA TOP

203'

**BEARING** 

Barren

Barren

Barren

Fresh Water

## NAME OF WELL: James Ranch Unit 138H

LEGAL DESCRIPTION - SURFACE: 2365' FSL, 1980' FWL, Section 25, T22S, R30E, Eddy County, NM. BHL: 1980' FSL, 330' FWL, Section 27, T22S, R30E, Eddy County, New Mexico.

MD

155'

368'

761'

3,568'

POINT 1: ESTIMATED FORMATION TOPS (See No. 2 Below)

## POINT 2: WATER, OIL, GAS AND/OR MINERAL BEARING FORMATIONS

TVD

155'

368'

761'

3.05

3,568'

ESTIMATED TOP FROM KB

Anticipated Formation Tops: KB 3365' (estimated)

**FORMATION** 

T/Fresh Water

4-1/2", 11.6#, N-80, 8rd, LT&C\*

\* Depending on availability.

T/Rustler

T/Salt

B/Salt

GL 3343'

T/Lamar	3,812'	3,812	- 447'	Barr	en
T/Ramsey	3,848'	3,848'		Oil/C	
T/Lower Cherry Canyon	6,002'	6,002	- 2,637	Oil/C	eas .
KOP	6,867'	6,867	·	Oil/C	Sas
LBC Lo "U"	7,294'	7,395'		Oil/C	as
Target #1	7,344'	9,498'	·	Oil/C	
EOC	7,344'	7,617		Oil/C	•
TD Horizontal Hole	7,304'	19,531	·	Oil/C	
POINT 3: CASING PROGRAM					
TYPE	INTERVALS	S (MD)	Hole Size	PURPOSE	CONDITION
20"	0'-	60'	24"	Conductor	Contractor Discretion
13-3/8", 48#, H-40, or 54.5#, J-55 8rd, ST&C*	0' -	751'	17-1/2"	Surface	New
9-5/8", 40#, N-80, 8rd, LT&C	0' - 38	332 <sup>i</sup>	12-1/4"	Intermediate	New
7", 26#, N-80, Buttress or 8rd LTC*	0' - 94		8-3/4"	Production	New
Completion System					
4-1/2", 11.6#, HCP-110 8rd. LT&C*			6-1/8"	Completion Sy	
4-1/2", 11 6#, N-80; 8rd, LT&C*	9,448' – 19	9,531'	6-1/8"	Completion Sys	stem New
CASING DESIGN SAFETY FACTOR	RS:	•			•
TYPE	TENSIC		<u>COLLAPSE</u>	<u>BURST</u>	•
13-3/8", 48#, H-40, 8rd, ST&C*	10.33		1.99	4.13	•
13-3/8", 54 5#, J-55, 8rd, STC*	24.25		3.10	6.51	
9-5/8", 40#, N-80, 8rd, LT&C	5.70		1.41	2.69	
7", 26#, N-80, Buttress*	4.05		1.39	1.77	
7", 26#, N-80, 8rd, LTC*	3.15		1.32	1.77	
Completion System					
4-1/2", 11.6#, HCP-110 8rd. LT&C*	3.82		2.22	2.62	

1 54

1.91

#### **DESIGN CRITERIA AND CASING LOADING ASSUMPTIONS:**

## SURFACE CASING - (13-3/8")

Burst

Tension A 1.6 design factor utilizing the effects of buoyancy (9.2 ppg).

Collapse A 1.0 design factor with full internal evacuation and a collapse force equal to the mud gradient in which the

casing will be run (0.48 psi/ft). The effects of axial load on collapse will be considered.

A 1.3 design factor with a surface pressure equal to the fracture gradient at setting depth less a gas gradient to the surface. Internal burst force at the shoe will be fracture pressure a that depth. Backup pressure will be formation pore pressure. In all cases a conservative fracture pressure will be used such

that it represents the upper limit of potential fracture resistance up to a 1.0 psi/ft gradient. The effects of

tension on burst will not be utilized.

## PROTECTIVE CASING - (9-5/8")

Tension A 1 6 design factor utilizing the effects of buoyancy (10 ppg).

Collapse A 1.0 design factor with full internal evacuation and a collapse force equal to the mud gradient in which the casing will be run (0.52 psi/ft). The effects of axial load on collapse will be considered.

In the case of development drilling, collapse design should be analyzed using internal evacuation equal to 1/3 the proposed total depth of the well. This criterion will be used when there is absolutely no potential of

the protective string being used as a production casing string.

Burst A 1.0 surface design factor and a 1.3 downhole design factor with a surface pressure equivalent to the

fracture gradient at setting depth less a gas gradient to the surface. Internal burst force at the shoe will be fracture pressure at that depth. Back pressure will be formation pore pressure. In all cases a conservative fracture pressure will be used such that it represents the upper limit of potential fracture resistance up to a

1.0 psi/ft gradient.

## Production CASING - (7")

Tension A 1.6 design factor utilizing the effects of buoyancy (9 0 ppg).

Collapse A 1.0 design factor with full internal evacuation and a collapse force equal to the mud gradient in which the

casing will be run (0.48 psi/ft). The effects of axial load on collapse will be considered.

Burst A 1.25 design factor with anticipated maximum tubing pressure (5000 psig) on top of the maximum

anticipated packer fluid gradient. (0.433 psi/ft) Backup on production strings will be formation pore

pressure. (0.433 psi/ft) The effects of tension on burst will not be utilized.

## Completion System - (4-1/2")

Tension A 1.6 design factor utilizing the effects of buoyancy (9.0 ppg).

Collapse A 1.0 design factor with full internal evacuation and a collapse force equal to the mud gradient in which the

casing will be run (0.48 psi/ft). The effects of axial load on collapse will be considered.

Burst A 1.25 design factor with anticipated maximum tubing pressure (5000 psig) on top of the maximum anticipated packer fluid gradient. (0.433 psi/ft) Backup on production strings will be formation pore

pressure. (0.433 psi/ft) The effects of tension on burst will not be utilized.

## POINT 4: PRESSURE CONTROL EQUIPMENT (SEE ATTACHED DIAGRAM 1)

The BOPE when rigged up on the 13-3/8" surface casing head (12-1/4" open hole) will consist of 13-5/8" X 5,000 psi dual ram BOP's with mud cross, choke manifold, chokes, and hydril per Diagram 1 (5,000 psi WP). The pipe and blind rams, choke, kill lines, kelly cocks, inside BOP, etc. when installed on the surface casing head will be hydro-tested to 250-300 psig and 2000 psig by independent tester. The hydril when installed on surface casing head will be tested to 1000 psi.

The BOPE when rigged up on the 9-5/8" intermediate casing spool (8-3/4" open hole) will consist of 13-5/8" x 5,000 psi annular, 13-5/8" x 5,000 psi pipe & blind rams with mud cross, choke manifold and chokes as in Diagram 1. The pipe and blind rams, choke, kill lines, kelly cocks inside BOP, etc. will be tested to 3000 psig by independent tester. In addition to the high pressure test, a low pressure (250-300 psig) test will be required. Hydril will be tested to 1500 psig.

The BOPE when rigged up on the 7" intermediate casing spool (6-1/8" open hole) will consist of 13-5/8" x 5,000 psi annular, 13-5/8" x 5,000 psi pipe & blind rams with mud cross choke manifold and chokes as in Diagram 1. The pipe and blind rams, choke, kelly lines, kelly cocks inside BOP, etc. will be tested to 3000 psig by independent tester. In addition to the high pressure test, a low pressure (250-300 psig) test will be required. Hydril will be tested to 1500 psig.

These tests will be performed:

- a) Upon installation
- b) After any component changes
- c) Thirty days after a previous test
- d) As required by well conditions

A function test to insure that the preventers are operating correctly will be performed on each trip.

### **POINT 5: MUD PROGRAM**

DEPTH	MUD TYPE	<u>WEIGHT</u>	_FV_	<u>PV</u>	YP	<u>F</u> L	_Ph
0' - 751'	FW Spud Mud	8.5 - 9.2	38-70	NC	NC	NC	10.0
751' - 3,832'	Brine Water	9.8 - 10.2	28-30	NC	NC	NC	9.5 - 10.5
3,832' - 9,498'	FW/Gel	8.7 - 9.0	28-36	NC	NC	NC	9.5 - 10.0
9,498' - 19,531'	FW/Gel/Starch	8.7 - 9.0	28-36	NC	NC	<100	9.5 - 10.0

NOTE: May increase vis for logging purposes only.

## **POINT 6: TECHNICAL STAGES OF OPERATION**

A) TESTING

None anticipated.

B) LOGGING SulOH

Run #1: GR with MWD during drilling of build and horizontal portions of 8-3/4" and 6-1/8"

hole.

Run #2: Shuttle log w/GR, PE, Density, Neutron, Resistivity in lateral leg open hole.

Mud Logger: Rigged up at 100'.

## C) CONVENTIONAL CORING

None anticipated

## D) CEMENT

INTERVAL	AMOUNT SXS	FT OF FILL	TYPE	GALS/SX	<u>PPG</u>	FT <sup>3</sup> /SX
<b>SURFACE:</b> Lead: 0' - 651'	550	651	ExtendaCem CZ	8.72	13.70	1.68
Tail: 651' – 751'	110	100	ExtendaCem CZ	8.72	13.70	1.68
INTERMEDIATE: Lead: 0' ~ 3332'	1050	3332	EconoCem HLC 5% CaCl + 5 #/sk Gilsonite	9.32	12.90	<b>1.85</b>
Tail· 3332' – 3832'	270	500	HalCem C	6.34	14.80	1.33
Production Stage 1: Lead: 5000' –6722'	530	1722	Tuned Light + 0.75% CFR-3 + 1.5#/sk CaCl	12.41	10.20	2.76
Tail: 6722' - 9498'	400	2776	VersaCem-PBSH2 + 0.4% Halad-9	8.76	13.0	1.65
DV Tool @ 5000'					,	
Stage 2: _Lead: 0' 4500'	380	4500	EconoCem HLC + 1% Econolite + 5% CaCl + 5#/sk Gılsonite	10.71	12.60	2.04
Tail: 4500' - 5000'	100	500	HalCem C	6.34	14.80	1.33

Cement excesses will be as follows:

Surface – 100% excess with cement circulated to surface.

Production -50% above gauge hole or 35% above electric log caliper with cement circulated 500' up into the 9-5/8" 1<sup>st</sup> intermediate casing in areas outside the SOPA. Cement will be circulated to surface on areas inside the SOPA.

Cement volumes will be adjusted proportionately for depth changes of the multi stage tool.

<sup>1&</sup>lt;sup>st</sup> Intermediate – 50% excess above fluid caliper with cement circulated to surface.

## E) Completion System

A 4-1/2" completion system with open hole packers will be run in the producing lateral to a depth of 19,531'. The top of the Completion System will be set at approximately 9,448'. Cement will not be required for this system.

## F) DIRECTIONAL DRILLING

BOPCO, L.P. plans to drill out the 9-5/8" intermediate casing with a 8-3/4" bit to a TVD of approximately 6,867' at which point a directional hole will be kicked off and drilled at an azimuth of 260.453 degrees, building angle at 12.00 deg/100' to 90 degrees at a TVD of 7,344' (MD 7,617'). This angle and azimuth will be maintained for 1,881' to a measured depth of 9,498' (7,344' TVD). At this depth 7", 26#, N80, Buttress, or 8rd LTC casing will be installed and cemented in two stages (DV Tool @ approximately 5000') with cement circulated to surface. A 6-1/8" open hole lateral will then be drilled out from 7" casing at an azimuth of 270.109 degrees, inclination of 90.234 degrees to a measured depth of 19,531', TVD 7,304'. At this depth a 4-1/2" Completion System with packers installed for zone isolation will be run into the producing lateral.

## G) H2S Safety Equipment

As stated in the BLM Onshore Order 6, for wells located in the SOPA, H<sub>2</sub>S equipment will be rigged up after setting surface casing. For the wells located inside the SOPA the flare pit or ½ steel pits will be located 150' from the location. For wells located outside the SOPA the flare pit or ½ steel pit will be located 100' away from the location. (See page 6 of Survey plat package) There is not any H<sub>2</sub>S anticipated in the area, although in the event that H<sub>2</sub>S is encountered, the H<sub>2</sub>S contingency plan attached will be implemented.

## POINT 7: ANTICIPATED RESERVOIR CONDITIONS

Normal pressures are anticipated throughout Delaware section. A BHP of 3436 psi (max) or MWE of 9.0 ppg is expected. Lost circulation may exist in the Delaware Section from 3,812'-7,344' TVD.

## **POINT 8: OTHER PERTINENT INFORMATION**

A) Auxiliary Equipment

Upper and lower kelly cocks. Full opening stab in valve on the rig floor.

B) Anticipated Starting Date

Upon approval

30 days drilling operations

14 days completion operations

JDB




## BOPCO, L.P.

Location Eddy County, NM Field JRU NAD27 Facility (JRU) No 138 & No 139

Slot JRU No 138H SHL Well JRU No 138H Wellborg: JRU No 138H PWB




	Well Profile Data									
Design Comment	MD (ft)	Inc (°)	Az (°)	TVD (ft)	Local N (ft)	Local E (ft)	DLS (%100ft)	VS (ft)		
Tie On	22.00	0.000	260.453	22 00	0 00	0.00	0 00	0 00		
Est KOP	6628 00	- 0.000	260.453	6628.00	0 00	0.00	0 00	0.00		
EOC	7753 09	90 007	260 453	7344 20	-118.80	-706 36	8 00	709 94		
Target #1 / 7" Casing	9396 09	90 007	260 453	7344 00	-391 32	-2326 60	0 00	2338.37		
Build	9879 03	90 234	270 109	7342 98	-431 00	-2807.34	2 00	2820.16		
No.138H PBHL	19428 59	90 234	270 109	7304 00	-412 86	-12356 80	0 00	12363 70		



Plot reference wellpath is Prelun_5	
True vertical depths are referenced to Rig on No 138H SHL (KB)	Gnd System NAD27 / TM New Mexico SP, Eastern Zone (3001), US feet
Measured depths are referenced to Rig on No 138H SHL (KB)	North Reference Grid north
Rig on No 13BH SHL (KB) to Mean Sea Level: 3365 feet	Scale True distance
Mean Sea Level to Mud line (At Slot JRU No 138H SHL): 0 feet	Depths are in feet
Coordinates are in feet referenced to Slot	Created by genibry on 9/15/2011



BGGM (1945 0 to 2012 0) by 60.27 Field 48697 5 nT Megnetic North 17 74 degrees Enter 17 true North 10.81 (122011) Gnd North 10.92 degrees East of True North To correct astrought from Twis Confluence 20 74 degrees To correct astrought from Magnetic to Gnd subtract 0.27 degrees For example II the Magnetic North Azeruth = 90 degs, then the Gnd North Azeruth = 90 + 7 47 = 97 47





## Planned Wellpath Report Prelim\_4 Page 1 of 7



REFER	ENCE WELLPATH IDENTIFICATION		
Operator	BOPCO, L.P.	Slot	JRU No.138H SHL
Area	Eddy County, NM	Well	JRU No.138H
Field	JRU NAD27	Wellbore	JRU No.138H PWB
Facility	(JRU) No.138 & No.139		

REPORT SETUP INFORMATION							
Projection System	NAD27 / TM New Mexico SP, Eastern Zone (3001), US feet	Software System	WellArchitect® 3.0.0				
North Reference	Grid	User	Gentbry				
Scale	0.999936	Report Generated	9/14/2011 at 11:22:33 AM				
Convergence at slot	0.27° East	Database/Source file	WA Midland/JRU_No.138H_PWB.xml				

WELLPATH LOCAT	ľľON					The same of the sa	
	Local coordinates		Grid co	ordinates	Geographic coordinates		
	North[ft]	East[ft]	Easting[US ft]	Northing[US ft]	Latitude	Longitude	
Slot Location	953.03	1062.08	653557.45	495857.89	32°21'44.093"N	103°50'09.657"W	
Facility Reference Pt			652495.44	494904.92	32°21'34.711"N	103°50'22.090"W	
Field Reference Pt			652495.44	494904.92	32°21'34.711"N	103°50'22.090"W	

WELLPATH DATU	M.		
Calculation method	Minimum curvature	Rig on No.138H SHL (KB) to Facility Vertical Datum	3365.00ft
Horizontal Reference Pt	Slot	Rig on No.138H SHL (KB) to Mean Sea Level	3365.00ft
Vertical Reference Pt	Rig on No.138H SHL (KB)	Rig on No.138H SHL (KB) to Mud Line at Slot (JRU No.138H SHL)	3365.00ft
MD Reference Pt	Rig on No.138H SHL (KB)	Section Origin	N 0.00, E 0.00 ft
Field Vertical Reference	Mean Sea Level	Section Azimuth	268.09°



# Planned Wellpath Report Prelim\_4 Page 2 of 7



REBER	ENCE WELLPATH IDENTIFICATION		
Operator	BOPCO, L.P.	Slot	JRU No.138H SHL
Area	Eddy County, NM	Well	JRU No.138H
Field	JRU NAD27	Wellbore	JRU No.138H PWB
Facility	(JRU) No.138 & No.139		

WELLP	ATH DA	TA (209	station	s) †=i	nterp	olate	ed/extrapo	lated stati	on		<del></del>	
MD [ft]	Inclination [°]		TVD [ft]	Vert Sect [ft]			Grid East [US ft]	Grid North [US ft]	Latitude	Longitude	DLS [°/100ft]	Comments
0.00†	0.000	260.453	0.00	0.00	0.00	0.00	653557.45	495857.89	32°21'44.093"N	103°50'09.657"W	0.00	
22.00	0.000	260.453	22.00	0.00	0.00	0.00	653557.45	495857.89	32°21'44.093"N	103°50'09.657"W	0.00	Tie On
122.00†	0.000	260.453	122.00	0.00	0.00	0.00	653557.45	495857.89	32°21'44.093"N	103°50'09.657"W	0.00	
222.00†	0.000	260.453	222.00	0.00	0.00	0.00	653557.45	495857.89	32°21'44.093"N	103°50'09.657"W	0.00	
322.00†	£⊈**0.000	260:453	* 322:00	·*************************************	0.00	0.00	653557.45	495857.89	\$32°21'44.093"N	2103°50'09.657"W	*0.00	
368.00†	0.000	260.453	368.00	0.00	0.00	0.00	653557.45	495857.89	32°21'44.093"N	103°50'09.657"W	0.00	T/Rustler
422.00†	0.000	260.453	422.00	0.00	0.00	0.00	653557.45	495857.89	32°21'44.093"N	103°50'09.657"W	0.00	
522.00†	0.000	260.453	522.00	0.00		0.00	653557.45	495857.89	32°21'44.093"N	103°50'09.657"W	0.00	
622.00†	0.000	260.453	622.00	0.00		0.00	653557.45	495857.89	32°21'44.093"N	103°50'09.657"W	0.00	
722.00†	0.000	260.453	722.00	*,0.00	*0.00	0.00	, 653557:45	495857.89	32°21'44'.093"N	103°50'09.657."W	~~0.00	A STATE OF
761.00†	0.000	260.453	761.00	0.00	0.00	0.00	653557.45	495857.89	32°21'44.093"N	103°50'09.657"W	0.00	T/Salt
822.00†	0.000	260.453	822.00	0.00		0.00	653557.45	495857.89	32°21'44.093"N	103°50'09.657"W	0.00	
922.00†	0.000	260.453	922.00	0.00	0.00	-	653557.45	495857.89	32°21'44.093"N	103°50'09.657"W	0.00	
1022.00†	0.000	···	1022.00	0.00		0.00	653557.45	495857.89	32°21'44.093"N	103°50'09.657"W	0.00	
1122.00†	The state of the state of the state of	260.453	4)	0.00	7	0.00			32°21¦44.093"N	103°50'09 657".W	0.00	
1222.00†		260.453		0.00	0.00		653557.45	495857.89	32°21'44.093"N	103°50'09.657"W	0.00	
1322.00†	0.000		1322.00	0.00	0.00		653557.45	495857.89	32°21'44.093"N	103°50'09.657"W	0.00	
1422.00†	0.000	260.453		0.00	0.00		653557.45	495857.89	32°21'44.093"N	103°50'09.657"W	0.00	
1522.00†	0.000	260.453		0.00		0.00	653557.45	495857.89	32°21'44.093"N	103°50'09.657"W	0.00	
1622.00†				¥, ¥0.00			653557.45		32°21'44:093"N	The state of the s	<i>\$</i> ,0:00	
1722.00†	0.000		1722.00	0.00	0.00	-	653557.45	495857.89	32°21'44.093"N	103°50'09.657"W	0.00	
1822.00†	0.000			0.00	0.00		653557.45	495857.89	32°21'44.093"N	103°50'09.657"W	0.00	
1922.00†	0.000			0.00	0.00		653557.45		32°21'44.093"N	103°50'09.657"W	0.00	
2022.00†	0.000		2022.00	0.00		0.00	653557.45	495857.89	32°21'44.093"N	103°50'09.657"W	0.00	
Charles and the Control of the Contr	0.000	The state of the s		0.00			653557.45	The second secon	7:32°21;44:093"N	103°50'09.657"W	% 0:00°	
2222.00†	.,	260.453	_,	0.00	0.00		653557.45	495857.89	32°21'44.093"N	103°50'09.657"W	0.00	
2322.00†	0.000			0.00	0.00		653557.45	495857.89	32°21'44.093"N	103°50'09.657"W	0.00	
2422.00†	0.000		***************************************	0.00		0.00	653557.45	495857.89	32°21'44.093"N	103°50'09.657"W	0.00	
2522.00†	0.000	260.453		0.00		0.00	653557.45	495857.89	32°21'44.093"N	103°50'09.657"W	0.00	
2622.00†			2622:00					495857:89				
2722.00†		260.453		0.00	0.00		653557.45	495857.89	32°21'44.093"N	103°50'09.657"W	0.00	
2822.00†	0.000	260.453		0.00		0.00	653557.45	495857.89	32°21'44.093"N	103°50'09.657"W	0.00	
2922.00†	0.000			0.00	0.00		653557.45	495857.89	32°21'44.093"N	103°50'09.657"W	0.00	
3022.00†	0.000			0.00	0.00		653557.45	495857.89	32°21'44.093"N	103°50'09.657"W	0.00	Company of the
3122.00†	The state of the s		3122.00	2707 1995			* 653557.45	A	Contract Annual Contract Contr		0.00	
3222.00†		260.453		0.00	0.00		653557.45	495857.89	32°21'44.093"N	103°50'09.657"W	0.00	
3322.00†	0.000			0.00		0.00	653557.45	495857.89	32°21'44.093"N	103°50'09.657"W	0.00	<u> </u>
3422.00†		260.453		0.00	0.00		653557.45	495857.89	32°21'44.093"N	103°50'09.657"W	0.00	<del> </del>
3522.00†		260.453		0.00				495857.89	32°21'44.093"N	103°50'09.657"W	0.00	272 C 477 F 18 18 7
3568.00†			73568.00					-		103%50'09.657#W		B/Salt : Start
3622.00†			3622.00	0.00	0.00				32°21'44.093"N	103°50'09.657"W	0.00	
3722.00†			3722.00	0.00	0.00		653557.45	·	32°21'44.093"N	-	0.00	
3812.00†			3812.00	0.00	0.00		653557.45	495857.89	32°21'44.093"N			T/Lamar Lime
3822.00†			3822.00	0.00	0.00		653557.45	495857.89	32°21'44.093"N	103°50'09.657"W	0.00	
3848.00+	0:000	260:453	3848.00	0.00	0.00	0.00	653557/45	495857,89	/32°21'44.093"N	3 103%50/09.657."W	0.00	T/Rāmsey 😤 🦠



## Planned Wellpath Report Prelim\_4 Page 3 of 7



REBER	RENCE WELLPATH IDENTIFICAT	TION	a managa at a separata pagasa ana, ang anaga ang ang ang ang ang ang ang a	r
Operator	BOPCO, L.P.	Slot	JRU No.138H SHL	
Area	Eddy County, NM	Well	JRU No.138H	
Field	JRU NAD27	Wellbore	JRU No.138H PWB	
Facility	(JRU) No.138 & No.139			

WELLI	PATH D	ATA (2	09 stati	ons) †	= inte	rpolate	d/extrapo	lated stat	ion	5		
MD [ft]	Inclination [°]	Azimuth [°]	TVD [ft]	Vert Sect [ft]	North [ft]	East [ft]	Grid East [US ft]	Grid North {US ft}	Latitude	Longitude	DLS [°/100ft]	Comments
3922.00†	0.000	260.453	3922.00	0.00	0.00	0.00	653557.45	495857.89	32°21'44.093"N	103°50'09.657"W	0.00	
4022.00†	0.000	260.453	4022.00	0.00	0.00	0.00	653557.45	495857.89	32°21'44.093"N	103°50'09.657"W	0.00	
4122.00†	0.000	260.453	4122.00	0.00	0.00	0.00	653557.45	495857.89	32°21'44.093"N	103°50'09.657"W	0.00	
4222.00†	0.000	260.453	4222.00	0.00	0.00					103°50'09.657"W	0.00	
4322.00†	0.000	260.453	4322.00	0.00	0.00	0.00	653557.45	495857.89	32°21'44.093"N	103°50'09.657"W	0.00	
4422.00†	0.000	260.453	4422.00	0.00	0.00	0.00	653557.45	495857.89	32°21'44.093"N	103°50'09.657"W	0.00	
4522.00†	0.000	260.453	4522.00	0.00	0.00	. 0.00	653557.45	495857.89	32°21'44.093"N	103°50'09.657"W	0.00	
4622.00†		260.453		0.00	0.00					103°50'09.657"W	0.00	
4722.00†	0.000	260.453	4722.00	0.00	0.00					103°50'09.657"W	0.00	
4822.00†	0.000	260.453	4822.00	0.00	0.00					103°50'09.657"W	0.00	man illustration of the contra
4922.00†		260.453		0.00	0.00		PROPERTY NAMED OF THE PROPERTY OF		32°21'44.093"N	103°50'09.657"W	0.00	
5022.00†		260.453		0.00	0.00					103°50'09.657"W	0.00	
5122.00†		260.453		0.00	0.00					103°50'09.657"W	0.00	
5222.00†		260.453		0.00	0.00				32°21'44.093"N	103°50'09.657"W	0.00	
5322.00†	0.000	260.453	5322.00	0.00	0.00	0.00	653557.45	495857.89	32°21'44.093"N	103°50'09'657"W	0:00	
5422.00†	0.000	260,453	5422.00	0.00	0.00	0.00	653557.45	495857.89	32°21'44.093"N	103°50'09.657"W	0.00	
5522.00†			5522.00	0.00	0.00	0.00	653557.45	495857.89	32°21'44.093"N	103°50'09.657"W	0.00	
5622.00†	0.000	260.453	5622.00	0.00	0.00					103°50'09.657"W	0.00	
5722.00†	0.000	260.453	5722.00	0.00	0.00	0.00	653557.45	495857.89	32°21'44.093"N	103°50'09.657"W	0.00	
5822.00†	0.000	260:453	5822:00	0.00	0.00					103°50'09.657"W	0.00	
5922.00†	0.000	260.453	5922.00	0.00	0.00					103°50'09.657"W	0.00	
6002.00†	0.000	260.453	6002.00	0.00	0.00	0.00	653557.45	495857.89	32°21'44.093"N	103°50'09.657"W	0.00	Lower Cherry Canyon
6022.00†	0.000	260.453	6022.00	0.00	0.00	0.00	653557.45	495857.89	32°21'44.093"N	103°50'09.657"W	0.00	
6122.00†	0.000	260.453	6122.00	0.00	0.00	0.00	653557.45	495857.89	32°21'44.093"N	103°50'09.657"W	0.00	
6222.00†	0.000	260:453	6222.00	0:00	0:00		653557.45	495857.89	32°21'44.093;"N	103°50'09:657"W	0.00	in in the man and
6322.00†	0.000	260.453	6322.00	0.00	0.00					103°50'09.657"W	0.00	
6422.00†	0.000	260.453	6422.00	0.00	0.00					103°50'09.657"W	0.00	
6522.00†	0.000	260.453	6522.00	0.00	0.00	0.00	653557.45	495857.89	32°21'44.093"N	103°50'09.657"W	0.00	
6622.00†	0.000	260.453	6622.00	.000	0.00		····		32°21'44.093"N	103°50'09.657"W	0.00	
6722.00	0.000	260.453	6722:00	0.00	0.00	€ 0.00	653557:45	495857.89	32°21'44.093"N	103°50'09.657"W	0.00	
6822.00†		260.453		0.00	0.00					103°50'09.657"W	0.00	
6867.00		260.453		0.00	0.00					103°50'09.657"W		Est KOP
6922.00†		260.453		3.14	-0.52					103°50'09.693"W	12.00	
7022.00†		260.453		24.72	-4.14				32°21'44.053"N	103°50'09.944"W	12.00	
7122.00†	A	777	7110.05	65.90	,-11.03				32°21'43.987"N		12.00	
7222.00†		260.453		124.89			·		32°21'43.892"N	103°50'11.107"W	12.00	
7322.00†		260.453		199.10					32°21'43.772"N	103°50'11.968"W	12.00	<u> </u>
7395.50†			7294.00	261.48		<del>,</del>		·		103°50'12.692"W	12.00	LBC Lo U
7422.00†			7305.20							103°50'12.969"W	12.00	
7522.00†	78.600	260:453	7335.05	379.70						103°50'14.064"W	: 12.00	Anna Carlotte
7617.12			7344.46							103°50'15.152"W	12.00	
7622.00†	90.014	260.453	7344.46	478.19	-80.02	-475.78	653081.70	495777.87	32°21'43.323"N	103°50'15.208"W	0.00	
7722.00†	90.014	260.453	7344.44	577.30	-96.61	-574.40	652983.09	495761.29	32°21'43.163"N	103°50'16.358"W	0.00	
7822.00†	90.014	260.453	7344.41	676.42	-113.20	-673.01	652884.48	495744.70	32°21'43.004"N	103°50'17.509"W	0.00	
7922.001	90.014	260.453	7344.39	775.53	-129.78	-771:63	652785:87	495728.12	32°21'42.844"N	103º50'18.659"W	0.00	of 2 2 1 1 2 - 1, 6 1



# Planned Wellpath Report Prelim\_4 Page 4 of 7



REPER	IENCE WELLPATE IDENTIFICATION		
Operator	BOPCO, L.P.	Slot	JRU No.138H SHL
Area	Eddy County, NM	Well	JRU No.138H
Field	JRU NAD27	Wellbore	JRU No.138H PWB
Facility	(JRU) No.138 & No.139		

WELLP	ATH DA	TA (2	09 statio	ons) †	= inter	polated	/extrapol	ated static	on :		, , , , , , , , , , , , , , , , , , ,	
MD [ft]	Inclination [°]	Azimuth [°]	TVD [ft]	Vert Sect [ft]	North [ft]	East [ft]	Grid East [US ft]	Grid North [US ft]	Latitude	Longitude	DLS [°/100ft]	Comments
8022.00†	90.014	260.453	7344.36	874.64						103°50'19.810"W	0.00	
8122.00†	90.014	260.453	7344.34	973.76	-162.95	-968.86	652588.66	495694.95	32°21'42.525"N	103°50'20.961"W	0.00	
8222.00†	90.014	260.453	7344.32	1072.87	-179.54	-1067.47	652490.05	495678.36	32°21'42.365"N	103°50'22.111"W	0.00	
8322.00†	90.014	260.453	7344.29	1171.99	-196.13	-1166.09	652391.44	495661.78	32°21'42.206"N	103°50'23.262"W	0.00	
8422:00	90.014	260:453	7344.27	1271:10	-212.71	1264.70	652292.83	495645.19	32°21-42.046"N	103°50'24'.412",W	_0.00	
8522.00†	90.014	260.453	7344.24	1370.21	-229.30	-1363.32	652194.22	495628.61	32°21'41.886"N	103°50'25.563"W	0.00	
8622.00†	90.014	260.453	7344.22	1469.33	-245.88	-1461.93	652095.62	495612.02	32°21'41.727"N	103°50'26.713"W	0.00	
8722.00†	90.014	260.453	7344.19	1568.44	-262.47	-1560.55	651997.01	495595.44	32°21'41.567"N	103°50'27.864"W	0.00	
8822.00†	90.014	260.453	7344.17	1667.55	-279.06	-1659.16	651898.40	495578.85	32°21'41.407"N	103°50'29.014"W	0.00	
8922.001	90.014	260.453	7344.14	1766.67	-295.64	-1757.78	651799.79	495562.27	32°21'41':248"N	103°50'30.165 <u>"</u> W	0.00	
9022.00†	90.014	260.453	7344.12	1865.78	-312.23	-1856.39	651701.18	495545.68	32°21'41.088"N	103°50'31.315"W	0.00	
9122.00†	90.014	260.453	7344.09	1964.90	-328.82	-1955.01	651602.57	495529.10	32°21'40.929"N	103°50'32.466"W	0.00	1
9222.00†	90.014	260.453	7344.07	2064.01	-345.40	-2053.62	651503.97	495512.51	32°21'40.769"N	103°50'33.616"W	0.00	
9322.00†	90.014	260.453	7344.04	2163.12	-361.99	-2152.24	651405.36	495495.93	32°21'40.609"N	103°50'34.767"W	0.00	
9422.00†	390.014	260:453	7344.02	2262:24	-378:57	-2250.85	651306.75	495479.34	32°21'40.450"N	103°50'35.917,"W	0.00	
9498.82	90.014	260.453	7344.00 <sup>1</sup>	2338.37	-391.32	-2326.60	651231.00	495466.60	32°21'40.327"N	103°50'36.801"W	0.00	Target #1 / 7" Casing
9522.00†			لاستستستا		5 Br. 6 C. 1					103°50'37.068"W	2.00	
9622.00†			7343.91							103°50'38.223"W	2.00	
9722.00†		·							***	103°50'39.383"W	2.00	
9822:001										103°50'40.546"W		n Suintal de la
9922.00†										103°50'41.711"W	2.00	A
9981.75				<del>, , , , , , , , , , , , , , , , , , , </del>		<del></del>				103°50'42.408"W	<u></u>	Build
10022.00†										103°50'42.877"W	0.00	Dund
10122.00†										103°50'44.043"W	0.00	
										103°50'45-208"W		
10322.00	770,000	7257						/	The state of the s	103°50'46.374"W	0.00	had attended
10422.00†	-{			<del>}</del>						103°50'47.540"W	0.00	
10522.00			L				<del></del>			103°50'48.706"W	0.00	<del></del>
10622.00†								·		103°50'49.871"W	0.00	
										103,50'51:037"W		Lo 3/4/19-20#03
10822.00†										103°50'52.203"W	0.00	Fried in State of the American
10922.00†										103°50'53.369"W	0.00	
1022.00†										103°50'54.534"W	0.00	
1122.00†										103°50'55.700"W	0.00	
1122:00										103°50'56.866"W		
11322.00†										103°50'58.032"W	0.00	A STATE OF THE PARTY OF THE PAR
11422.00†			7337.08							103°50'59.197"W	0.00	
1522.00†	J									103°51'00.363"W	0.00	
1622.00†										103°51'01.529"W	-	
										103°51'02.695"W	0.00	
1722.00     1822.00										103°51,024695°Wa 103°51'03.860"W		War Cart Day
										103°51'05.026"W	0.00	
1922.00†											0.00	
2022.00†										103°51'06.192"W	0.00	
12122.00†	90.234	270.109	7334.22	4939.03	-420.94	-4947.36	048010.22	495430.98	32°21'40.092"N	103°51'07.358"W	0.00	AND CONTRACTOR OF THE
12222:00	90.234	270:109	1000.61	2028:394	-420./3	-2U4/:26	0483 (0:23)	493431917	32°21:40:098%N	103°51¦08°524":W	0.00	PARENTE PARENT



# Planned Wellpath Report Prelim\_4 Page 5 of 7



REFER	ENCE WELLPATH IDENTIFICATION	No seem of the party of	
Operator	BOPCO, L.P.	Slot	JRU No.138H SHL
Area	Eddy County, NM	Well	JRU No.138H
Field	JRU NAD27	Wellbore	JRU No.138H PWB
Facility	(JRU) No.138 & No.139		

WELLPA	TH DA	ΓA (209	station	s) †=	interpo	lated/ext	rapolated	station	to a body of the models of the section	h		<del>*************************************</del>
MD [ft]	Inclination [°]	Azimuth	TVD [ft]	Vert Sect		East [ft]	Grid East [US ft]	Grid North [US ft]	Latitude	Longitude	DLS [°/100ft]	Comments
12322.00†		270.109		5158.93	-426.56		648410.24	495431.36	32°21'40.105"N	103°51'09.689"W	0.00	
12422.00†				5258.86	-426.37	-5247.55		495431.55	32°21'40.111"N	103°51'10.855"W	0.00	
12522.00†			7332.59	Caramanan and a second	-426.18			495431.74	32°21'40.117"N	103°51'12.021"W	0.00	
12622.00†		270.109		5458.74	-425.99	-5447.55	648110.26	495431.93	32°21'40.124"N	103°51'13.187"W	0.00	
412722.00†		270.109	1	5558.68				495432:12	32°21'40.130"N		0.00	
12822.00†		270.109	,		-425.61	-5647.55	647910.27	495432.31	32°21'40.136"N	103°51'15.518"W	0.00	<u> </u>
12922.00†		270.109	·}	5758.55	-425.42	-5747.55	647810.28	495432.50	32°21'40.143"N	103°51'16.684"W	0.00	
13022.00†			7330.55		-425.23	-5847.55		495432.69	32°21'40.149"N	103°51'17.850"W	0.00	
13122.00†	90.234	270.109	7330.14	5958.42	-425.04	-5947.55		495432.88	32°21'40.155"N	103°51'19.015"W	0.00	
13222.00†		270:109		<del></del>	L	-6047.55		495433.07		: 103°51'20.181;"W	0.00	6 3 4
13322.00†	M. acoccount W	270.109		6158.30	-424.66	-6147.54	647410.31	495433.26	32°21'40.168"N	103°51'21.347"W	0.00	الشمعاشم مدا
13422.00†		270.109		6258.23	-424.47	-6247.54	647310.32	495433.45	32°21'40.174"N	103°51'22.513"W	0.00	
13522.00†		270.109			-424.28		647210.33	495433.64	32°21'40.180"N	103°51'23.678"W	0.00	
13622.00†		270.109			-424.09	-6447.54	647110.33	495433.83	32°21'40.187"N	103°51'24.844"W	0.00	
13722.00†			7327.70	<del></del>	-423.90	<del></del>		495434:02	32°21'40:193"N	103°51'26.010"W	0.00	
13822.00†	90.234		7327.29	6657.98	-423.71	-6647.54	646910.35	495434.21	32°21'40.199"N	103°51'27.176"W	0.00	ti tua din mai
13922.00†	90.234		·	· <del></del>	-423.52	-6747.54	646810.36	495434.40	32°21'40.206"N	103°51'28.342"W	0.00	
14022.00†	90.234				-423.33	-6847.54	646710.36	495434.59	32°21'40.212"N	103°51'29.507"W	0.00	
14122.00†	90.234				-423.14	-6947.54	646610.37	495434.78	32°21'40.218"N	103°51'30.673"W	0.00	
14222.00†	90.234	270:109	<u> </u>	7057.73	422:95	-7047.54	646510.38	Trip-Street, Street, S	32°21'40.224"N		0.00	
14322.00†	7,111,111,111	The second second	7325.25	7157.67	-422.76	AND THE PARTY OF T	646410.39	495435.16	32°21'40.231"N	103°51'33.005"W	0.00	<u> </u>
14422.00†			7324.84		-422.57	-7247.53	646310.40	495435.35	32°21'40.237"N	103°51'34.170"W	0.00	
14522.00†			7324.43		-422.38	-7347.53	646210.40	495435.54	32°21'40.243"N	103°51'35.336"W	0.00	
14622.00†	90.234	270.109	7324.03	7457.48	-422.19	-7447.53	646110.41	495435.73	32°21'40.249"N	103°51'36.502"W	0.00	
14722.00	90:234	270.109	7323:62	7557.41			646010.42	495435.92	32°21'40.256"N	103°51/37.668"W	0.00	0.0
14822.00†	The state of the s	10.00	7323.21	7657.35	-421.81	-7647.53	645910.43	495436.11	32°21'40.262"N	103°51'38.833"W	0.00	
14922.00†		270.109		7757.29	-421.62	-7747.53	645810.43	495436.30	32°21'40.268"N	103°51'39.999"W	0.00	
15022.00†	90.234	270.109	7322.39	7857.22	-421.43	-7847.53	645710.44	495436.49	32°21'40.274"N	103°51'41.165"W	0.00	
15122.00†	90.234	270.109	7321.99	7957.16	-421.24	-7947.53	645610.45	495436.68	32°21'40.281"N	103°51'42.331"W	0.00	
15222.00†	90:234	270.109	7321:58	8057.10	-421.05	-8047.53°	645510.46	495436:87	.32°21'40.287"N	103°51,43.496"W	0.00	
15322.00†	90.234	270.109	7321.17	8157.03	-420.86	-8147.52	645410.46	495437.06	32°21'40.293"N	103°51'44.662"W	0.00	
15422.00†	90.234	270.109	7320.76	8256.97	-420.67	-8247.52	645310.47	495437.25	32°21'40.299"N	103°51'45.828"W	0.00	
15522.00†	90.234	270.109	7320.35	8356.91	-420.48	-8347.52	645210.48	495437.44	32°21'40.306"N	103°51'46.994"W	0.00	
15622.00†	90.234	270.109	7319.95	8456.84	-420.29	-8447.52	645110.49	495437.63	32°21'40.312"N	103°51'48.160"W	0.00	
15722.001	90.234	270.109	7319.54	8556.78	-420.10	-8547.52	645010.49	495437.82	32°21'40.318"N	- 103°51,49.325"W	0.00	, ,
15822.00†	90.234	270.109	7319.13	8656.72	-419.91	-8647.52	644910.50	495438.01	32°21'40.324"N	103°51'50.491"W	0:00	
15922.00†	90.234	270.109	7318.72	8756.66	-419.72	-8747.52	644810.51	495438.20	32°21'40.330"N	103°51'51.657"W	0.00	
16022.00†	90.234	270.109	7318.31	8856.59	-419.53	-8847.52	644710.52	495438.39	32°21'40.337"N	103°51'52.823"W	0.00	
16122.00†							644610.52	495438.58	32°21'40.343"N		0.00	
16222.001	90.234	270:109	7317.50	9056:47					32°21;40:349"N	103°51'55:154"W	0.00	2.4
16322.00†				9156.40		-9147.51	644410.54	495438.96	32°21'40.355"N	103°51'56.320"W	0.00	
16422.00†	90.234	270.109	7316 68	9256.34	-418.77	-9247.51	644310.55	495439.15	32°21'40.361"N	103°51'57.486"W	0.00	
16522.00†	90.234	270.109	7316.28	9356.28	-418.58	-9347.51	644210.55	495439.34	32°21'40.368"N	103°51'58.651"W	0.00	
16622.00†	90.234	270.109	7315.87	9456.21	-418.39	-9447.51	644110.56	495439.53	32°21'40.374"N	103°51'59.817"W	0.00	
16702 004	90.234	270:109	7315:46	9556.15	-418.20	-9547.51				103°52'00.983"W	0.00	



## Planned Wellpath Report Prelim\_4 Page 6 of 7



REFER	ENCE WELLPATH IDENTIFICATION		
Operator	BOPCO, L.P.	Slot	JRU No.138H SHL
Area	Eddy County, NM	Well	JRU No.138H
Field	JRU NAD27	Wellbore	JRU No.138H PWB
Facility	(JRU) No.138 & No.139		

WELLP	ATH DA	TA (20	9 statio	ns) †=	interp	olated/ex	trapolate	d station	•	2000 to the second of the State	Principal State No.	
	Inclination		TVD	Vert Sect	North	East		Grid North	Latitude	Longitude		Comments
[ft]	[°]	[°]	[ft]	[ft]	[ft]	[ft]	[US ft]	[US ft]		102052102 1401117	[°/100ft]	
16822.00†		270.109		<u> </u>	-418.01		643910.58		32°21'40.386"N	103°52'02.149"W	0.00	
16922.00†		270.109			-417.82				32°21'40.392"N	103°52'03.314"W	0.00	·
17022.00†		270.109			-417.63			495440.29	32°21'40.399"N	103°52'04.480"W	0.00	
17122.00†		270.109			-417.44				32°21'40.405"N	103°52'05.646"W	0.00	
17222.00†				10055.83	<u>-417:25</u>			The state of the s		-103°52'06:812"W	.0.00	
17322.00†	90.234	270.109	7313.01	10155.77	-417.06	-10147.50	643410.62	495440.86	32°21'40.417"N	103°52'07.978"W	0.00	
17422.00†	90.234	270.109	7312.60	10255.71	-416.87	-10247.50	643310.62	495441.05	32°21'40.423"N	103°52'09.143"W	0.00	
17522.00†	90.234	270.109	7312.20	10355.65	-416.68	-10347.50	643210.63	495441.24	32°21'40.429"N	103°52'10.309"W	0.00	
17622.00†	90.234	270.109	7311.79	10455.58	-416.49	-10447.50	643110.64	495441.43	32°21'40.436"N	103°52'11.475"W	0.00	
17722.00+	90.234	270:109	7311.38	10555:52	416.30	-10547.50	643010.65	495441.62	32°21'40.442"N	103°52'12.641."W	0.00	and the state of
17822.00†	90.234	270.109	7310.97	10655.46	-416.11	-10647.50	642910.65	495441.81	32°21'40.448"N	103°52'13.806"W	0.00	
17922.00†	90.234	270.109	7310.56	10755 39	-415.92	-10747.50	642810.66	495442.00	32°21'40.454"N	103°52'14.972"W	0.00	
18022.00†	90.234	270.109	7310.16	10855.33	-415.73	-10847.50	642710.67	495442.19	32°21'40.460"N	103°52'16.138"W	0.00	
18122.00†	90.234	270.109	7309.75	10955.27	-415.54	-10947.50	642610.68	495442.38	32°21'40.466"N	103°52'17.304"W	0.00	
18222.00†	90.234	270.109	7309:34	1,1055.20	415.35	-11047:49	642510.68	495442.57	32°21'40.473"N	3103°52'18:469"W	3: 0.00	
18322.00†	90.234	270.109	7308.93	11155.14	-415.16	-11147.49	642410.69	495442.76	32°21'40.479"N	103°52'19.635"W	0.00	
18422.00†	90.234	270.109	7308.52	11255.08	-414.97	-11247.49	642310.70	495442.95	32°21'40.485"N	103°52'20.801"W	0.00	
18522.00†	90.234	270.109	7308.12	11355.01	-414.78	-11347.49·	642210.71	495443.14	32°21'40.491"N	103°52'21.967"W	0.00	·
18622.00†	90.234	270.109	7307.71	11454.95	-414.59	-11447.49	642110.71	495443.33	32°21'40.497"N	103°52'23.133"W	0.00	/
18722.00†	90.234	270.109	7307:30	11554.89	414.40	-11547.49	642010!72	495443.52	32°21'40.503"N	103°52'24'298"W	0:00	
18822.00†	90.234	270.109	7306.89	11654.82	-414.21	-11647.49	641910.73	495443.71	32°21'40.509"N	103°52'25.464"W	0.00	
18922.00†	90.234	270.109	7306.49	11754.76	-414.02	-11747.49	641810.74	495443.90	32°21'40.516"N	103°52'26.630"W	0.00	
19022.00†	90.234	270.109	7306.08	11854.70	-413.83	-11847.49	641710.75	495444.09	32°21'40.522"N	103°52'27.796"W	0.00	
19122.00†	90.234	270.109	7305.67	11954.64	-413.64	-11947.49	641610.75	495444.28	32°21'40.528"N	103°52'28.961"W	0.00	
19222:00†	90.234	270:109	7305:26	12054.57	-413.45	-12047.48	6415/10:76	495444:47	32°21'40!534!'N	103252130:1271W	÷0.00	1.4
19322.00†	Contract Property of	DISTRICT REPORTS	THE PERSON NAMED IN COLUMN 1		THE PERSON NAMED IN COLUMN 2 I	-12147.48	The state of the s	The state of the s	32°21'40.540"N	103°52'31.293"W	0.00	
19422.00†	90.234	270.109	7304.45	12254.45	-413.07	-12247.48	641310.78	495444.85	32°21'40.546"N	103°52'32.459"W	0.00	
19522.00†	90.234	270.109	7304.04	12354.38	-412.88	-12347.48	641210.78	495445.04	32°21'40.552"N	103°52'33.624"W	0.00	
19531.32	90.234	270.109	7304.00 <sup>2</sup>	12363.70	-412.86	-12356.80	641201.46	495445.05	32°21'40.553"N	103°52'33.733"W	0.00	No.138H PBHL

HOLE & CASING	HOLE & CASING SECTIONS - Ref Wellbore: JRU No.138H PWB Ref Wellpath: Prelim_4												
String/Diameter	Start MD [ft]	End MD [ft]	Interval [ft]	Start TVD . [ft]	End TVD [ft]	Start N/S [ft]	Start E/W [ft]	End N/S . [ft]	End E/W [ft]				
8.75in Open Hole	22.00	9499.00	9477.00	22.00	7344.00	0.00	0.00	-391.35	-2326.78				
7in Casing	22.00	9499.00	9477.00	22.00	7344.00	0.00	0.00	-391.35	-2326.78				
6.125in Open Hole	9499.00	19531.32	10032.32	7,344.00	7304.00	-391.35	-2326.78	-412.86	-12356.80				



## Planned Wellpath Report Prelim\_4 Page 7 of 7




RDDDR	ENCE WELLPATH IDENTIFICATION	Walter Toler or perform Jones P. S.	
Operator	BOPCO, L.P.	Slot	JRU No.138H SHL
Area	Eddy County, NM	Well	JRU No.138H
Field	JRU NAD27	Wellbore	JRU No.138H PWB
Facility	(JRU) No.138 & No.139		

TARGETS		. ,				·····			. ,
Name	MD [ft]	TVD [ft]	North [ft]	East [ft]	Grid East .[US ft]	Grid North [US ft]	Latitude	Longitude	Shape
2) No.138H PBHL	19531.32	7304.00	-412.86	-12356.80	641201.46	495445.05	32°21'40,553"N	103°52'33.733"W	point
1) No.138H Target #1	9498.82	7.344,00	-391.32	-2326.60	651231.00	495466.60	.32°21'40.327"N	103°50'36.801"W	point

S	SURVEY PROGRAM - Ref Wellbore: JRU No.138H PWB Ref Wellpath: Prelim_4							
	Start MD	End MD	Positional Uncertainty Model	Log Name/Comment	Wellbore			
L	[ft]	[ft]						
	22.00	19531.32	NaviTrak (Standard)		JRU No.138H PWB			

## BOPCO, L. P. 13 5/8" X 5-M WP BOPE WITH 5-M WP ANNULAR




## THE FOLLOWING CONSTITUTE MINIMUM BLOWOUT PREVENTER REQUIREMENTS

- A. One double gate Blowout preventer with lower pipe rams and upper blind rams, all hydraulically controlled.
- B Opening on preventers between rams to be flanged, studded or clamped and at least two inches in diameter.
- C. All connections from operating manifold to preventers to be all steel hose or tube a mininum of one inch in diameter.
- D. The available closing pressure shall be at least 15% in excess of that required with suffficient volume to operate (close, open, and re-close) the preventers.
- E. All connections to and from preventers to have a pressure rating equivalent to that of the BOPs
- F Manual controls to be installed before drilling cement plug.
- G. Valve to control flow through drill pipe to be located on rig floor.
- H Chokes must be adjustable. Choke spool may be used between rams

## **DIAGRAM 1**

mud/gin Separator
or
to steel MUD TANKS

BLEED LINE TO STEEL 1/2 PIT LOCATED 100' FROM WELL



## HYDROGEN SULFIDE (H2S) CONTINGENCY PLAN

## Assumed 100 ppm ROE = 3000' 100 ppm H<sub>2</sub>S concentration shall trigger activation of this plan.

## **Emergency Procedures**

In the event of a release of gas containing H2S, the first responder(s) must

- Isolate the area and prevent entry by other persons into the 100 ppm ROE.
- Evacuate any public places encompassed by the 100 ppm ROE.
- Be equipped with H₂S monitors and air packs in order to control the release.
- Use the "buddy system" to ensure no injuries occur during the response
- Take precautions to avoid personal injury during this operation.
- Contact operator and/or local officials to aid in operation. See list of phone numbers attached.
- Have received training in the
  - Detection of H₂S, and
  - Measures for protection against the gas,
  - Equipment used for protection and emergency response.

## **Ignition of Gas source**

Should control of the well be considered lost and ignition considered, take care to protect against exposure to Sulfur Dioxide (SO<sub>2</sub>). Intentional ignition must be coordinated with the NMOCD and local officials. Additionally the NM State Police may become involved. NM State Police shall be the Incident Command on scene of any major release. Take care to protect downwind whenever this is an ignition of the gas.

## Characteristics of H<sub>2</sub>S and SO<sub>2</sub>

Common Name	Chemical Formula	Specific Gravity	Threshold Limit	Hazardous Limit	Lethal Concentration
Hydrogen Sulfide	H <sub>2</sub> S	1.189 Air = 1	10 ppm	100 ppm/hr	600 ppm
Sulfur Dioxide	SO <sub>2</sub>	2.21 Air = 1	2 ppm	N/A	1000 ppm

## **Contacting Authorities**


BOPCO L.P. personnel must liaison with local and state agencies to ensure a proper response to a major release. Additionally, the OCD must be notified of the release as soon as possible but no later than 4 hours. Agencies will ask for information such as type and volume of release, wind direction, location of release, etc. Be prepared with all information available including directions to site. The following call list of essential and potential responders has been prepared for use during a release. (Operator Name)'s response must be in coordination with the State of New México's "Hazardous Materials Emergency Response Plan" (HMER).

## H<sub>2</sub>S CONTINGENCY PLAN EMERGENCY CONTACTS

## **BOPCO L.P. Midland Office**

432-683-2277

Key Personnel		•	
Name	Title	Cell Phon	e Number
Stephen Martinez	Drilling Supt.	432-5	56-0262
Buddy Jenkins		432-2	38-3295
Bill Dannels	Engineer	432-6	38-9463
Brian Hammit	Engineer	432-6	38-9460
Charles Warne	Engineer	432-8	94-1392
Ambulance		911	
State Police		575-7	46-2703
Fire Department		575-7	46-2701
<b>Local Emergency Plan</b>	nning Committee	575-7	46-2122
New Mexico Oil Conse	ervation Division	575-7	48-1283
Carlsbad		,	
Ambulance		911	
			85-3137
Sheriff's Office		575-8	87-7551
Fire Department	nning Committee	575-8	87-3798
Local Emergency Plan	ning Committee	575-8	87-6544
US Bureau of Land Ma	nagement	575-8	87-6544
New Mexico Emergend	cy Response Commission (Sa	nta Fe)	505-476-9600
24 Hour	<u> </u>		505-827-9126
New Mexico State Eme	ergency Operations Center		505 <b>-</b> 476-9635
National Emergency R	lesponse Center (Washington	, DC)	800-424-8802
Other			
Boots & Coots IWC		800-256-9688	or 281-931-8884
Cudd PressureContro		432-580-3544	or 432-570-5300
Halliburton		575-746-2757	
B. J. Services		575-746-3569	
•	24 <sup>th</sup> St. Lubbock, Texas		806-743-9911
Aerocare - R3, Box 49	· · · · · · · · · · · · · · · · · · ·		806-747-8923
	2301 Yale Blvd SE #D3, Albuq.		505-842-4433
S B Air Med Service -	2505 Clark Carr Loop SE, Albu	uq., NM	505-842-4949



## **BLM On-Site Notes**

The Location onsite was conducted on 09/06/2011 by Cecil. Watkins – BOPCO L.P, Randy-Rust-BLM, and Robert Gomez with Basin Survey. The James Ranch Unit 138H was approved with a surface location at 2,365' FSL & 1980' FWL, Sec 25, T22S-R30E.

## **MULTI-POINT SURFACE USE PLAN**

## NAME OF WELL: James Ranch Unit 138H

LEGAL DESCRIPTION - SURFACE: 2365' FSL, 1980' FWL, Section 25, T22S, R30E, Eddy County, NM. BHL: 1980' FSL, 330' FWL, Section 27, T22S, R30E, Eddy County, New Mexico.

## **POINT 1: EXISTING ROADS**

A) Proposed Well Site Location:

See Form C-102 (Survey Plat).

B) Existing Roads:

From the WHIPP Site, go north 1 mile to lease road. Turn onto lease road and travel southwesterly for 1.8 miles to lease road. On lease road go south 0.9 miles to lease road, on lease road go southwesterly for 0.3 miles to lease road. On lease road go north 0.1 miles to proposed location.

C) Existing Road Maintenance or Improvement Plan:

See the Well Pad Layout and Topo Map of the survey plat (Sheet 1 and 2 of plat package)

## **POINT 2: NEW PLANNED ACCESS ROUTE**

A) Route Location:

There will be no new lease road built for this location. (See the Well Pad Layout of the survey plat (Sheet 1 of plat package)

B) Width

14' wide

C) Maximum Grade

Grade to match existing topography or as per BLM requirements.

D) Turnout Ditches

As required by BLM stipulations

E) Culverts, Cattle Guards, and Surfacing Equipment

If required, culverts and cattle guards will be set per BLM Specs.

## **POINT 3: LOCATION OF EXISTING WELLS**

The following wells are located within a one-mile radius of the location site. See the One-Mile Radius Map (Sheet 5 of the plat package).

Existing wells	(37)
Water wells	(0)

## POINT 4: LOCATION OF EXISTING OR PROPOSED FACILITIES

- A) No existing production facilities operated by BOPCO, L.P. are located within one mile of the James Ranch Unit #138H.
- B) New Facilities in the Event of Production:

Total production (oil, water, gas) from the JRU 138H will be sent through an above ground 2-7/8" steel flowline to an existing BOPCO, L.P. production facility; JRU 19 battery, T22S, R30E, Sec 36. The flowline will be laid following an existing DCP gas line ROW in the southeasterly direction between the JRU 91 and JRU 31 wells and onto the JRU 19 battery. A rental generator will be set at the JRU 138H for the initial testing. A sundry describing the permanent power line will be submitted at a later date.

C) Rehabilitation of Disturbed Areas Unnecessary for Production:

Following the construction, those access areas required for continued production will be graded to provide drainage and minimize erosion. The areas unnecessary for use will be graded to blend in with the surrounding topography (see Point 10)

## POINT 5: LOCATION AND TYPE OF WATER SUPPLY

A) Location and Type of Water Supply

Fresh water will be hauled from Johnson Station 50 miles east of Carlsbad, New Mexico or other commercial facilities. Brine water will be hauled from commercial facilities.

B) Water Transportation System

Water hauling to the location will be over the existing and proposed roads.

## POINT 6: SOURCE OF CONSTRUCTION MATERIALS

A) Materials

On-site caliche will be used. If this is not sufficient, caliche will be hauled from a BLM approved pit.

B) Land Ownership

Federally Owned

C) Materials Foreign to the Site

No construction materials foreign to this area are anticipated for this drill site

D) Access Roads

See the Well Pad Layout and Aerial Map of the survey plat (Sheet 1 and 4 of plat package)

## POINT 7: METHODS FOR HANDLING WASTE MATERIAL

## A) Cuttings

Cuttings will be contained in the roll off bins and disposed at Controlled Recovery Inc. located in Lea county, NM.

## B) Drilling Fluids

Drilling fluids will be contained in the steel pits, frac tanks and disposed at licensed disposal sites.

## C) Produced Fluids

Water production will be contained in the steel pits.

Hydrocarbon fluid or other fluids that may be produced during testing will be retained in test tanks. Prior to cleanup operations, any hydrocarbon material in the reserve pit will be removed by skimming or burning as the situation would dictate.

## D) Sewage

Current laws and regulations pertaining to the disposal of human waste will be complied with.

## E) Garbage

Portable containers will be utilized for garbage disposal during the drilling of this well.

## F) Cleanup of Well Site

Upon release of the drilling rig, the surface of the drilling pad will be graded to accommodate a completion rig if electric log analysis indicate potential productive zones. Reasonable cleanup will be performed prior to the final restoration of the site.

### **POINT 8: ANCILLARY FACILITIES**

None required.

## **POINT 9: WELL SITE LAYOUT**

#### A) Rig Orientation and Layout

The "Rig Layout Schematic" (Sheet 6 of plat package) shows the dimensions of the well pad, closed loop system, and the location of major rig components. Only minor leveling of the well site will be required. No significant cuts or fills will be necessary.

## B) Locations of Access Road

See the Well Pad Layout, Topo Map, and Vicinity Map of the survey plat (Sheet 1, 2, and 3 of plat package).

## C) Lining of the Pits

No reserve pits - closed loop system.

## POINT 10: PLANS FOR RESTORATION OF THE SURFACE

## A) Reserve Pit Cleanup - Not applicable. Closed loop drilling fluid system will be used

The pits will be fenced immediately after construction and shall be maintained until they are backfilled. Previous to backfill operations, any hydrocarbon material on the pits' surfaces shall be removed. The fluids and solids contained in the pits shall be backfilled with soil excavated from the site and soil adjacent to the reserve pits. The restored surface of the pits shall be contoured to prevent impoundment of surface water flow. Water-bars will be constructed as needed to prevent excessive erosion. Topsoil, as available, shall be placed over the restored surface in a uniform layer. The area will be seeded according to the Bureau of Land Management stipulations during the appropriate season following restoration.

## B) Restoration Plans - Production Developed

Those areas not required for production will be graded to blend with the surrounding topography. Topsoil, as available, will be placed upon those areas and seeded. The portion of the site required for production will be graded to minimize erosion and provide access during inclement conditions. Following depletion and abandonment of the site, restoration procedures will be those that follow under Item C. See diagram 2 for the proposed interim reclamation plat

## C) Restoration Plans - No Production Developed

With no production developed, the entire surface disturbed by construction of the well site will be restored. The site will be contoured to blend with the surrounding topography and provide drainage of surface water. The topsoil, as available, shall be replaced in a uniform layer and seeded according to the Bureau of Land Management's stipulations.

## D) Rehabilitation's Timetable

Upon completion of drilling operations, the initial cleanup of the site will be performed as soon as weather and site conditions allow economic execution of the work.

#### POINT 11: OTHER INFORMATION

## A) On-Site

The Location onsite was conducted on 09/06/2011 by Cecil. Watkins – BOPCO L.P, Randy-Rust-BLM, and Robert Gomez with Basin Survey. The James Ranch Unit 138H was approved with a surface location at 2.365' FSL & 1980' FWL, Sec 25, T22S-R30E.

## B) Soil

Caliche and sand.

## C) Vegetation

Sparse, primarily grasses and mesquite with very little grass.

## POINT 11: OTHER INFORMATION - cont'd...

D) Surface Use

Primarily grazing.

E) Surface Water

There are no ponds, lakes, streams or rivers within several miles of the wellsite.

F) Water Wells

There are no water wells located within a 1 mile radius of the proposed location.

G) Residences and Buildings

None in the immediate vicinity.

H) Historical Sites

None observed.

I) Archeological Resources

No independent archeological survey has been done. This well location is located in the area covered by Memorandum of Agreement – Permian Basin. A Payment of \$1420.00 fee for this project is included in this application. Any location or construction conflicts will be resolved before construction begins. Please see diagram 3 for flowline route.

J) Surface Ownership

The well site is on federally owned land. There will be no new access roads required for this location.

- K) Well signs will be posted at the drilling site.
- L) Open Pits

No open pits will be used for drilling or production. Any open top tanks will be netted.

M) Terrian

Slightly rolling hills.

## POINT 12: OPERATOR'S FIELD REPRESENTATIVE

(Field personnel responsible for compliance with development plan for surface use).

DRILLING Stephen Martinez Box 2760 Midland, Texas 79702 (432) 683-2277 PRODUCTION
Dean Clemmer
3104 East Green Street
Carlsbad, New Mexico 88220
(575) 887-7329

Carlos Cruz Box 2760 Midland, Texas 79702 (432) 683-2277

SMM/jdb

## BOPCO, L. P. 6 DESTA DRIVE, SUITE 3700 (79705) P. O. BOX 2760 **MIDLAND, TEXAS 79702**

(432) 683-2277

FAX (432) 687-0329

September 15, 2011

Bureau of Land Management 620 E. Greene Carlsbad, New Mexico 88220 Attn: John Chopp

Dear Mr. Chopp,

BOPCO, L.P. respectfully requests exception to the Prairie Chicken timing restrictions for James Ranch Unit #138H located 2365' FSL, 1980' FWL, of Section 25, T22S, R30E, Eddy County, New Mexico.

Sincerely,

Stephen Martinez

**Division Drilling Superintendent** 

**JDB** 

# BOPCO, L.P.

P. O. Box 2760 Midland, Texas 79702

432-683-2277

FAX-432-687-0329

September 15, 2011

Bureau of Land Management Carlsbad Field Office 620 East Green Street Carlsbad, New Mexico 88220-6292

Attn: Mr. Don Peterson – Assistant Field Manager, Minerals

RE: APPLICATION FOR PERMIT TO DRILL

JAMES RANCH UNIT 138H

2365' FSL, 1980' FWL, SEC. 25, T22S, R30E, EDDY COUNTY, NM

Dear Mr. Peterson,

In reference to the above captioned well, I hereby certify that I, or persons under my direct supervision have inspected the proposed drill site and access route; that I am familiar with the conditions which currently exist; that the statements made in the attached eight point drilling plan and multi-use surface plan are, to the best of my knowledge, true and correct; and that the work associated with operations proposed herein will be performed by BOPCO, L.P. and it's contractors and subcontractors in conformity with this plan and the terms and conditions under which it is approved. This statement is subject to the provisions of 18 U.S.C. 1001 for the filing of a false statement.

If you have any questions regarding the accuracy of the plan provided herein, please do not hesitate to contact me at (432) 683-2277.

Stephen M. Martinez

**Division Drilling Superintendent** 

# PECOS DISTRICT CONDITIONS OF APPROVAL

OPERATOR'S NAME:	BOPCO, L.P.
LEASE NO.:	NM-02952B
WELL NAME & NO.:	James Ranch Unit #138H
SURFACE HOLE FOOTAGE:	2365' FSL & 1980' FWL
BOTTOM HOLE FOOTAGE	1980' FSL & 330' FWL Sec. 27, T. 22 S., R. 30 E.
LOCATION:	Section 25, T. 22 S., R. 30 E., NMPM
COUNTY:	Eddy County, New Mexico

# TABLE OF CONTENTS

Standard Conditions of Approval (COA) apply to this APD. If any deviations to these standards exist or special COAs are required, the section with the deviation or requirement will be checked below.

General Provisions
Permit Expiration
Archaeology, Paleontology, and Historical Sites
Noxious Weeds
Special Requirements
Commercial Well Determination
<b>○</b> Construction
Notification
Topsoil
Closed Loop System
Federal Mineral Material Pits
Well Pads
Roads
☐ Road Section Diagram
<b>⊠</b> Drilling
Anti-collision Program
Logging Requirements
High Cave/Karst
R-111-P Potash
Waste Material and Fluids
☐ Production (Post Drilling)
Well Structures & Facilities
Pipelines
Electric Lines
Interim Reclamation
Final Ahandonment & Reclamation

## I. GENERAL PROVISIONS

The approval of the Application For Permit To Drill (APD) is in compliance with all applicable laws and regulations: 43 Code of Federal Regulations 3160, the lease terms, Onshore Oil and Gas Orders, Notices To Lessees, New Mexico Oil Conservation Division (NMOCD) Rules, National Historical Preservation Act As Amended, and instructions and orders of the Authorized Officer. Any request for a variance shall be submitted to the Authorized Officer on Form 3160-5, Sundry Notices and Report on Wells.

#### II. PERMIT EXPIRATION

If the permit terminates prior to drilling and drilling cannot be commenced within 60 days after expiration, an operator is required to submit Form 3160-5, Sundry Notices and Reports on Wells, requesting surface reclamation requirements for any surface disturbance. However, if the operator will be able to initiate drilling within 60 days after the expiration of the permit, the operator must have set the conductor pipe in order to allow for an extension of 60 days beyond the expiration date of the APD. (Filing of a Sundry Notice is required for this 60 day extension.)

# III. ARCHAEOLOGICAL, PALEONTOLOGY & HISTORICAL SITES

Any cultural and/or paleontological resource discovered by the operator or by any person working on the operator's behalf shall immediately report such findings to the Authorized Officer. The operator is fully accountable for the actions of their contractors and subcontractors. The operator shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery shall be made by the Authorized Officer to determine the appropriate actions that shall be required to prevent the loss of significant cultural or scientific values of the discovery. The operator shall be held responsible for the cost of the proper mitigation measures that the Authorized Officer assesses after consultation with the operator on the evaluation and decisions of the discovery. Any unauthorized collection or disturbance of cultural or paleontological resources may result in a shutdown order by the Authorized Officer.

## IV. NOXIOUS WEEDS

The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes the roads, pads, associated pipeline corridor, and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

# V. SPECIAL REQUIREMENT(S)

# **Commercial Well Determination**

Well is not in a participating area. A commercial well determination will need to be submitted.

# VI. CONSTRUCTION

#### A. NOTIFICATION

The BLM shall administer compliance and monitor construction of the access road and well pad. Notify the Carlsbad Field Office at (575) 234-5972 at least 3 working days prior to commencing construction of the access road and/or well pad.

When construction operations are being conducted on this well, the operator shall have the approved APD and Conditions of Approval (COA) on the well site and they shall be made available upon request by the Authorized Officer.

#### B. TOPSOIL

The operator shall stockpile the topsoil in a low profile manner in order to prevent wind/water erosion of the topsoil. The topsoil to be stripped is approximately 4 inches in depth. The topsoil will be used for interim and final reclamation.

#### C. CLOSED LOOP SYSTEM

Tanks are required for drilling operations: No Pits.

The operator shall properly dispose of drilling contents at an authorized disposal site.

#### D. FEDERAL MINERAL MATERIALS PIT

Payment shall be made to the BLM prior to removal of any federal mineral materials. Call the Carlsbad Field Office at (575) 234-5972.

# E. WELL PAD SURFACING

Surfacing of the well pad is not required.

If the operator elects to surface the well pad, the surfacing material may be required to be removed at the time of reclamation.

The well pad shall be constructed in a manner which creates the smallest possible surface disturbance, consistent with safety and operational needs.

#### F. ON LEASE ACCESS ROADS

#### Road Width

The access road shall have a driving surface that creates the smallest possible surface disturbance and does not exceed fourteen (14) feet in width. The maximum width of surface disturbance, when constructing the access road, shall not exceed twenty (20) feet.

#### Surfacing

Surfacing material is not required on the new access road driving surface. If the operator elects to surface the new access road or pad, the surfacing material may be required to be removed at the time of reclamation.

Where possible, no improvements should be made on the unsurfaced access road other than to remove vegetation as necessary, road irregularities, safety issues, or to fill low areas that may sustain standing water.


The Authorized Officer reserves the right to require surfacing of any portion of the access road at any time deemed necessary. Surfacing may be required in the event the road deteriorates, erodes, road traffic increases, or it is determined to be beneficial for future field development. The surfacing depth and type of material will be determined at the time of notification.

#### Crowning

Crowning shall be done on the access road driving surface. The road crown shall have a grade of approximately 2% (i.e., a 1" crown on a 14' wide road). The road shall conform to Figure 1; cross section and plans for typical road construction.

#### **Turnouts**

Vehicle turnouts shall be constructed on the road. Turnouts shall be intervisible with interval spacing distance less than 1000 feet. Turnouts shall be constructed on all blind curves. Turnouts shall conform to the following diagram:




### Drainage

Drainage control systems shall be constructed on the entire length of road (e.g. ditches, sidehill outsloping and insloping, lead-off ditches, culvert installation, and low water crossings).

A typical lead-off ditch has a minimum depth of 1 foot below and a berm of 6 inches above natural ground level. The berm shall be on the down-slope side of the lead-off ditch.

Cross Section of a Typical Lead-off Ditch



All lead-off ditches shall be graded to drain water with a 1 percent minimum to 3 percent maximum ditch slope. The spacing interval are variable for lead-off ditches and shall be determined according to the formula for spacing intervals of lead-off ditches, but may be amended depending upon existing soil types and centerline road slope (in %);

# Formula for Spacing Interval of Lead-off Ditches

Example - On a 4% road slope that is 400 feet long, the water flow shall drain water into a lead-off ditch. Spacing interval shall be determined by the following formula:

400 foot road with 4% road slope: 
$$\frac{400'}{4\%}$$
 + 100' = 200' lead-off ditch interval

#### **Culvert Installations**

Appropriately sized culvert(s) shall be installed at the deep waterway channel flow crossing.

#### Cattleguards

An appropriately sized cattleguard(s) sufficient to carry out the project shall be installed and maintained at fence crossing(s).

Any existing cattleguard(s) on the access road shall be repaired or replaced if they are damaged or have deteriorated beyond practical use. The operator shall be responsible for the condition of the existing cattleguard(s) that are in place and are utilized during lease operations.

A gate shall be constructed and fastened securely to H-braces.

#### Fence Requirement


Where entry is required across a fence line, the fence shall be braced and tied off on both sides of the passageway prior to cutting.

The operator shall notify the private surface landowner or the grazing allotment holder prior to crossing any fence(s).

#### **Public Access**

Public access on this road shall not be restricted by the operator without specific written approval granted by the Authorized Officer.

Figure 1 - Cross Sections and Plans For Typical Road Sections



# VII. DRILLING

### A. DRILLING OPERATIONS REQUIREMENTS

The BLM is to be notified a minimum of 4 hours in advance for a representative to witness:

- a. Spudding well
- b. Setting and/or Cementing of all casing strings
- c. BOPE tests

# **Eddy County**

Call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220, (575) 361-2822

- 1. Due to recent H2S encounters in the salt formation, it is recommended that monitoring equipment be onsite for potential Hydrogen Sulfide prior to drilling out the surface shoe. If Hydrogen Sulfide is encountered, please report measurements and formations to the BLM.
- 2. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval. If the drilling rig is removed without approval an Incident of Non-Compliance will be written and will be a "Major" violation.
- 3. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works is located, this does not include the dog house or stairway area.
- 4. The record of the drilling rate along with the GR/N well log run from TD to surface (horizontal well vertical portion of hole) shall be submitted to the BLM office as well as all other logs run on the borehole 30 days from completion. If available, a digital copy of the logs is to be submitted in addition to the paper copies. The Rustler top and top and bottom of Salt are to be recorded on the Completion Report.
- 5. Due to the proximity of the proposed well to existing wellbores, an anti-collision review must be performed prior to drilling and an anti-collision analysis generated during drilling. Submit the results to the BLM Carlsbad Field Office.

#### B. CASING

Changes to the approved APD casing and cement program require submitting a sundry and receiving approval prior to work. Failure to obtain approval prior to work will result in an Incident of Non-Compliance being issued.

Centralizers required on surface casing per Onshore Order 2.III.B.1.f.

Wait on cement (WOC) time prior to drilling out for a primary cement job will be a minimum 18 hours for a water basin, 24 hours in the potash area, or 500 pounds compressive strength, whichever is greater for all casing strings. DURING THIS WOC TIME, NO DRILL PIPE, ETC. SHALL BE RUN IN THE HOLE. Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. See individual casing strings for details regarding lead cement slurry requirements.

No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.

R-111-P Potash/WIPP HIGH CAVE/KARST

Possible water and brine flows in the Rustler, Salado and Castile formations. Possible lost circulation within the Rustler, Delaware and Bone Spring.

- 1. The 13-3/8 inch surface casing shall be set at approximately 751 feet (a minimum of 25 feet into the Rustler Anhydrite and above the salt) and cemented to the surface.
  - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.
  - b. Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry.
  - c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.
  - d. If cement falls back, remedial cementing will be done prior to drilling out that string.

□ Cement to surface. If cement does not circulate see B.1.a, c-d above. Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to cave/karst and potash.

2. The minimum required fill of cement behind the 9-5/8 inch intermediate casing is:

- 3. The minimum required fill of cement behind the 7 inch production casing is:
  - a. First stage to DV tool, cement shall:
  - Cement to circulate. If cement does not circulate, contact the appropriate BLM office before proceeding with second stage cement job. Operator should have plans as to how they will achieve circulation on the next stage.
  - b. Second stage above DV tool, cement shall:
  - Cement to surface. If cement does not circulate, contact the appropriate BLM office. Additional cement may be required excess calculates to 16%.
- 4. Cement not required on the 4-1/2" completion assembly. Packer system being used.
- 5. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.
- 6. Whenever a casing string is cemented in the R-111-P potash area, the NMOCD requirements shall be followed.

# C. PRESSURE CONTROL

- 1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in Onshore Oil and Gas Order No. 2 and API RP 53 Sec. 17.
- 2. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be 2000 (2M) psi. Operator installing a 5M but testing as a 2M system.
  - a. For surface casing only: If the BOP/BOPE is to be tested against casing, the wait on cement (WOC) time for that casing is to be met (see WOC statement at start of casing section). Independent service company required.

- 3. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the 9-5/8 intermediate casing shoe shall be 3000 (3M) psi. Operator installing a 5M but testing as a 3M system.
- 4. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.
  - a. In potash areas, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. For all casing strings, casing cut-off and BOP installation can be initiated at twelve hours after bumping the plug. However, **no tests** shall commence until the cement has had a minimum of 24 hours setup time.
  - b. The tests shall be done by an independent service company utilizing a test plug **not** a **cup** or **J-packer**. The operator also has the option of utilizing an independent tester to test without a plug (i.e. against the casing) pursuant to Onshore Order 2 with the pressure not to exceed 70% of the burst rating for the casing. Any test against the casing must meet the WOC time for water basin (18 hours) or potash (24 hours) or 500 pounds compressive strength, whichever is greater, prior to initiating the test (see casing segment as lead cement may be critical item).
  - c. The results of the test shall be reported to the appropriate BLM office.
  - d. All tests are required to be recorded on a calibrated test chart. A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.
  - e. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug.

## D. DRILL STEM TEST

If drill stem tests are performed, Onshore Order 2.III.D shall be followed.

# E. WASTE MATERIAL AND FLUIDS

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area.

Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.

# F. WIPP Requirements

The proposed well is located over 330' of the WIPP Land Withdrawal Area boundary. As a result, BOPCO, L.P. is requested, but not required to submit daily logs and deviation survey information to the Department of Energy per requirements of the Joint Powers Agreement. Information from this well will be included in the Quarterly Drilling Report. Information will also be provided to the New Mexico Oil Conservation Division after drilling activities have been completed. Any future entry into the well for purposes of completing additional drilling will require supplemental information.

BOPCO, L.P. can email the required information to Mr. Melvin Balderrama at Mclvin.Balderama@wipp.ws or Mr. J. Neatherlin at Jimmy.Neatherlin@wipp.ws fax to his attention at 575-234-6062.

CRW 111511

# VIII. PRODUCTION (POST DRILLING)

#### A. WELL STRUCTURES & FACILITIES

#### **Placement of Production Facilities**

Production facilities should be placed on the well pad to allow for maximum interim recontouring and revegetation of the well location.

#### **Containment Structures**

The containment structure shall be constructed to hold the capacity of the entire contents of the largest tank, plus 24 hour production, unless more stringent protective requirements are deemed necessary by the Authorized Officer.

# **Painting Requirement**

All above-ground structures including meter housing that are not subject to safety requirements shall be painted a flat non-reflective paint color Shale Green, Munsell Soil Color Chart # 5Y 4/2

#### STANDARD STIPULATIONS FOR SURFACE INSTALLED PIPELINES

A copy of the grant and attachments, including stipulations, survey plat and/or map, will be on location during construction. BLM personnel may request to you a copy of your permit during construction to ensure compliance with all stipulations.

Holder agrees to comply with the following stipulations to the satisfaction of the Authorized Officer:

- 1. The holder shall indemnify the United States against any liability for damage to life or property arising from the occupancy or use of public lands under this grant.
- 2. The holder shall comply with all applicable Federal laws and regulations existing or hereafter enacted or promulgated. In any event, the holder shall comply with the Toxic Substances Control Act of 1976 as amended, 15 USC 2601 et seq. (1982) with regards to any toxic substances that are used, generated by or stored on the right-of-way or on facilities authorized under this right-of-way grant. (See 40 CFR, Part 702-799 and especially, provisions on polychlorinated biphenyls, 40 CFR 761.1-761.193.) Additionally, any release of toxic substances (leaks, spills, etc.) in excess of the reportable quantity established by 40 CFR, Part 117 shall be reported as required by the Comprehensive Environmental Response, Compensation, and Liability Act, section 102b. A copy of any report required or requested by any Federal agency or State government as a result of a reportable release or spill of any toxic substances shall be furnished to the authorized officer concurrent with the filing of the reports to the involved Federal agency or State government.
- 3. The holder agrees to indemnify the United States against any liability arising from the release of any hazardous substance or hazardous waste (as these terms are defined in the

Comprehensive Environmental Response, Compensation and Liability Act of 1980, 42 U.S.C. 9601, et seq. or the Resource Conservation and Recovery Act, 42 U.S.C. 6901, et seq.) on the Right-of-Way (unless the release or threatened release is wholly unrelated to activity of the Right-of-Way holder's activity on the Right-of-Way), or resulting from the activity of the Right-of-Way holder on the Right-of-Way. This agreement applies without regard to whether a release is caused by the holder, its agent, or unrelated third parties.

- 4. The holder shall be liable for damage or injury to the United States to the extent provided by 43 CFR Sec. 2883.1-4. The holder shall be held to a standard of strict liability for damage or injury to the United States resulting from pipe rupture, fire, or spills caused or substantially aggravated by any of the following within the right-of-way or permit area:
- a. Activities of the holder including, but not limited to construction, operation, maintenance, and termination of the facility.
- b. Activities of other parties including, but not limited to:
  - (1) Land clearing.
  - (2) Earth-disturbing and earth-moving work.
  - (3) Blasting.
  - (4) Vandalism and sabotage.
- c. Acts of God.

The maximum limitation for such strict liability damages shall not exceed one million dollars (\$1,000,000) for any one event, and any liability in excess of such amount shall be determined by the ordinary rules of negligence of the jurisdiction in which the damage or injury occurred.

This section shall not impose strict liability for damage or injury resulting primarily from an act of war or from the negligent acts or omissions of the United States.

5. If, during any phase of the construction, operation, maintenance, or termination of the pipeline, any oil, salt water, or other pollutant should be discharged from the pipeline system, impacting Federal lands, the control and total removal, disposal, and cleaning up of such oil, salt water, or other pollutant, wherever found, shall be the responsibility of the holder, regardless of fault. Upon failure of the holder to control, dispose of, or clean up such discharge on or affecting Federal lands, or to repair all damages resulting therefrom, on the Federal lands, the Authorized Officer may take such measures as he deems necessary to control and clean up the discharge and restore the area, including, where appropriate, the aquatic environment and fish and wildlife habitats, at the full expense of the holder. Such action by the Authorized Officer shall not relieve the holder of any responsibility as provided herein.

6. All construction and maintenance activity will be confined to the authorized right-of-way width of feet.
6. (a) Where a polyline is laid along a <u>County</u> Road, the operator will lay that polyline ten (10)  feet out from the center of the ditch to prevent obstructing County Maintenance activities.
7. No blading or clearing of any vegetation will be allowed unless approved in writing by the Authorized Officer.
8. The holder shall install the pipeline on the surface in such a manner that will minimize suspension of the pipeline across low areas in the terrain. In hummocky of duney areas, the pipeline will be "snaked" around hummocks and dunes rather then suspended across these features.
9. The pipeline shall be buried with a minimum of inches under all roads, "two-tracks," and trails. Burial of the pipe will continue for 20 feet on each side of each crossing. The condition of the road, upon completion of construction, shall be returned to at least its former state with no bumps or dips remaining in the road surface.
10. The holder shall minimize disturbance to existing fences and other improvements on public lands. The holder is required to promptly repair improvements to at least their former state. Functional use of these improvements will be maintained at all times. The holder will contact the owner of any improvements prior to disturbing them. When necessary to pass through a fence line, the fence shall be braced on both sides of the passageway prior to cutting of the fence. No permanent gates will be allowed unless approved by the Authorized Officer.
11. In those areas where erosion control structures are required to stabilize soil conditions, the holder will install such structures as are suitable for the specific soil conditions being encountered and which are in accordance with sound resource management practices.
12. Excluding the pipe, all above-ground structures not subject to safety requirement shall be painted by the holder to blend with the natural color of the landscape. The paint used shall be a color which simulates "Standard Environmental Colors" – <b>Shale Green</b> , Munsell Soil Color No. 5Y 4/2; designated by the Rocky Mountain Five State

13. The pipeline will be identified by signs at the point of origin and completion of the right-of-way and at all road crossings. At a minimum, signs will state the holder's name, BLM serial number, and the product being transported. Signs will be maintained in a

Interagency Committee.

legible condition for the life of the pipeline.

- 14. The holder shall not use the pipeline route as a road for purposes other than routine maintenance as determined necessary by the Authorized Officer in consultation with the holder. The holder will take whatever steps are necessary to ensure that the pipeline route is not used as a roadway.
- 15. Any cultural and/or paleontological resource (historic or prehistoric site or object) discovered by the holder, or any person working on his behalf, on public or Federal land shall be immediately reported to the authorized officer. Holder shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the authorized officer. An evaluation of the discovery will be made by the authorized officer to determine appropriate cultural or scientific values. The holder will be responsible for the cost of evaluation and any decision as to proper mitigation measures will be made by the authorized officer after consulting with the holder.
- 16. The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes the roads, powerline corridor, and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

# IX. INTERIM RECLAMATION

During the life of the development, all disturbed areas not needed for active support of production operations should undergo interim reclamation in order to minimize the environmental impacts of development on other resources and uses.

Within six (6) months of well completion, operators should work with BLM surface management specialists (Jim Amos: 575-234-5909) to devise the best strategies to reduce the size of the location. Interim reclamation should allow for remedial well operations, as well as safe and efficient removal of oil and gas.

During reclamation, the removal of caliche is important to increasing the success of revegetating the site. Removed caliche that is free of contaminants may be used for road repairs, fire walls or for building other roads and locations. In order to operate the well or complete workover operations, it may be necessary to drive, park and operate on restored interim vegetation within the previously disturbed area. Disturbing revegetated areas for production or workover operations will be allowed. If there is significant disturbance and loss of vegetation, the area will need to be revegetated. Communicate with the appropriate BLM office for any exceptions/exemptions if needed.

All disturbed areas after they have been satisfactorily prepared need to be reseeded with the seed mixture provided below.

Upon completion of interim reclamation, the operator shall submit a Sundry Notices and Reports on Wells, Subsequent Report of Reclamation (Form 3160-5).

#### X. FINAL ABANDONMENT & RECLAMATION

At final abandonment, well locations, production facilities, and access roads must undergo "final" reclamation so that the character and productivity of the land are restored.

Earthwork for final reclamation must be completed within six (6) months of well plugging. All pads, pits, facility locations and roads must be reclaimed to a satisfactory revegetated, safe, and stable condition, unless an agreement is made with the landowner or BLM to keep the road and/or pad intact.

After all disturbed areas have been satisfactorily prepared, these areas need to be revegetated with the seed mixture provided below. Seeding should be accomplished by drilling on the contour whenever practical or by other approved methods. Seeding may need to be repeated until revegetation is successful, as determined by the BLM.

Operators shall contact a BLM surface protection specialist prior to surface abandonment operations for site specific objectives (Jim Amos: 575-234-5909).

Seed Mixture 2, for Sandy Sites

The holder shall seed all disturbed areas with the seed mixture listed below. The seed mixture shall be planted in the amounts specified in pounds of pure live seed (PLS)\* per acre. There shall be <u>no</u> primary or secondary noxious weeds in the seed mixture. Seed will be tested and the viability testing of seed will be done in accordance with State law (s) and within nine (9) months prior to purchase. Commercial seed will be either certified or registered seed. The seed container will be tagged in accordance with State law(s) and available for inspection by the authorized officer.

Seed will be planted using a drill equipped with a depth regulator to ensure proper depth of planting where drilling is possible. The seed mixture will be evenly and uniformly planted over the disturbed area (smaller/heavier seeds have a tendency to drop the bottom of the drill and are planted first). The holder shall take appropriate measures to ensure this does not occur. Where drilling is not possible, seed will be broadcast and the area shall be raked or chained to cover the seed. When broadcasting the seed, the pounds per acre are to be doubled. The seeding will be repeated until a satisfactory stand is established as determined by the authorized officer. Evaluation of growth will not be made before completion of at least one full growing season after seeding.

Species to be planted in pounds of pure live seed\* per acre:

#### Species

	l <u>b/acre</u>
Sand dropseed (Sporobolus cryptandrus)	1.0
Sand love grass (Eragrostis trichodes)	1.0

Plains bristlegrass (Setaria macrostachya)

2.0

\*Pounds of pure live seed:

Pounds of seed x percent purity x percent germination = pounds pure live seed

# DISTRICT I --- CHECKLIST FOR INTENTS TO DRILL

Operator	BORCD		OGRID #_	26073'
	# JAMUS BAUCH	138 H		ace Type (F) (S) (P
Location: UL	K, Sect 25, Twnship 22 s	i, RNG <u>30</u> e,		ace Type (F) (S) (P
A. C B. 1. O 2.	Date C101 rec'd 12 16  Check mark, Information is OK or GRID , BONDING , PROFILE , PROFILE , Sent Least Communication is OK or GRID , PROFILE , Sent Least Communication is OK or GRID , PROFILE , Sent Least Communication is OK or GRID , PROFILE , Sent Least Communication is OK or GRID , PROFILE , Sent Least Communication is OK or GRID , PROFILE , Sent Least Communication is OK or GRID , Sent Least Communication is OK or GRID , PROFILE , PROF	The Forms:  CODE WEL  CODE # wel  Modern of inactive we etter to Operator  Tor needs addition to the complete	L#, SIGNATU Is #32, # Inactive Ils:, to Santa Fe bonding:, To Santa Fe nancial Assurance:	113 120 4 RE
1.	Pool, NO, Signature a. Dedicated acreage b. SUR. Location Standard c. Well shares acres: Yes, 2 <sup>nd</sup> . Operator in same acreage, \ Agreement Letter, Disagre Intent to Directional Drill Yes a. Dedicated acreage b. Bottomhole Location Standa	Ridge: Sb.  , What Units: Non-Standard   No, # of wells_ Yes, No eement letter , No, , What Units	Code SO  Location plus this well #	443
4.	Downhole Commingle: Yes	_ No		
	a. Pool #2 Pool #3			
		•	, Code , Code	
D. Blo E. H2 F. C14 G. Doo 1. 2. 3.	Pool #4_ POTASH Area Yes	, No, NSL #, No, NSP #, No, SD #; PMX #	# or WFX #	
	OCD Approval Date 17/18 Reviewers	1 <u>201</u>	API #30-0/5	39766