

Carlsbad Field Office OCD Artesia

ATS-15-283
FORM APPROVED
OMB No. 1004-013
Expires July 31, 2010

UNITED STATES
DEPARTMENT OF THE INTERIOR R-111-POTASH
BUREAU OF LAND MANAGEMENT

APPLICATION FOR PERMIT TO DRILL OR REENTER

1a. Type of Work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER		7. If Unit or CA Agreement, Name and No.	
1b. Type of Well: <input checked="" type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Other <input type="checkbox"/> Single Zone <input type="checkbox"/> Multiple Zone		8. Lease Name and Well No. Solution Federal Com #3H	
2. Name of Operator COG Operating LLC.		9. API Well No. 30-015-43227	
3a. Address 2208 West Main Street Artesia, NM 88210	3b. Phone No. (include area code) 575-748-6940	10. Field and Pool, or Exploratory Parkway; Bone Spring	
4. Location of Well (Report location clearly and in accordance with any State requirements. *) At surface 190' FNL & 2250' FWL Lot 3 NENW SHL Sec 5-T20S-R30E At proposed prod. Zone 2310' FNL & 1980' FWL Unit Letter F SENW SHL Sec 8-T20S-R30E		11. Sec., T.R.M. or Blk and Survey or Area Sec. 5- T20S - R30E	
14. Distance in miles and direction from nearest town or post office* About 13 miles from Carlsbad		12. County or Parish Eddy County	13. State NM
15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. Unit line, if any) 190'	16. No. of acres in lease SHL: 599.68 BHL: 320	17. Spacing Unit dedicated to this well 239.99	
18. Distance from location* to nearest well, drilling, completed, applied for, on this lease, ft. SHL: 1281' (Solution #4H) BHL: 3042'	TVD: 8,365' MD: 15,522'	NMB000740 & NMB000215	
21. Elevations (Show whether DF, KDB, RT, GL, etc.) 3251.6' GL	22. Approximate date work will start* 1/1/2015	23. Estimated duration 30 days	

NORTHODOX
LOCATION

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, shall be attached to this form:

- | | |
|---|--|
| <ul style="list-style-type: none"> 1. Well plat certified by a registered surveyor. 2. A Drilling Plan 3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO shall be filed with the appropriate Forest Service Office). | <ul style="list-style-type: none"> 4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above). 5. Operator certification 6. Such other site specific information and/or plans as may be required by the authorized officer. |
|---|--|

25. Signature 	Name (Printed/Typed) MAFE PEREZ	Date 12-11-2014
 JUL 16 2015		
Approved by (Signature) IS/ JEANETTE MARTINEZ	Name (Printed/Typed) RECEIVED	Date JUL 16 2015
Title FIELD MANAGER	Office CARLSBAD FIELD OFFICE	

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.
Conditions of approval, if any, are attached.

APPROVAL FOR TWO YEARS

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Continued on page 2)

Capitan Controlled Water Basin

Approval Subject to General Requirements
& Special Stipulations Attached

SEE ATTACHED FOR
CONDITIONS OF APPROVAL


AD
7/17/15

*(Instructions on page 2)

Surface Use Plan
COG Operating LLC
Solution FederalCom #3H
SHL: 190' FNL & 2250' FWL Lot 3
Section 5, T20S, R30E
BHL: 2310' FNL & 1980' FWL UL F
Section 8, T20S, R30E
Eddy County, New Mexico

OPERATOR CERTIFICATION

I hereby certify that I, or persons under my direct supervision, have inspected the drill site and access road proposed herein; that I am familiar with the conditions that presently exist; that I have full knowledge of State and Federal laws applicable to this operation; that the statements made in this APD package are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or COG Operating LLC, am responsible for the operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filing of false statements. Executed this 2nd day of March, 2015.

Signed: 

Printed Name: Melanie J. Parker

Position: Regulatory Coordinator

Address: 2208 W. Main Street, Artesia, NM 88210


Telephone: (575) 748-6940

Field Representative (if not above signatory): Rand French

E-mail: mparker@concho.com

EXHIBIT 2

#3




R 30 E
T 19 S
T 20 S

LEGEND

- WELL
- WELLPAD
- ▨ FRAC POND
- PLATTED EXISTING ROAD
- PROPOSED ROAD
- EXISTING ROAD


SOLUTION FED ROAD REROUTE
 SECTIONS: 5, 29, 32 TOWNSHIP: 19 & 20 S. RANGE: 30 E.
 STATE: NEW MEXICO COUNTY: EDDY SURVEY: N.M.P.M
 W.O. # 14-1202 LEASE: SOLUTION FED



LOCATION MAP TOPO 06/13/2015 STP

CONCHO
 COG OPERATING, LLC

HARCROW SURVEYING, LLC.
 2314 W. MAIN ST, ARTESIA, NM 88210
 PH: (575) 746-2158 FAX: (575) 746-2158
 c.harcrow@harcrowsurveying.com



R 30 E
T 19 S
T 20 S

LEGEND

- WELL
- WELLPAD
- ▨ FRAC POND
- PLATTED EXISTING ROAD
- PROPOSED ROAD
- EXISTING ROAD

SOLUTION FED ROAD REROUTE

SECTIONS: 5, 29, 32 TOWNSHIP: 19 & 20 S. RANGE: 30 E.

STATE: NEW MEXICO COUNTY: EDDY SURVEY: N.M.P.M

W.O. # 14-1202 LEASE: SOLUTION FED

0 2,500 5,000 FEET


0 0.125 0.25 0.5 Miles

1 IN = 2,000 FT

LOCATION MAP IMAGERY 12/04/2014 SP

CONCHO
COG OPERATING, LLC

HARCROW SURVEYING, LLC.
2314 W. MAIN ST, ARTESIA, NM 88210
PH: (575) 746-2158 FAX: (575) 746-2158
c.harcrow@harcrowsurveying.com



R 30 E
T 19 S
T 20 S

LEGEND

- WELL
- ◻ WELLPAD
- ▨ FRAC POND
- PLATTED EXISTING ROAD
- PROPOSED ROAD
- EXISTING ROAD
- ◻ PRIVATE
- ▨ STATE OF NM
- ◻ US BLM

SOLUTION FED ROAD REROUTE

SECTIONS: 5, 29, 32 TOWNSHIP: 19 & 20 S. RANGE: 30 E.

STATE: NEW MEXICO COUNTY: EDDY SURVEY: N.M.P.M

W.O. # 14-1202 LEASE: SOLUTION FED

0 2,500 5,000 FEET


0 0.125 0.25 0.5 Miles 1 IN = 2,000 FT

LOCATION MAP PLAN STATUS 12/04/2014 SP


CONCHO
COG OPERATING, LLC

H HARCROW SURVEYING, LLC.
2314 W. MAIN ST, ARTESIA, NM 88210
PH: (575) 746-2158 FAX: (575) 746-2158
c.harcrow@harcrowsurveying.com


2,000 psi BOP Schematic




2,000 psi BOP Schematic



3,000 psi BOP Schematic





DATA FOR "WELLS WITHIN 1 MI." IS TAKEN FROM THE NEW MEXICO EMNRD WEBSITE. THE DATA HAS BEEN UPDATED THROUGH OCTOBER 18, 2014.

LEGEND

- WELL
- BOTTOMHOLE
- WELLS WITHIN 1 MI.
- 1 MI. BUFFER

SOLUTION FED COM #3H

SEC: 5 TWP: 20 S. RGE: 30 E. ELEVATION: 3251.6'

STATE: NEW MEXICO COUNTY: EDDY 190' FNL & 2250' FWL

W.O. # 14-1051 LEASE: SOLUTION FED COM SURVEY: N.M.P.M

0 2,500 5,000 FEET

0 0.15 0.3 0.6 Miles

1 IN = 2,250 FT

1-MILE MAP 10/23/2014 S.P.

CONCHO
COG OPERATING, LLC

HARCROW SURVEYING, LLC.
2314 W. MAIN ST, ARTESIA, NM 88210
PH: (575) 513-2570 FAX: (575) 746-2158
chad_harcrow77@yahoo.com

Solution Federal Com #3H

FID	OPERATOR	WELL_NAME	LATITUDE	LONGITUDE	API	SECTION	TOWNSHIP	RANGE	FTG_NS	NS_CD	FTG_EW	EW_CD	TVD_DEPTH	COMPL_STAT
0	H & W FOGERTY	STOREY 001	32.615105	-104.009282	3001504651	31	19.0S	30E	1980	S	1980	E	0	Plugged
1	HENRY BLACK DRLG CO	STATE LOWE 002	32.619602	-103.988884	3001504653	32	19.0S	30E	1650	N	990	E	0	Plugged
2	MARK WHELAN	RIGGS 001	32.608755	-104.008212	3001504661	6	20.0S	30E	330	N	1650	E	0	Plugged
3	A J HARDENDORF	RIGGS 001	32.586974	-104.006098	3001504664	7	20.0S	30E	2310	S	990	E	0	Plugged
4	GROVER-MANN BRO	RIGGS 001	32.593327	-104.00499	3001504665	7	20.0S	30E	660	N	660	E	0	Plugged
5	CONTINENTAL OIL	Cunningham 001	32.590619	-103.986775	3001504666	8	20.0S	30E	1650	N	330	E	0	Plugged
6	IKE LOVELADY INC	CONTINENTAL FED 5 001	32.604201	-103.996358	3001510003	5	20.0S	30E	1980	N	1980	W	0	Plugged
7	COG OPERATING LLC	STRAIGHT JOE STATE COM 001	32.611466	-104.000673	3001534068	32	19.0S	30E	660	S	660	W	12180	Active
8	COG OPERATING LLC	SHOELESS JOE 32 STATE COM 001H	32.621448	-104.001832	3001540586	32	19.0S	30E	990	N	300	W	8440	New (Not drilled or compl)
9	COG OPERATING LLC	SHOELESS JOE 32 STATE COM 004H	32.611304	-104.002207	3001541242	32	19.0S	30E	600	S	190	W	8378	New (Not drilled or compl)
10	COG OPERATING LLC	SHOELESS JOE 32 STATE COM 002H	32.61782	-104.002197	3001541238	32	19.0S	30E	2310	N	190	W	0	New (Not drilled or compl)
11	CIMAREX ENERGY CO. OF COLORADO	BURTON 6 FEDERAL COM 004H	32.608753	-104.006058	3001539332	6	20.0S	30E	330	N	990	E	0	New (Not drilled or compl)
12	CIMAREX ENERGY CO. OF COLORADO	BURTON 6 FEDERAL 003H	32.608756	-104.009288	3001539331	6	20.0S	30E	330	N	1980	E	0	New (Not drilled or compl)
13	COG OPERATING LLC	SHOELESS JOE 32 STATE COM 003H	32.61419	-104.002203	3001541028	32	19.0S	30E	1650	S	190	W	8405	New (Not drilled or compl)

COG Operating LLC, Solution Federal Com #3H

1. Geologic Formations

TVD of target @ EOC	8345'	Pilot hole depth	NA
MD at TD:	15522'	Deepest expected fresh water:	148'

Formation	Depth (TVD) from KB	Water/Mineral Bearing/Target Zone?	Hazards*
Quaternary Fill	Surface	Fresh Water	
Rustler	165'	Fresh Water	
Top of Salt	428'	Salt	
Tansill	1525'	Barren	
Yates	1605'	Barren	
Capitan Reef	1997'	Water	
Delaware Group	3423'	Oil/Gas	
Bone Spring	6177'	Oil/Gas	
2 nd Bone Spring	8041'	Target Zone	
3 rd Bone Spring	9123'	Will Not Penetrate	

*H2S, water flows, loss of circulation, abnormal pressures, etc.

2. Casing Program

See COA

per Alex Korzenewski

Hole Size	Casing Interval		Csg. Size	Weight (lbs)	Grade	Conn.	SF Collapse	SF Burst	SF Tension	
	From	To								
26"	0	350'	20"	94	J55	STC	3.36	2.50	23.80	
17 1/2"	0	1625' / 1685'	13.375"	54.45	J55	LTCSTC	1.34	1.75	6.19	
12 1/4"	0'	3443'	9.625"	40	J55	LTC	1.65	1.01	3.78	
8 3/4"	0	7824'	7.0"	26	P110	BTC	1.59	1.33	4.19	
8 3/4"	7844'	15522'	5.5"	17	P110	BTC	1.90	1.33	4.17	
7824'							BLM Minimum Safety Factor	1.125	1	1.6 Dry 1.8 Wet

- All casing strings will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.h
- BLM standard formulas where used on all SF calculations.
- Assumed 9.0 ppg MW equivalent pore pressure thru entire wellbore.

COG Operating LLC, Solution Federal Com #3H

	Y or N
Is casing new? If used, attach certification as required in Onshore Order #1	Y
Does casing meet API specifications? If no, attach casing specification sheet.	Y
Is premium or uncommon casing planned? If yes attach casing specification sheet.	N
Does the above casing design meet or exceed BLM's minimum standards? If not provide justification (loading assumptions, casing design criteria).	Y
Will the intermediate pipe be kept at a minimum 1/3 fluid filled to avoid approaching the collapse pressure rating of the casing?	Y
Is well located within Capitan Reef?	
If yes, does production casing cement tie back a minimum of 50' above the Reef?	Y
Is well within the designated 4 string boundary.	Y
Is well located in SOPA but not in R-111-P?	
If yes, are the first 2 strings cemented to surface and 3 rd string cement tied back 500' into previous casing?	N
Is well located in R-111-P and SOPA?	
If yes, are the first three strings cemented to surface?	Y
Is 2 nd string set 100' to 600' below the base of salt?	Y
Is well located in high Cave/Karst?	
If yes, are there two strings cemented to surface?	Y
(For 2 string wells) If yes, is there a contingency casing if lost circulation occurs?	
Is well located in critical Cave/Karst?	
If yes, are there three strings cemented to surface?	N

. Cementing Program

Casing	# Sks	Wt. lb/gal	Yld ft3/sack	H ₂ O gal/sk	500# Comp. Strength (hours)	Slurry Description
Surf.	875	13.5	1.75	9.2	10	Lead: Class C + 4.0% Gel+2% CaCl ₂ + 0.25 pps CF
	325	14.8	1.34	6.3	6	Tail: Class C + 2% CaCl ₂ + 0.25 pps CF
1 st Inter.	1200	12.7	1.75	11.5	10	Lead: Class "C" + 4.0 % Gel+2% CaCl ₂ + 0.25 pps CF
	375	14.8	1.32	6.3	6	Tail: Class C + 2% CaCl ₂ +0.25 pps CF
2nd Inter.	300	11.8	2.45	14.4	72	1 st stage Lead: 50:50:10 C: Poz:Gel w/5% Salt + 5 pps LCM + 0.25 pps CF
	250	14.8	1.32	6.3	6	1 st stage Tail: Class "C" w/2% CaCl ₂ + 0.25 pps CF
	DV Tool/ ECP @ approx. 1947'					
	425	11.8	2.45	14.4	72	2 nd stage lead: 50:50:10 C:Poz:Gel w/5% Salt+ 5 pps LCM + 0.25 pps CF
	200	14.8	1.32	6.3	6	2 nd stage Tail: Class "C" + 2% CaCl ₂ + 0.25 pps CF

COG Operating LLC, Solution Federal Com #3H

Prod.	600	11.9	2.51	14.2	22	Lead: EconoCem-H+ 0.5% Halad-322 + 5 pps Kol-Seal + 0.25 pps D-AIR 5000 + 0.2% HR-601
	2000	14.4	1.24	5.7	8	Tail: VersaCem + 0.4% GasStop+ 0.3% CFR-3 + 1% Salt + 0.1% HR-601

DV tool depth(s) will be adjusted based on hole conditions and cement volumes will be adjusted proportionally. DV tool will be set a minimum of 50 feet below previous casing and a minimum of 200 feet above current shoe. Lab reports with the 500 psi compressive strength time for the cement will be onsite for review.

Casing String	TOC	% Excess
Surface	0'	100%
1 st Intermediate	0'	100%
2 nd Intermediate	0'	100%
Production	0'	35%

4. Pressure Control Equipment

N	A variance is requested for the use of a diverter on the surface casing. See attached for schematic.
---	--

BOP installed and tested before drilling which hole?	Size?	Min. Required WP	Type	✓	Tested to:
17 1/2"	20"	2M	Annular	x	50% of working pressure 2000 psi WP
			Blind Ram		
			Pipe Ram		
			Double Ram		
			Other*		
12 1/4"	13 5/8"	2M	Annular	x	50% testing pressure 2000 psi WP
			Blind Ram		
			Pipe Ram		
			Double Ram		
			Other*		
8 3/4" & 7 7/8"	13 5/8"	3M	Annular	x	3000 psi WP
			Blind Ram	x	
			Pipe Ram	x	
			Double Ram		
			Other*		

*Specify if additional ram is utilized.

COG Operating LLC, Solution Federal Com #3H

BOP/BOPE will be tested by an independent service company to 250 psi low and the high pressure indicated above per Onshore Order 2 requirements. The System may be upgraded to a higher pressure but still tested to the working pressure listed in the table above. If the system is upgraded all the components installed will be functional and tested.

Pipe rams will be operationally checked each 24 hour period. Blind rams will be operationally checked on each trip out of the hole. These checks will be noted on the daily tour sheets. Other accessories to the BOP equipment will include a Kelly cock and floor safety valve (inside BOP) and choke lines and choke manifold. See attached schematics.

N	Formation integrity test will be performed per Onshore Order #2. On Exploratory wells or on that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.i.
N	A variance is requested for the use of a flexible choke line from the BOP to Choke Manifold. See attached for specs and hydrostatic test chart.
	NA Are anchors required by manufacturer?
N	A multibowl wellhead is being used. The BOP will be tested per Onshore Order #2 after installation on the surface casing which will cover testing requirements for a maximum of 30 days. If any seal subject to test pressure is broken the system must be tested.

5. Mud Program

Depth		Type	Weight (ppg)	Viscosity	Water Loss
From	To				
0	Surf. shoe	Fresh Water	8.4-8.6	29-40	N/C
Surf. shoe	1 st Int. shoe	Brine	10.0-10.1	29-32	N/C
1 st Int. shoe	2 nd Int. shoe	Fresh Water	8.4-8.7	28-32	N/C
2 nd Int. shoe	TD	Cut Brine	8.4-9.0	29-36	N/C

Sufficient mud materials to maintain mud properties and meet minimum lost circulation and weight increase requirements will be kept on location at all times.

What will be used to monitor the loss or gain of fluid?	PVT/Pason/Visual Monitoring
---	-----------------------------

6. Logging and Testing Procedures

Logging, Coring and Testing.	
X	Will run GR/CNL from TD to surface (horizontal well – vertical portion of hole). Stated logs run will be in the Completion Report and submitted to the BLM.
	No Logs are planned based on well control or offset log information.
	Drill stem test? If yes, explain
	Coring? If yes, explain

7. Drilling Conditions

Condition	Specify what type and where?
BH Pressure at deepest TVD	3680 psi
Abnormal Temperature	No

If severe losses are encountered in the Capitan Reef and hole conditions allow, dry drilling to TD while using only fresh water in mud system will be the preferred operation. If hole conditions do not allow dry drilling with fresh water – LCM sweeps, cement plugs, air or other loss circulation remedies may be introduced to operations to manage lost circulation. Cement will be circulated to surface in two stages using a stage tool and an external casing packer to isolate the weaker zones in the Capitan Reef.

Hydrogen Sulfide (H2S) monitors will be installed prior to drilling out the surface shoe. If H2S is detected in concentrations greater than 100 ppm, the operator will comply with the provisions of Onshore Oil and Gas Order #6. If Hydrogen Sulfide is encountered, measured values and formations will be provided to the BLM.	
N	H2S is present
Y	H2S Plan attached

8. Other facets of operation

Is this a walking operation? No

- No casings will be pre-set
- Anti-Collision practices will be used to avoid collision in vertical well bores

Attachments:

- BOP & Choke schematics
- Directional plan
- C102 and supporting maps
- Anti-collision report
- Rig plat schematic
- H2S plan schematic
- H2S contingency plan
- Interim reclamation plat

GEG: 10/20/14

COG OPERATING, LLC

Eddy County, NM
Solution Federal Com 3H
3H

Lateral

Plan: Plan #1

Standard Planning Report

09 October, 2014

Section Distances
Sec5,T20S,R30E
SHL - Lot 3
190'FNL, 2250'FWL
PP
330'FNL, 2244'FWL
Sec8,T20S,R30E
PBHL - Unit F
2310'FNL, 1980'FWL

Archer

Planning Report

Database:	EDM R5000.1 MULTI	Local Co-ordinate Reference:	Well 3H
Company:	COG OPERATING, LLC	TVD Reference:	3251'GL+19'KB @ 3270.00usft (McVay 6)
Project:	Eddy County, NM	MD Reference:	3251'GL+19'KB @ 3270.00usft (McVay 6)
Site:	Solution Federal Com 3H	North Reference:	Grid
Well:	3H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Lateral		
Design:	Plan #1		

Project:	Eddy County, NM		
Map System:	US State Plane 1927 (Exact solution)	System Datum:	Mean Sea Level
Geo Datum:	NAD 1927 (NADCON CONUS)		
Map Zone:	New Mexico East 3001		

Site:	Solution Federal 3H				
Site Position:	Northing:	585,437.50 usft	Latitude:	32° 36' 32.46 N	
From:	Map	Easting:	604,197.30 usft	Longitude:	103° 59' 41.83 W
Position Uncertainty:	0.00 usft	Slot Radius:	13.200 in	Grid Convergence:	0.18 °

Well:	3H					
Well Position	+N-S	0.00 usft	Northing:	585,437.50 usft	Latitude:	32° 36' 32.46 N
	+E-W	0.00 usft	Easting:	604,197.30 usft	Longitude:	103° 59' 41.83 W
Position Uncertainty	0.00 usft	Wellhead Elevation:	0.00 usft	Ground Level:	3,251.00 usft	

Wellbore:	Lateral				
Magnetics	Model Name	Sample Date	Declination	Dip Angle	Field Strength
	HDGM	10/9/2014	(°) 7.73	(°) 60.53	(nT) 48,519

Design:	Plan #1			
Audit Notes:				
Version:	Phase:	PROTOTYPE	Tie On Depth:	0.00
Vertical Section:	Depth From (TVD)	+N-S	+E-W	Direction
	(usft)	(usft)	(usft)	(°)
	0.00	0.00	0.00	181.98

Plan Sections										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N-S (usft)	+E-W (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	TFO (°)	Target
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
7,824.14	0.00	0.00	7,824.14	0.00	0.00	0.00	0.00	0.00	0.00	
8,640.80	89.83	181.98	8,345.00	-519.05	-17.94	11.00	11.00	0.00	181.98	
15,521.89	89.83	181.98	8,365.00	-7,396.00	-255.60	0.00	0.00	0.00	0.00	Solution 3H PBHL

Archer Planning Report

Database	EDM R5000.1 MULTI	Local Co-ordinate Reference:	Well 3H
Company	COG OPERATING, LLC	TVD Reference:	3251'GL+19'KB @ 3270.00usft (McVay 6)
Project	Eddy County, NM	MD Reference:	3251'GL+19'KB @ 3270.00usft (McVay 6)
Site	Solution Federal Com 3H	North Reference:	Grid
Well	3H	Survey Calculation Method:	Minimum Curvature
Wellbore	Lateral		
Design	Plan #1		

Planned Survey										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
100.00	0.00	0.00	100.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
200.00	0.00	0.00	200.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
300.00	0.00	0.00	300.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
400.00	0.00	0.00	400.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
500.00	0.00	0.00	500.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
600.00	0.00	0.00	600.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
700.00	0.00	0.00	700.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
800.00	0.00	0.00	800.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
900.00	0.00	0.00	900.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
1,000.00	0.00	0.00	1,000.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
1,100.00	0.00	0.00	1,100.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
1,200.00	0.00	0.00	1,200.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
1,300.00	0.00	0.00	1,300.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
1,400.00	0.00	0.00	1,400.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
1,500.00	0.00	0.00	1,500.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
1,600.00	0.00	0.00	1,600.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
1,700.00	0.00	0.00	1,700.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
1,800.00	0.00	0.00	1,800.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
1,900.00	0.00	0.00	1,900.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
2,000.00	0.00	0.00	2,000.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
2,100.00	0.00	0.00	2,100.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
2,200.00	0.00	0.00	2,200.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
2,300.00	0.00	0.00	2,300.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
2,400.00	0.00	0.00	2,400.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
2,500.00	0.00	0.00	2,500.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
2,600.00	0.00	0.00	2,600.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
2,700.00	0.00	0.00	2,700.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
2,800.00	0.00	0.00	2,800.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
2,900.00	0.00	0.00	2,900.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
3,000.00	0.00	0.00	3,000.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
3,100.00	0.00	0.00	3,100.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
3,200.00	0.00	0.00	3,200.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
3,300.00	0.00	0.00	3,300.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
3,400.00	0.00	0.00	3,400.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
3,500.00	0.00	0.00	3,500.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
3,600.00	0.00	0.00	3,600.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
3,700.00	0.00	0.00	3,700.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
3,800.00	0.00	0.00	3,800.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
3,900.00	0.00	0.00	3,900.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4,000.00	0.00	0.00	4,000.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4,100.00	0.00	0.00	4,100.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4,200.00	0.00	0.00	4,200.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4,300.00	0.00	0.00	4,300.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4,400.00	0.00	0.00	4,400.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4,500.00	0.00	0.00	4,500.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4,600.00	0.00	0.00	4,600.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4,700.00	0.00	0.00	4,700.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4,800.00	0.00	0.00	4,800.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4,900.00	0.00	0.00	4,900.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
5,000.00	0.00	0.00	5,000.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
5,100.00	0.00	0.00	5,100.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
5,200.00	0.00	0.00	5,200.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
5,300.00	0.00	0.00	5,300.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00

Archer Planning Report

Database	EDM R5000.1 MULTI	Local Co-ordinate Reference	Well 3H
Company	COG OPERATING, LLC	TVD Reference	3251'GL+19'KB @ 3270.00usft (McVay 6)
Project	Eddy County, NM	MD Reference	3251'GL+19'KB @ 3270.00usft (McVay 6)
Site	Solution Federal Corn 3H	North Reference	Grid
Well	3H	Survey Calculation Method	Minimum Curvature
Wellbore	Lateral		
Design	Plan #1		

Planned Survey										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/S (usft)	+E/W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	
5,400.00	0.00	0.00	5,400.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
5,500.00	0.00	0.00	5,500.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
5,600.00	0.00	0.00	5,600.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
5,700.00	0.00	0.00	5,700.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
5,800.00	0.00	0.00	5,800.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
5,900.00	0.00	0.00	5,900.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
6,000.00	0.00	0.00	6,000.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
6,100.00	0.00	0.00	6,100.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
6,200.00	0.00	0.00	6,200.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
6,300.00	0.00	0.00	6,300.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
6,400.00	0.00	0.00	6,400.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
6,500.00	0.00	0.00	6,500.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
6,600.00	0.00	0.00	6,600.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
6,700.00	0.00	0.00	6,700.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
6,800.00	0.00	0.00	6,800.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
6,900.00	0.00	0.00	6,900.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
7,000.00	0.00	0.00	7,000.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
7,100.00	0.00	0.00	7,100.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
7,200.00	0.00	0.00	7,200.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
7,300.00	0.00	0.00	7,300.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
7,400.00	0.00	0.00	7,400.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
7,500.00	0.00	0.00	7,500.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
7,600.00	0.00	0.00	7,600.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
7,700.00	0.00	0.00	7,700.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
7,800.00	0.00	0.00	7,800.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
7,824.14	0.00	0.00	7,824.14	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Start Build 11.00										
7,850.00	2.85	181.98	7,849.99	-0.64	-0.02	0.64	11.00	11.00	0.00	0.00
7,900.00	8.35	181.98	7,899.73	-5.51	-0.19	5.52	11.00	11.00	0.00	0.00
7,950.00	13.85	181.98	7,948.78	-15.12	-0.52	15.13	11.00	11.00	0.00	0.00
8,000.00	19.35	181.98	7,996.68	-29.39	-1.02	29.41	11.00	11.00	0.00	0.00
8,050.00	24.85	181.98	8,042.99	-48.18	-1.67	48.21	11.00	11.00	0.00	0.00
8,100.00	30.35	181.98	8,087.28	-71.32	-2.46	71.36	11.00	11.00	0.00	0.00
8,150.00	35.85	181.98	8,129.16	-98.59	-3.41	98.65	11.00	11.00	0.00	0.00
8,200.00	41.35	181.98	8,168.22	-129.75	-4.48	129.83	11.00	11.00	0.00	0.00
8,250.00	46.85	181.98	8,204.11	-164.51	-5.69	164.61	11.00	11.00	0.00	0.00
8,300.00	52.35	181.98	8,236.51	-202.55	-7.00	202.67	11.00	11.00	0.00	0.00
8,350.00	57.85	181.98	8,265.11	-243.51	-8.42	243.66	11.00	11.00	0.00	0.00
8,400.00	63.35	181.98	8,289.65	-287.03	-9.92	287.20	11.00	11.00	0.00	0.00
8,450.00	68.85	181.98	8,309.90	-332.69	-11.50	332.89	11.00	11.00	0.00	0.00
8,500.00	74.35	181.98	8,325.68	-380.09	-13.14	380.32	11.00	11.00	0.00	0.00
8,550.00	79.85	181.98	8,336.85	-428.78	-14.82	429.04	11.00	11.00	0.00	0.00
8,600.00	85.35	181.98	8,343.29	-478.31	-16.53	478.60	11.00	11.00	0.00	0.00
8,640.80	89.83	181.98	8,345.00	-519.05	-17.94	519.36	11.00	11.00	0.00	0.00
Start 6881.09 hold at 8640.80 MD										
8,700.00	89.83	181.98	8,345.18	-578.21	-19.98	578.55	0.00	0.00	0.00	0.00
8,800.00	89.83	181.98	8,345.47	-678.15	-23.44	678.55	0.00	0.00	0.00	0.00
8,900.00	89.83	181.98	8,345.76	-778.09	-26.89	778.55	0.00	0.00	0.00	0.00
9,000.00	89.83	181.98	8,346.05	-878.03	-30.34	878.55	0.00	0.00	0.00	0.00
9,100.00	89.83	181.98	8,346.34	-977.97	-33.80	978.55	0.00	0.00	0.00	0.00
9,200.00	89.83	181.98	8,346.63	-1,077.91	-37.25	1,078.55	0.00	0.00	0.00	0.00
9,300.00	89.83	181.98	8,346.92	-1,177.85	-40.71	1,178.55	0.00	0.00	0.00	0.00
9,400.00	89.83	181.98	8,347.21	-1,277.79	-44.16	1,278.55	0.00	0.00	0.00	0.00

Archer Planning Report

Database	EDM R5000.1 MULTI	Local Co-ordinate Reference	Well 3H
Company	COG OPERATING, LLC	TVD Reference	3251'GL+19'KB @ 3270.00usft (McVay 6)
Project	Eddy County, NM	MD Reference	3251'GL+19'KB @ 3270.00usft (McVay 6)
Site	Solution Federal Com 3H	North Reference	Grid
Well	3H	Survey Calculation Method	Minimum Curvature
Wellbore	Lateral		
Design	Plan #1		

Planned Survey										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	
9,500.00	89.83	181.98	8,347.50	-1,377.73	-47.61	1,378.55	0.00	0.00	0.00	
9,600.00	89.83	181.98	8,347.79	-1,477.67	-51.07	1,478.55	0.00	0.00	0.00	
9,700.00	89.83	181.98	8,348.08	-1,577.61	-54.52	1,578.55	0.00	0.00	0.00	
9,800.00	89.83	181.98	8,348.37	-1,677.55	-57.97	1,678.55	0.00	0.00	0.00	
9,900.00	89.83	181.98	8,348.66	-1,777.49	-61.43	1,778.55	0.00	0.00	0.00	
10,000.00	89.83	181.98	8,348.95	-1,877.43	-64.88	1,878.55	0.00	0.00	0.00	
10,100.00	89.83	181.98	8,349.24	-1,977.37	-68.34	1,978.55	0.00	0.00	0.00	
10,200.00	89.83	181.98	8,349.53	-2,077.31	-71.79	2,078.55	0.00	0.00	0.00	
10,300.00	89.83	181.98	8,349.83	-2,177.25	-75.24	2,178.55	0.00	0.00	0.00	
10,400.00	89.83	181.98	8,350.12	-2,277.19	-78.70	2,278.55	0.00	0.00	0.00	
10,500.00	89.83	181.98	8,350.41	-2,377.13	-82.15	2,378.55	0.00	0.00	0.00	
10,600.00	89.83	181.98	8,350.70	-2,477.07	-85.61	2,478.55	0.00	0.00	0.00	
10,700.00	89.83	181.98	8,350.99	-2,577.01	-89.06	2,578.55	0.00	0.00	0.00	
10,800.00	89.83	181.98	8,351.28	-2,676.95	-92.51	2,678.54	0.00	0.00	0.00	
10,900.00	89.83	181.98	8,351.57	-2,776.89	-95.97	2,778.54	0.00	0.00	0.00	
11,000.00	89.83	181.98	8,351.86	-2,876.83	-99.42	2,878.54	0.00	0.00	0.00	
11,100.00	89.83	181.98	8,352.15	-2,976.77	-102.87	2,978.54	0.00	0.00	0.00	
11,200.00	89.83	181.98	8,352.44	-3,076.71	-106.33	3,078.54	0.00	0.00	0.00	
11,300.00	89.83	181.98	8,352.73	-3,176.65	-109.78	3,178.54	0.00	0.00	0.00	
11,400.00	89.83	181.98	8,353.02	-3,276.59	-113.24	3,278.54	0.00	0.00	0.00	
11,500.00	89.83	181.98	8,353.31	-3,376.53	-116.69	3,378.54	0.00	0.00	0.00	
11,600.00	89.83	181.98	8,353.60	-3,476.47	-120.14	3,478.54	0.00	0.00	0.00	
11,700.00	89.83	181.98	8,353.89	-3,576.41	-123.60	3,578.54	0.00	0.00	0.00	
11,800.00	89.83	181.98	8,354.18	-3,676.35	-127.05	3,678.54	0.00	0.00	0.00	
11,900.00	89.83	181.98	8,354.48	-3,776.29	-130.51	3,778.54	0.00	0.00	0.00	
12,000.00	89.83	181.98	8,354.77	-3,876.23	-133.96	3,878.54	0.00	0.00	0.00	
12,100.00	89.83	181.98	8,355.06	-3,976.17	-137.41	3,978.54	0.00	0.00	0.00	
12,200.00	89.83	181.98	8,355.35	-4,076.11	-140.87	4,078.54	0.00	0.00	0.00	
12,300.00	89.83	181.98	8,355.64	-4,176.05	-144.32	4,178.54	0.00	0.00	0.00	
12,400.00	89.83	181.98	8,355.93	-4,275.99	-147.77	4,278.54	0.00	0.00	0.00	
12,500.00	89.83	181.98	8,356.22	-4,375.93	-151.23	4,378.54	0.00	0.00	0.00	
12,600.00	89.83	181.98	8,356.51	-4,475.86	-154.68	4,478.54	0.00	0.00	0.00	
12,700.00	89.83	181.98	8,356.80	-4,575.80	-158.14	4,578.54	0.00	0.00	0.00	
12,800.00	89.83	181.98	8,357.09	-4,675.74	-161.59	4,678.54	0.00	0.00	0.00	
12,900.00	89.83	181.98	8,357.38	-4,775.68	-165.04	4,778.54	0.00	0.00	0.00	
13,000.00	89.83	181.98	8,357.67	-4,875.62	-168.50	4,878.54	0.00	0.00	0.00	
13,100.00	89.83	181.98	8,357.96	-4,975.56	-171.95	4,978.53	0.00	0.00	0.00	
13,200.00	89.83	181.98	8,358.25	-5,075.50	-175.41	5,078.53	0.00	0.00	0.00	
13,300.00	89.83	181.98	8,358.54	-5,175.44	-178.86	5,178.53	0.00	0.00	0.00	
13,400.00	89.83	181.98	8,358.83	-5,275.38	-182.31	5,278.53	0.00	0.00	0.00	
13,500.00	89.83	181.98	8,359.12	-5,375.32	-185.77	5,378.53	0.00	0.00	0.00	
13,600.00	89.83	181.98	8,359.42	-5,475.26	-189.22	5,478.53	0.00	0.00	0.00	
13,700.00	89.83	181.98	8,359.71	-5,575.20	-192.67	5,578.53	0.00	0.00	0.00	
13,800.00	89.83	181.98	8,360.00	-5,675.14	-196.13	5,678.53	0.00	0.00	0.00	
13,900.00	89.83	181.98	8,360.29	-5,775.08	-199.58	5,778.53	0.00	0.00	0.00	
14,000.00	89.83	181.98	8,360.58	-5,875.02	-203.04	5,878.53	0.00	0.00	0.00	
14,100.00	89.83	181.98	8,360.87	-5,974.96	-206.49	5,978.53	0.00	0.00	0.00	
14,200.00	89.83	181.98	8,361.16	-6,074.90	-209.94	6,078.53	0.00	0.00	0.00	
14,300.00	89.83	181.98	8,361.45	-6,174.84	-213.40	6,178.53	0.00	0.00	0.00	
14,400.00	89.83	181.98	8,361.74	-6,274.78	-216.85	6,278.53	0.00	0.00	0.00	
14,500.00	89.83	181.98	8,362.03	-6,374.72	-220.31	6,378.53	0.00	0.00	0.00	
14,600.00	89.83	181.98	8,362.32	-6,474.66	-223.76	6,478.53	0.00	0.00	0.00	
14,700.00	89.83	181.98	8,362.61	-6,574.60	-227.21	6,578.53	0.00	0.00	0.00	
14,800.00	89.83	181.98	8,362.90	-6,674.54	-230.67	6,678.53	0.00	0.00	0.00	

Archer Planning Report

Database:	EDM R5000.1 MULTI	Local Co-ordinate Reference:	Well 3H
Company:	COG OPERATING, LLC	TVD Reference:	3251'GL+19'KB @ .3270.00usft (McVay 6)
Project:	Eddy County, NM	MD Reference:	3251'GL+19'KB @ 3270.00usft. (McVay 6)
Site:	Solution Federal Com.3H	North Reference:	Grid
Well:	3H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Lateral		
Design:	Plan #1		

Planned Survey										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	
14,900.00	89.83	181.98	8,363.19	-6,774.48	-234.12	6,778.53	0.00	0.00	0.00	
15,000.00	89.83	181.98	8,363.48	-6,874.42	-237.57	6,878.53	0.00	0.00	0.00	
15,100.00	89.83	181.98	8,363.77	-6,974.36	-241.03	6,978.53	0.00	0.00	0.00	
15,200.00	89.83	181.98	8,364.06	-7,074.30	-244.48	7,078.53	0.00	0.00	0.00	
15,300.00	89.83	181.98	8,364.36	-7,174.24	-247.94	7,178.53	0.00	0.00	0.00	
15,400.00	89.83	181.98	8,364.65	-7,274.18	-251.39	7,278.53	0.00	0.00	0.00	
15,500.00	89.83	181.98	8,364.94	-7,374.12	-254.84	7,378.52	0.00	0.00	0.00	
15,521.89	89.83	181.98	8,365.00	-7,396.00	-255.60	7,400.42	0.00	0.00	0.00	
TD at 15521.89										

Design Targets										
Target Name	hit/miss target	Dip Angle (°)	Dip Dir (°)	TVD (usft)	+N/-S (usft)	+E/-W (usft)	Northing (usft)	Easting (usft)	Latitude	Longitude
Solution 3H PP		0.00	0.00	0.00	-140.12	-4.84	585,297.38	604,192.46	32° 36' 31.07 N	103° 59' 41.89 W
- plan misses target center by 140.21usft at 0.00usft MD (0.00 TVD, 0.00 N, 0.00 E)										
- Point										
Solution 3H Surface		0.00	0.00	0.00	0.00	0.00	585,437.50	604,197.30	32° 36' 32.46 N	103° 59' 41.83 W
- plan hits target center										
- Point										
Solution 3H PBHL		0.00	0.00	8,365.00	-7,396.00	-255.60	578,041.50	603,941.70	32° 35' 19.28 N	103° 59' 45.09 W
- plan hits target center										
- Point										

Plan Annotations					
Measured Depth (usft)	Vertical Depth (usft)	Local Coordinates		Comment	
		+N/-S (usft)	+E/-W (usft)		
7,824.14	7,824.14	0.00	0.00	Start Build 11.00	
8,640.80	8,345.00	-519.05	-17.94	Start 6881.09 hold at 8640.80 MD	
15,521.89	8,365.00	-7,396.00	-255.60	TD at 15521.89	

COG OPERATING, LLC

Field: Eddy County, NM
 Site: Solution Federal Com 3H
 Well: 3H
 Wellbore: Lateral
 Plan: Plan #1

Name	TVD	+N-S	+E-W	Northing	Easting	Latitude	Longitude	Shape
Solution 3H PP	0.00	-140.12	-4.84	585297.38	604192.46	32° 36' 31.07 N	103° 59' 41.89 W	Point
Solution 3H Surface	0.00	0.00	0.00	585437.50	604197.30	32° 36' 32.46 N	103° 59' 41.83 W	Point
Solution 3H PBHL	8365.00	-7396.00	-255.60	578041.50	603941.70	32° 35' 19.28 N	103° 59' 45.09 W	Point



SECTION DETAILS

Sec	MD	Inc	Azi	TVD	+N-S	+E-W	Dleg	TFace	Vsect	Target
1	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
2	7824.14	0.00	0.00	7824.14	0.00	0.00	0.00	0.00	0.00	
3	8640.80	89.83	181.98	8345.00	-519.05	-17.94	11.00	181.98	519.36	
4	15521.89	89.83	181.98	8365.00	-7396.00	-255.60	0.00	0.00	7400.42	Solution 3H PBHL







Azimuths to Grid North
 True North: -0.18°
 Magnetic North: 7.55°

Magnetic Field
 Strength: 48518.6snT
 Dip Angle: 60.53°
 Date: 10/9/2014
 Model: HDGM

Section Distances

Sec5, T20S, R30E
 SHL - Lot 3
 190'FNL, 2250'FWL
 PP
 330'FNL, 2244'FWL
 Sec8, T20S, R30E
 PBHL - Unit F
 2310'FNL, 1980'FWL



ARCHER DIRECTIONAL DRILLING SERVICES
 12101, Cutten Rd. Houston, Texas 77066
 Phone: 281-301-2600 Fax: 281-301-2795

Design: Plan #1 (3H/Lateral)
 Created By: Keith Noack
 Date: 14:18, October 09 2014

LLD ACREAGE REPORT

Admin State: NM
Geo State: NM

MTR: 23 0200S 0300E

Section: 005

Sur Type	Sur No	Lid Suff	NE	NW	SW	SE	Sur Note	Dup Flg	Sub Surf	Acreage
			NNSS	NNSS	NNSS	NNSS				
A			--XX	--XX	XXXX	XXXX				480.000
L	1		X---	----	----	----				39.690
L	2		-X--	----	----	----				39.850
L	3		----	X---	----	----				39.990
L	4		----	-X--	----	----				40.150

Section 005 Total: 639.680

MTR Total Excluding Survey Notes C/D/R
and Sub Surf = Y 639.680

Grand Total Excluding Survey Notes C/D/R
and Sub Surf = Y: 639.680



New Mexico Office of the State Engineer

Water Column/Average Depth to Water

No records found.

PLSS Search:

Section(s): 8

Township: 20S

Range: 30E



New Mexico Office of the State Engineer
Water Column/Average Depth to Water

No records found.

PLSS Search:

Section(s): 5

Township: 20S

Range: 30E



New Mexico Office of the State Engineer

Water Column/Average Depth to Water

(A CLW##### in the POD suffix indicates the POD has been replaced & no longer serves a water right file.)

(R=POD has been replaced,
O=orphaned,

C=the file is (quarters are 1=NW 2=NE 3=SW 4=SE)

closed) (quarters are smallest to largest) (NAD83 UTM in meters) (In feet)

POD Number	POD Sub-Code	basin	County	Q	Q	Q	Sec	Tws	Rng	X	Y	Depth Well	Depth Water	Water Column
CP 00419		ED		4	3	32	20S	30E		594250	3599003*	262	170	92
CP 00431		ED		2	3	33	20S	30E		595857	3599419*	235	195	40
CP 00532		ED		4	3	4	21	20S	30E	596328	3602138*	335	150	185
CP 00537		LE		3	1	1	36	20S	30E	600176	3600161*	3500		
CP 00551		ED		1	1	1	33	20S	30E	595343	3600320*	286	187	99
CP 00775		ED		2	1	4	11	20S	30E	599515	3605981*	350	40	310
CP 00834		LE		2	3	06	20S	30E		592566	3607436*	120		

Average Depth to Water: **148 feet**

Minimum Depth: **40 feet**

Maximum Depth: **195 feet**

Record Count: 7

PLSS Search:


Township: 20S

Range: 30E


*UTM location was derived from PLSS - see Help

The data is furnished by the NMOSE/ISC and is accepted by the recipient with the expressed understanding that the OSE/ISC make no warranties, expressed or implied, concerning the accuracy, completeness, reliability, usability, or suitability for any particular purpose of the data.


2,000 psi BOP Schematic




2,000 psi BOP Schematic




3,000 psi BOP Schematic



2M Choke Manifold Equipment




3M Choke Manifold Equipment



COG Operating LLC
Rig Plat & Closed Loop Equipment Diagram

Well pad will be 340' X 340' with
cellar in center of pad




"I further certify that COG will comply with Rule 19.15.17
NMAC by using a Closed Loop System."


COG Operating LLC
 Solution Federal Com #3H
 H₂S Equipment Schematic
 Terrain: Shinnery sand hills.

Well pad will be 340' X 340'
 with cellar in center of pad

□ Location Entry
 Condition Sign
 Primary egress



Secondary egress.



□ Primary Briefing Area w/SCBA

Company Representative's Trailer



Prevaling Wind Direction in SENM



COG OPERATING LLC
HYDROGEN SULFIDE DRILLING OPERATIONS PLAN

1. HYDROGEN SULFIDE TRAINING

All personnel, whether regularly assigned, contracted, or employed on an unscheduled basis, will receive training from a qualified instructor in the following areas prior to commencing drilling operations on this well:

- a. The hazards and characteristics of hydrogen sulfide (H₂S).
- b. The proper use and maintenance of personal protective equipment and life support systems.
- c. The proper use of H₂S detectors, alarms, warning systems, briefing areas, evacuation procedures, and prevailing winds.
- d. The proper techniques for first aid and rescue procedures.

In addition, supervisory personnel will be trained in the following areas:

- a. The effects of H₂S on metal components. If high tensile tubulars are to be used, personnel will be trained in their special maintenance requirements.
- b. Corrective action and shut-in procedures when drilling or reworking a well and blowout prevention and well control procedures.
- c. The contents and requirements of the H₂S Drilling Operations Plan and the Public Protection Plan.

There will be an initial training session just prior to encountering a known or probable H₂S zone (within 3 days or 500 feet) and weekly H₂S and well control drills for all personnel in each crew. The initial training session shall include a review of the site specific H₂S Drilling Operations Plan and the Public Protection Plan. This plan shall be available at the well site. All personnel will be required to carry documentation that they have received the proper training.

2. H₂S SAFETY EQUIPMENT AND SYSTEMS

Note: All H₂S safety equipment and systems will be installed, tested, and operational when drilling reaches a depth of 500 feet above, or three days prior to penetrating the first zone containing or reasonably expected to contain H₂S. If H₂S greater than 100 ppm is encountered in the gas stream we will shut in and install H₂S equipment.

- a. Well Control Equipment:
 - Flare line.
 - Choke manifold with remotely operated choke.
 - Blind rams and pipe rams to accommodate all pipe sizes with properly sized closing unit.
 - Auxiliary equipment to include: annular preventer, mud-gas separator, rotating head.

- b. Protective equipment for essential personnel:
Mark II Surviveair 30-minute units located in the dog house and at briefing areas.
- c. H2S detection and monitoring equipment:
2 - portable H2S monitor positioned on location for best coverage and response. These units have warning lights and audible sirens when H2S levels of 20 ppm are reached.
- d. Visual warning systems:
Caution/Danger signs shall be posted on roads providing direct access to location. Signs will be painted a high visibility yellow with black lettering of sufficient size to be readable at a reasonable distance from the immediate location. Bilingual signs will be used, when appropriate. See example attached.
- e. Mud Program:
The mud program has been designed to minimize the volume of H2S circulated to the surface.
- f. Metallurgy:
All drill strings, casings, tubing, wellhead, blowout preventers, drilling spool, kill lines, choke manifold and lines, and valves shall be suitable for H2S service.
- g. Communication:
Company vehicles equipped with cellular telephone.

COG OPERATING LLC has conducted a review to determine if an H2S contingency plan is required for the above referenced well. We were able to conclude that any potential hazardous volume would be minimal. H2S concentrations of wells in this area from surface to TD are low enough; therefore, we do not believe that an H2S contingency plan is necessary.

W A R N I N G

**YOU ARE ENTERING AN H₂S AREA
AUTHORIZED PERSONNEL ONLY**

- 1. BEARDS OR CONTACT LENSES NOT ALLOWED***
- 2. HARD HATS REQUIRED***
- 3. SMOKING IN DESIGNATED AREAS ONLY***
- 4. BE WIND CONSCIOUS AT ALL TIMES***
- 5. CK WITH COG OPERATING LLC FOREMAN AT MAIN OFFICE***

COG OPERATING LLC

1-575-748-6940

EMERGENCY CALL LIST


	<u>OFFICE</u>	<u>MOBILE</u>
COG OPERATING LLC OFFICE	575-748-6940	
SHERYL BAKER	575-748-6940	432-934-1873
KENT GREENWAY	575-746-2010	432-557-1694
SETH WILD	432-683-7443	432-528-3633
WALTER ROYE	575-748-6940	432-934-1886

EMERGENCY RESPONSE NUMBERS

	<u>OFFICE</u>
STATE POLICE	575-748-9718
EDDY COUNTY SHERIFF	575-746-2701
EMERGENCY MEDICAL SERVICES (AMBULANCE)	911 or 575-746-2701
EDDY COUNTY EMERGENCY MANAGEMENT (HARRY BURGESS)	575-887-9511
STATE EMERGENCY RESPONSE CENTER (SERC)	575-476-9620
CARLSBAD POLICE DEPARTMENT	575-885-2111
CARLSBAD FIRE DEPARTMENT	575-885-3125
NEW MEXICO OIL CONSERVATION DIVISION	575-748-1283
INDIAN FIRE & SAFETY	800-530-8693
HALLIBURTON SERVICES	800-844-8451

Production Facility Layout
 Solution Federal Com #3H.
 Section 5 - T20S - R30E

Exhibit 3



Surface Use Plan of Operations

Introduction

The following surface use plan of operations will be followed and carried out once the APD is approved. No other disturbance will be created other than what was submitted in this surface use plan. If any other surface disturbance is needed after the APD is approved, a BLM approved sundry notice or right of way application will be acquired prior to any new surface disturbance.

Before any surface disturbance is created, stakes or flagging will be installed to mark boundaries of permitted areas of disturbance, including soils storage areas. As necessary, slope, grade, and other construction control stakes will be placed to ensure construction in accordance with the surface use plan. All boundary markers will be maintained in place until final construction cleanup is completed. If disturbance boundary markers are disturbed or knocked down, they will be replaced before construction proceeds.


If terms and conditions are attached to the approved APD and amend any of the proposed actions in this surface use plan, we will adhere to the terms and conditions.

1. Existing Roads

- a. The existing access road route to the proposed project is depicted on Exhibit 2. Improvements to the driving surface will be done where necessary. No new surface disturbance will be done, unless otherwise noted in the New or Reconstructed Access Roads section of this surface use plan.
- b. The existing access road route to the proposed project does cross lease boundaries and a BLM road right-of-way will be acquired from the BLM prior to construction activities.
- c. The operator will improve or maintain existing roads in a condition the same as or better than before operations begin. The operator will repair pot holes, clear ditches, repair the crown, etc. All existing structures on the entire access route such as cattleguards, other range improvement projects, culverts, etc. will be properly repaired or replaced if they are damaged or have deteriorated beyond practical use.
- d. We will prevent and abate fugitive dust as needed, whether created by vehicular traffic, equipment operations, or wind events. BLM written approval will be acquired before application of surfactants, binding agents, or other dust suppression chemicals on roadways.

2. New or Reconstructed Access Roads

- a. An access road will be needed for this proposed project. See the survey plat for the location of the access road.
- b. The length of access road needed to be constructed for this proposed project is about 433 feet.
- c. The maximum driving width of the access road will be 14 feet. The maximum width of surface disturbance when constructing the access road will not exceed 25 feet. All areas outside of the driving surface will be revegetated.
- d. The access road will be constructed with 6 inches of compacted Caliche.
- e. When the road travels on fairly level ground, the road will be crowned and ditched with a 2% slope from the tip of the road crown to the edge of the driving surface. The ditches will be 3 feet wide with 3:1 slopes. See Road Cross Section diagram below.



- f. The access road will be constructed with a ditch on each side of the road.
- g. The maximum grade for the access road will be 1 percent.
- h. No turnouts will be constructed on the proposed access road.
- i. No cattleguards will be installed for this proposed access road.
- j. No BLM right-of-way grant is needed for the construction of this access road.
- k. No culverts will be constructed for this proposed access road.
- l. No low water crossings will be constructed for the access road.
- m. Lead-off ditches will be constructed on the access road to divert water and prevent excessive erosion! Each lead-off ditch will be 6 inches deep and have a 6 inch berm above natural ground on the down hill slope. Each lead-off ditch will be graded to drain water with a 1 percent minimum to 3 percent maximum ditch slope. Lead-off ditches will not extend more than 10 feet off the road edge.
- n. Newly constructed or reconstructed roads, on surface under the jurisdiction of the Bureau of Land Management, will be constructed as outlined in the BLM "Gold Book" and to meet the standards of the anticipated traffic flow and all anticipated weather requirements as needed. Construction will include ditching, draining, crowning and capping or sloping and dipping the roadbed as necessary to provide a well-constructed and safe road.

3. Location of Existing Wells

- a. Exhibit 4 of the APD depicts all known wells within a one mile radius of the proposed well.
- b. 1 mile well data.

4. Location of Existing and/or Proposed Production Facilities

- a. All permanent, lasting more than 6 months, above ground structures including but not limited to pumpjacks, storage tanks, barrels, pipeline risers, meter housing, etc. that are not subject to safety requirements will be painted a non-reflective paint color, Shale Green, from the BLM Standard Environmental Colors chart, unless another color is required in the APD Conditions of Approval.
- b. If any type of production facilities are located on the well pad, they will be strategically placed to allow for maximum interim reclamation, recontouring, and revegetation of the well location.
- c. A production facility is proposed to be installed on the proposed well location. Production from the well will be processed on site in the production facility. Exhibit 3 depicts the location of the production facilities as they relate to the well and well pad.
- d. The proposed production facility will have a secondary containment structure that is constructed to hold the capacity of 1-1/2 times the largest tank, plus freeboard to account for percipitation, unless more stringent

protective requirements are deemed necessary.

e. There is no other diagram that depicts production facilities.

If any plans change regarding the production facility or other infrastructure (pipeline, electric line, etc.), we will submit a sundry notice or right of way (if applicable) prior to installation or construction.

Electric Line(s)

a. An electric line will be applied for through a sundry notice or BLM right of way at a later date.

5. Location and Types of Water

a. The location of the water well is as follows: Contractors water well.

b. The operator will use established or constructed oil and gas roads to transport water to the well site. The operator will try to utilize the identified access route in the surface use plan.

6. Construction Material

a. Caliche from approved Federal or State pit.

7. Methods for Handling Waste

a. Drilling fluids and produced oil and water from the well during drilling and completion operations will be stored safely and disposed of properly in an NMOCD approved disposal facility.

b. Garbage and trash produced during drilling and completion operations will be collected in a trash container and disposed of properly at a state approved disposal facility. All trash on and around the well site will be collected for disposal.

c. Human waste and grey water will be properly contained and disposed of properly at a state approved disposal facility.

d. After drilling and completion operations, trash, chemicals, salts, frac sand and other waste material will be removed and disposed of properly at a state approved disposal facility.

e. The well will be drilled utilizing a closed loop system. Drill cutting will be properly disposed of into steel tanks and taken to an NMOCD approved disposal facility.

8. Ancillary Facilities

a. No ancillary facilities will be needed for this proposed project.

9. Well Site Layout

a. The following information is presented in the well site survey plat or diagram:

i. reasonable scale (near 1":50')

ii. well pad dimensions

iii. well pad orientation

iv. drilling rig components

v. proposed access road

- vi. elevations of all points
 - vii. topsoil stockpile
 - viii. reserve pit location/dimensions if applicable
 - ix. other disturbances needed (flare pit, stinger, frac farm pad, etc.)
 - x. existing structures within the 600' x 600' archaeological surveyed area (pipelines, electric lines, well pads, etc)
- b. The proposed drilling pad was staked and surveyed by a professional surveyor. The attached survey plat of the well site depicts the drilling pad layout as staked.
- c. The submitted survey plat does depict all the necessary information required by Onshore Order No. 1.
- d. Topsoil Salvaging
- i. Grass, forbs, and small woody vegetation, such as mesquite will be excavated as the topsoil is removed. Large woody vegetation will be stripped and stored separately and respread evenly on the site following topsoil respreading. Topsoil depth is defined as the top layer of soil that contains 80% of the roots. In areas to be heavily disturbed, the top 6 inches of soil material, will be stripped and stockpiled on the perimeter of the well location and along the perimeter of the access road to control run-on and run-off, to keep topsoil viable, and to make redistribution of topsoil more efficient during interim reclamation. Stockpiled topsoil should include vegetative material. Topsoil will be clearly segregated and stored separately from subsoils. Contaminated soil will not be stockpiled, but properly treated and handled prior to topsoil salvaging.

10. Plans for Surface Reclamation

Reclamation Objectives

- i. The objective of interim reclamation is to restore vegetative cover and a portion of the landform sufficient to maintain healthy, biologically active topsoil; control erosion; and minimize habitat and forage loss, visual impact, and weed infestation, during the life of the well or facilities.
- ii. The long-term objective of final reclamation is to return the land to a condition similar to what existed prior to disturbance. This includes restoration of the landform and natural vegetative community, hydrologic systems, visual resources, and wildlife habitats. To ensure that the long-term objective will be reached through human and natural processes, actions will be taken to ensure standards are met for site stability, visual quality, hydrological functioning, and vegetative productivity.
- iii. The BLM will be notified at least 3 days prior to commencement of any reclamation procedures.
- iv. If circumstances allow, interim reclamation and/or final reclamation actions will be completed no later than 6 months from when the final well on the location has been completed or plugged. We will gain written permission from the BLM if more time is needed.
- v. Interim reclamation will be performed on the well site after the well is drilled and completed. Exhibit 3 depicts the location and dimensions of the planned interim reclamation for the well site.

Interim Reclamation Procedures (If performed)

1. Within 30 days of well completion, the well location and surrounding areas will be cleared of, and maintained free of, all materials, trash, and equipment not required for production.
2. In areas planned for interim reclamation, all the surfacing material will be removed and returned to the original mineral pit or recycled to repair or build roads and well pads.
3. The areas planned for interim reclamation will then be recontoured to the original contour if feasible,

or if not feasible, to an interim contour that blends with the surrounding topography as much as possible. Where applicable, the fill material of the well pad will be backfilled into the cut to bring the area back to the original contour. The interim cut and fill slopes prior to re-seeding will not be steeper than a 3:1 ratio, unless the adjacent native topography is steeper. Note: Constructed slopes may be much steeper during drilling, but will be recontoured to the above ratios during interim reclamation.

4. Topsoil will be evenly respread and aggressively revegetated over the entire disturbed area not needed for all-weather operations including cuts & fills. To seed the area, the proper BLM seed mixture, free of noxious weeds, will be used. Final seedbed preparation will consist of contour cultivating to a depth of 4 to 6 inches within 24 hours prior to seeding, dozer tracking, or other imprinting in order to break the soil crust and create seed germination micro-sites.

5. Proper erosion control methods will be used on the area to control erosion, runoff and siltation of the surrounding area.

6. The interim reclamation will be monitored periodically to ensure that vegetation has reestablished and that erosion is controlled.

Final Reclamation (well pad, buried pipelines, etc.)

1. Prior to final reclamation procedures, the well pad, road, and surrounding area will be cleared of material, trash, and equipment.

2. All surfacing material will be removed and returned to the original mineral pit or recycled to repair or build roads and well pads.

3. All disturbed areas, including roads, pipelines, pads, production facilities, and interim reclaimed areas will be recontoured to the contour existing prior to initial construction or a contour that blends indistinguishably with the surrounding landscape. Topsoil that was spread over the interim reclamation areas will be stockpiled prior to recontouring. The topsoil will be redistributed evenly over the entire disturbed site to ensure successful revegetation.

4. After all the disturbed areas have been properly prepared, the areas will be seeded with the proper BLM seed mixture, free of noxious weeds. Final seedbed preparation will consist of contour cultivating to a depth of 4 to 6 inches within 24 hours prior to seeding, dozer tracking, or other imprinting in order to break the soil crust and create seed germination micro-sites.

5. Proper erosion control methods will be used on the entire area to control erosion, runoff and siltation of the surrounding area.

6. All unused equipment and structures including pipelines, electric line poles, tanks, etc. that serviced the well will be removed.

7. All reclaimed areas will be monitored periodically to ensure that revegetation occurs, that the area is not redisturbed, and that erosion is controlled.

11. Surface Ownership

- a. The surface ownership of the proposed project is U. S. Government.

12. Other Information

- a. A. The area around the well site is grassland and the topsoil is sandy. The vegetation is moderately sparse with native prairie grasses, some mesquite and shinnery oak. No wildlife was observed but it is likely that mule deer, rabbits, coyotes and rodents traverse the area.

B. There is no permanent or live water in the immediate area.

C. There are no dwellings within 2 miles of this location.

D. If needed, a Cultural Resources Examination is being prepared by Boone Arch Services of NM, LLC., 2030 North Canal, Carlsbad, New Mexico, 88220, phone # 575-885-1352 and the results will be forwarded to your office in the near future. Otherwise, COG will be participating in the Permian Basin MOA Program.

13. Maps and Diagrams

Exhibit 2 - Existing Road

Exhibit 4 - Wells Within One Mile

Exhibit 3 - Production Facilities Diagram

Exhibit 3 - Interim Reclamation

PECOS DISTRICT CONDITIONS OF APPROVAL

OPERATOR'S NAME:	COG Operating, LLC
LEASE NO.:	NMNM-0429170
WELL NAME & NO.:	Solution Federal Com 3H
SURFACE HOLE FOOTAGE:	0190' FNL & 2250' FWL
BOTTOM HOLE FOOTAGE:	2310' FNL & 1980' FWL Sec. 08, T. 20 S., R 30 E.
LOCATION:	Section 05, T. 20 S., R 30 E., NMPM
COUNTY:	Eddy County, New Mexico

TABLE OF CONTENTS

Standard Conditions of Approval (COA) apply to this APD. If any deviations to these standards exist or special COAs are required, the section with the deviation or requirement will be checked below.

- General Provisions**
- Permit Expiration**
- Archaeology, Paleontology, and Historical Sites**
- Noxious Weeds**
- Special Requirements**
 - Communitization Agreement
 - Ground-level Abandoned Well Marker
 - Cave/Karst
- Construction**
 - Notification
 - Topsoil
 - Closed Loop System
 - Federal Mineral Material Pits
 - Well Pads
 - Roads
- Road Section Diagram**
- Drilling**
 - Cement Requirements
 - H2S Requirements
 - R-111-P Potash
 - High Cave/Karst
 - Capitan Reef
 - Logging Requirements
 - Waste Material and Fluids
- Production (Post Drilling)**
 - Well Structures & Facilities
- Interim Reclamation**
- Final Abandonment & Reclamation**

I. GENERAL PROVISIONS

The approval of the Application For Permit To Drill (APD) is in compliance with all applicable laws and regulations: 43 Code of Federal Regulations 3160, the lease terms, Onshore Oil and Gas Orders, Notices To Lessees, New Mexico Oil Conservation Division (NMOCD) Rules, National Historical Preservation Act As Amended, and instructions and orders of the Authorized Officer. Any request for a variance shall be submitted to the Authorized Officer on Form 3160-5, Sundry Notices and Report on Wells.

II. PERMIT EXPIRATION

If the permit terminates prior to drilling and drilling cannot be commenced within 60 days after expiration, an operator is required to submit Form 3160-5, Sundry Notices and Reports on Wells, requesting surface reclamation requirements for any surface disturbance. However, if the operator will be able to initiate drilling within 60 days after the expiration of the permit, the operator must have set the conductor pipe in order to allow for an extension of 60 days beyond the expiration date of the APD. (Filing of a Sundry Notice is required for this 60 day extension.)

III. ARCHAEOLOGICAL, PALEONTOLOGY & HISTORICAL SITES

Any cultural and/or paleontological resource discovered by the operator or by any person working on the operator's behalf shall immediately report such findings to the Authorized Officer. The operator is fully accountable for the actions of their contractors and subcontractors. The operator shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery shall be made by the Authorized Officer to determine the appropriate actions that shall be required to prevent the loss of significant cultural or scientific values of the discovery. The operator shall be held responsible for the cost of the proper mitigation measures that the Authorized Officer assesses after consultation with the operator on the evaluation and decisions of the discovery. Any unauthorized collection or disturbance of cultural or paleontological resources may result in a shutdown order by the Authorized Officer.

IV. NOXIOUS WEEDS

The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes the roads, pads, associated pipeline corridor, and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

V. SPECIAL REQUIREMENT(S)

Communitization Agreement

A Communitization Agreement covering the acreage dedicated to this well must be filed for approval with the BLM. The effective date of the agreement shall be prior to any sales. In addition, the well sign shall include the surface and bottom hole lease numbers. If the Communitization Agreement number is known, it shall also be on the sign. If not, it shall be placed on the sign when the sign is replaced.

Cave and Karst

** Depending on location, additional Drilling, Casing, and Cementing procedures may be required by engineering to protect critical karst groundwater recharge areas.

Cave/Karst Surface Mitigation

The following stipulations will be applied to minimize impacts during construction, drilling and production.

Construction:

In the advent that any underground voids are opened up during construction activities, construction activities will be halted and the BLM will be notified immediately.

No Blasting:

No blasting will be utilized for pad construction. The pad will be constructed and leveled by adding the necessary fill and caliche.

Pad Berming:

The entire perimeter of the well pad will be bermed to prevent oil, salt, and other chemical contaminants from leaving the well pad.

- The compacted berm shall be constructed at a minimum of 12 inches high with impermeable mineral material (e.g. caliche).
- No water flow from the uphill side(s) of the pad shall be allowed to enter the well pad.
- The topsoil stockpile shall be located outside the bermed well pad.
- Topsoil, either from the well pad or surrounding area, shall not be used to construct the berm.
- No storm drains, tubing or openings shall be placed in the berm.
- If fluid collects within the bermed area, the fluid must be vacuumed into a safe container and disposed of properly at a state approved facility.
- The integrity of the berm shall be maintained around the surfaced pad throughout the life of the well and around the downsized pad after interim reclamation has been completed.
- Any access road entering the well pad shall be constructed so that the integrity of the berm height surrounding the well pad is not compromised. (Any access road crossing the berm cannot be lower than the berm height.)

Tank Battery Liners and Berms:

Tank battery locations and all facilities will be lined and bermed. A 20 mil permanent liner will be installed with a 4 oz. felt backing to prevent tears or punctures. Tank battery berms must be large enough to contain 1 ½ times the content of the largest tank.

Leak Detection System:

A method of detecting leaks is required. The method could incorporate gauges to measure loss, situate valves and lines so they can be visually inspected, or installing electronic sensors to alarm when a leak is present. Leak detection plan will be submitted to BLM for approval.

Automatic Shut-off Systems:

Automatic shut off, check valves, or similar systems will be installed for pipelines and tanks to minimize the effects of catastrophic line failures used in production or drilling.

Cave/Karst Subsurface Mitigation

The following stipulations will be applied to protect cave/karst and ground water concerns:

Rotary Drilling with Fresh Water:

Fresh water will be used as a circulating medium in zones where caves or karst features are expected. SEE ALSO: Drilling COAs for this well.

Directional Drilling:

Kick off for directional drilling will occur at least 100 feet below the bottom of the cave occurrence zone. SEE ALSO: Drilling COAs for this well.

Lost Circulation:

ALL lost circulation zones from the surface to the base of the cave occurrence zone will be logged and reported in the drilling report.

Regardless of the type of drilling machinery used, if a void of four feet or more and circulation losses greater than 70 percent occur simultaneously while drilling in any cave-bearing zone, the BLM will be notified immediately by the operator. The BLM will assess the situation and work with the operator on corrective actions to resolve the problem.

Abandonment Cementing:

Upon well abandonment in high cave karst areas additional plugging conditions of approval may be required. The BLM will assess the situation and work with the operator to ensure proper plugging of the wellbore.

Pressure Testing:

Annual pressure monitoring will be performed by the operator on all casing annuli and reported in a sundry notice. If the test results indicated a casing failure has occurred, remedial action will be undertaken to correct the problem to the BLM's approval.

VI. CONSTRUCTION

A. NOTIFICATION

The BLM shall administer compliance and monitor construction of the access road and well pad. Notify the Carlsbad Field Office at (575) 234-5909 at least 3 working days prior to commencing construction of the access road and/or well pad.

When construction operations are being conducted on this well, the operator shall have the approved APD and Conditions of Approval (COA) on the well site and they shall be made available upon request by the Authorized Officer.

B. TOPSOIL

The operator shall strip the top portion of the soil (root zone) from the entire well pad area and stockpile the topsoil along the edge of the well pad as depicted in the APD. The root zone is typically six (6) inches in depth. All the stockpiled topsoil will be redistributed over the interim reclamation areas. Topsoil shall not be used for berming the pad or facilities. For final reclamation, the topsoil shall be spread over the entire pad area for seeding preparation.

Other subsoil (below six inches) stockpiles must be completely segregated from the topsoil stockpile. Large rocks or subsoil clods (not evident in the surrounding terrain) must be buried within the approved area for interim and final reclamation.

C. CLOSED LOOP SYSTEM

Tanks are required for drilling operations: No Pits.

The operator shall properly dispose of drilling contents at an authorized disposal site.

D. FEDERAL MINERAL MATERIALS PIT

Payment shall be made to the BLM prior to removal of any federal mineral materials. Call the Carlsbad Field Office at (575) 234-5972.

E. WELL PAD SURFACING

Surfacing of the well pad is not required.

If the operator elects to surface the well pad, the surfacing material may be required to be removed at the time of reclamation. The well pad shall be constructed in a manner which creates the smallest possible surface disturbance, consistent with safety and operational needs.

F. EXCLOSURE FENCING (CELLARS & PITS)

Exclosure Fencing

The operator will install and maintain exclosure fencing for all open well cellars to prevent access to public, livestock, and large forms of wildlife before and after drilling operations until the pit is free of fluids and the operator initiates backfilling. (For examples of exclosure fencing design, refer to BLM's Oil and Gas Gold Book, Exclosure Fence Illustrations, Figure 1, Page 18.)

G. ON LEASE ACCESS ROADS**Road Width**

The access road shall have a driving surface that creates the smallest possible surface disturbance and does not exceed fourteen (14) feet in width. The maximum width of surface disturbance, when constructing the access road, shall not exceed twenty-five (25) feet.

Surfacing

Surfacing material is not required on the new access road driving surface. If the operator elects to surface the new access road or pad, the surfacing material may be required to be removed at the time of reclamation.

Where possible, no improvements should be made on the unsurfaced access road other than to remove vegetation as necessary, road irregularities, safety issues, or to fill low areas that may sustain standing water.

The Authorized Officer reserves the right to require surfacing of any portion of the access road at any time deemed necessary. Surfacing may be required in the event the road deteriorates, erodes, road traffic increases, or it is determined to be beneficial for future field development. The surfacing depth and type of material will be determined at the time of notification.

Crowning

Crowning shall be done on the access road driving surface. The road crown shall have a grade of approximately 2% (i.e., a 1" crown on a 14' wide road). The road shall conform to Figure 1; cross section and plans for typical road construction.

Ditching

Ditching shall be required on both sides of the road.

Turnouts


Vehicle turnouts shall be constructed on the road. Turnouts shall be intervisible with interval spacing distance less than 1000 feet. Turnouts shall conform to Figure 1; cross section and plans for typical road construction.

Drainage

Drainage control systems shall be constructed on the entire length of road (e.g. ditches, sidehill outsloping and insloping, lead-off ditches, culvert installation, and low water crossings).

A typical lead-off ditch has a minimum depth of 1 foot below and a berm of 6 inches above natural ground level. The berm shall be on the down-slope side of the lead-off ditch.

Cross Section of a Typical Lead-off Ditch



All lead-off ditches shall be graded to drain water with a 1 percent minimum to 3 percent maximum ditch slope. The spacing interval are variable for lead-off ditches and shall be determined according to the formula for spacing intervals of lead-off ditches, but may be amended depending upon existing soil types and centerline road slope (in %);

Formula for Spacing Interval of Lead-off Ditches

Example - On a 4% road slope that is 400 feet long, the water flow shall drain water into a lead-off ditch. Spacing interval shall be determined by the following formula:

$$400 \text{ foot road with } 4\% \text{ road slope: } \frac{400'}{4\%} + 100' = 200' \text{ lead-off ditch interval}$$

Cattleguards

An appropriately sized cattleguard sufficient to carry out the project shall be installed and maintained at fence/road crossings. Any existing cattleguards on the access road route shall be repaired or replaced if they are damaged or have deteriorated beyond practical use. The operator shall be responsible for the condition of the existing cattleguards that are in place and are utilized during lease operations.

Fence Requirement

Where entry is granted across a fence line, the fence shall be braced and tied off on both sides of the passageway prior to cutting. The operator shall notify the private surface landowner or the grazing allotment holder prior to crossing any fences.

Public Access

Public access on this road shall not be restricted by the operator without specific written approval granted by the Authorized Officer.

Construction Steps

1. Salvage topsoil
2. Construct road

3. Redistribute topsoil
4. Revegetate slopes




Figure 1. Cross-sections and plans for typical road sections representative of BLM resource or FS local and higher-class roads.

VII. DRILLING

A. DRILLING OPERATIONS REQUIREMENTS

The BLM is to be notified in advance for a representative to witness:

- a. Spudding well (minimum of 24 hours)
- b. Setting and/or Cementing of all casing strings (minimum of 4 hours)
- c. BOPE tests (minimum of 4 hours)

Eddy County

Call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220,
(575) 361-2822

1. **Hydrogen Sulfide (H₂S) monitors shall be installed prior to drilling out the surface shoe. If H₂S is detected in concentrations greater than 100 ppm, the Hydrogen Sulfide area shall meet Onshore Order 6 requirements, which includes equipment and personnel/public protection items. If Hydrogen Sulfide is encountered, provide measured values and formations to the BLM.**
2. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval. **If the drilling rig is removed without approval – an Incident of Non-Compliance will be written and will be a “Major” violation.**
3. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works is located, this does not include the dog house or stairway area.
4. **The record of the drilling rate along with the GR/N well log run from TD to surface (horizontal well – vertical portion of hole) shall be submitted to the BLM office as well as all other logs run on the borehole 30 days from completion. If available, a digital copy of the logs is to be submitted in addition to the paper copies. The Rustler top and top and bottom of Salt are to be recorded on the Completion Report.**

B. CASING

Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size or are Non-API. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need prior approval if the altered cement plan has less

volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.). The initial wellhead installed on the well will remain on the well with spools used as needed.

Centralizers required on surface casing per Onshore Order 2.III.B.1.f.

Wait on cement (WOC) for Potash Areas:

After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi for all cement blends, 2) until cement has been in place at least **24 hours**. WOC time will be recorded in the driller's log.

No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.

R-111- P Potash

High Cave/Karst

Capitan Reef

Possibility of water flows in the Artesia Group and Salado.

Possibility of lost circulation in the Artesia Group, Capitan Reef, and Delaware.

A MINIMUM OF TWO CASING STRINGS CEMENTED TO SURFACE IS REQUIRED IN HIGH CAVE/KARST AREAS. THE CEMENT MUST BE IN A SOLID SHEATH. THEREFORE, ONE INCH OPERATIONS ARE NOT SUFFICIENT TO PROTECT CAVE KARST RESOURCES. A CASING DESIGN THAT HAS A ONE INCH JOB PERFORMED DOES NOT COUNT AS A SOLID SHEATH.

1. The **20** inch surface casing shall be set at approximately **350** feet and cemented to the surface. **If salt is encountered, set casing at least 25 feet above the salt.**
 - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.
 - b. **Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry.**
 - c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.

- d. If cement falls back, remedial cementing will be done prior to drilling out that string.
2. The minimum required fill of cement behind the 13-3/8 inch 1st intermediate casing, which shall be set at approximately 1680 feet (**Top of Seven Rivers formation**), is:

Cement to surface. If cement does not circulate see B.1.a, c-d above. **Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to cave/karst and potash.**

3. The minimum required fill of cement behind the 9-5/8 inch 2nd intermediate casing is:

Operator has proposed DV tool at depth of 1947', but will adjust cement proportionately if moved. DV tool shall be set a minimum of 50' below previous shoe and a minimum of 200' above current shoe. Operator shall submit sundry if DV tool depth cannot be set in this range. If an ECP is used, it is to be set a minimum of 50' below the shoe to provide cement across the shoe. If it cannot be set below the shoe, a CBL shall be run to verify cement coverage.

- a. First stage to DV tool:

Cement to circulate. If cement does not circulate, contact the appropriate BLM office before proceeding with second stage cement job. Operator should have plans as to how they will achieve circulation on the next stage.

- b. Second stage above DV tool:

Cement to surface. If cement does not circulate see B.1.a, c-d above. **Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to Capitan Reef and potash.**

Centralizers required on horizontal leg, must be type for horizontal service and a minimum of one every other joint.

4. The minimum required fill of cement behind the 7 X 5-1/2 inch production casing is:

Cement to surface. If cement does not circulate, contact the appropriate BLM office.

5. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.
6. Whenever a casing string is cemented in the R-111-P potash area, the NMOCD requirements shall be followed.

C. PRESSURE CONTROL

1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in Onshore Oil and Gas Order No. 2 and API 53.
2. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be **2000 (2M)** psi.
 - a. **For surface casing only:** If the BOP/BOPE is to be tested against casing, the wait on cement (WOC) time for that casing is to be met (see WOC statement at start of casing section). Independent service company required.
3. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the **9-5/8 2nd** intermediate casing shoe shall be **3000 (3M)** psi.
4. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.
 - a. In potash areas, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. For all casing strings, casing cut-off and BOP installation can be initiated at twelve hours after bumping the plug. However, **no tests** shall commence until the cement has had a minimum of 24 hours setup time.
 - b. The tests shall be done by an independent service company utilizing a test plug **not a cup or J-packer**. The operator also has the option of utilizing an independent tester to test without a plug (i.e. against the casing) pursuant to Onshore Order 2 with the pressure not to exceed 70% of the burst rating for the casing. Any test against the casing must meet the WOC time for water basin (8 hours) or potash (24 hours) or 500 pounds compressive strength, whichever is greater, prior to initiating the test (see casing segment as lead cement may be critical item).
 - c. The test shall be run on a 5000 psi chart for a 2-3M BOP/BOP, on a 10000 psi chart for a 5M BOP/BOPE and on a 15000 psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one hour chart. A circular chart shall have a maximum 2 hour clock. If a twelve hour or twenty-four hour chart is used, tester shall make a notation that it is run with a two hour clock.
 - d. The results of the test shall be reported to the appropriate BLM office.
 - e. All tests are required to be recorded on a calibrated test chart. **A copy of the BOP/BOPE test chart and a copy of independent service company test**

will be submitted to the appropriate BLM office.

- f. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug. This test shall be performed prior to the test at full stack pressure.

D. DRILL STEM TEST

If drill stem tests are performed, Onshore Order 2.III.D shall be followed.

E. WASTE MATERIAL AND FLUIDS

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area.

Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.

JAM 071315

VIII. PRODUCTION (POST DRILLING)

A. WELL STRUCTURES & FACILITIES

Placement of Production Facilities

Production facilities should be placed on the well pad to allow for maximum interim recontouring and revegetation of the well location.

Exclosure Netting (Open-top Tanks)

Immediately following active drilling or completion operations, the operator will take actions necessary to prevent wildlife and livestock access, including avian wildlife, to all open-topped tanks that contain or have the potential to contain salinity sufficient to cause harm to wildlife or livestock, hydrocarbons, or Resource Conservation and Recovery Act of 1976-exempt hazardous substances. At a minimum, the operator will net, screen, or cover open-topped tanks to exclude wildlife and livestock and prevent mortality. If the operator uses netting, the operator will cover and secure the open portion of the tank to prevent wildlife entry. The operator will net, screen, or cover the tanks until the operator removes the tanks from the location or the tanks no longer contain substances that could be harmful to wildlife or livestock. Use a maximum netting mesh size of 1 ½ inches. The netting must not be in contact with fluids and must not have holes or gaps.

Chemical and Fuel Secondary Containment and Exclosure Screening

The operator will prevent all hazardous, poisonous, flammable, and toxic substances from coming into contact with soil and water. At a minimum, the operator will install and maintain an impervious secondary containment system for any tank or barrel containing hazardous, poisonous, flammable, or toxic substances sufficient to contain the contents of the tank or barrel and any drips, leaks, and anticipated precipitation. The operator will dispose of fluids within the containment system that do not meet applicable state or U. S. Environmental Protection Agency livestock water standards in accordance with state law; the operator must not drain the fluids to the soil or ground. The operator will design, construct, and maintain all secondary containment systems to prevent wildlife and livestock exposure to harmful substances. At a minimum, the operator will install effective wildlife and livestock enclosure systems such as fencing, netting, expanded metal mesh, lids, and grate covers. Use a maximum netting mesh size of 1 ½ inches.

Open-Vent Exhaust Stack Enclosures

The operator will construct, modify, equip, and maintain all open-vent exhaust stacks on production equipment to prevent birds and bats from entering, and to discourage perching, roosting, and nesting. (*Recommended enclosure structures on open-vent exhaust stacks are in the shape of a cone.*) Production equipment includes, but may not be limited to, tanks, heater-treaters, separators, dehydrators, flare stacks, in-line units, and compressor mufflers.

Containment Structures

Proposed production facilities such as storage tanks and other vessels will have a secondary containment structure that is constructed to hold the capacity of 1.5 times the largest tank, plus freeboard to account for precipitation, unless more stringent protective requirements are deemed necessary.

Painting Requirement

All above-ground structures including meter housing that are not subject to safety requirements shall be painted a flat non-reflective paint color, **Shale Green** from the BLM Standard Environmental Color Chart (CC-001: June 2008).

IX. INTERIM RECLAMATION

During the life of the development, all disturbed areas not needed for active support of production operations should undergo interim reclamation in order to minimize the environmental impacts of development on other resources and uses.

Within six (6) months of well completion, operators should work with BLM surface management specialists (Jim Amos: 575-234-5909) to devise the best strategies to reduce the size of the location. Interim reclamation should allow for remedial well operations, as well as safe and efficient removal of oil and gas.

During reclamation, the removal of caliche is important to increasing the success of revegetating the site. Removed caliche that is free of contaminants may be used for road repairs, fire walls or for building other roads and locations. In order to operate the well or

complete workover operations, it may be necessary to drive, park and operate on restored interim vegetation within the previously disturbed area. Disturbing revegetated areas for production or workover operations will be allowed. If there is significant disturbance and loss of vegetation, the area will need to be revegetated. Communicate with the appropriate BLM office for any exceptions/exemptions if needed.

All disturbed areas after they have been satisfactorily prepared need to be reseeded with the seed mixture provided below.

Upon completion of interim reclamation, the operator shall submit a Sundry Notices and Reports on Wells, Subsequent Report of Reclamation (Form 3160-5).

X. FINAL ABANDONMENT & RECLAMATION

At final abandonment, well locations, production facilities, and access roads must undergo "final" reclamation so that the character and productivity of the land are restored.

Earthwork for final reclamation must be completed within six (6) months of well plugging. All pads, pits, facility locations and roads must be reclaimed to a satisfactory revegetated, safe, and stable condition, unless an agreement is made with the landowner or BLM to keep the road and/or pad intact.

After all disturbed areas have been satisfactorily prepared, these areas need to be revegetated with the seed mixture provided below. Seeding should be accomplished by drilling on the contour whenever practical or by other approved methods. Seeding may need to be repeated until revegetation is successful, as determined by the BLM.

Operators shall contact a BLM surface protection specialist prior to surface abandonment operations for site specific objectives (Jim Amos: 575-234-5909).

Ground-level Abandoned Well Marker to avoid raptor perching: Upon the plugging and subsequent abandonment of the well, the well marker will be installed at ground level on a plate containing the pertinent information for the plugged well.

Seed Mixture 4, for Gypsum Sites

The holder shall seed all disturbed areas with the seed mixture listed below. The seed mixture shall be planted in the amounts specified in pounds of pure live seed (PLS)* per acre. There shall be no primary or secondary noxious weeds in the seed mixture. Seed will be tested and the viability testing of seed will be done in accordance with State law(s) and within nine (9) months prior to purchase. Commercial seed will be either certified or registered seed. The seed container will be tagged in accordance with State law(s) and available for inspection by the authorized officer.

Seed will be planted using a drill equipped with a depth regulator to ensure proper depth of planting where drilling is possible. The seed mixture will be evenly and uniformly planted over the disturbed area (smaller/heavier seeds have a tendency to drop the bottom of the drill and are planted first). The holder shall take appropriate measures to ensure this does not occur. Where drilling is not possible, seed will be broadcast and the area shall be raked or chained to cover the seed. When broadcasting the seed, the pounds per acre are to be doubled. The seeding will be repeated until a satisfactory stand is established as determined by the authorized officer. Evaluation of growth will not be made before completion of at least one full growing season after seeding.

Species to be planted in pounds of pure live seed* per acre:

Species	lb/acre
Alkali Sacaton (<i>Sporobolus airoides</i>)	1.0
DWS □ Four-wing saltbush (<i>Atriplex canescens</i>)	5.0

DWS: DeWinged Seed

*Pounds of pure live seed:

Pounds of seed x percent purity x percent germination = pounds pure live seed