

Company:	Marathon Oil	Local Co-ordinate Reference:	Well No. 2H
Project:	Eddy County, NM	TVD Reference:	Well @ 3023.50usft (GL: 2997' KB: 26.5' (H&P498))
Site:	Fiddle Fee 24-28-23 (2-6-9)	MD Reference:	Well @ 3023.50usft (GL: 2997' KB: 26.5' (H&P498))
Well:	No. 2H	North Reference:	Grid
Wellbore:	OH	Survey Calculation Method:	Minimum Curvature
Design:	Prelim Plan A	Database:	WellPlanner1

**NM OIL CONSERVATION
ARTESIA DISTRICT**

Project:	Eddy County, NM			NOV 07 2017
Map System:	US State Plane 1927 (Exact solution)	System Datum:	Mean Sea Level	
Geo Datum:	NAD 1927 (NADCON CONUS)			
Map Zone:	New Mexico East 3001			
			RECEIVED	

RECEIVED

Site:	Fiddle Fee 24-28-23 (2-6-9)
Site Position:	From: Map
Position Uncertainty:	0.00 usft
North:	439,985.99 usft
East:	582,860.46 usft
Slot Radius:	13-3/16 "
Latitude:	32.2093548
Longitude:	-104.0654268
Grid Convergence:	0.14 °

Well:	No. 2H
Well Position	+N/-S 0.00 usft
+E/-W 0.00 usft	North: 439,985.99 usft
Position Uncertainty 0.00 usft	East: 582,860.46 usft
	Latitude: 32.2093548
	Longitude: -104.0654268
	Ground Level: 2,997.00 usft

Wellbore	OH				
Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	HDGM	10/26/2017	7.23	60.05	48,071.10

Design:	Prelim Plan A			
Audit Notes:				
Version:	Phase:	PLAN	Tie On Depth:	0.00
Vertical Section:	Depth From (TVD) (usft)	+N/-S (usft)	+E/-W (usft)	Direction (°)
	0.00	0.00	0.00	90.79

Survey Tool Program		Date	10/27/2017		
From (usft)	To (usft)	Survey (Wellbore)	Tool Name	Description	
0.00	5,000.00	Prelim Plan A (OH)	MWD+IFR1	OWSG MWD + IFR1	
5,000.00	10,000.00	Prelim Plan A (OH)	MWD+IFR1	OWSG MWD + IFR1	
10,000.00	14,242.97	Prelim Plan A (OH)	MWD+IFR1	OWSG MWD + IFR1	

Planned Survey									
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
[FiddleFee#2H]FTP									
100.00	0.00	0.00	100.00	0.00	0.00	0.00	0.00	0.00	0.00
200.00	0.00	0.00	200.00	0.00	0.00	0.00	0.00	0.00	0.00
300.00	0.00	0.00	300.00	0.00	0.00	0.00	0.00	0.00	0.00
400.00	0.00	0.00	400.00	0.00	0.00	0.00	0.00	0.00	0.00
500.00	0.00	0.00	500.00	0.00	0.00	0.00	0.00	0.00	0.00



Pro Directional Survey Report



Company:	Marathon Oil	Local Co-ordinate Reference:	Well No. 2H
Project:	Eddy County, NM	TVD Reference:	Well @ 3023.50usft (GL: 2997' KB: 26.5' (H&P498))
Site:	Fiddle Fee 24-28-23 (2-6-9)	MD Reference:	Well @ 3023.50usft (GL: 2997' KB: 26.5' (H&P498))
Well:	No. 2H	North Reference:	Grid
Wellbore:	OH	Survey Calculation Method:	Minimum Curvature
Design:	Prelim Plan A	Database:	WellPlanner1

Planned Survey									
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
600.00	0.00	0.00	600.00	0.00	0.00	0.00	0.00	0.00	0.00
700.00	0.00	0.00	700.00	0.00	0.00	0.00	0.00	0.00	0.00
800.00	0.00	0.00	800.00	0.00	0.00	0.00	0.00	0.00	0.00
900.00	0.00	0.00	900.00	0.00	0.00	0.00	0.00	0.00	0.00
1,000.00	0.00	0.00	1,000.00	0.00	0.00	0.00	0.00	0.00	0.00
1,100.00	0.00	0.00	1,100.00	0.00	0.00	0.00	0.00	0.00	0.00
1,200.00	0.00	0.00	1,200.00	0.00	0.00	0.00	0.00	0.00	0.00
1,300.00	0.75	297.95	1,300.00	0.31	-0.58	-0.58	0.75	0.75	0.00
1,400.00	1.50	297.95	1,399.98	1.23	-2.31	-2.33	0.75	0.75	0.00
1,500.00	2.25	297.95	1,499.92	2.76	-5.20	-5.24	0.75	0.75	0.00
1,600.00	3.00	297.95	1,599.82	4.91	-9.25	-9.32	0.75	0.75	0.00
1,700.00	3.75	297.95	1,699.84	7.67	-14.45	-14.55	0.75	0.75	0.00
1,800.00	4.50	297.95	1,799.38	11.04	-20.80	-20.95	0.75	0.75	0.00
1,900.00	5.25	297.95	1,899.02	15.02	-28.31	-28.51	0.75	0.75	0.00
2,000.00	6.00	297.95	1,998.54	19.62	-36.97	-37.23	0.75	0.75	0.00
2,100.00	6.75	297.95	2,097.92	24.82	-46.78	-47.11	0.75	0.75	0.00
2,200.00	7.50	297.95	2,197.15	30.63	-57.73	-58.15	0.75	0.75	0.00
2,300.00	8.25	297.95	2,296.20	37.06	-69.84	-70.34	0.75	0.75	0.00
2,400.00	9.00	297.95	2,395.07	44.08	-83.08	-83.68	0.75	0.75	0.00
2,500.00	9.75	297.95	2,493.73	51.72	-97.47	-98.18	0.75	0.75	0.00
2,533.33	10.00	297.95	2,526.57	54.40	-102.52	-103.26	0.75	0.75	0.00
2,600.00	10.00	297.95	2,592.23	59.83	-112.75	-113.56	0.00	0.00	0.00
2,700.00	10.00	297.95	2,690.71	67.96	-128.09	-129.01	0.00	0.00	0.00
2,800.00	10.00	297.95	2,789.19	76.10	-143.43	-144.46	0.00	0.00	0.00
2,900.00	10.00	297.95	2,887.67	84.24	-158.77	-159.91	0.00	0.00	0.00
2,960.91	10.00	297.95	2,947.66	89.20	-168.11	-169.32	0.00	0.00	0.00
3,000.00	9.61	297.95	2,986.17	92.32	-173.99	-175.24	1.00	-1.00	0.00
3,100.00	8.61	297.95	3,084.91	99.74	-187.97	-189.33	1.00	-1.00	0.00
3,200.00	7.61	297.95	3,183.91	106.35	-200.43	-201.88	1.00	-1.00	0.00
3,300.00	6.61	297.95	3,283.14	112.15	-211.37	-212.89	1.00	-1.00	0.00
3,400.00	5.61	297.95	3,382.57	117.14	-220.77	-222.36	1.00	-1.00	0.00
3,500.00	4.61	297.95	3,482.17	121.32	-228.63	-230.28	1.00	-1.00	0.00
3,600.00	3.61	297.95	3,581.91	124.67	-234.96	-236.66	1.00	-1.00	0.00
3,700.00	2.61	297.95	3,681.77	127.22	-239.75	-241.48	1.00	-1.00	0.00
3,800.00	1.61	297.95	3,781.70	128.94	-243.00	-244.76	1.00	-1.00	0.00
3,900.00	0.61	297.95	3,881.68	129.85	-244.71	-246.48	1.00	-1.00	0.00
3,960.91	0.00	0.00	3,942.59	130.00	-245.00	-246.77	1.00	-1.00	0.00
4,000.00	0.00	0.00	3,981.68	130.00	-245.00	-246.77	0.00	0.00	0.00
4,100.00	0.00	0.00	4,081.68	130.00	-245.00	-246.77	0.00	0.00	0.00
4,200.00	0.00	0.00	4,181.68	130.00	-245.00	-246.77	0.00	0.00	0.00
4,300.00	0.00	0.00	4,281.68	130.00	-245.00	-246.77	0.00	0.00	0.00
4,400.00	0.00	0.00	4,381.68	130.00	-245.00	-246.77	0.00	0.00	0.00



Pro Directional Survey Report



Company:	Marathon Oil	Local Co-ordinate Reference:	Well No. 2H
Project:	Eddy County, NM	TVD Reference:	Well @ 3023.50usft (GL: 2997' KB: 26.5' (H&P498))
Site:	Fiddle Fee 24-28-23 (2-6-9)	MD Reference:	Well @ 3023.50usft (GL: 2997' KB: 26.5' (H&P498))
Well:	No. 2H	North Reference:	Grid
Wellbore:	OH	Survey Calculation Method:	Minimum Curvature
Design:	Prelim Plan A	Database:	WellPlanner1

Planned Survey										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	
4,500.00	0.00	0.00	4,481.68	130.00	-245.00	-246.77	0.00	0.00	0.00	
4,600.00	0.00	0.00	4,581.68	130.00	-245.00	-246.77	0.00	0.00	0.00	
4,700.00	0.00	0.00	4,681.68	130.00	-245.00	-246.77	0.00	0.00	0.00	
4,800.00	0.00	0.00	4,781.68	130.00	-245.00	-246.77	0.00	0.00	0.00	
4,900.00	0.00	0.00	4,881.68	130.00	-245.00	-246.77	0.00	0.00	0.00	
5,000.00	0.00	0.00	4,981.68	130.00	-245.00	-246.77	0.00	0.00	0.00	
5,100.00	0.00	0.00	5,081.68	130.00	-245.00	-246.77	0.00	0.00	0.00	
5,200.00	0.00	0.00	5,181.68	130.00	-245.00	-246.77	0.00	0.00	0.00	
5,300.00	0.00	0.00	5,281.68	130.00	-245.00	-246.77	0.00	0.00	0.00	
5,400.00	0.00	0.00	5,381.68	130.00	-245.00	-246.77	0.00	0.00	0.00	
5,500.00	0.00	0.00	5,481.68	130.00	-245.00	-246.77	0.00	0.00	0.00	
5,600.00	0.00	0.00	5,581.68	130.00	-245.00	-246.77	0.00	0.00	0.00	
5,700.00	0.00	0.00	5,681.68	130.00	-245.00	-246.77	0.00	0.00	0.00	
5,800.00	0.00	0.00	5,781.68	130.00	-245.00	-246.77	0.00	0.00	0.00	
5,900.00	0.00	0.00	5,881.68	130.00	-245.00	-246.77	0.00	0.00	0.00	
6,000.00	0.00	0.00	5,981.68	130.00	-245.00	-246.77	0.00	0.00	0.00	
6,100.00	0.00	0.00	6,081.68	130.00	-245.00	-246.77	0.00	0.00	0.00	
6,200.00	0.00	0.00	6,181.68	130.00	-245.00	-246.77	0.00	0.00	0.00	
6,300.00	0.00	0.00	6,281.68	130.00	-245.00	-246.77	0.00	0.00	0.00	
6,400.00	0.00	0.00	6,381.68	130.00	-245.00	-246.77	0.00	0.00	0.00	
6,500.00	0.00	0.00	6,481.68	130.00	-245.00	-246.77	0.00	0.00	0.00	
6,600.00	0.00	0.00	6,581.68	130.00	-245.00	-246.77	0.00	0.00	0.00	
6,700.00	0.00	0.00	6,681.68	130.00	-245.00	-246.77	0.00	0.00	0.00	
6,800.00	0.00	0.00	6,781.68	130.00	-245.00	-246.77	0.00	0.00	0.00	
6,900.00	0.00	0.00	6,881.68	130.00	-245.00	-246.77	0.00	0.00	0.00	
7,000.00	0.00	0.00	6,981.68	130.00	-245.00	-246.77	0.00	0.00	0.00	
7,100.00	0.00	0.00	7,081.68	130.00	-245.00	-246.77	0.00	0.00	0.00	
7,200.00	0.00	0.00	7,181.68	130.00	-245.00	-246.77	0.00	0.00	0.00	
7,300.00	0.00	0.00	7,281.68	130.00	-245.00	-246.77	0.00	0.00	0.00	
7,400.00	0.00	0.00	7,381.68	130.00	-245.00	-246.77	0.00	0.00	0.00	
7,500.00	0.00	0.00	7,481.68	130.00	-245.00	-246.77	0.00	0.00	0.00	
7,600.00	0.00	0.00	7,581.68	130.00	-245.00	-246.77	0.00	0.00	0.00	
7,700.00	0.00	0.00	7,681.68	130.00	-245.00	-246.77	0.00	0.00	0.00	
7,800.00	0.00	0.00	7,781.68	130.00	-245.00	-246.77	0.00	0.00	0.00	
7,900.00	0.00	0.00	7,881.68	130.00	-245.00	-246.77	0.00	0.00	0.00	
8,000.00	0.00	0.00	7,981.68	130.00	-245.00	-246.77	0.00	0.00	0.00	
8,100.00	0.00	0.00	8,081.68	130.00	-245.00	-246.77	0.00	0.00	0.00	
8,200.00	0.00	0.00	8,181.68	130.00	-245.00	-246.77	0.00	0.00	0.00	
8,300.00	0.00	0.00	8,281.68	130.00	-245.00	-246.77	0.00	0.00	0.00	
8,400.00	0.00	0.00	8,381.68	130.00	-245.00	-246.77	0.00	0.00	0.00	
8,500.00	0.00	0.00	8,481.68	130.00	-245.00	-246.77	0.00	0.00	0.00	
8,600.00	0.00	0.00	8,581.68	130.00	-245.00	-246.77	0.00	0.00	0.00	



Pro Directional Survey Report



Company:	Marathon Oil	Local Co-ordinate Reference:	Well No. 2H
Project:	Eddy County, NM	TVD Reference:	Well @ 3023.50usft (GL: 2997' KB: 26.5' (H&P498))
Site:	Fiddle Fee 24-28-23 (2-6-9)	MD Reference:	Well @ 3023.50usft (GL: 2997' KB: 26.5' (H&P498))
Well:	No. 2H	North Reference:	Grid
Wellbore:	OH	Survey Calculation Method:	Minimum Curvature
Design:	Prelim Plan A	Database:	WellPlanner1

Planned Survey									
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N-S (usft)	+E-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
8,700.00	0.00	0.00	8,681.68	130.00	-245.00	-246.77	0.00	0.00	0.00
8,800.00	0.00	0.00	8,781.68	130.00	-245.00	-246.77	0.00	0.00	0.00
8,847.32	0.00	0.00	8,829.00	130.00	-245.00	-246.77	0.00	0.00	0.00
[FiddleFee#2H]KOP									
8,850.00	0.27	90.79	8,831.68	130.00	-244.99	-246.76	10.00	10.00	0.00
8,900.00	5.27	90.79	8,881.60	129.97	-242.58	-244.35	10.00	10.00	0.00
8,950.00	10.27	90.79	8,931.13	129.87	-235.83	-237.59	10.00	10.00	0.00
9,000.00	15.27	90.79	8,979.88	129.72	-224.78	-226.55	10.00	10.00	0.00
9,050.00	20.27	90.79	9,027.48	129.51	-209.53	-211.29	10.00	10.00	0.00
9,100.00	25.27	90.79	9,073.57	129.24	-190.19	-191.95	10.00	10.00	0.00
9,150.00	30.27	90.79	9,117.79	128.92	-166.90	-168.66	10.00	10.00	0.00
9,200.00	35.27	90.79	9,159.82	128.54	-139.85	-141.61	10.00	10.00	0.00
9,250.00	40.27	90.79	9,199.34	128.12	-109.24	-111.00	10.00	10.00	0.00
9,300.00	45.27	90.79	9,236.03	127.65	-75.30	-77.06	10.00	10.00	0.00
9,350.00	50.27	90.79	9,269.63	127.13	-38.30	-40.05	10.00	10.00	0.00
9,400.00	55.27	90.79	9,299.87	126.58	1.49	-0.25	10.00	10.00	0.00
9,450.00	60.27	90.79	9,326.53	126.00	43.77	42.03	10.00	10.00	0.00
9,500.00	65.27	90.79	9,349.40	125.38	88.21	86.47	10.00	10.00	0.00
9,550.00	70.27	90.79	9,368.31	124.74	134.47	132.74	10.00	10.00	0.00
9,600.00	75.27	90.79	9,383.12	124.08	182.21	180.48	10.00	10.00	0.00
9,650.00	80.27	90.79	9,393.71	123.40	231.06	229.33	10.00	10.00	0.00
9,700.00	85.27	90.79	9,400.00	122.71	280.64	278.92	10.00	10.00	0.00
9,737.37	89.00	90.79	9,401.87	122.19	317.95	316.23	10.00	10.00	0.00
9,800.00	89.00	90.79	9,402.96	121.33	380.56	378.86	0.00	0.00	0.00
9,900.00	89.00	90.79	9,404.70	119.94	480.54	478.84	0.00	0.00	0.00
10,000.00	89.00	90.79	9,406.43	118.55	580.52	578.83	0.00	0.00	0.00
10,100.00	89.00	90.79	9,408.17	117.17	680.49	678.81	0.00	0.00	0.00
10,200.00	89.00	90.79	9,409.91	115.78	780.47	778.80	0.00	0.00	0.00
10,300.00	89.00	90.79	9,411.65	114.40	880.44	878.78	0.00	0.00	0.00
10,400.00	89.00	90.79	9,413.38	113.01	980.42	978.77	0.00	0.00	0.00
10,500.00	89.00	90.79	9,415.12	111.62	1,080.39	1,078.75	0.00	0.00	0.00
10,600.00	89.00	90.79	9,416.86	110.24	1,180.37	1,178.73	0.00	0.00	0.00
10,700.00	89.00	90.79	9,418.60	108.85	1,280.34	1,278.72	0.00	0.00	0.00
10,800.00	89.00	90.79	9,420.33	107.46	1,380.32	1,378.70	0.00	0.00	0.00
10,900.00	89.00	90.79	9,422.07	106.08	1,480.29	1,478.69	0.00	0.00	0.00
11,000.00	89.00	90.79	9,423.81	104.69	1,580.27	1,578.67	0.00	0.00	0.00
11,100.00	89.00	90.79	9,425.55	103.31	1,680.24	1,678.66	0.00	0.00	0.00
11,200.00	89.00	90.79	9,427.28	101.92	1,780.22	1,778.64	0.00	0.00	0.00
11,300.00	89.00	90.79	9,429.02	100.53	1,880.19	1,878.63	0.00	0.00	0.00
11,400.00	89.00	90.79	9,430.76	99.15	1,980.17	1,978.61	0.00	0.00	0.00
11,500.00	89.00	90.79	9,432.49	97.76	2,080.14	2,078.60	0.00	0.00	0.00
11,600.00	89.00	90.79	9,434.23	96.38	2,180.12	2,178.58	0.00	0.00	0.00

Company:	Marathon Oil	Local Co-ordinate Reference:	Well No. 2H
Project:	Eddy County, NM	TVD Reference:	Well @ 3023.50usft (GL: 2997' KB: 26.5' (H&P498))
Site:	Fiddle Fee 24-28-23 (2-6-9)	MD Reference:	Well @ 3023.50usft (GL: 2997' KB: 26.5' (H&P498))
Well:	No. 2H	North Reference:	Grid
Wellbore:	OH	Survey Calculation Method:	Minimum Curvature
Design:	Prelim Plan A	Database:	WellPlanner1

Planned Survey									
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
11,700.00	89.00	90.79	9,435.97	94.99	2,280.10	2,278.57	0.00	0.00	0.00
11,800.00	89.00	90.79	9,437.71	93.60	2,380.07	2,378.55	0.00	0.00	0.00
11,900.00	89.00	90.79	9,439.44	92.22	2,480.05	2,478.54	0.00	0.00	0.00
12,000.00	89.00	90.79	9,441.18	90.83	2,580.02	2,578.52	0.00	0.00	0.00
12,100.00	89.00	90.79	9,442.92	89.44	2,680.00	2,678.51	0.00	0.00	0.00
12,200.00	89.00	90.79	9,444.66	88.06	2,779.97	2,778.49	0.00	0.00	0.00
12,300.00	89.00	90.79	9,446.39	86.67	2,879.95	2,878.48	0.00	0.00	0.00
12,400.00	89.00	90.79	9,448.13	85.29	2,979.92	2,978.46	0.00	0.00	0.00
12,500.00	89.00	90.79	9,449.87	83.90	3,079.90	3,078.45	0.00	0.00	0.00
12,600.00	89.00	90.79	9,451.61	82.51	3,179.87	3,178.43	0.00	0.00	0.00
12,700.00	89.00	90.79	9,453.34	81.13	3,279.85	3,278.42	0.00	0.00	0.00
12,800.00	89.00	90.79	9,455.08	79.74	3,379.82	3,378.40	0.00	0.00	0.00
12,900.00	89.00	90.79	9,456.82	78.36	3,479.80	3,478.39	0.00	0.00	0.00
13,000.00	89.00	90.79	9,458.56	76.97	3,579.77	3,578.37	0.00	0.00	0.00
13,100.00	89.00	90.79	9,460.29	75.58	3,679.75	3,678.36	0.00	0.00	0.00
13,200.00	89.00	90.79	9,462.03	74.20	3,779.72	3,778.34	0.00	0.00	0.00
13,300.00	89.00	90.79	9,463.77	72.81	3,879.70	3,878.33	0.00	0.00	0.00
13,400.00	89.00	90.79	9,465.50	71.42	3,979.68	3,978.31	0.00	0.00	0.00
13,500.00	89.00	90.79	9,467.24	70.04	4,079.65	4,078.30	0.00	0.00	0.00
13,600.00	89.00	90.79	9,468.98	68.65	4,179.63	4,178.28	0.00	0.00	0.00
13,700.00	89.00	90.79	9,470.72	67.27	4,279.60	4,278.27	0.00	0.00	0.00
13,800.00	89.00	90.79	9,472.45	65.88	4,379.58	4,378.25	0.00	0.00	0.00
13,900.00	89.00	90.79	9,474.19	64.49	4,479.55	4,478.24	0.00	0.00	0.00
14,000.00	89.00	90.79	9,475.93	63.11	4,579.53	4,578.22	0.00	0.00	0.00
14,100.00	89.00	90.79	9,477.67	61.72	4,679.50	4,678.21	0.00	0.00	0.00
14,200.00	89.00	90.79	9,479.40	60.34	4,779.48	4,778.19	0.00	0.00	0.00
14,242.97	89.00	90.79	9,480.15	59.74	4,822.44	4,821.16	0.00	0.00	0.00
[FiddleFee#2H]LTP/BHL									

Design Targets									
Target Name	Dip Angle (°)	Dip Dir. (°)	TVD (usft)	+N/-S (usft)	+E/-W (usft)	Northing (usft)	Easting (usft)	Latitude	Longitude
[FiddleFee#2H]FTP	0.00	0.01	0.00	126.83	-21.24	440,112.82	582,839.22	32.2097036	-104.0654945
- plan misses target center by 128.60usft at 0.00usft MD (0.00 TVD, 0.00 N, 0.00 E)									
- Point									
[FiddleFee#2H]KOP	0.00	0.00	8,829.00	130.00	-245.00	440,115.99	582,615.46	32.2097138	-104.0662179
- plan hits target center									
- Point									
[FiddleFee#2H]LTP/BHL	0.00	0.00	9,480.15	59.74	4,822.44	440,045.73	587,682.90	32.2094850	-104.0498345
- plan hits target center									
- Point									



Pro Directional
Survey Report



Company:	Marathon Oil	Local Co-ordinate Reference:	Well No. 2H
Project:	Eddy County, NM	TVD Reference:	Well @ 3023.50usft (GL: 2997' KB: 26.5' (H&P498))
Site:	Fiddle Fee 24-28-23 (2-6-9)	MD Reference:	Well @ 3023.50usft (GL: 2997' KB: 26.5' (H&P498))
Well:	No. 2H	North Reference:	Grid
Wellbore:	OH	Survey Calculation Method:	Minimum Curvature
Design:	Prelim Plan A	Database:	WellPlanner1

Checked By: _____	Approved By: _____	Date: _____
-------------------	--------------------	-------------