

Company:	Marathon Oil	Local Co-ordinate Reference:	Well No. 6H
Project:	Eddy County, NM	TVD Reference:	Well @ 3023.50usft (GL: 2997' + KB: 26.5' (H&P498))
Site:	Fiddle Fee 24-28-23 (2-6-9)	MD Reference:	Well @ 3023.50usft (GL: 2997' + KB: 26.5' (H&P498))
Well:	No. 6H	North Reference:	Grid
Wellbore:	OH	Survey Calculation Method:	Minimum Curvature
Design:	Prelim Plan A	Database:	WellPlanner1

NM OIL CONSERVATION
ARTESIA DISTRICT
NOV 07 2017

Project:	Eddy County, NM
Map System:	US State Plane 1927 (Exact solution)
Geo Datum:	NAD 1927 (NADCON CONUS)
Map Zone:	New Mexico East 3001
System Datum:	Mean Sea Level

Site:	Fiddle Fee 24-28-23 (2-6-9)
Site Position:	From: Map
Position Uncertainty:	0.00 usft
Northings:	439,985.99 usft
Easting:	582,860.46 usft
Slot Radius:	13-3/16 "
Latitude:	32.2093548
Longitude:	-104.0654268
Grid Convergence:	0.14 °

Well:	No. 6H
Well Position	+N/-S 0.00 usft
	+E/-W 0.00 usft
Position Uncertainty	0.00 usft
Northings:	439,935.99 usft
Easting:	582,860.46 usft
Wellhead Elevation:	usft
Latitude:	32.2092173
Longitude:	-104.0654273
Ground Level:	2,997.00 usft

Wellbore:	OH				
Magnetics	Model Name	Sample Date	Declination	Dip Angle	Field Strength
	HDCM	10/26/2017	7.23	60.05	48,071.10

Design:	Prelim Plan A			
Audit Notes:				
Version:	Phase: PLAN			
	Tie On Depth: 0.00			
Vertical Section:	Depth From (TVD)	+N/-S	+E/-W	Direction
	(usft)	(usft)	(usft)	(°)
	0.00	0.00	0.00	90.79

Survey Tool Program	Date 10/27/2017			
From	To	Survey (Wellbore)	Tool Name	Description
0.00	5,000.00	Prelim Plan A (OH)	MWD+IFR1	OWSG MWD + IFR1
5,000.00	10,000.00	Prelim Plan A (OH)	MWD+IFR1	OWSG MWD + IFR1
10,000.00	14,493.12	Prelim Plan A (OH)	MWD+IFR1	OWSG MWD + IFR1

Planned Survey									
Measured Depth	Inclination	Azimuth	Vertical Depth	+N/-S	+E/-W	Vertical Section	Dogleg Rate	Build Rate	Turn Rate
(usft)	(°)	(°)	(usft)	(usft)	(usft)	(usft)	(°/100usft)	(°/100usft)	(°/100usft)
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
[FiddleFee#6H]FTP									
100.00	0.00	0.00	100.00	0.00	0.00	0.00	0.00	0.00	0.00
200.00	0.00	0.00	200.00	0.00	0.00	0.00	0.00	0.00	0.00
300.00	0.00	0.00	300.00	0.00	0.00	0.00	0.00	0.00	0.00
400.00	0.00	0.00	400.00	0.00	0.00	0.00	0.00	0.00	0.00
500.00	0.00	0.00	500.00	0.00	0.00	0.00	0.00	0.00	0.00



Pro Directional Survey Report



Company:	Marathon Oil	Local Co-ordinate Reference:	Well No. 6H
Project:	Eddy County, NM	TVD Reference:	Well @ 3023.50usft (GL: 2997' + KB: 26.5' (H&P498))
Site:	Fiddle Fee 24-28-23 (2-6-9)	MD Reference:	Well @ 3023.50usft (GL: 2997' + KB: 26.5' (H&P498))
Well:	No. 6H	North Reference:	Grid
Wellbore:	OH	Survey Calculation Method:	Minimum Curvature
Design:	Prelim Plan A	Database:	WellPlanner1

Planned Survey									
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
600.00	0.00	0.00	600.00	0.00	0.00	0.00	0.00	0.00	0.00
700.00	0.00	0.00	700.00	0.00	0.00	0.00	0.00	0.00	0.00
800.00	0.00	0.00	800.00	0.00	0.00	0.00	0.00	0.00	0.00
900.00	0.00	0.00	900.00	0.00	0.00	0.00	0.00	0.00	0.00
1,000.00	0.00	0.00	1,000.00	0.00	0.00	0.00	0.00	0.00	0.00
1,100.00	0.00	0.00	1,100.00	0.00	0.00	0.00	0.00	0.00	0.00
1,200.00	0.00	0.00	1,200.00	0.00	0.00	0.00	0.00	0.00	0.00
1,300.00	0.00	0.00	1,300.00	0.00	0.00	0.00	0.00	0.00	0.00
1,400.00	0.00	0.00	1,400.00	0.00	0.00	0.00	0.00	0.00	0.00
1,500.00	0.00	0.00	1,500.00	0.00	0.00	0.00	0.00	0.00	0.00
1,600.00	0.75	287.09	1,600.00	0.19	-0.63	-0.63	0.75	0.75	0.00
1,700.00	1.50	287.09	1,699.98	0.77	-2.50	-2.51	0.75	0.75	0.00
1,800.00	2.25	287.09	1,799.92	1.73	-5.63	-5.65	0.75	0.75	0.00
1,900.00	3.00	287.09	1,899.82	3.08	-10.01	-10.05	0.75	0.75	0.00
2,000.00	3.75	287.09	1,999.64	4.81	-15.63	-15.70	0.75	0.75	0.00
2,100.00	4.50	287.09	2,099.38	6.92	-22.51	-22.60	0.75	0.75	0.00
2,166.67	5.00	287.09	2,165.82	8.54	-27.79	-27.90	0.75	0.75	0.00
2,200.00	5.00	287.09	2,199.03	9.39	-30.56	-30.69	0.00	0.00	0.00
2,300.00	5.00	287.09	2,298.65	11.96	-38.90	-39.06	0.00	0.00	0.00
2,400.00	5.00	287.09	2,398.27	14.52	-47.23	-47.42	0.00	0.00	0.00
2,500.00	5.00	287.09	2,497.89	17.08	-55.56	-55.79	0.00	0.00	0.00
2,600.00	5.00	287.09	2,597.51	19.64	-63.89	-64.15	0.00	0.00	0.00
2,700.00	5.00	287.09	2,697.12	22.20	-72.22	-72.52	0.00	0.00	0.00
2,800.00	5.00	287.09	2,796.74	24.76	-80.55	-80.88	0.00	0.00	0.00
2,900.00	5.00	287.09	2,896.36	27.32	-88.88	-89.25	0.00	0.00	0.00
3,000.00	5.00	287.09	2,995.98	29.88	-97.21	-97.61	0.00	0.00	0.00
3,100.00	5.00	287.09	3,095.60	32.44	-105.54	-105.98	0.00	0.00	0.00
3,200.00	5.00	287.09	3,195.22	35.00	-113.87	-114.35	0.00	0.00	0.00
3,300.00	5.00	287.09	3,294.84	37.56	-122.20	-122.71	0.00	0.00	0.00
3,400.00	5.00	287.09	3,394.46	40.12	-130.54	-131.08	0.00	0.00	0.00
3,500.00	5.00	287.09	3,494.08	42.68	-138.87	-139.44	0.00	0.00	0.00
3,600.00	5.00	287.09	3,593.70	45.24	-147.20	-147.81	0.00	0.00	0.00
3,700.00	5.00	287.09	3,693.32	47.81	-155.53	-156.17	0.00	0.00	0.00
3,800.00	5.00	287.09	3,792.94	50.37	-163.86	-164.54	0.00	0.00	0.00
3,900.00	5.00	287.09	3,892.56	52.93	-172.19	-172.90	0.00	0.00	0.00
4,000.00	5.00	287.09	3,992.18	55.49	-180.52	-181.27	0.00	0.00	0.00
4,100.00	5.00	287.09	4,091.80	58.05	-188.85	-189.63	0.00	0.00	0.00
4,200.00	5.00	287.09	4,191.42	60.61	-197.18	-198.00	0.00	0.00	0.00
4,300.00	5.00	287.09	4,291.04	63.17	-205.51	-206.36	0.00	0.00	0.00
4,400.00	5.00	287.09	4,390.66	65.73	-213.84	-214.73	0.00	0.00	0.00
4,500.00	5.00	287.09	4,490.28	68.29	-222.17	-223.10	0.00	0.00	0.00
4,511.82	5.00	287.09	4,502.05	68.59	-223.16	-224.08	0.00	0.00	0.00



Pro Directional Survey Report



Company:	Marathon Oil	Local Co-ordinate Reference:	Well No. 6H
Project:	Eddy County, NM	TVD Reference:	Well @ 3023.50usft (GL: 2997' + KB: 26.5' (H&P498))
Site:	Fiddle Fee 24-28-23 (2-6-9)	MD Reference:	Well @ 3023.50usft (GL: 2997' + KB: 26.5' (H&P498))
Well:	No. 6H	North Reference:	Grid
Wellbore:	OH	Survey Calculation Method:	Minimum Curvature
Design:	Prelim Plan A	Database:	WellPlanner1

Planned Survey										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	
4,600.00	4.12	287.09	4,589.95	70.65	-229.86	-230.81	1.00	-1.00	0.00	
4,700.00	3.12	287.09	4,689.75	72.51	-235.89	-236.87	1.00	-1.00	0.00	
4,800.00	2.12	287.09	4,789.64	73.85	-240.26	-241.25	1.00	-1.00	0.00	
4,900.00	1.12	287.09	4,889.60	74.68	-242.96	-243.96	1.00	-1.00	0.00	
5,000.00	0.12	287.09	4,989.60	75.00	-243.99	-245.00	1.00	-1.00	0.00	
5,011.82	0.00	0.00	5,001.41	75.00	-244.00	-245.01	1.00	-1.00	0.00	
5,100.00	0.00	0.00	5,089.60	75.00	-244.00	-245.01	0.00	0.00	0.00	
5,200.00	0.00	0.00	5,189.60	75.00	-244.00	-245.01	0.00	0.00	0.00	
5,300.00	0.00	0.00	5,289.60	75.00	-244.00	-245.01	0.00	0.00	0.00	
5,400.00	0.00	0.00	5,389.60	75.00	-244.00	-245.01	0.00	0.00	0.00	
5,500.00	0.00	0.00	5,489.60	75.00	-244.00	-245.01	0.00	0.00	0.00	
5,600.00	0.00	0.00	5,589.60	75.00	-244.00	-245.01	0.00	0.00	0.00	
5,700.00	0.00	0.00	5,689.60	75.00	-244.00	-245.01	0.00	0.00	0.00	
5,800.00	0.00	0.00	5,789.60	75.00	-244.00	-245.01	0.00	0.00	0.00	
5,900.00	0.00	0.00	5,889.60	75.00	-244.00	-245.01	0.00	0.00	0.00	
6,000.00	0.00	0.00	5,989.60	75.00	-244.00	-245.01	0.00	0.00	0.00	
6,100.00	0.00	0.00	6,089.60	75.00	-244.00	-245.01	0.00	0.00	0.00	
6,200.00	0.00	0.00	6,189.60	75.00	-244.00	-245.01	0.00	0.00	0.00	
6,300.00	0.00	0.00	6,289.60	75.00	-244.00	-245.01	0.00	0.00	0.00	
6,400.00	0.00	0.00	6,389.60	75.00	-244.00	-245.01	0.00	0.00	0.00	
6,500.00	0.00	0.00	6,489.60	75.00	-244.00	-245.01	0.00	0.00	0.00	
6,600.00	0.00	0.00	6,589.60	75.00	-244.00	-245.01	0.00	0.00	0.00	
6,700.00	0.00	0.00	6,689.60	75.00	-244.00	-245.01	0.00	0.00	0.00	
6,800.00	0.00	0.00	6,789.60	75.00	-244.00	-245.01	0.00	0.00	0.00	
6,900.00	0.00	0.00	6,889.60	75.00	-244.00	-245.01	0.00	0.00	0.00	
7,000.00	0.00	0.00	6,989.60	75.00	-244.00	-245.01	0.00	0.00	0.00	
7,100.00	0.00	0.00	7,089.60	75.00	-244.00	-245.01	0.00	0.00	0.00	
7,200.00	0.00	0.00	7,189.60	75.00	-244.00	-245.01	0.00	0.00	0.00	
7,300.00	0.00	0.00	7,289.60	75.00	-244.00	-245.01	0.00	0.00	0.00	
7,400.00	0.00	0.00	7,389.60	75.00	-244.00	-245.01	0.00	0.00	0.00	
7,500.00	0.00	0.00	7,489.60	75.00	-244.00	-245.01	0.00	0.00	0.00	
7,600.00	0.00	0.00	7,589.60	75.00	-244.00	-245.01	0.00	0.00	0.00	
7,700.00	0.00	0.00	7,689.60	75.00	-244.00	-245.01	0.00	0.00	0.00	
7,800.00	0.00	0.00	7,789.60	75.00	-244.00	-245.01	0.00	0.00	0.00	
7,900.00	0.00	0.00	7,889.60	75.00	-244.00	-245.01	0.00	0.00	0.00	
8,000.00	0.00	0.00	7,989.60	75.00	-244.00	-245.01	0.00	0.00	0.00	
8,100.00	0.00	0.00	8,089.60	75.00	-244.00	-245.01	0.00	0.00	0.00	
8,200.00	0.00	0.00	8,189.60	75.00	-244.00	-245.01	0.00	0.00	0.00	
8,300.00	0.00	0.00	8,289.60	75.00	-244.00	-245.01	0.00	0.00	0.00	
8,400.00	0.00	0.00	8,389.60	75.00	-244.00	-245.01	0.00	0.00	0.00	
8,500.00	0.00	0.00	8,489.60	75.00	-244.00	-245.01	0.00	0.00	0.00	
8,600.00	0.00	0.00	8,589.60	75.00	-244.00	-245.01	0.00	0.00	0.00	



Pro Directional Survey Report



Company:	Marathon Oil	Local Co-ordinate Reference:	Well No. 6H
Project:	Eddy County, NM	TVD Reference:	Well @ 3023.50usft (GL: 2997' + KB: 26.5' (H&P498))
Site:	Fiddle Fee 24-28-23 (2-6-9)	MD Reference:	Well @ 3023.50usft (GL: 2997' + KB: 26.5' (H&P498))
Well:	No. 6H	North Reference:	Grid
Wellbore:	OH	Survey Calculation Method:	Minimum Curvature
Design:	Prelim Plan A	Database:	WellPlanner1

Planned Survey									
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/S (usft)	+E/W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
8,700.00	0.00	0.00	8,689.60	75.00	-244.00	-245.01	0.00	0.00	0.00
8,800.00	0.00	0.00	8,789.60	75.00	-244.00	-245.01	0.00	0.00	0.00
8,900.00	0.00	0.00	8,889.60	75.00	-244.00	-245.01	0.00	0.00	0.00
9,000.00	0.00	0.00	8,989.60	75.00	-244.00	-245.01	0.00	0.00	0.00
9,075.90	0.00	0.00	9,065.50	75.00	-244.00	-245.01	0.00	0.00	0.00
9,100.00	2.41	83.28	9,089.59	75.06	-243.50	-244.51	10.00	10.00	0.00
9,129.77	5.39	83.28	9,119.28	75.30	-241.49	-242.50	10.00	10.00	0.00
[FiddleFee#6H]KOP									
9,150.00	7.41	83.28	9,139.39	75.56	-239.25	-240.27	10.00	10.00	0.00
9,200.00	12.41	83.28	9,188.63	76.57	-230.71	-231.74	10.00	10.00	0.00
9,250.00	17.41	83.28	9,236.93	78.07	-217.93	-218.99	10.00	10.00	0.00
9,300.00	22.41	83.28	9,283.93	80.06	-201.03	-202.11	10.00	10.00	0.00
9,350.00	27.41	83.28	9,329.26	82.53	-180.12	-181.24	10.00	10.00	0.00
9,400.00	32.41	83.28	9,372.59	85.44	-155.37	-156.53	10.00	10.00	0.00
9,451.79	37.59	83.28	9,415.00	88.92	-125.87	-127.09	10.00	10.00	0.00
9,500.00	41.45	83.28	9,452.18	92.51	-95.42	-96.68	8.00	8.00	0.00
9,550.00	45.45	83.28	9,488.48	96.53	-61.28	-62.60	8.00	8.00	0.00
9,600.00	49.45	83.28	9,522.28	100.84	-24.71	-26.09	8.00	8.00	0.00
9,650.00	53.45	83.28	9,553.44	105.41	14.12	12.66	8.00	8.00	0.00
9,700.00	57.45	83.28	9,581.79	110.23	55.01	53.48	8.00	8.00	0.00
9,750.00	61.45	83.28	9,607.21	115.27	97.76	96.16	8.00	8.00	0.00
9,800.00	65.45	83.28	9,629.55	120.50	142.17	140.49	8.00	8.00	0.00
9,850.00	69.45	83.28	9,648.73	125.90	188.02	186.26	8.00	8.00	0.00
9,900.00	73.45	83.28	9,664.64	131.45	235.08	233.25	8.00	8.00	0.00
9,950.00	77.45	83.28	9,677.20	137.11	283.14	281.22	8.00	8.00	0.00
10,000.00	81.45	83.28	9,686.35	142.86	331.94	329.94	8.00	8.00	0.00
10,050.00	85.45	83.28	9,692.06	148.67	381.26	379.18	8.00	8.00	0.00
10,094.43	89.00	83.28	9,694.21	153.87	425.33	423.17	8.00	8.00	0.00
10,100.00	89.00	83.45	9,694.31	154.51	430.86	428.69	3.00	0.00	3.00
10,200.00	89.00	86.45	9,696.06	163.31	530.45	528.14	3.00	0.00	3.00
10,300.00	89.00	89.45	9,697.81	166.89	630.36	628.00	3.00	0.00	3.00
10,344.67	89.00	90.79	9,698.59	166.80	675.02	672.65	3.00	0.00	3.00
10,400.00	89.00	90.79	9,699.56	166.04	730.33	727.98	0.00	0.00	0.00
10,500.00	89.00	90.79	9,701.31	164.67	830.31	827.96	0.00	0.00	0.00
10,600.00	89.00	90.79	9,703.06	163.29	930.29	927.95	0.00	0.00	0.00
10,700.00	89.00	90.79	9,704.81	161.91	1,030.26	1,027.93	0.00	0.00	0.00
10,800.00	89.00	90.79	9,706.55	160.54	1,130.24	1,127.91	0.00	0.00	0.00
10,900.00	89.00	90.79	9,708.30	159.16	1,230.21	1,227.90	0.00	0.00	0.00
11,000.00	89.00	90.79	9,710.05	157.79	1,330.19	1,327.88	0.00	0.00	0.00
11,100.00	89.00	90.79	9,711.80	156.41	1,430.16	1,427.87	0.00	0.00	0.00
11,200.00	89.00	90.79	9,713.55	155.04	1,530.14	1,527.85	0.00	0.00	0.00
11,300.00	89.00	90.79	9,715.30	153.66	1,630.11	1,627.84	0.00	0.00	0.00



Pro Directional Survey Report



Company:	Marathon Oil	Local Co-ordinate Reference:	Well No. 6H
Project:	Eddy County, NM	TVD Reference:	Well @ 3023.50usft (GL: 2997' + KB: 26.5' (H&P498))
Site:	Fiddle Fee 24-28-23 (2-6-9)	MD Reference:	Well @ 3023.50usft (GL: 2997' + KB: 26.5' (H&P498))
Well:	No. 6H	North Reference:	Grid
Wellbore:	OH	Survey Calculation Method:	Minimum Curvature
Design:	Prelim Plan A	Database:	WellPlanner1

Planned Survey									
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
11,400.00	89.00	90.79	9,717.05	152.29	1,730.09	1,727.82	0.00	0.00	0.00
11,500.00	89.00	90.79	9,718.80	150.91	1,830.06	1,827.81	0.00	0.00	0.00
11,600.00	89.00	90.79	9,720.54	149.53	1,930.04	1,927.79	0.00	0.00	0.00
11,700.00	89.00	90.79	9,722.29	148.16	2,030.01	2,027.78	0.00	0.00	0.00
11,800.00	89.00	90.79	9,724.04	146.78	2,129.99	2,127.76	0.00	0.00	0.00
11,900.00	89.00	90.79	9,725.79	145.41	2,229.96	2,227.75	0.00	0.00	0.00
12,000.00	89.00	90.79	9,727.54	144.03	2,329.94	2,327.73	0.00	0.00	0.00
12,100.00	89.00	90.79	9,729.29	142.66	2,429.91	2,427.72	0.00	0.00	0.00
12,200.00	89.00	90.79	9,731.04	141.28	2,529.89	2,527.70	0.00	0.00	0.00
12,300.00	89.00	90.79	9,732.79	139.91	2,629.86	2,627.69	0.00	0.00	0.00
12,400.00	89.00	90.79	9,734.54	138.53	2,729.84	2,727.67	0.00	0.00	0.00
12,500.00	89.00	90.79	9,736.28	137.16	2,829.81	2,827.65	0.00	0.00	0.00
12,600.00	89.00	90.79	9,738.03	135.78	2,929.79	2,927.64	0.00	0.00	0.00
12,700.00	89.00	90.79	9,739.78	134.40	3,029.77	3,027.62	0.00	0.00	0.00
12,800.00	89.00	90.79	9,741.53	133.03	3,129.74	3,127.61	0.00	0.00	0.00
12,900.00	89.00	90.79	9,743.28	131.65	3,229.72	3,227.59	0.00	0.00	0.00
13,000.00	89.00	90.79	9,745.03	130.28	3,329.69	3,327.58	0.00	0.00	0.00
13,100.00	89.00	90.79	9,746.78	128.90	3,429.67	3,427.56	0.00	0.00	0.00
13,200.00	89.00	90.79	9,748.53	127.53	3,529.64	3,527.55	0.00	0.00	0.00
13,300.00	89.00	90.79	9,750.27	126.15	3,629.62	3,627.53	0.00	0.00	0.00
13,400.00	89.00	90.79	9,752.02	124.78	3,729.59	3,727.52	0.00	0.00	0.00
13,500.00	89.00	90.79	9,753.77	123.40	3,829.57	3,827.50	0.00	0.00	0.00
13,600.00	89.00	90.79	9,755.52	122.02	3,929.54	3,927.49	0.00	0.00	0.00
13,700.00	89.00	90.79	9,757.27	120.65	4,029.52	4,027.47	0.00	0.00	0.00
13,800.00	89.00	90.79	9,759.02	119.27	4,129.49	4,127.46	0.00	0.00	0.00
13,900.00	89.00	90.79	9,760.77	117.90	4,229.47	4,227.44	0.00	0.00	0.00
14,000.00	89.00	90.79	9,762.52	116.52	4,329.44	4,327.43	0.00	0.00	0.00
14,100.00	89.00	90.79	9,764.27	115.15	4,429.42	4,427.41	0.00	0.00	0.00
14,200.00	89.00	90.79	9,766.01	113.77	4,529.39	4,527.39	0.00	0.00	0.00
14,300.00	89.00	90.79	9,767.76	112.40	4,629.37	4,627.38	0.00	0.00	0.00
14,400.00	89.00	90.79	9,769.51	111.02	4,729.34	4,727.36	0.00	0.00	0.00
14,493.12	89.00	90.79	9,771.14	109.74	4,822.44	4,820.47	0.00	0.00	0.00

[FiddleFee#6H]LTP/BHL



Pro Directional Survey Report



Company:	Marathon Oil	Local Co-ordinate Reference:	Well No. 6H
Project:	Eddy County, NM	TVD Reference:	Well @ 3023.50usft (GL: 2997' + KB: 26.5' (H&P498))
Site:	Fiddle Fee 24-28-23 (2-6-9)	MD Reference:	Well @ 3023.50usft (GL: 2997' + KB: 26.5' (H&P498))
Well:	No. 6H	North Reference:	Grid
Wellbore:	OH	Survey Calculation Method:	Minimum Curvature
Design:	Prelim Plan A	Database:	WellPlanner1

Design Targets									
Target Name	Dip Angle (°)	Dip Dir. (°)	TVD (usft)	+N/-S (usft)	+E/-W (usft)	Northing (usft)	Easting (usft)	Latitude	Longitude
[FiddleFee#6H]FTP - hit/miss target - Shape - plan misses target center by 178.10usft at 0.00usft MD (0.00 TVD, 0.00 N, 0.00 E) - Point	0.00	0.00	0.00	176.83	-21.24	440,112.82	582,839.22	32.2097036	-104.0654945
[FiddleFee#6H]KOP - plan misses target center by 2.54usft at 9129.77usft MD (9119.28 TVD, 75.30 N, -241.49 E) - Point	0.00	0.01	9,119.50	75.00	-244.00	440,010.99	582,616.46	32.2094251	-104.0662155
[FiddleFee#6H]LTP/BHL - plan hits target center - Point	0.00	0.00	9,771.14	109.74	4,822.44	440,045.73	587,682.90	32.2094850	-104.0498345

Checked By: _____	Approved By: _____	Date: _____
-------------------	--------------------	-------------