

**NM OIL CONSERVATION**  
ARTESIA DISTRICT

Form 3160-3  
(June 2015)

**SEP 30 2019**

FORM APPROVED  
OMB No. 1004-0137  
Expires: January 31, 2018

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

**RECEIVED**

**APPLICATION FOR PERMIT TO DRILL OR REENTER**

1a. Type of work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER		5. Lease Serial No. NMNM013413A
1b. Type of Well: <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other		6. If Indian, Allottee or Tribe Name
1c. Type of Completion: <input type="checkbox"/> Hydraulic Fracturing <input checked="" type="checkbox"/> Single Zone <input type="checkbox"/> Multiple Zone		7. If Unit or CA Agreement, Name and No.
2. Name of Operator MEWBOURNE OIL COMPANY		8. Lease Name and Well No. OXBOW 23/24 WOLF FED COM 1H 326143
3a. Address PO Box 5270 Hobbs NM 88240	3b. Phone No. (include area code) (575)393-5905	9. API Well No. 30-015-46313
4. Location of Well (Report location clearly and in accordance with any State requirements. *) At surface SWSW / 867 FSL / 233 FWL / LAT 32.1105163 / LONG -104.0657488 At proposed prod. zone NESE / 1625 FSL / 330 FEL / LAT 32.1126674 / LONG -104.0332694		10. Field and Pool, or Exploratory WILDCAT WOLFCAMP / WOLFCAMP GA
11. Sec., T, R, M, or Blk. and Survey or Area SEC 23, T25S, R28E / NMP		12. County or Parish EDDY
13. State NM		14. Distance in miles and direction from nearest town or post office* 8.5 miles
15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) 330 feet	16. No. of acres in lease 1280	17. Spacing Unit dedicated to this well 640
18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft. 50 feet	19. Proposed Depth 9749 feet / 19460 feet	20. BLM/BIA Bond No. in file FED: NM1693
21. Elevations (Show whether DF, KDB, RT, GL, etc.) 2959 feet	22. Approximate date work will start* 02/09/2019	23. Estimated duration 60 days
24. Attachments		

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, and the Hydraulic Fracturing rule per 43 CFR 3162.3-3 (as applicable)

- |  |   |
|--|---|
| 1. Well plat certified by a registered surveyor.   | 4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above). |
| 2. A Drilling Plan.  | 5. Operator certification.  |
| 3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO must be filed with the appropriate Forest Service Office). | 6. Such other site specific information and/or plans as may be requested by the BLM.            |

25. Signature (Electronic Submission)	Name (Printed/Typed) Bradley Bishop / Ph: (575)393-5905	Date 01/16/2019
Title Regulatory		
Approved by (Signature) (Electronic Submission)	Name (Printed/Typed) Cody Layton / Ph: (575)234-5959	Date 09/25/2019
Title Assistant Field Manager Lands & Minerals Office CARLSBAD		

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

**APPROVED WITH CONDITIONS**  
Approval Date: 09/25/2019

(Continued on page 2)

\*(Instructions on page 2)

RW 10-01-2019

## INSTRUCTIONS

**GENERAL:** This form is designed for submitting proposals to perform certain well operations, as indicated on Federal and Indian lands and leases for action by appropriate Federal agencies, pursuant to applicable Federal laws and regulations. Any necessary special instructions concerning the use of this form and the number of copies to be submitted, particularly with regard to local, area, or regional procedures and practices, either are shown below or will be issued by, or may be obtained from local Federal offices.

**ITEM 1:** If the proposal is to redrill to the same reservoir at a different subsurface location or to a new reservoir, use this form with appropriate notations. Consult applicable Federal regulations concerning subsequent work proposals or reports on the well.

**ITEM 4:** Locations on Federal or Indian land should be described in accordance with Federal requirements. Consult local Federal offices for specific instructions.

**ITEM 14:** Needed only when location of well cannot readily be found by road from the land or lease description. A plat, or plats, separate or on the reverse side, showing the roads to, and the surveyed location of, the well, and any other required information, should be furnished when required by Federal agency offices.

**ITEMS 15 AND 18:** If well is to be, or has been directionally drilled, give distances for subsurface location of hole in any present or objective productive zone.

**ITEM 22:** Consult applicable Federal regulations, or appropriate officials, concerning approval of the proposal before operations are started.

**ITEM 24:** If the proposal will involve hydraulic fracturing operations, you must comply with 43 CFR 3162.3-3, including providing information about the protection of usable water. Operators should provide the best available information about all formations containing water and their depths. This information could include data and interpretation of resistivity logs run on nearby wells. Information may also be obtained from state or tribal regulatory agencies and from local BLM offices.

## NOTICES

The Privacy Act of 1974 and regulation in 43 CFR 2.48(d) provide that you be furnished the following information in connection with information required by this application.

**AUTHORITY:** 30 U.S.C. 181 et seq., 25 U.S.C. 396; 43 CFR 3160

**PRINCIPAL PURPOSES:** The information will be used to: (1) process and evaluate your application for a permit to drill a new oil, gas, or service well or to reenter a plugged and abandoned well; and (2) document, for administrative use, information for the management, disposal and use of National Resource Lands and resources including (a) analyzing your proposal to discover and extract the Federal or Indian resources encountered; (b) reviewing procedures and equipment and the projected impact on the land involved; and (c) evaluating the effects of the proposed operation on the surface and subsurface water and other environmental impacts.

**ROUTINE USE:** Information from the record and/or the record will be transferred to appropriate Federal, State, and local or foreign agencies, when relevant to civil, criminal or regulatory investigations or prosecution, in connection with congressional inquiries and for regulatory responsibilities.

**EFFECT OF NOT PROVIDING INFORMATION:** Filing of this application and disclosure of the information is mandatory only if you elect to initiate a drilling or reentry operation on an oil and gas lease.

The Paperwork Reduction Act of 1995 requires us to inform you that:

The BLM collects this information to allow evaluation of the technical, safety, and environmental factors involved with drilling for oil and/or gas on Federal and Indian oil and gas leases. This information will be used to analyze and approve applications. Response to this request is mandatory only if the operator elects to initiate drilling or reentry operations on an oil and gas lease. The BLM would like you to know that you do not have to respond to this or any other Federal agency-sponsored information collection unless it displays a currently valid OMB control number.

**BURDEN HOURS STATEMENT:** Public reporting burden for this form is estimated to average 8 hours per response, including the time for reviewing instructions, gathering and maintaining data, and completing and reviewing the form. Direct comments regarding the burden estimate or any other aspect of this form to U.S. Department of the Interior, Bureau of Land Management (1004-0137), Bureau Information Connection Clearance Officer (WO-630), 1849 C Street, N.W., Mail Stop 401 L.S., Washington, D.C. 20240.

**Additional Operator Remarks**

**Location of Well**

- 1. SHL: SWSW / 867 FSL / 233 FWL / TWSP: 25S / RANGE: 28E / SECTION: 23 / LAT: 32.1105163 / LONG: -104.0657488 ( TVD: 0 feet, MD: 0 feet )  
PPP: NWSW / 1625 FSL / 330 FWL / TWSP: 25S / RANGE: 28E / SECTION: 23 / LAT: 32.1126034 / LONG: -104.0654326 ( TVD: 9385 feet, MD: 9441 feet )  
PPP: NWSW / 1625 FSL / 1327 FWL / TWSP: 25S / RANGE: 28E / SECTION: 24 / LAT: 32.112645 / LONG: -104.0450133 ( TVD: 9683 feet, MD: 15824 feet )  
PPP: NESE / 1625 FSL / 1327 FEL / TWSP: 25S / RANGE: 28E / SECTION: 24 / LAT: 32.1126613 / LONG: -104.0364896 ( TVD: 9731 feet, MD: 18463 feet )  
BHL: NESE / 1625 FSL / 330 FEL / TWSP: 25S / RANGE: 28E / SECTION: 24 / LAT: 32.1126674 / LONG: -104.0332694 ( TVD: 9749 feet, MD: 19460 feet )

**BLM Point of Contact**

Name: Tenille Ortiz  
Title: Legal Instruments Examiner  
Phone: 5752342224  
Email: tortiz@blm.gov

CONFIDENTIAL

## Review and Appeal Rights

A person contesting a decision shall request a State Director review. This request must be filed within 20 working days of receipt of the Notice with the appropriate State Director (see 43 CFR 3165.3). The State Director review decision may be appealed to the Interior Board of Land Appeals, 801 North Quincy Street, Suite 300, Arlington, VA 22203 (see 43 CFR 3165.4). Contact the above listed Bureau of Land Management office for further information.

CONFIDENTIAL

**PECOS DISTRICT  
DRILLING CONDITIONS OF APPROVAL**

<b>OPERATOR'S NAME:</b>	<b>Mewbourne Oil Company</b>
<b>LEASE NO.:</b>	<b>NMNM013413A</b>
<b>WELL NAME &amp; NO.:</b>	<b>Oxbow 23/24 W0LI Fed Com 1H</b>
<b>SURFACE HOLE FOOTAGE:</b>	<b>867'/S &amp; 233'/W</b>
<b>BOTTOM HOLE FOOTAGE:</b>	<b>1625'/S &amp; 330'/E</b>
<b>LOCATION:</b>	<b>Section 23, T.25 S., R.28 E., NMPM</b>
<b>COUNTY:</b>	<b>Eddy County, New Mexico</b>

COA

H2S	<input type="radio"/> Yes	<input checked="" type="radio"/> No	
Potash	<input checked="" type="radio"/> None	<input type="radio"/> Secretary	<input type="radio"/> R-111-P
Cave/Karst Potential	<input type="radio"/> Low	<input checked="" type="radio"/> Medium	<input type="radio"/> High
Variance	<input type="radio"/> None	<input checked="" type="radio"/> Flex Hose	<input type="radio"/> Other
Wellhead	<input type="radio"/> Conventional	<input checked="" type="radio"/> Multibowl	<input type="radio"/> Both
Other	<input type="checkbox"/> 4 String Area	<input type="checkbox"/> Capitan Reef	<input type="checkbox"/> WIPP
Other	<input type="checkbox"/> Fluid Filled	<input type="checkbox"/> Cement Squeeze	<input type="checkbox"/> Pilot Hole
Special Requirements	<input type="checkbox"/> Water Disposal	<input type="checkbox"/> COM	<input type="checkbox"/> Unit

**A. HYDROGEN SULFIDE**

Hydrogen Sulfide (H2S) monitors shall be installed prior to drilling out the surface shoe. If H2S is detected in concentrations greater than 100 ppm, the Hydrogen Sulfide area shall meet Onshore Order 6 requirements, which includes equipment and personnel/public protection items. If Hydrogen Sulfide is encountered, provide measured values and formations to the BLM.

**B. CASING**

1. The **13-3/8** inch surface casing shall be set at approximately **500** feet (a minimum of **70 feet (Eddy County)** into the Rustler Anhydrite and above the salt) and cemented to the surface.
  - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.
  - b. Wait on cement (WOC) time for a primary cement job will be a minimum of **8 hours** or 500 pounds compressive strength, whichever is greater. (This is to

- include the lead cement)
  - c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.
  - d. If cement falls back, remedial cementing will be done prior to drilling out that string.
2. The minimum required fill of cement behind the **9-5/8** inch intermediate casing is:
- a. Cement to surface. If cement does not circulate see B.1.a, c-d above.
- Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to cave/karst or potash.**

❖ In Medium Cave/Karst Areas if cement does not circulate to surface on the first two casing strings, the cement on the 3rd casing string must come to surface.

3. The minimum required fill of cement behind the **7** inch production casing is:

Operator has proposed a DV tool, the depth may be adjusted as long as the cement is changed proportionally. The DV tool may be cancelled if cement circulates to surface on the first stage.

- a. First stage to DV tool: Cement to circulate. If cement does not circulate off the DV tool, contact the appropriate BLM office before proceeding with second stage cement job.
  - b. Second stage above DV tool: Cement should tie-back at least **200 feet** into previous casing string. Operator shall provide method of verification.
4. The minimum required fill of cement behind the **4-1/2** inch production liner is: Cement should tie-back **100 feet** into the previous casing. Operator shall provide method of verification.

### **C. PRESSURE CONTROL**

1. Variance approved to use flex line from BOP to choke manifold. Manufacturer's specification to be readily available. No external damage to flex line. Flex line to be installed as straight as possible (no hard bends).
2. Operator has proposed a multi-bowl wellhead assembly. This assembly will only be tested when installed on the surface casing. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be **5000 (5M)** psi.
  - a. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
  - b. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.

- c. Manufacturer representative shall install the test plug for the initial BOP test.
- d. If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
- e. Whenever any seal subject to test pressure is broken, all the tests in OOGO2.III.A.2.i must be followed.

## GENERAL REQUIREMENTS

The BLM is to be notified in advance for a representative to witness:

- a. Spudding well (minimum of 24 hours)
- b. Setting and/or Cementing of all casing strings (minimum of 4 hours)
- c. BOPE tests (minimum of 4 hours)

Chaves and Roosevelt Counties  
 Call the Roswell Field Office, 2909 West Second St., Roswell NM 88201.  
 During office hours call (575) 627-0272.  
 After office hours call (575)

Eddy County  
 Call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220,  
 (575) 361-2822

Lea County  
 Call the Hobbs Field Station, 414 West Taylor, Hobbs NM 88240, (575)  
 393-3612

1. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval.
  - a. In the event the operator has proposed to drill multiple wells utilizing a skid/walking rig. Operator shall secure the wellbore on the current well, after installing and testing the wellhead, by installing a blind flange of like pressure rating to the wellhead and a pressure gauge that can be monitored while drilling is performed on the other well(s).
  - b. When the operator proposes to set surface casing with Spudder Rig
    - Notify the BLM when moving in and removing the Spudder Rig.
    - Notify the BLM when moving in the 2<sup>nd</sup> Rig. Rig to be moved in within 90 days of notification that Spudder Rig has left the location.
    - BOP/BOPE test to be conducted per Onshore Oil and Gas Order No. 2 as soon as 2nd Rig is rigged up on well.

2. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works are located, this does not include the dog house or stairway area.
3. The record of the drilling rate along with the GR/N well log run from TD to surface (horizontal well – vertical portion of hole) shall be submitted to the BLM office as well as all other logs run on the borehole 30 days from completion. If available, a digital copy of the logs is to be submitted in addition to the paper copies. The Rustler top and top and bottom of Salt are to be recorded on the Completion Report.

A. CASING

1. Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size or are Non-API. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.). The initial wellhead installed on the well will remain on the well with spools used as needed.
2. Wait on cement (WOC) for Potash Areas: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi for all cement blends, 2) until cement has been in place at least 24 hours. WOC time will be recorded in the driller's log.
3. Wait on cement (WOC) for Water Basin: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi at the shoe, 2) until cement has been in place at least 8 hours. WOC time will be recorded in the driller's log. See individual casing strings for details regarding lead cement slurry requirements.
4. Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. Have well specific cement details onsite prior to pumping the cement for each casing string.
5. No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.
6. On that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Formation at the shoe shall be tested to a minimum of the mud weight equivalent anticipated to control the

formation pressure to the next casing depth or at total depth of the well. This test shall be performed before drilling more than 20 feet of new hole.

7. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.
8. Whenever a casing string is cemented in the R-111-P potash area, the NMOCD requirements shall be followed.

#### B. PRESSURE CONTROL

1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in Onshore Oil and Gas Order No. 2 and API RP 53 Sec. 17.
2. If a variance is approved for a flexible hose to be installed from the BOP to the choke manifold, the following requirements apply: Check condition of flexible line from BOP to choke manifold, replace if exterior is damaged or if line fails test. Line to be as straight as possible with no hard bends and is to be anchored according to Manufacturer's requirements. The flexible hose can be exchanged with a hose of equal size and equal or greater pressure rating. Anchor requirements, specification sheet and hydrostatic pressure test certification matching the hose in service, to be onsite for review. These documents shall be posted in the company man's trailer and on the rig floor.
3. 5M or higher system requires an HCR valve, remote kill line and annular to match. The remote kill line is to be installed prior to testing the system and tested to stack pressure.
4. If the operator has proposed a multi-bowl wellhead assembly in the APD. The following requirements must be met:
  - a. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
  - b. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
  - c. Manufacturer representative shall install the test plug for the initial BOP test.
  - d. Whenever any seal subject to test pressure is broken, all the tests in OOGO2.III.A.2.i must be followed.
  - e. If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.

5. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.
  - a. In a water basin, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. The casing cut-off and BOP installation can be initiated four hours after installing the slips, which will be approximately six hours after bumping the plug. For those casing strings not using slips, the minimum wait time before cut-off is eight hours after bumping the plug. BOP/BOPE testing can begin after cut-off or once cement reaches 500 psi compressive strength (including lead when specified), whichever is greater. However, if the float does not hold, cut-off cannot be initiated until cement reaches 500 psi compressive strength (including lead when specified).
  - b. In potash areas, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. For all casing strings, casing cut-off and BOP installation can be initiated at twelve hours after bumping the plug. However, **no tests** shall commence until the cement has had a minimum of 24 hours setup time.
  - c. The tests shall be done by an independent service company utilizing a test plug not a cup or J-packer. The operator also has the option of utilizing an independent tester to test without a plug (i.e. against the casing) pursuant to Onshore Order 2 with the pressure not to exceed 70% of the burst rating for the casing. Any test against the casing must meet the WOC time for water basin (8 hours) or potash (24 hours) or 500 pounds compressive strength, whichever is greater, prior to initiating the test (see casing segment as lead cement may be critical item).
  - d. The test shall be run on a 5000 psi chart for a 2-3M BOP/BOP, on a 10000 psi chart for a 5M BOP/BOPE and on a 15000 psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one hour chart. A circular chart shall have a maximum 2 hour clock. If a twelve hour or twenty-four hour chart is used, tester shall make a notation that it is run with a two hour clock.
  - e. The results of the test shall be reported to the appropriate BLM office.
  - f. All tests are required to be recorded on a calibrated test chart. A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.
  - g. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug. This test shall be performed prior to the test at full stack pressure.

- h. BOP/BOPE must be tested by an independent service company within 500 feet of the top of the Wolfcamp formation if the time between the setting of the intermediate casing and reaching this depth exceeds 20 days. This test does not exclude the test prior to drilling out the casing shoe as per Onshore Order No. 2.

C. DRILLING MUD

Mud system monitoring equipment, with derrick floor indicators and visual and audio alarms, shall be operating before drilling into the Wolfcamp formation, and shall be used until production casing is run and cemented.

D. WASTE MATERIAL AND FLUIDS

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area.

Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.

**JJP09132019**

**PECOS DISTRICT  
SURFACE USE  
CONDITIONS OF APPROVAL**

OPERATOR'S NAME:	Mewbourne Oil Company
WELL NAME & NO.:	Oxbow 23/24 WOLI Fed Com 1H
SURFACE HOLE FOOTAGE:	867'/S & 233'/W
BOTTOM HOLE FOOTAGE:	1625'/S & 330'/E
LOCATION:	Section 23, T.25 S., R.28 E., NMPM
COUNTY:	Eddy County, New Mexico

**TABLE OF CONTENTS**

Standard Conditions of Approval (COA) apply to this APD. If any deviations to these standards exist or special COAs are required, the section with the deviation or requirement will be checked below.

- General Provisions**
- Permit Expiration**
- Archaeology, Paleontology, and Historical Sites**
- Noxious Weeds**
- Special Requirements**
  - Hydrology**
  - Cave/Karst
  - Special Status Plant Species Habitat
  - Texas Hornshell
- Construction**
  - Notification
  - Topsoil
  - Closed Loop System
  - Federal Mineral Material Pits
  - Well Pads
  - Roads
- Road Section Diagram**
- Production (Post Drilling)**
  - Well Structures & Facilities
- Interim Reclamation**
- Final Abandonment & Reclamation**

## **I. GENERAL PROVISIONS**

The approval of the Application For Permit To Drill (APD) is in compliance with all applicable laws and regulations: 43 Code of Federal Regulations 3160, the lease terms, Onshore Oil and Gas Orders, Notices To Lessees, New Mexico Oil Conservation Division (NMOCD) Rules, National Historical Preservation Act As Amended, and instructions and orders of the Authorized Officer. Any request for a variance shall be submitted to the Authorized Officer on Form 3160-5, Sundry Notices and Report on Wells.

## **II. PERMIT EXPIRATION**

If the permit terminates prior to drilling and drilling cannot be commenced within 60 days after expiration, an operator is required to submit Form 3160-5, Sundry Notices and Reports on Wells, requesting surface reclamation requirements for any surface disturbance. However, if the operator will be able to initiate drilling within 60 days after the expiration of the permit, the operator must have set the conductor pipe in order to allow for an extension of 60 days beyond the expiration date of the APD. (Filing of a Sundry Notice is required for this 60 day extension.)

## **III. ARCHAEOLOGICAL, PALEONTOLOGY & HISTORICAL SITES**

Any cultural and/or paleontological resource discovered by the operator or by any person working on the operator's behalf shall immediately report such findings to the Authorized Officer. The operator is fully accountable for the actions of their contractors and subcontractors. The operator shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery shall be made by the Authorized Officer to determine the appropriate actions that shall be required to prevent the loss of significant cultural or scientific values of the discovery. The operator shall be held responsible for the cost of the proper mitigation measures that the Authorized Officer assesses after consultation with the operator on the evaluation and decisions of the discovery. Any unauthorized collection or disturbance of cultural or paleontological resources may result in a shutdown order by the Authorized Officer.

## **IV. NOXIOUS WEEDS**

The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes the roads, pads, associated pipeline corridor, and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

## V. SPECIAL REQUIREMENT(S)

### Hydrology:

The entire well pad(s) will be bermed to prevent oil, salt, and other chemical contaminants from leaving the well pad. The compacted berm shall be constructed at a minimum of 12 inches with impermeable mineral material (e.g. caliche). Topsoil shall not be used to construct the berm. No water flow from the uphill side(s) of the pad shall be allowed to enter the well pad. The integrity of the berm shall be maintained around the surfaced pad throughout the life of the well and around the downsized pad after interim reclamation has been completed. Any water erosion that may occur due to the construction of the well pad during the life of the well will be quickly corrected and proper measures will be taken to prevent future erosion. Stockpiling of topsoil is required. The top soil shall be stockpiled in an appropriate location to prevent loss of soil due to water or wind erosion and not used for berming or erosion control. If fluid collects within the bermed area, the fluid must be vacuumed into a safe container and disposed of properly at a state approved facility.

Tank battery locations will be lined and bermed. A 20 mil permanent liner will be installed with a 4 oz. felt backing to prevent tears or punctures. Tank battery berms must be large enough to contain 1 ½ times the content of the largest tank or 24 hour production, whichever is greater. Automatic shut off, check valves, or similar systems will be installed for tanks to minimize the effects of catastrophic line failures used in production or drilling.

When crossing ephemeral drainages the pipeline(s) will be buried to a minimum depth of 48 inches from the top of pipe to ground level. Erosion control methods such as gabions and/or rock aprons should be placed on both up and downstream sides of the pipeline crossing. In addition, curled (weed free) wood/straw fiber wattles/logs and/or silt fences should be placed on the downstream side for sediment control during construction and maintained until soils and vegetation have stabilized. Water bars should be placed within the ROW to divert and dissipate surface runoff. A pipeline access road is not permitted to cross these ephemeral drainages. Traffic should be diverted to a preexisting route. Additional seeding may be required in floodplains and drainages to restore energy dissipating vegetation.

Prior to pipeline installation a leak detection plan should be developed. The method could incorporate gauges to detect pressure drops, situating valves and lines so they can be visually inspected periodically or installing electronic sensors to alarm when a leak is present. The leak detection plan will incorporate an automatic shut off system that will be installed for proposed pipelines to minimize the effects of an undesirable event.

Any water erosion that may occur due to the construction of overhead electric line and during the life of the power line will be quickly corrected and proper measures will be taken to prevent future erosion. A power pole should not be placed in drainages, playas,

wetlands, riparian areas, or floodplains and must span across the features at a distance away that would not promote further erosion.

**Special Status Plant Species (SSPS) Habitat Stipulations:**

Vehicles and equipment will be kept on existing roads and approved surfaces only, and will avoid travel across undisturbed surfaces; workers will be instructed not to park off the roads or ROW in undisturbed areas. Alterations to project design and additions of project components will require SSPS surveys and re-analysis of impacts if those project elements intersect SSPS suitable habitat.

**Texas Hornshell**

Oil and Gas and Associated Infrastructure Mitigation Measures for Zone D – CCA  
Boundary Requirements:

- Provide CEHMM with the permit, lease grant, or other authorization form BLM, if applicable.
- Provide CEHMM with plats or other electronic media describing the new surface disturbance for the project.

**Karst Resources**

**Cave/Karst Surface Mitigation**

The following stipulations will be applied to minimize impacts during construction, drilling and production:

**Construction:**

**General Construction:**

- No blasting
- The BLM, Carlsbad Field Office, will be informed immediately if any subsurface drainage channels, cave passages, or voids are penetrated during construction, and no additional construction shall occur until clearance has been issued by the Authorized Officer.
- All linear surface disturbance activities will avoid sinkholes and other karst features to lessen the possibility of encountering near surface voids during construction, minimize changes to runoff, and prevent untimely leaks and spills from entering the karst drainage system.
- All spills or leaks will be reported to the BLM immediately for their immediate and proper treatment.

**Pad Construction:**

- The pad will be constructed and leveled by adding the necessary fill and caliche – no blasting.

- The entire perimeter of the well pad will be bermed to prevent oil, salt, and other chemical contaminants from leaving the well pad.
- The compacted berm shall be constructed at a minimum of 12 inches high with impermeable mineral material (e.g., caliche).
- No water flow from the uphill side(s) of the pad shall be allowed to enter the well pad.
- The topsoil stockpile shall be located outside the bermed well pad.
- Topsoil, either from the well pad or surrounding area, shall not be used to construct the berm.
- No storm drains, tubing or openings shall be placed in the berm.
- If fluid collects within the bermed area, the fluid must be vacuumed into a safe container and disposed of properly at a state approved facility.
- The integrity of the berm shall be maintained around the surfaced pad throughout the life of the well and around the downsized pad after interim reclamation has been completed.
- Any access road entering the well pad shall be constructed so that the integrity of the berm height surrounding the well pad is not compromised (i.e. an access road crossing the berm cannot be lower than the berm height).
- Following a rain event, all fluids will vacuumed off of the pad and hauled off-site and disposed at a proper disposal facility.

**Tank Battery Construction:**

- The pad will be constructed and leveled by adding the necessary fill and caliche – no blasting.
- All tank battery locations and facilities will be lined and bermed.
- The liner should be at least 20 mil in thickness and installed with a 4 oz. felt backing, or equivalent, to prevent tears or punctures.
- Tank battery berms must be large enough to contain 1 ½ times the content of the largest tank.

**Road Construction:**

- Turnout ditches and drainage leadoffs will not be constructed in such a manner as to alter the natural flow of water into or out of cave or karst features.
- Special restoration stipulations or realignment may be required if subsurface features are discovered during construction.

**Buried Pipeline/Cable Construction:**

- Rerouting of the buried line(s) may be required if a subsurface void is encountered during construction to minimize the potential subsidence/collapse of the feature(s) as well as the possibility of leaks/spills entering the karst drainage system.

**Powerline Construction:**

- Smaller powerlines will be routed around sinkholes and other karst features to avoid or lessen the possibility of encountering near surface voids and to

minimize changes to runoff or possible leaks and spills from entering karst systems.

- Larger powerlines will adjust their pole spacing to avoid cave and karst features.
- Special restoration stipulations or realignment may be required if subsurface voids are encountered.

**Surface Flowlines Installation:**

- Flowlines will be routed around sinkholes and other karst features to minimize the possibility of leaks/spills from entering the karst drainage system.

**Leak Detection System:**

- A method of detecting leaks is required. The method could incorporate gauges to measure loss, situating valves and lines so they can be visually inspected, or installing electronic sensors to alarm when a leak is present.
- A leak detection plan will be submitted to BLM that incorporates an automatic shut off system (see below) to minimize the effects of an undesirable event that could negatively sensitive cave/karst resources.
- Well heads, pipelines (surface and buried), storage tanks, and all supporting equipment should be monitored regularly after installation to promptly identify and fix leaks.

**Automatic Shut-off Systems:**

- Automatic shut off, check valves, or similar systems will be installed for pipelines and tanks to minimize the effects of catastrophic line failures used in production or drilling.

**Cave/Karst Subsurface Mitigation**

The following stipulations will be applied to protect cave/karst and groundwater concerns:

**Closed Loop System:**

- A closed loop system using steel tanks will be utilized during drilling – no pits
- All fluids and cuttings will be hauled off-site and disposed of properly at an authorized site

**Rotary Drilling with Fresh Water:**

- Fresh water will be used as a circulating medium in zones where caves or karst features are expected. SEE ALSO: Drilling COAs for this well.

**Directional Drilling:**

- The kick off point for directional drilling will occur at least 100 feet below the bottom of the cave occurrence zone. SEE ALSO: Drilling COAs for this well.

**Lost Circulation:**

- ALL lost circulation zones between surface and the base of the cave occurrence zone will be logged and reported in the drilling report.
- If a void of four feet or more and circulation losses greater than 70 percent occur simultaneously while drilling in any cave-bearing zone, regardless of the type of drilling machinery used, the BLM will be notified immediately by the operator. The BLM will assess the situation and work with the operator on corrective actions to resolve the problem.

**Abandonment Cementing:**

- Additional plugging conditions of approval may be required upon well abandonment in high and medium karst potential occurrence zones.
- The BLM will assess the situation and work with the operator to ensure proper plugging of the wellbore.

**Pressure Testing:**

- The operator will perform annual pressure monitoring on all casing annuli and reported in a sundry notice.
- If the test results indicated a casing failure has occurred, remedial action will be undertaken to correct the problem to the BLM's approval.

## **VI. CONSTRUCTION**

### **A. NOTIFICATION**

The BLM shall administer compliance and monitor construction of the access road and well pad. Notify the Carlsbad Field Office at (575) 234-5909 at least 3 working days prior to commencing construction of the access road and/or well pad.

When construction operations are being conducted on this well, the operator shall have the approved APD and Conditions of Approval (COA) on the well site and they shall be made available upon request by the Authorized Officer.

### **B. TOPSOIL**

The operator shall strip the top portion of the soil (root zone) from the entire well pad area and stockpile the topsoil along the edge of the well pad as depicted in the APD. The root zone is typically six (6) inches in depth. All the stockpiled topsoil will be redistributed over the interim reclamation areas. Topsoil shall not be used for berming the pad or facilities. For final reclamation, the topsoil shall be spread over the entire pad area for seeding preparation.

Other subsoil (below six inches) stockpiles must be completely segregated from the topsoil stockpile. Large rocks or subsoil clods (not evident in the surrounding terrain) must be buried within the approved area for interim and final reclamation.

### **C. CLOSED LOOP SYSTEM**

Tanks are required for drilling operations: No Pits.

The operator shall properly dispose of drilling contents at an authorized disposal site.

### **D. FEDERAL MINERAL MATERIALS PIT**

Payment shall be made to the BLM prior to removal of any federal mineral materials. Call the Carlsbad Field Office at (575) 234-5972.

### **E. WELL PAD SURFACING**

Surfacing of the well pad is not required.

If the operator elects to surface the well pad, the surfacing material may be required to be removed at the time of reclamation. The well pad shall be constructed in a manner which creates the smallest possible surface disturbance, consistent with safety and operational needs.

### **F. EXCLOSURE FENCING (CELLARS & PITS)**

**Exclosure Fencing**

The operator will install and maintain exclosure fencing for all open well cellars to prevent access to public, livestock, and large forms of wildlife before and after drilling operations until the pit is free of fluids and the operator initiates backfilling. (For examples of exclosure fencing design, refer to BLM's Oil and Gas Gold Book, Exclosure Fence Illustrations, Figure 1, Page 18.)

**G. ON LEASE ACCESS ROADS****Road Width**

The access road shall have a driving surface that creates the smallest possible surface disturbance and does not exceed fourteen (14) feet in width. The maximum width of surface disturbance, when constructing the access road, shall not exceed twenty-five (25) feet.

**Surfacing**

Surfacing material is not required on the new access road driving surface. If the operator elects to surface the new access road or pad, the surfacing material may be required to be removed at the time of reclamation.

Where possible, no improvements should be made on the unsurfaced access road other than to remove vegetation as necessary, road irregularities, safety issues, or to fill low areas that may sustain standing water.

The Authorized Officer reserves the right to require surfacing of any portion of the access road at any time deemed necessary. Surfacing may be required in the event the road deteriorates, erodes, road traffic increases, or it is determined to be beneficial for future field development. The surfacing depth and type of material will be determined at the time of notification.

**Crowning**

Crowning shall be done on the access road driving surface. The road crown shall have a grade of approximately 2% (i.e., a 1" crown on a 14' wide road). The road shall conform to Figure 1; cross section and plans for typical road construction.

**Ditching**

Ditching shall be required on both sides of the road.

**Turnouts**


Vehicle turnouts shall be constructed on the road. Turnouts shall be intervisible with interval spacing distance less than 1000 feet. Turnouts shall conform to Figure 1; cross section and plans for typical road construction.

**Drainage**

Drainage control systems shall be constructed on the entire length of road (e.g. ditches, sidehill out sloping and insloping, lead-off ditches, culvert installation, and low water crossings).

A typical lead-off ditch has a minimum depth of 1 foot below and a berm of 6 inches above natural ground level. The berm shall be on the down-slope side of the lead-off ditch.

#### Cross Section of a Typical Lead-off Ditch



All lead-off ditches shall be graded to drain water with a 1 percent minimum to 3 percent maximum ditch slope. The spacing interval are variable for lead-off ditches and shall be determined according to the formula for spacing intervals of lead-off ditches, but may be amended depending upon existing soil types and centerline road slope (in %);

#### Formula for Spacing Interval of Lead-off Ditches

Example - On a 4% road slope that is 400 feet long, the water flow shall drain water into a lead-off ditch. Spacing interval shall be determined by the following formula:

$$400 \text{ foot road with } 4\% \text{ road slope: } \frac{400'}{4\%} + 100' = 200' \text{ lead-off ditch interval}$$

#### Cattle guards

An appropriately sized cattle guard sufficient to carry out the project shall be installed and maintained at fence/road crossings. Any existing cattle guards on the access road route shall be repaired or replaced if they are damaged or have deteriorated beyond practical use. The operator shall be responsible for the condition of the existing cattle guards that are in place and are utilized during lease operations.

#### Fence Requirement

Where entry is granted across a fence line, the fence shall be braced and tied off on both sides of the passageway prior to cutting. The operator shall notify the private surface landowner or the grazing allotment holder prior to crossing any fences.

#### Public Access

Public access on this road shall not be restricted by the operator without specific written approval granted by the Authorized Officer.

- Construction Steps**
1. Salvage topsoil
  2. Construct road
  3. Redistribute topsoil
  4. Revegetate slopes




Figure 1. Cross-sections and plans for typical road sections representative of BLM resource or FS local and higher-class roads.

## VII. PRODUCTION (POST DRILLING)

### A. WELL STRUCTURES & FACILITIES

#### **Placement of Production Facilities**

Production facilities should be placed on the well pad to allow for maximum interim recontouring and revegetation of the well location.

#### **Exclosure Netting (Open-top Tanks)**

Immediately following active drilling or completion operations, the operator will take actions necessary to prevent wildlife and livestock access, including avian wildlife, to all open-topped tanks that contain or have the potential to contain salinity sufficient to cause harm to wildlife or livestock, hydrocarbons, or Resource Conservation and Recovery Act of 1976-exempt hazardous substances. At a minimum, the operator will net, screen, or cover open-topped tanks to exclude wildlife and livestock and prevent mortality. If the operator uses netting, the operator will cover and secure the open portion of the tank to prevent wildlife entry. The operator will net, screen, or cover the tanks until the operator removes the tanks from the location or the tanks no longer contain substances that could be harmful to wildlife or livestock. Use a maximum netting mesh size of 1 ½ inches. The netting must not be in contact with fluids and must not have holes or gaps.

#### **Chemical and Fuel Secondary Containment and Exclosure Screening**

The operator will prevent all hazardous, poisonous, flammable, and toxic substances from coming into contact with soil and water. At a minimum, the operator will install and maintain an impervious secondary containment system for any tank or barrel containing hazardous, poisonous, flammable, or toxic substances sufficient to contain the contents of the tank or barrel and any drips, leaks, and anticipated precipitation. The operator will dispose of fluids within the containment system that do not meet applicable state or U. S. Environmental Protection Agency livestock water standards in accordance with state law; the operator must not drain the fluids to the soil or ground. The operator will design, construct, and maintain all secondary containment systems to prevent wildlife and livestock exposure to harmful substances. At a minimum, the operator will install effective wildlife and livestock exclosure systems such as fencing, netting, expanded metal mesh, lids, and grate covers. Use a maximum netting mesh size of 1 ½ inches.

#### **Open-Vent Exhaust Stack Exclosures**

The operator will construct, modify, equip, and maintain all open-vent exhaust stacks on production equipment to prevent birds and bats from entering, and to discourage perching, roosting, and nesting. (*Recommended exclosure structures on open-vent exhaust stacks are in the shape of a cone.*) Production equipment includes, but may not be limited to, tanks, heater-treaters, separators, dehydrators, flare stacks, in-line units, and compressor mufflers.

#### **Containment Structures**

Proposed production facilities such as storage tanks and other vessels will have a secondary containment structure that is constructed to hold the capacity of 1.5 times the largest tank, plus freeboard to account for precipitation, unless more stringent protective requirements are deemed necessary.

#### **Painting Requirement**

All above-ground structures including meter housing that are not subject to safety requirements shall be painted a flat non-reflective paint color, **Shale Green** from the BLM Standard Environmental Color Chart (CC-001: June 2008).

### **VIII. INTERIM RECLAMATION**

During the life of the development, all disturbed areas not needed for active support of production operations should undergo interim reclamation in order to minimize the environmental impacts of development on other resources and uses.

Within six (6) months of well completion, operators should work with BLM surface management specialists (Jim Amos: 575-234-5909) to devise the best strategies to reduce the size of the location. Interim reclamation should allow for remedial well operations, as well as safe and efficient removal of oil and gas.

During reclamation, the removal of caliche is important to increasing the success of revegetating the site. Removed caliche that is free of contaminants may be used for road repairs, fire walls or for building other roads and locations. In order to operate the well or complete workover operations, it may be necessary to drive, park and operate on restored interim vegetation within the previously disturbed area. Disturbing revegetated areas for production or workover operations will be allowed. If there is significant disturbance and loss of vegetation, the area will need to be revegetated. Communicate with the appropriate BLM office for any exceptions/exemptions if needed.

All disturbed areas after they have been satisfactorily prepared need to be reseeded with the seed mixture provided below.

Upon completion of interim reclamation, the operator shall submit a Sundry Notices and Reports on Wells, Subsequent Report of Reclamation (Form 3160-5).

### **IX. FINAL ABANDONMENT & RECLAMATION**

At final abandonment, well locations, production facilities, and access roads must undergo "final" reclamation so that the character and productivity of the land are restored.

Earthwork for final reclamation must be completed within six (6) months of well plugging. All pads, pits, facility locations and roads must be reclaimed to a satisfactory revegetated, safe, and stable condition, unless an agreement is made with the landowner or BLM to keep the road and/or pad intact.

After all disturbed areas have been satisfactorily prepared, these areas need to be revegetated with the seed mixture provided below. Seeding should be accomplished by drilling on the contour whenever practical or by other approved methods. Seeding may need to be repeated until revegetation is successful, as determined by the BLM.

Operators shall contact a BLM surface protection specialist prior to surface abandonment operations for site specific objectives (Jim Amos: 575-234-5909).

**Seed Mixture 1 for Loamy Sites**

Holder shall seed all disturbed areas with the seed mixture listed below. The seed mixture shall be planted in the amounts specified in pounds of pure live seed (PLS)\* per acre. There shall be no primary or secondary noxious weeds in the seed mixture. Seed shall be tested and the viability testing of seed will be done in accordance with State law(s) and within nine (9) months prior to purchase. Commercial seed shall be either certified or registered seed. The seed container shall be tagged in accordance with State law(s) and available for inspection by the Authorized Officer.

Seed shall be planted using a drill equipped with a depth regulator to ensure proper depth regulator to ensure proper depth of planting where drilling is possible. The seed mixture shall be evenly and uniformly planted over the disturbed area (small/heavier seeds have a tendency to drop the bottom of the drill and are planted first). Holder shall take appropriate measures to ensure this does not occur. Where drilling is not possible, seed shall be broadcast and the area shall be raked or chained to cover the seed. When broadcasting the seed, the pounds per acre shall be doubled. The seeding shall be repeated until a satisfactory stand is established as determined by the Authorized Officer. Evaluation of growth may not be made before completion of at least one full growing season after seeding.

Species to be planted in pounds of pure live seed\* per acre:

<u>Species</u>	<u>lb/acre</u>
Plains lovegrass ( <i>Eragrostis intermedia</i> )	0.5
Sand dropseed ( <i>Sporobolus cryptandrus</i> )	1.0
Sideoats grama ( <i>Bouteloua curtipendula</i> )	5.0
Plains bristlegrass ( <i>Setaria macrostachya</i> )	2.0

\*Pounds of pure live seed:

Pounds of seed x percent purity x percent germination = pounds pure live seed



U.S. Department of the Interior  
BUREAU OF LAND MANAGEMENT

# Operator Certification Data Report

09/26/2019

## Operator Certification

*I hereby certify that I, or someone under my direct supervision, have inspected the drill site and access route proposed herein; that I am familiar with the conditions which currently exist; that I have full knowledge of state and Federal laws applicable to this operation; that the statements made in this APD package are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for the operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filing of false statements.*

**NAME:** Bradley Bishop

**Signed on:** 01/11/2019

**Title:** Regulatory

**Street Address:**

**City:**

**State:**

**Zip:**

**Phone:** (575)393-5905

**Email address:** bbishop@mewbourne.com

## Field Representative

**Representative Name:**

**Street Address:**

**City:**

**State:**

**Zip:**

**Phone:**

**Email address:**



APD ID: 10400037789

Submission Date: 01/16/2019

Highlighted data reflects the most recent changes

Operator Name: MEWBOURNE OIL COMPANY

Well Name: OXBOW 23/24 W0LI FED COM

Well Number: 1H

[Show Final Text](#)

Well Type: CONVENTIONAL GAS WELL

Well Work Type: Drill

**Section 1 - General**

APD ID: 10400037789

Tie to previous NOS?

Submission Date: 01/16/2019

BLM Office: CARLSBAD

User: Bradley Bishop

Title: Regulatory

Federal/Indian APD: FED

Is the first lease penetrated for production Federal or Indian? FED

Lease number: NMNM013413A

Lease Acres: 1280

Surface access agreement in place?

Allotted?

Reservation:

Agreement in place? NO

Federal or Indian agreement:

Agreement number:

Agreement name:

Keep application confidential? YES

Permitting Agent? NO

APD Operator: MEWBOURNE OIL COMPANY

Operator letter of designation:

**Operator Info**

Operator Organization Name: MEWBOURNE OIL COMPANY

Operator Address: PO Box 5270

Zip: 88240

Operator PO Box:

Operator City: Hobbs

State: NM

Operator Phone: (575)393-5905

Operator Internet Address:

**Section 2 - Well Information**

Well in Master Development Plan? NO

Master Development Plan name:

Well in Master SUPO? NO

Master SUPO name:

Well in Master Drilling Plan? NO

Master Drilling Plan name:

Well Name: OXBOW 23/24 W0LI FED COM

Well Number: 1H

Well API Number:

Field/Pool or Exploratory? Field and Pool

Field Name: WILDCAT  
WOLFCAMP

Pool Name: WOLFCAMP GAS

Is the proposed well in an area containing other mineral resources? NONE

Operator Name: MEWBOURNE OIL COMPANY

Well Name: OXBOW 23/24 WOLI FED COM

Well Number: 1H

Is the proposed well in an area containing other mineral resources? NONE

Is the proposed well in a Helium production area? NO Use Existing Well Pad? NO New surface disturbance?

Type of Well Pad: MULTIPLE WELL

Multiple Well Pad Name:

Number: 4

Well Class: HORIZONTAL

OXBOW 23/24 LI & MP

Number of Legs: 1

Well Work Type: Drill

Well Type: CONVENTIONAL GAS WELL

Describe Well Type:

Well sub-Type: EXPLORATORY (WILDCAT)

Describe sub-type:

Distance to town: 8.5 Miles

Distance to nearest well: 50 FT

Distance to lease line: 330 FT

Reservoir well spacing assigned acres Measurement: 640 Acres

Well plat: Oxbow23\_24WOLIFedCom1H\_wellplat\_20190109141505.pdf

Well work start Date: 02/09/2019

Duration: 60 DAYS

Section 3 - Well Location Table

Survey Type: RECTANGULAR

Describe Survey Type:

Datum: NAD83

Vertical Datum: NAVD88

Survey number:

Reference Datum:

	NS-Foot	NS Indicator	EW-Foot	EW Indicator	Twsp	Range	Section	Aliquot/Lot/Tract	Latitude	Longitude	County	State	Meridian	Lease Type	Lease Number	Elevation	MD	TVD
SHL Leg #1	867	FSL	233	FWL	25S	28E	23	Aliquot SWS W	32.1105163	-104.0657488	EDD Y	NEW MEXI CO	NEW MEXI CO	F	NMNM 013413 A	2959	0	0
KOP Leg #1	1625	FSL	233	FWL	25S	28E	23	Aliquot NWS W	32.1126027	-104.0657459	EDD Y	NEW MEXI CO	NEW MEXI CO	F	NMNM 013413 A	-6138	9131	9097
PPP Leg #1	1625	FSL	1327	FEL	25S	28E	24	Aliquot NESE	32.1126613	-104.0364896	EDD Y	NEW MEXI CO	NEW MEXI CO	F	NMNM 088128	-6772	18463	9731

Operator Name: MEWBOURNE OIL COMPANY

Well Name: OXBOW 23/24 W0LI FED COM

Well Number: 1H

	NS-Foot	NS Indicator	EW-Foot	EW Indicator	Twsp	Range	Section	Aliquot/Lot/Tract	Latitude	Longitude	County	State	Meridian	Lease Type	Lease Number	Elevation	MD	TVD
PPP Leg #1	162 5	FSL	132 7	FWL	25S	28E	24	Aliquot NWS W	32.11264 5	- 104.0450 133	EDD Y	NEW MEXI CO	NEW MEXI CO	F	NMNM 013413 A	- 672 4	158 24	968 3
PPP Leg #1	162 5	FSL	330	FWL	25S	28E	23	Aliquot NWS W	32.11260 34	- 104.0654 326	EDD Y	NEW MEXI CO	NEW MEXI CO	F	NMNM 013413 A	- 642 6	944 1	938 5
EXIT Leg #1	162 5	FSL	330	FEL	25S	28E	24	Aliquot NESE	32.11266 74	- 104.0332 694	EDD Y	NEW MEXI CO	NEW MEXI CO	F	NMNM 088128	- 679 0	194 60	974 9
BHL Leg #1	162 5	FSL	330	FEL	25S	28E	24	Aliquot NESE	32.11266 74	- 104.0332 694	EDD Y	NEW MEXI CO	NEW MEXI CO	F	NMNM 088128	- 679 0	194 60	974 9

Operator Name: MEWBOURNE OIL COMPANY

Well Name: OXBOW 23/24 W0LI FED COM

Well Number: 1H

Pressure Rating (PSI): 5M

Rating Depth: 19460

Equipment: Annular, Blind Ram, Pipe Ram

Requesting Variance? YES

**Variance request:** A variance is requested for the use of a flexible choke line from the BOP to Choke Manifold. Anchors are not required by manufacturer. A multi-bowl wellhead is being used. See attached schematic.

**Testing Procedure:** BOP/BOPE will be tested by an independent service company to 250 psi low and the high pressure indicated above per Onshore Order 2 requirements. The System may be upgraded to a higher pressure but still tested to the working pressure listed in the table above. If the system is upgraded all the components installed will be functional and tested. Pipe rams will be operationally checked each 24 hour period. Blind rams will be operationally checked on each trip out of the hole. These checks will be noted on the daily tour sheets. Other accessories to the BOP equipment will include a Kelly cock and floor safety valve (inside BOP) and choke lines and choke manifold. See attached schematics.

**Choke Diagram Attachment:**

Oxbow\_23\_24\_W0LI\_Fed\_Com\_1H\_5M\_BOPE\_Choke\_Diagram\_20190115103254.pdf

Oxbow\_23\_24\_W0LI\_Fed\_Com\_1H\_Flex\_Line\_Specs\_20190115103255.pdf

**BOP Diagram Attachment:**

Oxbow\_23\_24\_W0LI\_Fed\_Com\_1H\_5M\_BOPE\_Schematic\_20190115103308.pdf

Oxbow\_23\_24\_W0LI\_Fed\_Com\_1H\_Multi\_Bowl\_WH\_20190115103308.pdf

### Section 3 - Casing

Casing ID	String Type	Hole Size	Csg Size	Condition	Standard	Tapered String	Top Set MD	Bottom Set MD	Top Set TVD	Bottom Set TVD	Top Set MSL	Bottom Set MSL	Calculated casing length MD	Grade	Weight	Joint Type	Collapse SF	Burst SF	Joint SF Type	Joint SF	Body SF Type	Body SF
1	SURFACE	17.5	13.625	NEW	API	N	0	500	0	500			500	H-40	48	ST&C	3.37	7.56	DRY	13.42	DRY	22.54
2	INTERMEDIATE	12.25	9.625	NEW	API	N	0	2610	0	2610			2610	J-55	36	LT&C	1.49	2.59	DRY	4.82	DRY	6
3	PRODUCTION	8.75	7.0	NEW	API	N	0	9872	0	9574			9872	HCP-110	26	LT&C	1.65	2.1	DRY	2.7	DRY	3.23
4	LINER	6.125	4.5	NEW	API	N	9131	19460	9097	9749			10329	P-110	13.5	LT&C	1.62	1.88	DRY	2.42	DRY	3.03

Casing Attachments

**Operator Name:** MEWBOURNE OIL COMPANY

**Well Name:** OXBOW 23/24 W0LI FED COM

**Well Number:** 1H

**Casing Attachments**

---

**Casing ID:** 1      **String Type:** SURFACE

**Inspection Document:**

**Spec Document:**

**Tapered String Spec:**

**Casing Design Assumptions and Worksheet(s):**

Oxbow\_23\_24\_W0LI\_Fed\_Com\_1H\_Csg\_Assumptions\_20190110104335.pdf

---

**Casing ID:** 2      **String Type:** INTERMEDIATE

**Inspection Document:**

**Spec Document:**

**Tapered String Spec:**

**Casing Design Assumptions and Worksheet(s):**

Oxbow\_23\_24\_W0LI\_Fed\_Com\_1H\_Csg\_Assumptions\_20190110104425.pdf

---

**Casing ID:** 3      **String Type:** PRODUCTION

**Inspection Document:**

**Spec Document:**

**Tapered String Spec:**

**Casing Design Assumptions and Worksheet(s):**

Oxbow\_23\_24\_W0LI\_Fed\_Com\_1H\_Csg\_Assumptions\_20190110104612.pdf

---

Operator Name: MEWBOURNE OIL COMPANY

Well Name: OXBOW 23/24 W0LI FED COM

Well Number: 1H

Casing Attachments

Casing ID: 4 String Type: LINER

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

Oxbow\_23\_24\_W0LI\_Fed\_Com\_1H\_Csg\_Assumptions\_20190110104724.pdf

Section 4 - Cement

String Type	Lead/Tail	Stage Tool Depth	Top MD	Bottom MD	Quantity (sx)	Yield	Density	Cu Ft	Excess%	Cement type	Additives
SURFACE	Lead		0	307	205	2.12	12.5	435	100	Class C	Salt, Gel, Extender, LCM
SURFACE	Tail		307	500	200	1.34	14.8	268	100	Class C	Retarder
INTERMEDIATE	Lead		0	1951	380	2.12	12.5	806	25	Class C	Salt, Gel, Extender, LCM
INTERMEDIATE	Tail		1951	2610	200	1.34	14.8	268	25	Class C	Retarder
PRODUCTION	Lead	3710	2410	3032	290	2.12	12.5	615	25	Class C	Gel, Retarder, Defoamer, Extender
PRODUCTION	Tail		3032	3710	100	1.34	14.8	134	25	Class H	Retarder, Fluid Loss, Defoamer
PRODUCTION	Lead	3710	3710	7427	345	2.12	12.5	731	25	Class C	Gel, Retarder, Defoamer, Extender
PRODUCTION	Tail		7427	9872	400	1.18	15.6	472	25	Class H	Retarder, Fluid Loss, Defoamer
LINER	Lead		9131	19460	415	2.97	11.2	1233	25	Class C	Salt, Gel, Fluid Loss, Retarder, Dispersant, Defoamer, Anti-Settling Agent

Operator Name: MEWBORNE OIL COMPANY

Well Name: OXBOW 23/24 WOLI FED COM

Well Number: 1H

### Section 5 - Circulating Medium

Mud System Type: Closed

Will an air or gas system be Used? NO

Description of the equipment for the circulating system in accordance with Onshore Order #2:

Diagram of the equipment for the circulating system in accordance with Onshore Order #2:

Describe what will be on location to control well or mitigate other conditions: Sufficient mud materials to maintain mud properties & meet minimum lost circulation and weight increase requirements will be kept on location at all times.

Describe the mud monitoring system utilized: Pason/PVT/Visual Monitoring

### Circulating Medium Table

Top Depth	Bottom Depth	Mud Type	Min Weight (lbs/gal)	Max Weight (lbs/gal)	Density (lbs/cu ft)	Gel Strength (lbs/100 sqft)	PH	Viscosity (CP)	Salinity (ppm)	Filtration (cc)	Additional Characteristics
0	500	SPUD MUD	8.6	8.8							
500	2610	SALT SATURATED	10	10							
2610	9574	WATER-BASED MUD	8.6	9.7							
9574	9749	OIL-BASED MUD	10	12							MW up to 13.0 ppg may be required for shale control. The highest MW needed to balance formation pressure is expected to be 12.0 ppg.

**Operator Name:** MEWBOURNE OIL COMPANY

**Well Name:** OXBOW 23/24 WOLI FED COM

**Well Number:** 1H

### Section 6 - Test, Logging, Coring

**List of production tests including testing procedures, equipment and safety measures:**

Will run GR/CNL from KOP (9131') to surface

Will run MWD GR from KOP (9131') to TD

**List of open and cased hole logs run in the well:**

CNL,GR,MWD,MUDLOG

**Coring operation description for the well:**

None

### Section 7 - Pressure

**Anticipated Bottom Hole Pressure:** 6590

**Anticipated Surface Pressure:** 4445.21

**Anticipated Bottom Hole Temperature(F):** 165

**Anticipated abnormal pressures, temperatures, or potential geologic hazards?** NO

**Describe:**

**Contingency Plans geohazards description:**

**Contingency Plans geohazards attachment:**

**Hydrogen Sulfide drilling operations plan required?** YES

**Hydrogen sulfide drilling operations plan:**

Oxbow\_23\_24\_WOLI\_Fed\_Com\_1H\_H2S\_Plan\_20190829154421.pdf

### Section 8 - Other Information

**Proposed horizontal/directional/multi-lateral plan submission:**

Oxbow\_23\_24\_WOLI\_Fed\_Com\_1H\_Dir\_Plan\_20190110140948.pdf

Oxbow\_23\_24\_WOLI\_Fed\_Com\_1H\_Dir\_Plot\_20190110140948.pdf

**Other proposed operations facets description:**

**Other proposed operations facets attachment:**

Oxbow\_23\_24\_WOLI\_Fed\_Com\_1H\_C101\_20190110141007.pdf

Oxbow\_23\_24\_WOLI\_Fed\_Com\_1H\_Drlg\_Program\_20190110141008.pdf

**Other Variance attachment:**





GATES E & S NORTH AMERICA, INC.  
 134 44TH STREET  
 CORPUS CHRISTI, TEXAS 78405

PHONE: 361-887-9807  
 FAX: 361-887-0812  
 EMAIL: [Tim.Cantu@gates.com](mailto:Tim.Cantu@gates.com)  
 WEB: [www.gates.com](http://www.gates.com)

**10K CEMENTING ASSEMBLY PRESSURE TEST CERTIFICATE**

Customer :	AUSTIN DISTRIBUTING	Test Date:	4/30/2015
Customer Ref. :	4060578	Hose Serial No.:	D-043015-7
Invoice No. :	500506	Created By:	JUSTIN CROPPER

Product Description:	10K3.548.0CK4.1/1610KFLGE/E LE		
End Fitting 1 :	4 1/16 10K FLG	End Fitting 2 :	4 1/16 10K FLG
Gates Part No. :	4773-6290	Assembly Code :	L36554102914D-043015-7
Working Pressure :	10,000 PSI	Test Pressure :	15,000 PSI

Gates E & S North America, Inc. certifies that the following hose assembly has been tested to the Gates Oilfield Roughneck Agreement/Specification requirements and passed the 15 minute hydrostatic test per API Spec 7K/Q1, Fifth Edition, June 2010, Test pressure 9.6.7 and per Table 9 to 15,000 psi in accordance with this product number. Hose burst pressure 9.6.7.2 exceeds the minimum of 2.5 times the working pressure per Table 9.

Quality Manager :	QUALITY
Date :	4/30/2015
Signature :	<i>Justin Cropper</i>

Production:	PRODUCTION
Date :	4/30/2015
Signature :	<i>Justin Cropper</i>

Form PTC - 01 Rev.02



60 MIN.





CHART POOL USA LTD.  
 PORTAGE, INDIANA

GATES ENGINEERING & SERVICES NA  
 MW 000-1HR  
 APR 30 1968  
 CANCELLED

Handwritten notes and calculations on the chart, including:  
 - "15000" written near the 15000 radial line.  
 - "10000" written near the 10000 radial line.  
 - "8000" written near the 8000 radial line.  
 - "6000" written near the 6000 radial line.  
 - "4000" written near the 4000 radial line.  
 - "2000" written near the 2000 radial line.  
 - "1000" written near the 1000 radial line.  
 - "500" written near the 500 radial line.  
 - "250" written near the 250 radial line.  
 - "125" written near the 125 radial line.  
 - "62.5" written near the 62.5 radial line.  
 - "31.25" written near the 31.25 radial line.  
 - "15.625" written near the 15.625 radial line.  
 - "7.8125" written near the 7.8125 radial line.  
 - "3.90625" written near the 3.90625 radial line.  
 - "1.953125" written near the 1.953125 radial line.  
 - "0.9765625" written near the 0.9765625 radial line.  
 - "0.48828125" written near the 0.48828125 radial line.  
 - "0.244140625" written near the 0.244140625 radial line.  
 - "0.1220703125" written near the 0.1220703125 radial line.  
 - "0.06103515625" written near the 0.06103515625 radial line.  
 - "0.030517578125" written near the 0.030517578125 radial line.  
 - "0.0152587890625" written near the 0.0152587890625 radial line.  
 - "0.00762939453125" written near the 0.00762939453125 radial line.  
 - "0.003814697265625" written near the 0.003814697265625 radial line.  
 - "0.0019073486328125" written near the 0.0019073486328125 radial line.  
 - "0.00095367431640625" written near the 0.00095367431640625 radial line.  
 - "0.000476837158203125" written near the 0.000476837158203125 radial line.  
 - "0.0002384185791015625" written near the 0.0002384185791015625 radial line.  
 - "0.00011920928955078125" written near the 0.00011920928955078125 radial line.  
 - "0.000059604644775390625" written near the 0.000059604644775390625 radial line.  
 - "0.0000298023223876953125" written near the 0.0000298023223876953125 radial line.  
 - "0.00001490116119384765625" written near the 0.00001490116119384765625 radial line.  
 - "0.000007450580596923828125" written near the 0.000007450580596923828125 radial line.  
 - "0.0000037252902984619140625" written near the 0.0000037252902984619140625 radial line.  
 - "0.00000186264514923095703125" written near the 0.00000186264514923095703125 radial line.  
 - "0.000000931322574615478515625" written near the 0.000000931322574615478515625 radial line.  
 - "0.0000004656612873077392578125" written near the 0.0000004656612873077392578125 radial line.  
 - "0.00000023283064365386962890625" written near the 0.00000023283064365386962890625 radial line.  
 - "0.000000116415321826934814453125" written near the 0.000000116415321826934814453125 radial line.  
 - "0.0000000582076609134674072265625" written near the 0.0000000582076609134674072265625 radial line.  
 - "0.00000002910383045673370361328125" written near the 0.00000002910383045673370361328125 radial line.  
 - "0.000000014551915228366851806640625" written near the 0.000000014551915228366851806640625 radial line.  
 - "0.0000000072759576141834259033203125" written near the 0.0000000072759576141834259033203125 radial line.  
 - "0.00000000363797880709171295166015625" written near the 0.00000000363797880709171295166015625 radial line.  
 - "0.000000001818989403545856475830078125" written near the 0.000000001818989403545856475830078125 radial line.  
 - "0.0000000009094947017729282379150390625" written near the 0.0000000009094947017729282379150390625 radial line.  
 - "0.00000000045474735088646411895751953125" written near the 0.00000000045474735088646411895751953125 radial line.  
 - "0.000000000227373675443232059478759765625" written near the 0.000000000227373675443232059478759765625 radial line.  
 - "0.0000000001136868377216160297393798828125" written near the 0.0000000001136868377216160297393798828125 radial line.  
 - "0.00000000005684341886080801486968994140625" written near the 0.00000000005684341886080801486968994140625 radial line.  
 - "0.000000000028421709430404007434844970703125" written near the 0.000000000028421709430404007434844970703125 radial line.  
 - "0.0000000000142108547152020037174224853515625" written near the 0.0000000000142108547152020037174224853515625 radial line.  
 - "0.00000000000710542735760100185871124267578125" written near the 0.00000000000710542735760100185871124267578125 radial line.  
 - "0.000000000003552713678800500929355621337890625" written near the 0.000000000003552713678800500929355621337890625 radial line.  
 - "0.0000000000017763568394002504646778106689453125" written near the 0.0000000000017763568394002504646778106689453125 radial line.  
 - "0.00000000000088817841970012523233890533447265625" written near the 0.00000000000088817841970012523233890533447265625 radial line.  
 - "0.00000000000044408920985006261616945266723828125" written near the 0.00000000000044408920985006261616945266723828125 radial line.  
 - "0.000000000000222044604925031308084726333619140625" written near the 0.000000000000222044604925031308084726333619140625 radial line.  
 - "0.0000000000001110223024625154040423631668095703125" written near the 0.0000000000001110223024625154040423631668095703125 radial line.  
 - "0.0000000000000555111512312577020211815840478828125" written near the 0.0000000000000555111512312577020211815840478828125 radial line.  
 - "0.0000000000000277555756156143510105907444419140625" written near the 0.0000000000000277555756156143510105907444419140625 radial line.  
 - "0.00000000000001387778780780717550529537222095703125" written near the 0.00000000000001387778780780717550529537222095703125 radial line.  
 - "0.00000000000000693889390390358775264768611095703125" written near the 0.00000000000000693889390390358775264768611095703125 radial line.  
 - "0.00000000000000346944695195179387632384305478828125" written near the 0.00000000000000346944695195179387632384305478828125 radial line.  
 - "0.000000000000001734723475975896938161921527394140625" written near the 0.000000000000001734723475975896938161921527394140625 radial line.  
 - "0.0000000000000008673617379879484690809607636970703125" written near the 0.0000000000000008673617379879484690809607636970703125 radial line.  
 - "0.00000000000000043368086899397423454048038184853515625" written near the 0.00000000000000043368086899397423454048038184853515625 radial line.  
 - "0.000000000000000216840434496987117270240190924267578125" written near the 0.000000000000000216840434496987117270240190924267578125 radial line.  
 - "0.0000000000000001084202172484935586351200954621337890625" written near the 0.0000000000000001084202172484935586351200954621337890625 radial line.  
 - "0.00000000000000005421010862424677931756004773119140625" written near the 0.00000000000000005421010862424677931756004773119140625 radial line.  
 - "0.000000000000000027105054312123389658780023865570703125" written near the 0.000000000000000027105054312123389658780023865570703125 radial line.  
 - "0.0000000000000000135525271560616948293900119327853515625" written near the 0.0000000000000000135525271560616948293900119327853515625 radial line.  
 - "0.00000000000000000677626357803084741469500596639267578125" written near the 0.00000000000000000677626357803084741469500596639267578125 radial line.  
 - "0.000000000000000003388131789015423707347502983196894140625" written near the 0.000000000000000003388131789015423707347502983196894140625 radial line.  
 - "0.0000000000000000016940658945077118536725014915974470703125" written near the 0.0000000000000000016940658945077118536725014915974470703125 radial line.  
 - "0.0000000000000000008470329472538559268361250745598723694140625" written near the 0.0000000000000000008470329472538559268361250745598723694140625 radial line.  
 - "0.0000000000000000004235164736269279634180625372799361970703125" written near the 0.0000000000000000004235164736269279634180625372799361970703125 radial line.  
 - "0.00000000000000000021175823681346398170903126863996809853515625" written near the 0.00000000000000000021175823681346398170903126863996809853515625 radial line.  
 - "0.0000000000000000001058791184067319908545063293199840478828125" written near the 0.0000000000000000001058791184067319908545063293199840478828125 radial line.  
 - "0.00000000000000000005293955920336599542727261465999202394140625" written near the 0.00000000000000000005293955920336599542727261465999202394140625 radial line.  
 - "0.000000000000000000026469779601682997713636307329996011970703125" written near the 0.000000000000000000026469779601682997713636307329996011970703125 radial line.  
 - "0.0000000000000000000132348898008414988568181536649980059853515625" written near the 0.0000000000000000000132348898008414988568181536649980059853515625 radial line.  
 - "0.00000000000000000000661744490042074942840907683249900299267578125" written near the 0.00000000000000000000661744490042074942840907683249900299267578125 radial line.  
 - "0.0000000000000000000033087224502103747142045384162499001496337890625" written near the 0.0000000000000000000033087224502103747142045384162499001496337890625 radial line.  
 - "0.0000000000000000000016543612251051873571022692081249900074819140625" written near the 0.0000000000000000000016543612251051873571022692081249900074819140625 radial line.  
 - "0.000000000000000000000827180612552593678551113454062499000374095703125" written near the 0.000000000000000000000827180612552593678551113454062499000374095703125 radial line.  
 - "0.00000000000000000000041359030627629683927555672703124990001870478828125" written near the 0.00000000000000000000041359030627629683927555672703124990001870478828125 radial line.  
 - "0.0000000000000000000002067951531381484196377783635156249900009352394140625" written near the 0.0000000000000000000002067951531381484196377783635156249900009352394140625 radial line.  
 - "0.000000000000000000000103397576569074209818889181757812499000046761970703125" written near the 0.000000000000000000000103397576569074209818889181757812499000046761970703125 radial line.  
 - "0.000000000000000000000051698788284537104944444590878906249900002338095703125" written near the 0.00000000000000000000005169878828453710494444590878906249900002338095703125 radial line.  
 - "0.00000000000000000000002584939414226855247222229543945312499000011690478828125" written near the 0.0000000000000000000000258493941422685524722229543945312499000011690478828125 radial line.  
 - "0.000000000000000000000012924697071134276236111147721970703124990000058452394140625" written near the 0.000000000000000000000012924697071134276236111147721970703124990000058452394140625 radial line.  
 - "0.00000000000000000000000646234853556713611805557386098531249900000292261970703125" written near the 0.00000000000000000000000646234853556713611805557386098531249900000292261970703125 radial line.  
 - "0.0000000000000000000000032311742677835559027777869304926562499000001461309853125" written near the 0.0000000000000000000000032311742677835559027777869304926562499000001461309853125 radial line.  
 - "0.000000000000000000000001615587133891777951388893465246328124990000007306549265625" written near the 0.000000000000000000000001615587133891777951388893465246328124990000007306549265625 radial line.  
 - "0.00000000000000000000000080779356694588897569444673262816406249900000036532746328125" written near the 0.00000000000000000000000080779356694588897569444673262816406249900000036532746328125 radial line.  
 - "0.0000000000000000000000004038967834729444878472233663140312499000000182663731640625" written near the 0.0000000000000000000000004038967834729444878472233663140312499000000182663731640625 radial line.  
 - "0.00000000000000000000000020194839173647224392361168157156249900000000913318658203125" written near the 0.00000000000000000000000020194839173647224392361168157156249900000000913318658203125 radial line.  
 - "0.00000000000000000000000010097419586823612196180584078787812499000000004566593291015625" written near the 0.00000000000000000000000010097419586823612196180584078787812499000000004566593291015625 radial line.  
 - "0.0000000000000000000000000504870979341180609809029203939390624990000000022832966455078125" written near the 0.0000000000000000000000000504870979341180609809029203939390624990000000022832966455078125 radial line.  
 - "0.00000000000000000000000002524354896705903049045146019696953124990000000114164832275390625" written near the 0.00000000000000000000000002524354896705903049045146019696953124990000000114164832275390625 radial line.  
 - "0.000000000000000000000000012621774483529515245225730098484765624990000000570824161376953125" written near the 0.000000000000000000000000012621774483529515245225730098484765624990000000570824161376953125 radial line.  
 - "0.000000000000000000000000006310887241764757622612865049242382812499000000285412080688476953125" written near the 0.000000000000000000000000006310887241764757622612865049242382812499000000285412080688476953125 radial line.  
 - "0.00000000000000000000000000315544362088237881130643252461196406249900000014270604034423828125" written near the 0.00000000000000000000000000315544362088237881130643252461196406249900000014270604034423828125 radial line.  
 - "0.0000000000000000000000000015777218104411894056532162623059820312499000000071353020172119640625" written near the 0.0000000000000000000000000015777218104411894056532162623059820312499000000071353020172119640625 radial line.  
 - "0.000000000000000000000000000788860905220594702826608131152991015624990000000356765100860598203125" written near the 0.000000000000000000000000000788860905220594702826608131152991015624990000000356765100860598203125 radial line.  
 - "0.0000000000000000000000000003944304526102973514133040655764955078124990000001783825504302991015625" written near the 0.0000000000000000000000000003944304526102973514133040655764955078124990000001783825504302991015625 radial line.  
 - "0.00000000000000000000000000019721522630514867570665203278747776406249900000008919127521514955078125" written near the 0.00000000000000000000000000019721522630514867570665203278747776406249900000008919127521514955078125 radial line.  
 - "0.0000000000000000000000000000986076131525743378533326163937388820312499000000044595637607572477640625" written near the 0.0000000000000000000000000000986076131525743378533326163937388820312499000000044595637607572477640625 radial line.  
 - "0.00000000000000000000000000004930380657628716892666630819686894140624990000000222978188037862388203125" written near the 0.000000000000000000000000000049303806576287168926666308196868941406249900000002229781880378623

# 5M BOPE & Closed Loop Equipment Schematic



Drawing not to scale

Note: All valves & lines on choke manifold are 4" unless otherwise noted. Exact manifold configuration may vary.



GATES E & S NORTH AMERICA, INC.  
 134 44TH STREET  
 CORPUS CHRISTI, TEXAS 78405

PHONE: 361-887-9807  
 FAX: 361-887-0812  
 EMAIL: [Tim.Cantu@gates.com](mailto:Tim.Cantu@gates.com)  
 WEB: [www.gates.com](http://www.gates.com)

**10K CEMENTING ASSEMBLY PRESSURE TEST CERTIFICATE**

Customer :	AUSTIN DISTRIBUTING	Test Date:	4/30/2015
Customer Ref. :	4060578	Hose Serial No.:	D-043015-7
Invoice No. :	500506	Created By:	JUSTIN CROPPER

Product Description: 10K3.548.0CK4.1/1610KFLGE/E LE

End Fitting 1 :	4 1/16 10K FLG	End Fitting 2 :	4 1/16 10K FLG
Gates Part No. :	4773-6290	Assembly Code :	L36554102914D-043015-7
Working Pressure :	10,000 PSI	Test Pressure :	15,000 PSI

Gates E & S North America, Inc. certifies that the following hose assembly has been tested to the Gates Oilfield Roughneck Agreement/Specification requirements and passed the 15 minute hydrostatic test per API Spec 7K/Q1, Fifth Edition, June 2010, Test pressure 9.6.7 and per Table 9 to 15,000 psi in accordance with this product number. Hose burst pressure 9.6.7.2 exceeds the minimum of 2.5 times the working pressure per Table 9.

Quality Manager :

QUALITY
4/30/2015
<i>Justin Cropper</i>

Production:

PRODUCTION
4/30/2015
<i>Justin Cropper</i>

Form PTC - 01 Rev.02






CHART POOL USA, INC.  
 PORTAGE, INDIANA

GATES ENGINEERING & SERVICES, INC.  
 APR 20 2005  
 APPROVED


60 MIN.

18000  
16000  
14000  
12000  
10000  
8000  
6000  
4000  
2000

HOSE ID 3 1/2  
 GRADE 10  
 TEST PRESSURE 15000 PSI  
 WORKING PRESSURE 10000 PSI  
 ASSEMBLY PRESSURE 12000 PSI  
 SERIAL 10172  
 END 13.1  
 10172-1994  
 10172-10172  
 13.1  
 15000 PSI

5 10 15 20 25 30 35


# 5M BOPE & Closed Loop Equipment Schematic



Drawing not to scale

Note: All valves & lines on choke manifold are 4" unless otherwise noted. Exact manifold configuration may vary.

# 5M BOPE & Closed Loop Equipment Schematic



Drawing not to scale

Note: All valves & lines on choke manifold are 4" unless otherwise noted. Exact manifold configuration may vary.



**GATES E & S NORTH AMERICA, INC.**  
 134 44TH STREET  
 CORPUS CHRISTI, TEXAS 78405

**PHONE: 361-887-9807**  
**FAX: 361-887-0812**  
**EMAIL: Tim.Cantu@gates.com**  
**WEB: www.gates.com**

**10K CEMENTING ASSEMBLY PRESSURE TEST CERTIFICATE**

Customer :	AUSTIN DISTRIBUTING	Test Date:	4/30/2015
Customer Ref. :	4060578	Hose Serial No.:	D-043015-7
Invoice No. :	500506	Created By:	JUSTIN CROPPER

Product Description: 10K3.548.0CK4.1/1610KFLGE/E LE

End Fitting 1 :	4 1/16 10K FLG	End Fitting 2 :	4 1/16 10K FLG
Gates Part No. :	4773-6290	Assembly Code :	L36554102914D-043015-7
Working Pressure :	10,000 PSI	Test Pressure :	15,000 PSI


**Gates E & S North America, Inc.** certifies that the following hose assembly has been tested to the Gates Oilfield Roughneck Agreement/Specification requirements and passed the 15 minute hydrostatic test per API Spec 7K/Q1, Fifth Edition, June 2010, Test pressure 9.6.7 and per Table 9 to 15,000 psi in accordance with this product number. Hose burst pressure 9.6.7.2 exceeds the minimum of 2.5 times the working pressure per Table 9.

Quality Manager :	QUALITY
Date :	4/30/2015
Signature :	<i>Justin Cropper</i>

Production:	PRODUCTION
Date :	4/30/2015
Signature :	<i>[Signature]</i>

Form PTC - 01 Rev.02





15

20

25

30

35

60 MIN

5

10

15

20

25

30

35

40

45

50

55

60

65

70

75

80

85

90

95

100

105

110

115

120

125

130

135

140

145

150

155

160

165

170

175

180

185

190

195

200

205

210

215

220

225

230

235

240

245

250

255

260

265

270

275

280

285

290

295

300

305

310

315

320

325

330

335

340

345

350

355

360

365

370

375

380

385

390

395

400

405

410

415

420

425

430

435

440

445

450

455

460

465

470

475

480

485

490

495

500

505

510

515

520

525

530

535

540

545

550

555

560

565

570

575

580

585

590

595

600

605

610

615

620

625

630

635

640

645

650

655

660

665

670

675

680

685

690

695

700

705

710

715

720

725

730

735

740

745

750

755

760

765

770

775

780

785

790

795

800

805

810

815

820

825

830

835

840

845

850

855

860

865

870

875

880

885

890

895

900

905

910

915

920

925

930

935

940

945

950

955

960

965

970

975

980

985

990

995

1000

1005

1010

1015

1020

1025

1030

1035

1040

1045

1050

1055

1060

1065

1070

1075

1080

1085

1090

1095

1100

1105

1110

1115

1120

1125

1130

1135

1140

1145

1150

1155

1160

1165

1170

1175

1180

1185

1190

1195

1200

1205

1210

1215

1220

1225

1230

1235

1240

1245

1250

1255

1260

1265

1270

1275

1280

1285

1290

1295

1300

1305

1310

1315

1320

1325

1330

1335

1340

1345

1350

1355

1360

1365

1370

1375

1380

1385

1390

1395

1400

1405

1410

1415

1420

1425

1430

1435

1440

1445

1450

1455

1460

1465

1470

1475

1480

1485

1490


1495

1500

1505

1510

# 5M BOPE & Closed Loop Equipment Schematic



Drawing not to scale

Note: All valves & lines on choke manifold are 4" unless otherwise noted. Exact manifold configuration may vary.



GATES E & S NORTH AMERICA, INC.  
 134 44TH STREET  
 CORPUS CHRISTI, TEXAS 78405

PHONE: 361-887-9807  
 FAX: 361-887-0812  
 EMAIL: [Tim.Cantu@gates.com](mailto:Tim.Cantu@gates.com)  
 WEB: [www.gates.com](http://www.gates.com)

**10K CEMENTING ASSEMBLY PRESSURE TEST CERTIFICATE**

Customer :	AUSTIN DISTRIBUTING	Test Date:	4/30/2015
Customer Ref. :	4060578	Hose Serial No.:	D-043015-7
Invoice No. :	500506	Created By:	JUSTIN CROPPER

Product Description:	10K3.548.0CK4.1/1610KFLGE/E LE		
End Fitting 1 :	4 1/16 10K FLG	End Fitting 2 :	4 1/16 10K FLG
Gates Part No. :	4773-6290	Assembly Code :	L36554102914D-043015-7
Working Pressure :	10,000 PSI	Test Pressure :	15,000 PSI


Gates E & S North America, Inc. certifies that the following hose assembly has been tested to the Gates Oilfield Roughneck Agreement/Specification requirements and passed the 15 minute hydrostatic test per API Spec 7K/Q1, Fifth Edition, June 2010, Test pressure 9.6.7 and per Table 9 to 15,000 psi in accordance with this product number. Hose burst pressure 9.6.7.2 exceeds the minimum of 2.5 times the working pressure per Table 9.

Quality Manager :	QUALITY
Date :	4/30/2015
Signature :	<i>Justin Cropper</i>

Production:	PRODUCTION
Date :	4/30/2015
Signature :	<i>[Signature]</i>

Form PTC - 01 Rev.02





GATES ENGINEERING & SERVICES NA  
CAIGCO  
MW  
APR 30 1975  
GENEVA, ILL.  
1000-1HR

CHART POOL USA, INC.  
PORTAGE, INDIANA

HOSE I.D. 3.6  
GRADE 10  
TEST PRESSURE 15000  
WORKING PRESSURE 10000  
ASSEMBLY DIA. 10000  
SERIAL 22550  
TEST DATE 4-30-75  
END 1 10/12  
END 2 16000  
END 3 18000


60 MIN



# CAMERON

A Schlumberger Company

## 13-5/8" MN-DS Wellhead System





C7585  
Rev. 02



NOTE: All dimensions on this drawing are estimated measurements and should be evaluated by engineering.

*Capping Hanger 57" conductor cut-off  
79*

Hydril "GK"  
13 5/8" 5M




Hydril "GK"




4 1/2" x 5 7/8" VBR

Cameron Type U  
13 5/8" 5M




BLIND RAMS




MUD CROSS



H.C.R.



7" RAMS





13 5/8" 5M

13 5/8" 5M

13 5/8" 5M

13 5/8" 5M






# CAMERON

A Schlumberger Company

## 13-5/8" MN-DS Wellhead System

Ground Level

Ground Level




*cupping flange 57" conductor cut-off*  
799

C7585  
Rev. 02

NOTE: All dimensions on this drawing are estimated measurements and should be evaluated by engineering.

Hydril "GK"  
13 5/8" 5M




Hydril "GK"


Cameron Type U  
13 5/8" 5M



4 1/2" x 5 7/8" VBR



BLIND RAMS




MUD CROSS


H.C.R.



7" RAMS





13 5/8" 5M



13 5/8" 5M



13 5/8" 5M






# CAMERON

A Schlumberger Company

## 13-5/8" MN-DS Wellhead System




C7585  
Rev. 02

NOTE: All dimensions on this drawing are estimated measurements and should be evaluated by engineering.




*Capping Storage 57" conductor cut-off*  
*79*

Hydril "GK"  
13 5/8" 5M




Hydril "GK"

Cameron Type U  
13 5/8" 5M




4 1/2" x 5 7/8" VBR

BLIND RAMS




MUD CROSS


H.C.R.



7" RAMS




13 5/8" 5M



13 5/8" 5M



13 5/8" 5M



Hydril "GK"  
13 5/8" 5M



Hydril "GK"




4 1/2" x 5 7/8" VBR

Cameron Type U  
13 5/8" 5M




BLIND RAMS




MUD CROSS


H.C.R.



7" RAMS




13 5/8" 5M



13 5/8" 5M

13 5/8" 5M






# CAMERON

A Schlumberger Company

## 13-5/8" MN-DS Wellhead System



**Mewbourne Oil Company, Oxbow 23/24 WOLI Fed Com #1H**  
**Sec 23 & 24, T25S, R28E**  
**SL: 867' FSL & 233' FWL (Sec 23)**  
**BHL: 1625' FSL & 330' FEL (Sec 24)**

**2. Casing Program**

Hole Size	Casing Interval		Csg. Size	Weight (lbs)	Grade	Conn.	SF Collapse	SF Burst	SF Jt Tension	SF Body Tension
	From	To								
17.5"	0'	500'	13.375"	48	H40	STC	3.37	7.56	13.42	22.54
12.25"	0'	2610'	9.625"	36	J55	LTC	1.49	2.59	4.82	6.00
8.75"	0'	9872'	7"	26	HCP110	LTC	1.65	2.10	2.70	3.23
6.125"	9131'	19460'	4.5"	13.5	P110	LTC	1.62	1.88	2.42	3.03
BLM Minimum Safety Factor							1.125	1	1.6 Dry 1.8 Wet	1.6 Dry 1.8 Wet

All casing strings will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.h

Must have table for contingency casing

	Y or N
Is casing new? If used, attach certification as required in Onshore Order #1	Y
Is casing API approved? If no, attach casing specification sheet.	Y
Is premium or uncommon casing planned? If yes attach casing specification sheet.	N
Does the above casing design meet or exceed BLM's minimum standards? If not provide justification (loading assumptions, casing design criteria).	Y
Will the pipe be kept at a minimum 1/3 fluid filled to avoid approaching the collapse pressure rating of the casing?	Y
Is well located within Capitan Reef?	N
If yes, does production casing cement tie back a minimum of 50' above the Reef?	
Is well within the designated 4 string boundary.	
Is well located in SOPA but not in R-111-P?	N
If yes, are the first 2 strings cemented to surface and 3 <sup>rd</sup> string cement tied back 500' into previous casing?	
Is well located in R-111-P and SOPA?	N
If yes, are the first three strings cemented to surface?	
Is 2 <sup>nd</sup> string set 100' to 600' below the base of salt?	
Is well located in high Cave/Karst?	N
If yes, are there two strings cemented to surface?	
(For 2 string wells) If yes, is there a contingency casing if lost circulation occurs?	
Is well located in critical Cave/Karst?	N
If yes, are there three strings cemented to surface?	

**Mewbourne Oil Company, Oxbow 23/24 WOLI Fed Com #1H**  
**Sec 23 & 24, T25S, R28E**  
**SL: 867' FSL & 233' FWL (Sec 23)**  
**BHL: 1625' FSL & 330' FEL (Sec 24)**

**2. Casing Program**

Hole Size	Casing Interval		Csg. Size	Weight (lbs)	Grade	Conn.	SF Collapse	SF Burst	SF Jt Tension	SF Body Tension
	From	To								
17.5"	0'	500'	13.375"	48	H40	STC	3.37	7.56	13.42	22.54
12.25"	0'	2610'	9.625"	36	J55	LTC	1.49	2.59	4.82	6.00
8.75"	0'	9872'	7"	26	HCP110	LTC	1.65	2.10	2.70	3.23
6.125"	9131'	19460'	4.5"	13.5	P110	LTC	1.62	1.88	2.42	3.03
BLM Minimum Safety Factor							1.125	1	1.6 Dry 1.8 Wet	1.6 Dry 1.8 Wet

All casing strings will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.h

Must have table for contingency casing

	Y or N
Is casing new? If used, attach certification as required in Onshore Order #1	Y
Is casing API approved? If no, attach casing specification sheet.	Y
Is premium or uncommon casing planned? If yes attach casing specification sheet.	N
Does the above casing design meet or exceed BLM's minimum standards? If not provide justification (loading assumptions, casing design criteria).	Y
Will the pipe be kept at a minimum 1/3 fluid filled to avoid approaching the collapse pressure rating of the casing?	Y
Is well located within Capitan Reef?	N
If yes, does production casing cement tie back a minimum of 50' above the Reef?	
Is well within the designated 4 string boundary.	
Is well located in SOPA but not in R-111-P?	N
If yes, are the first 2 strings cemented to surface and 3 <sup>rd</sup> string cement tied back 500' into previous casing?	
Is well located in R-111-P and SOPA?	N
If yes, are the first three strings cemented to surface?	
Is 2 <sup>nd</sup> string set 100' to 600' below the base of salt?	
Is well located in high Cave/Karst?	N
If yes, are there two strings cemented to surface?	
(For 2 string wells) If yes, is there a contingency casing if lost circulation occurs?	
Is well located in critical Cave/Karst?	N
If yes, are there three strings cemented to surface?	

**Mewbourne Oil Company, Oxbow 23/24 WOLI Fed Com #1H**  
**Sec 23 & 24, T25S, R28E**  
**SL: 867' FSL & 233' FWL (Sec 23)**  
**BHL: 1625' FSL & 330' FEL (Sec 24)**

**2. Casing Program**

Hole Size	Casing Interval		Csg. Size	Weight (lbs)	Grade	Conn.	SF Collapse	SF Burst	SF Jt Tension	SF Body Tension
	From	To								
17.5"	0'	500'	13.375"	48	H40	STC	3.37	7.56	13.42	22.54
12.25"	0'	2610'	9.625"	36	J55	LTC	1.49	2.59	4.82	6.00
8.75"	0'	9872'	7"	26	HCP110	LTC	1.65	2.10	2.70	3.23
6.125"	9131'	19460'	4.5"	13.5	P110	LTC	1.62	1.88	2.42	3.03
BLM Minimum Safety Factor							1.125	1	1.6 Dry 1.8 Wet	1.6 Dry 1.8 Wet

All casing strings will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.h

Must have table for contingency casing

	Y or N
Is casing new? If used, attach certification as required in Onshore Order #1	Y
Is casing API approved? If no, attach casing specification sheet.	Y
Is premium or uncommon casing planned? If yes attach casing specification sheet.	N
Does the above casing design meet or exceed BLM's minimum standards? If not provide justification (loading assumptions, casing design criteria).	Y
Will the pipe be kept at a minimum 1/3 fluid filled to avoid approaching the collapse pressure rating of the casing?	Y
Is well located within Capitan Reef?	N
If yes, does production casing cement tie back a minimum of 50' above the Reef?	
Is well within the designated 4 string boundary.	
Is well located in SOPA but not in R-111-P?	N
If yes, are the first 2 strings cemented to surface and 3 <sup>rd</sup> string cement tied back 500' into previous casing?	
Is well located in R-111-P and SOPA?	N
If yes, are the first three strings cemented to surface?	
Is 2 <sup>nd</sup> string set 100' to 600' below the base of salt?	
Is well located in high Cave/Karst?	N
If yes, are there two strings cemented to surface?	
(For 2 string wells) If yes, is there a contingency casing if lost circulation occurs?	
Is well located in critical Cave/Karst?	N
If yes, are there three strings cemented to surface?	

**Mewbourne Oil Company, Oxbow 23/24 WOLI Fed Com #1H**  
**Sec 23 & 24, T25S, R28E**  
**SL: 867' FSL & 233' FWL (Sec 23)**  
**BHL: 1625' FSL & 330' FEL (Sec 24)**

**2. Casing Program**

Hole Size	Casing Interval		Csg. Size	Weight (lbs)	Grade	Conn.	SF Collapse	SF Burst	SF Jt Tension	SF Body Tension
	From	To								
17.5"	0'	500'	13.375"	48	H40	STC	3.37	7.56	13.42	22.54
12.25"	0'	2610'	9.625"	36	J55	LTC	1.49	2.59	4.82	6.00
8.75"	0'	9872'	7"	26	HCP110	LTC	1.65	2.10	2.70	3.23
6.125"	9131'	19460'	4.5"	13.5	P110	LTC	1.62	1.88	2.42	3.03
BLM Minimum Safety Factor							1.125	1	1.6 Dry 1.8 Wet	1.6 Dry 1.8 Wet

All casing strings will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.h

Must have table for contingency casing

	Y or N
Is casing new? If used, attach certification as required in Onshore Order #1	Y
Is casing API approved? If no, attach casing specification sheet.	Y
Is premium or uncommon casing planned? If yes attach casing specification sheet.	N
Does the above casing design meet or exceed BLM's minimum standards? If not provide justification (loading assumptions, casing design criteria).	Y
Will the pipe be kept at a minimum 1/3 fluid filled to avoid approaching the collapse pressure rating of the casing?	Y
Is well located within Capitan Reef?	N
If yes, does production casing cement tie back a minimum of 50' above the Reef?	
Is well within the designated 4 string boundary.	
Is well located in SOPA but not in R-111-P?	N
If yes, are the first 2 strings cemented to surface and 3 <sup>rd</sup> string cement tied back 500' into previous casing?	
Is well located in R-111-P and SOPA?	N
If yes, are the first three strings cemented to surface?	
Is 2 <sup>nd</sup> string set 100' to 600' below the base of salt?	
Is well located in high Cave/Karst?	N
If yes, are there two strings cemented to surface?	
(For 2 string wells) If yes, is there a contingency casing if lost circulation occurs?	
Is well located in critical Cave/Karst?	N
If yes, are there three strings cemented to surface?	

Hydrogen Sulfide Drilling Operations Plan  
**Mewbourne Oil Company**

**1. General Requirements**

Rule 118 does not apply to this well because MOC has researched this area and no high concentrations of H<sub>2</sub>S were found. MOC will have on location and working all H<sub>2</sub>S safety equipment before the Delaware formation for purposes of safety and insurance requirements.

**2. Hydrogen Sulfide Training**

All personnel, whether regularly assigned, contracted, or employed on an unscheduled basis, will have received training from a qualified instructor in the following areas prior to entering the drilling pad area of the well:

1. The hazards and characteristics of hydrogen sulfide gas.
2. The proper use of personal protective equipment and life support systems.
3. The proper use of hydrogen sulfide detectors, alarms, warning systems, briefing areas, evacuation procedures.
4. The proper techniques for first aid and rescue operations.

Additionally, supervisory personnel will be trained in the following areas:

- 1 The effects of hydrogen sulfide on metal components. If high tensile tubular systems are utilized, supervisory personnel will be trained in their special maintenance requirements.
- 2 Corrective action and shut in procedures, blowout prevention, and well control procedures while drilling a well.
- 3 The contents of the Hydrogen Sulfide Drilling Operations Plan.

There will be an initial training session prior to encountering a known hydrogen sulfide source. The initial training session shall include a review of the site specific Hydrogen Sulfide Drilling Operations Plan.

**3. Hydrogen Sulfide Safety Equipment and Systems**

All hydrogen sulfide safety equipment and systems will be installed, tested, and operational prior to drilling below the 9 5/8" intermediate casing.

1. Well Control Equipment
  - A. Choke manifold with minimum of one adjustable choke/remote choke.
  - B. Blowout preventers equipped with blind rams and pipe rams to accommodate all pipe sizes with properly sized closing unit
  - C. Auxiliary equipment including annular type blowout preventer.
2. Protective Equipment for Essential Personnel

Thirty minute self contained work unit located in the dog house and at briefing areas.

Additionally: If H<sub>2</sub>S is encountered in concentrations less than 10 ppm, fans will be placed in work areas to prevent the accumulation of hazardous amounts of poisonous gas. If higher concentrations of H<sub>2</sub>S are detected the well will be shut in and a rotating head, mud/gas separator, remote choke and flare line with igniter will be installed.

3. Hydrogen Sulfide Protection and Monitoring Equipment  
Two portable hydrogen sulfide monitors positioned on location for optimum coverage and detection. The units shall have audible sirens to notify personnel when hydrogen sulfide levels exceed 20 PPM.
4. Visual Warning Systems
  - A. Wind direction indicators as indicated on the wellsite diagram.
  - B. Caution signs shall be posted on roads providing access to location. Signs shall be painted a high visibility color with lettering of sufficient size to be readable at reasonable distances from potentially contaminated areas.

**4. Mud Program**

The mud program has been designed to minimize the amount of hydrogen sulfide entrained in the mud system. Proper mud weight, safe drilling practices, and the use of hydrogen sulfide scavengers will minimize hazards while drilling the well.

**5. Metallurgy**

All tubular systems, wellheads, blowout preventers, drilling spools, kill lines, choke manifolds, and valves shall be suitable for service in a hydrogen sulfide environment when chemically treated.

**6. Communications**

State & County Officials phone numbers are posted on rig floor and supervisors trailer. Communications in company vehicles and toolpushers are either two way radios or cellular phones.

**7. Well Testing**

Drill stem testing is not an anticipated requirement for evaluation of this well. If a drill stem test is required, it will be conducted with a minimum number of personnel in the immediate vicinity. The test will be conducted during daylight hours only.

**8. Emergency Phone Numbers**

<b>Eddy County Sheriff's Office</b>	<b>911 or 575-887-7551</b>
<b>Ambulance Service</b>	<b>911 or 575-885-2111</b>
<b>Carlsbad Fire Dept</b>	<b>911 or 575-885-2111</b>
<b>Loco Hills Volunteer Fire Dept.</b>	<b>911 or 575-677-3266</b>
<b>Closest Medical Facility - Columbia Medical Center of Carlsbad</b>	<b>575-492-5000</b>

<b>Mewbourne Oil Company</b>	<b>Hobbs District Office</b>	<b>575-393-5905</b>
	<b>Fax</b>	<b>575-397-6252</b>
	<b>2<sup>nd</sup> Fax</b>	<b>575-393-7259</b>

<b>District Manager</b>	<b>Robin Terrell</b>	<b>575-390-4816</b>
<b>Drilling Superintendent</b>	<b>Frosty Lathan</b>	<b>575-390-4103</b>
	<b>Bradley Bishop</b>	<b>575-390-6838</b>
<b>Drilling Foreman</b>	<b>Wesley Noseff</b>	<b>575-441-0729</b>

# **Mewbourne Oil Company**

**Eddy County, New Mexico NAD 83**

**Oxbow 23/24 W0LI Fed Com #1H**

**SL: 867 FSL & 233 FWL (Sec 23)**

**Sec 23, T25S, R28E**

**BHL: 1625 FSL & 330 FEL (Sec 24)**

**Plan: Design #1**

## **Standard Planning Report**

**27 December, 2018**



Planning Report

<b>Database:</b>	Hobbs	<b>Local Co-ordinate Reference:</b>	Site Oxbow 23/24 WOLI Fed Com #1H
<b>Company:</b>	Mewbourne Oil Company	<b>TVD Reference:</b>	WELL @ 2959.0usft (Original Well Elev)
<b>Project:</b>	Eddy County, New Mexico NAD 83	<b>MD Reference:</b>	WELL @ 2959.0usft (Original Well Elev)
<b>Site:</b>	Oxbow 23/24 WOLI Fed Com #1H	<b>North Reference:</b>	Grid
<b>Well:</b>	SL: 867 FSL & 233 FWL (Sec 23)	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Wellbore:</b>	BHL: 1625 FSL & 330 FEL (Sec 24)		
<b>Design:</b>	Design #1		

<b>Project</b>	Eddy County, New Mexico NAD 83		
<b>Map System:</b>	US State Plane 1983	<b>System Datum:</b>	Mean Sea Level
<b>Geo Datum:</b>	North American Datum 1983		
<b>Map Zone:</b>	New Mexico Eastern Zone		

<b>Site</b>	Oxbow 23/24 WOLI Fed Com #1H				
<b>Site Position:</b>	<b>Northing:</b>	404,045.00 usft	<b>Latitude:</b>	32.1105163	
<b>From:</b> Map	<b>Easting:</b>	624,186.00 usft	<b>Longitude:</b>	-104.0657488	
<b>Position Uncertainty:</b>	0.0 usft	<b>Slot Radius:</b>	13-3/16 "	<b>Grid Convergence:</b>	0.14 °

<b>Well</b>	SL: 867 FSL & 233 FWL (Sec 23)					
<b>Well Position</b>	<b>+N-S</b>	0.0 usft	<b>Northing:</b>	404,045.00 usft	<b>Latitude:</b>	32.1105163
	<b>+E-W</b>	0.0 usft	<b>Easting:</b>	624,186.00 usft	<b>Longitude:</b>	-104.0657488
<b>Position Uncertainty</b>		0.0 usft	<b>Wellhead Elevation:</b>	2,959.0 usft	<b>Ground Level:</b>	2,932.0 usft

<b>Wellbore</b>	BHL: 1625 FSL & 330 FEL (Sec 24)				
<b>Magnetics</b>	<b>Model Name</b>	<b>Sample Date</b>	<b>Declination</b>	<b>Dip Angle</b>	<b>Field Strength</b>
			(°)	(°)	(nT)
	IGRF2010	12/27/2018	6.88	59.81	47,749

<b>Design</b>	Design #1			
<b>Audit Notes:</b>				
<b>Version:</b>	<b>Phase:</b>	PROTOTYPE	<b>Tie On Depth:</b>	0.0
<b>Vertical Section:</b>	<b>Depth From (TVD)</b>	<b>+N-S</b>	<b>+E-W</b>	<b>Direction</b>
	(usft)	(usft)	(usft)	(°)
	0.0	0.0	0.0	85.40

<b>Plan Sections</b>										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N-S (usft)	+E-W (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	TFO (°)	Target
0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.00	0.00	
500.0	0.00	0.00	500.0	0.0	0.0	0.00	0.00	0.00	0.00	
850.6	5.26	359.92	850.1	16.1	0.0	1.50	1.50	0.00	359.92	
8,780.8	5.26	359.92	8,746.9	742.9	-1.0	0.00	0.00	0.00	0.00	
9,131.4	0.00	0.00	9,097.0	759.0	-1.0	1.50	-1.50	0.00	180.00	KOP: 1625 FSL & 233
9,872.1	88.95	89.72	9,574.0	761.3	467.4	12.01	12.01	0.00	89.72	
19,460.4	88.95	89.72	9,749.0	809.0	10,054.0	0.00	0.00	0.00	0.00	BHL: 1625 FSL & 330

Planning Report

<b>Database:</b>	Hobbs	<b>Local Co-ordinate Reference:</b>	Site Oxbow 23/24 WOLI Fed Com #1H
<b>Company:</b>	Mewbourne Oil Company	<b>TVD Reference:</b>	WELL @ 2959.0usft (Original Well Elev)
<b>Project:</b>	Eddy County, New Mexico NAD 83	<b>MD Reference:</b>	WELL @ 2959.0usft (Original Well Elev)
<b>Site:</b>	Oxbow 23/24 WOLI Fed Com #1H	<b>North Reference:</b>	Grid
<b>Well:</b>	SL: 867 FSL & 233 FWL (Sec 23)	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Wellbore:</b>	BHL: 1625 FSL & 330 FEL (Sec 24)		
<b>Design:</b>	Design #1		

Planned Survey										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	
0.0	0.00	0.00	0.0	0.0	0.0	0.0	0.00	0.00	0.00	
<b>SL: 867 FSL &amp; 233 FWL (Sec 23)</b>										
100.0	0.00	0.00	100.0	0.0	0.0	0.0	0.00	0.00	0.00	
200.0	0.00	0.00	200.0	0.0	0.0	0.0	0.00	0.00	0.00	
300.0	0.00	0.00	300.0	0.0	0.0	0.0	0.00	0.00	0.00	
400.0	0.00	0.00	400.0	0.0	0.0	0.0	0.00	0.00	0.00	
500.0	0.00	0.00	500.0	0.0	0.0	0.0	0.00	0.00	0.00	
600.0	1.50	359.92	600.0	1.3	0.0	0.1	1.50	1.50	0.00	
700.0	3.00	359.92	699.9	5.2	0.0	0.4	1.50	1.50	0.00	
800.0	4.50	359.92	799.7	11.8	0.0	0.9	1.50	1.50	0.00	
850.6	5.26	359.92	850.1	16.1	0.0	1.3	1.50	1.50	0.00	
900.0	5.26	359.92	899.3	20.6	0.0	1.6	0.00	0.00	0.00	
1,000.0	5.26	359.92	998.9	29.8	0.0	2.3	0.00	0.00	0.00	
1,100.0	5.26	359.92	1,098.5	38.9	-0.1	3.1	0.00	0.00	0.00	
1,200.0	5.26	359.92	1,198.0	48.1	-0.1	3.8	0.00	0.00	0.00	
1,300.0	5.26	359.92	1,297.6	57.3	-0.1	4.5	0.00	0.00	0.00	
1,400.0	5.26	359.92	1,397.2	66.4	-0.1	5.2	0.00	0.00	0.00	
1,500.0	5.26	359.92	1,496.8	75.6	-0.1	6.0	0.00	0.00	0.00	
1,600.0	5.26	359.92	1,596.4	84.8	-0.1	6.7	0.00	0.00	0.00	
1,700.0	5.26	359.92	1,695.9	93.9	-0.1	7.4	0.00	0.00	0.00	
1,800.0	5.26	359.92	1,795.5	103.1	-0.1	8.1	0.00	0.00	0.00	
1,900.0	5.26	359.92	1,895.1	112.3	-0.1	8.9	0.00	0.00	0.00	
2,000.0	5.26	359.92	1,994.7	121.4	-0.2	9.6	0.00	0.00	0.00	
2,100.0	5.26	359.92	2,094.2	130.6	-0.2	10.3	0.00	0.00	0.00	
2,200.0	5.26	359.92	2,193.8	139.8	-0.2	11.0	0.00	0.00	0.00	
2,300.0	5.26	359.92	2,293.4	148.9	-0.2	11.7	0.00	0.00	0.00	
2,400.0	5.26	359.92	2,393.0	158.1	-0.2	12.5	0.00	0.00	0.00	
2,500.0	5.26	359.92	2,492.6	167.3	-0.2	13.2	0.00	0.00	0.00	
2,600.0	5.26	359.92	2,592.1	176.4	-0.2	13.9	0.00	0.00	0.00	
2,700.0	5.26	359.92	2,691.7	185.6	-0.2	14.6	0.00	0.00	0.00	
2,800.0	5.26	359.92	2,791.3	194.8	-0.3	15.4	0.00	0.00	0.00	
2,900.0	5.26	359.92	2,890.9	203.9	-0.3	16.1	0.00	0.00	0.00	
3,000.0	5.26	359.92	2,990.5	213.1	-0.3	16.8	0.00	0.00	0.00	
3,100.0	5.26	359.92	3,090.0	222.2	-0.3	17.5	0.00	0.00	0.00	
3,200.0	5.26	359.92	3,189.6	231.4	-0.3	18.3	0.00	0.00	0.00	
3,300.0	5.26	359.92	3,289.2	240.6	-0.3	19.0	0.00	0.00	0.00	
3,400.0	5.26	359.92	3,388.8	249.7	-0.3	19.7	0.00	0.00	0.00	
3,500.0	5.26	359.92	3,488.4	258.9	-0.3	20.4	0.00	0.00	0.00	
3,600.0	5.26	359.92	3,587.9	268.1	-0.4	21.1	0.00	0.00	0.00	
3,700.0	5.26	359.92	3,687.5	277.2	-0.4	21.9	0.00	0.00	0.00	
3,800.0	5.26	359.92	3,787.1	286.4	-0.4	22.6	0.00	0.00	0.00	
3,900.0	5.26	359.92	3,886.7	295.6	-0.4	23.3	0.00	0.00	0.00	
4,000.0	5.26	359.92	3,986.3	304.7	-0.4	24.0	0.00	0.00	0.00	
4,100.0	5.26	359.92	4,085.8	313.9	-0.4	24.8	0.00	0.00	0.00	
4,200.0	5.26	359.92	4,185.4	323.1	-0.4	25.5	0.00	0.00	0.00	
4,300.0	5.26	359.92	4,285.0	332.2	-0.4	26.2	0.00	0.00	0.00	
4,400.0	5.26	359.92	4,384.6	341.4	-0.4	26.9	0.00	0.00	0.00	
4,500.0	5.26	359.92	4,484.1	350.6	-0.5	27.7	0.00	0.00	0.00	
4,600.0	5.26	359.92	4,583.7	359.7	-0.5	28.4	0.00	0.00	0.00	
4,700.0	5.26	359.92	4,683.3	368.9	-0.5	29.1	0.00	0.00	0.00	
4,800.0	5.26	359.92	4,782.9	378.1	-0.5	29.8	0.00	0.00	0.00	
4,900.0	5.26	359.92	4,882.5	387.2	-0.5	30.5	0.00	0.00	0.00	
5,000.0	5.26	359.92	4,982.0	396.4	-0.5	31.3	0.00	0.00	0.00	
5,100.0	5.26	359.92	5,081.6	405.6	-0.5	32.0	0.00	0.00	0.00	

Planning Report

<b>Database:</b>	Hobbs	<b>Local Co-ordinate Reference:</b>	Site Oxbow 23/24 WOLI Fed Com #1H
<b>Company:</b>	Mewbourne Oil Company	<b>TVD Reference:</b>	WELL @ 2959.0usft (Original Well Elev)
<b>Project:</b>	Eddy County, New Mexico NAD 83	<b>MD Reference:</b>	WELL @ 2959.0usft (Original Well Elev)
<b>Site:</b>	Oxbow 23/24 WOLI Fed Com #1H	<b>North Reference:</b>	Grid
<b>Well:</b>	SL: 867 FSL & 233 FWL (Sec 23)	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Wellbore:</b>	BHL: 1625 FSL & 330 FEL (Sec 24)		
<b>Design:</b>	Design #1		

Planned Survey										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	
5,200.0	5.26	359.92	5,181.2	414.7	-0.5	32.7	0.00	0.00	0.00	
5,300.0	5.26	359.92	5,280.8	423.9	-0.6	33.4	0.00	0.00	0.00	
5,400.0	5.26	359.92	5,380.4	433.1	-0.6	34.2	0.00	0.00	0.00	
5,500.0	5.26	359.92	5,479.9	442.2	-0.6	34.9	0.00	0.00	0.00	
5,600.0	5.26	359.92	5,579.5	451.4	-0.6	35.6	0.00	0.00	0.00	
5,700.0	5.26	359.92	5,679.1	460.6	-0.6	36.3	0.00	0.00	0.00	
5,800.0	5.26	359.92	5,778.7	469.7	-0.6	37.1	0.00	0.00	0.00	
5,900.0	5.26	359.92	5,878.3	478.9	-0.6	37.8	0.00	0.00	0.00	
6,000.0	5.26	359.92	5,977.8	488.0	-0.6	38.5	0.00	0.00	0.00	
6,100.0	5.26	359.92	6,077.4	497.2	-0.7	39.2	0.00	0.00	0.00	
6,200.0	5.26	359.92	6,177.0	506.4	-0.7	39.9	0.00	0.00	0.00	
6,300.0	5.26	359.92	6,276.6	515.5	-0.7	40.7	0.00	0.00	0.00	
6,400.0	5.26	359.92	6,376.1	524.7	-0.7	41.4	0.00	0.00	0.00	
6,500.0	5.26	359.92	6,475.7	533.9	-0.7	42.1	0.00	0.00	0.00	
6,600.0	5.26	359.92	6,575.3	543.0	-0.7	42.8	0.00	0.00	0.00	
6,700.0	5.26	359.92	6,674.9	552.2	-0.7	43.6	0.00	0.00	0.00	
6,800.0	5.26	359.92	6,774.5	561.4	-0.7	44.3	0.00	0.00	0.00	
6,900.0	5.26	359.92	6,874.0	570.5	-0.8	45.0	0.00	0.00	0.00	
7,000.0	5.26	359.92	6,973.6	579.7	-0.8	45.7	0.00	0.00	0.00	
7,100.0	5.26	359.92	7,073.2	588.9	-0.8	46.5	0.00	0.00	0.00	
7,200.0	5.26	359.92	7,172.8	598.0	-0.8	47.2	0.00	0.00	0.00	
7,300.0	5.26	359.92	7,272.4	607.2	-0.8	47.9	0.00	0.00	0.00	
7,400.0	5.26	359.92	7,371.9	616.4	-0.8	48.6	0.00	0.00	0.00	
7,500.0	5.26	359.92	7,471.5	625.5	-0.8	49.4	0.00	0.00	0.00	
7,600.0	5.26	359.92	7,571.1	634.7	-0.8	50.1	0.00	0.00	0.00	
7,700.0	5.26	359.92	7,670.7	643.9	-0.8	50.8	0.00	0.00	0.00	
7,800.0	5.26	359.92	7,770.3	653.0	-0.9	51.5	0.00	0.00	0.00	
7,900.0	5.26	359.92	7,869.8	662.2	-0.9	52.2	0.00	0.00	0.00	
8,000.0	5.26	359.92	7,969.4	671.4	-0.9	53.0	0.00	0.00	0.00	
8,100.0	5.26	359.92	8,069.0	680.5	-0.9	53.7	0.00	0.00	0.00	
8,200.0	5.26	359.92	8,168.6	689.7	-0.9	54.4	0.00	0.00	0.00	
8,300.0	5.26	359.92	8,268.2	698.9	-0.9	55.1	0.00	0.00	0.00	
8,400.0	5.26	359.92	8,367.7	708.0	-0.9	55.9	0.00	0.00	0.00	
8,500.0	5.26	359.92	8,467.3	717.2	-0.9	56.6	0.00	0.00	0.00	
8,600.0	5.26	359.92	8,566.9	726.4	-1.0	57.3	0.00	0.00	0.00	
8,700.0	5.26	359.92	8,666.5	735.5	-1.0	58.0	0.00	0.00	0.00	
8,780.8	5.26	359.92	8,746.9	742.9	-1.0	58.6	0.00	0.00	0.00	
8,800.0	4.97	359.92	8,766.1	744.6	-1.0	58.7	1.50	-1.50	0.00	
8,900.0	3.47	359.92	8,865.8	752.0	-1.0	59.3	1.50	-1.50	0.00	
9,000.0	1.97	359.92	8,965.7	756.7	-1.0	59.7	1.50	-1.50	0.00	
9,100.0	0.47	359.92	9,065.6	758.9	-1.0	59.9	1.50	-1.50	0.00	
9,131.4	0.00	0.00	9,097.0	759.0	-1.0	59.9	1.50	-1.50	0.00	
<b>KOP: 1625 FSL &amp; 233 FWL (Sec 23)</b>										
9,200.0	8.24	89.72	9,165.4	759.0	3.9	64.8	12.01	12.01	0.00	
9,300.0	20.25	89.72	9,262.1	759.1	28.5	89.3	12.01	12.01	0.00	
9,400.0	32.26	89.72	9,351.7	759.4	72.7	133.3	12.01	12.01	0.00	
9,441.0	37.18	89.72	9,385.3	759.5	96.0	156.6	12.01	12.01	0.00	
<b>FTP: 1625 FSL &amp; 330 FWL (Sec 23)</b>										
9,500.0	44.27	89.72	9,430.0	759.7	134.5	195.0	12.01	12.01	0.00	
9,600.0	56.28	89.72	9,493.8	760.1	211.2	271.5	12.01	12.01	0.00	
9,700.0	68.29	89.72	9,540.2	760.5	299.6	359.6	12.01	12.01	0.00	
9,800.0	80.30	89.72	9,567.3	761.0	395.7	455.5	12.01	12.01	0.00	
9,872.1	88.95	89.72	9,574.0	761.3	467.4	526.9	12.01	12.01	0.00	
9,900.0	88.95	89.72	9,574.5	761.5	495.3	554.8	0.00	0.00	0.00	

Planning Report

<b>Database:</b>	Hobbs	<b>Local Co-ordinate Reference:</b>	Site Oxbow 23/24 WOLI Fed Com #1H
<b>Company:</b>	Mewbourne Oil Company	<b>TVD Reference:</b>	WELL @ 2959.0usft (Original Well Elev)
<b>Project:</b>	Eddy County, New Mexico NAD 83	<b>MD Reference:</b>	WELL @ 2959.0usft (Original Well Elev)
<b>Site:</b>	Oxbow 23/24 WOLI Fed Com #1H	<b>North Reference:</b>	Grid
<b>Well:</b>	SL: 867 FSL & 233 FWL (Sec 23)	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Wellbore:</b>	BHL: 1625 FSL & 330 FEL (Sec 24)		
<b>Design:</b>	Design #1		

Planned Survey										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	
10,000.0	88.95	89.72	9,576.3	762.0	595.3	654.5	0.00	0.00	0.00	
10,100.0	88.95	89.72	9,578.2	762.5	695.3	754.2	0.00	0.00	0.00	
10,200.0	88.95	89.72	9,580.0	763.0	795.3	853.9	0.00	0.00	0.00	
10,300.0	88.95	89.72	9,581.8	763.5	895.2	953.6	0.00	0.00	0.00	
10,400.0	88.95	89.72	9,583.6	764.0	995.2	1,053.3	0.00	0.00	0.00	
10,500.0	88.95	89.72	9,585.5	764.5	1,095.2	1,153.0	0.00	0.00	0.00	
10,600.0	88.95	89.72	9,587.3	764.9	1,195.2	1,252.7	0.00	0.00	0.00	
10,700.0	88.95	89.72	9,589.1	765.4	1,295.2	1,352.4	0.00	0.00	0.00	
10,800.0	88.95	89.72	9,590.9	765.9	1,395.1	1,452.1	0.00	0.00	0.00	
10,900.0	88.95	89.72	9,592.8	766.4	1,495.1	1,551.8	0.00	0.00	0.00	
11,000.0	88.95	89.72	9,594.6	766.9	1,595.1	1,651.5	0.00	0.00	0.00	
11,100.0	88.95	89.72	9,596.4	767.4	1,695.1	1,751.2	0.00	0.00	0.00	
11,200.0	88.95	89.72	9,598.2	767.9	1,795.1	1,850.9	0.00	0.00	0.00	
11,300.0	88.95	89.72	9,600.1	768.4	1,895.1	1,950.6	0.00	0.00	0.00	
11,400.0	88.95	89.72	9,601.9	768.9	1,995.0	2,050.3	0.00	0.00	0.00	
11,500.0	88.95	89.72	9,603.7	769.4	2,095.0	2,150.0	0.00	0.00	0.00	
11,600.0	88.95	89.72	9,605.5	769.9	2,195.0	2,249.7	0.00	0.00	0.00	
11,700.0	88.95	89.72	9,607.4	770.4	2,295.0	2,349.4	0.00	0.00	0.00	
11,800.0	88.95	89.72	9,609.2	770.9	2,395.0	2,449.1	0.00	0.00	0.00	
11,900.0	88.95	89.72	9,611.0	771.4	2,495.0	2,548.8	0.00	0.00	0.00	
12,000.0	88.95	89.72	9,612.8	771.9	2,594.9	2,648.5	0.00	0.00	0.00	
12,100.0	88.95	89.72	9,614.7	772.4	2,694.9	2,748.2	0.00	0.00	0.00	
12,200.0	88.95	89.72	9,616.5	772.9	2,794.9	2,847.9	0.00	0.00	0.00	
12,300.0	88.95	89.72	9,618.3	773.4	2,894.9	2,947.6	0.00	0.00	0.00	
12,400.0	88.95	89.72	9,620.1	773.9	2,994.9	3,047.3	0.00	0.00	0.00	
12,500.0	88.95	89.72	9,622.0	774.4	3,094.8	3,147.0	0.00	0.00	0.00	
12,600.0	88.95	89.72	9,623.8	774.9	3,194.8	3,246.7	0.00	0.00	0.00	
12,700.0	88.95	89.72	9,625.6	775.4	3,294.8	3,346.4	0.00	0.00	0.00	
12,800.0	88.95	89.72	9,627.4	775.9	3,394.8	3,446.1	0.00	0.00	0.00	
12,900.0	88.95	89.72	9,629.3	776.4	3,494.8	3,545.8	0.00	0.00	0.00	
13,000.0	88.95	89.72	9,631.1	776.9	3,594.8	3,645.5	0.00	0.00	0.00	
13,100.0	88.95	89.72	9,632.9	777.4	3,694.7	3,745.2	0.00	0.00	0.00	
13,200.0	88.95	89.72	9,634.7	777.9	3,794.7	3,844.9	0.00	0.00	0.00	
13,300.0	88.95	89.72	9,636.6	778.4	3,894.7	3,944.6	0.00	0.00	0.00	
13,400.0	88.95	89.72	9,638.4	778.9	3,994.7	4,044.3	0.00	0.00	0.00	
13,500.0	88.95	89.72	9,640.2	779.4	4,094.7	4,144.0	0.00	0.00	0.00	
13,600.0	88.95	89.72	9,642.0	779.9	4,194.6	4,243.7	0.00	0.00	0.00	
13,700.0	88.95	89.72	9,643.9	780.4	4,294.6	4,343.4	0.00	0.00	0.00	
13,800.0	88.95	89.72	9,645.7	780.9	4,394.6	4,443.1	0.00	0.00	0.00	
13,900.0	88.95	89.72	9,647.5	781.4	4,494.6	4,542.8	0.00	0.00	0.00	
14,000.0	88.95	89.72	9,649.3	781.9	4,594.6	4,642.5	0.00	0.00	0.00	
14,100.0	88.95	89.72	9,651.2	782.3	4,694.6	4,742.2	0.00	0.00	0.00	
14,200.0	88.95	89.72	9,653.0	782.8	4,794.5	4,841.9	0.00	0.00	0.00	
14,300.0	88.95	89.72	9,654.8	783.3	4,894.5	4,941.6	0.00	0.00	0.00	
14,400.0	88.95	89.72	9,656.6	783.8	4,994.5	5,041.3	0.00	0.00	0.00	
14,500.0	88.95	89.72	9,658.5	784.3	5,094.5	5,141.0	0.00	0.00	0.00	
14,600.0	88.95	89.72	9,660.3	784.8	5,194.5	5,240.7	0.00	0.00	0.00	
14,700.0	88.95	89.72	9,662.1	785.3	5,294.5	5,340.4	0.00	0.00	0.00	
14,800.0	88.95	89.72	9,663.9	785.8	5,394.4	5,440.1	0.00	0.00	0.00	
14,900.0	88.95	89.72	9,665.8	786.3	5,494.4	5,539.8	0.00	0.00	0.00	
15,000.0	88.95	89.72	9,667.6	786.8	5,594.4	5,639.5	0.00	0.00	0.00	
15,100.0	88.95	89.72	9,669.4	787.3	5,694.4	5,739.2	0.00	0.00	0.00	
15,200.0	88.95	89.72	9,671.2	787.8	5,794.4	5,838.9	0.00	0.00	0.00	
15,300.0	88.95	89.72	9,673.1	788.3	5,894.3	5,938.6	0.00	0.00	0.00	

Planning Report

<b>Database:</b>	Hobbs	<b>Local Co-ordinate Reference:</b>	Site Oxbow 23/24 WOLI Fed Com #1H
<b>Company:</b>	Mewbourne Oil Company	<b>TVD Reference:</b>	WELL @ 2959.0usft (Original Well Elev)
<b>Project:</b>	Eddy County, New Mexico NAD 83	<b>MD Reference:</b>	WELL @ 2959.0usft (Original Well Elev)
<b>Site:</b>	Oxbow 23/24 WOLI Fed Com #1H	<b>North Reference:</b>	Grid
<b>Well:</b>	SL: 867 FSL & 233 FWL (Sec 23)	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Wellbore:</b>	BHL: 1625 FSL & 330 FEL (Sec 24)		
<b>Design:</b>	Design #1		

Planned Survey



Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
15,400.0	88.95	89.72	9,674.9	788.8	5,994.3	6,038.3	0.00	0.00	0.00
15,500.0	88.95	89.72	9,676.7	789.3	6,094.3	6,138.0	0.00	0.00	0.00
15,600.0	88.95	89.72	9,678.5	789.8	6,194.3	6,237.7	0.00	0.00	0.00
15,700.0	88.95	89.72	9,680.4	790.3	6,294.3	6,337.4	0.00	0.00	0.00
15,800.0	88.95	89.72	9,682.2	790.8	6,394.3	6,437.1	0.00	0.00	0.00
15,823.7	88.95	89.72	9,682.6	790.9	6,418.0	6,460.8	0.00	0.00	0.00
<b>PPP2: 1625 FSL &amp; 1327 FWL (Sec 24)</b>									
15,900.0	88.95	89.72	9,684.0	791.3	6,494.2	6,536.8	0.00	0.00	0.00
16,000.0	88.95	89.72	9,685.8	791.8	6,594.2	6,636.5	0.00	0.00	0.00
16,100.0	88.95	89.72	9,687.7	792.3	6,694.2	6,736.2	0.00	0.00	0.00
16,200.0	88.95	89.72	9,689.5	792.8	6,794.2	6,835.9	0.00	0.00	0.00
16,300.0	88.95	89.72	9,691.3	793.3	6,894.2	6,935.6	0.00	0.00	0.00
16,400.0	88.95	89.72	9,693.1	793.8	6,994.1	7,035.3	0.00	0.00	0.00
16,500.0	88.95	89.72	9,695.0	794.3	7,094.1	7,135.0	0.00	0.00	0.00
16,600.0	88.95	89.72	9,696.8	794.8	7,194.1	7,234.7	0.00	0.00	0.00
16,700.0	88.95	89.72	9,698.6	795.3	7,294.1	7,334.4	0.00	0.00	0.00
16,800.0	88.95	89.72	9,700.4	795.8	7,394.1	7,434.1	0.00	0.00	0.00
16,900.0	88.95	89.72	9,702.3	796.3	7,494.1	7,533.8	0.00	0.00	0.00
17,000.0	88.95	89.72	9,704.1	796.8	7,594.0	7,633.5	0.00	0.00	0.00
17,100.0	88.95	89.72	9,705.9	797.3	7,694.0	7,733.2	0.00	0.00	0.00
17,200.0	88.95	89.72	9,707.7	797.8	7,794.0	7,832.9	0.00	0.00	0.00
17,300.0	88.95	89.72	9,709.6	798.3	7,894.0	7,932.6	0.00	0.00	0.00
17,400.0	88.95	89.72	9,711.4	798.8	7,994.0	8,032.3	0.00	0.00	0.00
17,500.0	88.95	89.72	9,713.2	799.3	8,094.0	8,132.0	0.00	0.00	0.00
17,600.0	88.95	89.72	9,715.0	799.8	8,193.9	8,231.7	0.00	0.00	0.00
17,700.0	88.95	89.72	9,716.9	800.2	8,293.9	8,331.4	0.00	0.00	0.00
17,800.0	88.95	89.72	9,718.7	800.7	8,393.9	8,431.1	0.00	0.00	0.00
17,900.0	88.95	89.72	9,720.5	801.2	8,493.9	8,530.8	0.00	0.00	0.00
18,000.0	88.95	89.72	9,722.3	801.7	8,593.9	8,630.5	0.00	0.00	0.00
18,100.0	88.95	89.72	9,724.2	802.2	8,693.8	8,730.2	0.00	0.00	0.00
18,200.0	88.95	89.72	9,726.0	802.7	8,793.8	8,829.9	0.00	0.00	0.00
18,300.0	88.95	89.72	9,727.8	803.2	8,893.8	8,929.6	0.00	0.00	0.00
18,400.0	88.95	89.72	9,729.6	803.7	8,993.8	9,029.3	0.00	0.00	0.00
18,463.2	88.95	89.72	9,730.8	804.0	9,057.0	9,092.3	0.00	0.00	0.00
<b>PPP3: 1625 FSL &amp; 1327 FEL (Sec 24)</b>									
18,500.0	88.95	89.72	9,731.5	804.2	9,093.8	9,129.0	0.00	0.00	0.00
18,600.0	88.95	89.72	9,733.3	804.7	9,193.8	9,228.7	0.00	0.00	0.00
18,700.0	88.95	89.72	9,735.1	805.2	9,293.7	9,328.4	0.00	0.00	0.00
18,800.0	88.95	89.72	9,736.9	805.7	9,393.7	9,428.1	0.00	0.00	0.00
18,900.0	88.95	89.72	9,738.8	806.2	9,493.7	9,527.8	0.00	0.00	0.00
19,000.0	88.95	89.72	9,740.6	806.7	9,593.7	9,627.5	0.00	0.00	0.00
19,100.0	88.95	89.72	9,742.4	807.2	9,693.7	9,727.2	0.00	0.00	0.00
19,200.0	88.95	89.72	9,744.2	807.7	9,793.6	9,826.9	0.00	0.00	0.00
19,300.0	88.95	89.72	9,746.1	808.2	9,893.6	9,926.6	0.00	0.00	0.00
19,400.0	88.95	89.72	9,747.9	808.7	9,993.6	10,026.3	0.00	0.00	0.00
19,460.4	88.95	89.72	9,749.0	809.0	10,054.0	10,086.5	0.00	0.00	0.00
<b>BHL: 1625 FSL &amp; 330 FEL (Sec 24)</b>									

## Planning Report

<b>Database:</b>	Hobbs	<b>Local Co-ordinate Reference:</b>	Site Oxbow 23/24 WOLI Fed Com #1H
<b>Company:</b>	Mewbourne Oil Company	<b>TVD Reference:</b>	WELL @ 2959.0usft (Original Well Elev)
<b>Project:</b>	Eddy County, New Mexico NAD 83	<b>MD Reference:</b>	WELL @ 2959.0usft (Original Well Elev)
<b>Site:</b>	Oxbow 23/24 WOLI Fed Com #1H	<b>North Reference:</b>	Grid
<b>Well:</b>	SL: 867 FSL & 233 FWL (Sec 23)	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Wellbore:</b>	BHL: 1625 FSL & 330 FEL (Sec 24)		
<b>Design:</b>	Design #1		

Design Targets										
Target Name	Dip Angle	Dip Dir.	TVD	+N/-S	+E/-W	Northing	Easting	Latitude	Longitude	
- hit/miss target - Shape	(°)	(°)	(usft)	(usft)	(usft)	(usft)	(usft)			
SL: 867 FSL & 233 FWL - plan hits target center - Point	0.00	0.00	0.0	0.0	0.0	404,045.00	624,186.00	32.1105163	-104.0657488	
KOP: 1625 FSL & 233 F - plan hits target center - Point	0.00	0.00	9,097.0	759.0	-1.0	404,804.00	624,185.00	32.1126027	-104.0657459	
FTP: 1625 FSL & 330 F - plan hits target center - Point	0.00	0.00	9,385.3	759.5	96.0	404,804.48	624,282.00	32.1126034	-104.0654326	
PPP2: 1625 FSL & 1327 - plan hits target center - Point	0.00	0.00	9,682.6	790.9	6,418.0	404,835.92	630,604.00	32.1126450	-104.0450133	
PPP3: 1625 FSL & 1327 - plan hits target center - Point	0.00	0.00	9,730.8	804.0	9,057.0	404,849.04	633,243.00	32.1126613	-104.0364896	
BHL: 1625 FSL & 330 F - plan hits target center - Point	0.00	0.00	9,749.0	809.0	10,054.0	404,854.00	634,240.00	32.1126674	-104.0332694	

# Oxbow 23/24 WOLI Fed Com #1H



**Mewbourne Oil Company, Oxbow 23/24 WOLI Fed Com #1H**  
**Sec 23 & 24, T25S, R28E**  
**SL: 867' FSL & 233' FWL (Sec 23)**  
**BHL: 1625' FSL & 330' FEL (Sec 24)**

**2. Casing Program**

Hole Size	Casing Interval		Csg. Size	Weight (lbs)	Grade	Conn.	SF Collapse	SF Burst	SF Jt Tension	SF Body Tension
	From	To								
17.5"	0'	500'	13.375"	48	H40	STC	3.37	7.56	13.42	22.54
12.25"	0'	2610'	9.625"	36	J55	LTC	1.49	2.59	4.82	6.00
8.75"	0'	9872'	7"	26	HCP110	LTC	1.65	2.10	2.70	3.23
6.125"	9131'	19460'	4.5"	13.5	P110	LTC	1.62	1.88	2.42	3.03
BLM Minimum Safety Factor							1.125	1	1.6 Dry 1.8 Wet	1.6 Dry 1.8 Wet

All casing strings will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.h

Must have table for contingency casing

	Y or N
Is casing new? If used, attach certification as required in Onshore Order #1	Y
Is casing API approved? If no, attach casing specification sheet.	Y
Is premium or uncommon casing planned? If yes attach casing specification sheet.	N
Does the above casing design meet or exceed BLM's minimum standards? If not provide justification (loading assumptions, casing design criteria).	Y
Will the pipe be kept at a minimum 1/3 fluid filled to avoid approaching the collapse pressure rating of the casing?	Y
Is well located within Capitan Reef?	Y
If yes, does production casing cement tie back a minimum of 50' above the Reef?	
Is well within the designated 4 string boundary.	
Is well located in SOPA but not in R-111-P?	N
If yes, are the first 2 strings cemented to surface and 3 <sup>rd</sup> string cement tied back 500' into previous casing?	
Is well located in R-111-P and SOPA?	N
If yes, are the first three strings cemented to surface?	
Is 2 <sup>nd</sup> string set 100' to 600' below the base of salt?	
Is well located in high Cave/Karst?	N
If yes, are there two strings cemented to surface?	
(For 2 string wells) If yes, is there a contingency casing if lost circulation occurs?	
Is well located in critical Cave/Karst?	N
If yes, are there three strings cemented to surface?	

**Mewbourne Oil Company, Oxbow 23/24 WOLI Fed Com #1H**  
**Sec 23 & 24, T25S, R28E**  
**SL: 867' FSL & 233' FWL (Sec 23)**  
**BHL: 1625' FSL & 330' FEL (Sec 24)**

**3. Cementing Program**

Casing	# Sks	Wt. lb/gal	Yld ft <sup>3</sup> /sack	H <sub>2</sub> O gal/sk	500# Comp. Strength (hours)	Slurry Description
Surf.	205	12.5	2.12	11	10	Lead: Class C + Salt + Gel + Extender + LCM
	200	14.8	1.34	6.3	8	Tail: Class C + Retarder
Inter.	380	12.5	2.12	11	10	Lead: Class C + Salt + Gel + Extender + LCM
	200	14.8	1.34	6.3	8	Tail: Class C + Retarder
Prod. Stg 1	345	12.5	2.12	11	9	Lead: Class C + Gel + Retarder + Defoamer + Extender
	400	15.6	1.18	5.2	10	Tail: Class H + Retarder + Fluid Loss + Defoamer
ECP/DV Tool @ 3710'						
Prod. Stg 2	290	12.5	2.12	11	10	Lead: Class C + Salt + Gel + Extender + LCM
	100	14.8	1.34	6.3	8	Tail: Class C + Retarder
Liner	415	11.2	2.97	18	16	Class C + Salt + Gel + Fluid Loss + Retarder + Dispersant + Defoamer + Anti-Settling Agent

A copy of cement test will be available on location at time of cement job providing pump times & compressive strengths.

Casing String	TOC	% Excess
Surface	0'	100%
Intermediate	0'	25%
Production	2410'	25%
Liner	9131'	25%

**Mewbourne Oil Company, Oxbow 23/24 W0LI Fed Com #1H**  
**Sec 23 & 24, T25S, R28E**  
**SL: 867' FSL & 233' FWL (Sec 23)**  
**BHL: 1625' FSL & 330' FEL (Sec 24)**

**4. Pressure Control Equipment**

Y	Variance: A variance is requested for use of a 5000 psi annular BOP with the 10,000 psi BOP stack. Please see attached description and procedure.
---	---

BOP installed and tested before drilling which hole?	Size?	System Rated WP	Type	✓	Tested to:
12-1/4"	13-5/8"	10M	Annular	X	5,000#
			Blind Ram	X	10,000#
			Pipe Ram	X	
			Double Ram		
			Other*		

\*Specify if additional ram is utilized.

BOP/BOPE will be tested by an independent service company to 250 psi low and the high pressure indicated above per Onshore Order 2 requirements. The System may be upgraded to a higher pressure but still tested to the working pressure listed in the table above. If the system is upgraded all the components installed will be functional and tested.

Pipe rams will be operationally checked each 24 hour period. Blind rams will be operationally checked on each trip out of the hole. These checks will be noted on the daily tour sheets. Other accessories to the BOP equipment will include a Kelly cock and floor safety valve (inside BOP) and choke lines and choke manifold. See attached schematics.

X	Formation integrity test will be performed per Onshore Order #2. On Exploratory wells or on that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.i.
Y	A variance is requested for the use of a flexible choke line from the BOP to Choke Manifold. See attached for specs and hydrostatic test chart.
N	Are anchors required by manufacturer?
Y	A multibowl wellhead is being used. The BOP will be tested per Onshore Order #2 after installation on the surface casing which will cover testing requirements for a maximum of 30 days. If any seal subject to test pressure is broken the system must be tested. <ul style="list-style-type: none"> <li>• Provide description here: See attached schematic.</li> </ul>

**Mewbourne Oil Company, Oxbow 23/24 WOLI Fed Com #1H**  
**Sec 23 & 24, T25S, R28E**  
**SL: 867' FSL & 233' FWL (Sec 23)**  
**BHL: 1625' FSL & 330' FEL (Sec 24)**

**5. Mud Program**

TVD		Type	Weight (ppg)	Viscosity	Water Loss
From	To				
0	500	FW Gel	8.6-8.8	28-34	N/C
500	2610	Saturated Brine	10.0	28-34	N/C
2610	9574	Cut Brine	8.6-9.5	28-34	N/C
9097	9749	OBM	10.0-13.0	30-40	<10cc

Sufficient mud materials to maintain mud properties and meet minimum lost circulation and weight increase requirements will be kept on location at all times.

What will be used to monitor the loss or gain of fluid?	Pason/PVT/Visual Monitoring
---	-----------------------------

**6. Logging and Testing Procedures**

Logging, Coring and Testing.	
X	Will run GR/CNL from KOP (9,131') to surface (horizontal well – vertical portion of hole). Stated logs run will be in the Completion Report and submitted to the BLM.
	No Logs are planned based on well control or offset log information.
	Drill stem test? If yes, explain
	Coring? If yes, explain

Additional logs planned	Interval
X	Gamma Ray
	Density
	CBL
	Mud log
	PEX

**Mewbourne Oil Company, Oxbow 23/24 WOLI Fed Com #1H**  
**Sec 23 & 24, T25S, R28E**  
**SL: 867' FSL & 233' FWL (Sec 23)**  
**BHL: 1625' FSL & 330' FEL (Sec 24)**

**7. Drilling Conditions**

Condition	Specify what type and where?
BH Pressure at deepest TVD	6590 psi
Abnormal Temperature	No

Mitigation measure for abnormal conditions. Describe. Lost circulation material/sweeps/mud scavengers in surface hole. Weighted mud for possible over-pressure in Wolfcamp formation.

Hydrogen Sulfide (H2S) monitors will be installed prior to drilling out the surface shoe. If H2S is detected in concentrations greater than 100 ppm, the operator will comply with the provisions of Onshore Oil and Gas Order #6. If Hydrogen Sulfide is encountered, measured values and formations will be provided to the BLM.
--

	H2S is present
X	H2S Plan attached

**8. Other facets of operation**

Is this a walking operation? If yes, describe.  
 Will be pre-setting casing? If yes, describe.

Attachments  
 Directional Plan  
 Other, describe



APD ID: 10400037789

Submission Date: 01/16/2019

Highlighted data  
reflects the most  
recent changes

Operator Name: MEWBOURNE OIL COMPANY

Well Name: OXBOW 23/24 W0LI FED COM

Well Number: 1H

[Show Final Text](#)

Well Type: CONVENTIONAL GAS WELL

Well Work Type: Drill

### Section 1 - Existing Roads

Will existing roads be used? YES

Existing Road Map:

Oxbow23\_24W0LIFedCom1H\_existingroadmap\_20190109135706.pdf

Existing Road Purpose: ACCESS,FLUID TRANSPORT

Row(s) Exist? NO

**ROW ID(s)**

ID:

Do the existing roads need to be improved? NO

Existing Road Improvement Description:

Existing Road Improvement Attachment:

### Section 2 - New or Reconstructed Access Roads

Will new roads be needed? NO

### Section 3 - Location of Existing Wells

Existing Wells Map? YES

Attach Well map:

Oxbow23\_24W0LIFedCom1H\_existingwellmap\_20190109135726.pdf

Operator Name: MEWBOURNE OIL COMPANY

Well Name: OXBOW 23/24 WOLI FED COM

Well Number: 1H

### Section 4 - Location of Existing and/or Proposed Production Facilities

Submit or defer a Proposed Production Facilities plan? SUBMIT

Production Facilities description: Battery site located on the west side of well pad.

Production Facilities map:

Oxbow23\_24WOLIFedCom1H\_productionfacilitymap\_20190109135749.pdf

### Section 5 - Location and Types of Water Supply

#### Water Source Table

Water source type: IRRIGATION

Water source use type: SURFACE CASING  
INTERMEDIATE/PRODUCTION CASING  
DUST CONTROL

Source latitude: 32.65556

Source longitude: -104.4587

Source datum: NAD83

Water source permit type: WATER WELL

Water source transport method: TRUCKING

Source land ownership: PRIVATE

Source transportation land ownership: PRIVATE

Water source volume (barrels): 2135

Source volume (acre-feet): 0.27518675

Source volume (gal): 89670

Water source and transportation map:

Oxbow23\_24WOLIFedCom1H\_watersourceandtransmap\_20190109135813.pdf

Water source comments:

New water well? NO

#### New Water Well Info

Well latitude:

Well Longitude:

Well datum:

**Operator Name:** MEWBOURNE OIL COMPANY

**Well Name:** OXBOW 23/24 WOLI FED COM

**Well Number:** 1H

**Well target aquifer:**

**Est. depth to top of aquifer(ft):**

**Est thickness of aquifer:**

**Aquifer comments:**

**Aquifer documentation:**

**Well depth (ft):**

**Well casing type:**

**Well casing outside diameter (in.):**

**Well casing inside diameter (in.):**

**New water well casing?**

**Used casing source:**

**Drilling method:**

**Drill material:**

**Grout material:**

**Grout depth:**

**Casing length (ft.):**

**Casing top depth (ft.):**

**Well Production type:**

**Completion Method:**

**Water well additional information:**

**State appropriation permit:**

**Additional information attachment:**

### Section 6 - Construction Materials

**Using any construction materials:** YES

**Construction Materials description:** Caliche

**Construction Materials source location attachment:**

Oxbow23\_24WOLIFedCom1H\_calichesourceandtransmap\_20190109135834.pdf

### Section 7 - Methods for Handling Waste

**Waste type:** DRILLING

**Waste content description:** Drill cuttings

**Amount of waste:** 1335 barrels

**Waste disposal frequency :** One Time Only

**Safe containment description:** 20 yard roll off bins

**Safe containmant attachment:**

**Waste disposal type:** HAUL TO COMMERCIAL FACILITY

**Disposal location ownership:** PRIVATE

**Disposal type description:**

**Disposal location description:** NMOCD approved waste disposal locations are CRI or Lea Land, both facilities are located on HWY 62/180, Sec. 27 T20S R32E.

**Operator Name:** MEWBOURNE OIL COMPANY

**Well Name:** OXBOW 23/24 WOLI FED COM

**Well Number:** 1H

**Waste type:** SEWAGE

**Waste content description:** Human waste & grey water

**Amount of waste:** 1500 gallons

**Waste disposal frequency :** Weekly

**Safe containment description:** 2,000 gallon plastic container

**Safe containmant attachment:**

**Waste disposal type:** HAUL TO COMMERCIAL FACILITY      **Disposal location ownership:** PRIVATE

**Disposal type description:**

**Disposal location description:** City of Carlsbad Water Treatment facility

**Waste type:** GARBAGE

**Waste content description:** Garbage & trash from all drilling & completion procedures

**Amount of waste:** 1500 pounds

**Waste disposal frequency :** One Time Only

**Safe containment description:** Enclosed trash trailers

**Safe containmant attachment:**

**Waste disposal type:** HAUL TO COMMERCIAL FACILITY      **Disposal location ownership:** PRIVATE

**Disposal type description:**

**Disposal location description:** County of Eddy waste management

### Reserve Pit

**Reserve Pit being used?** NO

**Temporary disposal of produced water into reserve pit?**

**Reserve pit length (ft.)**      **Reserve pit width (ft.)**

**Reserve pit depth (ft.)**      **Reserve pit volume (cu. yd.)**

**Is at least 50% of the reserve pit in cut?**

**Reserve pit liner**

**Reserve pit liner specifications and installation description**

### Cuttings Area

**Cuttings Area being used?** NO

**Are you storing cuttings on location?** YES

**Operator Name:** MEWBOURNE OIL COMPANY

**Well Name:** OXBOW 23/24 W0LI FED COM

**Well Number:** 1H

**Description of cuttings location** Drill cuttings will be properly contained in steel tanks (20 yard roll off bins.) and taken to an NMOCD approved disposal facility listed below. After drilling and completion operations, trash, chemicals, salts, frac sand and other waste material will be removed and disposed of properly at the said facilities. NMOCD approved waste disposal locations are CRI or Lea Land, both facilities are located on HWY 62/180, Sec. 27 T20S R32E.

**Cuttings area length (ft.)**

**Cuttings area width (ft.)**

**Cuttings area depth (ft.)**

**Cuttings area volume (cu. yd.)**

**Is at least 50% of the cuttings area in cut?**

**WCuttings area liner**

**Cuttings area liner specifications and installation description**

### Section 8 - Ancillary Facilities

**Are you requesting any Ancillary Facilities?:** NO

**Ancillary Facilities attachment:**

**Comments:**

### Section 9 - Well Site Layout

**Well Site Layout Diagram:**

Oxbow23\_24W0LIFedCom1H\_wellsitelayout\_20190109135916.pdf

**Comments:**

### Section 10 - Plans for Surface Reclamation

**Type of disturbance:** New Surface Disturbance

**Multiple Well Pad Name:** OXBOW 23/24 LI & MP

**Multiple Well Pad Number:** 4

**Recontouring attachment:**

**Drainage/Erosion control construction:** None required

**Drainage/Erosion control reclamation:** None required

**Well pad proposed disturbance (acres):** 3.54

**Well pad interim reclamation (acres):** 0.733

**Well pad long term disturbance (acres):** 2.807

**Road proposed disturbance (acres):** 0.55

**Road interim reclamation (acres):** 0

**Road long term disturbance (acres):** 0

**Powerline proposed disturbance (acres):** 0

**Powerline interim reclamation (acres):** 0

**Powerline long term disturbance (acres):** 0

**Pipeline proposed disturbance (acres):** 0

**Pipeline interim reclamation (acres):** 0

**Pipeline long term disturbance (acres):** 0

**Other proposed disturbance (acres):** 0

**Other interim reclamation (acres):** 0

**Other long term disturbance (acres):** 0

**Operator Name:** MEWBOURNE OIL COMPANY

**Well Name:** OXBOW 23/24 WOLI FED COM

**Well Number:** 1H

**Total proposed disturbance:** 4.09      **Total interim reclamation:** 0.733      **Total long term disturbance:** 2.807

**Disturbance Comments:** The length of the pipeline is unknown. A sundry notice will be filed for approval of said pipeline.

**Reconstruction method:** Remove caliche, redistribute topsoil over reclaimed area & reseed.

**Topsoil redistribution:** Use backhoe/loader to spread material.

**Soil treatment:** None

**Existing Vegetation at the well pad:** Various brush & grasses.

**Existing Vegetation at the well pad attachment:**

**Existing Vegetation Community at the road:** Various brush & grasses.

**Existing Vegetation Community at the road attachment:**

**Existing Vegetation Community at the pipeline:** Various brush & grasses.

**Existing Vegetation Community at the pipeline attachment:**

**Existing Vegetation Community at other disturbances:** Various brush & grasses.

**Existing Vegetation Community at other disturbances attachment:**

**Non native seed used?** NO

**Non native seed description:**

**Seedling transplant description:**

**Will seedlings be transplanted for this project?** NO

**Seedling transplant description attachment:**

**Will seed be harvested for use in site reclamation?** NO

**Seed harvest description:**

**Seed harvest description attachment:**

## Seed Management

### Seed Table

**Seed type:**

**Seed source:**

**Seed name:**

**Source name:**

**Source address:**

**Source phone:**

**Operator Name:** MEWBOURNE OIL COMPANY

**Well Name:** OXBOW 23/24 WOLI FED COM

**Well Number:** 1H

**Seed cultivar:**

**Seed use location:**

**PLS pounds per acre:**

**Proposed seeding season:**

Seed Summary	
Seed Type	Pounds/Acre

**Total pounds/Acre:**

**Seed reclamation attachment:**

**Operator Contact/Responsible Official Contact Info**

**First Name:** Bradley

**Last Name:** Bishop

**Phone:** (575)393-5905

**Email:** bbishop@mewbourne.com

**Seedbed prep:** recontouring

**Seed BMP:** NA

**Seed method:** broadcast & drill

**Existing invasive species?** NO

**Existing invasive species treatment description:**

**Existing invasive species treatment attachment:**

**Weed treatment plan description:** None

**Weed treatment plan attachment:**

**Monitoring plan description:** Visual inspection within 3 months of interim reclamation.

**Monitoring plan attachment:**

**Success standards:** Complete re-growth within 1 year of interim reclamation.

**Pit closure description:** None

**Pit closure attachment:**

**Section 11 - Surface Ownership**

**Disturbance type:** WELL PAD

**Describe:**

**Surface Owner:** BUREAU OF LAND MANAGEMENT

**Other surface owner description:**

**BIA Local Office:**

**BOR Local Office:**

**COE Local Office:**

**Operator Name:** MEWBOURNE OIL COMPANY

**Well Name:** OXBOW 23/24 WOLI FED COM

**Well Number:** 1H

**DOD Local Office:**

**NPS Local Office:**

**State Local Office:**

**Military Local Office:**

**USFWS Local Office:**

**Other Local Office:**

**USFS Region:**

**USFS Forest/Grassland:**

**USFS Ranger District:**

**Disturbance type:** NEW ACCESS ROAD

**Describe:**

**Surface Owner:** BUREAU OF LAND MANAGEMENT

**Other surface owner description:**

**BIA Local Office:**

**BOR Local Office:**

**COE Local Office:**

**DOD Local Office:**

**NPS Local Office:**

**State Local Office:**

**Military Local Office:**

**USFWS Local Office:**

**Other Local Office:**

**USFS Region:**

**USFS Forest/Grassland:**

**USFS Ranger District:**

**Operator Name:** MEWBOURNE OIL COMPANY

**Well Name:** OXBOW 23/24 WOLI FED COM

**Well Number:** 1H

**Disturbance type:** NEW ACCESS ROAD

**Describe:**

**Surface Owner:** BUREAU OF LAND MANAGEMENT

**Other surface owner description:**

**BIA Local Office:**

**BOR Local Office:**

**COE Local Office:**

**DOD Local Office:**

**NPS Local Office:**

**State Local Office:**

**Military Local Office:**

**USFWS Local Office:**

**Other Local Office:**

**USFS Region:**

**USFS Forest/Grassland:**

**USFS Ranger District:**

**Disturbance type:** OTHER

**Describe:** Production Facility

**Surface Owner:** BUREAU OF LAND MANAGEMENT

**Other surface owner description:**

**BIA Local Office:**

**BOR Local Office:**

**COE Local Office:**

**DOD Local Office:**

**NPS Local Office:**

**State Local Office:**

**Military Local Office:**

**USFWS Local Office:**

**Other Local Office:**

**USFS Region:**

**USFS Forest/Grassland:**

**USFS Ranger District:**

**Operator Name:** MEWBOURNE OIL COMPANY

**Well Name:** OXBOW 23/24 W0LI FED COM

**Well Number:** 1H

### Section 12 - Other Information

**Right of Way needed?** NO

**Use APD as ROW?**

**ROW Type(s):**

#### ROW Applications

**SUPO Additional Information:**

**Use a previously conducted onsite?** YES

**Previous Onsite information:** APR 11 2018 Met with BLM & RRC surveying & staked location @ location 1490' FSL & 500' FWL, Sec 23, T25S, R28E, Eddy Co., NM. This location was unacceptable due to large drainage on north edge of location. Moved location to 867' FSL & 233' FWL, Sec 23, T25S R28E, Eddy Co., NM. This appears to be a drillable location with pit area to the west. (Elevation @ 2932'). Topsoil will be stockpiled on south edge of well pad. Location is 350' x 450'. Lease road will be on SE corner of location heading south to Oxbow 26/25 DA well pad. Oxbow 23/24 W1LI, Oxbow 23/24 W1MP & Oxbow 23/24 W2MP are staked on this location. Lat: 32.11051642 N, Long -104.06575016 W NAD 83. Will require hydrology mitigation on east and south sides of well pad.


#### Other SUPO Attachment

Oxbow23\_24W0LIFedCom1H\_interimreclamationdiagram\_20190109140019.pdf

Oxbow23\_24W0LIFedCom1H\_gascaptureplan\_20190109140032.pdf

# VICINITY MAP

NOT TO SCALE



**SECTION 23, TWP. 25 SOUTH, RGE. 28 EAST,  
N. M. P. M., EDDY CO., NEW MEXICO**

OPERATOR: Mewbourne Oil Company

LOCATION: 867' FSL & 233' FWL

LEASE: Oxbow 23/24 WOLI Fed Com

ELEVATION: 2932'

WELL NO.: 1H

*Copyright 2016 - All Rights Reserved*


NO.	REVISION	DATE
JOB NO.:	LS1804461R	
DWG. NO.:	1804461R-3	

# RRC


701 S. CECIL ST., HOBBS, NM 88240 (575) 964-8200

SCALE:	N. T. S.
DATE:	11-13-2018
SURVEYED BY:	ML/TF
DRAWN BY:	KAKN
APPROVED BY:	RMH
SHEET:	1 OF 1

# EXISTING WELL MAP OXBOW 23/24 WOLI FED COM #1H



**MEWBOURNE OIL COMPANY**  
**OXBOW 23/24 WOLI FED COM #1H**  
**(867' FSL & 233' FWL)**  
**SECTION 23, T25S, R28E**  
**N. M. P. M., EDDY COUNTY, NEW MEXICO**




DIRECTIONS TO LOCATION

*From the intersection of CR-722 (Bumpy Rd.) and HWY-285 (Pecos HWY):*  
*Go South on HWY-285 approx. 1.5 miles to a lease road on the left;*  
*Turn left and go East approx. 0.3 miles to a lease road on the left;*  
*Turn left and go North approx. 0.5 miles to proposed road;*  
*Continue North on proposed road approx. 0.2 miles to location on the left.*

THIS IS NOT A BOUNDARY SURVEY, APPARENT PROPERTY CORNERS AND PROPERTY LINES ARE SHOWN FOR INFORMATION ONLY, BOUNDARY DATA IS SHOWN FROM A PREVIOUS SURVEY REFERENCED HEREON.

I, R. M. Howett, a N. M. Professional Surveyor, hereby certify that I prepared this unclassified survey of a well location from an actual survey made on the ground under my direct supervision, said survey and plat meet the Min. Stds. for Land Surveying in the State of N. M. and are true and correct to the best of my knowledge and belief.

*Robert M. Howett*  
 Robert M. Howett NM PS 19680



SCALE: 1" = 100'  
 0 50 100  
 BEARINGS ARE  
 NAD 83 GRID - NM EAST  
 DISTANCES ARE GROUND

Copyright 2016 - All Rights Reserved


NO.	REVISION	DATE
JOB NO.: LS1804461R		
DWG. NO.: 1804461R-4		

**RRC**

701 S. CECIL ST., HOBBS, NM 88240 (575) 964-8200


SCALE: 1" = 100'
DATE: 11-13-2018
SURVEYED BY: ML/TF
DRAWN BY: KAKN
APPROVED BY: RMH
SHEET: 1 OF 1







MEWBOURNE OIL COMPANY  
 OXBOW 23/24 WOLI FED COM #1H  
 (867' FSL & 233' FWL)  
 SECTION 23, T25S, R28E  
 N. M. P. M., EDDY COUNTY, NEW MEXICO




DIRECTIONS TO LOCATION

From the intersection of CR-722 (Bumpy Rd.) and HWY-285 (Pecos HWY);  
 Go South on HWY-285 approx. 1.5 miles to a lease road on the left;  
 Turn left and go East approx. 0.3 miles to a lease road on the left;  
 Turn left and go North approx. 0.5 miles to proposed road;  
 Continue North on proposed road approx. 0.2 miles to location on the left.

THIS IS NOT A BOUNDARY SURVEY, APPARENT PROPERTY CORNERS AND PROPERTY LINES ARE SHOWN FOR INFORMATION ONLY, BOUNDARY DATA IS SHOWN FROM A PREVIOUS SURVEY REFERENCED HEREON.

I, R. M. Howett, a N. M. Professional Surveyor, hereby certify that I prepared this unclassified survey of a well location from an actual survey made on the ground under my direct supervision, said survey and plat meet the Min. Stds. for Land Surveying in the State of N. M. and are true and correct to the best of my knowledge and belief.

*Robert M. Howett*  
 Robert M. Howett NM PS 19680



SCALE: 1" = 100'  
 0 50 100  
 BEARINGS ARE  
 NAD 83 GRID - NM EAST  
 DISTANCES ARE GROUND

Copyright 2016 - All Rights Reserved

NO.	REVISION	DATE
JOB NO.: LS1804461R		
DWG. NO.: 1804461R-4		



701 S. CECIL ST., HOBBS, NM 88240 (575) 964-8200

SCALE: 1" = 100'
DATE: 11-13-2018
SURVEYED BY: ML/TF
DRAWN BY: KAKN
APPROVED BY: RMH
SHEET: 1 OF 1

**Operator Name:** MEWBOURNE OIL COMPANY

**Well Name:** OXBOW 23/24 WOLI FED COM

**Well Number:** 1H

**Lined pit Monitor description:**

**Lined pit Monitor attachment:**

**Lined pit: do you have a reclamation bond for the pit?**

**Is the reclamation bond a rider under the BLM bond?**

**Lined pit bond number:**

**Lined pit bond amount:**

**Additional bond information attachment:**

### **Section 3 - Unlined Pits**

**Would you like to utilize Unlined Pit PWD options? NO**

**Produced Water Disposal (PWD) Location:**

**PWD disturbance (acres):**

**PWD surface owner:**

**Unlined pit PWD on or off channel:**

**Unlined pit PWD discharge volume (bbl/day):**

**Unlined pit specifications:**

**Precipitated solids disposal:**

**Describe precipitated solids disposal:**

**Precipitated solids disposal permit:**

**Unlined pit precipitated solids disposal schedule:**

**Unlined pit precipitated solids disposal schedule attachment:**

**Unlined pit reclamation description:**

**Unlined pit reclamation attachment:**

**Unlined pit Monitor description:**

**Unlined pit Monitor attachment:**

**Do you propose to put the produced water to beneficial use?**

**Beneficial use user confirmation:**

**Estimated depth of the shallowest aquifer (feet):**

**Does the produced water have an annual average Total Dissolved Solids (TDS) concentration equal to or less than that of the existing water to be protected?**

**TDS lab results:**

**Geologic and hydrologic evidence:**

**State authorization:**

**Unlined Produced Water Pit Estimated percolation:**

**Unlined pit: do you have a reclamation bond for the pit?**

**Operator Name:** MEWBOURNE OIL COMPANY

**Well Name:** OXBOW 23/24 WOLI FED COM

**Well Number:** 1H

**Is the reclamation bond a rider under the BLM bond?**

**Unlined pit bond number:**

**Unlined pit bond amount:**

**Additional bond information attachment:**

#### **Section 4 - Injection**

**Would you like to utilize Injection PWD options?** NO

**Produced Water Disposal (PWD) Location:**

**PWD surface owner:**

**PWD disturbance (acres):**

**Injection PWD discharge volume (bbl/day):**

**Injection well mineral owner:**

**Injection well type:**

**Injection well number:**

**Injection well name:**

**Assigned injection well API number?**

**Injection well API number:**

**Injection well new surface disturbance (acres):**

**Minerals protection information:**

**Mineral protection attachment:**

**Underground Injection Control (UIC) Permit?**

**UIC Permit attachment:**

#### **Section 5 - Surface Discharge**

**Would you like to utilize Surface Discharge PWD options?** NO

**Produced Water Disposal (PWD) Location:**

**PWD surface owner:**

**PWD disturbance (acres):**

**Surface discharge PWD discharge volume (bbl/day):**

**Surface Discharge NPDES Permit?**

**Surface Discharge NPDES Permit attachment:**

**Surface Discharge site facilities information:**

**Surface discharge site facilities map:**

#### **Section 6 - Other**

**Would you like to utilize Other PWD options?** NO

**Produced Water Disposal (PWD) Location:**

**PWD surface owner:**

**PWD disturbance (acres):**

**Other PWD discharge volume (bbl/day):**

**Operator Name:** MEWBOURNE OIL COMPANY

**Well Name:** OXBOW 23/24 WOLI FED COM

**Well Number:** 1H

**Other PWD type description:**

**Other PWD type attachment:**

**Have other regulatory requirements been met?**

**Other regulatory requirements attachment:**



U.S. Department of the Interior  
BUREAU OF LAND MANAGEMENT

## Bond Info Data Report

09/26/2019

**APD ID:** 10400037789

**Submission Date:** 01/16/2019

Highlighted data  
reflects the most  
recent changes

**Operator Name:** MEWBOURNE OIL COMPANY

**Well Name:** OXBOW 23/24 WOLI FED COM

**Well Number:** 1H

[Show Final Text](#)

**Well Type:** CONVENTIONAL GAS WELL

**Well Work Type:** Drill

### Bond Information

**Federal/Indian APD:** FED

**BLM Bond number:** NM1693

**BIA Bond number:**

**Do you have a reclamation bond?** NO

**Is the reclamation bond a rider under the BLM bond?**

**Is the reclamation-bond BLM or Forest Service?**

**BLM reclamation bond number:**

**Forest Service reclamation bond number:**

**Forest Service reclamation bond attachment:**

**Reclamation bond number:**

**Reclamation bond amount:**

**Reclamation bond rider amount:**

**Additional reclamation bond information attachment:**