

8. TESTING, LOGGING AND CORING PROGRAM:
Samples: Run samples at 10' intervals from Surface to TD.
DST's: Test zones as recommended by wellsite geologist.
Logging: Dual Laterolog and Compensated Neutron/Density log with Gamma Ray and Caliper will be run from surface casing shoe to TD.
Coring: None planned
9. ABNORMAL PRESSURES, TEMPERATURES OR HYDROGEN SULFIDE:
None anticipated. Maximum bottom-hole pressure should not exceed 1500 psi.
10. ANTICIPATED STARTING DATE: Drilling will commence about December 29, 1981. Drilling should be completed within 21 days. Completion operations (perforations and stimulation) will follow drilling operations.