

6. Pressure Control Equipment: A 3000 psi working pressure B.O.P. will be installed after the 8 5/8" casing is set and cemented.
7. Proposed Testing, Logging and Coring Programs:
Testing: None
Logging: CNL-FDC; DLL-MSFL
Coring : None
8. Auxiliary Equipment: A kelly cock will be installed on the rig floor while drilling operations are in progress.
9. Abnormal Pressures or Temperature Zones: No abnormal pressures or temperature zones are anticipated.
10. Anticipated Starting Date: Commence drilling operations October 20, 1987.