

6. TESTING PROGRAM

Possible DST's will be performed as dictated by shows. Such tests, if necessary, will be conducted under prudent industry practice.

Open hole logs planned:

DLL/MSFL/GR
CNL/LD/GR/CAL
SONIC WITH GR

Gamma Ray logs will be run to the surface.

7. POTENTIAL HAZARDS

No H₂S, abnormal temperatures or abnormal pressures are anticipated. None of the above problems were reported on the dry hole located 1291.8' West of this proposed location.

8. ESTIMATED STARTING DATE

Anticipate starting operations as soon as possible subject to approval of this permit.