

6. Proposed Mud Program

0 - 1100' Fresh Water-Native; Mud Wt: 8.3 - 9.2, Viscosity
28-34 Sec

7. Auxiliary Equipment

A safety valve and subs to fit all strings will be kept on the floor at all times. An upper kelly cock valve will be utilized with the handle available on the rig floor.

8. Testing, Logging, and Coring Programs

A. Coring Program:

None anticipated.

B. Testing Program:

Possible DST's in Wolfcamp and Fusselman.

C. Logging Program:

TD-Surface - GR/DIL, GR/LDT/CNL, DLL/MSFL.

9. Abnormal Pressures, Temperatures or Potential Hazards

None anticipated

10. Anticipated Starting Date

As soon as possible

