

BOP's are 10" Series 900 Type "E"  
Shaffer Double Hydraulic 6000 PSI  
test, 3000 psi working pressure. All  
additional valves and connections  
are the same test and working pressures.

