

District - 184860  
Prop - 26086  
Pool - 3220

**Mershon No. 2 (old well converted):**

Initial injection shall be down the casing into the Loco Hills, Metex, and Premier zones. A liner and tubing and packer or tubing and formation packer may be run later if performance requires selective injection between the Loco Hills zone and the Metex and Premier zones.

Casing in the latter two wells, Collier No. 1 and Mershon No. 2, shall be pressure-tested prior to placing the wells on injection. The casing must satisfactorily hold a 3000 psi test pressure for 30 minutes. Operator shall notify the Artesia district office of the Commission of the date and hour said pressure tests are to be conducted.

---

w/w order K-3341

