NM OIL CONS COMMISSION

Drawer DD

Artesia, NM 88210

c/5/


Firm 3160-5

UNITED STATES

FORM APPROVED

lune 1990)		NT OF THE INTERIOR		Budget Bureau No. 1004-0135 Expires: March 31, 1993	
	BUREAU OF	LAND MANAGEMENT		5. Lease Designation and Serial No.	
	SUNDRY NOTICES	I.C029392B 6. If Indian, Allottee or Tribe Name			
Do not use	this form for proposals to di		y to a different reservo		
<u>, </u>	SUBMIT	IN TRIPLICATE		7. If Unit or CA, Agreement Designation	
1 Type of Well			46.2 Aug		
Oil Well	Gas Well Other		MOA 5.2"	8. Well Name and No.	
2 Name of Open	alor		0 C D.	Hinkle B-26#2	
Tom Bo	oyd Drilling Co.,	Inc. (Enerloc Re	esourcesce Inc.)	9. API Well No. 05609	
Address and T	•		ARIESITA	30015 87322001	
616 Me	echem Dr., Ruidoso, ell (Footage, Sec., T., R., M., or Survey D	10. Field and Pool, or Exploratory Area Shugart, Yates, 7-Rive			
	ell (Pootage, Sec., I., R., M., or Survey L	Suesition Arrandourg			
#2	EST & 220 EWT Soc	A A GOODBAN TO LANGUAGE OF E			
1000 1	FSL & 330 FWL, Sec.	. 20, 1-10-5, n-	·31-E \(\)	Eddy County N M	
	HECK ARRODRIATE BOY	O TO INDICATE MATI	IDE OF NOTICE DE	Eddy County, N.M.	
- Cr	HECK APPROPRIATE BOX	S) TO INDICATE NATO	THE OF NOTICE, HER	ORI, OR OTHER DATA	
TY	PE OF SUBMISSION	TYPE OF ACTION			
X	S Notice of Intent	XX Abandonm	ent	Change of Plans	
	_	Recompleti		New Construction	
Subsequent Report		Plugging Back		Non-Routine Fracturing	
	_	Casing Rep	pair	Water Shut-Off	
Final Abandonment Notice		Altering Casing		Conversion to Injection	
		Other	· 	Dispose Water	
				(Note: Report results of multiple completion on We'. Completion or Recompletion Report and Log form	
Describe Propo	sed or Completed Operations (Clearly state a	Il pertinent details, and give pertinent of	lates, including estimated date of sta	rting any proposed work. If well is directionally drilled	
	in halo open and true vertices			ent plum (Class UCH	
	6/gal.)from 3720 to		1120. Spot cem	ent plug (Class "C",	
	9.016/gal. mud fr		י מי		
	cement plug from				
	t mud from 2550' to				
			and anat mud	haak +a 501	
6 Spot	t cement plug from	501 hook to 315'	and spot mud	Dack to but,	
0.2001	5/8" casing.	oo back to sur	race. Pump cem	ent between 5 1/2" casin	
		Postoro			
1.Frec	et dry hole marker.	nestore.			

Signed	Title President	Date_	6/30/94
(This space for Federal or State office use) Boyd Approved b (ORIG. SGD.) JOE G. LARA	PETROLEUM ENGINEER	Date	10/27/94
Approved b (ORIG. SGD.) JOE G. LARA Conditions of approval, if any: See attached. Leaving 100	Also perf 5/2" rsg @ 845 emt Dlug Srom 795'-895	4	Squeeze ON



BUREAU OF LAND MANAGEMENT CARLSBAD RESOURCE AREA

Permanent Abandonment of Wells on Federal Lands

Conditions of Approval

- 1. <u>Approval:</u> Plugging operations shall commence within 90 days from the approval date of plugging procedure.
- 2. <u>Notification:</u> Contact the appropriate BLM office at least 24 hours prior to the commencing of any plugging operations. For wells in Eddy County call (505)887-6544; for wells in Lea County call (505) 393-3612.
- 3. <u>Blowout Preventers:</u> A blowout preventer (BOP), as appropriate, shall be installed before commencing any plugging operation. The minimum BOP requirement is a 2M system for a well not deeper than 9,090 feet; a 3M system for a well not deeper than 13,636 feet; and a 5M system for a well not deeper than 22,727 feet.
- 4. <u>Mud Requirement:</u> Mud shall be placed between all plugs. Minimum consistency of plugging mud shall be obtained by mixing at the rate of 25 sacks (50 pounds each) of gel per 100 barrels of water. Minimum nine (9) pounds per gallon.
- 5. <u>Cement Requirement:</u> Sufficient cement shall be used to bring any required plug to the specified depth and length. Any given cement volumes on the proposed plugging procedure are merely estimates and are not final.

Unless otherwise specified in the approved procedure, the cement plug shall consist of either class "C" , for up to 7,500 feet of depth, mixed at 14.8 lbs./gal. with 6.3 gallons of fresh water per sack or class "H" , for deeper than 7,500 feet plugs, mixed at 16.4 lbs./gal. with 4.3 gallons of fresh water per sack.

- or 3 feet below final restored ground level (whichever is deeper). The well bore shall then be capped with a 4-inch pipe, 10-feet in length, 4 feet above ground and embedded in cement. The following information shall be permanently inscribed on the dry hole marker: Well name and number, the name of the operator, the lease serial number, the surveyed location (the quarter-quarter section, section, township and range or other authorized survey designation acceptable to the authorized officer; such as metes and bounds).
- 7. <u>Subsequent Plugging Reporting:</u> Within 30 days after plugging work is completed, file one original and five copies of the Subsequent Report of Abandonment, Form 3160-5 to BLM. The report should give in detail the manner in which the plugging work was carried out, the extent (by depths) of cement plugs placed, and the size and location (by depths) of casing left in the well. Show <u>date</u> well was plugged.

Following the submittal and approval of the Subsequent Report of Abandonment, surface restoration conditions of approval will be developed and furnished to you.