

WOLFCAMP

PRODUCTION
FACILITIES

CHRISTMAS TREE IS 5000# WP
THRUOUT

MORROW

PRODUCTION
FACILITIES

SURFACE

10 3/4" 31# CSG. CMTD. @
417' W/400 SX. CIRC. 140 SX.
CMT.

1 CMT. BASKET @ 1000'

1 CMT. BASKET @ 1500'

8 5/8" 24 & 28# CSG SET @ 2800'
CMTD. W/1121 SX. CMT. TOP @ 541'

BFC MODEL "L" SLIDING
SLEEVE @ 8744'

CEMENT TOP @ 6880'

BFC TYPE "F" SEATING
NIPPLE @ 8878'

GUIBERSON TYPE UNI-III
RETR. PROD. PKR. W/
HYDRAULIC HOLD-DOWN &
CROSS-OVER ASSY.

8810' BFC MODEL "J" PORTED NIPPLE

OTIS TYPE "S" PORTED
NIPPLE @ 8820'

8866' } PERF. W/2 .32" HOLES/FOOT

8890' } THREE 2 3/8" OD EUE BLAST
8895' } JOINTS OPPOSITE PERFORATED
8902' } INTERVAL

WOLFCAMP INTERVAL

CENTRALIZERS INSTALLED AT
8740, 8780, 8820, 8860,
8900, & 8940

BAKER LOK-SET 10,982'
RETRIEVABLE PROD. PKR.

BAKER MODEL "R" SEATING NIPPLE
W/BALL & SEAT STANDING VALVE @
10,981'

MORROW INTERVAL

2 3/8" EUE N-80 TBG. SET
@ 11,048'

11,025' } PERF. W/4 .32" HOLES
11,028' } PER FOOT

11,041' } PERF. W/4 .32" HOLES
11,047' } PER FOOT

HALLIBURTON "SV" CEMENT RETAINER
@ 11,055'

11,065' }
11,075' } PERF. INTERVALS
11,080' } SQUEEZED W/150 SX.
11,090' }

11,115'
11,130'

CENTRALIZERS INSTALLED AT
10920, 10940, 10980, 11020,
11060, & 11100

ORIG. PBTD 11,411'

5 1/2" 17# & 20# CSG. CMTD.
@ 11,549' W/1025 SX. CMT.
BASKETS @ 9000' AND 9500'

DEPCO, Inc.

DIAGRAMMATIC SKETCH OF DUAL COMPLETION

DHY STATE NO. 1

SEC. 23 T. 19 S., R. 28 E.

EDDY CO., NEW MEXICO