

BOP PROGRAM

2 Diagrams of pressure control equipment is attached. Additional information about the pressure control equipment and testing/maintenance is as follows:

20" Conductor:

Flow nipple only. No BOP.

9 5/8" Casing:

Size: 11" 3000 psi WP double ram hydraulic with annular.

Pressure rating: 3000 psi WP, 6000 psi test.

Testing procedure: Annular to be tested to 1500 psi.

Testing frequency: Pressure test upon installation.
Operational checks daily and on all trips.