

October 11, 1974

In addition to the blow out preventer program shown on the attached plat, the following equipment will be installed and in operation before drilling out from under the 9-5/8" casing:

1. Swaco adjustable choke in choke manifold.
2. Pit volume totalizer.
3. Flow line sensor.
4. Degasser.

Also prior to drilling out under the 9-5/8", the BOP's and related control equipment will be pressure tested to rated working pressure by an independent testing company.

The well will be drilled in accordance with USGS requirements stated in their Order No. 30 CFR 221.24, 221.36 and 221.37.

Please contact me at the above address if further information is needed to evaluate this request.

Yours very truly,



E. Y. Wilder
Operations Manager
Southwest Region
E & P Division

EYW/ljs

Attachments