



BOP rams will be actuated on each trip of drill pipe and will be tested before drilling the plug on each casing string.

*NOTE: ALL VALVES ARE METAL-TO-METAL SEAL AND FLANGED. ALL COMPONENTS MUST MEET ABOVE MINIMUM PRESSURE RATINGS. ALL COMPONENTS TO BE TESTED TO RATED PRESSURE AFTER ASSEMBLY AND BEFORE FURTHER DOWNHOLE OPERATIONS MAY BE CONDUCTED.

Mobil Producing Texas & New Mexico Inc. Houston, Texas		Scale
MOBIL NO. <u>Well 2</u> <u>State SS Lease</u> (LEASE)		Date Drawn Checked Approved Revised
<u>Eddy</u> COUNTY, <u>New Mexico</u> STATE		
BLOWOUT PREVENTER ASSEMBLY (<u>10"</u> IN. <u>5000</u> PSI WP*)		<i>18 Jan 84</i>