

LAGUNA GRANDE UNIT (FEDERAL) #3  
PLANNED COMPLETION PROCEDURE

I. Morrow Sandstone

- A. Perforate through tubing with approximately 1000 psi differential pressure into the wellbore in a mild clay stabilized acid with iron sequestering agents.
- B. Acidize and/or fracture stimulate as required (estimate 8000 gallons acid with 300 scf/bbl nitrogen).