



EOG Resources, Inc.
5509 Champions Drive
Midland, Texas 79706

January 16, 2018

EMNRD/OCD
Attn: Bradford Billings 1220
South St Francis Dr.
Santa Fe, NM 87505

Re: Form C-147 with accompanying documentation
Chili Pepper Reuse Water Facility and Containment Pit

Dear Mr. Billings,

Thank you for allowing EOG to continue to promote water reuse in the State of New Mexico for our operations. Please find attached C-147 form with accompanying documentation for the Chili Pepper Reuse Water Facility and Containment Pit.

Please do not hesitate to contact me with any questions, comments for concerns.

Sincerely,

A handwritten signature in black ink, appearing to read "Dustin Kinder", written over a white background.

Dustin Kinder
EOG Resources, Water Resource Manager

District I
1625 N. French Dr., Hobbs, NM 88240
District II
811 S. First St., Artesia, NM 88210
District III
1000 Rio Brazos Road, Aztec, NM 87410
District IV
1220 S. St. Francis Dr., Santa Fe, NM 87505

State of New Mexico
Energy Minerals and Natural Resources
Department
Oil Conservation Division
1220 South St. Francis Dr.
Santa Fe, NM 87505

Form C-147
Revised April 3, 2017

Recycling Facility and/or Recycling Containment

Type of Facility: Recycling Facility Recycling Containment*
Type of action: Permit Registration
 Modification Extension
 Closure Other (explain) _____

* At the time C-147 is submitted to the division for a Recycling Containment, a copy shall be provided to the surface owner.

Be advised that approval of this request does not relieve the operator of liability should operations result in pollution of surface water, ground water or the environment. Nor does approval relieve the operator of its responsibility to comply with any other applicable governmental authority's rules, regulations or ordinances.

1.
Operator: EOG Resources, Inc. (For multiple operators attach page with information) OGRID #: OGRID #7377
Address: 5509 Champions Dr. Midland, TX 79706
Facility or well name (include API# if associated with a well): Chili Pepper Water Recycling Facility and Containment Pit
OCD Permit Number: _____ (For new facilities the permit number will be assigned by the district office)
U/L or Qtr/Qtr NENW4 / NWNW4 Section 17 Township 23S Range 35E County: Lea
Surface Owner: Federal State Private Tribal Trust or Indian Allotment

2.
 Recycling Facility:
Location of recycling facility (if applicable): Latitude N:477765.21 Longitude E:832097.86 NAD83
Proposed Use: Drilling* Completion* Production* Plugging*
**The re-use of produced water may NOT be used until fresh water zones are cased and cemented*
 Other, *requires permit for other uses. Describe use, process, testing, volume of produced water and ensure there will be no adverse impact on groundwater or surface water.*
 Fluid Storage
 Above ground tanks Recycling containment Activity permitted under 19.15.17 NMAC explain type _____
 Activity permitted under 19.15.36 NMAC explain type: _____ Other explain _____
 For multiple or additional recycling containments, attach design and location information of each containment
 Closure Report (required within 60 days of closure completion): Recycling Facility Closure Completion Date: _____

3.
 Recycling Containment:
 Annual Extension after initial 5 years (attach summary of monthly leak detection inspections for previous year)
Center of Recycling Containment (if applicable): Latitude N:477759.27 Longitude E:831559.33 NAD83
 For multiple or additional recycling containments, attach design and location information of each containment
 Lined Liner type: Thickness 60 mil LLDPE HDPE PVC Other _____
 String-Reinforced
Liner Seams: Welded Factory Other _____ Volume: 1MM bbl Dimensions: L 600 x W 600 x D 16 (inside)
 Recycling Containment Closure Completion Date: _____

4.

Bonding:

- Covered under bonding pursuant to 19.15.8 NMAC per 19.15.34.15(A)(2) NMAC (These containments are limited to only the wells owned or operated by the owners of the containment.)
- Bonding in accordance with 19.15.34.15(A)(1). Amount of bond \$ _____ (work on these facilities cannot commence until bonding amounts are approved)
- Attach closure cost estimate and documentation on how the closure cost was calculated.

5.

Fencing:

- Four foot height, four strands of barbed wire evenly spaced between one and four feet
- Alternate. Please specify: Please see attached Variance Request Detail

6.

Signs:

- 12"x 24", 2" lettering, providing Operator's name, site location, and emergency telephone numbers
- Signed in compliance with 19.15.16.8 NMAC

7.

Variations:

Justifications and/or demonstrations that the proposed variance will afford reasonable protection against contamination of fresh water, human health, and the environment.

Check the below box only if a variance is requested:

- Variance(s): Requests must be submitted to the appropriate division district for consideration of approval. If a Variance is requested, include the variance information on a separate page and attach it to the C-147 as part of the application.
- If a Variance is requested, it must be approved prior to implementation.**

8.

Siting Criteria for Recycling Containment

Instructions: The applicant must provide attachments that demonstrate compliance for each siting criteria below as part of the application. Potential examples of the siting attachment source material are provided below under each criteria.

General siting

Ground water is less than 50 feet below the bottom of the Recycling Containment.

NM Office of the State Engineer - iWATERS database search; USGS; Data obtained from nearby wells

- Yes No
- NA

Within incorporated municipal boundaries or within a defined municipal fresh water well field covered under a municipal ordinance adopted pursuant to NMSA 1978, Section 3-27-3, as amended.

- Written confirmation or verification from the municipality; written approval obtained from the municipality

- Yes No
- NA

Within the area overlying a subsurface mine.

- Written confirmation or verification or map from the NM EMNRD-Mining and Minerals Division

- Yes No

Within an unstable area.

- Engineering measures incorporated into the design; NM Bureau of Geology & Mineral Resources; USGS; NM Geological Society; topographic map

- Yes No

Within a 100-year floodplain. FEMA map

- Yes No

Within 300 feet of a continuously flowing watercourse, or 200 feet of any other significant watercourse, or lakebed, sinkhole, or playa lake (measured from the ordinary high-water mark).

- Topographic map; visual inspection (certification) of the proposed site

- Yes No

Within 1000 feet from a permanent residence, school, hospital, institution, or church in existence at the time of initial application.

- Visual inspection (certification) of the proposed site; aerial photo; satellite image

- Yes No

Within 500 horizontal feet of a spring or a fresh water well used for domestic or stock watering purposes, in existence at the time of initial application.

- NM Office of the State Engineer - iWATERS database search; visual inspection (certification) of the proposed site

- Yes No

Within 500 feet of a wetland.

- US Fish and Wildlife Wetland Identification map; topographic map; visual inspection (certification) of the proposed site

- Yes No

9.

Recycling Facility and/or Containment Checklist:

Instructions: Each of the following items must be attached to the application. Indicate, by a check mark in the box, that the documents are attached.

- Design Plan - based upon the appropriate requirements.
- Operating and Maintenance Plan - based upon the appropriate requirements.
- Closure Plan - based upon the appropriate requirements.
- Site Specific Groundwater Data -
- Siting Criteria Compliance Demonstrations –
- Certify that notice of the C-147 (only) has been sent to the surface owner(s)**

10.

Operator Application Certification:

I hereby certify that the information and attachments submitted with this application are true, accurate and complete to the best of my knowledge and belief.

Name (Print): Dustin Kinder Title: Water Resource Manager

Signature:  Date: 1/16/2018

e-mail address: dustin_kinder@eogresources.com Telephone: 817-806-0470

11.

OCD Representative Signature: _____ **Approval Date:** _____

Title: _____ **OCD Permit Number:** _____

OCD Conditions _____

Additional OCD Conditions on Attachment



Variance Request for Bird Deterrent

Re: Chili Pepper Reuse Water Recycling Facility and Containment Pit

EOG Resources, Inc. would like to request the OCD's approval for a variance regarding bird deterrents at the location described above. EOG proposes to utilize the Bird-X Mega Blaster Pro, creating intermittent distress calls to create a "danger zone" that frightens native and or migrating birds and wildlife from the water recycling facility and containment pit area. Two units would be installed, each containing 2 built-in high output amplifiers and houses 20 speakers, capable of producing up to 125 decibels and a frequency range from 2,000 – 10,000 Hz.

Please note that EOG Resources, Inc. is currently utilizing this same bird deterrent, which was approved on OCD Permit No. 12

Please see details below.

Mega Blaster Pro – Specs:


- Coverage: Up to 30 acres from single unit
- Box dimensions: Box 1: 23" x 18" x 16" (23 lbs., unit & speaker), Box 2: 32" x 24" x 5" (17 lbs., solar panel)
- Power Input: 12vDC (3 amps) via solar panel and battery
- Sound Pressure: up to 125 decibels
- Frequency: 2,000–10,000 Hz
- Library of predator calls



- Full customizable to the species of bird in our area of operation
- Compliance: UL & CE listed
- EPA Est. 075310-OR-001
- Included: Generating unit with two built-in high-output amplifiers, 20-speaker tower with audio cables, 40 watt solar panel, battery clips, & all mounting hardware
- The unit is typically mounted with a tripod pole setup. The tripod would be a typical sturdy tripod that would be used to support a large PA speaker. The pole that would fit into the top of the tripod that the speaker tower, control box and solar panel would mount to should be $\frac{3}{4}$ " diameter and be 6-12 feet tall. The taller the pole the greater the distance the sound will travel.
- The effective range of the Mega Blaster Pro is 30 acres, in a circular coverage pattern around the 20-speaker tower with a radius of about 666 feet. The 20-speaker tower features 5 speakers pointing in each direction to create the even dispersal



This is the typical configuration EOG Resources is currently utilizing at the Southern Red Hills Water Recycling Facility and Containment Pit.





Variance Request for Fencing

Re: Chili Pepper Reuse Water Recycling Facility and Containment Pit

EOG Resources, Inc. would like to request the OCD's approval for a variance regarding fencing at the location described above. EOG proposes to utilize a 6 foot galvanized chain link fence with 3 strands of barb wire on the top of the chain link fencing. The 3 strands of barb wire will be mounted on a galvanized barb bracket with a 45 degree angle pointing towards the outside of the location. Each post hole will be drilled via auger to ensure a consistent and accurate depth and will be set in concrete. Six 18" x 18" swinging gates will be installed at ground level for temporary waterlines to pass through. The gates will remain closed as depicted in the pictures below to ensure no wildlife can access the containment site when no waterlines are present.

Please note that EOG Resources, Inc. is currently utilizing this same fence design, which was approved on OCD Permit No. 12

Please see details below.



This is the typical configuration EOG Resources is currently utilizing at the Southern Red Hills Water Recycling Facility and Containment Pit.





Chili Pepper Reuse Water Recycling Facility and Containment Pit

NMOCD Submittal – C147 Registration Application

January 16, 2018

Table of Contents

I.	Introduction	2
II.	C-147 Detail	2
	Operator and Facility / Location Detail	
	Recycling Facility Detail	
	Recycling Containment Detail	
	Bonding	
	Fencing	
	Signage	
	Variances	
	Siting Criteria for Recycling Containment	
	Recycling Facility and Containment Checklist	
III.	List of Attachments	6
	Attachments and Supporting Documents	

Introduction

EOG Resources respectfully requests registration of the herein described Reuse Water Recycling Facility and Containment Pit located in Lea County, New Mexico. The enclosed/attached information will demonstrate compliance with all rules as outlined in 19.15.34 NMAC.


C-147 Detail

Operator and Facility / Location Detail

The proposed reuse water containment facility & containment pit, referred to as the Chili Pepper Reuse Water Recycling Facility and Containment Pit, will be owned and operated by EOG Resources, Inc. (EOG) and located in Township 23 South, Range 35 East, and Section 17 in southwestern Lea County.

Recycling Facility Detail

The proposed containment pit will be located adjacent to the Chili Pepper Water Recycling Facility and will hold treated water for use in EOG hydraulic fracturing operations. As depicted in the attached schematic, the adjacent recycling facility will utilize advanced water treatment technologies to produce a clean brine effluent prior to storage and subsequent reuse. An oxidation and solids removal/filtering system will treat the incoming influent stream to internal standards sufficient for hydraulic fracturing reuse applications.



Recycling Containment Detail

EOG Resources is proposing to construct a multi-liner containment pit utilizing leak detection systems to ensure an intact leak free barrier system. As depicted in the attached design plan and schematics, *Chili_Pepper*, the proposed pit will incorporate standards that meet or exceed the required standards per 19.15.34.12 NMAC. The proposed recycle containment will be approximately 600 x 600 inside floor dimensions with 4:1 inside and outside berm grades. Approximate wall height will average 11ft from outside ground level to ensure no surface water run on will occur. The top of levee shall be approximately 20ft wide 2% outside sloping grade to ensure no surface water run on will occur. The containment pit floor and wall preparation will include laser finished grade free of rocks, debris and sharp edges, compacted to a density to ensure an unyielding base. At onset of pit construction, all vegetative material and top soil will be removed and stockpiled at the outside toe of the levee slopes. The interior liner system of the containment pit will

consist of a 10 ounce geotextile felt base layer to protect the secondary geomembrane liner from any protruding floor irregularities. The secondary geomembrane liner will be composed of 40 mil HDPE. Between the secondary and primary liners will consist of 200 mil geonet sloping to the leak detection trough. The primary liner consist of 60 mil HDPE liner. All liners will meet or exceed EPA SW-846 method 9090A. All seams will be oriented vertically with 4-6 inch liner overlap and all seam testing shall exceed all guidelines. As depicted in the attached design plan, *Chili_Pepper*, the proposed containment pit will include a center aligned leak detection trough and collection sump completed with perforated pipe and pump casing allowing for installation of a leak detection pump system. Both inlet and discharge manifold systems, depicted in *Chili_Pepper*, will be installed to prevent any liner damage from water entrance velocity or hose installation. Two audible bird deterrents will be utilized to deter any native birds and wildlife from the containment pit area.

Bonding

EOG Resources will source and distribute reuse water for the Chili Pepper Reuse Water Recycling Facility and Containment Pit from wells solely operated by EOG. Therefore, attached are the details of Bond Number SUR0013939 – Megabond #OGB0959 – State of New Mexico Land Office Oil and Gas Minerals Division

Fencing

Please see Variance detail.

Signage

As shown in the attached example sign, EOG shall place the appropriate signage along the water recycling facility and containment pit perimeter that meets all guidelines established in 19.15.34.12 C NMAC.

See List of Attachments

Variances

EOG Resources is seeking two variances as indicated in Section 7 of the C-147 registration form, to install two audible Mega Blaster Pro bird deterrents capable of covering up to 30 acres each. The second request is to enclose the perimeter with a 6 foot galvanized chain link fence with 3 strand 45 degree barbed wire arm toppers.

Siting Criteria for Recycling Containment

Enclosed within this submittal are comprehensive third party reports detailing conformity to siting criteria described in Section 8 of the C-147 registration form; a detailed list and description of these attachments can be found in the subsequent section: *List of Attachments*.

Recycling Facility and Containment Checklist

As indicated in Section 9 on the attached C-147 form, all the required attachments have been included on the submittal and certification of C-147 delivery to the landowner is acknowledged.

List of Attachments

Attachments and Supporting Documents

- Water Containment Design and Engineered Drawing
- Water Containment Liner / Leak Detection Detail
- Bond Detail
- Signage Sample



EOG RESOURCES CHILI PEPPER AREA CONTAINMENT POND PRELIMINARY PLAN LEA COUNTY, NEW MEXICO


INDEX	
SHEET 1	COVER PAGE
SHEET 2	OVERALL SITE LAYOUT
SHEET 3	OPTION I POND LAYOUT
SHEET 4	OPTION II POND LAYOUT
SHEET 5	OPTION I POND CALCULATIONS
SHEET 6	OPTION II POND CALCULATIONS
SHEET 7	POND CROSS SECTION PROFILES
SHEET 8	DETAILS 1 OF 3
SHEET 9	DETAILS 2 OF 3
SHEET 10	DETAILS 3 OF 3

GENERAL NOTES

1. COORDINATE INFORMATION ARE BASED ON STATE PLANES COORDINATE, NEW MEXICO EAST ZONE (4726), NAD 83. THE CONTRACTOR SHALL IDENTIFY ANY DISCREPANCIES PRIOR TO PROCEEDING WITH CONSTRUCTION.
2. THE CONTRACTOR SHALL IDENTIFY AND LOCATE UTILITY LINES, MONITORING WELLS, SURVEY MONUMENTS, AND OTHER NEARBY STRUCTURES PRIOR TO PERFORMING WORK. UTILITIES, MONITORING WELLS, SURVEY MONUMENTS AND OTHER NEARBY STRUCTURES SHALL BE PROTECTED FROM DAMAGE DURING THIS WORK. ANY DAMAGE TO UTILITY LINES, MONITORING WELLS, SURVEY MONUMENTS, AND OTHER NEARBY STRUCTURES DURING THE WORK SHALL BE REPAIRED BY THE CONTRACTOR AT NO ADDITIONAL COST TO THE OWNER. COSTS ASSOCIATED WITH THESE REPAIRS SHALL INCLUDE THE ACTUAL REPAIR COSTS AND ANY ENGINEER OR SURVEY COSTS NECESSARY TO COMPLETE THE REPAIR.



1400 EVERMAN PARKWAY, Ste. 146 • FT. WORTH, TEXAS 76140
TELEPHONE: (817) 744-7512 • FAX (817) 744-7548
WWW.TOPOGRAPHIC.COM



COVER SHEET


CHILI PEPPER AREA CONTAINMENT POND
FOR
EOG RESOURCES

DATE:	01/08/18
FILE:	CHILI_PEPPER
DRAWN BY:	ARG
REVIEWED BY:	CCC
SCALE:	N/A
SHEET :	1 OF 10

REVISION:



SCALE: 1" = 2000'
0' 1000' 2000'



SITE LOCATION EXHIBIT

CHILI PEPPER AREA CONTAINMENT POND
FOR
EOG RESOURCES



DATE:	01/08/18	REVISION:	
FILE:	CHILI_PEPPER		
DRAWN BY:	ARG		
REVIEWED BY:	CCC		
SCALE:	1"=2000'		
SHEET :	2 OF 10		



SCALE: 1" = 120'
 0' 60' 120'

LEGEND:



- EXISTING 10' CONTOUR
- EXISTING 2' CONTOUR
- PROPOSED 10' CONTOUR
- PROPOSED 5' CONTOUR



OPTION #1

CHILI PEPPER AREA CONTAINMENT POND
 FOR
EOG RESOURCES

DATE:	01/08/18
FILE:	CHILI_PEPPER
DRAWN BY:	ARG
REVIEWED BY:	CCC
SCALE:	1"=120'
SHEET :	3 OF 10
REVISION:	



- LEGEND:**
- - - - - EXISTING 10' CONTOUR
 - - - - - EXISTING 2' CONTOUR
 - PROPOSED 10' CONTOUR
 - PROPOSED 2' CONTOUR

EARTHWORK QUANTITIES

CUT VOLUME:	111,909 YD ³
FILL VOLUME:	97,863 YD ³
TOPSOIL (6" STOCKPILED):	13,456 YD ³
TOTAL EXPORT (IMPORT):	590 YD ³
TOTAL GRADING AREA:	16.68 ACRES

POND SUMMARY

MAX VOLUME:	1,494,916 BBLs
MAX AREA:	12.02 ACRES
MAX ELEVATION OF POND:	3,375.75 FT
2' FREEBOARD ELEVATION:	3,373.75 FT
VOLUME AT FREEBOARD:	1,314,731 BBLs

*VOLUMES ASSUME A FILL FACTOR OF 1.20



STAGE STORAGE				
ELEV	AREA (ACRES)	VOLUME (BBLs)	VOLUME (ACRE FT)	VOLUME (CY)
3347.70	0.00	0.00	0.00	0.00
3348.00	0.03	48.74	0.01	10.13
3348.50	0.04	168.61	0.02	35.06
3349.00	0.05	335.50	0.04	69.77
3349.50	0.06	547.05	0.07	113.76
3350.00	0.07	805.23	0.10	167.45
3350.50	0.09	1118.14	0.14	232.51
3351.00	0.11	1498.03	0.19	311.51
3351.50	0.16	1960.93	0.25	407.77
3352.00	0.26	2573.84	0.33	535.22
3352.50	0.50	3883.74	0.50	807.62
3353.00	0.81	6244.48	0.80	1298.52
3353.50	1.20	9951.16	1.28	2069.32
3354.00	1.69	15336.68	1.98	3189.23
3354.50	2.31	22985.33	2.96	4779.75
3355.00	2.91	32943.11	4.25	6850.45
3355.50	3.56	45313.83	5.84	9422.91
3356.00	4.25	60309.54	7.77	12541.23
3356.50	4.89	77895.59	10.04	16198.21
3357.00	5.50	97881.61	12.62	20354.26
3357.50	6.11	120233.54	15.50	25002.30
3358.00	6.74	144966.84	18.69	30145.53
3358.50	7.26	172018.83	22.17	35770.93
3359.00	7.68	200886.13	25.89	41773.82
3359.50	7.99	231132.36	29.79	48063.46
3360.00	8.18	262346.59	33.81	54554.39
3360.50	8.31	294158.86	37.92	61169.68
3361.00	8.44	326476.88	42.08	67890.14
3361.50	8.57	359305.84	46.31	74716.85
3362.00	8.69	392617.28	50.61	81643.89
3362.50	8.83	426378.00	54.96	88664.35
3363.00	8.96	460596.76	59.37	95780.07
3363.50	9.08	495268.24	63.84	102989.92
3364.00	9.20	530389.78	68.36	110293.37
3364.50	9.32	565966.02	72.95	117691.37
3365.00	9.44	601997.29	77.59	125183.99
3365.50	9.55	638486.81	82.30	132771.90
3366.00	9.67	675436.08	87.06	140455.42
3366.50	9.84	712864.18	91.88	148238.51
3367.00	9.97	750780.25	96.77	156123.07
3367.50	10.08	789163.44	101.72	164104.77
3368.00	10.22	828015.01	106.73	172183.87
3368.50	10.38	867379.45	111.80	180369.62
3369.00	10.51	907232.30	116.94	188656.93
3369.50	10.67	947598.91	122.14	197051.07
3370.00	10.83	988476.86	127.41	205551.55
3370.50	11.02	1029905.52	132.75	214166.55
3371.00	11.20	1071926.45	138.16	222904.71
3371.50	11.41	1114593.87	143.66	231777.30
3372.00	11.70	1158069.64	149.27	240817.99
3372.50	11.91	1202568.75	155.00	250071.48
3373.00	11.94	1247345.34	160.77	259382.67
3373.50	11.98	1292235.71	166.56	268717.53
3373.75	12.00	1314730.66	169.46	273395.30
3374.00	12.01	1337225.61	172.36	278073.07
3374.50	12.02	1382261.31	178.16	287438.15
3375.00	12.02	1427321.55	183.97	296808.32
3375.50	12.02	1472384.82	189.78	306179.13
3375.75	12.02	1494916.46	192.68	310864.53

SUB-GRADE VOLUME
530,389.78 BBLs - 68.36 AC-FT
SHOWN GRAPHICALLY LEFT

BREACH VOLUME
964,526.68 BBLs - 124.32 AC-FT
SHOWN GRAPHICALLY LEFT

2 FT FREEBOARD


STAGE STORAGE/GRADING CALCULATIONS

**OPTION #1 CONTAINMENT POND
FOR
EOG RESOURCES**

REVISION:

DATE:	01/08/18
FILE:	CHILI_PEPPER
DRAWN BY:	ARG
REVIEWED BY:	CCC
SCALE:	1"=200'
SHEET :	5 OF 10





SCALE: 1" = 200'
0' 100' 200'

LEGEND:

- EXISTING 10' CONTOUR
- EXISTING 2' CONTOUR
- PROPOSED 10' CONTOUR
- PROPOSED 2' CONTOUR

EARTHWORK QUANTITIES

CUT VOLUME: 113,388 YD³
 FILL VOLUME: 99,663 YD³
 TOPSOIL (6" STOCKPILED): 13,576 YD³
 TOTAL EXPORT (IMPORT): 148 YD³
 TOTAL GRADING AREA: 16.83 ACRES

*VOLUMES ASSUME A FILL FACTOR OF 1.20

POND SUMMARY


MAX VOLUME: 1,494,462 BBLs
 MAX AREA: 12.02 ACRES
 MAX ELEVATION OF POND: 3,375.65 FT
 2' FREEBOARD ELEVATION: 3,373.65 FT
 VOLUME AT FREEBOARD: 1,314,273 BBLs

STAGE STORAGE				
ELEV	AREA (ACRES)	VOLUME (BBLs)	VOLUME (ACRE FT)	VOLUME (CY)
3347.60	0.00	0.00	0.00	0.00
3348.00	0.03	69.26	0.01	14.40
3348.50	0.04	197.89	0.03	41.15
3349.00	0.05	374.06	0.05	77.78
3349.50	0.06	594.04	0.08	123.53
3350.00	0.08	861.69	0.11	179.19
3350.50	0.09	1186.86	0.15	246.80
3351.00	0.13	1582.32	0.20	329.04
3351.50	0.17	2065.55	0.27	429.53
3352.00	0.30	2753.74	0.35	572.63
3352.50	0.56	4244.91	0.55	882.72
3353.00	0.88	6836.94	0.88	1421.73
3353.50	1.28	10836.12	1.40	2253.35
3354.00	1.79	16572.39	2.14	3446.19
3354.50	2.43	24679.60	3.18	5132.07
3355.00	3.04	35122.81	4.53	7303.71
3355.50	3.68	47983.73	6.18	9978.11
3356.00	4.37	63474.08	8.18	13199.29
3356.50	5.01	81539.98	10.51	16956.06
3357.00	5.62	102011.06	13.15	21212.97
3357.50	6.23	124850.67	16.09	25962.42
3358.00	6.87	150075.24	19.34	31207.81
3358.50	7.34	177483.81	22.88	36907.36
3359.00	7.73	206569.81	26.63	42955.73
3359.50	8.01	236945.52	30.54	49272.29
3360.00	8.20	268241.35	34.57	55780.19
3360.50	8.34	300134.20	38.69	62412.23
3361.00	8.47	332542.77	42.86	69151.53
3361.50	8.60	365467.56	47.11	75998.16
3362.00	8.71	398861.88	51.41	82942.44
3362.50	8.86	432711.95	55.77	89981.48
3363.00	8.99	467021.20	60.20	97116.01
3363.50	9.11	501777.65	64.68	104343.54
3364.00	9.22	536987.52	69.21	111665.35
3364.50	9.34	572651.86	73.81	119081.67
3365.00	9.46	608770.55	78.47	126592.47
3365.50	9.58	645347.02	83.18	134198.47
3366.00	9.72	682387.96	87.96	141901.05
3366.50	9.86	719917.34	92.79	149705.20
3367.00	9.98	757922.25	97.69	157608.24
3367.50	10.11	796394.14	102.65	165608.38
3368.00	10.27	835347.77	107.67	173708.70
3368.50	10.40	874813.09	112.76	181915.43
3369.00	10.53	914753.42	117.91	190220.93
3369.50	10.70	955228.54	123.12	198637.64
3370.00	10.88	996226.65	128.41	207163.10
3370.50	11.04	1037773.35	133.76	215802.65
3371.00	11.22	1079911.55	139.19	224565.19
3371.50	11.49	1122738.20	144.71	233470.90
3372.00	11.79	1166439.26	150.35	242558.44
3372.50	11.92	1211063.60	156.10	251837.97
3373.00	11.95	1255861.03	161.87	261153.49
3373.50	11.99	1300772.30	167.66	270492.69
3373.65	11.99	1314273.15	169.40	273300.16
3374.00	12.01	1345775.12	173.46	279850.93
3374.50	12.02	1390817.28	179.27	289217.34
3375.00	12.02	1435879.56	185.08	298587.94
3375.50	12.02	1480942.83	190.88	307958.75
3375.65	12.02	1494461.82	192.63	310769.99

SUB-GRADE VOLUME
536,987.52 BBLs - 69.21 AC-FT
SHOWN GRAPHICALLY LEFT

BREACH VOLUME
967,474.30 BBLs - 123.42 AC-FT
SHOWN GRAPHICALLY LEFT

2 FT FREEBOARD




STAGE STORAGE/GRADING CALCULATIONS

**OPTION #2 CONTAINMENT POND
FOR
EOG RESOURCES**


REVISION:

DATE: 01/08/18
 FILE: CHILI_PEPPER
 DRAWN BY: ARG
 REVIEWED BY: CCC
 SCALE: 1"=200'
 SHEET: 6 OF 10


OPTION #1 SECTION A-A





OPTION #2 SECTION A-A



OPTION #1 SECTION B-B



OPTION #2 SECTION B-B



HORIZONTAL SCALE

VERTICAL SCALE




PROPOSED CROSS SECTIONS


CHILI PEPPER AREA CONTAINMENT POND
FOR
EOG RESOURCES

DATE:	01/08/18
FILE:	CHILI_PEPPER
DRAWN BY:	ARG
REVIEWED BY:	CCC
SCALE:	1"=100'
SHEET :	7 OF 10

REVISION:




1 TYPICAL BERM SECTION
NTS




2 SUCTION PIPE SECTION
NTS



NOTES:
-ALL MATERIALS EXCEPT WHEELS 10 GA 304 S/S
-FLANGE 1/4" 304 S/S WELDED CONSTRUCTION 3/4" #9 304 S/S
-EXPANDED METAL COVER WELDED TO TOP




3 SUCTION FUNNEL
NTS



NOTES:
1. AMOUNT OF LAYERS WILL VARY BY POND TYPE AND WHERE A RUB SHEET IS UTILIZED.


4 TYPICAL ANCHOR TRENCH
NTS



5 BRINE WATER LINER SYSTEM
NTS

REVISION:

DATE:	01/08/18
FILE:	CHILI_PEPPER
DRAWN BY:	ARG
REVIEWED BY:	CCC
SCALE:	N/A
SHEET :	8 OF 10



BRINE WATER SECTION

FRESH WATER SECTION

6 LEAK DETECTION SUMP
NTS




DETAILS 2 OF 3

CHILI PEPPER AREA CONTAINMENT POND
FOR
EOG RESOURCES

REVISION:

DATE:	01/08/18
FILE:	CHILI_PEPPER
DRAWN BY:	ARG
REVIEWED BY:	CCC
SCALE:	N/A
SHEET:	9 OF 10



7 POND FILL APPARATUS
NTS



- (1) Acceptance of pit construction for liner install:
 - a. Pit foundation and laterals properly compacted, smooth, and free of rocks/debris/sharp edges
 - b. Pit top wide enough to install an anchor trench, and provide adequate room for inspection/maintenance
 - c. Slope of interior subgrade, drainage lines and laterals per specs
- (2) Geomembrane Liner Layers
 - a. Geotextile
 - b. Secondary (lower) liner
 - c. Leak detection system
 - d. Primary (upper) liner
 - e. Anchor trench- Liner edges anchored in the bottom of a compacted earth-filled trench **>18"deep**
- (3) Geomembrane Properties
 - a. Primary: 60 mil HDPE, equivalent, or better
 - b. Secondary: 40 mil HDPE, equivalent, or better
 - c. Impervious, synthetic material resistant to UV, petroleum hydrocarbons, salts, and acidic and alkaline solutions
 - d. Comply with EPA SW-846 Method 9090A, or subsequent relevant publication
- (4) Geomembrane Install
 - a. Field- Welded Liner seams
 - i. Performed by Qualified Personnel
 - ii. Thermally seamed (hot wedge) with a double track weld to create air pocket
 - iii. **4-6" liner overlap**
 - iv. Number of seams minimized
 - v. Seams oriented seams up and down slopes
 - vi. **No horizontal seams <5' of the slope toe**
 - b. Geomembrane Testing
 - i. Performed by Qualified Personnel
 - ii. Non-destructive Air Channel Testing
 - iii. Destruct testing
 - iv. Vacuum Testing
 - v. Spark Testing

PO Box 1806
Aledo, TX 76008
P: (817) 441-1235
F: (817) 441-1270
www.mustangenergyservices.com

- (5) Other installed items
 - i. Vents
 - ii. Rub Sheets
 - iii. Boots
 - iv. Sump aggregate
 - v. Solid/perforated pipes
 - vi. Escape Ladders
 - vii. Height Markers
 - viii. Conductive Liner
- (6) Leak Detection System
 - a. 200 mil or greater Geonet or Geocomposite drainage liner
 - b. Installed between upper/lower geomembrane liners
 - c. Piping collection system
 - d. Drainage, collection, and removal system sloped to facilitate the earliest possible leak detection
 - e. Pipe to convey collected fluids to a collection/disposal system located outside the permanent **pit's perimeter**

PO Box 1806
Aledo, TX 76008
P: (817) 441-1235
F: (817)4411270
www.mustangenergyservices.com



RIDER

To be attached to and form part of Bond No. SUR0013939.

Issued on behalf of EOG Resources, Inc as Principal, and in favor of Commissioner of Public Lands, New Mexico State Land Office as Obligee.

It is agreed that:

Bond is changed to include the following EOG Subsidiaries under State Land Bond No. OGB0959:

EOG Resources & Meridian Oil, EOG Resources & Mitchell Energy, EOG Resources & Murchison O&G, EOG Resources & Nortex G&O Co., EOG Resources & Read & Stevens, EOG Resources Marketing, Inc., EOG Resources Inc, Enron Oil and Gas Co., Enron Oil & Gas, EOG Resources & Internorth Inc, EOG Resources & Meridian Oil, EOG Resources & Sun Operating, Enron Oil & Gas Company, & EOG Resources

This rider shall become effective as of February 13, 2012

PROVIDED, however, that the liability of the Surety under the attached bond as changed by this Rider shall not be cumulative.

Signed, sealed and dated February 13, 2012.

By: Argonaut Insurance Company

Gina Rodriguez
Attorney-in-Fact Gina Rodriguez

Accepted: Commissioner of Public Lands, New Mexico State Land Office

Obligee

EOG Resources, Inc

Principal

By: _____

By: Helen Y. Lim
Helen Y. Lim, VP & Treasurer

Argonaut Insurance Company
225 W. Washington, 6th Floor
Chicago, IL 60606

AS-0026046

POWER OF ATTORNEY

KNOW ALL MEN BY THESE PRESENTS: That the Argonaut Insurance Company, a Corporation duly organized and existing under the laws of the State of Illinois and having its principal office in the County of Cook, Illinois does hereby nominate, constitute and appoint:

Donald R. Gibson, Sandra Parker, Tannis Mattson, Melissa Haddick, Terri Morrison, Gina Rodriguez

its true and lawful agent and attorney-in-fact, to make, execute, seal and deliver for and on its behalf as surety, and as its act and deed any and all bonds, contracts, agreements of indemnity and other undertakings in suretyship provided, however, that the penal sum of any one such instrument executed hereunder shall not exceed the sum of:


\$15,000,000.00

This Power of Attorney is granted and is signed and sealed under and by the authority of the following Resolution adopted by the Board of Directors of Argonaut Insurance Company:

"RESOLVED, That the President, Senior Vice President, Vice President, Assistant Vice President, Secretary, Treasurer and each of them hereby is authorized to execute powers of attorney, and such authority can be executed by use of facsimile signature, which may be attested or acknowledged by any officer or attorney, of the Company, qualifying the attorney or attorneys named in the given power of attorney, to execute in behalf of, and acknowledge as the act and deed of the Argonaut Insurance Company, all bond undertakings and contracts of suretyship, and to affix the corporate seal thereto."

IN WITNESS WHEREOF, Argonaut Insurance Company has caused its official seal to be hereunto affixed and these presents to be signed by its duly authorized officer on the 15th day of September, 2008.

Argonaut Insurance Company





By: _____

Michael E. Arledge President

STATE OF TEXAS
COUNTY OF BEXAR SS:

On this 15th day of September, 2008 A.D., before me, a Notary Public of the State of Texas, in and for the County of Bexar, duly commissioned and qualified, came THE ABOVE OFFICER OF THE COMPANY, to me personally known to be the individual and officer described in, and who executed the preceding instrument, and he acknowledged the execution of same, and being by me duly sworn, deposed and said that he is the officer of the said Company aforesaid, and that the seal affixed to the preceding instrument is the Corporate Seal of said Company, and the said Corporate Seal and his signature as officer were duly affixed and subscribed to the said instrument by the authority and direction of the said corporation, and that Resolution adopted by the Board of Directors of said Company, referred to in the preceding instrument is now in force.


IN TESTIMONY WHEREOF, I have hereunto set my hand, and affixed my Official Seal at the County of Bexar, the day and year first above written.



(Notary Public)

I, the undersigned Officer of the Argonaut Insurance Company, Illinois Corporation, do hereby certify that the original POWER OF ATTORNEY of which the foregoing is a full, true and correct copy is still in full force and effect and has not been revoked.

IN WITNESS WHEREOF, I have hereunto set my hand, and affixed the Seal of said Company, on the 13th day of February 2012



Robert F. Thomas Vice President

ONLINE Version

NEW MEXICO STATE LAND OFFICE – Oil, Gas, and Minerals Division
BOND FOR CONTRACT PERFORMANCE AND SURFACE OR IMPROVEMENT DAMAGE
Surface Improvement Damage Megabond

BOND NO. SUR0013000

(For use of Surety Company)

BOND NO. _____

(For use of State Land Office)

Know all men by these presents

EOG Resources, Inc., P.O. Box 4362, Houston, TX 77210-4362

, as **Principal**,

and Argonaut Insurance Company, as **Surety**, a corporation organized,

existing and doing business under and by virtue of the laws of the State of Illinois and

authorized to transact a surety business in the State of New Mexico, are held and firmly bound unto the New Mexico Commissioner of Public Lands in the sum of **Twenty-five Thousand Dollars (\$25,000)** for the following uses:

1. For the use and benefit of the Commissioner, to secure the performance of said Principal as lessee under one or more state leases or permits for minerals, oil and gas, coal or geothermal resources or as holder under one or more state rights-of-way or easements which Principal has heretofore executed or may hereafter execute with the Commissioner; and

2. For the use and benefit of the Commissioner, state surface lessees, state land contract purchasers, state patentees, and their successors and assigns, to pay for damages to the surface of lands subject to a state lease or permit for minerals, oil and gas, coal or geothermal resources or a state right-of-way or easement held by Principal, or for damages to surface improvements located thereon, suffered by reason of Principal's operations under a state lease or permit for minerals, oil and gas, coal or geothermal resources or under a state right-of-way or easement.

For the payment of said sum, well and truly to be made, Principal and Surety bind themselves, their heirs, executors, administrators, successors and assigns, jointly and severally.

The conditions of the foregoing obligations are:

1. If the above bound Principal or its successors or assigns shall well and truly perform and keep all terms, covenants, conditions, and requirements of all state leases for minerals, oil and gas, coal or geothermal resources and of all state rights-of-way and easements heretofore or hereafter executed by the Commissioner and Principal, including the payment of royalties when due and compliance with all established mining plans; and

2. If Principal or its successors or assigns shall in all respects make good and sufficient recompense, satisfaction or payment to the Commissioner of Public Lands for damages to the surface of lands subject to a state lease or permit for minerals, oil and gas, coal or geothermal resources or a state right-of-way or easement held by Principal and for damages to livestock, water, crops, tangible improvements or surface improvements of any kind located thereon suffered by reason of Principal's operations under such state lease, permit, right-of-way or easement heretofore or hereafter executed by the Commissioner and Principal;

THEN, the obligation to pay the sum of Twenty-five Thousand Dollars (\$25,000) shall be null and void.

If, however, Principal shall default or otherwise fail in performance under such state lease, permit, right-of-way or easement, including the failure to pay royalties when due or to comply with established mining plans, or if Principal shall fail or refuse to make good and sufficient recompense, satisfaction or payment to the Commissioner for damages to the surface of the above designated lands or to improvements located thereon, then the obligation to pay said sum shall remain in full force and effect.

The liability of Surety upon this bond shall not expire upon the termination of any state lease or permit or any

renewal or extension thereof for minerals, oil and gas, coal or geothermal resources or any state right-of-way or easement or any renewal or extension thereof which Principal or its successors or assigns has heretofore executed or may hereafter execute with the Commissioner, but shall be and remain in full force and effect until released in writing by the Commissioner of Public Lands.

Principal and Surety further agree that in the event an action is brought on this bond and a court of competent jurisdiction determines Principal or Surety is in breach of the agreements contained in this bond, Principal or Surety or both of them shall pay to the Commissioner the costs associated with the recovery of the amounts due hereunder, including reasonable attorneys' fees.

This bond is executed pursuant to the laws of the State of New Mexico, including Sections 19-8-24, 19-9-12, 19-10-26, 19-13-19, and 46-6-1 through -9, NMSA 1978.

The premium for which this bond is written is One Hundred Thirteen and No/100----- Dollars.

In witness whereof we hereunto set our hands this 30th day of January, 20 12.

EOG Resources, Inc.
PRINCIPAL
P.O. Box 4362, Houston, TX 77210-4362 **BB**
Address
BY [Signature]
Signature Helen Y. Lim, VP & Treasurer

Title
(Note: Principal, if corporation, affix
Corporate seal here.)

Argonaut Insurance Company
SURETY
225 W. Washington, 6th Floor, Chicago, IL 60606
Address
BY [Signature]
Attorney-in-Fact Signature
Gina Rodriguez

(Note: Corporate surety, affix
Corporate seal here.)

ACKNOWLEDGMENT FORM FOR NATURAL PERSONS

STATE OF _____)
) ss.
COUNTY OF _____)

On this _____ day of _____, 20____,
before me personally appeared _____, to me known to
be the person(s) described in and who executed the same as (his, her, their) free act and deed.

IN WITNESS WHEREOF, I have hereunto set my hand and seal on the day and year in this certificate first above written.

My commission expires Notary Public name Signature, notary


(Notary Seal)

ACKNOWLEDGMENT FORM FOR CORPORATION

STATE OF TEXAS)
COUNTY OF HARRIS) ss.

On this 19th day of January, 20 12, before me personally appeared Helen Y. Lim, to me personally known, who, being by me duly sworn, did say that s/ he is VP & Treasurer of EOG Resources, Inc. and that this instrument was signed and sealed on behalf of said corporation by authority of its board of directors, and acknowledged said instrument to be the free act and deed of said corporation.

IN WITNESS WHEREOF, I have hereunto set my hand and seal on the day and year in this certificate first above written. April 3, 2014 My commission expires Mary J. Grisaffi Notary Public name Signature notary (Notary Seal)




ACKNOWLEDGMENT FORM FOR CORPORATE SURETY

STATE OF TEXAS)
COUNTY OF Harris) ss.

On this 30th day of January, 20 12, before me personally appeared Gina Rodriguez, to me personally known, who, being by me duly sworn, did say that s/ he is Attorney-in-Fact of Argonaut Insurance Company and that this instrument was signed and sealed on behalf of said corporation by authority of its board of directors, and acknowledged said instrument to be the free act and deed of said corporation.

IN WITNESS WHEREOF, I have hereunto set my hand and seal on the day and year in this certificate first above written. 11-30-2014 My commission expires Elizabeth Rhodes Notary Public name Signature, notary (Notary Seal)



Note: Corporate surety, attach power of attorney.

APPROVED this day of , 20

COMMISSIONER OF PUBLIC LANDS

NOTE: File before development or operations are commenced, with: Commissioner of Public Lands New Mexico State Land Office, OGMD P.O. Box 1148 or 310 Old Santa Fe Trail Santa Fe, New Mexico 87504-1148 Santa Fe, NM 87501-2708

**Argonaut Insurance Company
225 W. Washington, 6th Floor
Chicago, IL 60606**

AS-0026041

POWER OF ATTORNEY

KNOW ALL MEN BY THESE PRESENTS: That the Argonaut Insurance Company, a Corporation duly organized and existing under the laws of the State of Illinois and having its principal office in the County of Cook, Illinois does hereby nominate, constitute and appoint:

Donald R. Gibson, Sandra Parker, Tannis Mattson, Melissa Haddick, Terri Morrison, Gina Rodriguez

its true and lawful agent and attorney-in-fact, to make, execute, seal and deliver for and on its behalf as surety, and as its act and deed any and all bonds, contracts, agreements of indemnity and other undertakings in suretyship provided, however, that the penal sum of any one such instrument executed hereunder shall not exceed the sum of:


\$15,000,000.00

This Power of Attorney is granted and is signed and sealed under and by the authority of the following Resolution adopted by the Board of Directors of Argonaut Insurance Company:

"RESOLVED, That the President, Senior Vice President, Vice President, Assistant Vice President, Secretary, Treasurer and each of them hereby is authorized to execute powers of attorney, and such authority can be executed by use of facsimile signature, which may be attested or acknowledged by any officer or attorney, of the Company, qualifying the attorney or attorneys named in the given power of attorney, to execute in behalf of, and acknowledge as the act and deed of the Argonaut Insurance Company, all bond undertakings and contracts of suretyship, and to affix the corporate seal thereto."

IN WITNESS WHEREOF, Argonaut Insurance Company has caused its official seal to be hereunto affixed and these presents to be signed by its duly authorized officer on the 15th day of September, 2008.

Argonaut Insurance Company





By: _____

Michael E. Arledge President

STATE OF TEXAS
COUNTY OF BEXAR SS:

On this 15th day of September, 2008 A.D., before me, a Notary Public of the State of Texas, in and for the County of Bexar, duly commissioned and qualified, came THE ABOVE OFFICER OF THE COMPANY, to me personally known to be the individual and officer described in, and who executed the preceding instrument, and he acknowledged the execution of same, and being by me duly sworn, deposed and said that he is the officer of the said Company aforesaid, and that the seal affixed to the preceding instrument is the Corporate Seal of said Company, and the said Corporate Seal and his signature as officer were duly affixed and subscribed to the said instrument by the authority and direction of the said corporation, and that Resolution adopted by the Board of Directors of said Company, referred to in the preceding instrument is now in force.


IN TESTIMONY WHEREOF, I have hereunto set my hand, and affixed my Official Seal at the County of Bexar, the day and year first above written.



(Notary Public)

I, the undersigned Officer of the Argonaut Insurance Company, Illinois Corporation, do hereby certify that the original POWER OF ATTORNEY of which the foregoing is a full, true and correct copy is still in full force and effect and has not been revoked.

IN WITNESS WHEREOF, I have hereunto set my hand, and affixed the Seal of said Company, on the 30th day of January 2012



Robert F. Thomas Vice President



EOG Resources, Inc.
1111 Bagby
Sky Lobby 2
Houston, Texas 77002

Date: 1-12-2012

P.O. Box 4362
Houston, Texas 77210-4362

Requestor: Roger Motley **Division:** Midland
Telephone: 432-686-3642 **Fax:** 432-686-3733

Principal (Name & Address of EOG Entity, if other than EOG Resources, Inc.):
EOG Resources, Inc.
P.O. Box 4362
Houston, TX 77210 4362

Obligee (Name & Physical Address of Party requiring bond) **Phone:**
Commissioner of Public Lands
New Mexico State Land Office – Right of Way Division
310 Old Santa Fe Trail
Santa Fe, New Mexico
Effective Date of Bond: 1-30-2012 **Date Bond Required:** 1-20-2012
Amount of Bond: \$25,000
Bond Type:
Performance _____
License/Permit _____
Road Crossing _____
Right of Way _____
Oil & Gas Drilling _____
Plugging & Surface Restoration _____
Other: Surface Improvement Damage Megabond
(If court bond, please provide a copy of judgment and bond form)

Bond Description: (Road, mileage, Well #, Location, County, etc)
This Megabond will cover all operations by EOG Resources, Inc. on our State of New Mexico leases.

Other Comments/Information:

Deliver completed Bonds by Fed Ex To:
Requestor Roger Motley, Midland Division Land Dept.
Obligee Nick Jaramillo, New Mexico State Land Office – Right of Way Division
310 Old Santa Fe Trail
Santa Fe, New Mexico 78501-2708



CHILI PEPPER REUSE WATER PIT
NENW4/ NWNW4 SEC. 17 – T23S – R35E
LEA COUNTY, NM
EMERGENCY CONTACT:
575-392-3647

CAUTION

DANGER

**PPE
REQUIRED**

**H₂S
MAY BE PRESENT**

DANGER

NOTICE

**NO
SMOKING**

**AUTHORIZED
PERSONNEL ONLY**



Operating and Maintenance Plan

CHILI PEPPER REUSE WATER CONTAINMENT PIT

1. Overview

The attached plan details the operational requirements regarding the Chili Pepper Reuse Water Containment Pit. In addition, the required reporting and inspections as well as the appropriate actions/notifications are listed.

2. Purpose

The attached plan implements the operational requirement as outlined by NMOCD under 19.15.34 NMAC. Application of this plan will ensure the reuse water containment pit is operated in a manner that minimizes any risk to health, safety, and environment.

3. Operational Requirements

Below are the operational requirements that must be adhered to at all times. Deviation from these requirements is prohibited.

- Inlet flow
 - Recycling facility effluent stream water must meet all water quality norms before water is introduced into the containment pit. These norms are to include no detected oil in the stream.
 - Inlet water may only be introduced into the containment pit via the diffuser manifold as to not cause any stress or damage to the liner system.
 - A minimum of 3ft of freeboard will be maintained in the reuse water containment pit at all times.

- Effluent Flow
 - Effluent water may only exit the reuse water containment via the permanent discharge header system; no external hoses or pipes may be placed into the pit at any time
 - Effluent water may only be transferred to EOG Resources' completion operations; no transfer to 3rd parties is allowed
 - Effluent water may only be transferred through an EOG leak detection transfer system; all protocols and procedures regarding the automated leak detection system must be followed

- Volume Reporting
 - All influent and effluent volumes are to be logged daily. These volumes are to be tracked via inbound and outbound mag meters and tracked via paper and SCADA systems



- Site Inspection
 - The pit and surrounding area are to be inspected daily while water is contained within the pit. These inspections are to include all inlet/outlet piping, berms, exposed liner, surrounding grounds and fencing

- Leak Detection Testing
 - Leak detection testing shall be conducted daily. Testing shall include starting the leak detection sump pump to determine if any is fluid has collected in the collection sump. The sump pump shall be run for a minimum of 5 minutes to allow for inlet flow. If any flow is detected the proper notification to the Hobbs NMOCD will occur and drainage will commence

4. Daily Reporting & Inspections

- List of Daily Reporting and Inspections to be completed:
 - Influent and Effluent Volume Reporting
 - Site and Containment Pit Inspection
 - Leak Detection

5. Notifications

In the event of a leak detection denoting a compromised liner below the water level, notice shall be provided to be the Hobbs division office of the NMCOD within 48 hours of detection.

District 1

1625 N. French Drive
Hobbs, New Mexico 88240

OFFICE: (575) 393-6161 FAX: (575) 393-0720
EMERGENCY NUMBER - MOBILE: (575) 370-3186

Business Hours:
7:00 AM-12:00 PM and 1:00 - 4:00 PM
Monday through Friday

6. Associated Forms

- List of Associated forms for Operating and Maintenance Plan
 - NA



Water Containment Closure Plan

CHILI PEPPER REUSE WATER CONTAINMENT PIT

1. Overview

The attached plan details the requirements regarding the closure of the Chili Pepper Reuse Water Containment Pit. In addition, the required sampling and reporting obligations are detailed.

2. Purpose

The attached plan implements the closure requirement as outlined by NMOCD under 19.15.34.14 NMAC. Application of this plan will ensure the reuse water containment pit is closed and reclamation is completed in a manner that minimizes any risk to health, safety, and environment.

3. Closure Requirements

- Containment Pit Drainage
 - All reuse water remaining in the containment pit shall be removed from the impoundment within 60 days operations cessation. The removed fluids will then be transferred a division approved disposal facility. Records of all removal, transfer and disposal activities shall be retained for inclusion in the final closure report submittal.
- Liner Material Removal and Disposal
 - Removal of the liner shall be conducted in manner that minimizes any risk of soil disturbance to the surface within and surrounding the containment. The removed liner material will then be transferred to and disposed of at a division approved disposal facility. Records of all removal, transfer and disposal activities shall be retained for inclusion in the final closure report submittal.
- Soil Sampling
 - Soil sampling shall be conducted at the locations depicted in the below schematic, Sampling Point Diagram, by a qualified third party contractor and analyzed at NELAC certified laboratory.
 - If any contaminant concentration is higher than the parameters listed in Table 1 in 19.15.34.14 NMAC, notice shall be provided the Hobbs NMOCD office before proceeding with closure.
 - If all sample concentrations are less than or equal to the parameters listed in Table 1 in 19.15.34.14 NMAC, then closure can proceed, backfilling with non-waste containing, uncontaminated, earthen material

- Sampling Diagram



- Site Reclamation and Re-vegetation
 - Following closure, reclamation of the containment's location can commence and ensure that it is returned to a safe and stable location that blends with the surrounding undisturbed area. Topsoils and subsoils shall be replaced to original positions and contoured to achieve erosion free long term stability and preservation of surface water flow patterns.
 - The disturbed area shall then be reseeded in the first favorable growing season following closure of the containment. The surface area shall be restored to the condition that existed prior to the construction of the containment
 - Reclamation of all disturbed areas no longer in use shall be considered complete when all ground surface disturbing activities at the site have been completed and a uniform vegetative cover has been established that reflects a life form ration of +/- 50% of pre-disturbance levels and a total percent plant cover of at least 70% of pre-disturbance levels, excluding noxious weeds.



4. Closure and Reclamation Report Submittal / Notice

- Closure Report
 - Within 60 days of closure completion, EOG shall submit a closure report on form C-147 to the NMOCD Hobbs office, including required attachments, to document all closure activities including sampling results and the details of any backfilling, capping or covering.
 - The closure report shall certify that all information in the report and attachments is correct and that EOG has complied with all applicable closure requirements and conditions specified in the division rules or directives
- Reclamation Notice
 - EOG shall notify the NMOCD Hobbs office when all reclamation and re-vegetation are complete

5. Notifications

In the event of any deviance from this closure plan or exceeding of a sampling constituent, notice shall be provided to the NMOC Hobbs office.

District 1

1625 N. French Drive
Hobbs, New Mexico 88240

OFFICE: (575) 393-6161 FAX: (575) 393-0720
EMERGENCY NUMBER - MOBILE: (575) 370-3186

Business Hours:
7:00 AM-12:00 PM and 1:00 - 4:00 PM
Monday through Friday


6. Associated Forms

- List of Associated forms for containment pit closure
 - NA

SOIL BORING / MONITORING WELL LOG

PROJECT: Jal, NM - Pit Sites
 PROJECT NUMBER: 700438.209.02
 CLIENT: EOG Resources
 BORING / WELL NUMBER: ChiliPepper
 TOTAL DEPTH: 75
 SURFACE ELEVATION: _____
 GEOLOGIST: Patrick Tucker
 LATITUDE: _____

DRILLING COMPANY: Talon/LPE
 DRILLER: Ronnie Rodriguez
 DRILLING METHOD: Hollow Stem Auger/Continuous Core
 BORE HOLE DIAMETER: 6"
 SCREEN: Diam. _____ Length _____ Slot Size _____
 CASING: Diam. _____ Length _____ Type _____
 DATE DRILLED: 1/10/2018
 LONGITUDE: _____

DEPTH (FT.)	Soil Symbol	WELL CONSTRUCTION	Pt. Sample ID:	SAMPLES	SAMPLE INTERVAL	DESCRIPTION INTERVAL	DESCRIPTION OF STRATUM	DEPTH (FT.)
0								0
			SB1-1'		0'-5'		Silty Sand - Top Soil to Caliche Dry - No Moisture Red Brown	
5			SB1-5'		5'-10'		Caliche - Hard Pan Dry - No Moisture Tan/White	5
10			SB1-10'		10'-15'		Caliche - Hard Pan Dry - No Moisture Tan/White	10
15			SB1-15'		15'-20'		Caliche - Hard Pan Dry - No Moisture Tan/White	15
20			SB1-20'		20'-25'		Caliche - Sandstone @ 22' Dry - No Moisture Tan/White	20
25		SB1-25'		25'-30'		Sandstone Dry - No Moisture Tan/Pink	25	
30						Caliche w/ Gravel	30	


REMARKS:

THIS BORING LOG SHOULD NOT BE USED SEPERATE FROM THE ORIGINAL REPORT



SOIL BORING / MONITORING WELL LOG

PROJECT: <u>Jal, NM - Pit Sites</u>	DRILLING COMPANY: <u>Talon/LPE</u>
PROJECT NUMBER: <u>700438.209.02</u>	DRILLER: <u>Ronnie Rodriguez</u>
CLIENT: <u>EOG Resources</u>	DRILLING METHOD: <u>Hollow Stem Auger/Continuous Core</u>
BORING / WELL NUMBER: <u>ChiliPepper</u>	BORE HOLE DIAMETER: <u>6"</u>
TOTAL DEPTH: <u>75</u>	SCREEN: Diam. <u> </u> Length <u> </u> Slot Size <u> </u>
SURFACE ELEVATION: <u> </u>	CASING: Diam. <u> </u> Length <u> </u> Type <u> </u>
GEOLOGIST: <u>Patrick Tucker</u>	DATE DRILLED: <u>1/10/2018</u>
LATITUDE: <u> </u>	LONGITUDE: <u> </u>

DEPTH (FT.)	Soil Symbol	WELL CONSTRUCTION	Pt. Sample ID:	SAMPLES	SAMPLE INTERVAL	DESCRIPTION INTERVAL	DESCRIPTION OF STRATUM	DEPTH (FT.)
			SB1-30'	█	30'-35'		Dry - No Moisture Tan/Gray Pcpt.	
35			SB1-35'	█	35'-40'		Sandstone - Slow Penetration Dry - No Moisture Yellowish Red *staining	35
40			SB1-40'	█	40'-45'		Sandstone - showing Clay Lens Dry - Low Moisture	40
45			SB1-45'	█	45'-50'		Sandstone - showing Clay lens Dry - Low Moisture Yellowish Red	45
50			SB1-50'	█	50'-55'		Sandstone - showing clay Dry - Low Moisture Light Yellow Red	50
55			SB1-55'	█	55'-60'		Sandstone w/clays Dry - Low Moisture Light Yellowish Red	55
60						Sandstone w/clays Dry - Low Moisture	60	

REMARKS:


THIS BORING LOG SHOULD NOT BE USED SEPERATE FROM THE ORIGINAL REPORT



SOIL BORING / MONITORING WELL LOG

PROJECT: Jal, NM - Pit Sites
 PROJECT NUMBER: 700438.209.02
 CLIENT: EOG Resources
 BORING / WELL NUMBER: ChiliPepper
 TOTAL DEPTH: 75
 SURFACE ELEVATION: _____
 GEOLOGIST: Patrick Tucker
 LATITUDE: _____

DRILLING COMPANY: Talon/LPE
 DRILLER: Ronnie Rodriguez
 DRILLING METHOD: Hollow Stem Auger/Continuous Core
 BORE HOLE DIAMETER: 6"
 SCREEN: Diam. _____ Length _____ Slot Size _____
 CASING: Diam. _____ Length _____ Type _____
 DATE DRILLED: 1/10/2018
 LONGITUDE: _____

DEPTH (FT.)	Soil Symbol	WELL CONSTRUCTION	Pt. Sample ID:	SAMPLES	SAMPLE INTERVAL	DESCRIPTION INTERVAL	DESCRIPTION OF STRATUM	DEPTH (FT.)
65			SB1-60'	60'-65'			Light Yellowish Red	65
70			SB1-65'	65'-70'			Sandstone w/clays Dry - Low Moisture Light Yellowish Red	70
75			SB1-70'	70'-75'			Sandstone w/clays Dry - Low Moisture Light Yellowish Red	75
75				SB1-75'		75'		Bottom of Hole
80								80
85								85
90								90

REMARKS:

THIS BORING LOG SHOULD NOT BE USED SEPERATE FROM THE ORIGINAL REPORT





10 January 2018

Mr. Dustin Kinder
EOG Resources, Inc.
5509 Champions Drive
Midland, TX 79706

**Re: Comprehensive Resource Review – Chili Pepper Water Reuse Site
Lea County, New Mexico**

Dear Mr. Kinder:

Goshawk Environmental Consulting, Inc. (Goshawk) conducted a comprehensive desktop resource review and limited field investigations for the Chili Pepper Water Reuse Site in Lea County, New Mexico. This resource review included Waters of the US (WATERS), Threatened or Endangered (T/E) Species, and Cultural Resources. The purpose of these investigations was to evaluate whether the proposed water reuse site contained any protected resources, the approximate size and location of identified protected resources, and associated development constraints, if applicable. Goshawk also conducted a cultural resources archival review and survey for the site. All figures are in Appendix A.

INTRODUCTION

The Chili Pepper Water Reuse Site will include a double-lined water pit with leak detection, a tanker off load and storage area, a reuse water treatment facility, and freshwater blending system. The site is approximately 1,225 feet long (east to west) and 910 feet wide (north to south) and encompasses approximately 25.59 acres. The site is generally located in a very rural portion of Lea County, where land use is primarily cattle ranching and oil/gas exploration and production.

WATERS REVIEW

REGULATORY BACKGROUND AND METHODOLOGY

Investigations to identify potential WATERS within the proposed Chili Pepper Water Reuse Site included a resource review, followed by a field investigation. The resource review included inspection of available United States Geological Survey (USGS) 7.5-minute topographic quadrangle for San Simon Sink, New Mexico; recent digital aerial orthoimagery; and the Natural Resource Conservation Service (NRCS) Soil Survey Geographic Database (SSURGO). Field investigations were performed in accordance with US Army Corps of Engineers (USACE) guidelines, utilizing the *Corps of Engineers Wetlands Delineation Manual – Technical Report Y-87-1* (January 1987) and the *Regional Supplement to the Corps of Engineers Wetland Delineation Manual: Arid West Region (Version 2.0) – ERDC/EL TR-08-28* (September 2008).

The jurisdictional status of identified features was determined based on 33 CFR 328.3(a), along with the US Army Core of Engineers (USACE)–Environmental Protection Agency (EPA) joint guidance on Clean Water Act (CWA) jurisdiction, following the US Supreme Court’s decision in *Rapanos v. United States* and *Carabell v. United States*. Current guidance states that the USACE and EPA will assert jurisdiction over (1) traditionally navigable waters (TNWs) and all wetlands adjacent to TNWs; (2) relatively permanent waters (RPWs), which include non-navigable tributaries of TNWs that typically flow year-round or have continuous flow at least seasonally, and all wetlands that are directly abutting RPWs; and (3) other water bodies such as non-RPWs; wetlands adjacent to non-RPWs; and wetlands adjacent to but not directly abutting an RPW that are analyzed and determined to have a significant nexus with a TNW. A significant nexus exists if the tributary, in combination with all of its adjacent wetlands, has more than a speculative or an insubstantial effect on the chemical, physical, and/or biological integrity of a TNW.



LITERATURE REVIEW

Topographic Map

The topographic quadrangle (Figure 1) indicates the Chili Pepper Water Reuse Site is entirely within grasslands (white background). The terrain is relatively flat, with the site lying between the 3,360 and 3,370 feet above mean sea level contour lines. Drainage occurs by overland sheet flow toward the west-southwest. The nearest potential WATERS is the San Simon Sink, located approximately 4,540 feet to the southwest of the site. The Chili Pepper Water Reuse Site is within the Lower Pecos River Watershed. The nearest direct line point to the Pecos River is approximately 39 miles southwest. There are no improvements noted on the site; however, there are several unimproved roads mapped in the general vicinity. There is no indication of any potential WATERS within the boundary of the site.

Aerial Orthoimagery

The aerial orthoimagery (Figure 2) indicates the Chili Pepper Water Reuse Site is within relatively open grasslands, intermixed with shrubs. Some of the mapped unimproved roads are depicted on the aerial orthoimagery as caliche-topped roads. Others appear to be old ranch roads. A well pad is indicated east of the proposed water reuse pit. There are no potential WATERS indicated on or near the site.

Soils

The NRCS SSURGO spatial data (Figure 3) indicate the soil map units underlying the Chili Pepper Water Reuse Site are Ratliff-Wink fine sandy loam (MN) and Kermit-Berino fine sands (KM). The primary soil components of these map units are Ratliff loam, Wink fine sand, Kermit fine sands, and Berino loamy fine sands. None of the primary components of these soils are listed as hydric soils.

FIELD INVESTIGATION

A field investigation was conducted on 9 January 2018 in order to determine the presence of potential WATERS within the Chili Pepper Water Reuse Site. The site was traversed on-foot. The site conditions are generally consistent with those depicted on the topographic map and aerial orthoimagery described above. Topographically, the site is relatively flat. Vegetation within the site consists primarily of honey mesquite (*Prosopis glandulosa*), plains yucca (*Yucca glauca*), and broom snakeweed (*Gutierrezia sarothrae*), with a few other desert forbs and grasses.

Surface water run-off from the site is likely very rare. Drainage occurs primarily by overland sheet flow toward the west. No evidence of any Ordinary High Water Mark (OHWM) or standing water was found within the site. Additionally, no flowing watercourse, lake bed, sinkhole, or playa exhibiting an OHWM are found on the site or within 300 feet of the site. A search in the general vicinity of the site did not reveal any seeps, springs, wetlands, or water wells within 500 feet of the site.

REGULATORY DEVELOPMENT CONSTRAINTS

It is Goshawk's opinion that construction of the Chili Pepper Water Reuse Site will not impact any WATERS. It is important to note that only the USACE has the authority to make a formal determination defining its jurisdictional limits under the CWA. Approved jurisdictional determinations are made by the USACE in accordance with internal policies and procedures in place at that time, and on a case-by-case basis using information at its disposal (such as other permits in the local area and case law) that may not be readily available to the public. Therefore, Goshawk's opinion should not be considered authoritative, and cannot wholly eliminate uncertainty regarding the USACE's jurisdictional limits.



THREATENED OR ENDANGERED SPECIES

REGULATORY BACKGROUND AND METHODOLOGY

The Endangered Species Act prohibits any action that causes a “take” of any listed T/E species. “Take” is defined as harm or harassment, including hunting, wounding, killing, trapping, and the capture or collection of individuals of listed species. The law also protects against the degradation or loss of vital habitat for listed species. The United States Fish and Wildlife Service (USFWS) and National Marine Fisheries Service are the regulatory authorities for federally listed T/E species.

State-listed T/E species are protected under New Mexico Wildlife Conservation Act (17-2-41). The New Mexico Department of Game and Fish (NMDGF) has the authority to establish a list of fish and wildlife species that are endangered or threatened. Unlike the federal Act, the state’s regulation makes no provision for the protection of wildlife species from indirect take (e.g., destruction of habitat or unfavorable management practices); rather, it protects from the unlawful killing, trade, or transportation of state-listed species. Therefore, the state-listed species are only a potential development constraint if listed species are determined to be currently occupying the tract.

Literature and agency file searches were conducted to identify the potential occurrence of any federally and state-listed T/E species near the Chili Pepper Water Reuse Site. An internet search of the USFWS *Information, Planning, and Conservation System* (IPaC) was conducted for Lea County to identify federally listed T/E species “that should be considered as part of an effects analysis” for the site. Additionally, a report from the NMDGF Biota Information System of New Mexico (BISON-M) was obtained and reviewed for the Lea County.

RESOURCE REVIEW

The T/E species listed in the IPaC Trust Resource Report for Lea County is the northern aplomado falcon (*Falco femoralis*). Critical habitat for this species is not designated within the Chili Pepper Water Reuse Site or the immediate vicinity.

The state-listed T/E species on NMDGF BISON-M County List for Lea County dated 31 December 2017 include: bald eagle (*Haliaeetus leucocephalus*), aplomado falcon, peregrine falcon (*Falco peregrinus*), arctic peregrine falcon (*Falco peregrinus tundrius*), least tern, broad-billed hummingbird (*Cynanthus latirostris*), Bell’s vireo (*Vireo bellii*), Baird’s sparrow (*Ammodramus bairdii*), and dunes sagebrush lizard (*Sceloporus arenicolus*).

DEVELOPMENT CONSTRAINTS

The northern aplomado falcon is listed for many southern New Mexico counties (including Lea County) and west Texas counties within its historic range. Historically, the falcon utilized open desert grasslands and/or savannas, where scattered shrubs and trees provide roosting and nesting locations. Although the proposed site is within shrublands, the land uses of this area (heavy cattle grazing and oil/gas production) likely precludes the northern aplomado falcon from utilizing the site.

State regulations prohibit the taking, possession, transportation, or sale of any state-listed T/E species. Because Lea County has the potential to support state-listed T/E species, care should be taken to avoid direct impacts (including harassment, harm, killing, and/or collection) to any species that may inhabit the site. The state-listed birds would have the ability to leave the site during active construction to avoid impacts. However, the dunes sagebrush lizard is ground-dwelling and relatively slow-moving, which makes it more likely to be impacted by construction activities than other state-listed species. The dunes sagebrush lizard is more commonly found in the northern and eastern portions of Lea County. The site lacks suitable habitat for the dunes sagebrush lizard.



The lack of habitat for the northern aplomado falcon, coupled with the current land use, makes it highly unlikely that this species is utilizing the site. Furthermore, only the dunes sagebrush lizard would be susceptible to direct impacts during construction of the site. Care should be taken to avoid harassment, harm, killing, and/or collecting of the dunes sagebrush lizard. No further investigations relative to T/E species are recommended.

CULTURAL RESOURCES DESKTOP REVIEW

REGULATORY BACKGROUND AND METHODOLOGY

Section 106 of the National Historic Preservation Act (NHPA) of 1966 requires Federal agencies to consider the effects of their actions on historic properties and provide the State Historic Preservation Office (SHPO) and the Advisory Council on Historic Preservation (ACHP) an opportunity to comment on their projects. Historic properties are defined as archaeological sites, standing structures, or other historic resources listed on or eligible for listing on the National Register of Historic Places (NRHP). The New Mexico Prehistoric and Historic Sites Preservation Act and the New Mexico Cultural Properties Act provide protection of archaeological sites (prehistoric and historic) listed in the State Register of Cultural Properties or on the NRHP.

The regulatory process seeks to determine if a project will have an “effect” upon historic properties. The term “effect” is defined as an “alteration to the characteristics of historic property qualifying it for inclusion in, or eligibility for the National Register (of Historic Places).” An effect is “adverse” when it will endanger those qualities that make the property eligible for inclusion on the NRHP.

Goshawk performed a Class I archival review to evaluate the potential for historic properties present near the Chili Pepper Water Reuse Site. The Archaeological Records Management Section’s New Mexico Cultural Resources Information System (NMCRIS) online database, geospatial data obtained from the US Bureau of Land Management (BLM) Carlsbad Field Office, and the Natural Resources Conservation Service Web Soil Survey were utilized for the review. Following the archival review, a Class III Archaeological Survey was conducted for the site and 100-foot buffer around the site.

ARCHIVAL REVIEW

Nearby Archaeological Sites

According to NMCRIS, there are no previously recorded archaeological sites within the Chili Pepper Reuse Site. The nearest recorded archaeological site, LA# 121114, lies 2,061 feet (628 meters) north of the reuse site. Site LA# 121114 is a Late Pueblo Jornada Mogollon site recorded to contain lithic debitage, chipped stone tools, ground stone tools, Chupadero Brownware ceramics, and fire-cracked rock with at least five recorded fire-cracked rock features. The site was originally recorded by Don Clifton Consulting Archaeologist in 1996 under NMCRIS activity 54145, and has since been revisited twice, most recently by Lone Mountain Archaeological Services in 2001 under NMCRIS activity 75147. The site was determined to be eligible for listing on the National Register of Historic Places (NRHP) by the last two recorders, the BLM, and the SHPO in 2004.

National Register Properties

No NRHP-listed properties have been recorded near the proposed site. According to the NMCRIS database, the nearest NRHP-listed property is the Pope’s Wells Site (LA# 69016). This site consists of the remains of a camp and well site that was part of efforts to establish a water well in the area in the 1850’s. The site lies 19.76 miles west-southwest of the proposed reuse site.



Soils Analysis

Soils mapped within the proposed site consist of Ratliff-Wink fine sandy loams and Kermit-Berino fine sands. Ratliff-Wink fine sandy loams are very shallow fine sandy loams over clay loams typically found on plains. They are composed of calcareous alluvium and eolian deposits derived from sedimentary rock. The Kermit-Berino fine sands are shallow to very deep fine sands overlying clay loams. Considering the soils present, there is a low to moderate probability for the presence of temporally stratified cultural resources within the proposed Chili Pepper Reuse Site.

ARCHAEOLOGICAL SURVEY

Goshawk performed a cultural resources survey on 9 January 2018 for the Chili Pepper Water Reuse Site and 100-foot archaeological survey buffer, encompassing a total of 39.30 acres (Figure 4). Transects were walked at 50-foot intervals over the entire survey area. The site is situated upon exposed hard pan soils with sparse vegetation. Terrain slopes slightly upward to the northeast and south, and surface visibility averaged 70-90%. The intensive survey yielded no cultural material.

DEVELOPMENT CONSTRAINTS

The cultural resources archival review determined there is a low probability for the presence of significant prehistoric resources within the site. No cultural material or archaeological sites were identified during the cultural resources survey. No impacts to cultural resources would be expected by the Chili Pepper Water Reuse Site.

SUMMARY

Based on the results of the Resource Review, it is Goshawk's opinion that the construction of the Chili Pepper Water Reuse Site is unlikely to impact any sensitive natural resources, including WATERS and T/E species. Based on the negative results from the cultural resources survey, it is Goshawk's opinion that the site does not contain significant cultural resources. In the unlikely event that cultural resources (including human remains) are discovered, all construction or maintenance activities should be immediately halted and a qualified archaeologist should be notified. If you have any questions or desire additional information, please contact our office.

Sincerely,



Natasia Mitchell
Environmental Specialist



Steven Evans
Project Archaeologist

Cc: Michael Yemm, EOG Resources, Inc.
Galan Kelley, EOG Resources, Inc.
Wesley Moss, EOG Resources, Inc.




APPENDIX A
FIGURES



APPENDIX A
FIGURES





Map Source: USGS, San Simon Sink,
New Mexico Quadrangle.

Date: 9 January 2018


0 500 1,000 Feet


Figure 1
USGS Topographic Map
Lea County, New Mexico

Chili Pepper Water Reuse Pit
Township 23S; Range 35E; Section 17

LEGEND

-  Water Reuse Pit
-  Proposed Lease Road





LEGEND

- Water Reuse Pit
- Proposed Lease Road

Map Source: EOG's Spatial on Demand.
Global Imagery: DigitalGlobe Most Recent.


0 500 1,000 Feet


Figure 2
Aerial Orthoimagery
Lea County, New Mexico

Date: 9 January 2018



Chili Pepper Water Reuse Pit
Township 23S; Range 35E; Section 17





LEGEND

-  Water Reuse Pit
-  Proposed Lease Road

Soil Map Units

-  MN=Ratliff-Wink fine sandy loam
-  KM=Kermit-Berino fine sands


Map Source: USDA/NRCS - National Geospatial Center of Excellence. Soil Survey Geographic (SSURGO) database, Lea County, New Mexico.




Figure 3
 NRCS SSURGO Soils Map
 Lea County, New Mexico

Chili Pepper Water Reuse Pit
 Township 23S; Range 35E; Section 17

Date: 9 January 2018





LEGEND

- Water Reuse Pit
- Proposed Lease Road
- Archaeological Survey Area (39.3 acres)

Map Source: USGS, San Simon Sink, New Mexico Quadrangle.





Figure 4
Archaeological Survey Area Map
Lea County, New Mexico

Chili Pepper Water Reuse Pit
Township 23S; Range 35E; Section 17

Date: 9 January 2018





January 15, 2018

#5E26751

Mr. Dustin Cole Kinder
EOG Resources, Inc.
421 West 3rd Street, Suite 150
Fort Worth, TX 46102

Subject: C-147 Recycling Containment Permit Siting Criteria Attachment, Proposed Chili Pepper Recycling Facility, Lea County, New Mexico

Dear Mr. Kinder:

Souder, Miller & Associates (SMA) is pleased to submit the enclosed C-147 Siting Criteria Explanation and supporting documentations for the proposed Chili Pepper Recycling Containment Pond to be constructed in southeastern Lea County, New Mexico. The proposed recycling containment will be composed of a lined pond with an approximate capacity of 27.5 million gallons, and be located in Township 23S, Range 35E, NW/4 of Section 17, located to the north of U.S. Highway 128 and south of County Road 21.

Below are details on the siting criteria in Section 8 of the C-147 permit. Supporting documentation are included in the Appendices indicated in each siting criteria explanation. Information obtained from the supporting documentation was confirmed during a site visit by Austin Weyant with SMA on January 3, 2018.

8.1 Groundwater is less than 50 feet below the bottom of the recycling containment

The regional geology near the proposed Chili Pepper Recycling Containment pond is variable. The facility is located near the eastern boundary of a large geologic feature named the San Simon Swale, a structure formed by infilling of collapse structures that has resulted in a thick package of alluvial sediments overlying Triassic-aged redbed units, including the Chinle Formation and the Santa Rosa Sandstone (Nicholson & Clebsch, 1961). Near the proposed facility, the alluvium is estimated to be approximately 150-200 feet thick, however, further west, the alluvial thickness increases to nearly 300 feet. East of the proposed project, the most commonly utilized aquifer occurs within the regionally extensive Triassic redbeds, with the most productive zone consisting of the Santa Rosa Sandstone. To the west of the project, several smaller wells are completed within the quarterly alluvial sediments of the San Simon Swale. The groundwater elevation measured in a monitoring well approximately two miles to the west within the alluvial sediments is 140 feet below ground surface (elevation of 3,220 feet above mean sea level) (USGS, 2017). Groundwater flow in the area is thought to be to the west into the San Simon Swale (Nicholson & Clebsch, 1961).

Groundwater, as indicated by lithology logs from recent drilling activities near the site (location indicated on Figure 1), was not encountered at depths above 75 feet below ground surface (bgs), suggesting the maximum groundwater elevation in the area is 3,293 feet above mean sea level (amsl). The proposed facility is located at an elevation of approximately 3,368 feet above mean sea level, and

the base of the containment pond will be installed to a maximum depth of 20 feet bgs, or an elevation of approximately 3,348 ft amsl. As such, groundwater is present at an elevation over 50 feet from below the bottom of the Recycling Containment. Supporting information from nearby New Mexico Office of the State Engineer (NMOSE) registered wells, United States Geological Society (USGS) monitoring wells, and recent lithology logs are included as Appendix A. The exact borehole coordinates from the recent drilling activities are: LAT N32 18.589; LONG W-103 23.623.

8.2 Facility is located within municipal boundary or within a defined fresh water well field

The facility is located approximately 17.6 miles from the nearest municipality (City of Jal) in an area consisting predominantly of oil and gas development. The proposed facility is not within any defined freshwater field as no municipal water wells are present near the facility location. A vicinity map of the proposed facility on a USGS topographic map is included as Figure 1. A map indicating the location of wells registered with the NMOSE is included as Appendix A.

8.3 Facility is located within an area overlying a subsurface mine

Information from the USGS Topographic map covering the location of the facility as well as a map from the New Mexico Energy, Minerals, and Natural Resources Department (EMNRD) indicates that no subsurface mines or quarries are present within the facility boundaries. There are no quarries or subsurface mines within a one (1) mile radius of the facility boundaries. A vicinity map of the facility on a USGS topographic map is included as Figure 1. A map indicating the location of active mines from the EMNRD website is included as Appendix B.

8.4 Facility is located within an unstable area

The facility is located in generally flat topography with no nearby mapped faults. The USGS Seismic hazard map places the region as a low-risk area for potential earthquakes or other seismic hazards. As such, SMA believes the facility is not located in an unstable area. A vicinity map of the facility on a USGS topographic map is included as Figure 1, and a geologic map of the area with known faults is included as Figure 3. A seismic hazards map is included as Appendix C.

8.5 Facility is located within a 100-year floodplain

The facility is located within FEMA Zone D in an area that is not covered by printed flood maps. Information from the FEMA Floodplain online database indicates that no known 100-year floodplains are present within 10 miles of the facility. A screenshot of the proposed facility area from the online FEMA Floodplain database is included as Appendix D.

8.6 Facility is located within a 300 feet of a continuously flowing watercourse or 200 feet of any other significant watercourse, lakebed, sinkhole, or playa lake

The nearest continually flowing watercourse, as indicated on the USGS topographic map, is over 3 miles from the proposed facility boundary; the nearest ephemeral water course is located approximately 2.8 miles to the northeast of the proposed facility. Lakebeds and/or sinkholes are located approximately 1 mile southwest of the facility. A vicinity map of the facility on a USGS topographic map is included as Figure 1, and an aerial photo of the project area is included as Figure 2.

The absence of watercourses, lakebeds, sinkholes, and playa lakes in the near vicinity of the proposed facility was confirmed by a site visit conducted by Mr. Austin Weyant of SMA on January 3, 2018.

8.7 Facility is located within 1,000 feet of an existing residence, school, hospital, institution, or church at time of initial inspection

The facility is located over 2.18 miles from the nearest private residence. The closest facilities to the proposed facility are existing oil field tank batteries and well pads surrounding the facility. A vicinity map of the facility on a USGS topographic map is included as Figure 1, and an aerial photo of the project area is included as Figure 2. The absence of residences, schools, hospitals, churches, or institutions in the vicinity of the proposed facility was confirmed by a site visit conducted by Mr. Austin Weyant of SMA on January 3, 2018.

8.8 Facility is located within 500 feet of a spring or fresh water well in existence at time of initial inspection

The nearest freshwater well registered with the NMOSE or USGS is located approximately 4,660 feet to the southwest of the proposed facility. No springs are indicated on USGS topographic maps within 1,000 feet of the proposed facility. A vicinity map of the facility on a USGS topographic map is included as Figure 1, and an aerial photo of the project area indicating the location of registered wells is included as Figure 2. Supporting information from nearby NMOSE wells and the USGS monitoring wells is included as Appendix A. The absence of springs or drinking water wells in the vicinity of the proposed facility was confirmed by a site visit conducted by Mr. Austin Weyant of SMA on January 3, 2018.

8.9 Facility is located within 500 feet of a wetland

The nearest wetland as mapped by the United States Fish and Wildlife Service is approximately 1 mile from the proposed facility. A map prepared by the US FWS online wetland database is included as Appendix E. The absence of potential wetlands in the vicinity of the proposed facility was confirmed by a site visit conducted by Mr. Austin Weyant of SMA on January 3, 2017.

If you have any questions, please do not hesitate to call me at 505-299-0942 or to e-mail me at matthew.earthman@soudermiller.com .

Sincerely,

SOUDER, MILLER AND ASSOCIATES




Matthew A. Earthman, P.G.
Project Geoscientist

- Enclosures:
- Figure 1: Vicinity Map on USGS Topographic Quad
 - Figure 2: Site Aerial Photo
 - Figure 3: Geologic Map of Proposed Facility Area

- Appendix A: Groundwater & Well Information (NMOSE & USGS)
- Appendix B: Active Mine/Quarry Map (NM EMNRD)
- Appendix C: USGS Seismic Hazard Map
- Appendix D: FEMA Floodplain Information
- Appendix E: Wetlands & Critical Habitat Map (US FWS)



Figures



Legend

Chili Pepper Reuse Pit

**SITE MAP - TOPOGRAPHICAL MAP
EOG CHILI PEPPER RECYCLING FACILITY
S17, R35E T23S, LEA COUNTY, NM.**



Figure 1

Date Saved: 12/26/2017	By: _____	Date: _____	Revisions	Descr: _____
	By: _____	Date: _____		Descr: _____
Copyright 2015 Souder, Miller & Associates - All Rights Reserved				

Drawn	_____	Curtis Pattillo
Checked	_____	
Approved	_____	



201 South Halaguena Street
Carlsbad, New Mexico 88221
(575) 689-7040
www.soudermiller.com
Serving the Southwest & Rocky Mountains



Legend

Chili Pepper Reuse Pit

**SITE MAP - AERIAL PHOTOGRAPH
EOG CHILI PEPPER RECYCLING FACILITY
S17, R35E T23S, LEA COUNTY, NM.**

Figure 2

Date Saved: 12/26/2017	By: _____	Date: _____	Revisions	Descr: _____
	By: _____	Date: _____		Descr: _____
Copyright 2015 Souder, Miller & Associates - All Rights Reserved				


Drawn	_____	Curtis Pattillo
Checked	_____	
Approved	_____	



201 South Halaguena Street
Carlsbad, New Mexico 88221
(575) 689-7040
www.soudermiller.com
Serving the Southwest & Rocky Mountains



 Approximate Facility Outline




Description		Rev #	Date
SOUDER, MILLER & ASSOCIATES  401 West Broadway Avenue Farmington, NM 87401 Phone (505) 325-7535 Toll-Free (800) 519-0098 Fax (505) 326-0045 Serving the Southwest & Rocky Mountains www.soudermiller.com			

GEOLOGIC MAP OF PROPOSED FACILITY AREA CHILI PEPPER AREA REUSED PIT LEA, COUNTY, NEW MEXICO		
Designed CP	Drawn DJB	Checked RSA
Date: December 2017		
Scale: Horiz: 1" = 3000' Vert: N/A		
Project No: 5E26868		
FIGURE 3		



Appendix A

Groundwater & Well Information (NMOSE & USGS)



SITE MAP - OSE WELLS MAP
EOG CHILI PEPPER RECYCLING FACILITY
S17, R35E T23S, LEA COUNTY, NM.

Date Saved: 1/2/2018	By: _____	Date: _____	Revisions	Descr: _____
	By: _____	Date: _____		Descr: _____
Copyright 2015 Souder, Miller & Associates - All Rights Reserved				

Drawn	_____	Curtis Pattillo
Checked	_____	
Approved	_____	




201 South Halaguena Street
 Carlsbad, New Mexico 88221
 (575) 689-7040
 www.soudermiller.com
 Serving the Southwest & Rocky Mountains

SOIL BORING / MONITORING WELL LOG

PROJECT: Jal, NM - Pit Sites
 PROJECT NUMBER: 700438.209.02
 CLIENT: EOG Resources
 BORING / WELL NUMBER: ChiliPepper
 TOTAL DEPTH: 75
 SURFACE ELEVATION: _____
 GEOLOGIST: Patrick Tucker
 LATITUDE: _____

DRILLING COMPANY: Talon/LPE
 DRILLER: Ronnie Rodriguez
 DRILLING METHOD: Hollow Stem Auger/Continuous Core
 BORE HOLE DIAMETER: 6"
 SCREEN: Diam. _____ Length _____ Slot Size _____
 CASING: Diam. _____ Length _____ Type _____
 DATE DRILLED: 1/10/2018
 LONGITUDE: _____

DEPTH (FT.)	Soil Symbol	WELL CONSTRUCTION	Pt. Sample ID:	SAMPLES	SAMPLE INTERVAL	DESCRIPTION INTERVAL	DESCRIPTION OF STRATUM	DEPTH (FT.)
0								0
			SB1-1'		0'-5'		Silty Sand - Top Soil to Caliche Dry - No Moisture Red Brown	5
5			SB1-5'		5'-10'		Caliche - Hard Pan Dry - No Moisture Tan/White	10
			SB1-10'		10'-15'		Caliche - Hard Pan Dry - No Moisture Tan/White	15
15			SB1-15'		15'-20'		Caliche - Hard Pan Dry - No Moisture Tan/White	20
			SB1-20'		20'-25'		Caliche - Sandstone @ 22' Dry - No Moisture Tan/White	25
25		SB1-25'		25'-30'		Sandstone Dry - No Moisture Tan/Pink	30	
30						Caliche w/ Gravel	30	

REMARKS:

THIS BORING LOG SHOULD NOT BE USED SEPERATE FROM THE ORIGINAL REPORT



SOIL BORING / MONITORING WELL LOG

PROJECT: <u>Jal, NM - Pit Sites</u>	DRILLING COMPANY: <u>Talon/LPE</u>
PROJECT NUMBER: <u>700438.209.02</u>	DRILLER: <u>Ronnie Rodriguez</u>
CLIENT: <u>EOG Resources</u>	DRILLING METHOD: <u>Hollow Stem Auger/Continuous Core</u>
BORING / WELL NUMBER: <u>ChiliPepper</u>	BORE HOLE DIAMETER: <u>6"</u>
TOTAL DEPTH: <u>75</u>	SCREEN: Diam. <u> </u> Length <u> </u> Slot Size <u> </u>
SURFACE ELEVATION: <u> </u>	CASING: Diam. <u> </u> Length <u> </u> Type <u> </u>
GEOLOGIST: <u>Patrick Tucker</u>	DATE DRILLED: <u>1/10/2018</u>
LATITUDE: <u> </u>	LONGITUDE: <u> </u>

DEPTH (FT.)	Soil Symbol	WELL CONSTRUCTION	Pt. Sample ID:	SAMPLES	SAMPLE INTERVAL	DESCRIPTION INTERVAL	DESCRIPTION OF STRATUM	DEPTH (FT.)
			SB1-30'	█	30'-35'		Dry - No Moisture Tan/Gray Pcpt.	
35			SB1-35'	█	35'-40'		Sandstone - Slow Penetration Dry - No Moisture Yellowish Red *staining	35
40			SB1-40'	█	40'-45'		Sandstone - showing Clay Lens Dry - Low Moisture	40
45			SB1-45'	█	45'-50'		Sandstone - showing Clay lens Dry - Low Moisture Yellowish Red	45
50			SB1-50'	█	50'-55'		Sandstone - showing clay Dry - Low Moisture Light Yellow Red	50
55			SB1-55'	█	55'-60'		Sandstone w/clays Dry - Low Moisture Light Yellowish Red	55
60						Sandstone w/clays Dry - Low Moisture	60	

REMARKS:


THIS BORING LOG SHOULD NOT BE USED SEPERATE FROM THE ORIGINAL REPORT



SOIL BORING / MONITORING WELL LOG

PROJECT: Jal, NM - Pit Sites
 PROJECT NUMBER: 700438.209.02
 CLIENT: EOG Resources
 BORING / WELL NUMBER: ChiliPepper
 TOTAL DEPTH: 75
 SURFACE ELEVATION:
 GEOLOGIST: Patrick Tucker
 LATITUDE:


DRILLING COMPANY: Talon/LPE
 DRILLER: Ronnie Rodriguez
 DRILLING METHOD: Hollow Stem Auger/Continuous Core
 BORE HOLE DIAMETER: 6"
 SCREEN: Diam. ___ Length ___ Slot Size ___
 CASING: Diam. ___ Length ___ Type ___
 DATE DRILLED: 1/10/2018
 LONGITUDE:

DEPTH (FT.)	Soil Symbol	WELL CONSTRUCTION	Pt. Sample ID:	SAMPLES	SAMPLE INTERVAL	DESCRIPTION INTERVAL	DESCRIPTION OF STRATUM	DEPTH (FT.)
65			SB1-60'	█	60'-65'		Light Yellowish Red	65
70			SB1-65'	█	65'-70'		Sandstone w/clays Dry - Low Moisture Light Yellowish Red	70
75			SB1-70'	█	70'-75'		Sandstone w/clays Dry - Low Moisture Light Yellowish Red	75
				SB1-75'			75'	Bottom of Hole
80								80
85								85
90								90

REMARKS:

THIS BORING LOG SHOULD NOT BE USED SEPERATE FROM THE ORIGINAL REPORT





EXPLANATION

Pleistocene and Recent	[Sand symbol]	Sand <i>Thin cover of drift sand in most places; locally dunes 20-40 feet high</i>	QUATERNARY	}	CRETACEOUS
	[Qal symbol]	Qal Alluvium <i>Sand and gravel along dry washes; silt and sand in lake beds; includes some wind-deposited sand around depressions</i>			
Pliocene	[To symbol]	To Ogallala formation <i>Chiefly sand, poorly to well-cemented with calcium carbonate; contains some clay, silt, and gravel; capped in most places by caliche</i>	TERTIARY	}	TRIASSIC
	[Rc, Rs, Rd symbols]	Rc-Rs-Rd Dockum group <i>Rc-Chinle formation, red and green claystone, minor siltstone, and fine-grained sandstone; Rs-Santa Rosa sandstone, red to white poorly sorted, coarse-grained, crossbedded sandstone; Rd-rocks of the Dockum group, undifferentiated</i>			
			}		
			CRETACEOUS		


— 3500 — Contours on the red-bed surface
- - - - - Dashed where approximate or inferred.
 Contour interval 50 feet. Datum mean sea level

Base adapted from New Mexico State Highway Department, general highway map, 1941.



Geology by Alexander Nicholson, Jr., 1953-4.
 Contours on buried red-bed surface compiled by Alexander Nicholson, Jr., Alfred Clebsch, Jr., and S.R. Ash from shot-hole logs, 1960.

PLATE 1. GEOLOGIC MAP OF SOUTHERN LEA COUNTY, NEW MEXICO



EXPLANATION

150°
252°
Water well

Upper figure is depth to water; lower figure is depth of well. Open circles are wells finished in Tertiary or Quaternary rocks; solid circles are wells finished in Triassic rocks

F = Flowing
R = Reported
P = Water level measured while pumping
D = Dry
? = Uncertainty as to aquifer
> = More than
< = Less than
(See tables 6 and 7 for detailed well data.)

3925 ————
Water-table contour in Tertiary or Quaternary rocks
Dashed where inferred or uncertain. Contour interval 25 feet. Datum mean sea level

3500 ————
Water-table or piezometric contour on water body in Triassic aquifers
Dashed where inferred or uncertain. Contour interval 100 feet. Datum mean sea level

Approximate position of boundary between Triassic rocks and saturated Tertiary and Quaternary rocks

Base adapted from New Mexico State Highway Department, general highway map, 1941.

Compiled by Alfred Clebsch, Jr., 1960, using data collected mainly by Alexander Nicholson, Jr., in 1953 and 1954.


PLATE 2. GROUND-WATER MAP OF SOUTHERN LEA COUNTY, NEW MEXICO



Appendix B

Active Mine/Quarry Map (NM EMNRD)

Active Mines in Lea County, New Mexico, November 2014




- Metals**
- Coal
 - Potash
 - Copper
 - Gold & Silver
 - Molybdenum

- Industrial Minerals**
- Calcite
 - Gemstone
 - Gypsum
 - Humate
 - Perlite
 - Pumice
 - Salt
 - Silica / Flux
 - Silver Silica
 - Zeolites

- Aggregate & Stone**
- Aggregate
 - Caliche
 - Clay & Shale
 - Dimension & Flagstone
 - Limestone
 - Red Dog
 - Scoria
 - Travertine


Data: November 2014 database query, Mining & Minerals Division, Mine Registration, Reporting & Safeguarding Program.
 Basemap: Esri ArcGIS Online, National Geographic.
 Map: Linda S. DeLay, GISP



Active Mines in New Mexico



12 / 28 / 2017 11 : 13 : 07 AM



Esri, HERE, DeLorme, MapmyIndia, © OpenStreetMap contributors,
and the GIS user community
Source: Esri, DigitalGlobe, GeoEye, Earthstar Geographics,
CNES/Airbus DS, USDA, USGS, AeroGRID, IGN, and the GIS User
Community




Appendix C

USGS Seismic Hazard Map

Information by Region - New Mexico

2014 Seismic Hazard Map




[USGS National Seismic Hazard Maps](#)



Appendix D

FEMA Floodplain Information



Site Map - FEMA Streams and Rivers Map
 EOG Chili Pepper Recycling Facility
 S17, R35E T23S, Lea County, NM.

Legend

- Chili Pepper
- CFO_FEMA_Streams_Rivers
- 1milebuffer

NORTH


Date Saved: 12/26/2017	By: _____	Date: _____	Revisions	Descr: _____
	By: _____	Date: _____		Descr: _____
Copyright 2015 Souder, Miller & Associates - All Rights Reserved				

Drawn	<u>Curtis Pattillo</u>
Checked	_____
Approved	_____



201 South Halaguena Street
 Carlsbad, New Mexico 88221
 (575) 689-7040
 www.soudermiller.com
 Serving the Southwest & Rocky Mountains

FEMA's National Flood Hazard Layer (Official)



Data from Flood Insurance Rate Maps (FIRMs) where available digitally. New NFHL FIRMette Print app available: <http://tinyurl.com/j4xwp5e>

1mi

USGS The National Map: Orthoimagery | National Geospatial-Intelligence Agency (NGA); Delta State University; Esri | Print here instead: <http://tinyurl.com/j4xwp5e> Support: FEMAMapSpecialist@riskmapcds.com



Appendix E

Wetlands & Critical Habitat Map (US FWS)



U.S. Fish and Wildlife Service, National Standards and Support Team, wetlands_team@fws.gov

December 26, 2017

Wetlands

- | | | | | | |
|---|--------------------------------|---|-----------------------------------|---|----------|
|  | Estuarine and Marine Deepwater |  | Freshwater Emergent Wetland |  | Lake |
|  | Estuarine and Marine Wetland |  | Freshwater Forested/Shrub Wetland |  | Other |
| | |  | Freshwater Pond |  | Riverine |

This map is for general reference only. The US Fish and Wildlife Service is not responsible for the accuracy or currentness of the base data shown on this map. All wetlands related data should be used in accordance with the layer metadata found on the Wetlands Mapper web site.