

Mewbourne Oil Company

Lea County, New Mexico NAD 83

Gazelle 22 B2NC Fed Com #2H

Sec 22, T23S, R34E

SL: 200' FSL & 1750' FWL

BHL: 100' FNL & 1850' FWL

Plan: Design #1

Standard Planning Report

11 July, 2018

Planning Report

Database:	Hobbs	Local Co-ordinate Reference:	Site Gazelle 22 B2NC Fed Com #2H
Company:	Mewbourne Oil Company	TVD Reference:	WELL @ 3498.0usft (Original Well Elev)
Project:	Lea County, New Mexico NAD 83	MD Reference:	WELL @ 3498.0usft (Original Well Elev)
Site:	Gazelle 22 B2NC Fed Com #2H	North Reference:	Grid
Well:	Sec 22, T23S, R34E	Survey Calculation Method:	Minimum Curvature
Wellbore:	BHL: 100' FNL & 1850' FWL		
Design:	Design #1		

Project	Lea County, New Mexico NAD 83		
Map System:	US State Plane 1983	System Datum:	Mean Sea Level
Geo Datum:	North American Datum 1983		
Map Zone:	New Mexico Eastern Zone		

Site		Gazelle 22 B2NC Fed Com #2H			
Site Position:		Northing:	467,929.00 usft	Latitude:	32.2833963
From:	Map	Easting:	810,979.00 usft	Longitude:	-103.4608087
Position Uncertainty:	0.0 usft	Slot Radius:	13-3/16 "	Grid Convergence:	0.47 °

Well	Sec 22, T23S, R34E					
Well Position	+N/-S	0.0 usft	Northing:	467,929.00 usft	Latitude:	32.2833963
	+E/-W	0.0 usft	Easting:	810,979.00 usft	Longitude:	-103.4608087
Position Uncertainty		0.0 usft	Wellhead Elevation:	3,498.0 usft	Ground Level:	3,471.0 usft

Wellbore	BHL: 100' FNL & 1850' FWL				
Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	IGRF2010	7/11/2018	6.66	60.08	47,955

Design	Design #1			
Audit Notes:				
Version:	Phase:	PROTOTYPE	Tie On Depth:	0.0
Vertical Section:	Depth From (TVD) (usft)	+N/-S (usft)	+E/-W (usft)	Direction (°)
	0.0	0.0	0.0	0.64

Plan Sections										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	TFO (°)	Target
0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.00	0.00	
5,075.0	0.00	0.00	5,075.0	0.0	0.0	0.00	0.00	0.00	0.00	
5,205.1	2.60	151.52	5,205.1	-2.6	1.4	2.00	2.00	0.00	151.52	
9,784.7	2.60	151.52	9,779.9	-185.4	100.6	0.00	0.00	0.00	0.00	
9,914.8	0.00	0.00	9,910.0	-188.0	102.0	2.00	-2.00	0.00	180.00	KOP @ 9910'
10,665.7	90.00	359.49	10,388.0	290.0	97.7	11.99	11.99	0.00	-0.51	
15,358.9	90.00	359.49	10,388.0	4,983.0	56.0	0.00	0.00	0.00	0.00	BHL: 100' FNL & 1850'

Planning Report

Database:	Hobbs	Local Co-ordinate Reference:	Site Gazelle 22 B2NC Fed Com #2H
Company:	Mewbourne Oil Company	TVD Reference:	WELL @ 3498.0usft (Original Well Elev)
Project:	Lea County, New Mexico NAD 83	MD Reference:	WELL @ 3498.0usft (Original Well Elev)
Site:	Gazelle 22 B2NC Fed Com #2H	North Reference:	Grid
Well:	Sec 22, T23S, R34E	Survey Calculation Method:	Minimum Curvature
Wellbore:	BHL: 100' FNL & 1850' FWL		
Design:	Design #1		

Planned Survey									
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
0.0	0.00	0.00	0.0	0.0	0.0	0.0	0.00	0.00	0.00
SL: 200' FSL & 1750' FWL									
100.0	0.00	0.00	100.0	0.0	0.0	0.0	0.00	0.00	0.00
200.0	0.00	0.00	200.0	0.0	0.0	0.0	0.00	0.00	0.00
300.0	0.00	0.00	300.0	0.0	0.0	0.0	0.00	0.00	0.00
400.0	0.00	0.00	400.0	0.0	0.0	0.0	0.00	0.00	0.00
500.0	0.00	0.00	500.0	0.0	0.0	0.0	0.00	0.00	0.00
600.0	0.00	0.00	600.0	0.0	0.0	0.0	0.00	0.00	0.00
700.0	0.00	0.00	700.0	0.0	0.0	0.0	0.00	0.00	0.00
800.0	0.00	0.00	800.0	0.0	0.0	0.0	0.00	0.00	0.00
900.0	0.00	0.00	900.0	0.0	0.0	0.0	0.00	0.00	0.00
1,000.0	0.00	0.00	1,000.0	0.0	0.0	0.0	0.00	0.00	0.00
1,100.0	0.00	0.00	1,100.0	0.0	0.0	0.0	0.00	0.00	0.00
1,200.0	0.00	0.00	1,200.0	0.0	0.0	0.0	0.00	0.00	0.00
1,300.0	0.00	0.00	1,300.0	0.0	0.0	0.0	0.00	0.00	0.00
1,400.0	0.00	0.00	1,400.0	0.0	0.0	0.0	0.00	0.00	0.00
1,500.0	0.00	0.00	1,500.0	0.0	0.0	0.0	0.00	0.00	0.00
1,600.0	0.00	0.00	1,600.0	0.0	0.0	0.0	0.00	0.00	0.00
1,700.0	0.00	0.00	1,700.0	0.0	0.0	0.0	0.00	0.00	0.00
1,800.0	0.00	0.00	1,800.0	0.0	0.0	0.0	0.00	0.00	0.00
1,900.0	0.00	0.00	1,900.0	0.0	0.0	0.0	0.00	0.00	0.00
2,000.0	0.00	0.00	2,000.0	0.0	0.0	0.0	0.00	0.00	0.00
2,100.0	0.00	0.00	2,100.0	0.0	0.0	0.0	0.00	0.00	0.00
2,200.0	0.00	0.00	2,200.0	0.0	0.0	0.0	0.00	0.00	0.00
2,300.0	0.00	0.00	2,300.0	0.0	0.0	0.0	0.00	0.00	0.00
2,400.0	0.00	0.00	2,400.0	0.0	0.0	0.0	0.00	0.00	0.00
2,500.0	0.00	0.00	2,500.0	0.0	0.0	0.0	0.00	0.00	0.00
2,600.0	0.00	0.00	2,600.0	0.0	0.0	0.0	0.00	0.00	0.00
2,700.0	0.00	0.00	2,700.0	0.0	0.0	0.0	0.00	0.00	0.00
2,800.0	0.00	0.00	2,800.0	0.0	0.0	0.0	0.00	0.00	0.00
2,900.0	0.00	0.00	2,900.0	0.0	0.0	0.0	0.00	0.00	0.00
3,000.0	0.00	0.00	3,000.0	0.0	0.0	0.0	0.00	0.00	0.00
3,100.0	0.00	0.00	3,100.0	0.0	0.0	0.0	0.00	0.00	0.00
3,200.0	0.00	0.00	3,200.0	0.0	0.0	0.0	0.00	0.00	0.00
3,300.0	0.00	0.00	3,300.0	0.0	0.0	0.0	0.00	0.00	0.00
3,400.0	0.00	0.00	3,400.0	0.0	0.0	0.0	0.00	0.00	0.00
3,500.0	0.00	0.00	3,500.0	0.0	0.0	0.0	0.00	0.00	0.00
3,600.0	0.00	0.00	3,600.0	0.0	0.0	0.0	0.00	0.00	0.00
3,700.0	0.00	0.00	3,700.0	0.0	0.0	0.0	0.00	0.00	0.00
3,800.0	0.00	0.00	3,800.0	0.0	0.0	0.0	0.00	0.00	0.00
3,900.0	0.00	0.00	3,900.0	0.0	0.0	0.0	0.00	0.00	0.00
4,000.0	0.00	0.00	4,000.0	0.0	0.0	0.0	0.00	0.00	0.00
4,100.0	0.00	0.00	4,100.0	0.0	0.0	0.0	0.00	0.00	0.00
4,200.0	0.00	0.00	4,200.0	0.0	0.0	0.0	0.00	0.00	0.00
4,300.0	0.00	0.00	4,300.0	0.0	0.0	0.0	0.00	0.00	0.00
4,400.0	0.00	0.00	4,400.0	0.0	0.0	0.0	0.00	0.00	0.00
4,500.0	0.00	0.00	4,500.0	0.0	0.0	0.0	0.00	0.00	0.00
4,600.0	0.00	0.00	4,600.0	0.0	0.0	0.0	0.00	0.00	0.00
4,700.0	0.00	0.00	4,700.0	0.0	0.0	0.0	0.00	0.00	0.00
4,800.0	0.00	0.00	4,800.0	0.0	0.0	0.0	0.00	0.00	0.00
4,900.0	0.00	0.00	4,900.0	0.0	0.0	0.0	0.00	0.00	0.00
5,000.0	0.00	0.00	5,000.0	0.0	0.0	0.0	0.00	0.00	0.00
5,075.0	0.00	0.00	5,075.0	0.0	0.0	0.0	0.00	0.00	0.00
5,100.0	0.50	151.52	5,100.0	-0.1	0.1	-0.1	2.00	2.00	0.00

Planning Report

Database:	Hobbs	Local Co-ordinate Reference:	Site Gazelle 22 B2NC Fed Com #2H
Company:	Mewbourne Oil Company	TVD Reference:	WELL @ 3498.0usft (Original Well Elev)
Project:	Lea County, New Mexico NAD 83	MD Reference:	WELL @ 3498.0usft (Original Well Elev)
Site:	Gazelle 22 B2NC Fed Com #2H	North Reference:	Grid
Well:	Sec 22, T23S, R34E	Survey Calculation Method:	Minimum Curvature
Wellbore:	BHL: 100' FNL & 1850' FWL		
Design:	Design #1		

Planned Survey									
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
5,200.0	2.50	151.52	5,200.0	-2.4	1.3	-2.4	2.00	2.00	0.00
5,205.1	2.60	151.52	5,205.1	-2.6	1.4	-2.6	2.00	2.00	0.00
5,300.0	2.60	151.52	5,299.9	-6.4	3.5	-6.3	0.00	0.00	0.00
5,400.0	2.60	151.52	5,399.8	-10.4	5.6	-10.3	0.00	0.00	0.00
5,500.0	2.60	151.52	5,499.7	-14.4	7.8	-14.3	0.00	0.00	0.00
5,600.0	2.60	151.52	5,599.5	-18.4	10.0	-18.2	0.00	0.00	0.00
5,700.0	2.60	151.52	5,699.4	-22.4	12.1	-22.2	0.00	0.00	0.00
5,800.0	2.60	151.52	5,799.3	-26.3	14.3	-26.2	0.00	0.00	0.00
5,900.0	2.60	151.52	5,899.2	-30.3	16.5	-30.1	0.00	0.00	0.00
6,000.0	2.60	151.52	5,999.1	-34.3	18.6	-34.1	0.00	0.00	0.00
6,100.0	2.60	151.52	6,099.0	-38.3	20.8	-38.1	0.00	0.00	0.00
6,200.0	2.60	151.52	6,198.9	-42.3	23.0	-42.0	0.00	0.00	0.00
6,300.0	2.60	151.52	6,298.8	-46.3	25.1	-46.0	0.00	0.00	0.00
6,400.0	2.60	151.52	6,398.7	-50.3	27.3	-50.0	0.00	0.00	0.00
6,500.0	2.60	151.52	6,498.6	-54.3	29.5	-54.0	0.00	0.00	0.00
6,600.0	2.60	151.52	6,598.5	-58.3	31.6	-57.9	0.00	0.00	0.00
6,700.0	2.60	151.52	6,698.4	-62.3	33.8	-61.9	0.00	0.00	0.00
6,800.0	2.60	151.52	6,798.3	-66.3	36.0	-65.9	0.00	0.00	0.00
6,900.0	2.60	151.52	6,898.2	-70.3	38.1	-69.8	0.00	0.00	0.00
7,000.0	2.60	151.52	6,998.1	-74.2	40.3	-73.8	0.00	0.00	0.00
7,100.0	2.60	151.52	7,098.0	-78.2	42.4	-77.8	0.00	0.00	0.00
7,200.0	2.60	151.52	7,197.9	-82.2	44.6	-81.7	0.00	0.00	0.00
7,300.0	2.60	151.52	7,297.8	-86.2	46.8	-85.7	0.00	0.00	0.00
7,400.0	2.60	151.52	7,397.7	-90.2	48.9	-89.7	0.00	0.00	0.00
7,500.0	2.60	151.52	7,497.6	-94.2	51.1	-93.6	0.00	0.00	0.00
7,600.0	2.60	151.52	7,597.5	-98.2	53.3	-97.6	0.00	0.00	0.00
7,700.0	2.60	151.52	7,697.4	-102.2	55.4	-101.6	0.00	0.00	0.00
7,800.0	2.60	151.52	7,797.3	-106.2	57.6	-105.5	0.00	0.00	0.00
7,900.0	2.60	151.52	7,897.2	-110.2	59.8	-109.5	0.00	0.00	0.00
8,000.0	2.60	151.52	7,997.1	-114.2	61.9	-113.5	0.00	0.00	0.00
8,100.0	2.60	151.52	8,097.0	-118.2	64.1	-117.4	0.00	0.00	0.00
8,200.0	2.60	151.52	8,196.9	-122.1	66.3	-121.4	0.00	0.00	0.00
8,300.0	2.60	151.52	8,296.8	-126.1	68.4	-125.4	0.00	0.00	0.00
8,400.0	2.60	151.52	8,396.7	-130.1	70.6	-129.3	0.00	0.00	0.00
8,500.0	2.60	151.52	8,496.6	-134.1	72.8	-133.3	0.00	0.00	0.00
8,600.0	2.60	151.52	8,596.5	-138.1	74.9	-137.3	0.00	0.00	0.00
8,700.0	2.60	151.52	8,696.3	-142.1	77.1	-141.2	0.00	0.00	0.00
8,800.0	2.60	151.52	8,796.2	-146.1	79.3	-145.2	0.00	0.00	0.00
8,900.0	2.60	151.52	8,896.1	-150.1	81.4	-149.2	0.00	0.00	0.00
9,000.0	2.60	151.52	8,996.0	-154.1	83.6	-153.1	0.00	0.00	0.00
9,100.0	2.60	151.52	9,095.9	-158.1	85.8	-157.1	0.00	0.00	0.00
9,200.0	2.60	151.52	9,195.8	-162.1	87.9	-161.1	0.00	0.00	0.00
9,300.0	2.60	151.52	9,295.7	-166.1	90.1	-165.0	0.00	0.00	0.00
9,400.0	2.60	151.52	9,395.6	-170.0	92.3	-169.0	0.00	0.00	0.00
9,500.0	2.60	151.52	9,495.5	-174.0	94.4	-173.0	0.00	0.00	0.00
9,600.0	2.60	151.52	9,595.4	-178.0	96.6	-176.9	0.00	0.00	0.00
9,700.0	2.60	151.52	9,695.3	-182.0	98.8	-180.9	0.00	0.00	0.00
9,784.7	2.60	151.52	9,779.9	-185.4	100.6	-184.3	0.00	0.00	0.00
9,800.0	2.30	151.52	9,795.2	-186.0	100.9	-184.8	2.00	-2.00	0.00
9,900.0	0.30	151.52	9,895.2	-188.0	102.0	-186.8	2.00	-2.00	0.00
9,914.8	0.00	0.00	9,910.0	-188.0	102.0	-186.8	2.00	-2.00	0.00
KOP @ 9910'									
10,000.0	10.21	359.49	9,994.7	-180.4	101.9	-179.3	11.99	11.99	0.00

Planning Report

Database:	Hobbs	Local Co-ordinate Reference:	Site Gazelle 22 B2NC Fed Com #2H
Company:	Mewbourne Oil Company	TVD Reference:	WELL @ 3498.0usft (Original Well Elev)
Project:	Lea County, New Mexico NAD 83	MD Reference:	WELL @ 3498.0usft (Original Well Elev)
Site:	Gazelle 22 B2NC Fed Com #2H	North Reference:	Grid
Well:	Sec 22, T23S, R34E	Survey Calculation Method:	Minimum Curvature
Wellbore:	BHL: 100' FNL & 1850' FWL		
Design:	Design #1		

Planned Survey										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	
10,100.0	22.20	359.49	10,090.6	-152.6	101.7	-151.4	11.99	11.99	0.00	
10,200.0	34.18	359.49	10,178.6	-105.4	101.3	-104.3	11.99	11.99	0.00	
10,209.5	35.32	359.49	10,186.4	-100.0	101.2	-98.9	11.99	11.99	0.00	
FTP: 100' FSL & 1850' FWL										
10,300.0	46.17	359.49	10,254.8	-41.0	100.7	-39.9	11.99	11.99	0.00	
10,400.0	58.16	359.49	10,316.1	37.8	100.0	38.9	11.99	11.99	0.00	
10,500.0	70.14	359.49	10,359.6	127.6	99.2	128.7	11.99	11.99	0.00	
10,600.0	82.13	359.49	10,383.5	224.5	98.3	225.6	11.99	11.99	0.00	
10,665.7	90.00	359.49	10,388.0	290.0	97.7	291.1	11.99	11.99	0.00	
LP: 490' FSL & 1850' FWL										
10,700.0	90.00	359.49	10,388.0	324.3	97.4	325.4	0.00	0.00	0.00	
10,800.0	90.00	359.49	10,388.0	424.3	96.6	425.4	0.00	0.00	0.00	
10,900.0	90.00	359.49	10,388.0	524.3	95.7	525.4	0.00	0.00	0.00	
11,000.0	90.00	359.49	10,388.0	624.3	94.8	625.3	0.00	0.00	0.00	
11,100.0	90.00	359.49	10,388.0	724.3	93.9	725.3	0.00	0.00	0.00	
11,200.0	90.00	359.49	10,388.0	824.3	93.0	825.3	0.00	0.00	0.00	
11,300.0	90.00	359.49	10,388.0	924.3	92.1	925.3	0.00	0.00	0.00	
11,400.0	90.00	359.49	10,388.0	1,024.3	91.2	1,025.3	0.00	0.00	0.00	
11,500.0	90.00	359.49	10,388.0	1,124.3	90.3	1,125.2	0.00	0.00	0.00	
11,600.0	90.00	359.49	10,388.0	1,224.3	89.4	1,225.2	0.00	0.00	0.00	
11,700.0	90.00	359.49	10,388.0	1,324.3	88.5	1,325.2	0.00	0.00	0.00	
11,800.0	90.00	359.49	10,388.0	1,424.3	87.7	1,425.2	0.00	0.00	0.00	
11,900.0	90.00	359.49	10,388.0	1,524.3	86.8	1,525.2	0.00	0.00	0.00	
12,000.0	90.00	359.49	10,388.0	1,624.3	85.9	1,625.1	0.00	0.00	0.00	
12,100.0	90.00	359.49	10,388.0	1,724.3	85.0	1,725.1	0.00	0.00	0.00	
12,200.0	90.00	359.49	10,388.0	1,824.3	84.1	1,825.1	0.00	0.00	0.00	
12,300.0	90.00	359.49	10,388.0	1,924.3	83.2	1,925.1	0.00	0.00	0.00	
12,400.0	90.00	359.49	10,388.0	2,024.3	82.3	2,025.1	0.00	0.00	0.00	
12,500.0	90.00	359.49	10,388.0	2,124.3	81.4	2,125.0	0.00	0.00	0.00	
12,600.0	90.00	359.49	10,388.0	2,224.2	80.5	2,225.0	0.00	0.00	0.00	
12,700.0	90.00	359.49	10,388.0	2,324.2	79.7	2,325.0	0.00	0.00	0.00	
12,800.0	90.00	359.49	10,388.0	2,424.2	78.8	2,425.0	0.00	0.00	0.00	
12,817.8	90.00	359.49	10,388.0	2,442.0	78.6	2,442.7	0.00	0.00	0.00	
PPP-2: 2641' FNL & 1850' FWL										
12,900.0	90.00	359.49	10,388.0	2,524.2	77.9	2,525.0	0.00	0.00	0.00	
13,000.0	90.00	359.49	10,388.0	2,624.2	77.0	2,624.9	0.00	0.00	0.00	
13,100.0	90.00	359.49	10,388.0	2,724.2	76.1	2,724.9	0.00	0.00	0.00	
13,200.0	90.00	359.49	10,388.0	2,824.2	75.2	2,824.9	0.00	0.00	0.00	
13,300.0	90.00	359.49	10,388.0	2,924.2	74.3	2,924.9	0.00	0.00	0.00	
13,400.0	90.00	359.49	10,388.0	3,024.2	73.4	3,024.9	0.00	0.00	0.00	
13,500.0	90.00	359.49	10,388.0	3,124.2	72.5	3,124.8	0.00	0.00	0.00	
13,600.0	90.00	359.49	10,388.0	3,224.2	71.6	3,224.8	0.00	0.00	0.00	
13,700.0	90.00	359.49	10,388.0	3,324.2	70.8	3,324.8	0.00	0.00	0.00	
13,800.0	90.00	359.49	10,388.0	3,424.2	69.9	3,424.8	0.00	0.00	0.00	
13,900.0	90.00	359.49	10,388.0	3,524.2	69.0	3,524.8	0.00	0.00	0.00	
14,000.0	90.00	359.49	10,388.0	3,624.2	68.1	3,624.7	0.00	0.00	0.00	
14,100.0	90.00	359.49	10,388.0	3,724.2	67.2	3,724.7	0.00	0.00	0.00	
14,200.0	90.00	359.49	10,388.0	3,824.2	66.3	3,824.7	0.00	0.00	0.00	
14,300.0	90.00	359.49	10,388.0	3,924.2	65.4	3,924.7	0.00	0.00	0.00	
14,400.0	90.00	359.49	10,388.0	4,024.2	64.5	4,024.6	0.00	0.00	0.00	
14,500.0	90.00	359.49	10,388.0	4,124.2	63.6	4,124.6	0.00	0.00	0.00	
14,600.0	90.00	359.49	10,388.0	4,224.2	62.8	4,224.6	0.00	0.00	0.00	
14,700.0	90.00	359.49	10,388.0	4,324.2	61.9	4,324.6	0.00	0.00	0.00	

Planning Report

Database:	Hobbs	Local Co-ordinate Reference:	Site Gazelle 22 B2NC Fed Com #2H
Company:	Mewbourne Oil Company	TVD Reference:	WELL @ 3498.0usft (Original Well Elev)
Project:	Lea County, New Mexico NAD 83	MD Reference:	WELL @ 3498.0usft (Original Well Elev)
Site:	Gazelle 22 B2NC Fed Com #2H	North Reference:	Grid
Well:	Sec 22, T23S, R34E	Survey Calculation Method:	Minimum Curvature
Wellbore:	BHL: 100' FNL & 1850' FWL		
Design:	Design #1		

Planned Survey										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	
14,800.0	90.00	359.49	10,388.0	4,424.2	61.0	4,424.6	0.00	0.00	0.00	
14,900.0	90.00	359.49	10,388.0	4,524.2	60.1	4,524.5	0.00	0.00	0.00	
15,000.0	90.00	359.49	10,388.0	4,624.2	59.2	4,624.5	0.00	0.00	0.00	
15,100.0	90.00	359.49	10,388.0	4,724.2	58.3	4,724.5	0.00	0.00	0.00	
15,200.0	90.00	359.49	10,388.0	4,824.1	57.4	4,824.5	0.00	0.00	0.00	
15,300.0	90.00	359.49	10,388.0	4,924.1	56.5	4,924.5	0.00	0.00	0.00	
15,358.9	90.00	359.49	10,388.0	4,983.0	56.0	4,983.3	0.00	0.00	0.00	
BHL: 100' FNL & 1850' FWL										

Design Targets										
Target Name - hit/miss target - Shape	Dip Angle (°)	Dip Dir. (°)	TVD (usft)	+N/-S (usft)	+E/-W (usft)	Northing (usft)	Easting (usft)	Latitude	Longitude	
SL: 200' FSL & 1750' FV - plan hits target center - Point	0.00	0.00	0.0	0.0	0.0	467,929.00	810,979.00	32.2833963	-103.4608087	
KOP @ 9910' - plan hits target center - Point	0.00	0.00	9,910.0	-188.0	102.0	467,741.00	811,081.00	32.2828773	-103.4604836	
FTP: 100' FSL & 1850' F - plan hits target center - Point	0.00	0.00	10,186.4	-100.0	101.2	467,829.00	811,080.22	32.2831192	-103.4604838	
BHL: 100' FNL & 1850' F - plan hits target center - Point	0.00	0.00	10,388.0	4,983.0	56.0	472,912.00	811,035.00	32.2970911	-103.4604963	
LP: 490' FSL & 1850' FV - plan hits target center - Point	0.00	0.00	10,388.0	290.0	97.7	468,218.98	811,076.75	32.2841912	-103.4604848	
PPP-2: 2641' FNL & 185 - plan hits target center - Point	0.00	0.00	10,388.0	2,442.0	78.6	470,371.00	811,057.60	32.2901066	-103.4604901	

Gazelle 22 B2NC Fed Com #2H

