

District I
1625 N. French Dr., Hobbs, NM 88240
Phone: (505) 393-6161 Fax: (505) 393-0720
District II
811 S. First St., Artesia, NM 88210
Phone: (505) 748-1283 Fax: (505) 748-9720
District III
1000 Rio Brazos Road, Aztec, NM 87410
Phone: (505) 334-6178 Fax: (505) 334-6170
District IV
1220 S. St. Francis Dr., Santa Fe, NM 87505
Phone: (505) 476-3460 Fax: (505) 476-3462

State of New Mexico
Energy, Minerals & Natural Resources
Department
OIL CONSERVATION DIVISION
1220 South St. Francis Dr.
Santa Fe, NM 87505

FORM C-102

Revised August 1, 2011

Submit one copy to appropriate

District Office

☐ AMENDED REPORT

WELL LOCATION AND ACREAGE DEDICATION PLAT

¹ API Number 30-025-46734	² Pool Code 59900	³ Pool Name TRIPLE X; BONE SPRING
⁴ Property Code 313956	⁵ Property Name NEPTUNE 10 STATE COM	⁶ Well Number 204H
⁷ OGRID No. 7377	⁸ Operator Name EOG RESOURCES, INC.	⁹ Elevation 3607'

¹⁰Surface Location


UL or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
P	10	24-S	33-E	-	870'	SOUTH	997'	EAST	LEA

¹¹Bottom Hole Location If Different From Surface

UL or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
B	3	24-S	33-E	-	100'	NORTH	2016'	EAST	LEA

¹² Dedicated Acres 320.08	¹³ Joint or Infill	¹⁴ Consolidation Code	¹⁵ Order No.
---	-------------------------------	----------------------------------	-------------------------

No allowable will be assigned to this completion until all interests have been consolidated or a non-standard unit has been approved by the division.

¹⁷OPERATOR CERTIFICATION

I hereby certify that the information contained herein is true and complete to the best of my knowledge and belief, and that this organization either owns a working interest or unleased mineral interest in the land including the proposed bottom hole location or has a right to drill this well at this location pursuant to a contract with an owner of such a mineral or working interest, or to a voluntary pooling agreement or a compulsory pooling order heretofore entered by the division.

Kay Maddox 11/17/2020
Signature Date

KAY MADDOX
Printed Name


kay_maddox@eogresources.com
E-mail Address

¹⁸SURVEYOR CERTIFICATION

I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true to the best of my belief.

11/20/2019

Date of Survey
Signature and Seal of Professional Surveyor




Certificate Number

SCALE: 1" = 2000'

0' 1000' 2000'

SECTION 10 TOWNSHIP 24-S, RANGE 33-E, N.M.P.M.
LEA COUNTY, NEW MEXICO



LEASE NAME & WELL NO.: NEPTUNE 10 STATE COM #204H
SECTION 10 TWP 24-S RGE 33-E SURVEY N.M.P.M.
COUNTY LEA STATE NM ELEVATION 3607'
DESCRIPTION 870' FSL & 997' FEL



1400 EVERMAN PARKWAY, Ste. 146 • FT. WORTH, TEXAS 76140
TELEPHONE: (817) 744-7512 • FAX (817) 744-7554
2903 NORTH BIG SPRING • MIDLAND, TEXAS 79705
TELEPHONE: (432) 682-1653 OR (800) 767-1653 • FAX (432) 682-1743
WWW.TOPOGRAPHIC.COM



Ramon A. Dominguez, P.S. No. 24508
JULY 30, 2020



NEPTUNE 10 STATE COM #204H AS-COMPLETE	REVISION:	
	INT	DATE
DATE: 07/30/2020		
FILE:AD_NEPTUNE10STATECOM_204H		
DRAWN BY: H.B.		
SHEET: 1 OF 1		

NOTES:

1. ORIGINAL DOCUMENT SIZE: 8.5" X 11"
2. ALL BEARINGS, DISTANCES, AND COORDINATE VALUES CONTAINED HEREIN ARE GRID BASED UPON THE NEW MEXICO COORDINATE SYSTEM, EAST ZONE, U.S. SURVEY FEET, NORTH AMERICAN DATUM 1983.
3. THIS WELL LOCATION SHOWN HEREON HAS BEEN SURVEYED ON THE GROUND UNDER MY SUPERVISION AND PREPARED ACCORDING TO THE EVIDENCE FOUND AT THE TIME OF SURVEY, AND DATA PROVIDED BY EOG RESOURCES, INC. THIS CERTIFICATION IS MADE AND LIMITED TO THOSE PERSONS OR ENTITIES SHOWN ON THE FACE OF THIS PLAT AND IS NON-TRANSFERABLE. THIS SURVEY IS CERTIFIED FOR THIS TRANSACTION ONLY.

Intent ☐ As Drilled ☐ XXX

API # 30-025-46734								
Operator Name: EOG RESOURCES, INC			Property Name: NEPTUNE 10 STATE COM			Well Number 204H		

Kick Off Point (KOP)

UL O	Section 10	Township 24S	Range 33E	Lot	Feet 46	From N/S SOUTH	Feet 1912	From E/W EAST	County LEA
Latitude 32.2249928					Longitude 103.5578417				NAD 1983

First Take Point (FTP)

UL O	Section 10	Township 24S	Range 33E	Lot	Feet 585	From N/S SOUTH	Feet 1963	From E/W EAST	County LEA
Latitude 32.2264753					Longitude 103.5580077				NAD 1983

Last Take Point (LTP)

UL B	Section 3	Township 24S	Range 33E	Lot	Feet 110	From N/S NORTH	Feet 2017	From E/W EAST	County LEA
Latitude 32.2535256					Longitude 103.5581889				NAD 1983

Is this well the defining well for the Horizontal Spacing Unit? ☐ NO

Is this well an infill well? ☐ YES

If infill is yes please provide API if available, Operator Name and well number for Defining well for Horizontal Spacing Unit.

API # 30-025-44464								
Operator Name: EOG RESOURCES, INC			Property Name: NEPTUNE 10 STATE COM			Well Number 102H		

KZ 06/29/2018



EOG Resources - Midland

Lea County, NM (NAD 83 NME)

Neptune 10 State Com

#204H

OH

Design: OH

Midland PVA

16 March, 2020



EOG Resources
Midland PVA

Company:	EOG Resources - Midland			Local Co-ordinate Reference:	Well #204H
Project:	Lea County, NM (NAD 83 NME)			TVD Reference:	KB 25 @ 3632.0usft
Site:	Neptune 10 State Com			MD Reference:	KB 25 @ 3632.0usft
Well:	#204H			North Reference:	Grid
Wellbore:	OH			Survey Calculation Method:	Minimum Curvature
Design:	OH			Database:	EDM

Project	Lea County, NM (NAD 83 NME)				
Map System:	US State Plane 1983	System Datum:	Mean Sea Level		
Geo Datum:	North American Datum 1983				
Map Zone:	New Mexico Eastern Zone				

Site	Neptune 10 State Com				
Site Position:		Northing:	446,557.00 usft	Latitude:	32° 13' 31.172 N
From:	Map	Easting:	778,984.00 usft	Longitude:	103° 33' 53.609 W
Position Uncertainty:	0.0 usft	Slot Radius:	13-3/16 "	Grid Convergence:	0.41 °

Well	#204H					
Well Position	+N-S	0.0 usft	Northing:	447,282.00 usft	Latitude:	32° 13' 38.126 N
	+E-W	0.0 usft	Easting:	782,054.00 usft	Longitude:	103° 33' 17.578 W
Position Uncertainty	0.0 usft	Wellhead Elevation:	usft	Ground Level:	3,607.0 usft	

Wellbore	OH				
Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	IGRF2015	2/9/2020	6.66	60.03	47,668.05640954

Design	OH				
Audit Notes:					
Version:	1.0	Phase:	ACTUAL	Tie On Depth:	0.0
Vertical Section:	Depth From (TVD) (usft)	+N-S (usft)	+E-W (usft)	Direction (°)	
	0.0	0.0	0.0	353.72	

Survey Program	Date	3/16/2020		
From (usft)	To (usft)	Survey (Wellbore)	Tool Name	Description
175.0	20,186.0	Prodirectional (OH)	EOG MWD+IFR1	MWD + IFR1



EOG Resources
Midland PVA

Company:	EOG Resources - Midland	Local Co-ordinate Reference:	Well #204H
Project:	Lea County, NM (NAD 83 NME)	TVD Reference:	KB 25 @ 3632.0usft
Site:	Neptune 10 State Com	MD Reference:	KB 25 @ 3632.0usft
Well:	#204H	North Reference:	Grid
Wellbore:	OH	Survey Calculation Method:	Minimum Curvature
Design:	OH	Database:	EDM

MD (usft)	Inc (°)	Azi (azimuth) (°)	TVD (usft)	N/S (usft)	E/W (usft)	DLeg (°/100usft)	Build (°/100usft)	Turn (°/100usft)	High to Plan (usft)	Right to Plan (usft)
0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.00	1.0	0.0
175.0	0.40	299.60	175.0	0.3	-0.5	0.23	0.23	0.00	-0.6	0.0
232.0	0.50	288.10	232.0	0.5	-0.9	0.24	0.18	-20.18	-1.0	-0.2
405.0	0.50	270.60	405.0	0.7	-2.4	0.09	0.00	-10.12	-2.4	-0.7
494.0	0.50	261.50	494.0	0.7	-3.2	0.09	0.00	-10.22	-3.1	-1.1
589.0	0.60	251.20	589.0	0.4	-4.1	0.15	0.11	-10.84	-3.7	-1.7
683.0	0.70	236.40	683.0	0.0	-5.0	0.21	0.11	-15.74	-4.2	-2.7
778.0	0.70	231.50	778.0	-0.7	-5.9	0.06	0.00	-5.16	-5.1	-3.1
872.0	0.40	234.90	872.0	-1.3	-6.7	0.32	-0.32	3.62	-6.2	-2.8
966.0	0.30	226.60	966.0	-1.6	-7.1	0.12	-0.11	-8.83	-6.3	-3.7
1,061.0	0.50	146.00	1,061.0	-2.1	-7.1	0.57	0.21	-84.84	2.2	-7.0
1,156.0	1.00	119.20	1,156.0	-2.9	-6.1	0.63	0.53	-28.21	3.9	-5.5
1,279.0	1.10	123.50	1,278.9	-4.1	-4.2	0.10	0.08	3.50	1.3	-5.7
1,423.0	0.60	233.20	1,422.9	-5.3	-3.6	0.99	-0.35	76.18	-6.1	2.0
1,518.0	1.20	224.80	1,517.9	-6.3	-4.7	0.64	0.63	-8.84	-7.7	1.1
1,614.0	4.40	232.60	1,613.8	-9.2	-8.4	3.35	3.33	8.12	-10.0	2.1
1,710.0	5.80	235.60	1,709.4	-14.2	-15.3	1.48	1.46	3.12	-13.1	2.3
1,806.0	7.90	244.50	1,804.7	-19.8	-25.3	2.44	2.19	9.27	-15.6	2.8
1,901.0	8.70	248.70	1,898.7	-25.2	-37.8	1.06	0.84	4.42	-18.0	0.6
2,091.0	9.20	250.40	2,086.4	-35.5	-65.5	0.30	0.26	0.89	-16.8	-10.0
2,185.0	10.90	243.50	2,179.0	-42.0	-80.6	2.21	1.81	-7.34	-11.6	-17.8
2,280.0	12.50	236.70	2,272.0	-51.7	-97.2	2.22	1.68	-7.16	-6.9	-22.7
2,374.0	14.00	230.70	2,363.5	-64.4	-114.5	2.16	1.60	-6.38	-4.5	-24.7
2,469.0	14.00	230.50	2,455.7	-79.0	-132.3	0.05	0.00	-0.21	-5.6	-25.1
2,563.0	13.80	231.80	2,546.9	-93.2	-149.9	0.39	-0.21	1.38	-7.2	-25.4
2,658.0	13.40	232.30	2,639.3	-106.9	-167.5	0.44	-0.42	0.53	-8.0	-26.3
2,752.0	13.10	231.80	2,730.7	-120.2	-184.5	0.34	-0.32	-0.53	-7.7	-27.2



EOG Resources
Midland PVA

Company:	EOG Resources - Midland	Local Co-ordinate Reference:	Well #204H
Project:	Lea County, NM (NAD 83 NME)	TVD Reference:	KB 25 @ 3632.0usft
Site:	Neptune 10 State Com	MD Reference:	KB 25 @ 3632.0usft
Well:	#204H	North Reference:	Grid
Wellbore:	OH	Survey Calculation Method:	Minimum Curvature
Design:	OH	Database:	EDM

Survey											
MD (usft)	Inc. (°)	Azi (azimuth) (°)	TVD (usft)	N/S (usft)	E/W (usft)	DLeg (°/100usft)	Build (°/100usft)	Turn (°/100usft)	High to Plan (usft)	Right to Plan (usft)	
2,847.0	12.50	232.30	2,823.4	-133.1	-201.1	0.64	-0.63	0.53	-7.2	-28.0	
2,942.0	12.00	232.70	2,916.2	-145.4	-217.0	0.53	-0.53	0.42	-5.7	-29.0	
3,132.0	14.00	226.90	3,101.4	-173.1	-249.5	1.26	1.05	-3.05	-1.9	-29.2	
3,226.0	13.30	226.30	3,192.7	-188.0	-265.9	0.82	-0.74	1.49	-3.2	-28.4	
3,321.0	12.70	226.60	3,285.3	-202.2	-281.9	0.64	-0.63	0.32	-2.9	-27.9	
3,416.0	12.10	229.00	3,378.0	-215.7	-297.3	0.64	-0.63	0.42	-1.7	-27.5	
3,510.0	12.60	228.80	3,469.9	-228.9	-312.4	0.53	0.53	-0.21	-0.1	-27.2	
3,605.0	14.00	223.00	3,562.3	-244.1	-328.0	2.03	1.47	-6.11	2.5	-25.5	
3,699.0	14.00	222.50	3,653.5	-260.8	-343.5	0.13	0.00	-0.53	1.3	-22.9	
3,793.0	13.30	222.60	3,744.9	-277.1	-358.5	0.75	-0.74	0.11	0.5	-20.2	
3,888.0	11.70	223.20	3,837.6	-292.2	-372.5	1.69	-1.68	0.63	1.5	-17.6	
3,982.0	12.70	221.40	3,929.5	-306.9	-385.8	1.14	1.06	-1.91	3.5	-14.7	
4,077.0	16.00	219.30	4,021.5	-324.9	-401.0	3.52	3.47	-2.21	1.9	-11.0	
4,171.0	15.60	219.30	4,112.0	-344.7	-417.2	0.43	-0.43	0.00	-2.6	-7.0	
4,266.0	14.10	218.70	4,203.8	-363.6	-432.6	1.59	-1.58	-0.63	-5.5	-3.0	
4,360.0	12.90	217.20	4,295.2	-380.9	-446.1	1.33	-1.28	-1.60	-6.3	1.2	
4,455.0	11.90	216.00	4,386.0	-397.3	-458.2	1.09	-1.05	-1.26	-5.5	6.0	
4,549.0	10.60	210.20	4,480.2	-412.6	-468.3	1.83	-1.38	-6.17	-3.9	11.7	
4,644.0	10.20	201.20	4,573.6	-428.0	-475.7	1.76	-0.42	-9.47	-3.5	20.0	
4,738.0	12.70	212.00	4,665.8	-444.5	-484.2	3.49	2.66	11.49	2.5	28.5	
4,833.0	12.50	211.20	4,758.5	-462.2	-495.1	0.28	-0.21	-0.84	2.1	35.3	
4,927.0	12.50	207.70	4,850.2	-479.9	-505.1	0.81	0.00	-3.72	-0.3	42.8	
5,022.0	12.20	201.00	4,943.0	-498.3	-513.4	1.54	-0.32	-7.05	-6.2	51.8	
5,116.0	11.50	197.70	5,035.0	-516.5	-519.9	1.04	-0.74	-3.51	-10.1	62.3	
5,192.0	10.10	198.50	5,109.7	-530.1	-524.3	1.85	-1.84	1.05	-8.6	71.5	
5,305.0	9.10	196.50	5,221.1	-548.0	-530.0	0.93	-0.88	-1.77	-8.2	85.1	
5,401.0	9.70	214.30	5,315.8	-562.0	-536.7	3.08	0.62	18.54	24.0	91.7	



EOG Resources
Midland PVA

Company: EOG Resources - Midland				Local Co-ordinate Reference: Well #204H			
Project: Lea County, NM (NAD 83 NME)				TVD Reference: KB 25 @ 3632.0usft			
Site: Neptune 10 State Com				MD Reference: KB 25 @ 3632.0usft			
Well: #204H				North Reference: Grid			
Wellbore: OH				Survey Calculation Method: Minimum Curvature			
Design: OH				Database: EDM			

Survey											
MD (usft)	Inc (°)	Azi (azimuth) (°)	TVD (usft)	N/S (usft)	E/W (usft)	DIeg (°/100usft)	Buld (°/100usft)	Turn (°/100usft)	High to Plan (usft)	Right to Plan (usft)	
5,497.0	13.30	228.00	5,409.9	-576.1	-549.4	4.68	3.75	14.27	48.0	86.2	
5,592.0	16.50	238.90	5,501.7	-590.4	-569.1	4.46	3.37	11.47	60.1	74.6	
5,688.0	17.30	241.00	5,593.6	-604.3	-593.3	1.05	0.83	2.19	56.2	68.7	
5,784.0	17.90	262.40	5,685.2	-613.2	-620.4	6.73	0.62	22.29	67.4	37.3	
5,880.0	17.70	238.70	5,776.7	-622.8	-647.5	7.50	-0.21	-24.69	40.6	51.5	
5,976.0	17.20	237.40	5,868.3	-638.0	-672.0	0.66	-0.52	-1.35	32.3	49.1	
6,072.0	17.90	236.00	5,959.8	-653.9	-696.2	0.85	0.73	-1.46	23.8	47.1	
6,168.0	18.20	234.40	6,051.1	-670.9	-720.6	0.60	0.31	-1.67	14.5	45.5	
6,262.0	17.50	234.00	6,140.6	-687.7	-744.0	0.76	-0.74	-0.43	6.7	43.9	
6,356.0	13.90	233.50	6,231.0	-702.7	-764.5	3.83	-3.83	-0.53	2.3	42.4	
6,451.0	13.20	232.40	6,323.4	-716.1	-782.2	0.79	-0.74	-1.16	1.1	41.2	
6,546.0	12.10	234.70	6,416.1	-728.5	-799.0	1.27	-1.16	2.42	3.6	39.7	
6,640.0	10.70	244.70	6,508.3	-737.9	-814.9	2.57	-1.49	10.64	12.9	34.6	
6,735.0	10.80	257.50	6,601.6	-743.6	-831.6	2.51	0.11	13.47	22.1	22.8	
6,830.0	10.90	256.30	6,694.9	-747.7	-849.0	0.26	0.11	-1.26	23.3	13.3	
6,925.0	11.00	255.30	6,788.2	-752.1	-866.5	0.23	0.11	-1.05	24.8	4.2	
7,020.0	8.60	249.60	6,881.8	-756.9	-881.9	2.72	-2.53	-6.00	28.8	-1.7	
7,115.0	7.60	245.80	6,975.8	-761.9	-894.3	1.19	-1.05	-4.00	36.4	-6.3	
7,209.0	5.40	225.90	7,069.2	-767.6	-903.1	3.32	-2.34	-21.17	45.2	5.4	
7,304.0	4.80	212.50	7,163.9	-774.0	-908.5	1.40	-0.63	-14.11	49.9	19.4	
7,399.0	4.70	213.50	7,258.5	-780.6	-912.8	0.14	-0.11	1.05	54.8	22.3	
7,493.0	5.30	204.60	7,352.2	-787.8	-916.7	1.04	0.64	-9.47	51.4	34.0	
7,588.0	5.50	201.10	7,446.8	-796.0	-920.2	0.41	0.21	-3.68	46.0	40.0	
7,682.0	1.40	171.20	7,540.6	-801.4	-921.6	4.62	-4.36	-31.81	16.6	58.2	
7,735.7	1.17	166.53	7,594.2	-802.6	-921.4	0.47	-0.43	-8.70	10.8	59.8	
Brushy Top (Neptune 10 St Com #204H)											
7,777.0	1.00	161.60	7,635.5	-803.3	-921.2	0.47	-0.41	-12.18	4.8	60.5	



EOG Resources
Midland PVA

Company:	EOG Resources - Midland	Local Co-ordinate Reference:	Well #204H
Project:	Lea County, NM (NAD 83 NME)	TVD Reference:	KB 25 @ 3632.0usft
Site:	Neptune 10 State Com	MD Reference:	KB 25 @ 3632.0usft
Well:	#204H	North Reference:	Grid
Wellbore:	OH	Survey Calculation Method:	Minimum Curvature
Design:	OH	Database:	EDM

MD (usft)	Inc (°)	Azi (azimuth) (°)	TVD (usft)	N/S (usft)	E/W (usft)	DLeg (°/100usft)	Build (°/100usft)	Turn (°/100usft)	High to Plan (usft)	Right to Plan (usft)
7,871.0	1.40	165.70	7,729.5	-805.2	-920.6	0.44	0.43	4.47	7.2	60.0
7,968.0	1.30	158.50	7,824.5	-807.3	-919.9	0.21	-0.11	-7.58	-2.6	60.3
8,061.0	1.30	154.40	7,919.5	-809.3	-919.1	0.10	0.00	-4.32	-9.1	59.9
8,155.0	1.20	155.60	8,013.5	-811.2	-918.2	0.11	-0.11	1.28	-9.9	60.1
8,250.0	1.30	146.40	8,108.4	-813.0	-917.2	0.24	0.11	-9.68	-21.4	57.6
8,344.0	1.30	153.60	8,202.4	-814.8	-916.1	0.17	0.00	7.66	-16.1	59.9
8,439.0	1.50	156.10	8,297.4	-816.9	-915.2	0.22	0.21	2.63	-15.8	60.6
8,534.0	1.70	151.60	8,392.3	-819.3	-914.0	0.25	0.21	-4.74	-23.2	59.1
8,628.0	1.50	150.20	8,486.3	-821.6	-912.7	0.22	-0.21	-1.49	-27.2	58.5
8,723.0	1.60	144.00	8,581.3	-823.7	-911.3	0.21	0.11	-6.53	-36.0	55.1
8,817.0	1.40	153.00	8,675.2	-825.8	-910.0	0.33	-0.21	9.57	-29.3	60.2
8,912.0	1.40	158.70	8,770.2	-827.9	-909.1	0.15	0.00	6.00	-25.5	63.0
9,007.0	1.00	150.40	8,865.2	-829.7	-908.2	0.46	-0.42	-8.74	-36.3	58.4
9,101.0	1.00	156.70	8,959.2	-831.2	-907.5	0.12	0.00	6.70	-31.3	62.2
9,196.0	0.50	172.60	9,054.2	-832.4	-907.1	0.57	-0.53	16.74	-14.3	68.6
9,290.0	0.40	225.40	9,148.2	-833.0	-907.3	0.44	-0.11	56.17	45.4	53.2
9,385.0	0.10	144.40	9,243.2	-833.3	-907.5	0.42	-0.32	-85.26	-45.6	52.8
9,474.0	4.72	336.48	9,332.1	-830.0	-908.9	5.42	5.20	-188.67	29.8	-61.3
KOP MD:9474.0', TVD:9332.1', N/S:-830.0', E/W:-908.9', INC:4.72										
9,516.0	7.00	336.40	9,373.8	-826.1	-910.6	5.42	5.42	-0.19	25.6	-61.2
9,611.0	22.80	350.50	9,465.4	-802.5	-916.0	16.94	16.63	14.84	-5.6	-62.7
9,670.6	28.08	358.89	9,519.2	-777.0	-918.2	10.71	8.86	14.08	-26.2	-59.7
FTP Crossing, MD:9670.6', TVD:9519.2', N/S:-777.0', E/W:-918.2', INC:28.08										
9,705.0	31.30	2.50	9,549.1	-760.0	-918.0	10.71	9.36	10.49	-36.3	-58.2
9,800.0	38.10	2.90	9,627.1	-706.0	-915.4	7.16	7.16	0.42	-52.7	-60.3
9,894.0	43.60	354.70	9,698.3	-644.7	-916.9	8.16	5.85	-8.72	-55.1	-65.0
9,961.1	50.17	352.49	9,744.1	-596.0	-922.4	10.07	9.78	-3.29	-57.5	-61.0
FTP (Neptune 10 St Com #204H)										



EOG Resources
Midland PVA

Company:	EOG Resources - Midland	Local Co-ordinate Reference:	Well #204H
Project:	Lea County, NM (NAD 83 NME)	TVD Reference:	KB 25 @ 3632.0usft
Site:	Neptune 10 State Com	MD Reference:	KB 25 @ 3632.0usft
Well:	#204H	North Reference:	Grid
Wellbore:	OH	Survey Calculation Method:	Minimum Curvature
Design:	OH	Database:	EDM

Survey											
MD (usft)	Inc (°)	Azi (azimuth) (°)	TVD (usft)	N/S (usft)	E/W (usft)	DLeg (°/100usft)	Build (°/100usft)	Turn (°/100usft)	High to Plan (usft)	Right to Plan (usft)	
9,989.0	52.90	351.70	9,761.5	-574.4	-925.4	10.07	9.82	-2.85	-58.4	-58.4	
10,084.0	59.60	351.40	9,814.2	-496.3	-937.1	7.06	7.05	-0.32	-59.5	-46.4	
10,179.0	59.30	350.80	9,862.5	-415.5	-949.7	0.63	-0.32	-0.63	-47.8	-33.5	
10,272.0	69.50	354.20	9,902.6	-332.5	-960.5	11.45	10.97	3.66	-29.0	-21.0	
10,367.0	80.00	355.80	9,927.6	-241.3	-968.5	11.17	11.05	1.68	-10.2	-13.0	
10,461.0	90.80	355.20	9,935.1	-148.0	-975.8	11.51	11.49	-0.64	-2.5	-6.2	
10,556.0	90.60	357.90	9,934.0	-53.2	-981.5	2.85	-0.21	2.84	-3.4	-1.2	
10,650.0	88.10	359.30	9,935.0	40.8	-983.8	3.05	-2.66	1.49	-2.1	0.4	
10,745.0	88.30	358.70	9,938.0	135.7	-985.5	0.67	0.21	-0.63	1.2	1.4	
10,840.0	87.60	358.80	9,941.4	230.6	-987.6	0.74	-0.74	0.11	4.8	2.7	
10,934.0	87.30	358.40	9,945.6	324.5	-989.9	0.53	-0.32	-0.43	9.3	4.3	
11,029.0	86.80	358.00	9,950.5	419.3	-992.8	0.67	-0.53	-0.42	14.4	6.6	
11,123.0	89.40	358.50	9,953.6	513.2	-995.7	2.82	2.77	0.53	17.8	8.8	
11,218.0	89.70	358.60	9,954.3	608.2	-998.1	0.33	0.32	0.11	18.8	10.5	
11,313.0	89.70	358.60	9,954.8	703.2	-1,000.4	0.00	0.00	0.00	19.6	12.1	
11,408.0	89.80	358.70	9,955.3	798.1	-1,002.7	0.15	0.11	0.11	20.3	13.6	
11,503.0	89.80	358.80	9,955.6	893.1	-1,004.7	0.11	0.00	0.11	20.9	15.0	
11,598.0	89.60	358.80	9,956.1	988.1	-1,006.7	0.21	-0.21	0.00	21.6	16.3	
11,692.0	89.70	359.10	9,956.7	1,082.1	-1,008.5	0.34	0.11	0.32	22.5	17.3	
11,787.0	90.20	359.10	9,956.7	1,177.1	-1,009.9	0.53	0.53	0.00	22.8	18.1	
11,882.0	90.50	359.30	9,956.2	1,272.0	-1,011.3	0.38	0.32	0.21	22.5	18.7	
11,976.0	90.90	359.70	9,955.0	1,366.0	-1,012.1	0.60	0.43	0.43	21.6	18.9	
12,071.0	91.40	0.00	9,953.1	1,461.0	-1,012.3	0.61	0.53	0.32	20.0	18.4	
12,165.0	88.60	0.40	9,953.1	1,555.0	-1,012.0	3.01	-2.98	0.43	20.2	17.4	
12,260.0	88.50	0.00	9,955.5	1,650.0	-1,011.7	0.43	-0.11	-0.42	22.9	16.3	
12,354.0	88.90	0.00	9,957.6	1,743.9	-1,011.7	0.43	0.43	0.00	25.3	15.6	
12,449.0	89.80	359.70	9,958.7	1,838.9	-1,011.9	1.00	0.95	-0.32	26.7	15.2	



EOG Resources
Midland PVA

Company:	EOG Resources - Midland	Local Co-ordinate Reference:	Well #204H
Project:	Lea County, NM (NAD 83 NME)	TVD Reference:	KB 25 @ 3632.0usft
Site:	Neptune 10 State Com	MD Reference:	KB 25 @ 3632.0usft
Well:	#204H	North Reference:	Grid
Wellbore:	OH	Survey Calculation Method:	Minimum Curvature
Design:	OH	Database:	EDM

MD (usft)	Inc (°)	Azi (azimuth) (°)	TVD (usft)	N/S (usft)	E/W (usft)	DLeg (°/100usft)	Build (°/100usft)	Turn (°/100usft)	High to Plan (usft)	Right to Plan (usft)
12,472.5	89.40	359.58	9,958.9	1,862.5	-1,012.1	1.76	-1.68	-0.53	26.9	15.2
TGT#1(Neptune 10 St Com #204H)										
12,544.0	88.20	359.20	9,960.4	1,933.9	-1,012.8	1.76	-1.68	-0.53	28.7	15.4
12,639.0	88.70	358.80	9,963.0	2,028.9	-1,014.5	0.67	0.53	-0.42	31.8	16.4
12,733.0	89.00	358.50	9,964.8	2,122.8	-1,016.7	0.45	0.32	-0.32	34.1	17.9
12,828.0	91.00	359.20	9,964.8	2,217.8	-1,018.6	2.23	2.11	0.74	34.6	19.1
12,922.0	91.10	359.30	9,963.1	2,311.8	-1,019.9	0.15	0.11	0.11	33.4	19.6
13,017.0	91.30	359.20	9,961.1	2,406.7	-1,021.1	0.24	0.21	-0.11	31.9	20.1
13,111.0	91.10	359.50	9,959.2	2,500.7	-1,022.2	0.38	-0.21	0.32	30.4	20.5
13,204.0	90.70	359.30	9,957.7	2,593.7	-1,023.1	0.48	-0.43	-0.22	29.4	20.8
13,299.0	91.10	359.40	9,956.2	2,688.7	-1,024.2	0.43	0.42	0.11	28.4	21.2
13,393.0	91.60	359.20	9,954.0	2,782.6	-1,025.4	0.57	0.53	-0.21	26.6	21.6
13,487.0	92.10	358.20	9,951.0	2,876.6	-1,027.5	1.19	0.53	-1.06	24.1	23.1
13,582.0	92.90	358.50	9,946.8	2,971.4	-1,030.2	0.90	0.84	0.32	20.4	25.1
13,676.0	92.40	359.80	9,942.5	3,065.3	-1,031.6	1.48	-0.53	1.38	16.5	25.8
13,771.0	90.40	0.00	9,940.1	3,160.3	-1,031.8	2.12	-2.11	0.21	14.7	25.3
13,866.0	90.40	359.30	9,939.5	3,255.3	-1,032.4	0.74	0.00	-0.74	14.5	25.1
13,961.0	90.50	359.00	9,938.7	3,350.3	-1,033.8	0.33	0.11	-0.32	14.2	25.8
14,055.0	91.00	358.90	9,937.5	3,444.3	-1,035.5	0.54	0.53	-0.11	13.5	26.9
14,150.0	90.50	0.30	9,936.3	3,539.2	-1,036.2	1.56	-0.53	1.47	12.7	26.8
14,244.0	89.20	1.10	9,936.5	3,633.2	-1,035.0	1.62	-1.38	0.85	13.4	25.0
14,339.0	89.10	0.90	9,937.9	3,728.2	-1,033.4	0.24	-0.11	-0.21	15.3	22.6
14,433.0	89.10	0.80	9,939.4	3,822.2	-1,032.0	0.11	0.00	-0.11	17.3	20.5
14,460.4	89.24	0.89	9,939.8	3,849.5	-1,031.6	0.61	0.53	0.32	17.8	19.9
TGT#2(Neptune 10 St Com #204H)										
14,528.0	89.60	1.10	9,940.5	3,917.2	-1,030.4	0.61	0.53	0.32	18.2	18.2
14,623.0	90.20	0.60	9,940.6	4,012.2	-1,029.0	0.82	0.63	-0.53	17.8	16.1



EOG Resources
Midland PVA

Company:	EOG Resources - Midland	Local Co-ordinate Reference:	Well #204H
Project:	Lea County, NM (NAD 83 NME)	TVD Reference:	KB 25 @ 3632.0usft
Site:	Neptune 10 State Com	MD Reference:	KB 25 @ 3632.0usft
Well:	#204H	North Reference:	Grid
Wellbore:	OH	Survey Calculation Method:	Minimum Curvature
Design:	OH	Database:	EDM

Survey											
MD (usft)	Inc (°)	Azi (azimuth) (°)	TVD (usft)	N/S (usft)	E/W (usft)	DLeg (°/100usft)	Build (°/100usft)	Turn (°/100usft)	High to Plan (usft)	Right to Plan (usft)	
14,717.0	89.80	0.00	9,940.6	4,106.2	-1,028.5	0.77	-0.43	-0.64	17.1	15.0	
14,812.0	88.40	0.30	9,942.1	4,201.1	-1,028.2	1.51	-1.47	0.32	18.0	14.0	
14,907.0	87.90	0.50	9,945.2	4,296.1	-1,027.6	0.57	-0.53	0.21	20.4	12.6	
15,002.0	87.80	0.30	9,948.8	4,391.0	-1,026.9	0.24	-0.11	-0.21	23.4	11.3	
15,097.0	87.90	0.50	9,952.3	4,485.9	-1,026.2	0.24	0.11	0.21	26.3	9.9	
15,191.0	90.10	0.30	9,954.0	4,579.9	-1,025.6	2.35	2.34	-0.21	27.3	8.5	
15,286.0	90.00	0.10	9,953.9	4,674.9	-1,025.3	0.24	-0.11	-0.21	26.6	7.5	
15,380.0	89.80	359.60	9,954.0	4,768.9	-1,025.5	0.57	-0.21	-0.53	26.1	7.1	
15,475.0	90.50	0.20	9,953.8	4,863.9	-1,025.7	0.97	0.74	0.63	25.3	6.5	
15,569.0	90.50	1.00	9,953.0	4,957.9	-1,024.7	0.85	0.00	0.85	23.8	4.8	
15,664.0	90.00	1.40	9,952.6	5,052.9	-1,022.7	0.67	-0.53	0.42	22.8	2.2	
15,757.0	90.20	2.10	9,952.4	5,145.8	-1,019.9	0.78	0.22	0.75	22.0	-1.4	
15,851.0	90.30	2.20	9,952.0	5,239.8	-1,016.3	0.15	0.11	0.11	21.0	-5.6	
15,946.0	88.50	359.80	9,953.0	5,334.7	-1,014.7	3.16	-1.89	-2.53	21.3	-8.0	
15,996.1	88.66	0.17	9,954.2	5,384.9	-1,014.7	0.80	0.32	0.74	22.2	-8.3	
TGT#3(Neptune 10 St Com #204H)											
16,041.0	88.80	0.50	9,955.2	5,429.7	-1,014.4	0.80	0.32	0.74	22.7	-8.9	
16,135.0	88.60	0.40	9,957.4	5,523.7	-1,013.7	0.24	-0.21	-0.11	23.4	-10.3	
16,229.0	87.90	0.00	9,960.2	5,617.6	-1,013.4	0.86	-0.74	-0.43	24.9	-11.4	
16,324.0	88.40	0.00	9,963.3	5,712.6	-1,013.4	0.53	0.53	0.00	26.6	-12.1	
16,418.0	88.50	0.10	9,965.8	5,806.6	-1,013.3	0.15	0.11	0.11	27.8	-12.8	
16,513.0	88.70	359.40	9,968.2	5,901.5	-1,013.7	0.77	0.21	-0.74	28.7	-13.1	
16,607.0	88.80	358.60	9,970.2	5,995.5	-1,015.3	0.86	0.11	-0.85	29.4	-12.2	
16,688.0	88.12	357.92	9,972.4	6,076.5	-1,017.8	1.19	-0.84	-0.84	30.4	-10.3	
TGT#4(Neptune 10 St Com #204H)											
16,702.0	88.00	357.80	9,972.9	6,090.4	-1,018.3	1.19	-0.84	-0.84	30.7	-9.9	
16,796.0	89.80	356.60	9,974.7	6,184.3	-1,022.9	2.30	1.91	-1.28	32.4	-6.0	



EOG Resources
Midland PVA

Company:	EOG Resources - Midland	Local Co-ordinate Reference:	Well #204H
Project:	Lea County, NM (NAD 83 NME)	TVD Reference:	KB 25 @ 3632.0usft
Site:	Neptune 10 State Com	MD Reference:	KB 25 @ 3632.0usft
Well:	#204H	North Reference:	Grid
Wellbore:	OH	Survey Calculation Method:	Minimum Curvature
Design:	OH	Database:	EDM

MD (usft)	Inc (°)	Azi (azimuth) (°)	TVD (usft)	N/S (usft)	E/W (usft)	DLeg (°/100usft)	Build (°/100usft)	Turn (°/100usft)	High to Plan (usft)	Right to Plan (usft)
16,891.0	92.10	356.60	9,973.1	6,279.1	-1,026.5	2.42	2.42	0.00	30.8	-1.1
16,986.0	92.20	356.00	9,969.5	6,373.8	-1,034.7	0.64	0.11	-0.63	27.3	4.4
17,080.0	92.00	356.50	9,966.1	6,467.6	-1,040.8	0.57	-0.21	0.53	23.8	9.8
17,175.0	92.00	356.20	9,962.8	6,562.3	-1,046.8	0.32	0.00	-0.32	20.6	15.1
17,269.0	91.50	356.70	9,959.9	6,656.1	-1,052.7	0.75	-0.53	0.53	17.7	20.3
17,364.0	91.40	359.00	9,957.5	6,751.0	-1,056.2	2.42	-0.11	2.42	15.3	23.2
17,459.0	91.50	359.10	9,955.1	6,845.9	-1,057.8	0.15	0.11	0.11	12.9	24.0
17,553.0	88.90	357.60	9,954.8	6,939.9	-1,060.5	3.19	-2.77	-1.60	12.6	26.1
17,647.0	89.50	358.10	9,956.1	7,033.8	-1,064.0	0.83	0.64	0.53	13.9	28.9
17,742.0	89.10	357.10	9,957.2	7,128.7	-1,068.0	1.13	-0.42	-1.05	15.1	32.2
17,836.0	91.90	357.50	9,956.4	7,222.6	-1,072.4	3.01	2.98	0.43	14.3	34.0
17,931.0	91.80	357.30	9,953.3	7,317.5	-1,076.7	0.24	-0.11	-0.21	11.2	33.3
18,026.0	92.20	356.80	9,950.0	7,412.3	-1,081.6	0.67	0.42	-0.53	7.9	33.0
18,121.0	93.00	356.40	9,945.7	7,507.0	-1,087.3	0.94	0.84	-0.42	3.6	33.4
18,215.0	91.30	356.90	9,942.2	7,600.8	-1,092.8	1.89	-1.81	0.53	0.1	33.7
18,310.0	92.10	356.70	9,939.4	7,695.6	-1,098.1	0.87	0.84	-0.21	-2.7	33.8
18,404.0	92.70	356.60	9,935.4	7,789.3	-1,103.5	0.65	0.64	-0.11	-6.6	34.2
18,499.0	90.80	358.50	9,932.5	7,884.2	-1,107.6	2.83	-2.00	2.00	-9.6	33.0
18,593.0	89.50	358.90	9,932.3	7,978.2	-1,109.7	1.45	-1.38	0.43	-9.8	30.0
18,687.0	89.80	359.10	9,932.9	8,072.2	-1,111.4	0.38	0.32	0.21	-9.2	26.4
18,782.0	90.10	358.90	9,932.9	8,167.1	-1,113.0	0.38	0.32	-0.21	-9.1	22.9
18,876.0	90.30	358.80	9,932.6	8,261.1	-1,114.9	0.24	0.21	-0.11	-9.5	19.6
18,970.0	89.50	357.90	9,932.8	8,355.1	-1,117.6	1.28	-0.85	-0.96	-9.3	17.2
19,065.0	90.90	358.40	9,932.5	8,450.0	-1,120.7	1.56	1.47	0.53	-9.6	15.0
19,159.0	91.30	357.50	9,930.6	8,543.9	-1,124.1	1.05	0.43	-0.96	-11.4	13.2
19,254.0	88.80	359.00	9,930.6	8,638.9	-1,127.0	3.07	-2.63	1.58	-11.5	10.9
19,348.0	89.30	359.50	9,932.1	8,732.9	-1,128.2	0.75	0.53	0.53	-9.9	7.0



EOG Resources
Midland PVA

Company:	EOG Resources - Midland	Local Co-ordinate Reference:	Well #204H
Project:	Lea County, NM (NAD 83 NME)	TVD Reference:	KB 25 @ 3632.0usft
Site:	Neptune 10 State Com	MD Reference:	KB 25 @ 3632.0usft
Well:	#204H	North Reference:	Grid
Wellbore:	OH	Survey Calculation Method:	Minimum Curvature
Design:	OH	Database:	EDM

MD (usft)	Inc (°)	Azi (azimuth) (°)	TVD (usft)	N/S (usft)	E/W (usft)	DLeg (°/100usft)	Build (°/100usft)	Turn (°/100usft)	High to Plan (usft)	Right to Plan (usft)
19,442.0	89.70	2.60	9,932.9	8,826.8	-1,126.5	3.33	0.43	3.30	-9.1	0.4
19,501.1	89.76	2.35	9,933.2	8,885.9	-1,123.9	0.43	0.11	-0.42	-8.8	-3.8
AC TGT (Neptune 10 St Com #204H)										
19,537.0	89.80	2.20	9,933.4	8,921.8	-1,122.5	0.43	0.11	-0.42	-8.7	-5.6
19,632.0	90.10	1.60	9,933.4	9,016.7	-1,119.3	0.71	0.32	-0.63	-8.6	-7.6
19,726.0	90.40	1.50	9,933.0	9,110.7	-1,116.8	0.34	0.32	-0.11	-9.0	-5.8
19,821.0	88.20	3.60	9,934.2	9,205.6	-1,112.6	3.20	-2.32	2.21	-7.8	-2.3
19,915.0	88.30	3.90	9,937.1	9,299.3	-1,106.4	0.34	0.11	0.32	-5.0	2.4
20,010.0	88.50	3.70	9,939.7	9,394.1	-1,100.1	0.30	0.21	-0.21	-2.3	10.2
20,105.0	88.90	3.10	9,941.9	9,488.9	-1,094.5	0.76	0.42	-0.63	-0.2	22.0
Last MWD Survey (MD=20105.0)										
20,186.0	88.90	3.10	9,943.4	9,569.7	-1,090.1	0.00	0.00	0.00	1.3	34.8
Projection to Bit (MD=20186.0) - PBHL (Neptune 10 St Com #204H)										

Design Annotations				
Measured Depth (usft)	Vertical Depth (usft)	Local Coordinates		Comment
		+N/-S (usft)	+E/-W (usft)	
9,474.0	9,332.1	-830.0	-908.9	KOP, MD:9474.0, TVD:9332.1, N/S:-830.0, E/W:-908.9, INC:4.72
9,670.6	9,519.2	-777.0	-918.2	FTP Crossing, MD:9670.6, TVD:9519.2, N/S:-777.0, E/W:-918.2, INC:28.08
20,105.0	9,941.9	9,488.9	-1,094.5	Last MWD Survey (MD=20105.0)
20,186.0	9,943.4	9,569.7	-1,090.1	Projection to Bit (MD=20186.0)

Checked By: _____ Approved By: _____ Date: _____

I certify this survey to be true and correct to the best of my belief and knowledge.

Kay Maddox 11/18/2020
Signed Date



Lea County, NM (NAD 83 NME)

Neptune 10 State Com

#204H

Plan #1

PROJECT DETAILS: Lea County, NM (NAD 83 NME)

Geodetic System: US State Plane 1983
Datum: North American Datum 1983
Ellipsoid: GRS 1980
Zone: New Mexico Eastern Zone
System Datum: Mean Sea Level



Azinuths to Grid North
True North: -0.42°
Magnetic North: 6.24°

Magnetic Field
Strength: 47668.1nT
Dip Angle: 60.03°
Date: 2/9/2020
Model: IGRF2015

To convert a Magnetic Direction to a Grid Direction, Add 6.24°
To convert a Magnetic Direction to a True Direction, Add 6.66° East
To convert a True Direction to a Grid Direction, Subtract 0.42°

WELL DETAILS: #204H






3507.0
KB = 25 @ 3531.0usft
Northing 447282.00
Easting 762054.00
Latitude 32° 33' 38.126 N
Longitude 103° 33' 17.578 W
Slot

SECTION DETAILS

Sec	MD	Inc	Azi	TVD	+N/-S	+E/-W	Dleg	TFace	Vsect	Target
1	0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.0	
2	1500.0	0.00	0.00	1500.0	0.0	0.0	0.00	0.00	0.0	
3	2103.6	13.27	229.75	2157.7	-45.4	-58.4	2.00	229.75	-42.8	
4	7072.3	13.27	229.75	6835.3	-777.6	-918.6	0.00	0.00	-872.3	
5	7736.0	0.00	0.00	7593.0	-827.0	-977.0	2.00	180.00	-715.1	Brushy Top(Neptune 10 St Com #204H)
6	9507.0	0.00	0.00	9364.0	-827.0	-977.0	0.00	0.00	-715.1	
7	10408.6	90.16	359.58	9937.0	-252.4	-981.3	10.00	359.58	-143.5	TGT#1(Neptune 10 St Com #204H)
8	12924.2	90.16	359.58	9931.0	188.31	-996.5	0.00	0.00	1901.0	TGT#2(Neptune 10 St Com #204H)
9	12530.6	90.29	359.58	9931.0	188.9	-997.0	2.00	0.00	1967.4	TGT#3(Neptune 10 St Com #204H)
10	14510.8	90.29	359.58	9921.0	3849.4	-1011.6	0.00	0.00	3937.0	TGT#4(Neptune 10 St Com #204H)
11	14544.0	89.62	359.58	9921.0	3882.8	-1011.9	2.00	-180.00	3970.3	
12	16046.6	89.62	359.58	9931.0	5385.4	-1023.0	0.00	0.00	5465.0	
13	16069.4	89.16	359.58	9931.2	5408.2	-1023.2	2.00	-180.00	5487.7	
14	16738.3	89.16	359.58	9941.0	6077.0	-1028.1	0.00	0.00	6153.0	
15	16780.6	90.01	359.58	9941.3	6119.3	-1028.4	2.00	0.29	6195.1	
16	17780.6	90.01	359.58	9941.1	7119.3	-1035.8	0.00	0.00	7189.9	
17	17916.9	90.00	359.58	9941.1	7255.5	-1040.0	2.00	-90.17	7325.7	
18	19447.7	90.00	359.58	9941.1	8784.0	-1124.0	0.00	0.00	8854.3	
19	20200.0	90.01	12.48	9941.0	9531.4	-1063.0	2.08	89.98	9590.5	
20	20241.5	90.01	12.48	9941.0	9572.0	-1054.0	0.00	0.00	9628.9	PBHL (Neptune 10 St Com #204H)

WELLBORE TARGET DETAILS (MAP CO-ORDINATES)

Name	TVD	+N/-S	+E/-W	Northing	Easting	Shape
Brushy Top(Neptune 10 St Com #204H)	7593.0	-827.0	-977.0	446456.00	761077.00	Polygon
TGT#1(Neptune 10 St Com #204H)	9921.0	3849.4	-1011.6	451131.40	761042.37	Point
TGT#2(Neptune 10 St Com #204H)	9931.0	1883.1	-996.5	449445.10	761057.09	Point
TGT#3(Neptune 10 St Com #204H)	9931.0	5385.4	-1023.0	452667.40	761031.00	Point
FTP (Neptune 10 St Com #204H)	9937.0	-777.0	-977.0	446508.00	761077.00	Point
PBHL (Neptune 10 St Com #204H)	9941.0	9572.0	-1054.0	453559.00	761025.58	Point
TGT#4(Neptune 10 St Com #204H)	9941.0	6077.0	-1028.1	453559.00	761025.58	Point
AC TGT (Neptune 10 St Com #204H)	9941.1	8886.0	-1126.2	456167.99	760927.90	Circle (Radius: 15.0)



Lea County, NM (NAD 83 NME)
Neptune 10 State Com
#204H
Plan #1