

OCD-HOBBS  
HOBBS OCD

FORM APPROVED  
OMB No. 1004-0137  
Expires July 31, 2010

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

DEC 05 2011


APPLICATION FOR PERMIT TO DRILL OR REENTER

RECEIVED

1a. Type of work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER		5. Lease Serial No. NMLC029405B	
1b. Type of Well: <input checked="" type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Other <input type="checkbox"/> Single Zone <input type="checkbox"/> Multiple Zone		6. If Indian, Allottee or Tribe Name	
2. Name of Operator ConocoPhillips Company		7. If Unit or CA Agreement, Name and No.	
3a. Address 3300 N "A" St, Bldg 6 Midland, TX 79705		8. Lease Name and Well No. <b>&lt;38653&gt;</b> Ruby Federal 9	
3b. Phone No. (include area code) (432)688-6913		9. API Well No. 30-025- 40360	
4. Location of Well (Report location clearly and in accordance with any State requirements.) At surface 480 FSL 1650 FEL UL O, Sec 18, T 17S, R 32E At proposed prod. zone		10. Field and Pool, or Exploratory Maljamar, Yeso, West	
14. Distance in miles and direction from nearest town or post office* 4.5 Miles south of Maljamar, NM		11. Sec., T. R. M. or Blk. and Survey or Area Sec. 18, T17S, R32E	
15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) 480' FSL		12. County or Parish Lea	
16. No. of acres in lease 1601.9		13. State NM	
17. Spacing Unit dedicated to this well 40		18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft. 576' From Michell "B" #20	
19. Proposed Depth 6934'		20. BLM/BIA Bond No. on file ES0085	
21. Elevations (Show whether DF, KDB, RT, GL, etc.) 3964' GL		22. Approximate date work will start* 01/11/2012	
23. Estimated duration 10 days		24. Attachments	

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No.1, must be attached to this form:

- |  |   |
|--|---|
| 1. Well plat certified by a registered surveyor.   | 4. Bond to cover the operations-unless covered by an existing bond on file (see Item 20 above). |
| 2. A Drilling Plan.  | 5. Operator certification   |
| 3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO must be filed with the appropriate Forest Service Office). | 6. Such other site specific information and/or plans as may be required by the BLM.             |

25. Signature 	Name (Printed/Typed) Brian D Maiorino	Date 10/10/2011
---	--	--------------------

Title Regulatory Specialist		
--------------------------------	--	--

Approved by (Signature) /s/ Don Peterson	Name (Printed/Typed)	Date NOV 30 2011
---	----------------------	---------------------

Title FIELD MANAGER	Office CARLSBAD FIELD OFFICE
------------------------	---------------------------------

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.  
Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

APPROVAL FOR TWO YEARS

(Continued on page 2)

\*(Instructions on page 2)

Roswell Controlled Water Basin

Ka  
12/8/11

SEE ATTACHED FOR  
CONDITIONS OF APPROVAL

APPROVAL SUBJECT TO  
GENERAL REQUIREMENTS  
AND SPECIAL STIPULATIONS  
ATTACHED

DISTRICT I  
1625 N. French Dr., Hobbs, NM 88240

DISTRICT II  
1901 W. Grand Avenue, Artesia, NM 88210

DISTRICT III  
1000 Rio Brazos Ed., Artesia, NM 87410

DISTRICT IV  
1820 S. St. Francis Dr., Santa Fe, NM 87505

State of New Mexico  
Energy, Minerals & Natural Resources Department

OIL CONSERVATION DIVISION  
1220 South St. Frances Dr. HOBBS OCD  
Santa Fe, NM 87505

Form C-102  
Revised October 12, 2005  
Submit to Appropriate District Office  
State Lease - 4 Copies  
Fee Lease - 3 Copies

DEC 05 2011

☐ AMENDED REPORT

WELL LOCATION AND ACREAGE DEDICATION PLAT

API Number 30-025-40360	Pool Code 44500	Pool Name Maljano: 1/250, west
Property Code 38653	Property Name RUBY FEDERAL	Well Number 9
OGRID No. 217817	Operator Name CONOCOPHILLIPS	Elevation 3965'

Surface Location

UL or lot No.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
0	18	17 S	32 E		480	SOUTH	1650	EAST	LEA

Bottom Hole Location If Different From Surface

UL or lot No.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
Dedicated Acres 4.0	Joint or Infill	Consolidation Code	Order No.						

NO ALLOWABLE WILL BE ASSIGNED TO THIS COMPLETION UNTIL ALL INTERESTS HAVE BEEN CONSOLIDATED OR A NON-STANDARD UNIT HAS BEEN APPROVED BY THE DIVISION

<p>NOTE:</p> <p>1) Plane Coordinates shown hereon are Transverse Mercator Grid and Conform to the "New Mexico Coordinate System", New Mexico East Zone, North American Datum of 1927. Distances shown hereon are mean horizontal surface values.</p>	<p>OPERATOR CERTIFICATION</p> <p>I hereby certify the information contained herein is true and complete to the best of my knowledge and belief, and that this organization either owns a working interest or unleased mineral interest in the land including the proposed bottom hole location or has a right to drill this well at this location pursuant to a contract with an owner of such a mineral or working interest, or to a voluntary pooling agreement or a compulsory pooling order heretofore entered by the division.</p> <p><u>B. J. J.</u> 10/6/11 Signature Date</p> <p><u>Brian Maljano</u> Printed Name</p>
	<p>SURVEYOR CERTIFICATION</p> <p>I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision and that the same is true and correct to the best of my belief.</p> <p>September 14, 2011</p> <p>Date of Survey</p> <p>Signature &amp; Seal of Professional Surveyor</p> <p>W.O. Num.: 2011-1371</p> <p>Certificate No. 12185</p>

Plane Coordinates  
X = 663,191.9  
Y = 665,572.8

3967.7' 3971.5' 1650' 3958.4' 3966.5' 480'

Drilling Plan  
ConocoPhillips Company  
Maljamar; Yeso, west

Ruby Federal #9

Lea County, New Mexico

HOBBS OCD

DEC 05 2011

RECEIVED

**1. Estimated tops of geological markers and estimated depths to water, oil, or gas formations:**

The ranges of depths for the formation tops, thicknesses, and planned Total Depths for all the wells to be drilled under this Master Drilling Plan are presented in the table below.

The datum for these depths is RKB (which is 14' above Ground Level).

Formations	Top Depths FT MD	Contents
Quaternary	Surface	Fresh Water
Rustler	677	Anhydrite
Salado (top of salt)	849	Salt
Tansill (base of salt)	1859	Gas, Oil and Water
Yates	2041	Gas, Oil and Water
Seven Rivers	2368	Gas, Oil and Water
Queen	2988	Gas, Oil and Water
Grayburg	3390	Gas, Oil and Water
San Andres	3752	Gas, Oil and Water
Glorieta	5264	Gas, Oil and Water
Paddock	5341	Gas, Oil and Water
Blinberry	5665	Gas, Oil and Water
Tubb	6744	Gas, Oil and Water
Deepest estimated perforation	6618 – 6820	Deepest estimated perforation is ~ 10' above Top of Tubb
Total Depth (maximum)	6934	200' below deepest estimated perforation

All of the water bearing formations identified above will be protected by setting of the 8-5/8" surface casing 25' – 70' into the Rustler formation and circulating of cement from casing shoe to surface in accordance with the provisions of Onshore Oil and Gas Order No. 2 and New Mexico Oil Conservation Division Title 19.

The targeted oil and gas bearing formations identified above protected by setting of the 5-1/2" production casing 10' off bottom of TD and circulating of cement from casing shoe to surface in accordance with the provisions of Onshore Oil and Gas Order No. 2 and New Mexico Oil Conservation Division Title 19.

## 2. Proposed casing program:

Type	Hole Size (in)	Interval MD RKB (ft)		OD (inches)	Wt (lb/ft)	Gr	Conn	Condition	Safety Factors Calculated per BLM Load Formulas		
		From	To						Burst	Collapse	Tension Dry/Buoyant
Cond	20"	0	40' – 85' (30' – 75' BGL)	16"	0.5" wall	B	Line Pipe	New	NA	NA	NA
Alt. Cond	20"	0	40' – 85' (30' – 75' BGL)	13-3/8"	48#	H-40	PE	New	NA	NA	NA
Surf	12-1/4"	0	702'-747'	8-5/8"	24#	J-55	STC	New	7.98	3.63	11.9 / 13.6
Prod	7-7/8"	0	6879-6924'	5-1/2"	17#	L-80	LTC	New	2.46	1.71	2.81 / 3.32

The casing will be suitable for H<sub>2</sub>S Service.

The surface and production casing will be set approximately 10' off bottom and we will drill the hole with a 45' range uncertainty for casing set depth to fit the casing string so that the cementing head is positioned at the floor for the cement job.

The production casing will be set 155' to 200' below the deepest estimated perforation to provide rathole for the pumping completion and for the logs to get deep enough to log the interval of interest.

### 3. Proposed cementing program:

#### 16" or 13-3/8" Conductor:

Cement to surface with rathole mix, ready mix or Class C Neat cement.

(Note: The gravel used in the cement is not to exceed 3/8" dia)

TOC at surface.

#### 8-5/8" Surface Casing:

The intention for the cementing program for the Surface Casing is to:

- Place the Tail Slurry from the casing shoe to 300' above the casing shoe,
- Bring the Lead Slurry to surface.

Spacer: 20 bbls Fresh Water

Slurry		Intervals Ft MD		Excess %	Sx	Vol Cuft	Additives	Yield ft <sup>3</sup> /sx
Lead	Class C	Surface	486' – 531'	170	350	<del>598</del> 586	4%Bentonite 2%CaCl2 .125%Polyflake .2% antifoam Excess =130%	1.68
Tail	Class C	486' – 531'	786'-831'	100	200	<del>264</del> 268	1% CaCl2 Excess = 100%	1.34

Displacement: Fresh Water with approximately 250 ppm gluteraldehyde biocide.

**Note: In accordance with the Pecos District Conditions of Approval, we will Wait on Cement (WOC) for a period of not less than 18 hrs after placement or until at least 500 psi compressive strength has been reached in both the Lead Slurry and Tail Slurry cements on the Surface Casing, whichever is greater.**

#### 5-1/2" Production Casing Cementing Program:

The intention for the cementing program for the Production Casing is to:

- Place the Tail Slurry from the casing shoe to a point approximately 200' above the top of the Paddock,
- Bring the Lead Slurry to surface.

Spacer: 20 bbls Fresh Water

Slurry		Intervals Ft MD		Excess %	Sx	Vol Cuft	Additives	Yield ft <sup>3</sup> /sx
Lead	50:50 Poz/C	Surface	5181' – 5311'	15	1000	<del>464</del> 2640	10% Bentonite 8 lbs/sx Salt 0.4% Fluid loss additive 0.125% LCM if needed Excess=10% or more if needed	2.64
Tail	Class H	5181' – 5311'	6914'-6959'	10	480	<del>91</del> 513	0.2% Fluid loss additive 0.3% Dispersant 0.15% Retarder 0.2% Antifoam Excess=10% or more if needed	1.07

Displacement: Fresh Water with approximately 250 ppm gluteraldehyde biocide.

#### **Proposal for Option to Adjust Production Casing Cement Volumes:**

The production casing cement volumes presented above are estimates based on data from previous wells. We will adjust these volumes based on the caliper log data for each well and our trends for amount of cement returns to surface. Also, if no caliper log is available for any particular well, we would propose an option to possibly increase the production casing cement volumes to account for any uncertainty in regard to the hole volume.

#### **4. Pressure Control Equipment:**

A 11" 3M system will be installed, used, maintained, and tested accordingly as described in Onshore Oil and Gas Order No. 2.

Our BOP equipment will be:

- Rotating Head
- Annular BOP, 11" 3M
- Blind Ram, 11" 3M
- Pipe Ram, 11" 3M

After nipping up, and every 30 days thereafter, preventors will be pressure tested. BOP will be inspected and operated at least daily to insure good working order. All pressure and operating tests will be recorded on the daily drilling reports. Ram Type preventors will be tested to rated working pressure or 70% of the minimum internal yield of the casing. Annular type preventer(s) shall be tested to 50% of approved BOP stack working pressure. Pressure shall be maintained at least 10 minutes or until provisions of test are met, whichever is longer. BOP will comply with all provisions of Onshore Oil and Gas Order No. 2 as specified. **See Attached BOPE Schematic.**

#### **5. Proposed Mud System**

The mud systems that are proposed for use are as follows:

DEPTH	TYPE	Density ppg	FV sec/qt	API Fluid Loss cc/30 min	pH
0 – Surface Casing Point	Fresh Water or Fresh Water Native Mud	8.5 – 9.0	28 – 40	N.C.	N.C.
Surface Casing Point to TD	Brine (Saturated NaCl <sub>2</sub> )	10	29	N.C.	10 - 11
Conversion to Mud at TD	Brine Based Mud (NaCl <sub>2</sub> )	10	34 – 45	5 – 10	10 - 11

Drilling mud containing H<sub>2</sub>S shall be degassed in accordance with API RP-49, item 5.14. The gases shall be piped into the flare system. Gas detection equipment and pit level flow monitoring equipment will be on location. ConocoPhillips Company will maintain sufficient mud and weighted material on location at all times.

**6. Logging, Coring, and Testing Program:**

- a. No drill stem tests will be done
- b. No mud logging is planned, but might possibly be done if it is determined that this data is needed;
- c. No whole cores are planned
- d. The open hole electrical logging program is planned to be as follows:
  - Total Depth to 2500': Resistivity, Density, and Gamma Ray.
  - Total Depth to surface Casing Shoe: Caliper
  - Total Depth to surface, Gamma Ray and Neutron
  - Formation pressure data (XPT) on electric line if needed (optional)
  - Rotary Sidewall Cores on electric line if needed (optional)
  - BHC or Dipole Sonic if needed (optional)
  - Spectral Gamma Ray if needed (optional)

**7. Abnormal Pressures and Temperatures:**

- No abnormal pressures are expected to be encountered.
- Loss of circulation is a possibility in the horizons below the Top of Grayburg. We expect that normal Loss of Circulation Material will be successful in healing any such loss of circulation events.
  - The bottom hole pressure is expected to be 8 55 ppg gradient.
- The estimated H<sub>2</sub>S concentrations and ROE calculations for the gas in the zones to be penetrated are presented in the table below for the various producing horizons in this area:

FORMATION / ZONE	H2S (PPM)	Gas Rate (MCFD)	ROE 100 PPM	ROE 500 PPM
Grayburg / San Andres (from MCA)	14000	38	59	27
Yeso Group	400	433	34	15

ConocoPhillips will comply with the provisions of Oil and Gas Order # 6

**8. Anticipated starting date and duration of operations:**

Well pad and road constructions will begin as soon as all agency approvals are obtained. Anticipated date to drill these wells begin from early 2012 through the end after receiving approval of the APD.

**Attachments:**


- Attachment # 1 . . . . BOP and Choke Manifold Schematic – 3M System
- Attachment # 2 . . . . . Diagram of Choke Manifold Equipment

**Contact Information:**

Program prepared by:  
James Chen  
Drilling Engineer, ConocoPhillips Company  
Phone (832) 486-2184  
Cell (832) 768-1647  
Date: August 4, 2011




# Attachment # 1



Item	Description
1	Rotating Head (11")
2A	Shut-in Line and Valve
2B	Flow Line (8")
2C	Shale Shakers and Solids Settling Tank
2D	Cuttings Bins for Zero Discharge
2E	Mud/Gas Separator with vent line to flare and return line to mud system
3	Annular BOP (11", 3000 psi)
4	Double Ram BOP (11", 3000 psi) with Band Rams in Upper Set and Pipe Rams in Lower Set
5	KIL Line (2" Flexible Hose, 3000 psi WP)
6	KIL Line Valve, Inner (2-1/8", 3000 / 5000 psi WP)
7	KIL Line Valve, Outer (2-1/8", 3000 / 5000 psi WP)
8	KIL Line Check Valve (2-1/8", 3000 / 5000 psi WP)
9	Choke Line (2" Steel Line, 3000 psi WP)
10	Choke Line Valve, Inner (2-1/8", 3000 psi WP)
11	Choke Line Valve, Outer, (Hydraulically operated, 2-1/8", 3000 psi WP)
12	Spacer Spool (50' 2M x 2M)
13	Spacer Spool (50' 2M x 2M)
14	Casing Head (11" 5M)
15	Ball Valve and Threaded Nipple on Casing Head Outlet, 2" 5M
16	Surface Casing

Drawn by: Steven G. Moore, Chief Drilling Engineer, Mid-Continent Business Unit, ConocoPhillips Company, 12-July-2011

## CHOKE MANIFOLD ARRANGEMENT



Item	Description
1	Manual Adjustable Choke, 2-1/16", 3M
2	Manual Adjustable Choke, 2-1/16", 3M
3	Gate Valve, 2-1/16" 5M
4	Gate Valve, 2-1/16" 5M
5	Gate Valve, 2-1/16" 5M
6	Gate Valve, 2-1/16" 5M
7	Gate Valve, 3-1/8" 3M
8	Gate Valve, 2-1/16" 5M
9	Gate Valve, 2-1/16" 5M
10	Gate Valve, 2-1/16" 5M
11	Gate Valve, 2-1/16" 5M
12	Gate Valve, 3-1/8" 3M
13	Gate Valve, 2-1/16" 5M
14	Gate Valve, 2-1/16" 5M
15	Pressure Gauge
16	2" hammer union tie-in point for BOP Tester

Drawn by.

Steven O. Moore

Chief Drilling Engineer, Mid-Continent Business Unit, ConocoPhillips Company

Date: 03-Nov-2011

ConocoPhillips Company  
Closed Loop System Design, Operating and Maintenance, and Closure Plan

Well: Ruby Federal #9

Date: October 10, 2011

ConocoPhillips proposes the following plan for design, operating and maintenance, and closure of our proposed closed loop system for the above named well:

1. We propose to use a closed loop system with steel pits, haul-off bins, and frac tanks for containing all cuttings, solids, mud, water, brine, and liquids. We will not dig a pit, nor will we use a drying pad, nor will we build an earth pit above ground level, nor will we dispose of or bury any waste on location.

All drilling waste and all drilling fluids (fresh water, brine, mud, cuttings, drill solids, cement returns, and any other liquid or solid that may be involved) will be contained on location in the rig's steel pits or in haul-off bins or in frac tanks as needed. The intent is as follows:

- We propose to use the rigs's steel pits for containing and maintaining the drilling fluids.
- We propose to remove cuttings and drilled solids from the mud by using solids control equipment and to contain such cuttings and drilled solids on location in haul-off bins.
- We propose that any excess water that may need to be stored on location will be stored in frac tanks.

The closed loop system components will be inspected daily by each tour and any needed repairs will be made immediately. Any leak in the system will be repaired immediately, and any spilled liquids and / or solids will be cleaned immediately, and the area where any such spill occurred will be remediated immediately.

2. Cuttings and solids will be removed from location in haul-off bins by an authorized contractor and disposed of at an authorized facility. For this well, we propose the following disposal facility:

Controlled Recovery Inc,  
4507 West Carlsbad Hwy, Hobbs, NM 88240,  
P.O. Box 388 Hobbs, New Mexico 88241  
Toll Free Phone: 877.505.4274, Local Phone Number: 432-638-4076

The physical address for the plant where the disposal facility is located is Highway 62/180 at mile marker 66 (33 miles East of Hobbs, NM and 32 miles West of Carlsbad, NM).

The Permit Number for CRI is R9166

A photograph showing the type of haul-off bins that will be used is attached


3. Mud will be transported by vacuum truck and disposed of at Controlled Recovery Inc at the facility described above.
4. Fresh Water and Brine will be hauled off by vacuum truck and disposed of at an authorized salt water disposal well. We propose the following for disposal of fresh water and brine as needed:
  - Nabors Well Services Company, 3221 NW County Rd, Hobbs, NM 88240, PO 5208 Hobbs, NM, 88241, Permit SWD 092. (Well Location: Section 3, T19S R37E)
  - Basic Energy Services, PO Box 1869 Eunice, NM 88231 Phone Number 575 394 2545, Facility located at Hwy 18, Mile Marker 19, Eunice, NM.

James Chen, Staff Drilling Engineer  
ConocoPhillips Company, 600 North Dairy Ashford, Room #2WL-13018, Houston, TX 77079-1175  
Office: 832-486-2184  
Cell: 832-768-1647


# SPECIFICATIONS

## Heavy Duty Split Metal Rolling Lid


FLOOR: 3/16" PL one piece  
 CROSS MEMBER: 3" x 4" channel 16" on center  
 WALLS: 3/16" PL solid welded with tubing top inside liner hooks  
 DOOR: 3/16" PL with tubing frame  
 FRONT: 3/16" PL slant formed  
 PICK UP: Standard cable with 2" x 6" x 1/4" rails, gusset at each crossmember  
 WHEELS: 10" DIA x 9" long with grease fittings  
 DOOR LATCH: 3 Independent ratchet binders with chains vertical second latch  
 GASKETS: Extruded rubber seal with metal retainers  
 WELDS: All welds continuous except sub-structure crossmembers  
 FINISH: Coated inside and out with direct to metal rust inhibiting acrylic enamel color coat  
 HYDROTESTING: Full capacity static test  
 DIMENSIONS: 22'-11" long (21'-8" inside), 99" wide (88" inside) see drawing for height  
 OPTIONS: Steel grit blast and special paint, Amalgroll, Heli and Dino pickup  
 ROOF: 3/16" PL roof panels with tubing and channel support frame  
 LIDS: (2) 68" x 90" metal rolling lids spring loaded self raising  
 ROLLERS: 4" V-groove rollers with delrin bearings and grease fittings  
 OPENING: (2) 60" x 82" openings with 8" divider centered on container  
 LATCH: (2) Independent ratchet binders with chains per lid  
 GASKETS: Extruded rubber seal with metal retainers



CONT.	A	B
20 YD	41	53
25 YD	53	65
30 YD	65	77




# ConocoPhillips Location Schematic and Rig Layout for Closed Loop System Precision #194 (PICTURE NOT TO SCALE)




Ruby Fadsan #9

Tmm  
8/15/2011

ConocoPhillips  
Drilling Location  
Closed Loop Pits



Well: Ruby Falcón #9



CELLAR: 6' DIA. x 4' TIN HORN