

OCD-HOBBS

HOBBS OCD

Δ76-11-880  
FORM APPROVED  
OMB No. 1004-0137  
Expires July 31, 2010

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

DEC 05 2011

APPLICATION FOR PERMIT TO DRILL OR REENTER

1a. Type of work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER		5. Lease Serial No. NMLC029405B	
1b. Type of Well: <input checked="" type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Other <input type="checkbox"/> Single Zone <input type="checkbox"/> Multiple Zone		6. If Indian, Allottee or Tribe Name	
2. Name of Operator ConocoPhillips Company		7. If Unit or CA Agreement, Name and No.	
3a. Address 3300 N "A" St, Bldg 6 Midland, TX 79705		8. Lease Name and Well No. <b>&lt;38653&gt;</b> Ruby Federal 2	
3b. Phone No. (include area code) (432)688-6913		9. API Well No. 30-025- 40394	
4. Location of Well (Report location clearly and in accordance with any State requirements*) At surface 1140 FSL 2310 FEL UL O, Sec 17, T 17S, R 32E At proposed prod. zone		10. Field and Pool, or Exploratory Maljamar; Yeso, West	
14. Distance in miles and direction from nearest town or post office* 4.5 Miles south of Maljamar, NM		12. County or Parish Lea	13. State NM
15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) 1140' FSL	16. No. of acres in lease 1601.9	17. Spacing Unit dedicated to this well 40	
18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft. 371' From Elvis #2	19. Proposed Depth 6969'	20. BLM/BIA Bond No. on file ES0085	
21. Elevations (Show whether DF, KDB, RT, GL, etc.) 4004' GL	22. Approximate date work will start* 01/31/2012	23. Estimated duration 10 days	

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No.1, must be attached to this form:

- |  |   |
|--|---|
| 1. Well plat certified by a registered surveyor.   | 4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above). |
| 2. A Drilling Plan.  | 5. Operator certification   |
| 3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO must be filed with the appropriate Forest Service Office). | 6. Such other site specific information and/or plans as may be required by the BLM.             |

25. Signature <b>B. D. Maiorino</b>	Name (Printed/Typed) Brian D Maiorino	Date 10/10/2011
-------------------------------------	--	--------------------

Title  
Regulatory Specialist

Approved by (Signature)	Name (Printed/Typed)	Date <b>DEC - 1 2011</b>
-------------------------	----------------------	--------------------------

Title <b>FIELD MANAGER</b>	Office <b>CARLSBAD FIELD OFFICE</b>	Date <b>DEC - 1 2011</b>
-------------------------------	--	-----------------------------

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Conditions of approval, if any, are attached.

**APPROVAL FOR TWO YEARS**

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Continued on page 2)

**NSL-6528**

\*(Instructions on page 2)

Roswell Controlled Water Basin

SEE ATTACHED FOR  
CONDITIONS OF APPROVAL

APPROVAL SUBJECT TO  
GENERAL REQUIREMENTS  
AND SPECIAL STIPULATIONS  
ATTACHED

JAN 10 2012 **dm**

HOBBS OGD

DEC 05 2011

RECEIVED

Drilling Plan  
ConocoPhillips Company  
Maljamar; Yeso, west

Ruby Federal #2

Lea County, New Mexico

1. Estimated tops of geological markers and estimated depths to water, oil, or gas formations:

The ranges of depths for the formation tops, thicknesses, and planned Total Depths for all the wells to be drilled under this Master Drilling Plan are presented in the table below.

The datum for these depths is RKB (which is 14' above Ground Level).

Formations	Top Depths FT MD	Contents
Quaternary	Surface	Fresh Water
Rustler	761	Anhydrite
Salado (top of salt)	937	Salt
Tansill (base of salt)	1913	Gas, Oil and Water
Yates	2071	Gas, Oil and Water
Seven Rivers	2379	Gas, Oil and Water
Queen	3033	Gas, Oil and Water
Grayburg	3448	Gas, Oil and Water
San Andres	3824	Gas, Oil and Water
Glorieta	5307	Gas, Oil and Water
Paddock	5381	Gas, Oil and Water
Blinbry	5760	Gas, Oil and Water
Tubb	6779	Gas, Oil and Water
Deepest estimated perforation	6769	Deepest estimated perforation is ~ 10' above Top of Tubb
Total Depth (maximum)	6969	200' below deepest estimated perforation

All of the water bearing formations identified above will be protected by setting of the 8-5/8" surface casing 25' – 70' into the Rustler formation and circulating of cement from casing shoe to surface in accordance with the provisions of Onshore Oil and Gas Order No. 2 and New Mexico Oil Conservation Division Title 19.

The targeted oil and gas bearing formations identified above protected by setting of the 5-1/2" production casing 10' off bottom of TD and circulating of cement from casing shoe to surface in accordance with the provisions of Onshore Oil and Gas Order No. 2 and New Mexico Oil Conservation Division Title 19.

## 2. Proposed casing program:

Type	Hole Size (in)	Interval MD RKB (ft)		OD (inches)	Wt (lb/ft)	Gr	Conn	Condition	Safety Factors Calculated per BLM Load Formulas		
		From	To						Burst	Collapse	Tension Dry/Buoyant
Cond	20"	0	40' – 85' (30' – 75' BGL)	16"	0.5" wall	B	Line Pipe	New	NA	NA	NA
Alt. Cond	20"	0	40' – 85' (30' – 75' BGL)	13-3/8"	48#	H-40	PE	New	NA	NA	NA
Surf	12-1/4"	0	786'-831'	8-5/8"	24#	J-55	STC	New	7.98	3.63	11.9 / 13.6
Prod	7-7/8"	0	6914'-6959'	5-1/2"	17#	L-80	LTC	New	2.46	1.71	2.81 / 3.32

The casing will be suitable for H<sub>2</sub>S Service.

The surface and production casing will be set approximately 10' off bottom and we will drill the hole with a 45' range uncertainty for casing set depth to fit the casing string so that the cementing head is positioned at the floor for the cement job.

The production casing will be set 155' to 200' below the deepest estimated perforation to provide rathole for the pumping completion and for the logs to get deep enough to log the interval of interest.

### 3. Proposed cementing program:

#### 16" or 13-3/8" Conductor:

Cement to surface with rathole mix, ready mix or Class C Neat cement.

(Note: The gravel used in the cement is not to exceed 3/8" dia)

TOC at surface.

#### 8-5/8" Surface Casing:

The intention for the cementing program for the Surface Casing is to:

- Place the Tail Slurry from the casing shoe to 300' above the casing shoe,
- Bring the Lead Slurry to surface.

Spacer: 20 bbls Fresh Water

Slurry		Intervals Ft MD		Excess %	Sx	Vol Cuft	Additives	Yield ft <sup>3</sup> /sx
Lead	Class C	Surface	486' – 531'	170	350	598	4%Bentonite 2%CaCl <sub>2</sub> .125%Polyflake .2% antifoam Excess =130%	1.68
Tail	Class C	486' – 531'	786'-831'	100	200	264	1% CaCl <sub>2</sub> Excess = 100%	1.34

Displacement: Fresh Water with approximately 250 ppm gluteraldehyde biocide.

**Note: In accordance with the Pecos District Conditions of Approval, we will Wait on Cement (WOC) for a period of not less than 18 hrs after placement or until at least 500 psi compressive strength has been reached in both the Lead Slurry and Tail Slurry cements on the Surface Casing, whichever is greater.**

#### 5-1/2" Production Casing Cementing Program:

The intention for the cementing program for the Production Casing is to:

- Place the Tail Slurry from the casing shoe to a point approximately 200' above the top of the Paddock,
- Bring the Lead Slurry to surface.

Spacer: 20 bbls Fresh Water

Slurry		Intervals Ft MD		Excess %	Sx	Vol Cuft	Additives	Yield ft <sup>3</sup> /sx
Lead	50:50 Poz/C	Surface	5181' – 5311'	15	1000	464 <del>264</del>	10% Bentonite 8 lbs/sx Salt 0.4% Fluid loss additive 0.125% LCM if needed Excess=10% or more if needed	2.64
Tail	Class H	5181' – 5311'	6914'-6959'	10	480	91 <del>513</del>	0.2% Fluid loss additive 0.3% Dispersant 0.15% Retarder 0.2% Antifoam Excess=10% or more if needed	1.07

*Inserted  
17 Nov 2011*

Displacement: Fresh Water with approximately 250 ppm gluteraldehyde biocide.

#### **Proposal for Option to Adjust Production Casing Cement Volumes:**

The production casing cement volumes presented above are estimates based on data from previous wells. We will adjust these volumes based on the caliper log data for each well and our trends for amount of cement returns to surface. Also, if no caliper log is available for any particular well, we would propose an option to possibly increase the production casing cement volumes to account for any uncertainty in regard to the hole volume.

#### **4. Pressure Control Equipment:**

A 11" 3M system will be installed, used, maintained, and tested accordingly as described in Onshore Oil and Gas Order No. 2.

Our BOP equipment will be:

- Rotating Head
- Annular BOP, 11" 3M
- Blind Ram, 11" 3M
- Pipe Ram, 11" 3M

*See COA*

After nipping up, and every 30 days thereafter, preventors will be pressure tested. BOP will be inspected and operated at least daily to insure good working order. All pressure and operating tests will be recorded on the daily drilling reports. Ram Type preventors will be tested to rated working pressure or 70% of the minimum internal yield of the casing. Annular type preventer(s) shall be tested to 50% of approved BOP stack working pressure. Pressure shall be maintained at least 10 minutes or until provisions of test are met, whichever is longer. BOP will comply with all provisions of Onshore Oil and Gas Order No. 2 as specified. **See Attached BOPE Schematic.**

#### **5. Proposed Mud System**

The mud systems that are proposed for use are as follows:

DEPTH	TYPE	Density ppg	FV sec/qt	API Fluid Loss cc/30 min	pH
0 – Surface Casing Point	Fresh Water or Fresh Water Native Mud	8.5 – 9.0	28 – 40	N.C.	N.C.
Surface Casing Point to TD	Brine (Saturated NaCl <sub>2</sub> )	10	29	N.C.	10 - 11
Conversion to Mud at TD	Brine Based Mud (NaCl <sub>2</sub> )	10	34 – 45	5 – 10	10 - 11

Drilling mud containing H<sub>2</sub>S shall be degassed in accordance with API RP-49, item 5.14. The gases shall be piped into the flare system. Gas detection equipment and pit level flow monitoring equipment will be on location. ConocoPhillips Company will maintain sufficient mud and weighted material on location at all times

*Tomas  
14 Nov 2011*

**6. Logging, Coring, and Testing Program:**

- a. No drill stem tests will be done
- b. No mud logging is planned, but might possibly be done if it is determined that this data is needed;
- c. No whole cores are planned
- d. The open hole electrical logging program is planned to be as follows:
  - Total Depth to 2500': Resistivity, Density, and Gamma Ray.
  - Total Depth to surface Casing Shoe: Caliper
  - Total Depth to surface, Gamma Ray and Neutron
  - Formation pressure data (XPT) on electric line if needed (optional)
  - Rotary Sidewall Cores on electric line if needed (optional)
  - BHC or Dipole Sonic if needed (optional)
  - Spectral Gamma Ray if needed (optional)

**7. Abnormal Pressures and Temperatures:**

- No abnormal pressures are expected to be encountered.
- Loss of circulation is a possibility in the horizons below the Top of Grayburg. We expect that normal Loss of Circulation Material will be successful in healing any such loss of circulation events.
  - The bottom hole pressure is expected to be 8.55 ppg gradient.
- The estimated H<sub>2</sub>S concentrations and ROE calculations for the gas in the zones to be penetrated are presented in the table below for the various producing horizons in this area:

FORMATION / ZONE	H2S (PPM)	Gas Rate (MCFD)	ROE 100 PPM	ROE 500 PPM
Grayburg / San Andres (from MCA)	14000	38	59	27
Yeso Group	400	433	34	15

ConocoPhillips will comply with the provisions of Oil and Gas Order # 6

**8. Anticipated starting date and duration of operations:**

Well pad and road constructions will begin as soon as all agency approvals are obtained. Anticipated date to drill these wells begin from early 2012 through the end after receiving approval of the APD.


**Attachments:**

- Attachment # 1 ..... BOP and Choke Manifold Schematic – 3M System
- Attachment # 2 ..... Diagram of Choke Manifold Equipment

**Contact Information:**

Program prepared by:  
James Chen  
Drilling Engineer, ConocoPhillips Company  
Phone (832) 486-2184  
Cell (832) 768-1647  
Date: October 7, 2011

## Attachment # 1




Item	Description
1	Rotating Head (11")
2A	Fillup Line and Valve
2B	Flow Line (2")
2C	Shale Shakers and Solids Settling Tank
2D	Outfalls Bins for Zero Discharge
2E	Mud Gas Separator with vent line to flare and return line to mud system
3	Annular BOP (11", 3000 psi)
4	Double Ram BOP (11", 3000 psi, with Blind Rams in Upper Set and Pipe Rams in Lower Set)
5	KI) Line (2" Flexible Hose, 3000 psi WP)
6	KI) Line Valve, Inner (2-1/8" 3000 / 5000 psi WP)
7	KI) Line Valve, Outer (2-1/8", 3000 / 5000 psi WP)
8	KI) Line Check Valve (2-1/8", 3000 / 5000 psi WP)
9	Choke Line (2" Steel Line, 3000 psi WP)
10	Choke Line Valve, Inner (3-1/8", 3000 psi WP)
11	Choke Line Valve, Outer, (Hydraulically operated, 3-1/8", 3000 psi WP)
12	Spacer Bop (56" 2M x 2M)
13	Spacer Bop (56" 2M x 2M)
14	Casing Head (11" 2M)
15	Ball Valve and Threaded Nipple on Casing Head Outlet, 2" 2M
16	Surface Casing

Drawn by: Steven O. Moore, Chief Drilling Engineer, M&C-Continental Business Unit, ConocoPhillips Company, 13-July-2011



## CHOKE MANIFOLD ARRANGEMENT



Item	Description
1	Manual Adjustable Choke, 2-1/16", 3M
2	Manual Adjustable Choke, 2-1/16", 3M
3	Gate Valve, 2-1/16" 5M
4	Gate Valve, 2-1/16" 5M
5	Gate Valve, 2-1/16" 5M
6	Gate Valve, 2-1/16" 5M
7	Gate Valve, 3-1/8" 3M
8	Gate Valve, 2-1/16" 5M
9	Gate Valve, 2-1/16" 5M
10	Gate Valve, 2-1/16" 5M
11	Gate Valve, 2-1/16" 5M
12	Gate Valve, 3-1/8" 3M
13	Gate Valve, 2-1/16" 5M
14	Gate Valve, 2-1/16" 5M
15	Pressure Gauge
16	2" hammer union tie-in point for BOP Tester

Drawn by:

Steven O. Moore

Chief Drilling Engineer, Mid-Continent Business Unit, ConocoPhillips Company

Date: 03-Nov-2011

ConocoPhillips Company  
Closed Loop System Design, Operating and Maintenance, and Closure Plan

Well: Ruby Federal #2

Date: October 10, 2011

ConocoPhillips proposes the following plan for design, operating and maintenance, and closure of our proposed closed loop system for the above named well:

1. We propose to use a closed loop system with steel pits, haul-off bins, and frac tanks for containing all cuttings, solids, mud, water, brine, and liquids. We will not dig a pit, nor will we use a drying pad, nor will we build an earth pit above ground level, nor will we dispose of or bury any waste on location.

All drilling waste and all drilling fluids (fresh water, brine, mud, cuttings, drill solids, cement returns, and any other liquid or solid that may be involved) will be contained on location in the rig's steel pits or in haul-off bins or in frac tanks as needed. The intent is as follows:

- We propose to use the rig's steel pits for containing and maintaining the drilling fluids.
- We propose to remove cuttings and drilled solids from the mud by using solids control equipment and to contain such cuttings and drilled solids on location in haul-off bins.
- We propose that any excess water that may need to be stored on location will be stored in frac tanks

The closed loop system components will be inspected daily by each tour and any needed repairs will be made immediately. Any leak in the system will be repaired immediately, and any spilled liquids and / or solids will be cleaned immediately, and the area where any such spill occurred will be remediated immediately.

2. Cuttings and solids will be removed from location in haul-off bins by an authorized contractor and disposed of at an authorized facility. For this well, we propose the following disposal facility:

Controlled Recovery Inc,  
4507 West Carlsbad Hwy, Hobbs, NM 88240,  
P.O. Box 388 Hobbs, New Mexico 88241  
Toll Free Phone: 877.505.4274, Local Phone Number: 432-638-4076

The physical address for the plant where the disposal facility is located is Highway 62/180 at mile marker 66 (33 miles East of Hobbs, NM and 32 miles West of Carlsbad, NM).

The Permit Number for CRI is R9166

A photograph showing the type of haul-off bins that will be used is attached.


3. Mud will be transported by vacuum truck and disposed of at Controlled Recovery Inc at the facility described above.
4. Fresh Water and Brine will be hauled off by vacuum truck and disposed of at an authorized salt water disposal well. We propose the following for disposal of fresh water and brine as needed:
  - Nabors Well Services Company, 3221 NW County Rd, Hobbs, NM 88240, PO 5208 Hobbs, NM, 88241, Permit SWD 092. (Well Location: Section 3, T19S R37E)
  - Basic Energy Services, PO Box 1869 Eunice, NM 88231 Phone Number 575 394 2545, Facility located at Hwy 18, Mile Marker 19, Eunice, NM.

James Chen, Staff Drilling Engineer  
ConocoPhillips Company, 600 North Dairy Ashford, Room #2WL-13018, Houston, TX 77079-1175  
Office: 832-486-2184  
Cell: 832-768-1647


# SPECIFICATIONS

## Heavy Duty Split Metal Rolling Lid


FLOOR: 3/16" PL one piece  
 CROSS MEMBER: 8 x 4" I channel 16' on center  
 WALLS: 3/16" PL solid welded with tubing top inside liner hooks  
 DOOR: 3/16" PL with tubing frame  
 FRONT: 3/16" PL slant formed  
 PICK UP: Standard cable with 2" x 6" x 1/4" rails, gusset at each crossmember  
 WHEELS: 10" DIA x 9" long with grease fittings  
 DOOR LATCH: 3 Independent ratchet binders with chains, vertical second latch  
 GASKETS: Extruded rubber seal with metal retainers  
 WELDS: All welds continuous except sub-structure crossmembers  
 FINISH: Coated inside and out with direct to metal rust inhibiting acrylic enamel color coat  
 HYDROTESTING: Full capacity static test  
 DIMENSIONS: 22'-11" long (21'-8" inside), 99" wide (88" inside), see drawing for height  
 OPTIONS: Steel grit blast and special paint, Armroll, Roll and Dine pickup  
 ROOF: 3/16" PL roof panels with tubing and channel support frame  
 LIDS: (2) 68" x 90" metal rolling lids spring loaded self raising  
 ROLLERS: 4" V-groove rollers with delrin bearings and grease fittings  
 OPENING: (2) 60" x 82" openings with 6" divider centered on container  
 LATCH: (2) Independent ratchet binders with chains per lid  
 GASKETS: Extruded rubber seal with metal retainers



CONT.	A	B
20 YD	41	53
25 YD	53	65
30 YD	65	77



# ConocoPhillips Location Schematic and Rig Layout for Closed Loop System Precision #194 (PICTURE NOT TO SCALE)



Turn  
 8/15/2011