

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

OCD Hobbs
HOBBS OCD

FORM APPROVED
OMB No. 1004-0137
Expires: October 31, 2014

SUNDRY NOTICES AND REPORTS ON WELLS
Do not use this form for proposals to drill or to re-enter an abandoned well. Use Form 3160-3 (APD) for such proposals.

JAN 28 2013

5. Lease Serial No.
NMLC27508

6. If Indian, Allottee or Tribe Name

SUBMIT IN TRIPLICATE - Other instructions on page 2. RECEIVED

1. Type of Well
 Oil Well Gas Well Other

2. Name of Operator
ConocoPhillips Company

3a. Address
P. O. Box 51810 Midland TX 79710

3b. Phone No. (include area code)
(432)688-9174

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)
UL F, 2010' FNL & 2560' FWL, Sec 29, 26S, 32E

7. If Unit of CA/Agreement, Name and/or No.

8. Well Name and No.
Wilder 29 Federal 1 SWD

9. API Well No.
30-025-40500

10. Field and Pool or Exploratory Area
SWD; Cherry Canyon

11. County or Parish, State
LEA NM

12. CHECK THE APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input checked="" type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other <u>Frac</u>
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operation: Clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomplete horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports must be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 must be filed once testing has been completed. Final Abandonment Notices must be filed only after all requirements, including reclamation, have been completed and the operator has determined that the site is ready for final inspection.)

Proposed plans call for pulling tubing, adding perfs at 5204'-5765' and perform fracture stimulation 5204'-5765' job down tubing. Re-install injection tubing & injection packer (5190'). Re-install wellhead. Perform Mechanical Integrity Test (Contact BLM/NMOCD a minimum of 72 hours prior to conducting MIT test). Place wellbore in disposal service per terms of NMOCD Administrative SWD orders 1303 & 1303A.

SUBJECT TO LIKE APPROVAL BY STATE

14. I hereby certify that the foregoing is true and correct. Name (Printed/Typed)
Rhonda Rogers

Signature: *Rhonda Rogers*

Title Staff Regulatory Technician

Date 12/12/2012

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved by


Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Title

Office



Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.



9 5/8" 36# @ 1058' cmt w/ 600 sxs

AS-1X packer @ 5747'

Perfs: 5765-85', 5811-40'

7" 26# @ 6251' cmt w/ 1340 sx

TD/PBTD 6275'/6205'

PRESENT MECHANICAL SKETCH

Wilder Federal 29-1 SWD


2010' FNL & 2560' FWL, Section 29. T26S, R32E

API #: 30-025-40500 32° 0' 54.688" N
 FIELD: Red Hill West 103° 41' 49.304" W
 CO ST: Lea, NM
 DATES: SPUD: 4/20/12 IC:
 LAST WORKOVER:
 DIAGRAM REVISED: D. McPherson 09/05/2012

	CASING		LINER	TUBING
Hole Size	12 1/4"	8 3/4"		
Pipe Size	9 5/8"	7"		3 1/2"
Weight	36#	26#		9.3#
Grade	J-55	P-110		L-80
Thread	ST&C	BTC		
Depth	1058'	6250.9'		5756.75'
ELEVATION:	GR 3129' KB 3142'			

TUBING	From	To	
ELEVATION:	13.00	0.00	13.00
3 - 3 1/2" 9.3# L-80 pup jts	24.00	13.00	37.00
175 jt 3 1/2" 9.3# L-80 tubing	5708.08	37.00	5745.08
1 - on/off tool w F profile	2.00	5745.08	5747.08
1 - AS-1X packer	7.40	5747.08	5754.48
1 - R nipple (2.75")	1.27	5754.48	5755.75
1 - WL Reentry guide	1.00	5755.75	5756.75

COMMENTS



9 3/4" 36# @ 1058' cmt w/ 600 sxs

AS-1X packer @ 5190'

Perfs: 5204-5227', 5259-5312', 5329-5397'
 Perfs: 5438-5457', 5480-5516', 5578-5598'
 Perfs: 5657-5715', 5744-5765'

Perfs: 5765-5785', 5811-5840'

7" 26# @ 6251' cmt w/ 1340 sx

PROPOSED MECHANICAL SKETCH

ADD PERFS TO SW DISPOSAL

Wilder Federal 29-1 SWD

2010' FNL & 2560' FWL, Section 29, T26S, R32E

API #: 30-025-40500 32° 0' 54.688" N
 FIELD: Red Hill West 103° 41' 49.304" W
 CO ST: Lea, NM
 DATES: SPUD: 4/20/12 IC:
 LAST WORKOVER:
 DIAGRAM REVISED: D. McPherson 09/12/2012

	CASING		LINER	TUBING
Hole Size	12 1/4"	8 3/4"		
Pipe Size	9 3/4"	7"		3 1/2"
Weight	36#	26#		9.3#
Grade	J-55	P-110		L-80
Thread	ST&C	BTC		
Depth	1058'	6250.9'		5199.67'
ELEVATION:	GR 3129' KB 3142'			

TUBING	From	To	
ELEVATION:	13.00	0.00	13.00
3 - 3 1/2" 9.3# L-80 pup jts	24.00	13.00	37.00
168 jt 3 1/2" 9.3# L-80 tubing	5151.00	37.00	5188.00
1 - on/off tool w F profile	2.00	5188.00	5190.00
1 - AS-1X packer	7.40	5190.00	5197.40
1 - R nipple (2.75")	1.27	5197.40	5198.67
1 - WL Reentry guide	1.00	5198.67	5199.67

COMMENTS