September 2013

C-144 Permit Package for Caza Ridge 14 State No. 4H Temporary Pit Section 14 T23S R34E Lea County NM



Prepared for
Caza Operating, LLC
Midland, Texas

Prepared by
R.T. Hicks Consultants, Ltd.
Albuquerque, New Mexico

R. T. HICKS CONSULTANTS, LTD.

901 Rio Grande Blvd NW ▲ Suite F-142 ▲ Albuquerque, NM 87104 ▲ 505.266.5004 ▲ Fax: 505.266-0745

September 17, 2013

HOBBS OCD

SEP 18 2013

RECEIVED

Mr. Geoffrey Leking
NMOCD District
1625 French Drive
Hobbs, New Mexico 88240
Via E-mail and Regular Mail

RE: Caza Operating LLC, Caza Ridge "14" State No. 4H C-144 Permit Modification

Dear Geoffrey:

On behalf of Caza Operating, enclosed are:

1. A C-144 Form to modify the existing application (approved on February 18, 2013) to comply with the new Rule and
2. Updated (and recent OCD-approved) closure plans that are consistent with the new Rule.

The site-specific write-up, figures, plates, and appendix are unchanged from the earlier approved plan. To date, we have conducted our initial sampling of the cuttings, but have not received the results, additionally we are continuing to remove chlorides via the drainage system.

Please contact me if you have any questions of need additional information.

Sincerely,
R.T. Hicks Consultants

Dale T. Littlejohn

Dale T. Littlejohn

Copy: Richard Wright, Caza Operating, LLC
Terry Warnell, NM State Land Office

C-144 and Site Specific Information for Temporary Pit

R.T. Hicks Consultants, Ltd.
901 Rio Grande Blvd. NW, Suite F-142
Albuquerque, NM 87104

District I
1625 N. French Dr., Hobbs, NM 88240
District II
811 S. First St., Artesia, NM 88210
District III
1000 Rio Brazos Road, Aztec, NM 87410
District IV
1220 S. St. Francis Dr., Santa Fe, NM 87505

HOBBS OCD
SEP 18 2013
RECEIVED

State of New Mexico
Energy Minerals and Natural Resources
Department
Oil Conservation Division
1220 South St. Francis Dr.
Santa Fe, NM 87505

Form C-144
Revised June 6, 2013

For temporary pits, below-grade tanks, and *multi-well fluid management pits*, submit to the appropriate NMOCD District Office.
For permanent pits submit to the Santa Fe Environmental Bureau office and provide a copy to the appropriate NMOCD District Office.

Pit, Below-Grade Tank, or Proposed Alternative Method Permit or Closure Plan Application

Type of action:
- ☐ Below grade tank registration
- ☒ Permit of a pit or proposed alternative method
- ☐ Closure of a pit, below-grade tank, or proposed alternative method
- ☒ Modification to an existing permit/or registration
- ☐ Closure plan only submitted for an existing permitted or non-permitted pit, below-grade tank, or proposed alternative method

Instructions: Please submit one application (Form C-144) per individual pit, below-grade tank or alternative request

Please be advised that approval of this request does not relieve the operator of liability should operations result in pollution of surface water, ground water or the environment. Nor does approval relieve the operator of its responsibility to comply with any other applicable governmental authority's rules, regulations or ordinances.

1.
Operator: Caza Operating LLC OGRID #: 249099
Address: 200 North Loraine, Suite 1550, Midland, Texas 79701
Facility or well name: Caza Ridge "14" State Well No. 4H
API Number: 30-025-40936 OCD Permit Number: P1-05637
U/L or Qtr/Qtr P Section 14 Township 23S Range 34E County: Lea
Center of Proposed Design: Latitude 32.298141° N Longitude -103.433951° W NAD: ☒ 1927 ☐ 1983
Surface Owner: ☐ Federal ☒ State ☐ Private ☐ Tribal Trust or Indian Allotment

2.
☒ **Pit:** Subsection F, G or J of 19.15.17.11 NMAC
Temporary: ☒ Drilling ☐ Workover
☐ Permanent ☐ Emergency ☐ Cavitation ☐ P&A ☐ Multi-Well Fluid Management Low Chloride Drilling Fluid ☐ yes ☒ no
☒ Lined ☐ Unlined Liner type: Thickness 20 mil ☐ LLDPE ☒ HDPE ☐ PVC ☐ Other
☒ String-Reinforced
Liner Seams: ☒ Welded ☒ Factory ☐ Other Volume: 40,961 bbl Dimensions: L 116 x W 327 x D 6-8 ft (drilling) 12 ft (fluids cell)

3.
☐ **Below-grade tank:** Subsection I of 19.15.17.11 NMAC
Volume: bbl Type of fluid:
Tank Construction material:
☐ Secondary containment with leak detection ☐ Visible sidewalls, liner, 6-inch lift and automatic overflow shut-off
☐ Visible sidewalls and liner ☐ Visible sidewalls only ☐ Other
Liner type: Thickness mil ☐ HDPE ☐ PVC ☐ Other

4.
☐ **Alternative Method:**
Submittal of an exception request is required. Exceptions must be submitted to the Santa Fe Environmental Bureau office for consideration of approval.

5.
Fencing: Subsection D of 19.15.17.11 NMAC *(Applies to permanent pits, temporary pits, and below-grade tanks)*
☐ Chain link, six feet in height, two strands of barbed wire at top *(Required if located within 1000 feet of a permanent residence, school, hospital, institution or church)*
☒ Four foot height, four strands of barbed wire evenly spaced between one and four feet
☐ Alternate. Please specify

6.
Netting: Subsection E of 19.15.17.11 NMAC *(Applies to permanent pits and permanent open top tanks)*

☐ Screen ☐ Netting ☐ Other_____

☐ Monthly inspections (If netting or screening is not physically feasible)

7.
Signs: Subsection C of 19.15.17.11 NMAC

☐ 12"x 24", 2" lettering, providing Operator's name, site location, and emergency telephone numbers

☒ Signed in compliance with 19.15.16.8 NMAC

8.
Variances and Exceptions:

Justifications and/or demonstrations of equivalency are required. Please refer to 19.15.17 NMAC for guidance.

Please check a box if one or more of the following is requested, if not leave blank:

☐ Variance(s): Requests must be submitted to the appropriate division district for consideration of approval.

☐ Exception(s): Requests must be submitted to the Santa Fe Environmental Bureau office for consideration of approval.

9.
Siting Criteria (regarding permitting): 19.15.17.10 NMAC

Instructions: The applicant must demonstrate compliance for each siting criteria below in the application. Recommendations of acceptable source material are provided below. **Siting criteria does not apply to drying pads or above-grade tanks.**

General siting	
Ground water is less than 25 feet below the bottom of a low chloride temporary pit or below-grade tank. - ☐ NM Office of the State Engineer - iWATERS database search; ☐ USGS; ☐ Data obtained from nearby wells	☐ Yes ☐ No ☒ NA
Ground water is less than 50 feet below the bottom of a Temporary pit, permanent pit, or Multi-Well Fluid Management pit . NM Office of the State Engineer - iWATERS database search; USGS; Data obtained from nearby wells **See Figures 1&2**	☐ Yes ☒ No ☐ NA
Within incorporated municipal boundaries or within a defined municipal fresh water well field covered under a municipal ordinance adopted pursuant to NMSA 1978, Section 3-27-3, as amended. **(Does not apply to below grade tanks) See Figure 5** - Written confirmation or verification from the municipality; Written approval obtained from the municipality	☐ Yes ☒ No
Within the area overlying a subsurface mine. **(Does not apply to below grade tanks) See Figure 7** - Written confirmation or verification or map from the NM EMNRD-Mining and Mineral Division	☐ Yes ☒ No
Within an unstable area. **(Does not apply to below grade tanks) See Figure 8** - Engineering measures incorporated into the design; NM Bureau of Geology & Mineral Resources; USGS; NM Geological Society; Topographic map	☐ Yes ☒ No
Within a 100-year floodplain. **(Does not apply to below grade tanks) See Figure 9** - FEMA map	☐ Yes ☒ No
Below Grade Tanks	
Within 100 feet of a continuously flowing watercourse, significant watercourse, lake bed, sinkhole, wetland or playa lake (measured from the ordinary high-water mark). - *Topographic map; Visual inspection (certification) of the proposed site*	☐ Yes ☐ No
Within 200 horizontal feet of a spring or a fresh water well used for public or livestock consumption;. - NM Office of the State Engineer - iWATERS database search; Visual inspection (certification) of the proposed site	☐ Yes ☐ No
Temporary Pit using Low Chloride Drilling Fluid *(maximum chloride content 15,000 mg/liter)*	
Within 100 feet of a continuously flowing watercourse, or any other significant watercourse or within 200 feet of any lakebed, sinkhole, or playa lake (measured from the ordinary high-water mark). (Applies to low chloride temporary pits.) - Topographic map; Visual inspection (certification) of the proposed site	☐ Yes ☐ No
Within 300 feet from a occupied permanent residence, school, hospital, institution, or church in existence at the time of initial application. - Visual inspection (certification) of the proposed site; Aerial photo; Satellite image	☐ Yes ☐ No
Within 200 horizontal feet of a spring or a private, domestic fresh water well used by less than five households for domestic or stock watering purposes, or 300feet of any other fresh water well or spring, in existence at the time of the initial application. NM Office of the State Engineer - iWATERS database search; Visual inspection (certification) of the proposed site	☐ Yes ☐ No

Within 100 feet of a wetland. - US Fish and Wildlife Wetland Identification map; Topographic map; Visual inspection (certification) of the proposed site	☐ Yes ☐ No
Temporary Pit Non-low chloride drilling fluid	
Within 300 feet of a continuously flowing watercourse, or any other significant watercourse, or within 200 feet of any lakebed, sinkhole, or playa lake (measured from the ordinary high-water mark). **See Figure 3** - Topographic map; Visual inspection (certification) of the proposed site	☐ Yes ☒ No
Within 300 feet from a permanent residence, school, hospital, institution, or church in existence at the time of initial application. - Visual inspection (certification) of the proposed site; Aerial photo; Satellite image. **See Figure 4**	☐ Yes ☒ No
Within 500 horizontal feet of a spring or a private, domestic fresh water well used by less than five households for domestic or stock watering purposes, or 1000 feet of any other fresh water well or spring, in the existence at the time of the initial application; - NM Office of the State Engineer - iWATERS database search; Visual inspection (certification) of the proposed site **See Figures 1 & 2**	☐ Yes ☒ No
Within 300 feet of a wetland. **See Figure 6** - US Fish and Wildlife Wetland Identification map; Topographic map; Visual inspection (certification) of the proposed site	☐ Yes ☒ No
Permanent Pit or Multi-Well Fluid Management Pit	
Within 300 feet of a continuously flowing watercourse, or 200 feet of any other significant watercourse, or lakebed, sinkhole, or playa lake (measured from the ordinary high-water mark). - Topographic map; Visual inspection (certification) of the proposed site	☐ Yes ☐ No
Within 1000 feet from a permanent residence, school, hospital, institution, or church in existence at the time of initial application. - Visual inspection (certification) of the proposed site; Aerial photo; Satellite image	☐ Yes ☐ No
Within 500 horizontal feet of a spring or a fresh water well used for domestic or stock watering purposes, in existence at the time of initial application. - NM Office of the State Engineer - iWATERS database search; Visual inspection (certification) of the proposed site	☐ Yes ☐ No
Within 500 feet of a wetland. - US Fish and Wildlife Wetland Identification map; Topographic map; Visual inspection (certification) of the proposed site	☐ Yes ☐ No

10.

Temporary Pits, Emergency Pits, and Below-grade Tanks Permit Application Attachment Checklist: Subsection B of 19.15.17.9 NMAC

Instructions: Each of the following items must be attached to the application. Please indicate, by a check mark in the box, that the documents are attached.

☐ Hydrogeologic Report (Below-grade Tanks) - based upon the requirements of Paragraph (4) of Subsection B of 19.15.17.9 NMAC
☒ Hydrogeologic Data (Temporary and Emergency Pits) - based upon the requirements of Paragraph (2) of Subsection B of 19.15.17.9 NMAC
☒ Siting Criteria Compliance Demonstrations - based upon the appropriate requirements of 19.15.17.10 NMAC
☒ Design Plan - based upon the appropriate requirements of 19.15.17.11 NMAC
☒ Operating and Maintenance Plan - based upon the appropriate requirements of 19.15.17.12 NMAC
☒ Closure Plan (Please complete Boxes 14 through 18, if applicable) - based upon the appropriate requirements of Subsection C of 19.15.17.9 NMAC and 19.15.17.13 NMAC

☐ Previously Approved Design (attach copy of design) API Number: _____ or Permit Number: _____

11.

Multi-Well Fluid Management Pit Checklist: Subsection B of 19.15.17.9 NMAC

Instructions: Each of the following items must be attached to the application. Please indicate, by a check mark in the box, that the documents are attached.

☐ Design Plan - based upon the appropriate requirements of 19.15.17.11 NMAC
☐ Operating and Maintenance Plan - based upon the appropriate requirements of 19.15.17.12 NMAC
☐ A List of wells with approved application for permit to drill associated with the pit.
☐ Closure Plan (Please complete Boxes 14 through 18, if applicable) - based upon the appropriate requirements of Subsection C of 19.15.17.9 NMAC and 19.15.17.13 NMAC
☐ Hydrogeologic Data - based upon the requirements of Paragraph (4) of Subsection B of 19.15.17.9 NMAC
☐ Siting Criteria Compliance Demonstrations - based upon the appropriate requirements of 19.15.17.10 NMAC

☐ Previously Approved Design (attach copy of design) API Number: _____ or Permit Number: _____

12.
Permanent Pits Permit Application Checklist: Subsection B of 19.15.17.9 NMAC
Instructions: Each of the following items must be attached to the application. Please indicate, by a check mark in the box, that the documents are attached.

- ☐ Hydrogeologic Report - based upon the requirements of Paragraph (1) of Subsection B of 19.15.17.9 NMAC
- ☐ Siting Criteria Compliance Demonstrations - based upon the appropriate requirements of 19.15.17.10 NMAC
- ☐ Climatological Factors Assessment
- ☐ Certified Engineering Design Plans - based upon the appropriate requirements of 19.15.17.11 NMAC
- ☐ Dike Protection and Structural Integrity Design - based upon the appropriate requirements of 19.15.17.11 NMAC
- ☐ Leak Detection Design - based upon the appropriate requirements of 19.15.17.11 NMAC
- ☐ Liner Specifications and Compatibility Assessment - based upon the appropriate requirements of 19.15.17.11 NMAC
- ☐ Quality Control/Quality Assurance Construction and Installation Plan
- ☐ Operating and Maintenance Plan - based upon the appropriate requirements of 19.15.17.12 NMAC
- ☐ Freeboard and Overtopping Prevention Plan - based upon the appropriate requirements of 19.15.17.11 NMAC
- ☐ Nuisance or Hazardous Odors, including H_2S, Prevention Plan
- ☐ Emergency Response Plan
- ☐ Oil Field Waste Stream Characterization
- ☐ Monitoring and Inspection Plan
- ☐ Erosion Control Plan
- ☐ Closure Plan - based upon the appropriate requirements of Subsection C of 19.15.17.9 NMAC and 19.15.17.13 NMAC

13.
Proposed Closure: 19.15.17.13 NMAC
Instructions: Please complete the applicable boxes, Boxes 14 through 18, in regards to the proposed closure plan.

Type: ☒ Drilling ☐ Workover ☐ Emergency ☐ Cavitation ☐ P&A ☐ Permanent Pit ☐ Below-grade Tank ☐ Multi-well Fluid Management Pit ☐ Alternative

Proposed Closure Method: ☐ Waste Excavation and Removal
☐ Waste Removal (Closed-loop systems only)
☒ On-site Closure Method (Only for temporary pits and closed-loop systems)
☒ In-place Burial ☐ On-site Trench Burial
☐ Alternative Closure Method

14.
Waste Excavation and Removal Closure Plan Checklist: (19.15.17.13 NMAC) ***Instructions: Each of the following items must be attached to the closure plan. Please indicate, by a check mark in the box, that the documents are attached.***

- ☐ Protocols and Procedures - based upon the appropriate requirements of 19.15.17.13 NMAC
- ☐ Confirmation Sampling Plan (if applicable) - based upon the appropriate requirements of Subsection C of 19.15.17.13 NMAC
- ☐ Disposal Facility Name and Permit Number (for liquids, drilling fluids and drill cuttings)
- ☐ Soil Backfill and Cover Design Specifications - based upon the appropriate requirements of Subsection H of 19.15.17.13 NMAC
- ☐ Re-vegetation Plan - based upon the appropriate requirements of Subsection H of 19.15.17.13 NMAC
- ☐ Site Reclamation Plan - based upon the appropriate requirements of Subsection H of 19.15.17.13 NMAC

15.
Siting Criteria (regarding on-site closure methods only): 19.15.17.10 NMAC
Instructions: Each siting criteria requires a demonstration of compliance in the closure plan. Recommendations of acceptable source material are provided below. Requests regarding changes to certain siting criteria require justifications and/or demonstrations of equivalency. Please refer to 19.15.17.10 NMAC for guidance.

Ground water is less than 25 feet below the bottom of the buried waste. - NM Office of the State Engineer - iWATERS database search; USGS; Data obtained from nearby wells	☐ Yes ☒ No ☐ NA
Ground water is between 25-50 feet below the bottom of the buried waste - NM Office of the State Engineer - iWATERS database search; USGS; Data obtained from nearby wells	☐ Yes ☒ No ☐ NA
Ground water is more than 100 feet below the bottom of the buried waste. - NM Office of the State Engineer - iWATERS database search; USGS; Data obtained from nearby wells	☒ Yes ☐ No ☐ NA
Within 100 feet of a continuously flowing watercourse, or 200 feet of any other significant watercourse, lakebed, sinkhole, or playa lake (measured from the ordinary high-water mark). - Topographic map; Visual inspection (certification) of the proposed site	☐ Yes ☒ No
Within 300 feet from a permanent residence, school, hospital, institution, or church in existence at the time of initial application. - Visual inspection (certification) of the proposed site; Aerial photo; Satellite image	☐ Yes ☒ No
Within 300 horizontal feet of a private, domestic fresh water well or spring used for domestic or stock watering purposes, in existence at the time of initial application. - NM Office of the State Engineer - iWATERS database; Visual inspection (certification) of the proposed site	☐ Yes ☒ No
Written confirmation or verification from the municipality; Written approval obtained from the municipality	☐ Yes ☒ No
Within 300 feet of a wetland. US Fish and Wildlife Wetland Identification map; Topographic map; Visual inspection (certification) of the proposed site	☐ Yes ☒ No
Within incorporated municipal boundaries or within a defined municipal fresh water well field covered under a municipal ordinance	

adopted pursuant to NMSA 1978, Section 3-27-3, as amended. - Written confirmation or verification from the municipality; Written approval obtained from the municipality	☐ Yes ☒ No
Within the area overlying a subsurface mine. - Written confirmation or verification or map from the NM EMNRD-Mining and Mineral Division	☐ Yes ☒ No
Within an unstable area. - Engineering measures incorporated into the design; NM Bureau of Geology & Mineral Resources; USGS; NM Geological Society; Topographic map	☐ Yes ☒ No
Within a 100-year floodplain. - FEMA map	☐ Yes ☒ No

16.
On-Site Closure Plan Checklist: (19.15.17.13 NMAC) ***Instructions: Each of the following items must be attached to the closure plan. Please indicate, by a check mark in the box, that the documents are attached.***

- ☒ Siting Criteria Compliance Demonstrations - based upon the appropriate requirements of 19.15.17.10 NMAC
- ☒ Proof of Surface Owner Notice - based upon the appropriate requirements of Subsection E of 19.15.17.13 NMAC
- ☐ Construction/Design Plan of Burial Trench (if applicable) based upon the appropriate requirements of Subsection K of 19.15.17.11 NMAC
- ☒ Construction/Design Plan of Temporary Pit (for in-place burial of a drying pad) - based upon the appropriate requirements of 19.15.17.11 NMAC
- ☒ Protocols and Procedures - based upon the appropriate requirements of 19.15.17.13 NMAC
- ☐ Confirmation Sampling Plan (if applicable) - based upon the appropriate requirements of 19.15.17.13 NMAC
- ☒ Waste Material Sampling Plan - based upon the appropriate requirements of 19.15.17.13 NMAC
- ☐ Disposal Facility Name and Permit Number (for liquids, drilling fluids and drill cuttings or in case on-site closure standards cannot be achieved)
- ☒ Soil Cover Design - based upon the appropriate requirements of Subsection H of 19.15.17.13 NMAC
- ☒ Re-vegetation Plan - based upon the appropriate requirements of Subsection H of 19.15.17.13 NMAC
- ☒ Site Reclamation Plan - based upon the appropriate requirements of Subsection H of 19.15.17.13 NMAC

17.
Operator Application Certification:

I hereby certify that the information submitted with this application is true, accurate and complete to the best of my knowledge and belief.

Name (Print): Richard Wright Title: Production Superintendent

Signature: Richard L. Wright Date: September 17, 2013

e-mail address: rwright@cazapetro.com Telephone: (432) 682-7472 (x1006)

18.
OCD Approval: ☒ MOD Permit Application (including closure plan) ☐ Closure Plan (only) ☐ OCD Conditions (see attachment)

OCD Representative Signature: Geoffrey Leking **Approval Date:** 9/18/13

Title: Environmental Specialist **OCD Permit Number:** P1-05637

19.
Closure Report (required within 60 days of closure completion): 19.15.17.13 NMAC

Instructions: Operators are required to obtain an approved closure plan prior to implementing any closure activities and submitting the closure report. The closure report is required to be submitted to the division within 60 days of the completion of the closure activities. Please do not complete this section of the form until an approved closure plan has been obtained and the closure activities have been completed.

☐ **Closure Completion Date:**

20.
Closure Method:

☐ Waste Excavation and Removal ☐ On-Site Closure Method ☐ Alternative Closure Method ☐ Waste Removal (Closed-loop systems only)

☐ If different from approved plan, please explain.

21.
Closure Report Attachment Checklist: ***Instructions: Each of the following items must be attached to the closure report. Please indicate, by a check mark in the box, that the documents are attached.***

- ☐ Proof of Closure Notice (surface owner and division)
- ☐ Proof of Deed Notice (required for on-site closure for private land only)
- ☐ Plot Plan (for on-site closures and temporary pits)
- ☐ Confirmation Sampling Analytical Results (if applicable)
- ☐ Waste Material Sampling Analytical Results (required for on-site closure)
- ☐ Disposal Facility Name and Permit Number
- ☐ Soil Backfilling and Cover Installation
- ☐ Re-vegetation Application Rates and Seeding Technique
- ☐ Site Reclamation (Photo Documentation)

On-site Closure Location: Latitude _____ Longitude _____ NAD: ☐1927 ☐ 1983

22.

Operator Closure Certification:

I hereby certify that the information and attachments submitted with this closure report is true, accurate and complete to the best of my knowledge and belief. I also certify that the closure complies with all applicable closure requirements and conditions specified in the approved closure plan.

Name (Print): _____ Title: _____

Signature: _____ Date: _____

e-mail address: _____ Telephone: _____

Distance to Groundwater

Figure 1, Figure 2, and the discussion presented below demonstrates that groundwater (fresh water as defined by NMOCD Rules) at the location is greater than 100 feet beneath the temporary pit.

Figure 1 is an area geologic and topographic map that shows:
1. The location of the temporary pit as an orange square.
2. Water wells from the OSE database as a blue triangle inside colored circles that indicate well depth. Please note, OSE wells are often miss-located in the WATERS database as older wells are plotted in the center of the quarter, quarter, quarter, of the Section Township and Range.
3. Water wells from the USGS database as large green triangles.
4. Water wells, which are not documented in the public databases but were identified by field inspection or other published reports as light blue squares.
5. The depth-to-water from the most recent available measurement for each well is provided adjacent to the well symbol.

Figure 2 is an area topographic map shows:
1. The location of the temporary pit as an orange square.
2. Water wells with the same symbols as those shown in Figure 1.
3. The date of the most recent depth-to-water measurement for each water well.

Geology

The proposed temporary pit is located on an outcrop of Quaternary Age older alluvial deposits (Qoa on Figure 1). These fine-grained sands and clays, along with the Quaternary eolian and piedmont deposits (Qe/Qp and Qp), are present as a thin covering of the underlying Tertiary Ogallala Formation. The Ogallala Formation consists primarily of sand with some clay, silt and gravel, generally capped by caliche. Based on information from Ground-Water Report 6 (GWR-6) *Geology and Ground-Water Conditions in Southern Lea County, New Mexico* by Alexander Nicholson and Alfred Clebsch (1961), the Ogallala Formation is approximately 100 to 150 feet thick and overlies a hard red-bed layer of the upper Triassic.

Topographically, the site is a located within the San Simon Swale, a broad (4-mile wide) northwest to southeast trending valley that is bordered by Antelope Ridge, 1.5 miles to the southwest and San Simon Ridge, 2.5 miles to the northeast. Approximately 200 feet of topographic relief is present from the top of the ridges to the valley floor. In the center of the valley, approximately 1.5 miles to the northeast of the site is the San Simon Sink, a broad (1-mile wide) topographic depression that extends to approximately 70 feet below the valley floor.

Water Table Elevation

Nine water wells were identified in the area surrounding the Caza Ridge 14 State No. 4H site to determine the water table elevation below the temporary pit. They include four wells from the New Mexico Office of the State Engineer (OSE) database and three wells from the USGS database. Water well #33 is not included in the published databases but is described in both the Open File Report No. 95 (OFR-95) and GWR-6. Water well #42 was identified only by field

inspection. A summary of the available water well data, with respect to groundwater elevation, is provided on the table below.

Well Numbers	Well Location						Well Source Information							Groundwater Elevation Data						Gauging Date
	Township (south)	Range (east)	Section	Quarter Section (64,	16,	4)	NM-OSE Database	USGS Database	Open File Rpt. 95	GW Report No. 6	USGS Topo Sheet	Aerial Photograph	Field Verification	Surface Elevation (published)	Surface Elevation (Topo Sheet)	Well Total Depth (published)	Depth to Water (published)	Groundwater Elev. (published)	Groundwater Elev. (using topo elev.)	
#33 (Wood)	23	35	6	3	3	3			✓	✓	✓	✓	✓	3,359	3,360	149	141.4	3,218	3,219	11/18/77
#E-07616	23	34	11	4	4	1	✓						--	3,370	3,370	500	300	3,070	3,070	8/20/00
#503	23	34	16	3	3	3		✓			✓		--	3,478	3,487	--	345.3	3,133	3,142	3/8/96
#CP-00637	23	34	15	3	3	4	✓					✓	--	3,450	3,450	430	430	3,020	3,020	7/9/81
#CP-00618	23	34	22	1	2	4	✓							3,423	3,420	428	295	3,128	3,125	5/5/80
#CP-00606	23	34	23	1	4	1	✓							3,388	3,390	650	265	3,123	3,125	7/26/79
#499	23	34	22	2	4	4		✓						3,420	3,420	--	282.2	3,138	3,138	3/8/96
#42 (Deep)	23	34	23	1	4	4					✓	✓	✓	--	3,375	--	232.9	--	3,142	10/10/12
#486	23	35	29	2	2	2		✓			✓	--	--	3,370	3,370	--	234.8	3,135	3,135	3/13/96

✓ Indicates well was verified, (blank) indicates well not verified, and -- indicates no attempt to verify



Visual inspections of questionable wells were performed to verify the information provided by the public records and published reports. Initially, an attempt was made to identify each well using USGS topographic maps. The surface elevations of wells identified on the maps were compared to the published surface elevation, if available. Wells that could not be verified using maps were searched for using current and historic satellite photographs in an effort to identify windmills, tanks, or roads associated with the well. Locations that could not be verified by maps or photographs were verified in the field. Attempts were also made to gauge wells during the field investigation when access was permitted. The results of the field inspections are summarized as follows:

- Only two of the nine water wells (#33 and #42) could be physically located by field inspection. Water well #42 was accessed on October 10, 2012 and the depth-to-water was measured at 232.9 feet below ground surface.

- Water well #CP-00637 is believed to be located at a gas plant, but was not located. Of the remaining six wells, a careful search was conducted for the three nearest wells (#CP-00606, #CP-00618, and #499), based on the location provided by the database. It is assumed that these wells were present but abandoned prior to 1997 (earliest available aerial photograph). This level of confidence is based on a favorable comparison of the published surface elevation with the USGS topographic map elevation at the reported well locations.

Hydrogeology

GWR-6 (1961) indicates that Ogallala groundwater is not present as a regional aquifer within the San Simon Swale, although well #33, located approximately 2 miles to the northeast of the site is designated as an Ogallala (Tertiary) well with a total depth of 149 feet (3,210 feet above sea level). Based on the depth-to-water measurements (published and recent) the regional

groundwater (Triassic Santa Rosa Formation) is present across the area at an elevation below 3,150 feet.

The most recent depth-to-water measurement was taken by the RTH field investigator from water well #42, located 4,000 feet south of the Caza Ridge 14 State #4H site as discussed above. Based on that measurement the groundwater elevation is 3,142 feet above sea level, which is consistent with the published data from the nearby wells. The surface elevation at the proposed location of the temporary pit is 3,366 feet above sea level (approximately 224 feet above the groundwater depth).

Distance to Surface Water

Figure 3 and the site visit demonstrates that the location is not within 300 feet of a continuously flowing watercourse, or 200 feet of any other significant watercourse or lakebed, sinkhole, or playa lake (measured from the ordinary high-water mark).

- The nearest topographic low area is the San Simon Sink located 1.5 miles to the northeast, but it did not contain surface water on the day of the inspection.
- No other watercourses, as defined by NMOCD Rules, or water bodies exist with 300-feet of the location.

Distance to Permanent Residence or Structures

Figure 4 and the site visit demonstrates that the location is not within 300 feet from a permanent residence, school, hospital, institution, church, or other structure in existence at the time of initial application.

Distance to Non-Public Water Supply

Figures 1 and Figure 2 demonstrates that the location is not within 500 horizontal feet of a private, domestic fresh water well or spring that less than five households use for domestic or stock watering purposes, or within 1000 horizontal feet of any other fresh water well or spring, in existence at the time of initial application.

- Figure 1 and 2 show the locations of all area water; the nearest water well is located approximately 4,000 feet to the south (Water well #42). There are no known domestic water wells located within the mapping area.
- No springs were identified within the mapping area.

Distance to Municipal Boundaries and Fresh Water Fields

Figure 5 demonstrates that the location is not within incorporated municipal boundaries or defined municipal fresh water well fields covered under a municipal ordinance adopted pursuant to NMSA 1978, Section 3-27-3, as amended.

- The closest municipality is Eunice, NM approximately 22 miles to the northeast.
- The closest public well field is located approximately 43 miles to the northwest.

Distance to Wetlands

Figure 6 demonstrates the location is not within 500 feet of wetlands.

- The nearest designated wetlands is a "Freshwater Pond" located approximately 1.5 mile to the northeast (San Simon Sink).

Distance to Subsurface Mines

Figure 7 and our general reconnaissance of the area demonstrate that the nearest subsurface mines are caliche pits.

- The nearest caliche pit is located approximately 5 miles to the southwest.

Distance to High or Critical Karst Areas

Figure 8 shows the location of the temporary pits with respect BLM Karst areas

- The proposed temporary pit is located within a "low" potential karst area.
- The nearest "high" or "critical" potential karst area is located approximately 28 miles west of the site.
- No evidence of solution voids were observed near the site during the field inspection.

Distance to 100-Year Floodplain

Figure 9 demonstrates that the location is within an area that has not yet been mapped by the Federal Emergency Management Agency with respect to the Flood Insurance Rate 100-Year Floodplain.

Site Specific Information
Figures

R.T. Hicks Consultants, Ltd.
901 Rio Grande Blvd. NW, Suite F-142
Albuquerque, NM 87104



R.T. Hicks Consultants, Ltd 901 Rio Grande Blvd NW Suite F-142 Albuquerque, NM 87104 Ph: 505.266.5004	Geology and Depth to Groundwater	Figure 1
	Caza Operating - Caza Ridge 14 State 4H	Jan 2013



R.T. Hicks Consultants, Ltd 901 Rio Grande Blvd NW Suite F-142 Albuquerque, NM 87104 Ph: 505.266.5004	Date of Water Level Measurements	Figure 2
	Caza Operating - Caza Ridge 14 State 4H	Jan 2013



R.T. Hicks Consultants, Ltd 901 Rio Grande Blvd NW Suite F-142 Albuquerque, NM 87104 Ph: 505.266.5004	Nearest Surface Water or Sinkhole	Figure 3
	Caza Operating - Caza Ridge 14 State 4H	Jan 2013



R.T. Hicks Consultants, Ltd
901 Rio Grande Blvd NW Suite F-142
Albuquerque, NM 87104
Ph: 505.266.5004

Nearest Structures

Caza Operating - Caza Ridge 14 State 4H

Figure 4

Jan 2013



N
W E
S

0 5 Miles

R.T. Hicks Consultants, Ltd 901 Rio Grande Blvd NW Suite F-142 Albuquerque, NM 87104 Ph: 505.266.5004	Nearest Municipal Boundaries and Wellfields	Figure 5
	Caza Operating - Caza Ridge 14 State 4H	Jan 2013



R.T. Hicks Consultants, Ltd
901 Rio Grande Blvd NW Suite F-142
Albuquerque, NM 87104
Ph: 505.266.5004

Nearest Wetland

Caza Operating - Caza Ridge 14 State 4H

Figure 6

Jan 2013



R.T. Hicks Consultants, Ltd 901 Rio Grande Blvd NW Suite F-142 Albuquerque, NM 87104 Ph: 505.266.5004	Nearest Mines	Figure 7
	Caza Operating - Caza Ridge 14 State 4H	Jan 2013



R.T. Hicks Consultants, Ltd
901 Rio Grande Blvd NW Suite F-142
Albuquerque, NM 87104
Ph: 505.266.5004

BLM Cave/Karst Potential Map

Figure 8

Caza Operating - Caza Ridge 14 State 4H

Jan 2013

Figure 9



NATIONAL FLOOD INSURANCE PROGRAM

MAP INDEX

FIRM

FLOOD INSURANCE RATE MAP

LEA COUNTY,
NEW MEXICO
AND INCORPORATED AREAS

MAP INDEX

PANELS PRINTED: 440, 445, 955, 965, 1165, 1170, 1200, 1335, 1345, 1355, 1365, 1670, 2102

MAP NUMBER
35025CIND0A

EFFECTIVE DATE
DECEMBER 16, 2008

Federal Emergency Management Agency

Site Specific Information Plates

R.T. Hicks Consultants, Ltd.
901 Rio Grande Blvd. NW, Suite F-142
Albuquerque, NM 87104



R.T. Hicks Consultants 901 Rio Grande Blvd. NW Suite F-142 Albuquerque, N. M. 87104	**Drilling Cell**	**Plate 1**	North
	Caza Operating - Caza Ridge 14 State 4H	**Jan-13**	



Overall Drilling Cell Dimensions	Total Width of both Cells	**167.0**	[feet]
	Toal Length of both Cells	**116.0**	
	Rise over Run for all slopes	**2.0**	[-]
Inner Horseshoe Pit Dimensions	Width of Inner Horseshoe Cell	**75.0**	[feet]
	Length of Inner Horseshoe Cell	**70.0**	
	Depth of Inner Horseshoe Cell	**7.0**	
	Inner Horseshoe Cell Floor (A to A')	**22.0**	[feet]
	Inner Horseshoe Cell Floor "width" (B to B')	**9.0**	
	Width of Inner Horseshoe Divider on the ground surface	**1.0**	[feet]
	Length of Inner Horseshoe Divider on the ground surface	**20.0**	
Divider Dimensions	Width of Divider between Inner and Outer Horseshoe Cells	**1.0**	[feet]
Outer Horseshoe Pit Dimensions	Length of Outer Horseshoe Cell (Discharge Side)	**116.0**	*[feet]*
	Width of Outer Horseshoe Cell (Discharge Side)	**50.0**	
	Depth of Outer Horseshoe Cell (Discharge Side)	**6.0**	
	Length of Outer Horseshoe Cell (Suction Side)	**116.0**	[feet]
	Width of Outer Horseshoe Cell (Suction Side)	**40.0**	
	Depth of Outer Horseshoe Cell (Suction Side)	**7.0**	
	Length of Outer Horseshoe Cell (Far Side)	**45.0**	[feet]
	Width of Outer Horseshoe Cell (Far Side)	**167.0**	
	Depth of Outer Horseshoe Cell (Far Side)	**8.0**	
	Width of Outer Horseshoe Cell Floor (Suction Side C to C')	**12.0**	[feet]
	Width of Outer Horseshoe Cell Floor (Far Side D to D')	**17.0**	
	Width of Outer Horseshoe Cell Floor (Discharge Side E to E')	**22.00**	

R.T. Hicks Consultants
901 Rio Grande Blvd. NW
Suite F-142
Albuquerque, N. M. 87104

Drilling Cell Dimenstion	**Plate 2**
Caza Operating - Caza Ridge 14 State 4H	**Jan-13**



R.T. Hicks Consultants 901 Rio Grande Blvd. NW Suite F-142 Albuquerque, N. M. 87104	**Pad Dimensions and Pit in Relation to Borehole Location, Caza Ridge State # 14**	**Plate 3**
	Caza Operating Company	**February, 2013**



Pad Dimensions	Overall Pad Width (East-West Dimension)	**400.0**	[feet]
	Overall Pad Length (North-South Dimension)	**400.0**	
	Distance From Eastern Site Boundary to Borehole	**200.0**	
	Distance from Southern Site Boundary to Borehole	**200.0**	

Pit Location Relative to Borehole	Distance from Borehole to Southern side of Pit	**55.0**	[feet]
	Distance from SW corner of Inner Horseshoe to Borehole North-South Axis	**75.0**	

Overall Pit Dimensions	Total Width of Drilling and Fluid Cells (East-West)	**327.0**	[feet]
	Total Length of Cells (North-South)	**116.0**	
	Rise over Run for all slopes	**2.0**	[-]

Drilling Cell Dimensions	Width of Inner Horseshoe and Outer Horseshoe (East West Dimension includes dividers)	**167.0**	[feet]
	Length of Inner Horseshoe and Outer Horseshoe Cells (North-South Dimension includes divider)	**116.0**	
	Length of Inner Horseshoe Divider on the ground surface (North-South dimension)	**20.0**	[feet]
	Distance from SW corner of Inner Horseshoe to Inner Horseshoe Divider Axis	**37.5**	

Fluid Cell Dimensions	Length of Fluid Cell (North-South Dimension ofEast Side Cell)	**116.0**	[feet]
	Width of Fluid Cell (East - West dimension of East Side Cell)	**150.0**	
	Depth of Fluid Cell	**12.0**	
	Length of Fluid Cell Floor (North-South Dimension)	**68.0**	[feet]
	Width of Fluid Cell floor (East - West dimension)	**102.0**	
	Divider Width between Drilling Cells and Fluid Cell	**10.0**	[feet]

R.T. Hicks Consultants 901 Rio Grande Blvd. NW Suite F-142 Albuquerque, N. M. 87104	**Dimensions of Drilling Pit in Relation to Site Dimensions, Caza Ridge State #14**	**Plate 4**
	Caza Operating Company	**February 2013**

Appendix A

Survey Information

R.T. Hicks Consultants, Ltd.
901 Rio Grande Blvd. NW, Suite F-142
Albuquerque, NM 87104

SECTION 14, TOWNSHIP 23 SOUTH, RANGE 34 EAST, N.M.P.M.

LEA COUNTY NEW MEXICO



DIRECTIONS TO CAZA RIDGE 14 STATE #4H

FROM THE INTERSECTION OF DELAWARE BASIN ROAD AND ADOBE ROAD GO EAST APPROX. 1.2 MILES; TURN RIGHT AND GO SOUTH APPROX. 1.9 MILES. THIS LOCATION IS APPROX. 650' EAST.

200 0 200 400 Feet

Scale: 1"=200'

CAZA OPERATING, LLC

CAZA RIDGE 14 STATE #4H WELL
LOCATED 330 FEET FROM THE SOUTH LINE
AND 660 FEET FROM THE EAST LINE OF SECTION 14,
TOWNSHIP 23 SOUTH, RANGE 34 EAST, N.M.P.M.,
LEA COUNTY, NEW MEXICO

Survey Date: 1/15/13	CAD Date: 1/17/13	Drawn By: BKL	
W.O. No.: 13110069	Rev: .	Rel. W.O.:	Sheet 1 of 1

PROVIDING SURVEYING SERVICES
SINCE 1946
JOHN WEST SURVEYING COMPANY
412 N. DAL PASO
HOBBS, N.M. 88240
(575) 393-3117 www.jwsc.biz

Generic Plans for Temporary Pits

R.T. Hicks Consultants, Ltd.
901 Rio Grande Blvd. NW, Suite F-142
Albuquerque, NM 87104

Temporary Pit Design/Construction Plan

Plates 1, 2, 3 and 4 show the design of the temporary pit proposed for this project. Field conditions and the drilling rig layout will determine the final configuration of the pit cells, which will consists of the following:

1. A cell for drilling fluid circulation and cuttings storage consisting of:
    a. An outer horseshoe for fresh water and cut-brine fluid and cuttings
    b. An inner horseshoe for brine and fluid and cuttings
2. A cell for the storage of fresh water (drilling/stimulation) and stimulation flow-back water prior to re-use or disposal (Plate 3 and 4)

In addition to the commitments listed below, the operator will install a system that can drain water entrained in the drilling waste of the drilling pit. As described in the closure plan, this system of fabric-wrapped perforated pipe and drainage mats lie on the bottom of the drilling cell of the pit – the brine cell and the outer cell. The system will drain to the lowest corner of each cell, generally near the suction area. The exact location will be determined upon completion of the cells. Standpipes rise from the depression and can house a solar-powered pump. The drainage system for the brine cell removes water to an above-ground tank, the fluids cell of the pit, or directly to a truck for re-use or disposal. The drainage system may also be used to introduce fresher water below the residual cuttings/mud, causing the introduced fluid to move upwards through the cuttings/mud and enhance the solids rinsing process. Introduced water can be removed from the pit for re-use via a vacuum truck or recovered from the drainage system at the bottom.

The temporary storage of fluids, fluid reuse or fluid disposal will be conducted in a manner approved by division rules that prevents the contamination of fresh water and protects public health and the environment. This drainage and rinsing system allows the operator to:

- Recover clear water for possible re-use
- Reduce the concentration of constituents of concern in the drilling waste by removing some water entrained in the drilling waste.

Precipitation and the possible addition of relatively fresh water (see closure plan) will rinse the solid drilling waste, causing additional reduction in the constituents of concern as the water is recovered for re-use or disposal.

For any temporary storage of fluids derived from the drilling pit and placed in an above-ground tank, the following will apply:

1. Construction, operation and maintenance of the temporary storage tank(s) will adhere to all applicable NMOCD Rules including but not limited to:
    a. Safety stipulations
    b. Protection from hydrogen sulfide mandates
    c. Signage and identification requirements
    d. Secondary containment requirements for temporary tanks
    e. Applicable netting requirements

2. Any cleaning of the temporary tank(s) will adhere to NMOCD Rules relating to tank cleaning.
3. Transportation of water or drilling fluids derived from the drilling pit will adhere to all applicable NMOCD Rules relating to transportation.
4. Storage of water or drilling fluids in temporary above-ground tanks will also adhere to all applicable Federal mandates.

During final closure of the pit, the tanks and secondary containment system will be removed from the location and the area beneath the tank inspected for any leakage. If any leakage is suspected, the operator will sample the soil beneath the tanks and report any release pursuant to NMOCD Rules.

Finally, we intend to place any temporary tank used in conjunction with the pit drainage system on a 20-mil liner with a berm around it that would allow any inadvertently released fluids to drain or be pumped back into the pit.

Construction/Design Plan of Temporary Pit

Stockpile Topsoil

Prior to constructing the pit the qualified contractor will strip and stockpile the topsoil for use as the final cover or fill at the time of closure.

Signage

The operator will post an upright sign in a conspicuous place in compliance with 19.15.16.8 NMAC as the pit and the well are operated by the same operator. Section 19.15.16.8 states in part:

> 19.15.16.8 SIGN ON WELLS:
> B. For drilling wells, the operator shall post the sign on the derrick or not more than 20 feet from the well.
> C. The sign shall be of durable construction and the lettering shall be legible and large enough to be read under normal conditions at a distance of 50 feet.
> F. Each sign shall show the:
> (1) well number;
> (2) property name;
> (3) operator's name;
> (4) location by footage, quarter-quarter section, township and range (or unit letter can be substituted for the quarter-quarter section);
> and
> (5) API number.

The sign will also provide emergency telephone numbers.

Fencing:

During drilling or workover operations, the operator will not fence the edge of the pit adjacent to the drilling or workover rig.

As the pit is not located within 1000 feet of a permanent residence, school, hospital, institution or church, the operator will fence the pit to exclude livestock with four-wire strands evenly spaced in the interval between one foot and four feet above ground level.

Earthwork

The temporary pit will have a properly constructed foundation and interior slopes consisting of a firm, unyielding base, smooth and free of rocks, debris, sharp edges or irregularities to prevent the liner's rupture or tear.

The slopes of the pit will be no steeper than two horizontal feet to one vertical foot (2H:1V) unless in the transmittal letter the operator requested an alternative to the slope requirement with a demonstration that the pit can be operated in a safe manner to prevent contamination of fresh water and protect public health and the environment.

A berm or ditch will surround the temporary pit to prevent run-on of surface water.

If the transmittal letter identifies concerns relating to the presence of karst and associated instability, during construction of the pit the contractor will compact the earth material that forms the foundation for the pit liner. An expected proctor density of greater than 90% will be achieved by

1. adding water to the earth material as appropriate,
2. compacting the earth by walking a crawler-type tractor down the sides and bottom of the pit
3. repeating this process with a second 6-inch lift of earth material if necessary

Liner Installation

The geomembrane liner will consist of 20-mil string reinforced HDPE or equivalent liner material identified in the transmittal letter or on Form C-144 (that the appropriate division district office approves through approval of this permit application). The geomembrane liner will be composed of an impervious, synthetic material that is resistant to petroleum hydrocarbons, salts and acidic and alkaline solutions. The liner material will be resistant to ultraviolet light. Liner compatibility will comply with EPA SW-846 method 9090A.

The operator will direct the liner installation contractor to:

1. minimize liner seams and orient them up and down, not across a slope
2. use factory welded seams where possible
3. overlap liners four to six inches and orient seams parallel to the line of maximum slope, i.e., oriented along, not across, the slope, prior to any field seaming
4. minimize the number of welded field seams in comers and irregularly shaped areas
5. utilize only qualified personnel to weld field seams
6. avoid excessive stress-strain on the liner
7. place geotextile under the liner where needed to reduce localized stress-strain or protuberances that may otherwise compromise the liner's integrity
8. anchor the edges of all liners in the bottom of a compacted earth-filled trench that is at least 18 inches deep
9. place additional material (liner, felt, etc.) to ensure that the liner is protected from any fluid force or mechanical damage at any point of discharge into or suction from the lined temporary pit.

A berm or ditch will surround the temporary pit to prevent run-on of surface water. During drilling operations, the operator may elect to remove run-on protection on the pit edge adjacent to the drilling or workover rig provided that the pit is being used to collect liquids escaping from the drilling or workover rig and this additional fluid will not cause a breach of the temporary pit.

The temporary pit will not be used to vent or flare gas and the volume of the temporary drilling pit, including freeboard, will not exceed 10 acre-feet.

Temporary Pit Operating and Maintenance Plan

The operator will maintain and operate the pit in accordance with the following plan to contain liquids and solids and maintain the integrity of the liner to prevent contamination of fresh water and protect public health and the environment.

If feasible, the operator will recycle, reuse or reclaim all drilling fluids in the temporary pit in a manner approved by division rules that prevents the contamination of fresh water and protects public health and the environment. Re-use of drilling fluids and workover fluids (stimulation flow-back) for drilling and stimulation of subsequent wells is anticipated. If re-use is not possible, fluids will be sent to disposal at a division-approved facility.

The operator will not discharge into or store any hazardous waste in the pit.

If the pit develops a leak or if any penetration of the pit liner occurs above the liquid's surface, then the operator will repair the damage or initiate replacement of the liner within 48 hours of discovery or will seek a variance from the division district office within this time period.

If the pit develops a leak or if any penetration of the pit liner occurs below the liquid's surface, then the operator will remove all liquid above the damage or leak line within 48 hours of discovery. The operator will also notify the district division office (19.15.29 NMAC) within this same 48 hours of the discovery and repair the damage or replace the pit liner.

The operator will ensure that the drilling contractor installs and uses a header, diverter or other hardware that prevents damage to the liner by erosion, fluid jets or impact from installation and removal of hoses or pipes during injection or withdrawal of liquids.

During construction, the operator or qualified contractor will install diversion ditches and berms around the pit as necessary to prevent the collection of surface water run-on. As outlined in the Construction and Design Plan, during drilling operations, the edge of the temporary pit adjacent to the drilling or workover rig may not have run-on protection if the operator is using the temporary pit to collect liquids escaping from the drilling or workover rig and run-on will not result in a breach of the temporary pit.

The operator will maintain on site an oil absorbent boom to contain and remove oil from the pit's surface.

The operator will only discharge fluids or mineral solids (including cement) generated or used during the drilling, completion, or workover processes into the pit.

The operator will maintain the temporary pit free of miscellaneous solid waste or debris. Immediately after cessation of drilling or a workover operation, the operator will remove any visible or measurable layer of oil from the surface of the pit.

The operator will maintain at least two feet of freeboard for the temporary pit, except under extenuating circumstances, which will be noted on the pit inspection log as described below.

The operator will inspect the temporary pit containing drilling fluids daily while the drilling rig or workover rig is on site. After the rigs have left the site, the operator will inspect the pit weekly as long as liquids are present in the pit. The operator will maintain a log of the inspections. The operator will make the log available to the division district office upon request.

The operator will remove all free drilling fluids from the surface of the temporary pit within 60 days from the date that the last drilling or workover rig associated with the pit permit is released. The operator will note the date of this release upon Form C-105 or C-103 upon well or workover completion. The operator may request an extension up to two months from the division district office as long as this additional time does not exceed the temporary pit life span (Subsection R of 19.15.17.7 NMAC).

Temporary Pit In-Place Closure Plan

The wastes in the temporary pit are destined for in place burial at the drilling location or, if stated in the permit transmittal letter, a nearby site on the same lease.

The operator will not begin closure operations without approval of the closure plan submitted with the permit application.

Siting Criteria Compliance Demonstration

Compliance with siting criteria is described in the site-specific information appended to the C-144.

Proof of Surface Owner Notice

The application package was transmitted to the surface landowner and OCD via email.

Construction/Design Plan of Temporary Pit

The design and construction protocols for the temporary pit are provided in the design and construction plan and in Plates 1-2. The drainage system described in the design and construction plan (above) is not shown on the Plates but can be important element of the closure plan.

General Protocols and Procedures

- All free liquids from the pit will be recycled or disposed in a manner consistent with OCD Rules.
- Residual drilling fluids will be removed from the pit within 60 days of release of the drilling rig.
- Water derived from the well stimulation program (flow-back or unused fresh water) that is significantly higher quality than the residual drilling fluids *may* discharge into the pit. The fresher water *may* discharge into the drainage system to flow through the solids or onto the solids in the pit.
- A low-flow pump *may* remove water from the drainage system to a tank or a fluids cell of the temporary pit; thereby further rinsing the residual solids in the pit.
- 20-60 days after placement of fresh flow-back water into the drilling cell, any water in the pit will be removed for re-use or disposal.
- The residual drilling mud and cuttings will be stabilized to a capacity sufficient to support the 4-foot thick soil cover.
- The residual pit solids will not be mixed at a ratio greater than 1 part pit solids to 3 parts dry earth material (e.g. subsoil).
- The pit will not be closed until the stabilized pit contents pass the paint filter liquids test.

Waste Material Sampling Plan

Prior to closure, a five-point (minimum) composite sample of the residual solids in the pit will be tested in a laboratory to demonstrate that the stabilized material will not exceed the contaminant concentrations listed in Table II of 19.15.17.13 NMAC mixed in a ratio of 3:1 with the earth material to be used for mixing and stabilization of the residual cuttings and mud.

In-place burial is the selected on-site disposal alternative.

If a concentration of a contaminant within the material mixed at a ratio not exceeding 3:1 is higher than the concentration given in Table II, closure will proceed in accordance with Subsection C of 19.15.17.13 NMAC.

Protocols and Procedures for Earthwork

Stabilization of the residual cuttings and mud is accomplished by mixing dry earth material within the temporary pit footprint. After stabilization the operator or qualified contractor will:

1. Place a geomembrane cover over the waste material in a way to prevent infiltration of water and so that infiltrated water does not collect on the geomembrane cover after the upper soil cover has been placed.
2. Use a geomembrane cover made of 20-mil string reinforced HDPE liner or an equivalent cover approved by the district office that is composed of an impervious, synthetic material that is resistant to petroleum hydrocarbons, salts and acidic and alkaline solutions and complies with EPA SW-846 Method 9090A.
3. Over the sloping, stabilized material and liner, place the **Soil Cover Design**:
   a. at least 3-feet of compacted, uncontaminated, non-waste containing earthen fill with chloride concentrations less than 600 mg/kg as analyzed by EPA Method 300.0.
   b. either the background thickness of topsoil or one foot of suitable material to establish vegetation at the site, whichever is greater, over the 3-foot earth material.
4. Contour the cover to blend with the surrounding topography and to prevent erosion of the cover and ponding over the cover.

Closure Notice

The operator will notify the surface owner by certified mail, return receipt requested, that the operator plans closure operations at least 72 hours, but not more than one week, prior to any closure operation. The notice will include the well name, API number, and location.

After approval for in-place burial, the operator shall notify the district office verbally and in writing at least 72 hours but not more than one week before any closure operation. Notice will include the operator's and the location of the temporary pit. The location will include unit letter, section number, township and range. If the location is associated with a well, then the well's name, number and API number will be included.

Should onsite burial be on private land, the operator will file a deed notice including exact location of the burial with the county clerk of the county where the onsite burial is located.

Closure Report

Within 60 days of closure completion, the operator will submit a

i. closure report on form C-144, with necessary attachments
ii. a certification that all information in the report and attachments is correct, that the operator has complied with all applicable closure requirements and conditions

specified in the approved closure plan

iii. a plat of the pit location on form C-l05

iv. if burial is in a nearby trench/pit, a separate C-105 showing the exact location

Unless the permit transmittal letter requests an alternative maker to comply with surface landowner specifications, the operator will place at the center of an onsite burial a steel marker that

- is not less than four inches in diameter
- is placed at the bottom of a three-foot deep hole (minimum) that is filled with cement to secure the marker
- is at least four feet above mean ground level
- permanently displays the operator name, lease name, well number, unit letter, section, township and range in welded or stamped legible letters/numbers

Timing of Closure

The operator will close the temporary pit within 6 months from the date the drilling or workover rig was released from the site. This date will be noted on form C-105 or C-103 filed with the division upon the well's or workover's completion.

Reclamation and Re-vegetation Plan

In addition to the area of the in-place burial, the operator will reclaim to a safe and stable condition that blends with the surrounding undisturbed area

1. the pit location not used for burial
2. other areas associated with the in-place burial including access roads

Areas not reclaimed as described herein due to their use in production or drilling operations will be stabilized and maintained to minimize dust and erosion.

As stated above, the soil cover for burial in-place

A. consists of a minimum of three feet of non-waste containing, uncontaminated, earthen material with chloride concentrations less than 600 mg/kg as analyzed by EPA Method 300.0 placed over the liner and stabilized solids

B. is capped by the background thickness of topsoil or 1-foot of suitable material to establish vegetation, whichever is greater

C. blends into surrounding topography

D. is graded to prevent ponding and to minimize erosion

For all areas disturbed by the closure process that will not be used for production operations or future drilling, the operator will

I. Replace topsoils and subsoils to their original relative positions

II. Grade so as to achieve erosion control, long-term stability and preservation of surface

water flow patterns

III. Reseed in the first favorable growing season following closure

Re-vegetation and reclamation plans imposed by the surface owner will be outlined in communications with the OCD.

The operator will notify the division when the surface grading work element of reclamation is complete.

The operator will notify the division when the site meets the surface owner's requirements or exhibits a uniform vegetative cover that reflects a life-form ratio of plus or minus fifty percent (50%) of pre-disturbance levels and a total percent plant cover of at least seventy percent (70%) of pre-disturbance levels, excluding noxious weeds.