

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

HOBBS OCD

## APPLICATION FOR PERMIT TO DRILL OR REENTER

AUG 08 2014

|                                                                                                                                                                                                                        |                                                     |                                                                                      |                                                   |
|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------|--------------------------------------------------------------------------------------|---------------------------------------------------|
| 1a. Type of work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER                                                                                                                           |                                                     | 7. If Unit or CA Agreement, Name and No.                                             |                                                   |
| 1b. Type of Well: <input checked="" type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Other <input checked="" type="checkbox"/> Single Zone <input type="checkbox"/> Multiple Zone |                                                     | 8. Lease Name and Well No. <b>313575</b><br>War Hammer 25 Federal COM W1 3H          |                                                   |
| 2. Name of Operator<br>ConocoPhillips Company <b>217817</b>                                                                                                                                                            |                                                     | 9. API Well No.<br><b>30-025-42027</b>                                               |                                                   |
| 3a. Address P.O. BOX 51810<br>Midland, Texas 79710                                                                                                                                                                     |                                                     | 10. Field and Pool, or Exploratory <b>98081</b><br><b>WC-025 G09 3263225A</b>        |                                                   |
| 3b. Phone No. (include area code)<br>(281)206-5282                                                                                                                                                                     |                                                     | 11. Sec., T. R. M. or Blk. and Survey or Area <b>WOLF CAMP</b><br>Section 25-26S-32E |                                                   |
| 4. Location of Well (Report location clearly and in accordance with any State requirements. *)<br>At surface 316 FNL & 125 FEL (NWNW) 25-26S-32E<br>At proposed prod. zone 330 FSL & 380 FEL 36-26S-32E                |                                                     | 12. County or Parish<br>Lea                                                          |                                                   |
| 14. Distance in miles and direction from nearest town or post office*<br>35.7 miles west of Jal, NM.                                                                                                                   |                                                     | 13. State<br>NM                                                                      |                                                   |
| 15. Distance from proposed* location to nearest property or lease line, ft.<br>(Also to nearest drig. unit line, if any)                                                                                               | 330'                                                | 16. No. of acres in lease<br>600                                                     | 17. Spacing Unit dedicated to this well<br>224.99 |
| 18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft.                                                                                                             | 33'                                                 | 19. Proposed Depth<br>18865' MD/12355' TVD                                           | 20. BLM/BIA Bond No. on file<br>ES0085            |
| 21. Elevations (Show whether DF, KDB, RT, GL, etc.)<br>3138' GL                                                                                                                                                        | 22. Approximate date work will start*<br>01/01/2015 | 23. Estimated duration<br>30 days                                                    |                                                   |

## 24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No.1, must be attached to this form:

- |                                                                                                                                                |                                                                                                 |
|------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------|
| 1. Well plat certified by a registered surveyor.                                                                                               | 4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above). |
| 2. A Drilling Plan.                                                                                                                            | 5. Operator certification                                                                       |
| 3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO must be filed with the appropriate Forest Service Office). | 6. Such other site specific information and/or plans as may be required by the BLM.             |

|                                             |                                          |                          |
|---------------------------------------------|------------------------------------------|--------------------------|
| 25. Signature <b>Kristina Mickens</b>       | Name (Printed/Typed)<br>KRISTINA MICKENS | Date<br>03/03/2014       |
| Title<br>REGULATORY SPECIALIST              |                                          |                          |
| Approved by (Signature) <b>Steve Caffey</b> | Name (Printed/Typed)                     | Date <b>AUG - 6 2014</b> |
| Title<br>FIELD MANAGER                      |                                          |                          |
| Office<br>CARLSBAD FIELD OFFICE             |                                          |                          |

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Conditions of approval, if any, are attached.

APPROVAL FOR TWO YEARS

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Continued on page 2)

Carlsbad Controlled Water Basin

**KZ**  
**08/08/14**

E-PERMITTING - - **New Well KZ**

Comp \_\_\_\_\_ P&A \_\_\_\_\_ TA \_\_\_\_\_

CSNG \_\_\_\_\_ Loc CHG \_\_\_\_\_

ReComp \_\_\_\_\_ Add New Pool \_\_\_\_\_

Cancel Well \_\_\_\_\_ Create Pool \_\_\_\_\_

Approval Subject to General Requirements  
& Special Stipulations AttachedSEE ATTACHED FOR  
CONDITIONS OF APPROVAL

AUG 08 2014

## Operator Certification

HOBBS OCD

AUG 08 2014

CONOCOPHILLIPS COMPANY

RECEIVED

### CERTIFICATION:

I hereby certify that I, or persons under my direct supervision, have inspected the proposed drill site and access route proposed herein; that I am familiar with the conditions which currently exist; that I have full knowledge of State and Federal laws applicable to this operation; that the statements made in this APD package are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for the operations conducted under this application with bond coverage provided by Nationwide Bond ES0085. These statements are subject to the provisions of 18 U.S.C. 1001 for the filing of false statements.



Date: 03/03/2014

Kristina Mickens  
Regulatory Specialist

**Drilling Program**  
**ConocoPhillips Company**  
 War Hammer 25 Federal COM W3 1H  
 250' FNL 125' FEL (SHL)  
 330' FSL 380' FEL (BHL)  
 Sec 25-T26S-R32E  
 Lea County, New Mexico

**HOBBS OCD**

**AUG 08 2014**

**RECEIVED**

**1. Estimated tops of geological formations:**  
 Geologic Formation at surface: Quaternary

| Formation          | TVD (ft) |
|--------------------|----------|
| Base Fresh Water   | 300      |
| Rustler            | 600      |
| Top Salt           | 1050     |
| Base Salt          | 4689     |
| * Cherry Canyon    | 5671     |
| * Brushy Canyon    | 7368     |
| * Bone Spring Carb | 8865     |
| * Avalon           | 9071     |
| * 1st Bone Spring  | 9758     |
| * 2nd Bone Spring  | 10141    |
| * 3rd Bone Spring  | 10654    |
| * Wolfcamp         | 11835    |

**2. Estimated depth/thickness of freshwater and/or hydrocarbons:**

Water: Fresh water is anticipated above the Rustler at 300' and will be protected by surface casing at 950' and cemented to surface.

Hydrocarbons: Oil and gas are anticipated in the formations annotated above (\*). These zones will be isolated as necessary.

**3. Pressure Control Equipment:**

\*Please see attached BOPE and Choke Manifold Schematic for more detail.

A 13-5/8" BOP system will be installed and tested prior to drilling out of the surface casing shoe. The BOP system will be utilized to drill the intermediate and production hole sections, and will be tested per BLM Onshore Oil & Gas Order No. 2 per each hole section specified in the final column of the table in section four.

Pressure tests will be conducted at the initial installation of the BOPE and again if needed 30 days from the initial test as per BLM Onshore Oil and Gas Order No. 2. BOPE controls will be installed prior to drilling under the surface casing and will be used until the completion of drilling operations. Prior to drilling the intermediate 1 and intermediate 2 holes the BOPE will be tested per 5m working system requirements. Prior to drilling the production interval the BOPE will be tested per 10M system requirements.

ConocoPhillips Company requests a variance to use a flexible line between the BOP and the choke. The testing and manufacturing specifications for this equipment is attached. The line will be kept as straight as possible with minimum turns.

**4. Proposed Casing Program**

\*All tubulars used for this design will be new.

| Hole Size (in) | Casing (in) | Wt/Ft | Grade | Connection | Depth (ft) | Depth (ftTVD) | Depth (ftMD) | BOPE System |
|----------------|-------------|-------|-------|------------|------------|---------------|--------------|-------------|
| 17 1/2         | 13 3/8      | 54.5  | J-55  | BTC        | 0-950      | 950           | 950          | N/A         |
| 12 1/4         | 9 5/8       | 40    | L-80  | BTC        | 0-4825     | 4825          | 4825         | 5M          |
| 8 3/4          | 7 5/8       | 33.7  | P-110 | Wedge 523  | 0-12150    | 12150         | 12150        | 5M          |
| 6 5/8          | 4 1/2       | 15.1  | P-110 | BTC        | 0-19670    | 12974         | 19670        | 10M         |

Minimum casing design factors: Collapse:1.125, Burst 1.0, Tensile Strength 1.6 dry / 1.8 buoyant

| Hole Size (in) | Casing (in) | Burst | Collapse | Tension |
|----------------|-------------|-------|----------|---------|
| 17 1/2         | 13 3/8      | 6.07  | 2.51     | 20.39   |
| 12 1/4         | 9 5/8       | 2.18  | 1.17     | 5.84    |
| 8 3/4          | 7 5/8       | 1.85  | 1.34     | 3.11    |
| 6 5/8          | 4 1/2       | 1.60  | 1.70     | 3.21    |

**Drilling Program**  
**ConocoPhillips Company**  
War Hammer 25 Federal COM W3 1H  
250' FNL 125' FEL (SHL)  
330' FSL 380' FEL (BHL)  
Sec 25-T26S-R32E

**5. Proposed Cementing Program**

Lea County, New Mexico

|                                                                                                                     |      | Volume (sx) | Type                 | Weight (ppg) | Yield (ft <sup>3</sup> /sx) | Water (Gal/sx) | Excess | Cement Top |
|---------------------------------------------------------------------------------------------------------------------|------|-------------|----------------------|--------------|-----------------------------|----------------|--------|------------|
| Surface                                                                                                             | Lead | 530         | Class C              | 13.5         | 1.73                        | 9.14           | 100%   | Surface    |
|                                                                                                                     | Tail | 310         | Class C              | 14.8         | 1.35                        | 6.39           | 100%   | 650ft      |
| Additives (BWOB): 4% Extender, 2% CaCl <sub>2</sub> , 0.125 lb/sx LCM, 0.2% Anti-Foam                               |      |             |                      |              |                             |                |        |            |
| Intermediate 1                                                                                                      | Lead | 1430        | Class C              | 12.9         | 1.97                        | 10.88          | 100%   | Surface    |
|                                                                                                                     | Tail | 380         | Class C              | 14.8         | 1.35                        | 6.19           | 100%   | 500ft      |
| Additives (BWOB): 4% Extender, 2% CaCl <sub>2</sub> , 0.125 lb/sx LCM, 0.2% Anti-Foam                               |      |             |                      |              |                             |                |        |            |
| Intermediate 2                                                                                                      | Lead | 430         | Tuned Light          | 9.5          | 3.45                        | 14.38          | 100%   | 4325ft     |
|                                                                                                                     | Tail | 140         | Class C              | 13.2         | 1.61                        | 8.20           | 100%   | 11650ft    |
| Additives (BWOB): 0.4% Dispersant, 1 lb/sx Salt, 0.1% Retarder, 0.5% Fluid Loss, 3 lb/sx LCM                        |      |             |                      |              |                             |                |        |            |
| Production                                                                                                          | Lead |             |                      |              |                             |                |        |            |
|                                                                                                                     | Tail | 550         | Class <del>A</del> H | 15.0         | 2.61                        | 6.00           | 30%    | 11650ft    |
| Additives (BWOB): 0.4% Retarder, 0.2% Anti-foam, 0.7 Anti-gelling, 0.4% Fluid Loss, 2% Expanding Agent, 5.0% Silica |      |             |                      |              |                             |                |        |            |

**6. Proposed Fluids Program**

| Depth (ft)                 | Type          | Mud Weight (ppg) | Viscosity | Fluid Loss |
|----------------------------|---------------|------------------|-----------|------------|
| 0 to 950 <del>770</del>    | Spud Mud      | 8.4 - 9.3        | 32-36     | NC         |
| 950 <del>770</del> to 4825 | Brine         | 9.3 - 10.5       | 28-30     | ≤5         |
| 4825 to 12150              | Cut Brine     | 8.6 - 9.1        | 30-40     | ≤5         |
| 12150 to 19695             | Oil Based Mud | 12.0 - 14.0      | 30-40     | ≤5         |

Sufficient fluid volume, weight material, and additives will be available onsite at all times. Visual and electronic mud monitoring equipment will be in place to indicate gain or loss.

**7. Formation Evaluation Program**

Samples: Dry samples taken 30' from intermediate casing point to TD. GC Tracers KOP to TD.  
Logging: GR/Neutron from base salt to surface. GR from 200' above KOP to TD. Shuttle log in the lateral.

**8. Anticipated Wellbore Conditions**

|                                       | Value                                                                                                                                                                                                                                                                                                                                                                            | Comments                                           |
|---------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------|
| Bottom Hole Pressure (psi)            | 7265                                                                                                                                                                                                                                                                                                                                                                             | Assumes 0.78psi/ft - 0.22psi/ft Partial Evacuation |
| Bottom Hole Temperature (°F)          | 202                                                                                                                                                                                                                                                                                                                                                                              | Assumes 0.01deg/100ft                              |
| Abnormal Pressure / Potential Hazards | Losses below Delaware will be mitigated with lost circulation material. Potential overpressure below the top of Wolfcamp will be mitigated with mud weight. If H <sub>2</sub> S is encountered the operator will comply with the provisions of Onshore Oil and Gas Order No. 6. All personnel will be familiar with all aspects of safe operation being used to drill this well. |                                                    |

**9. Directional Plan:**

| Kick off Point (ft) | Landing TVD (ft) | Landing MD (ft) | Total Measured Depth (ft) |
|---------------------|------------------|-----------------|---------------------------|
| 12412               | 12974            | 13312           | 19695                     |

\*ConocoPhillips proposes to drill a vertical wellbore to kick off point and then drill horizontally to TD. Please see the attached directional plan for more detail.

**10. Anticipated Start / Duration**

ConocoPhillips Company intends to drill and complete this well approximately 90 days from spud.

March 05 2014



**Size:** 7.625 in.  
**Wall:** 0.430 in.  
**Weight:** 33.70 lbs/ft  
**Grade:** P110  
**Min. Wall Thickness:** 87.5 %

**Connection:** Wedge 523™  
**Casing/Tubing:** CAS


| PIPE BODY DATA             |                 |                            |                |
|----------------------------|-----------------|----------------------------|----------------|
| GEOMETRY                   |                 |                            |                |
| Nominal OD                 | 7.625 in.       | Nominal Weight             | 33.70 lbs/ft   |
|                            |                 | Standard Drift Diameter    | 6.640 in.      |
| Nominal ID                 | 6.765 in.       | Wall Thickness             | 0.430 in.      |
|                            |                 | Special Drift Diameter     | N/A            |
| Plain End Weight           | 33.07 lbs/ft.   |                            |                |
| PERFORMANCE                |                 |                            |                |
| Body Yield Strength        | 1069 x 1000 lbs | Internal Yield             | 10860 psi      |
|                            |                 | SMYS                       | 110000 psi     |
| Collapse                   | 7870 psi        |                            |                |
| WEDGE 523™ CONNECTION DATA |                 |                            |                |
| GEOMETRY                   |                 |                            |                |
| Connection OD              | 7.775 in.       | Connection ID              | 6.675 in.      |
|                            |                 | Make-Up Loss               | 4.060 in.      |
| Critical Section Area      | 7.057 sq. in.   | Threads per in.            | 3.06           |
| PERFORMANCE                |                 |                            |                |
| Tension Efficiency         | 72.6 %          | Joint Yield Strength       | 776 x 1000 lbs |
|                            |                 | Internal Pressure Capacity | 10860 psi      |
| Compression Strength       | 881 x 1000 lbs  | Compression Efficiency     | 82.4 %         |
| External Pressure Capacity | 7870 psi        | Bending                    | 48 °/100 ft    |
| MAKE-UP TORQUES            |                 |                            |                |
| Minimum                    | 9900 ft-lbs.    | Target                     | 11900 ft-lbs   |
|                            |                 | Maximum (±)                | 17300 ft-lbs   |
| OPERATIONAL LIMIT TORQUES  |                 |                            |                |
| Operating Torque           | 42000 ft-lbs    | Yield Torque               | 63000 ft-lbs   |
| BLANKING DIMENSIONS        |                 |                            |                |
| Blanking Dimensions        |                 |                            |                |

\* If you need to use torque values that are higher than the maximum indicated, please contact a local Tenaris technical sales representative.

### **7-5/8" Collapse Load Case Justification**

Per conversation with Chris Walls on February 28<sup>th</sup>, for our intermediate casing program for the subject well, we feel that 7-5/8" 29.7# P-110 BTC would not be at risk of collapse when set as intermediate casing at approximately 12669'. Our reasons are as follows:

1. The 7-5/8" intermediate casing for this well would not be subject to the production collapse load case of being pumped off to zero pressure on the inside by beam pump or ESP production pumping the fluid level down. The 7-5/8" casing would be isolated from the beam pumping production collapse load case by the production casing that would be run subsequent to this string.
2. If loss of circulation occurs during the drilling phase while drilling below the 7-5/8" intermediate casing, we would expect the fluid level would fall no further than 5000' below the surface of ground before reaching hydrostatic balance with the pressure of the loss zone. Our anticipated maximum mud weight for drilling below the 7-5/8" intermediate casing is 14.0 ppg, and our experience has been that we have not had severe losses with this mud weight in our previous wells in this area.
3. The 7-5/8" casing will be filled with mud while running it by filling it at least once every 30 joints (1260').



|           |                           |                              |                                                   |
|-----------|---------------------------|------------------------------|---------------------------------------------------|
| Database: | EDM 5000.1 Single User Db | Local Co-ordinate Reference: | Well W1 3H                                        |
| Company:  | ConocoPhillips            | TVD Reference:               | Well @ 3164.00usft (H&P 499 RKB: 25' + GL: 3139') |
| Project:  | Lea County, NM            | MD Reference:                | Well @ 3164.00usft (H&P 499 RKB: 25' + GL: 3139') |
| Site:     | War Hammer 25 Fed Com     | North Reference:             | Grid                                              |
| Well:     | W1 3H                     | Survey Calculation Method:   | Minimum Curvature                                 |
| Wellbore: | Original Hole             |                              |                                                   |
| Design:   | Design #1                 |                              |                                                   |

|             |                                      |               |                |
|-------------|--------------------------------------|---------------|----------------|
| Project     | Lea County, NM                       |               |                |
| Map System: | US State Plane 1927 (Exact solution) | System Datum: | Mean Sea Level |
| Geo Datum:  | NAD 1927 (NADCON CONUS)              |               |                |
| Map Zone:   | New Mexico East 3001                 |               |                |

|                       |                       |                   |                   |
|-----------------------|-----------------------|-------------------|-------------------|
| Site                  | War Hammer 25 Fed Com |                   |                   |
| Site Position:        | From:                 | Map               |                   |
| Position Uncertainty: | 0.00 usft             | Slot Radius:      | 13.20 in          |
|                       |                       | Northings:        | 371,782.24 usft   |
|                       |                       | Easting:          | 721,157.76 usft   |
|                       |                       | Latitude:         | 32° 1' 12.490 N   |
|                       |                       | Longitude:        | 103° 37' 11.140 W |
|                       |                       | Grid Convergence: | 0.38 °            |

|                      |           |                     |                   |
|----------------------|-----------|---------------------|-------------------|
| Well                 | W1 3H     |                     |                   |
| Well Position        | +N/-S     | -65.68 usft         | Northings:        |
|                      | +E/-W     | 0.43 usft           | Easting:          |
| Position Uncertainty | 0.00 usft | Wellhead Elevation: | 0.00 usft         |
|                      |           | Latitude:           | 32° 1' 11.840 N   |
|                      |           | Longitude:          | 103° 37' 11.140 W |
|                      |           | Ground Level:       | 3,139.00 usft     |

|           |               |             |                |
|-----------|---------------|-------------|----------------|
| Wellbore  | Original Hole |             |                |
| Magnetics | Model Name    | Sample Date | Declination    |
|           |               |             | (°)            |
|           | User Defined  | 2/20/2014   | 7.37           |
|           |               |             | Dip Angle      |
|           |               |             | (°)            |
|           |               |             | 59.90          |
|           |               |             | Field Strength |
|           |               |             | (nT)           |
|           |               |             | 48,206         |

|                   |                  |        |               |
|-------------------|------------------|--------|---------------|
| Design            | Design #1        |        |               |
| Audit Notes:      |                  |        |               |
| Version:          | Phase:           | PLAN   | Tie On Depth: |
|                   |                  |        | 0.00          |
| Vertical Section: | Depth From (TVD) | +N/-S  | +E/-W         |
|                   | (usft)           | (usft) | (usft)        |
|                   | 0.00             | 0.00   | 0.00          |
|                   |                  |        | Direction     |
|                   |                  |        | (°)           |
|                   |                  |        | 181.72        |

| Plan Sections         |                 |             |                       |              |              |                       |                      |                     |         |              |
|-----------------------|-----------------|-------------|-----------------------|--------------|--------------|-----------------------|----------------------|---------------------|---------|--------------|
| Measured Depth (usft) | Inclination (°) | Azimuth (°) | Vertical Depth (usft) | +N/-S (usft) | +E/-W (usft) | Dogleg Rate (°/100ft) | Build Rate (°/100ft) | Turn Rate (°/100ft) | TFO (°) | Target       |
| 0.00                  | 0.00            | 0.00        | 0.00                  | 0.00         | 0.00         | 0.00                  | 0.00                 | 0.00                | 0.00    |              |
| 2,400.00              | 0.00            | 0.00        | 2,400.00              | 0.00         | 0.00         | 0.00                  | 0.00                 | 0.00                | 0.00    |              |
| 2,733.23              | 5.00            | 239.97      | 2,732.81              | -7.27        | -12.58       | 1.50                  | 1.50                 | 0.00                | 239.97  |              |
| 5,766.20              | 5.00            | 239.97      | 5,754.24              | -139.52      | -241.36      | 0.00                  | 0.00                 | 0.00                | 0.00    |              |
| 6,099.42              | 0.00            | 179.60      | 6,087.04              | -146.79      | -253.94      | 1.50                  | -1.50                | -18.12              | -180.00 | VT (W1 3H)   |
| 11,794.43             | 0.00            | 179.60      | 11,782.05             | -146.77      | -253.93      | 0.00                  | 0.00                 | 0.00                | 0.00    |              |
| 12,694.42             | 90.00           | 179.60      | 12,355.00             | -719.71      | -249.93      | 10.00                 | 10.00                | 0.00                | 0.00    | EOC (W1 3H)  |
| 18,864.90             | 90.00           | 179.60      | 12,355.00             | -6,890.04    | -206.83      | 0.00                  | 0.00                 | 0.00                | 0.00    | PBHL (W1 3H) |

|           |                           |                              |                                                   |
|-----------|---------------------------|------------------------------|---------------------------------------------------|
| Database: | EDM 5000.1 Single User Db | Local Co-ordinate Reference: | Well W1 3H                                        |
| Company:  | ConocoPhillips            | TVD Reference:               | Well @ 3164.00usft (H&P 499 RKB: 25' + GL: 3139') |
| Project:  | Lea County, NM            | MD Reference:                | Well @ 3164.00usft (H&P 499 RKB: 25' + GL: 3139') |
| Site:     | War Hammer 25 Fed Com     | North Reference:             | Grid                                              |
| Well:     | W1 3H                     | Survey Calculation Method:   | Minimum Curvature                                 |
| Wellbore: | Original Hole             |                              |                                                   |
| Design:   | Design #1                 |                              |                                                   |

### Planned Survey

| Measured Depth (usft)                                     | Inclination (°) | Azimuth (°) | Vertical Depth (usft) | +N/-S (usft) | +E/-W (usft) | Vertical Section (usft) | Dogleg Rate (°/100ft) | Build Rate (°/100ft) | Turn Rate (°/100ft) |
|-----------------------------------------------------------|-----------------|-------------|-----------------------|--------------|--------------|-------------------------|-----------------------|----------------------|---------------------|
| 0.00                                                      | 0.00            | 0.00        | 0.00                  | 0.00         | 0.00         | 0.00                    | 0.00                  | 0.00                 | 0.00                |
| <b>SHL (W1 3H)</b>                                        |                 |             |                       |              |              |                         |                       |                      |                     |
| 100.00                                                    | 0.00            | 0.00        | 100.00                | 0.00         | 0.00         | 0.00                    | 0.00                  | 0.00                 | 0.00                |
| 200.00                                                    | 0.00            | 0.00        | 200.00                | 0.00         | 0.00         | 0.00                    | 0.00                  | 0.00                 | 0.00                |
| 300.00                                                    | 0.00            | 0.00        | 300.00                | 0.00         | 0.00         | 0.00                    | 0.00                  | 0.00                 | 0.00                |
| 400.00                                                    | 0.00            | 0.00        | 400.00                | 0.00         | 0.00         | 0.00                    | 0.00                  | 0.00                 | 0.00                |
| 500.00                                                    | 0.00            | 0.00        | 500.00                | 0.00         | 0.00         | 0.00                    | 0.00                  | 0.00                 | 0.00                |
| 600.00                                                    | 0.00            | 0.00        | 600.00                | 0.00         | 0.00         | 0.00                    | 0.00                  | 0.00                 | 0.00                |
| 700.00                                                    | 0.00            | 0.00        | 700.00                | 0.00         | 0.00         | 0.00                    | 0.00                  | 0.00                 | 0.00                |
| 800.00                                                    | 0.00            | 0.00        | 800.00                | 0.00         | 0.00         | 0.00                    | 0.00                  | 0.00                 | 0.00                |
| 900.00                                                    | 0.00            | 0.00        | 900.00                | 0.00         | 0.00         | 0.00                    | 0.00                  | 0.00                 | 0.00                |
| 1,000.00                                                  | 0.00            | 0.00        | 1,000.00              | 0.00         | 0.00         | 0.00                    | 0.00                  | 0.00                 | 0.00                |
| 1,100.00                                                  | 0.00            | 0.00        | 1,100.00              | 0.00         | 0.00         | 0.00                    | 0.00                  | 0.00                 | 0.00                |
| 1,200.00                                                  | 0.00            | 0.00        | 1,200.00              | 0.00         | 0.00         | 0.00                    | 0.00                  | 0.00                 | 0.00                |
| 1,300.00                                                  | 0.00            | 0.00        | 1,300.00              | 0.00         | 0.00         | 0.00                    | 0.00                  | 0.00                 | 0.00                |
| 1,400.00                                                  | 0.00            | 0.00        | 1,400.00              | 0.00         | 0.00         | 0.00                    | 0.00                  | 0.00                 | 0.00                |
| 1,500.00                                                  | 0.00            | 0.00        | 1,500.00              | 0.00         | 0.00         | 0.00                    | 0.00                  | 0.00                 | 0.00                |
| 1,600.00                                                  | 0.00            | 0.00        | 1,600.00              | 0.00         | 0.00         | 0.00                    | 0.00                  | 0.00                 | 0.00                |
| 1,700.00                                                  | 0.00            | 0.00        | 1,700.00              | 0.00         | 0.00         | 0.00                    | 0.00                  | 0.00                 | 0.00                |
| 1,800.00                                                  | 0.00            | 0.00        | 1,800.00              | 0.00         | 0.00         | 0.00                    | 0.00                  | 0.00                 | 0.00                |
| 1,900.00                                                  | 0.00            | 0.00        | 1,900.00              | 0.00         | 0.00         | 0.00                    | 0.00                  | 0.00                 | 0.00                |
| 2,000.00                                                  | 0.00            | 0.00        | 2,000.00              | 0.00         | 0.00         | 0.00                    | 0.00                  | 0.00                 | 0.00                |
| 2,100.00                                                  | 0.00            | 0.00        | 2,100.00              | 0.00         | 0.00         | 0.00                    | 0.00                  | 0.00                 | 0.00                |
| 2,200.00                                                  | 0.00            | 0.00        | 2,200.00              | 0.00         | 0.00         | 0.00                    | 0.00                  | 0.00                 | 0.00                |
| 2,300.00                                                  | 0.00            | 0.00        | 2,300.00              | 0.00         | 0.00         | 0.00                    | 0.00                  | 0.00                 | 0.00                |
| 2,400.00                                                  | 0.00            | 0.00        | 2,400.00              | 0.00         | 0.00         | 0.00                    | 0.00                  | 0.00                 | 0.00                |
| <b>Start Build 1.50 - Build 1.5°/100' (W1 3H)</b>         |                 |             |                       |              |              |                         |                       |                      |                     |
| 2,500.00                                                  | 1.50            | 239.97      | 2,499.99              | -0.66        | -1.13        | 0.69                    | 1.50                  | 1.50                 | 0.00                |
| 2,600.00                                                  | 3.00            | 239.97      | 2,599.91              | -2.62        | -4.53        | 2.75                    | 1.50                  | 1.50                 | 0.00                |
| 2,700.00                                                  | 4.50            | 239.97      | 2,699.69              | -5.89        | -10.19       | 6.20                    | 1.50                  | 1.50                 | 0.00                |
| 2,733.23                                                  | 5.00            | 239.97      | 2,732.81              | -7.27        | -12.58       | 7.64                    | 1.50                  | 1.50                 | 0.00                |
| <b>Start 3032.96 hold at 2733.23 MD - Hold 5° (W1 3H)</b> |                 |             |                       |              |              |                         |                       |                      |                     |
| 2,800.00                                                  | 5.00            | 239.97      | 2,799.32              | -10.18       | -17.61       | 10.71                   | 0.00                  | 0.00                 | 0.00                |
| 2,900.00                                                  | 5.00            | 239.97      | 2,898.94              | -14.54       | -25.16       | 15.29                   | 0.00                  | 0.00                 | 0.00                |
| 3,000.00                                                  | 5.00            | 239.97      | 2,998.56              | -18.90       | -32.70       | 19.87                   | 0.00                  | 0.00                 | 0.00                |
| 3,100.00                                                  | 5.00            | 239.97      | 3,098.18              | -23.26       | -40.24       | 24.46                   | 0.00                  | 0.00                 | 0.00                |
| 3,200.00                                                  | 5.00            | 239.97      | 3,197.80              | -27.62       | -47.79       | 29.04                   | 0.00                  | 0.00                 | 0.00                |
| 3,300.00                                                  | 5.00            | 239.97      | 3,297.42              | -31.98       | -55.33       | 33.63                   | 0.00                  | 0.00                 | 0.00                |
| 3,400.00                                                  | 5.00            | 239.97      | 3,397.04              | -36.34       | -62.87       | 38.21                   | 0.00                  | 0.00                 | 0.00                |
| 3,500.00                                                  | 5.00            | 239.97      | 3,496.66              | -40.70       | -70.42       | 42.80                   | 0.00                  | 0.00                 | 0.00                |
| 3,600.00                                                  | 5.00            | 239.97      | 3,596.28              | -45.06       | -77.96       | 47.38                   | 0.00                  | 0.00                 | 0.00                |
| 3,700.00                                                  | 5.00            | 239.97      | 3,695.90              | -49.42       | -85.50       | 51.97                   | 0.00                  | 0.00                 | 0.00                |
| 3,800.00                                                  | 5.00            | 239.97      | 3,795.52              | -53.79       | -93.05       | 56.55                   | 0.00                  | 0.00                 | 0.00                |
| 3,900.00                                                  | 5.00            | 239.97      | 3,895.14              | -58.15       | -100.59      | 61.14                   | 0.00                  | 0.00                 | 0.00                |
| 4,000.00                                                  | 5.00            | 239.97      | 3,994.76              | -62.51       | -108.13      | 65.72                   | 0.00                  | 0.00                 | 0.00                |
| 4,100.00                                                  | 5.00            | 239.97      | 4,094.38              | -66.87       | -115.68      | 70.31                   | 0.00                  | 0.00                 | 0.00                |
| 4,200.00                                                  | 5.00            | 239.97      | 4,194.00              | -71.23       | -123.22      | 74.89                   | 0.00                  | 0.00                 | 0.00                |
| 4,300.00                                                  | 5.00            | 239.97      | 4,293.62              | -75.59       | -130.76      | 79.48                   | 0.00                  | 0.00                 | 0.00                |
| 4,400.00                                                  | 5.00            | 239.97      | 4,393.24              | -79.95       | -138.31      | 84.06                   | 0.00                  | 0.00                 | 0.00                |
| 4,500.00                                                  | 5.00            | 239.97      | 4,492.86              | -84.31       | -145.85      | 88.65                   | 0.00                  | 0.00                 | 0.00                |
| 4,600.00                                                  | 5.00            | 239.97      | 4,592.48              | -88.67       | -153.39      | 93.23                   | 0.00                  | 0.00                 | 0.00                |
| 4,700.00                                                  | 5.00            | 239.97      | 4,692.10              | -93.03       | -160.94      | 97.82                   | 0.00                  | 0.00                 | 0.00                |

|           |                           |                              |                                                   |
|-----------|---------------------------|------------------------------|---------------------------------------------------|
| Database: | EDM 5000.1 Single User Db | Local Co-ordinate Reference: | Well W1 3H                                        |
| Company:  | ConocoPhillips            | TVD Reference:               | Well @ 3164.00usft (H&P 499 RKB: 25' + GL: 3139') |
| Project:  | Lea County, NM            | MD Reference:                | Well @ 3164.00usft (H&P 499 RKB: 25' + GL: 3139') |
| Site:     | War Hammer 25 Fed Com     | North Reference:             | Grid                                              |
| Well:     | W1 3H                     | Survey Calculation Method:   | Minimum Curvature                                 |
| Wellbore: | Original Hole             |                              |                                                   |
| Design:   | Design #1                 |                              |                                                   |

| Planned Survey                                      |                 |             |                       |              |              |                         |                       |                      |                     |  |
|-----------------------------------------------------|-----------------|-------------|-----------------------|--------------|--------------|-------------------------|-----------------------|----------------------|---------------------|--|
| Measured Depth (usft)                               | Inclination (°) | Azimuth (°) | Vertical Depth (usft) | +N/-S (usft) | +E/-W (usft) | Vertical Section (usft) | Dogleg Rate (°/100ft) | Build Rate (°/100ft) | Turn Rate (°/100ft) |  |
| 4,800.00                                            | 5.00            | 239.97      | 4,791.72              | -97.39       | -168.48      | 102.40                  | 0.00                  | 0.00                 | 0.00                |  |
| 4,900.00                                            | 5.00            | 239.97      | 4,891.34              | -101.75      | -176.02      | 106.99                  | 0.00                  | 0.00                 | 0.00                |  |
| 5,000.00                                            | 5.00            | 239.97      | 4,990.96              | -106.11      | -183.57      | 111.57                  | 0.00                  | 0.00                 | 0.00                |  |
| 5,100.00                                            | 5.00            | 239.97      | 5,090.58              | -110.47      | -191.11      | 116.16                  | 0.00                  | 0.00                 | 0.00                |  |
| 5,200.00                                            | 5.00            | 239.97      | 5,190.20              | -114.83      | -198.65      | 120.74                  | 0.00                  | 0.00                 | 0.00                |  |
| 5,300.00                                            | 5.00            | 239.97      | 5,289.82              | -119.19      | -206.20      | 125.33                  | 0.00                  | 0.00                 | 0.00                |  |
| 5,400.00                                            | 5.00            | 239.97      | 5,389.44              | -123.55      | -213.74      | 129.91                  | 0.00                  | 0.00                 | 0.00                |  |
| 5,500.00                                            | 5.00            | 239.97      | 5,489.06              | -127.91      | -221.28      | 134.50                  | 0.00                  | 0.00                 | 0.00                |  |
| 5,600.00                                            | 5.00            | 239.97      | 5,588.68              | -132.27      | -228.83      | 139.08                  | 0.00                  | 0.00                 | 0.00                |  |
| 5,700.00                                            | 5.00            | 239.97      | 5,688.29              | -136.63      | -236.37      | 143.67                  | 0.00                  | 0.00                 | 0.00                |  |
| 5,766.20                                            | 5.00            | 239.97      | 5,754.24              | -139.52      | -241.36      | 146.70                  | 0.00                  | 0.00                 | 0.00                |  |
| Start DLS 1.50 TFO -180.00 - Drop 1.5°/100' (W1 3H) |                 |             |                       |              |              |                         |                       |                      |                     |  |
| 5,800.00                                            | 4.49            | 239.97      | 5,787.93              | -140.92      | -243.78      | 148.17                  | 1.50                  | -1.50                | 0.00                |  |
| 5,900.00                                            | 2.99            | 239.97      | 5,887.71              | -144.18      | -249.43      | 151.61                  | 1.50                  | -1.50                | 0.00                |  |
| 6,000.00                                            | 1.49            | 239.96      | 5,987.63              | -146.14      | -252.82      | 153.66                  | 1.50                  | -1.50                | 0.00                |  |
| 6,099.42                                            | 0.00            | 179.60      | 6,087.04              | -146.79      | -253.94      | 154.35                  | 1.50                  | -1.50                | -60.72              |  |
| Start 5695.01 hold at 6099.42 MD - VT (W1 3H)       |                 |             |                       |              |              |                         |                       |                      |                     |  |
| 6,200.00                                            | 0.00            | 179.60      | 6,187.62              | -146.79      | -253.94      | 154.35                  | 0.00                  | 0.00                 | 0.00                |  |
| 6,300.00                                            | 0.00            | 179.60      | 6,287.62              | -146.79      | -253.94      | 154.35                  | 0.00                  | 0.00                 | 0.00                |  |
| 6,400.00                                            | 0.00            | 179.60      | 6,387.62              | -146.79      | -253.94      | 154.35                  | 0.00                  | 0.00                 | 0.00                |  |
| 6,500.00                                            | 0.00            | 179.60      | 6,487.62              | -146.79      | -253.94      | 154.35                  | 0.00                  | 0.00                 | 0.00                |  |
| 6,600.00                                            | 0.00            | 179.60      | 6,587.62              | -146.79      | -253.94      | 154.35                  | 0.00                  | 0.00                 | 0.00                |  |
| 6,700.00                                            | 0.00            | 179.60      | 6,687.62              | -146.79      | -253.94      | 154.35                  | 0.00                  | 0.00                 | 0.00                |  |
| 6,800.00                                            | 0.00            | 179.60      | 6,787.62              | -146.79      | -253.94      | 154.35                  | 0.00                  | 0.00                 | 0.00                |  |
| 6,900.00                                            | 0.00            | 179.60      | 6,887.62              | -146.79      | -253.94      | 154.35                  | 0.00                  | 0.00                 | 0.00                |  |
| 7,000.00                                            | 0.00            | 179.60      | 6,987.62              | -146.79      | -253.94      | 154.35                  | 0.00                  | 0.00                 | 0.00                |  |
| 7,100.00                                            | 0.00            | 179.60      | 7,087.62              | -146.79      | -253.94      | 154.35                  | 0.00                  | 0.00                 | 0.00                |  |
| 7,200.00                                            | 0.00            | 179.60      | 7,187.62              | -146.79      | -253.94      | 154.35                  | 0.00                  | 0.00                 | 0.00                |  |
| 7,300.00                                            | 0.00            | 179.60      | 7,287.62              | -146.80      | -253.94      | 154.35                  | 0.00                  | 0.00                 | 0.00                |  |
| 7,380.38                                            | 0.00            | 179.60      | 7,368.00              | -146.80      | -253.94      | 154.35                  | 0.00                  | 0.00                 | 0.00                |  |
| Brushy Canyon                                       |                 |             |                       |              |              |                         |                       |                      |                     |  |
| 7,400.00                                            | 0.00            | 179.60      | 7,387.62              | -146.80      | -253.94      | 154.35                  | 0.00                  | 0.00                 | 0.00                |  |
| 7,500.00                                            | 0.00            | 179.60      | 7,487.62              | -146.80      | -253.94      | 154.35                  | 0.00                  | 0.00                 | 0.00                |  |
| 7,600.00                                            | 0.00            | 179.60      | 7,587.62              | -146.80      | -253.94      | 154.35                  | 0.00                  | 0.00                 | 0.00                |  |
| 7,700.00                                            | 0.00            | 179.60      | 7,687.62              | -146.80      | -253.94      | 154.35                  | 0.00                  | 0.00                 | 0.00                |  |
| 7,800.00                                            | 0.00            | 179.60      | 7,787.62              | -146.80      | -253.94      | 154.35                  | 0.00                  | 0.00                 | 0.00                |  |
| 7,900.00                                            | 0.00            | 179.60      | 7,887.62              | -146.80      | -253.94      | 154.35                  | 0.00                  | 0.00                 | 0.00                |  |
| 8,000.00                                            | 0.00            | 179.60      | 7,987.62              | -146.80      | -253.94      | 154.35                  | 0.00                  | 0.00                 | 0.00                |  |
| 8,100.00                                            | 0.00            | 179.60      | 8,087.62              | -146.80      | -253.94      | 154.35                  | 0.00                  | 0.00                 | 0.00                |  |
| 8,200.00                                            | 0.00            | 179.60      | 8,187.62              | -146.80      | -253.94      | 154.35                  | 0.00                  | 0.00                 | 0.00                |  |
| 8,300.00                                            | 0.00            | 179.60      | 8,287.62              | -146.80      | -253.94      | 154.36                  | 0.00                  | 0.00                 | 0.00                |  |
| 8,400.00                                            | 0.00            | 179.60      | 8,387.62              | -146.80      | -253.94      | 154.36                  | 0.00                  | 0.00                 | 0.00                |  |
| 8,500.00                                            | 0.00            | 179.60      | 8,487.62              | -146.80      | -253.94      | 154.36                  | 0.00                  | 0.00                 | 0.00                |  |
| 8,600.00                                            | 0.00            | 179.60      | 8,587.62              | -146.80      | -253.94      | 154.36                  | 0.00                  | 0.00                 | 0.00                |  |
| 8,700.00                                            | 0.00            | 179.60      | 8,687.62              | -146.80      | -253.94      | 154.36                  | 0.00                  | 0.00                 | 0.00                |  |
| 8,800.00                                            | 0.00            | 179.60      | 8,787.62              | -146.80      | -253.94      | 154.36                  | 0.00                  | 0.00                 | 0.00                |  |
| 8,877.38                                            | 0.00            | 179.60      | 8,865.00              | -146.80      | -253.94      | 154.36                  | 0.00                  | 0.00                 | 0.00                |  |
| Bone Spring 1st Carbonate Top                       |                 |             |                       |              |              |                         |                       |                      |                     |  |
| 8,900.00                                            | 0.00            | 179.60      | 8,887.62              | -146.80      | -253.94      | 154.36                  | 0.00                  | 0.00                 | 0.00                |  |
| 9,000.00                                            | 0.00            | 179.60      | 8,987.62              | -146.80      | -253.94      | 154.36                  | 0.00                  | 0.00                 | 0.00                |  |
| 9,083.38                                            | 0.00            | 179.60      | 9,071.00              | -146.80      | -253.94      | 154.36                  | 0.00                  | 0.00                 | 0.00                |  |

|           |                           |                              |                                                   |
|-----------|---------------------------|------------------------------|---------------------------------------------------|
| Database: | EDM 5000.1 Single User Db | Local Co-ordinate Reference: | Well W1 3H                                        |
| Company:  | ConocoPhillips            | TVD Reference:               | Well @ 3164.00usft (H&P 499 RKB: 25' + GL: 3139') |
| Project:  | Lea County, NM            | MD Reference:                | Well @ 3164.00usft (H&P 499 RKB: 25' + GL: 3139') |
| Site:     | War Hammer 25 Fed Com     | North Reference:             | Grid                                              |
| Well:     | W1 3H                     | Survey Calculation Method:   | Minimum Curvature                                 |
| Wellbore: | Original Hole             |                              |                                                   |
| Design:   | Design #1                 |                              |                                                   |

| Planned Survey                         |                 |             |                       |              |              |                         |                       |                      |                     |
|----------------------------------------|-----------------|-------------|-----------------------|--------------|--------------|-------------------------|-----------------------|----------------------|---------------------|
| Measured Depth (usft)                  | Inclination (°) | Azimuth (°) | Vertical Depth (usft) | +N/-S (usft) | +E/-W (usft) | Vertical Section (usft) | Dogleg Rate (°/100ft) | Build Rate (°/100ft) | Turn Rate (°/100ft) |
| <b>Avalon A</b>                        |                 |             |                       |              |              |                         |                       |                      |                     |
| 9,100.00                               | 0.00            | 179.60      | 9,087.62              | -146.80      | -253.94      | 154.36                  | 0.00                  | 0.00                 | 0.00                |
| 9,200.00                               | 0.00            | 179.60      | 9,187.62              | -146.80      | -253.94      | 154.36                  | 0.00                  | 0.00                 | 0.00                |
| 9,285.38                               | 0.00            | 179.60      | 9,273.00              | -146.80      | -253.94      | 154.36                  | 0.00                  | 0.00                 | 0.00                |
| <b>Avalon B</b>                        |                 |             |                       |              |              |                         |                       |                      |                     |
| 9,300.00                               | 0.00            | 179.60      | 9,287.62              | -146.80      | -253.94      | 154.36                  | 0.00                  | 0.00                 | 0.00                |
| 9,400.00                               | 0.00            | 179.60      | 9,387.62              | -146.80      | -253.94      | 154.36                  | 0.00                  | 0.00                 | 0.00                |
| 9,434.38                               | 0.00            | 179.60      | 9,422.00              | -146.80      | -253.94      | 154.36                  | 0.00                  | 0.00                 | 0.00                |
| <b>Avalon C</b>                        |                 |             |                       |              |              |                         |                       |                      |                     |
| 9,500.00                               | 0.00            | 179.60      | 9,487.62              | -146.80      | -253.94      | 154.36                  | 0.00                  | 0.00                 | 0.00                |
| 9,600.00                               | 0.00            | 179.60      | 9,587.62              | -146.80      | -253.94      | 154.36                  | 0.00                  | 0.00                 | 0.00                |
| 9,700.00                               | 0.00            | 179.60      | 9,687.62              | -146.81      | -253.94      | 154.36                  | 0.00                  | 0.00                 | 0.00                |
| 9,728.38                               | 0.00            | 179.60      | 9,716.00              | -146.81      | -253.94      | 154.36                  | 0.00                  | 0.00                 | 0.00                |
| <b>Avalon D</b>                        |                 |             |                       |              |              |                         |                       |                      |                     |
| 9,770.38                               | 0.00            | 179.60      | 9,758.00              | -146.81      | -253.94      | 154.36                  | 0.00                  | 0.00                 | 0.00                |
| <b>1st Bone Spring Sand</b>            |                 |             |                       |              |              |                         |                       |                      |                     |
| 9,800.00                               | 0.00            | 179.60      | 9,787.62              | -146.81      | -253.94      | 154.36                  | 0.00                  | 0.00                 | 0.00                |
| 9,900.00                               | 0.00            | 179.60      | 9,887.62              | -146.81      | -253.94      | 154.36                  | 0.00                  | 0.00                 | 0.00                |
| 9,982.38                               | 0.00            | 179.60      | 9,970.00              | -146.81      | -253.94      | 154.36                  | 0.00                  | 0.00                 | 0.00                |
| <b>FBS shale</b>                       |                 |             |                       |              |              |                         |                       |                      |                     |
| 10,000.00                              | 0.00            | 179.60      | 9,987.62              | -146.81      | -253.94      | 154.36                  | 0.00                  | 0.00                 | 0.00                |
| 10,100.00                              | 0.00            | 179.60      | 10,087.62             | -146.81      | -253.94      | 154.36                  | 0.00                  | 0.00                 | 0.00                |
| 10,153.38                              | 0.00            | 179.60      | 10,141.00             | -146.81      | -253.94      | 154.36                  | 0.00                  | 0.00                 | 0.00                |
| <b>2nd Bone Spring Carbonate</b>       |                 |             |                       |              |              |                         |                       |                      |                     |
| 10,200.00                              | 0.00            | 179.60      | 10,187.62             | -146.81      | -253.94      | 154.36                  | 0.00                  | 0.00                 | 0.00                |
| 10,300.00                              | 0.00            | 179.60      | 10,287.62             | -146.81      | -253.94      | 154.36                  | 0.00                  | 0.00                 | 0.00                |
| 10,310.38                              | 0.00            | 179.60      | 10,298.00             | -146.81      | -253.94      | 154.36                  | 0.00                  | 0.00                 | 0.00                |
| <b>2nd Bone Spring Sand</b>            |                 |             |                       |              |              |                         |                       |                      |                     |
| 10,400.00                              | 0.00            | 179.60      | 10,387.62             | -146.81      | -253.94      | 154.36                  | 0.00                  | 0.00                 | 0.00                |
| 10,500.00                              | 0.00            | 179.60      | 10,487.62             | -146.81      | -253.94      | 154.36                  | 0.00                  | 0.00                 | 0.00                |
| 10,600.00                              | 0.00            | 179.60      | 10,587.62             | -146.81      | -253.94      | 154.36                  | 0.00                  | 0.00                 | 0.00                |
| 10,666.38                              | 0.00            | 179.60      | 10,654.00             | -146.81      | -253.94      | 154.37                  | 0.00                  | 0.00                 | 0.00                |
| <b>3rd Bone Spring Carbonate</b>       |                 |             |                       |              |              |                         |                       |                      |                     |
| 10,700.00                              | 0.00            | 179.60      | 10,687.62             | -146.81      | -253.94      | 154.37                  | 0.00                  | 0.00                 | 0.00                |
| 10,800.00                              | 0.00            | 179.60      | 10,787.62             | -146.81      | -253.94      | 154.37                  | 0.00                  | 0.00                 | 0.00                |
| 10,900.00                              | 0.00            | 179.60      | 10,887.62             | -146.81      | -253.94      | 154.37                  | 0.00                  | 0.00                 | 0.00                |
| 11,000.00                              | 0.00            | 179.60      | 10,987.62             | -146.81      | -253.94      | 154.37                  | 0.00                  | 0.00                 | 0.00                |
| 11,100.00                              | 0.00            | 179.60      | 11,087.62             | -146.81      | -253.94      | 154.37                  | 0.00                  | 0.00                 | 0.00                |
| 11,200.00                              | 0.00            | 179.60      | 11,187.62             | -146.81      | -253.94      | 154.37                  | 0.00                  | 0.00                 | 0.00                |
| 11,300.00                              | 0.00            | 179.60      | 11,287.62             | -146.81      | -253.94      | 154.37                  | 0.00                  | 0.00                 | 0.00                |
| 11,400.00                              | 0.00            | 179.60      | 11,387.62             | -146.81      | -253.94      | 154.37                  | 0.00                  | 0.00                 | 0.00                |
| 11,500.00                              | 0.00            | 179.60      | 11,487.62             | -146.81      | -253.94      | 154.37                  | 0.00                  | 0.00                 | 0.00                |
| 11,501.38                              | 0.00            | 179.60      | 11,489.00             | -146.81      | -253.94      | 154.37                  | 0.00                  | 0.00                 | 0.00                |
| <b>3rd Bone Spring Sand</b>            |                 |             |                       |              |              |                         |                       |                      |                     |
| 11,600.00                              | 0.00            | 179.60      | 11,587.62             | -146.81      | -253.94      | 154.37                  | 0.00                  | 0.00                 | 0.00                |
| 11,700.00                              | 0.00            | 179.60      | 11,687.62             | -146.81      | -253.94      | 154.37                  | 0.00                  | 0.00                 | 0.00                |
| 11,794.42                              | 0.00            | 179.60      | 11,782.04             | -146.81      | -253.94      | 154.37                  | 0.00                  | 0.00                 | 0.00                |
| <b>Start Build 10.00 - KOP (W1 3H)</b> |                 |             |                       |              |              |                         |                       |                      |                     |
| 11,800.00                              | 0.56            | 179.60      | 11,787.62             | -146.79      | -253.93      | 154.35                  | 10.00                 | 10.00                | 0.00                |
| 11,847.46                              | 5.30            | 179.60      | 11,835.00             | -149.22      | -253.91      | 156.77                  | 10.00                 | 10.00                | 0.00                |
| <b>Wolfcamp</b>                        |                 |             |                       |              |              |                         |                       |                      |                     |

|           |                           |                              |                                                   |
|-----------|---------------------------|------------------------------|---------------------------------------------------|
| Database: | EDM 5000.1 Single User Db | Local Co-ordinate Reference: | Well W1 3H                                        |
| Company:  | ConocoPhillips            | TVD Reference:               | Well @ 3164.00usft (H&P 499 RKB: 25' + GL: 3139') |
| Project:  | Lea County, NM            | MD Reference:                | Well @ 3164.00usft (H&P 499 RKB: 25' + GL: 3139') |
| Site:     | War Hammer 25 Fed Com     | North Reference:             | Grid                                              |
| Well:     | W1 3H                     | Survey Calculation Method:   | Minimum Curvature                                 |
| Wellbore: | Original Hole             |                              |                                                   |
| Design:   | Design #1.                |                              |                                                   |

| Planned Survey                                         |                 |             |                       |              |              |                         |                       |                      |                     |
|--------------------------------------------------------|-----------------|-------------|-----------------------|--------------|--------------|-------------------------|-----------------------|----------------------|---------------------|
| Measured Depth (usft)                                  | Inclination (°) | Azimuth (°) | Vertical Depth (usft) | +N/-S (usft) | +E/-W (usft) | Vertical Section (usft) | Dogleg Rate (°/100ft) | Build Rate (°/100ft) | Turn Rate (°/100ft) |
| 11,850.00                                              | 5.56            | 179.60      | 11,837.53             | -149.46      | -253.91      | 157.01                  | 10.00                 | 10.00                | 0.00                |
| 11,900.00                                              | 10.56           | 179.60      | 11,887.02             | -156.47      | -253.86      | 164.02                  | 10.00                 | 10.00                | 0.00                |
| 11,950.00                                              | 15.56           | 179.60      | 11,935.72             | -167.76      | -253.79      | 175.30                  | 10.00                 | 10.00                | 0.00                |
| 12,000.00                                              | 20.56           | 179.60      | 11,983.24             | -183.25      | -253.68      | 190.78                  | 10.00                 | 10.00                | 0.00                |
| 12,050.00                                              | 25.56           | 179.60      | 12,029.23             | -202.83      | -253.54      | 210.35                  | 10.00                 | 10.00                | 0.00                |
| 12,067.61                                              | 27.32           | 179.60      | 12,045.00             | -210.67      | -253.49      | 218.18                  | 10.00                 | 10.00                | 0.00                |
| <b>Wolfcamp 1</b>                                      |                 |             |                       |              |              |                         |                       |                      |                     |
| 12,100.00                                              | 30.56           | 179.60      | 12,073.34             | -226.34      | -253.38      | 233.84                  | 10.00                 | 10.00                | 0.00                |
| 12,150.00                                              | 35.56           | 179.60      | 12,115.23             | -253.60      | -253.19      | 261.09                  | 10.00                 | 10.00                | 0.00                |
| 12,200.00                                              | 40.56           | 179.60      | 12,154.59             | -284.42      | -252.97      | 291.88                  | 10.00                 | 10.00                | 0.00                |
| 12,250.00                                              | 45.56           | 179.60      | 12,191.11             | -318.54      | -252.73      | 325.98                  | 10.00                 | 10.00                | 0.00                |
| 12,300.00                                              | 50.56           | 179.60      | 12,224.52             | -355.72      | -252.47      | 363.14                  | 10.00                 | 10.00                | 0.00                |
| 12,350.00                                              | 55.56           | 179.60      | 12,254.56             | -395.67      | -252.19      | 403.06                  | 10.00                 | 10.00                | 0.00                |
| 12,400.00                                              | 60.56           | 179.60      | 12,281.00             | -438.08      | -251.90      | 445.45                  | 10.00                 | 10.00                | 0.00                |
| 12,450.00                                              | 65.56           | 179.60      | 12,303.65             | -482.64      | -251.59      | 489.97                  | 10.00                 | 10.00                | 0.00                |
| 12,500.00                                              | 70.56           | 179.60      | 12,322.33             | -529.00      | -251.26      | 536.31                  | 10.00                 | 10.00                | 0.00                |
| 12,550.00                                              | 75.56           | 179.60      | 12,336.89             | -576.82      | -250.93      | 584.09                  | 10.00                 | 10.00                | 0.00                |
| 12,600.00                                              | 80.56           | 179.60      | 12,347.24             | -625.72      | -250.59      | 632.96                  | 10.00                 | 10.00                | 0.00                |
| 12,650.00                                              | 85.56           | 179.60      | 12,353.28             | -675.33      | -250.24      | 682.54                  | 10.00                 | 10.00                | 0.00                |
| 12,694.42                                              | 90.00           | 179.60      | 12,355.00             | -719.71      | -249.93      | 726.89                  | 10.00                 | 10.00                | 0.00                |
| <b>Start 6170.48 hold at 12694.42 MD - EOC (W1 3H)</b> |                 |             |                       |              |              |                         |                       |                      |                     |
| 12,700.00                                              | 90.00           | 179.60      | 12,355.00             | -725.29      | -249.89      | 732.46                  | 0.00                  | 0.00                 | 0.00                |
| 12,800.00                                              | 90.00           | 179.60      | 12,355.00             | -825.29      | -249.19      | 832.39                  | 0.00                  | 0.00                 | 0.00                |
| 12,900.00                                              | 90.00           | 179.60      | 12,355.00             | -925.28      | -248.49      | 932.33                  | 0.00                  | 0.00                 | 0.00                |
| 13,000.00                                              | 90.00           | 179.60      | 12,355.00             | -1,025.28    | -247.80      | 1,032.26                | 0.00                  | 0.00                 | 0.00                |
| 13,100.00                                              | 90.00           | 179.60      | 12,355.00             | -1,125.28    | -247.10      | 1,132.19                | 0.00                  | 0.00                 | 0.00                |
| 13,200.00                                              | 90.00           | 179.60      | 12,355.00             | -1,225.28    | -246.40      | 1,232.12                | 0.00                  | 0.00                 | 0.00                |
| 13,300.00                                              | 90.00           | 179.60      | 12,355.00             | -1,325.27    | -245.70      | 1,332.05                | 0.00                  | 0.00                 | 0.00                |
| 13,400.00                                              | 90.00           | 179.60      | 12,355.00             | -1,425.27    | -245.00      | 1,431.98                | 0.00                  | 0.00                 | 0.00                |
| 13,500.00                                              | 90.00           | 179.60      | 12,355.00             | -1,525.27    | -244.30      | 1,531.91                | 0.00                  | 0.00                 | 0.00                |
| 13,600.00                                              | 90.00           | 179.60      | 12,355.00             | -1,625.27    | -243.60      | 1,631.85                | 0.00                  | 0.00                 | 0.00                |
| 13,700.00                                              | 90.00           | 179.60      | 12,355.00             | -1,725.26    | -242.91      | 1,731.78                | 0.00                  | 0.00                 | 0.00                |
| 13,800.00                                              | 90.00           | 179.60      | 12,355.00             | -1,825.26    | -242.21      | 1,831.71                | 0.00                  | 0.00                 | 0.00                |
| 13,900.00                                              | 90.00           | 179.60      | 12,355.00             | -1,925.26    | -241.51      | 1,931.64                | 0.00                  | 0.00                 | 0.00                |
| 14,000.00                                              | 90.00           | 179.60      | 12,355.00             | -2,025.26    | -240.81      | 2,031.57                | 0.00                  | 0.00                 | 0.00                |
| 14,100.00                                              | 90.00           | 179.60      | 12,355.00             | -2,125.25    | -240.11      | 2,131.50                | 0.00                  | 0.00                 | 0.00                |
| 14,200.00                                              | 90.00           | 179.60      | 12,355.00             | -2,225.25    | -239.41      | 2,231.44                | 0.00                  | 0.00                 | 0.00                |
| 14,300.00                                              | 90.00           | 179.60      | 12,355.00             | -2,325.25    | -238.72      | 2,331.37                | 0.00                  | 0.00                 | 0.00                |
| 14,400.00                                              | 90.00           | 179.60      | 12,355.00             | -2,425.25    | -238.02      | 2,431.30                | 0.00                  | 0.00                 | 0.00                |
| 14,500.00                                              | 90.00           | 179.60      | 12,355.00             | -2,525.24    | -237.32      | 2,531.23                | 0.00                  | 0.00                 | 0.00                |
| 14,600.00                                              | 90.00           | 179.60      | 12,355.00             | -2,625.24    | -236.62      | 2,631.16                | 0.00                  | 0.00                 | 0.00                |
| 14,700.00                                              | 90.00           | 179.60      | 12,355.00             | -2,725.24    | -235.92      | 2,731.09                | 0.00                  | 0.00                 | 0.00                |
| 14,800.00                                              | 90.00           | 179.60      | 12,355.00             | -2,825.24    | -235.22      | 2,831.02                | 0.00                  | 0.00                 | 0.00                |
| 14,900.00                                              | 90.00           | 179.60      | 12,355.00             | -2,925.24    | -234.52      | 2,930.96                | 0.00                  | 0.00                 | 0.00                |
| 15,000.00                                              | 90.00           | 179.60      | 12,355.00             | -3,025.23    | -233.83      | 3,030.89                | 0.00                  | 0.00                 | 0.00                |
| 15,100.00                                              | 90.00           | 179.60      | 12,355.00             | -3,125.23    | -233.13      | 3,130.82                | 0.00                  | 0.00                 | 0.00                |
| 15,200.00                                              | 90.00           | 179.60      | 12,355.00             | -3,225.23    | -232.43      | 3,230.75                | 0.00                  | 0.00                 | 0.00                |
| 15,300.00                                              | 90.00           | 179.60      | 12,355.00             | -3,325.23    | -231.73      | 3,330.68                | 0.00                  | 0.00                 | 0.00                |
| 15,400.00                                              | 90.00           | 179.60      | 12,355.00             | -3,425.22    | -231.03      | 3,430.61                | 0.00                  | 0.00                 | 0.00                |
| 15,500.00                                              | 90.00           | 179.60      | 12,355.00             | -3,525.22    | -230.33      | 3,530.55                | 0.00                  | 0.00                 | 0.00                |
| 15,600.00                                              | 90.00           | 179.60      | 12,355.00             | -3,625.22    | -229.63      | 3,630.48                | 0.00                  | 0.00                 | 0.00                |
| 15,700.00                                              | 90.00           | 179.60      | 12,355.00             | -3,725.22    | -228.94      | 3,730.41                | 0.00                  | 0.00                 | 0.00                |

|           |                           |                              |                                                   |
|-----------|---------------------------|------------------------------|---------------------------------------------------|
| Database: | EDM 5000.1 Single User Db | Local Co-ordinate Reference: | Well W1 3H                                        |
| Company:  | ConocoPhillips            | TVD Reference:               | Well @ 3164.00usft (H&P 499 RKB: 25' + GL: 3139') |
| Project:  | Lea County, NM            | MD Reference:                | Well @ 3164.00usft (H&P 499 RKB: 25' + GL: 3139') |
| Site:     | War Hammer 25 Fed Com     | North Reference:             | Grid                                              |
| Well:     | W1 3H                     | Survey Calculation Method:   | Minimum Curvature                                 |
| Wellbore: | Original Hole             |                              |                                                   |
| Design:   | Design #1                 |                              |                                                   |

| Planned Survey                |                 |             |                       |              |              |                         |                       |                      |                     |
|-------------------------------|-----------------|-------------|-----------------------|--------------|--------------|-------------------------|-----------------------|----------------------|---------------------|
| Measured Depth (usft)         | Inclination (°) | Azimuth (°) | Vertical Depth (usft) | +N/-S (usft) | +E/-W (usft) | Vertical Section (usft) | Dogleg Rate (°/100ft) | Build Rate (°/100ft) | Turn Rate (°/100ft) |
| 15,800.00                     | 90.00           | 179.60      | 12,355.00             | -3,825.21    | -228.24      | 3,830.34                | 0.00                  | 0.00                 | 0.00                |
| 15,900.00                     | 90.00           | 179.60      | 12,355.00             | -3,925.21    | -227.54      | 3,930.27                | 0.00                  | 0.00                 | 0.00                |
| 16,000.00                     | 90.00           | 179.60      | 12,355.00             | -4,025.21    | -226.84      | 4,030.20                | 0.00                  | 0.00                 | 0.00                |
| 16,100.00                     | 90.00           | 179.60      | 12,355.00             | -4,125.21    | -226.14      | 4,130.14                | 0.00                  | 0.00                 | 0.00                |
| 16,200.00                     | 90.00           | 179.60      | 12,355.00             | -4,225.20    | -225.44      | 4,230.07                | 0.00                  | 0.00                 | 0.00                |
| 16,300.00                     | 90.00           | 179.60      | 12,355.00             | -4,325.20    | -224.75      | 4,330.00                | 0.00                  | 0.00                 | 0.00                |
| 16,400.00                     | 90.00           | 179.60      | 12,355.00             | -4,425.20    | -224.05      | 4,429.93                | 0.00                  | 0.00                 | 0.00                |
| 16,500.00                     | 90.00           | 179.60      | 12,355.00             | -4,525.20    | -223.35      | 4,529.86                | 0.00                  | 0.00                 | 0.00                |
| 16,600.00                     | 90.00           | 179.60      | 12,355.00             | -4,625.19    | -222.65      | 4,629.79                | 0.00                  | 0.00                 | 0.00                |
| 16,700.00                     | 90.00           | 179.60      | 12,355.00             | -4,725.19    | -221.95      | 4,729.72                | 0.00                  | 0.00                 | 0.00                |
| 16,800.00                     | 90.00           | 179.60      | 12,355.00             | -4,825.19    | -221.25      | 4,829.66                | 0.00                  | 0.00                 | 0.00                |
| 16,900.00                     | 90.00           | 179.60      | 12,355.00             | -4,925.19    | -220.55      | 4,929.59                | 0.00                  | 0.00                 | 0.00                |
| 17,000.00                     | 90.00           | 179.60      | 12,355.00             | -5,025.18    | -219.86      | 5,029.52                | 0.00                  | 0.00                 | 0.00                |
| 17,100.00                     | 90.00           | 179.60      | 12,355.00             | -5,125.18    | -219.16      | 5,129.45                | 0.00                  | 0.00                 | 0.00                |
| 17,200.00                     | 90.00           | 179.60      | 12,355.00             | -5,225.18    | -218.46      | 5,229.38                | 0.00                  | 0.00                 | 0.00                |
| 17,300.00                     | 90.00           | 179.60      | 12,355.00             | -5,325.18    | -217.76      | 5,329.31                | 0.00                  | 0.00                 | 0.00                |
| 17,400.00                     | 90.00           | 179.60      | 12,355.00             | -5,425.17    | -217.06      | 5,429.25                | 0.00                  | 0.00                 | 0.00                |
| 17,500.00                     | 90.00           | 179.60      | 12,355.00             | -5,525.17    | -216.36      | 5,529.18                | 0.00                  | 0.00                 | 0.00                |
| 17,600.00                     | 90.00           | 179.60      | 12,355.00             | -5,625.17    | -215.67      | 5,629.11                | 0.00                  | 0.00                 | 0.00                |
| 17,700.00                     | 90.00           | 179.60      | 12,355.00             | -5,725.17    | -214.97      | 5,729.04                | 0.00                  | 0.00                 | 0.00                |
| 17,800.00                     | 90.00           | 179.60      | 12,355.00             | -5,825.16    | -214.27      | 5,828.97                | 0.00                  | 0.00                 | 0.00                |
| 17,900.00                     | 90.00           | 179.60      | 12,355.00             | -5,925.16    | -213.57      | 5,928.90                | 0.00                  | 0.00                 | 0.00                |
| 18,000.00                     | 90.00           | 179.60      | 12,355.00             | -6,025.16    | -212.87      | 6,028.83                | 0.00                  | 0.00                 | 0.00                |
| 18,100.00                     | 90.00           | 179.60      | 12,355.00             | -6,125.16    | -212.17      | 6,128.77                | 0.00                  | 0.00                 | 0.00                |
| 18,200.00                     | 90.00           | 179.60      | 12,355.00             | -6,225.15    | -211.47      | 6,228.70                | 0.00                  | 0.00                 | 0.00                |
| 18,300.00                     | 90.00           | 179.60      | 12,355.00             | -6,325.15    | -210.78      | 6,328.63                | 0.00                  | 0.00                 | 0.00                |
| 18,400.00                     | 90.00           | 179.60      | 12,355.00             | -6,425.15    | -210.08      | 6,428.56                | 0.00                  | 0.00                 | 0.00                |
| 18,500.00                     | 90.00           | 179.60      | 12,355.00             | -6,525.15    | -209.38      | 6,528.49                | 0.00                  | 0.00                 | 0.00                |
| 18,600.00                     | 90.00           | 179.60      | 12,355.00             | -6,625.15    | -208.68      | 6,628.42                | 0.00                  | 0.00                 | 0.00                |
| 18,700.00                     | 90.00           | 179.60      | 12,355.00             | -6,725.14    | -207.98      | 6,728.36                | 0.00                  | 0.00                 | 0.00                |
| 18,800.00                     | 90.00           | 179.60      | 12,355.00             | -6,825.14    | -207.28      | 6,828.29                | 0.00                  | 0.00                 | 0.00                |
| 18,864.90                     | 90.00           | 179.60      | 12,355.00             | -6,890.04    | -206.83      | 6,893.14                | 0.00                  | 0.00                 | 0.00                |
| TD at 18864.90 - PBHL (W1 3H) |                 |             |                       |              |              |                         |                       |                      |                     |


|           |                           |                              |                                                   |
|-----------|---------------------------|------------------------------|---------------------------------------------------|
| Database: | EDM 5000.1 Single User Db | Local Co-ordinate Reference: | Well W1 3H                                        |
| Company:  | ConocoPhillips            | TVD Reference:               | Well @ 3164.00usft (H&P 499 RKB: 25' + GL: 3139') |
| Project:  | Lea County, NM            | MD Reference:                | Well @ 3164.00usft (H&P 499 RKB: 25' + GL: 3139') |
| Site:     | War Hammer 25 Fed Com     | North Reference:             | Grid                                              |
| Well:     | W1 3H                     | Survey Calculation Method:   | Minimum Curvature                                 |
| Wellbore: | Original Hole             |                              |                                                   |
| Design:   | Design #1                 |                              |                                                   |

| Design Targets                                                                                  |           |          |           |           |         |            |            |                 |                   |
|-------------------------------------------------------------------------------------------------|-----------|----------|-----------|-----------|---------|------------|------------|-----------------|-------------------|
| Target Name                                                                                     | Dip Angle | Dip Dir. | TVD       | +N/-S     | +E/-W   | Northing   | Easting    | Latitude        | Longitude         |
| - hit/miss target                                                                               | (°)       | (°)      | (usft)    | (usft)    | (usft)  | (usft)     | (usft)     |                 |                   |
| - Shape                                                                                         |           |          |           |           |         |            |            |                 |                   |
| SHL (W1 3H)                                                                                     | 0.00      | 0.00     | 0.00      | 0.00      | 0.00    | 371,716.56 | 721,158.19 | 32° 1' 11.840 N | 103° 37' 11.140 W |
| - plan hits target center                                                                       |           |          |           |           |         |            |            |                 |                   |
| - Point                                                                                         |           |          |           |           |         |            |            |                 |                   |
| Build 1.5°/100' (W1 3H)                                                                         | 0.00      | 0.00     | 2,400.00  | 0.00      | 0.00    | 371,716.56 | 721,158.19 | 32° 1' 11.840 N | 103° 37' 11.140 W |
| - plan hits target center                                                                       |           |          |           |           |         |            |            |                 |                   |
| - Point                                                                                         |           |          |           |           |         |            |            |                 |                   |
| Hold 5° (W1 3H)                                                                                 | 0.00      | 0.00     | 2,732.81  | -7.27     | -12.58  | 371,709.29 | 721,145.61 | 32° 1' 11.769 N | 103° 37' 11.287 W |
| - plan hits target center                                                                       |           |          |           |           |         |            |            |                 |                   |
| - Point                                                                                         |           |          |           |           |         |            |            |                 |                   |
| Drop 1.5°/100' (W1 3H)                                                                          | 0.00      | 0.00     | 5,754.24  | -139.52   | -241.36 | 371,577.04 | 720,916.82 | 32° 1' 10.475 N | 103° 37' 13.954 W |
| - plan hits target center                                                                       |           |          |           |           |         |            |            |                 |                   |
| - Point                                                                                         |           |          |           |           |         |            |            |                 |                   |
| VT (W1 3H)                                                                                      | 0.00      | 0.00     | 6,087.04  | -146.79   | -253.94 | 371,569.77 | 720,904.25 | 32° 1' 10.404 N | 103° 37' 14.101 W |
| - plan hits target center                                                                       |           |          |           |           |         |            |            |                 |                   |
| - Point                                                                                         |           |          |           |           |         |            |            |                 |                   |
| KOP (W1 3H)                                                                                     | 0.00      | 0.00     | 11,782.04 | -146.77   | -253.93 | 371,569.79 | 720,904.25 | 32° 1' 10.404 N | 103° 37' 14.101 W |
| - plan misses target center by 0.05usft at 11794.42usft MD (11782.04 TVD, -146.81 N, -253.94 E) |           |          |           |           |         |            |            |                 |                   |
| - Point                                                                                         |           |          |           |           |         |            |            |                 |                   |
| PBHL (W1 3H)                                                                                    | 0.00      | 0.00     | 12,355.00 | -6,890.04 | -206.83 | 364,826.52 | 720,951.36 | 32° 0' 3.670 N  | 103° 37' 14.070 W |
| - plan hits target center                                                                       |           |          |           |           |         |            |            |                 |                   |
| - Point                                                                                         |           |          |           |           |         |            |            |                 |                   |
| EOC (W1 3H)                                                                                     | 0.00      | 0.00     | 12,355.00 | -719.71   | -249.93 | 370,996.85 | 720,908.26 | 32° 1' 4.734 N  | 103° 37' 14.098 W |
| - plan hits target center                                                                       |           |          |           |           |         |            |            |                 |                   |
| - Point                                                                                         |           |          |           |           |         |            |            |                 |                   |

| Formations     |                |                               |           |      |               |
|----------------|----------------|-------------------------------|-----------|------|---------------|
| Measured Depth | Vertical Depth | Name                          | Lithology | Dip  | Dip Direction |
| (usft)         | (usft)         |                               |           | (°)  | (°)           |
| 7,380.38       | 7,368.00       | Brushy Canyon                 |           | 0.00 | 0.00          |
| 8,877.38       | 8,865.00       | Bone Spring 1st Carbonate Top |           | 0.00 | 0.00          |
| 9,083.38       | 9,071.00       | Avalon A                      |           | 0.00 | 0.00          |
| 9,285.38       | 9,273.00       | Avalon B                      |           | 0.00 | 0.00          |
| 9,434.38       | 9,422.00       | Avalon C                      |           | 0.00 | 0.00          |
| 9,728.38       | 9,716.00       | Avalon D                      |           | 0.00 | 0.00          |
| 9,770.38       | 9,758.00       | 1st Bone Spring Sand          |           | 0.00 | 0.00          |
| 9,982.38       | 9,970.00       | FBS shale                     |           | 0.00 | 0.00          |
| 10,153.38      | 10,141.00      | 2nd Bone Spring Carbonate     |           | 0.00 | 0.00          |
| 10,310.38      | 10,298.00      | 2nd Bone Spring Sand          |           | 0.00 | 0.00          |
| 10,666.38      | 10,654.00      | 3rd Bone Spring Carbonate     |           | 0.00 | 0.00          |
| 11,501.38      | 11,489.00      | 3rd Bone Spring Sand          |           | 0.00 | 0.00          |
| 11,847.46      | 11,835.00      | Wolfcamp                      |           | 0.00 | 0.00          |
| 12,067.61      | 12,045.00      | Wolfcamp 1                    |           | 0.00 | 0.00          |

|           |                           |                              |                                                   |
|-----------|---------------------------|------------------------------|---------------------------------------------------|
| Database: | EDM 5000.1 Single User Db | Local Co-ordinate Reference: | Well W1 3H                                        |
| Company:  | ConocoPhillips            | TVD Reference:               | Well @ 3164.00usft (H&P 499 RKB: 25' + GL: 3139') |
| Project:  | Lea County, NM            | MD Reference:                | Well @ 3164.00usft (H&P 499 RKB: 25' + GL: 3139') |
| Site:     | War Hammer 25 Fed Com     | North Reference:             | Grid                                              |
| Well:     | W1 3H                     | Survey Calculation Method:   | Minimum Curvature                                 |
| Wellbore: | Original Hole             |                              |                                                   |
| Design:   | Design #1                 |                              |                                                   |

| Plan Annotations      |                       |                   |              |                                   |
|-----------------------|-----------------------|-------------------|--------------|-----------------------------------|
| Measured Depth (usft) | Vertical Depth (usft) | Local Coordinates |              | Comment                           |
|                       |                       | +N/-S (usft)      | +E/-W (usft) |                                   |
| 2,400.00              | 2,400.00              | 0.00              | 0.00         | Start Build 1.50                  |
| 2,733.23              | 2,732.81              | -7.27             | -12.58       | Start 3032.96 hold at 2733.23 MD  |
| 5,766.20              | 5,754.24              | -139.52           | -241.36      | Start DLS 1.50 TFO -180.00        |
| 6,099.42              | 6,087.04              | -146.79           | -253.94      | Start 5695.01 hold at 6099.42 MD  |
| 11,794.43             | 11,782.05             | -146.81           | -253.94      | Start Build 10.00                 |
| 12,694.42             | 12,355.00             | -719.71           | -249.93      | Start 6170.48 hold at 12694.42 MD |
| 18,864.90             | 12,355.00             | -6,890.04         | -206.83      | .TD at 18864.90                   |



- LEGEND
- ① - 4 1/16"-10M FLANGED END GATE VALVE
  - ② - 4 1/16"-10M FLANGED END GATE VALVE WITH DOUBLE ACTING HYDRAULIC ACTUATOR
  - ③ - 2 1/16"-10M FLANGED END GATE VALVE
  - ④ - 2 1/16"-10M FLANGED END CHECK VALVE
  - ⑤ - DOUBLE STUDDED ADAPTER

10M annular see COA  
10M required below 7-5/8" shoe

SHAFFER BOLTED-COVER SPHERICAL ANNULAR PREVENTER, (API 16A MONOGRAMMED, 13 5/8"-10M WP), 10M BOTTOM FLANGE x 14,300 LBS WITH SHAFFER API 16A HOT OIL RESISTANT ACRYLONITRILE ELEMENT)

CAMERON UM DOUBLE RAM-TYPE PREVENTER (API 16A MONOGRAMMED, 13 5/8"-10M WP), WITH 5" CAMERON PIPE RAMS (CAMRAM FRONT PACKERS & TOP SEALS) IN TOP CAVITY AND CAMERON DS SHEARING BLIND RAMS IN BOTTOM CAVITY, BOTTOM FLANGE x STUDDED TOP (WEIGHT = 21,100 LBS, WITH RAMS)

13 5/8"-10M WP CAMERON DRILLING SPOOL (API 16A MONOGRAMMED), STUDDED TOP x FLANGED BOTTOM, WITH 4 1/16"-10M WP FLANGED OUTLETS (WEIGHT APPROXIMATELY 6,000 LBS)

CAMERON UM SINGLE RAM-TYPE PREVENTER (API 16A MONOGRAMMED, 13 5/8"-10M WP), WITH 5" CAMERON PIPE RAMS (CAMRAM FRONT PACKERS & TOP SEALS) BOTTOM FLANGE x STUDDED TOP (WEIGHT = 10,900 LBS)

SEE LIFT LUG DETAIL

3'-11 7/8"

4'-3 7/8"

12'-7 1/2"

1'-8 7/8"


2'-6 7/8"

11'-1 5/8" CLOSED

12'-5 3/8" OPERATING

16'-5" OPENED

13 5/8-10M STACK



CAMERON LIFT EYES, 2 PER PREVENTER, 50 SHORT TON RATED CAPACITY EACH.

PRELIMINARY  
April-14-2011  
DRAFTSMAN  
ENGINEER

API 8A MONOGRAMMED CAMERON CHOKE AND KILLING VALVE ASSEMBLIES ARE NOT SHOWN FOR CLARITY

WEIGHTS DO NOT INCLUDE HOSES, ADAPTER SPOOLS OR QUICK CONNECT FITTINGS

# PROPRIETARY

THIS DRAWING AND THE IDEAS AND INFORMATION INCLUDED IN THIS DRAWING ARE PROPRIETARY AND ARE NOT TO BE REPRODUCED, DISTRIBUTED OR DISCLOSED IN ANY MANNER, WITHOUT THE PRIOR WRITTEN CONSENT OF A DULY AUTHORIZED OFFICER OF HELMERICH & PAYNE INTL DRILLING CO.




HELMERICH & PAYNE  
INTERNATIONAL DRILLING CO.

| ENGINEERING APPROVAL | DATE           | TITLE                                                                                   |
|----------------------|----------------|-----------------------------------------------------------------------------------------|
| JAV                  | 12/18/07       | ADDED SHEET 03                                                                          |
| JBG                  | 4-10-07        | ORIENTATION REVERSED DOUBLE STUDDED ADAPTER, VALVES 1, 2, 3, 4 AND 10 CHECK VALVE ADDED |
| JBG                  | 4-04-07        | ADDED TO SPACER ADAPTER SPOOL                                                           |
| MWL                  | 02-07-07       | ADDED ADAPTER SPOOL                                                                     |
| MWL                  | 08-13-02       | CORRECTED BOP STACK                                                                     |
| REV                  | DATE           | DESCRIPTION                                                                             |
| BY                   | SCALE: 3/4"=1' | SHEET: 1 OF 1                                                                           |




13 5/8"-10M BOP 3 RAM STACK  
FLEXRIG3

CUSTOMER: H&P  
PROJECT: FLEXRIG3  
DRAWN: MTS  
DATE: 6-5-02  
DWG. NO.: 210-P1-07  
REV: E




Note: Dimensional information reflected on this drawing are estimated measurements only.

Helmerich & Payne  
Rig Flex 3 Manifold with 3rd Choke Run




Name: Jeanette Date: 9-9-08 Working Pressure: # J-3737-3

CAMERON



Quality Document

|                                                                                                                                                                                                                                                                                                                                                                                                    |           |                                            |                                                                                                                                                                                                                                            |                              |  |
|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------|--------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------|--|
| <b>QUALITY CONTROL</b>                                                                                                                                                                                                                                                                                                                                                                             |           |                                            |                                                                                                                                                                                                                                            | CERT. N°: 184                |  |
| <b>INSPECTION AND TEST CERTIFICATE</b>                                                                                                                                                                                                                                                                                                                                                             |           |                                            |                                                                                                                                                                                                                                            |                              |  |
| PURCHASER: ContiTech Beattie Co.                                                                                                                                                                                                                                                                                                                                                                   |           |                                            | P.O. N°: 005438                                                                                                                                                                                                                            |                              |  |
| CONTITECH ORDER N°: 516273                                                                                                                                                                                                                                                                                                                                                                         |           | HOSE TYPE: 3" ID Choke and Kill Hose       |                                                                                                                                                                                                                                            |                              |  |
| HOSE SERIAL N°: 61477                                                                                                                                                                                                                                                                                                                                                                              |           | NOMINAL / ACTUAL LENGTH: 10,67 m / 10,71 m |                                                                                                                                                                                                                                            |                              |  |
| W.P. 68,9 MPa 10000 psi                                                                                                                                                                                                                                                                                                                                                                            |           | T.P. 103,4 MPa 15000 psi                   |                                                                                                                                                                                                                                            | Duration: 60 min.            |  |
| Pressure test with water at ambient temperature                                                                                                                                                                                                                                                                                                                                                    |           |                                            |                                                                                                                                                                                                                                            |                              |  |
| See attachment. ( 1 page )                                                                                                                                                                                                                                                                                                                                                                         |           |                                            |                                                                                                                                                                                                                                            |                              |  |
| <p>↑ 10 mm = 10 Min.</p> <p>→ 10 mm = 20 MPa</p>                                                                                                                                                                                                                                                                                                                                                   |           |                                            |                                                                                                                                                                                                                                            |                              |  |
| COUPLINGS Type                                                                                                                                                                                                                                                                                                                                                                                     |           | Serial N°                                  |                                                                                                                                                                                                                                            | Quality                      |  |
| 3" coupling with                                                                                                                                                                                                                                                                                                                                                                                   |           | 10178 10173                                |                                                                                                                                                                                                                                            | AISI 4130                    |  |
| 4 1/16" 10K API Flange end                                                                                                                                                                                                                                                                                                                                                                         |           |                                            |                                                                                                                                                                                                                                            | AISI 4130                    |  |
|                                                                                                                                                                                                                                                                                                                                                                                                    |           |                                            |                                                                                                                                                                                                                                            | Heat N°                      |  |
|                                                                                                                                                                                                                                                                                                                                                                                                    |           |                                            |                                                                                                                                                                                                                                            | 20231                        |  |
|                                                                                                                                                                                                                                                                                                                                                                                                    |           |                                            |                                                                                                                                                                                                                                            | 33051                        |  |
| <b>NOT DESIGNED FOR WELL TESTING</b>                                                                                                                                                                                                                                                                                                                                                               |           |                                            |                                                                                                                                                                                                                                            | <b>API Spec 16 C</b>         |  |
|                                                                                                                                                                                                                                                                                                                                                                                                    |           |                                            |                                                                                                                                                                                                                                            | <b>Temperature rate: "B"</b> |  |
| All metal parts are flawless                                                                                                                                                                                                                                                                                                                                                                       |           |                                            |                                                                                                                                                                                                                                            |                              |  |
| WE CERTIFY THAT THE ABOVE HOSE HAS BEEN MANUFACTURED IN ACCORDANCE WITH THE TERMS OF THE ORDER INSPECTED AND PRESSURE TESTED AS ABOVE WITH SATISFACTORY RESULT.                                                                                                                                                                                                                                    |           |                                            |                                                                                                                                                                                                                                            |                              |  |
| STATEMENT OF CONFORMITY: We hereby certify that the above items/equipment supplied by us are in conformity with the terms, conditions and specifications of the above Purchaser Order and that these items/equipment were fabricated inspected and tested in accordance with the referenced standards, codes and specifications and meet the relevant acceptance criteria and design requirements. |           |                                            |                                                                                                                                                                                                                                            |                              |  |
| COUNTRY OF ORIGIN HUNGARY/EU                                                                                                                                                                                                                                                                                                                                                                       |           |                                            |                                                                                                                                                                                                                                            |                              |  |
| Date:                                                                                                                                                                                                                                                                                                                                                                                              | Inspector |                                            | Quality Control                                                                                                                                                                                                                            |                              |  |
| 30. January 2012.                                                                                                                                                                                                                                                                                                                                                                                  |           |                                            | ContiTech Rubber<br>Industrial Kft.<br>Quality Control Dept.<br>  |                              |  |

Confession Referred under Rule 302.  
 Subscribed at St. Louis, Missouri, this 11th day of  
 February, 1922. Signed J. C. GIBSON  
 Attorney

From: +30 62 565 737  
 Fax: +30 62 500 736  
 e-mail: [info@had.com.gr](mailto:info@had.com.gr)  
 Internet: [www.had.com.gr](http://www.had.com.gr)

The Court of Criminal Causes as  
Happening Court  
Happening Court No. 111 05-02 021502  
E-1111 No. 111 021502

Bank 1135  
Comptons Sq.  
Exhibit  
1-1220115-11100015-0200000

## No: 182, 184, 185


Page: 1/1

**Certified Public  
Industrial Hyg.  
Quality Control Dept.**

[illegible]

## Attachment # 1

|                                     |                      |
|-------------------------------------|----------------------|
| CONTITECH RUBBER<br>Industrial Kft. | No: QC-DB- 45 / 2012 |
|                                     | Page: 9 / 50         |



## Hose Data Sheet

|                              |                                                                    |
|------------------------------|--------------------------------------------------------------------|
| CRI Order No.                | 516273                                                             |
| Customer                     | ContiTech Beattie Co.                                              |
| Customer Order No            | PO5438 STOCK                                                       |
| Item No.                     | 3                                                                  |
| Hose Type                    | Flexible Hose                                                      |
| <b>Standard</b>              | <b>API SPEC 16 C</b>                                               |
| Inside dia in inches         | 3                                                                  |
| Length                       | 35 ft                                                              |
| Type of coupling one end     | FLANGE 4 1/16" API SPEC 6A TYPE 6BX FOR 10000 PSIBX155 RING GROOVE |
| Type of coupling other end   | FLANGE 4 1/16" API SPEC 6A TYPE 6BX FOR 10000 PSIBX155 RING GROOVE |
| H2S service NACE MR0175      | Yes                                                                |
| Working Pressure             | 10 000 psi                                                         |
| Design Pressure              | 10 000 psi                                                         |
| Test Pressure                | 15 000 psi                                                         |
| Safety Factor                | 2,25                                                               |
| Marking                      | USUAL PHOENIX                                                      |
| Cover                        | NOT FIRE RESISTANT                                                 |
| Outside protection           | St. steel outer wrap                                               |
| Internal stripwound tube     | No                                                                 |
| Lining                       | OIL RESISTANT                                                      |
| Safety clamp                 | No                                                                 |
| Lifting collar               | No                                                                 |
| Element C                    | No                                                                 |
| Safety chain                 | No                                                                 |
| Safety wire rope             | No                                                                 |
| Max. design temperature [°C] | 100                                                                |
| Min. design temperature [°C] | -20                                                                |
| MBR operating [m]            | 1,60                                                               |
| MBR storage [m]              | 1,40                                                               |
| Type of packing              | WOODEN CRATE ISPM-15                                               |

## **Request for Variance**

### **ConocoPhillips Company**

Lease Number: NMLC 069515

Well: War Hammer 25 Federal COM W1 3H

Location: Sec. 25, T26S, R32E

Rig: If drilled with H&P 486

Date: 3/3/2014

### **Request:**

ConocoPhillips Company respectfully requests a variance to install a flexible choke line instead of a straight choke line prescribed in the Onshore Order No. 2, III.A.2.b Minimum standards and enforcement provisions for choke manifold equipment. This request is made under the provision of Onshore Order No. 2, IV Variances from Minimum Standard. The rig to be used to drill this well is equipped with a flexible choke line if the requested variance is approved and determined that the proposed alternative meets the objectives of the applicable minimum standards.

### **Justifications:**

The applicability of the flexible choke line will reduce the number of target tees required to make up from the choke valve to the choke manifold. This configuration will facilitate ease of rig up and BOPE Testing.

### **Attachments:**

- Attachment # 1 Specification from Manufacturer
- Attachment # 2 Mill & Test Certification from Manufacturer

### **Contact Information:**

Program prepared by:

Jason A. Levinson

Drilling Engineer, ConocoPhillips Company

Phone (281) 206-5335

Cell (281) 682-2783

Date: 05 February 2014



Fluid Technology

Quality Document

453.369-001

| QUALITY CONTROL<br>INSPECTION AND TEST CERTIFICATE                                                                                                                                                                                                                                                                                                                                                 |           |                                            |                                                                     | CERT. N°: 1098      |  |
|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------|--------------------------------------------|---------------------------------------------------------------------|---------------------|--|
| PURCHASER: ContiTech Beattie Co.                                                                                                                                                                                                                                                                                                                                                                   |           |                                            |                                                                     | P.O. N°: 004452     |  |
| CONTITECH ORDER N°: 482598                                                                                                                                                                                                                                                                                                                                                                         |           | HOSE TYPE: 3" ID                           |                                                                     | Choke and Kill Hose |  |
| HOSE SERIAL N°: 56839                                                                                                                                                                                                                                                                                                                                                                              |           | NOMINAL / ACTUAL LENGTH: 10,67 m / 10,69 m |                                                                     |                     |  |
| W.P. 68,9 MPa 10000 psi                                                                                                                                                                                                                                                                                                                                                                            |           | T.P. 103,4 MPa 15000 psi                   |                                                                     | Duration: 60 min.   |  |
| <p>Pressure test with water at ambient temperature</p> <p style="text-align: center;">See attachment. ( 1 page )</p> <p>↑ 10 min = 10 Min.<br/>→ 10 min = 25 MPa</p>                                                                                                                                                                                                                               |           |                                            |                                                                     |                     |  |
| COUPLINGS Type                                                                                                                                                                                                                                                                                                                                                                                     | Serial N° | Quality                                    | Heat N°                                                             |                     |  |
| 3" coupling with                                                                                                                                                                                                                                                                                                                                                                                   | 8436 1682 | AISI 4130                                  | 16837                                                               |                     |  |
| 4 1/16" Flange end                                                                                                                                                                                                                                                                                                                                                                                 |           | AISI 4130                                  | 31296 31501                                                         |                     |  |
| <b>API Spec 16 C</b><br><b>Temperature rate: "B"</b>                                                                                                                                                                                                                                                                                                                                               |           |                                            |                                                                     |                     |  |
| All metal parts are flawless                                                                                                                                                                                                                                                                                                                                                                       |           |                                            |                                                                     |                     |  |
| WE CERTIFY THAT THE ABOVE HOSE HAS BEEN MANUFACTURED IN ACCORDANCE WITH THE TERMS OF THE ORDER INSPECTED AND PRESSURE TESTED AS ABOVE WITH SATISFACTORY RESULT.                                                                                                                                                                                                                                    |           |                                            |                                                                     |                     |  |
| STATEMENT OF CONFORMITY: We hereby certify that the above items/equipment supplied by us are in conformity with the terms, conditions and specifications of the above Purchaser Order and that these items/equipment were fabricated inspected and tested in accordance with the referenced standards, codes and specifications and meet the relevant acceptance criteria and design requirements. |           |                                            |                                                                     |                     |  |
| COUNTRY OF ORIGIN HUNGARY/EU                                                                                                                                                                                                                                                                                                                                                                       |           |                                            |                                                                     |                     |  |
| Date:                                                                                                                                                                                                                                                                                                                                                                                              | Inspector | Quality Control                            | ContiTech Rubber<br>Industrial Kft.<br>Quality Control Dept.<br>(3) |                     |  |
| 02. November 2010.                                                                                                                                                                                                                                                                                                                                                                                 |           |                                            |                                                                     |                     |  |

Certified Product (various Kft.)


Fax: +36 82 661 207

The Court of Commercial Disputes at

Budapest


## Attachment # 1

|                                     |                                      |
|-------------------------------------|--------------------------------------|
| CONTITECH RUBBER<br>Industrial Kft. | No: QC-DB- 45 / 2012<br>Page: 9 / 50 |
|-------------------------------------|--------------------------------------|



## Hose Data Sheet

|                              |                                                                     |
|------------------------------|---------------------------------------------------------------------|
| CRI Order No.                | 516273                                                              |
| Customer                     | ContiTech Beattie Co.                                               |
| Customer Order No            | PO5438 STOCK                                                        |
| Item No.                     | 3                                                                   |
| Hose Type                    | Flexible Hose                                                       |
| <b>Standard</b>              | <b>API SPEC 16 C</b>                                                |
| Inside dia in inches         | 3                                                                   |
| Length                       | 35 ft                                                               |
| Type of coupling one end     | FLANGE 4 1/16" API SPEC 6A TYPE 6BX FOR 10000 PSIBX155 RING GROOVE  |
| Type of coupling other end   | FLANGE 4 1/16" API SPEC 6A TYPE 6BX FOR 10000 PSI BX155 RING GROOVE |
| H2S service NACE MR0175      | Yes                                                                 |
| Working Pressure             | 10 000 psi                                                          |
| Design Pressure              | 10 000 psi                                                          |
| Test Pressure                | 15 000 psi                                                          |
| Safety Factor                | 2,25                                                                |
| Marking                      | USUAL PHOENIX                                                       |
| Cover                        | NOT FIRE RESISTANT                                                  |
| Outside protection           | St. steel outer wrap                                                |
| Internal stripwound tube     | No                                                                  |
| Lining                       | OIL RESISTANT                                                       |
| Safety clamp                 | No                                                                  |
| Lifting collar               | No                                                                  |
| Element C                    | No                                                                  |
| Safety chain                 | No                                                                  |
| Safety wire rope             | No                                                                  |
| Max. design temperature [°C] | 100                                                                 |
| Min. design temperature [°C] | -20                                                                 |
| MBR operating [m]            | 1,60                                                                |
| MBR storage [m]              | 1,40                                                                |
| Type of packing              | WOODEN CRATE ISPM-15                                                |



ContiTech Rubber  
Industrial Kft.  
Quality Control Dept.  
(3)

03.20.2020/09.17.5...

## **Request for Variance**

### **ConocoPhillips Company**

Lease Number: NMLC 069515

Well: War Hammer 25 Federal COM W1 3H

Location: Sec. 25, T26S, R32E

Rig: If drilled with H&P 453

Date: 3/3/2014

### **Request:**

ConocoPhillips Company respectfully requests a variance to install a flexible choke line instead of a straight choke line prescribed in the Onshore Order No. 2, III.A.2.b Minimum standards and enforcement provisions for choke manifold equipment. This request is made under the provision of Onshore Order No. 2, IV Variances from Minimum Standard. The rig to be used to drill this well is equipped with a flexible choke line if the requested variance is approved and determined that the proposed alternative meets the objectives of the applicable minimum standards.

### **Justifications:**

The applicability of the flexible choke line will reduce the number of target tees required to make up from the choke valve to the choke manifold. This configuration will facilitate ease of rig up and BOPE Testing.

### **Attachments:**

- Attachment # 1 Specification from Manufacturer
- Attachment # 2 Mill & Test Certification from Manufacturer

### **Contact Information:**

Program prepared by:

Jason A. Levinson

Drilling Engineer, ConocoPhillips Company


Phone (281) 206-5335

Cell (281) 682-2783

Date: 05 February 2014



# BACKFILL AROUND PIPE




BACKFILL DIRT TO BE AS  
FREE OF ROCKS AND LARGE  
PARTICLES AS POSSIBLE


TRACER WIRE INSTALLED  
2" ABOVE NON-METALLIC

SOFT FILL DIRT OR SAND  
WITH NO ROCKS OR SOLID  
PARTICLES GREATER THAN  
1" IN CIRCUMFERENCE

# BACKFILL AROUND PIPE



(4 QTY) 4" PIPE + (4 QTY) 2" PIPE  
 \*4" AND 2" PIPE ALTERNATING FOR TOTAL OF 8  
 PIPES\*  
 6" CLEARANCE AT BOTH ENDS  
 12" CLEARANCE BETWEEN EACH PIPE



### DESIGNED APPURTENANCE LOADING

| TYPE               | ELEVATION | TYPE                          | ELEVATION |
|--------------------|-----------|-------------------------------|-----------|
| 5000# Fall Load    | 50        | 12ft x 2.5" dia. Whip Antenna | 30        |
| Andrew 2' w/Radome | 30        | 12ft x 2.5" dia. Whip Antenna | 25        |
| Andrew 2' w/Radome | 30        |                               |           |

### MATERIAL STRENGTH

| GRADE   | Fy     | Fu     | GRADE | Fy     | Fu     |
|---------|--------|--------|-------|--------|--------|
| A572-50 | 50 ksi | 65 ksi | A36   | 36 ksi | 58 ksi |

### TOWER DESIGN NOTES

1. Tower designed for Exposure C to the TIA-222-G Standard.
2. Tower designed for a 90 mph basic wind in accordance with the TIA-222-G Standard.
3. Tower is also designed for a 30 mph basic wind with 0.25 in ice. Ice is considered to increase in thickness with height.
4. Deflections are based upon a 60 mph wind.
5. Tower Structure Class II.
6. Topographic Category 1 with Crest Height of 0.00 ft
7. TOWER RATING: 41.1%



This engineering document is intended to be used as a sales tool. The engineering judgments herein are general in nature and are not intended to be site specific. Per section 107 of the International Building Code site specific drawings are required. Therefore, if or when this equipment is to be installed, a site specific analysis including site specific conditions (antenna equipment loading, elevations, wind speed, topographic factors, exposure coefficients, structure class, and soil strengths, ect) should be considered. DaVinci can provide site specific documents to meet the requirements of the building code and to ensure that the mounts, tower & foundation has sufficient structural capacity to support the proposed loading.

ALL REACTIONS  
ARE FACTORED

MAX. CORNER REACTIONS AT BASE:


DOWN: 10768 lb  
SHEAR: 182 lb

UPLIFT: -10132 lb  
SHEAR: 271 lb



1/21/2014

|                                  |  |                                                                                        |                               |
|----------------------------------|--|----------------------------------------------------------------------------------------|-------------------------------|
| <b>DaVinci Engineering, Inc.</b> |  | Job: <b>9914267-011</b>                                                                |                               |
| PO Box 1966                      |  | Project: <b>30-ft Light Duty Tower</b>                                                 |                               |
| Santa Maria, CA 93456            |  | Client: <b>Lea County, New Mexico</b>                                                  | Drawn by: <b>Simon Leland</b> |
| Phone: (805) 922-5221            |  | Code: <b>TIA-222-G</b>                                                                 | Date: <b>01/21/14</b>         |
| FAX: (805) 880-0402              |  | Path: <b>R:\Engineering Documents\TOWER FILES\DaVinci Tower 26702014\14267-011.dwg</b> | Scale: <b>NTS</b>             |
|                                  |  |                                                                                        | Dwg No. <b>E-1</b>            |



DALEY TOWER SERVICE, INC.

**DAVINCI**  
Engineering, Inc.

PO BOX 1966 SANTA MARIA, CALIFORNIA 93456  
PHONE: (805) 922-5221 FAX: (805) 880-0402  
Project # 9914267-011

THIS ENGINEERING DOCUMENT IS INTENDED TO BE USED AS A SALES TOOL. THE ENGINEERING JUDGMENTS HEREIN ARE GENERAL IN NATURE AND ARE NOT INTENDED TO BE SITE SPECIFIC. PER SECTION 107 OF THE INTERNATIONAL BUILDING CODE SITE SPECIFIC DRAWINGS ARE REQUIRED. THEREFORE, IF OR WHEN THIS EQUIPMENT IS TO BE INSTALLED, A SITE SPECIFIC ANALYSIS INCLUDING SITE SPECIFIC CONDITIONS (ANTENNA EQUIPMENT LOADING, ELEVATIONS, WIND SPEED, TOPOGRAPHIC FACTORS, EXPOSURE COEFFICIENTS, STRUCTURE CLASS, AND SOIL STRENGTHS, ECT) SHOULD BE CONSIDERED. DAVINCI CAN PROVIDE SITE SPECIFIC DOCUMENTS TO MEET THE REQUIREMENTS OF THE BUILDING CODE AND TO ENSURE THAT THE FOUNDATION HAS SUFFICIENT STRUCTURAL CAPACITY TO SUPPORT THE PROPOSED LOADING.

4000 PSI CONCRETE

10'-0" DALEY LIGHT  
DUTY TOWER SECTION  
EMBEDDED 8'-0"




**TYPICAL FOUNDATION NOTES:**

1. FOUNDATION DESIGN IS BASED ON THE FOLLOWING ASSUMED SOIL VALUES:  
UNIT WEIGHT OF SOIL: 100 PCF  
ALLOWABLE BEARING CAPACITY: 2000 PSF  
ALLOWABLE LATERAL LOAD: 200 PSF/FT DEPTH  
GROUND WATER BELOW THE DEPTH OF THE CAISSON

2. ALL FOUNDATION CONCRETE SHALL HAVE A MINIMUM COMPRESSIVE STRENGTH OF 4000 PSI WITHIN 28 DAYS OF PLACEMENT. PROPORTIONING OF THE CONCRETE MIX SHALL BE DESIGNED BY AN APPROVED LABORATORY. ALL CONCRETE CONSTRUCTION SHALL BE IN ACCORDANCE WITH ACI 318, "THE BUILDING CODE REQUIREMENTS FOR REINFORCED CONCRETE", LATEST EDITION. CEMENT SHALL BE TYPE II, LOW ALKALI, CONFORMING TO ASTM C-150. ALL AGGREGATE USED IN THE CONCRETE SHALL CONFORM TO ASTM C-33. USE ONLY AGGREGATES KNOWN NOT TO CAUSE EXCESSIVE SHRINKAGE.

3. ESTIMATED CONCRETE VOLUME = 2 CUBIC YARDS.

4. THE FOUNDATION HAS BEEN DESIGNED TO RESIST THE FOLLOWING FACTORED LOADS:  
OVERTURNING MOMENT: 26,000 FT\*LBS; SHEAR: 750 LBS; AXIAL: 1200 LBS.



**CAISSON FOUNDATION**  
SCALE: NTS

|                                                                                                                                                 |         |                        |             |                   |
|-------------------------------------------------------------------------------------------------------------------------------------------------|---------|------------------------|-------------|-------------------|
| <b>tnxTower</b><br><br><b>DaVinci Engineering, Inc.</b><br>PO Box 1966<br>Santa Maria, CA 93456<br>Phone: (805) 922-5221<br>FAX: (805) 880-0402 | Job     | 9914267-011            | Page        | 1 of 11           |
|                                                                                                                                                 | Project | 30-ft Light Duty Tower | Date        | 16:20:09 01/21/14 |
|                                                                                                                                                 | Client  | Lea County, New Mexico | Designed by | Simon Leland      |

## Tower Input Data

The main tower is a 3x free standing tower with an overall height of 30.00 ft above the ground line.

The base of the tower is set at an elevation of 0.00 ft above the ground line.

The face width of the tower is 1.50 ft at the top and 1.50 ft at the base.

This tower is designed using the TIA-222-G standard.

The following design criteria apply:

Basic wind speed of 90 mph.

Structure Class II.

Exposure Category C.

Topographic Category 1.

Crest Height 0.00 ft.

Nominal ice thickness of 0.2500 in.

Ice thickness is considered to increase with height.

Ice density of 56 pcf.

A wind speed of 30 mph is used in combination with ice.


Deflections calculated using a wind speed of 60 mph.

A non-linear (P-delta) analysis was used.

Pressures are calculated at each section.

Stress ratio used in tower member design is 1.

Local bending stresses due to climbing loads, feed line supports, and appurtenance mounts are not considered.



Triangular Tower

|                                                                                                                                                 |         |                        |             |                   |
|-------------------------------------------------------------------------------------------------------------------------------------------------|---------|------------------------|-------------|-------------------|
| <b>tnxTower</b><br><br><b>DaVinci Engineering, Inc.</b><br>PO Box 1966<br>Santa Maria, CA 93456<br>Phone: (805) 922-5221<br>FAX: (805) 880-0402 | Job     | 9914267-011            | Page        | 2 of 11           |
|                                                                                                                                                 | Project | 30-ft Light Duty Tower | Date        | 16:20:09 01/21/14 |
|                                                                                                                                                 | Client  | Lea County, New Mexico | Designed by | Simon Leland      |

### Tower Section Geometry

| Tower Section | Tower Elevation | Assembly Database | Description | Section Width | Number of Sections | Section Length |
|---------------|-----------------|-------------------|-------------|---------------|--------------------|----------------|
|               | ft              |                   |             | ft            |                    | ft             |
| T1-T3         | 30.00-0.00      |                   |             | 1.50          | 3                  | 10.00          |

### Tower Section Geometry (cont'd)

| Tower Section | Tower Elevation | Diagonal Spacing | Bracing Type | Has K Brace End Panels | Has Horizontals | Top Girt Offset | Bottom Girt Offset |
|---------------|-----------------|------------------|--------------|------------------------|-----------------|-----------------|--------------------|
|               | ft              | ft               |              |                        |                 | in              | in                 |
| T1-T3         | 30.00-0.00      | 1.33             | Z Brace      | No                     | Yes             | 4.0000          | 4.0000             |

### Tower Section Geometry (cont'd)

| Tower Elevation     | Leg Type    | Leg Size | Leg Grade           | Diagonal Type | Diagonal Size | Diagonal Grade  |
|---------------------|-------------|----------|---------------------|---------------|---------------|-----------------|
| ft                  |             |          |                     |               |               |                 |
| T1-T3<br>30.00-0.00 | Solid Round | 1        | A572-50<br>(50 ksi) | Solid Round   | 1/2           | A36<br>(36 ksi) |

### Tower Section Geometry (cont'd)

| Tower Elevation     | Top Girt Type | Top Girt Size | Top Girt Grade  | Bottom Girt Type | Bottom Girt Size | Bottom Girt Grade |
|---------------------|---------------|---------------|-----------------|------------------|------------------|-------------------|
| ft                  |               |               |                 |                  |                  |                   |
| T1-T3<br>30.00-0.00 | Solid Round   | 1/2           | A36<br>(36 ksi) | Solid Round      | 1/2              | A36<br>(36 ksi)   |

### Tower Section Geometry (cont'd)

| Tower Elevation     | No. of Mid Girts | Mid Girt Type | Mid Girt Size | Mid Girt Grade  | Horizontal Type | Horizontal Size | Horizontal Grade |
|---------------------|------------------|---------------|---------------|-----------------|-----------------|-----------------|------------------|
| ft                  |                  |               |               |                 |                 |                 |                  |
| T1-T3<br>30.00-0.00 | None             | Solid Round   |               | A36<br>(36 ksi) | Solid Round     | 1/2             | A36<br>(36 ksi)  |

### Tower Section Geometry (cont'd)

| Tower Elevation     | Gusset Area (per face) | Gusset Thickness | Gusset Grade    | Adjust. Factor $A_f$ | Adjust. Factor $A_r$ | Weight Mult. | Double Angle Stitch Bolt Spacing Diagonals | Double Angle Stitch Bolt Spacing Horizontals |
|---------------------|------------------------|------------------|-----------------|----------------------|----------------------|--------------|--------------------------------------------|----------------------------------------------|
| ft                  | ft <sup>2</sup>        | in               |                 |                      |                      |              | in                                         | in                                           |
| T1-T3<br>30.00-0.00 | 0.00                   | 0.0000           | A36<br>(36 ksi) | 1                    | 1                    | 1            | 36.0000                                    | 36.0000                                      |

|                                                                                                                                                 |         |                        |                             |
|-------------------------------------------------------------------------------------------------------------------------------------------------|---------|------------------------|-----------------------------|
| <b>tnxTower</b><br><br><b>DaVinci Engineering, Inc.</b><br>PO Box 1966<br>Santa Maria, CA 93456<br>Phone: (805) 922-5221<br>FAX: (805) 880-0402 | Job     | 9914267-011            | Page<br>3 of 11             |
|                                                                                                                                                 | Project | 30-ft Light Duty Tower | Date<br>16:20:09 01/21/14   |
|                                                                                                                                                 | Client  | Lea County, New Mexico | Designed by<br>Simon Leland |

### Tower Section Geometry (cont'd)

| Tower<br>Elevation<br>ft | Leg<br>Connection<br>Type | Leg             |     | Diagonal        |     | Top Girt        |     | Bottom Girt     |     | Mid Girt        |     | Long Horizontal |     | Short Horizontal |     |
|--------------------------|---------------------------|-----------------|-----|-----------------|-----|-----------------|-----|-----------------|-----|-----------------|-----|-----------------|-----|------------------|-----|
|                          |                           | Bolt Size<br>in | No. | Bolt Size<br>in | No. | Bolt Size<br>in | No. | Bolt Size<br>in | No. | Bolt Size<br>in | No. | Bolt Size<br>in | No. | Bolt Size<br>in  | No. |
| T1-T3<br>30.00-0.00      | Flange                    | 0.7500<br>A325N | 1   | 0.6250<br>A325N | 0   | 0.6250<br>A325N | 0   | 0.6250<br>A325N | 0   | 0.6250<br>A325N | 0   | 0.6250<br>A325N | 0   | 0.6250<br>A325N  | 0   |

### Feed Line/Linear Appurtenances - Entered As Round Or Flat

| Description            | Face<br>or<br>Leg | Allow<br>Shield | Component<br>Type | Placement<br>ft | Face<br>Offset<br>in | Lateral<br>Offset<br>(Frac FW) | # | #<br>Per<br>Row | Clear<br>Spacing<br>in | Width or<br>Diameter<br>in | Perimeter<br>in | Weight<br>plf |
|------------------------|-------------------|-----------------|-------------------|-----------------|----------------------|--------------------------------|---|-----------------|------------------------|----------------------------|-----------------|---------------|
| LDF5-50A<br>(7/8 FOAM) | C                 | No              | Ar (CaAa)         | 25.00 - 3.00    | -3.0000              | 0.25                           | 4 | 2               | 1.0900                 | 1.0900                     |                 | 0.33          |
| LDF5-50A<br>(7/8 FOAM) | C                 | No              | Ar (CaAa)         | 30.00 - 25.00   | -1.5000              | 0.25                           | 3 | 2               | 1.0900                 | 1.0900                     |                 | 0.33          |

### Feed Line/Linear Appurtenances Section Areas

| Tower<br>Section | Tower<br>Elevation<br>ft | Face | A <sub>R</sub><br>ft <sup>2</sup> | A <sub>F</sub><br>ft <sup>2</sup> | C <sub>A</sub> A <sub>A</sub><br>In Face<br>ft <sup>2</sup> | C <sub>A</sub> A <sub>A</sub><br>Out Face<br>ft <sup>2</sup> | Weight<br>lb |
|------------------|--------------------------|------|-----------------------------------|-----------------------------------|-------------------------------------------------------------|--------------------------------------------------------------|--------------|
| T1               | 30.00-20.00              | A    | 0.000                             | 0.000                             | 0.000                                                       | 0.000                                                        | 0.00         |
|                  |                          | B    | 0.000                             | 0.000                             | 0.000                                                       | 0.000                                                        | 0.00         |
|                  |                          | C    | 0.000                             | 0.000                             | 3.815                                                       | 0.000                                                        | 11.55        |
| T2               | 20.00-10.00              | A    | 0.000                             | 0.000                             | 0.000                                                       | 0.000                                                        | 0.00         |
|                  |                          | B    | 0.000                             | 0.000                             | 0.000                                                       | 0.000                                                        | 0.00         |
|                  |                          | C    | 0.000                             | 0.000                             | 4.360                                                       | 0.000                                                        | 13.20        |
| T3               | 10.00-0.00               | A    | 0.000                             | 0.000                             | 0.000                                                       | 0.000                                                        | 0.00         |
|                  |                          | B    | 0.000                             | 0.000                             | 0.000                                                       | 0.000                                                        | 0.00         |
|                  |                          | C    | 0.000                             | 0.000                             | 3.052                                                       | 0.000                                                        | 9.24         |

### Shielding Factor Ka

| Tower<br>Section | Feed Line<br>Record No. | Description         | Feed Line<br>Segment Elev. | K <sub>a</sub><br>No Ice | K <sub>a</sub><br>Ice |
|------------------|-------------------------|---------------------|----------------------------|--------------------------|-----------------------|
| T1               | 1                       | LDF5-50A (7/8 FOAM) | 20.00 - 25.00              | 0.6000                   | 0.6000                |
| T1               | 2                       | LDF5-50A (7/8 FOAM) | 25.00 - 30.00              | 0.6000                   | 0.6000                |
| T2               | 1                       | LDF5-50A (7/8 FOAM) | 10.00 - 20.00              | 0.6000                   | 0.6000                |
| T3               | 1                       | LDF5-50A (7/8 FOAM) | 3.00 - 10.00               | 0.6000                   | 0.6000                |

### User Defined Loads

| Description     | Elevation<br>ft | Offset<br>From<br>Centroid<br>ft | Azimuth<br>Angle<br>° | Weight<br>lb | F <sub>x</sub><br>lb | F <sub>z</sub><br>lb | Wind Force<br>lb | C <sub>A</sub> A <sub>c</sub><br>ft <sup>2</sup> |
|-----------------|-----------------|----------------------------------|-----------------------|--------------|----------------------|----------------------|------------------|--------------------------------------------------|
| 5000# Fall Load | 50.00           | 0.00                             | 0.0000                | No Ice       | 0.00                 | 0.00                 | 0.00             | 0.00                                             |
|                 |                 |                                  |                       | Ice          | 5000.00              | 0.00                 | 0.00             | 0.00                                             |
|                 |                 |                                  |                       | Service      | 5000.00              | 0.00                 | 0.00             | 0.00                                             |

|                                                                                                                                                 |         |                        |             |                   |
|-------------------------------------------------------------------------------------------------------------------------------------------------|---------|------------------------|-------------|-------------------|
| <b>tnxTower</b><br><br><b>DaVinci Engineering, Inc.</b><br>PO Box 1966<br>Santa Maria, CA 93456<br>Phone: (805) 922-5221<br>FAX: (805) 880-0402 | Job     | 9914267-011            | Page        | 4 of 11           |
|                                                                                                                                                 | Project | 30-ft Light Duty Tower | Date        | 16:20:09 01/21/14 |
|                                                                                                                                                 | Client  | Lea County, New Mexico | Designed by | Simon Leland      |

### Discrete Tower Loads

| Description                   | Face<br>or<br>Leg | Offset<br>Type | Offsets:<br>Horz<br>Lateral<br>Vert<br>ft | Azimuth<br>Adjustment<br>° | Placement<br>ft | C <sub>AA</sub><br>Front | C <sub>AA</sub><br>Side | Weight<br>lb   |
|-------------------------------|-------------------|----------------|-------------------------------------------|----------------------------|-----------------|--------------------------|-------------------------|----------------|
| 12ft x 2.5" dia. Whip Antenna | A                 | From Leg       | 0.50                                      | 0.0000                     | 30.00           | No Ice<br>1/2" Ice       | 3.34<br>4.70            | 23.30<br>51.07 |
| 12ft x 2.5" dia. Whip Antenna | A                 | From Leg       | 0.50                                      | 0.0000                     | 25.00           | No Ice<br>1/2" Ice       | 3.34<br>4.70            | 23.30<br>51.07 |

### Dishes

| Description        | Face<br>or<br>Leg | Dish<br>Type           | Offset<br>Type | Offsets:<br>Horz<br>Lateral<br>Vert<br>ft | Azimuth<br>Adjustment<br>° | 3 dB<br>Beam<br>Width<br>° | Elevation<br>ft | Outside<br>Diameter<br>ft | Aperture<br>Area<br>ft <sup>2</sup> | Weight<br>lb    |
|--------------------|-------------------|------------------------|----------------|-------------------------------------------|----------------------------|----------------------------|-----------------|---------------------------|-------------------------------------|-----------------|
| Andrew 2' w/Radome | B                 | Paraboloid<br>w/Radome | From<br>Leg    | 0.50<br>0.50<br>0.00                      | 0.0000                     |                            | 30.00           | 2.00                      | No Ice<br>1/2" Ice                  | 70.00<br>282.00 |
| Andrew 2' w/Radome | C                 | Paraboloid<br>w/Radome | From<br>Leg    | 0.50<br>0.50<br>0.00                      | 0.0000                     |                            | 30.00           | 2.00                      | No Ice<br>1/2" Ice                  | 70.00<br>282.00 |

### Discrete Appurtenance Pressures - No Ice $G_H = 0.850$

| Description                   | Aiming<br>Azimuth<br>° | Weight<br>lb | Offset <sub>x</sub><br>ft | Offset <sub>z</sub><br>ft | z<br>ft | K <sub>z</sub> | q <sub>z</sub><br>psf | C <sub>AAc</sub><br>Front<br>ft <sup>2</sup> | C <sub>AAc</sub><br>Side<br>ft <sup>2</sup> |
|-------------------------------|------------------------|--------------|---------------------------|---------------------------|---------|----------------|-----------------------|----------------------------------------------|---------------------------------------------|
| 12ft x 2.5" dia. Whip Antenna | 0.0000                 | 23.30        | 0.00                      | -1.37                     | 30.00   | 0.982          | 17                    | 3.34                                         | 3.34                                        |
| 12ft x 2.5" dia. Whip Antenna | 0.0000                 | 23.30        | 0.00                      | -1.37                     | 25.00   | 0.945          | 17                    | 3.34                                         | 3.34                                        |
| Sum Weight:                   |                        | 46.60        |                           |                           |         |                |                       |                                              |                                             |

### Dish Pressures - No Ice

| Elevation<br>ft | Dish<br>Description | Aiming<br>Azimuth<br>° | Weight<br>lb | Offset <sub>x</sub><br>ft | Offset <sub>z</sub><br>ft | K <sub>z</sub> | A <sub>A</sub><br>ft <sup>2</sup> | q <sub>z</sub><br>psf |
|-----------------|---------------------|------------------------|--------------|---------------------------|---------------------------|----------------|-----------------------------------|-----------------------|
| 30.00           | Andrew 2' w/Radome  | 120.0000               | 70.00        | 1.18                      | 0.68                      | 0.982          | 3.14                              | 17                    |
| 30.00           | Andrew 2' w/Radome  | 240.0000               | 70.00        | -1.18                     | 0.68                      | 0.982          | 3.14                              | 17                    |
|                 | Sum Weight:         |                        | 140.00       |                           |                           |                |                                   |                       |

|                                                                                                                                                 |         |                        |             |                   |
|-------------------------------------------------------------------------------------------------------------------------------------------------|---------|------------------------|-------------|-------------------|
| <b>tnxTower</b><br><br><b>DaVinci Engineering, Inc.</b><br>PO Box 1966<br>Santa Maria, CA 93456<br>Phone: (805) 922-5221<br>FAX: (805) 880-0402 | Job     | 9914267-011            | Page        | 5 of 11           |
|                                                                                                                                                 | Project | 30-ft Light Duty Tower | Date        | 16:20:09 01/21/14 |
|                                                                                                                                                 | Client  | Lea County, New Mexico | Designed by | Simon Leland      |

## Load Combinations

| Comb.<br>No. | Description                        |
|--------------|------------------------------------|
| 1            | Dead Only                          |
| 2            | 1.2 Dead+1.6 Wind 0 deg - No Ice   |
| 3            | 0.9 Dead+1.6 Wind 0 deg - No Ice   |
| 4            | 1.2 Dead+1.6 Wind 30 deg - No Ice  |
| 5            | 0.9 Dead+1.6 Wind 30 deg - No Ice  |
| 6            | 1.2 Dead+1.6 Wind 60 deg - No Ice  |
| 7            | 0.9 Dead+1.6 Wind 60 deg - No Ice  |
| 8            | 1.2 Dead+1.6 Wind 90 deg - No Ice  |
| 9            | 0.9 Dead+1.6 Wind 90 deg - No Ice  |
| 10           | 1.2 Dead+1.6 Wind 120 deg - No Ice |
| 11           | 0.9 Dead+1.6 Wind 120 deg - No Ice |
| 12           | 1.2 Dead+1.6 Wind 150 deg - No Ice |
| 13           | 0.9 Dead+1.6 Wind 150 deg - No Ice |
| 14           | 1.2 Dead+1.6 Wind 180 deg - No Ice |
| 15           | 0.9 Dead+1.6 Wind 180 deg - No Ice |
| 16           | 1.2 Dead+1.6 Wind 210 deg - No Ice |
| 17           | 0.9 Dead+1.6 Wind 210 deg - No Ice |
| 18           | 1.2 Dead+1.6 Wind 240 deg - No Ice |
| 19           | 0.9 Dead+1.6 Wind 240 deg - No Ice |
| 20           | 1.2 Dead+1.6 Wind 270 deg - No Ice |
| 21           | 0.9 Dead+1.6 Wind 270 deg - No Ice |
| 22           | 1.2 Dead+1.6 Wind 300 deg - No Ice |
| 23           | 0.9 Dead+1.6 Wind 300 deg - No Ice |
| 24           | 1.2 Dead+1.6 Wind 330 deg - No Ice |
| 25           | 0.9 Dead+1.6 Wind 330 deg - No Ice |
| 26           | 1.2 Dead+1.0 Ice                   |
| 27           | 1.2 Dead+1.0 Wind 0 deg+1.0 Ice    |
| 28           | 1.2 Dead+1.0 Wind 30 deg+1.0 Ice   |
| 29           | 1.2 Dead+1.0 Wind 60 deg+1.0 Ice   |
| 30           | 1.2 Dead+1.0 Wind 90 deg+1.0 Ice   |
| 31           | 1.2 Dead+1.0 Wind 120 deg+1.0 Ice  |
| 32           | 1.2 Dead+1.0 Wind 150 deg+1.0 Ice  |
| 33           | 1.2 Dead+1.0 Wind 180 deg+1.0 Ice  |
| 34           | 1.2 Dead+1.0 Wind 210 deg+1.0 Ice  |
| 35           | 1.2 Dead+1.0 Wind 240 deg+1.0 Ice  |
| 36           | 1.2 Dead+1.0 Wind 270 deg+1.0 Ice  |
| 37           | 1.2 Dead+1.0 Wind 300 deg+1.0 Ice  |
| 38           | 1.2 Dead+1.0 Wind 330 deg+1.0 Ice  |
| 39           | Dead+Wind 0 deg - Service          |
| 40           | Dead+Wind 30 deg - Service         |
| 41           | Dead+Wind 60 deg - Service         |
| 42           | Dead+Wind 90 deg - Service         |
| 43           | Dead+Wind 120 deg - Service        |
| 44           | Dead+Wind 150 deg - Service        |
| 45           | Dead+Wind 180 deg - Service        |
| 46           | Dead+Wind 210 deg - Service        |
| 47           | Dead+Wind 240 deg - Service        |
| 48           | Dead+Wind 270 deg - Service        |
| 49           | Dead+Wind 300 deg - Service        |
| 50           | Dead+Wind 330 deg - Service        |

|                                                                                                                                                 |         |                        |                             |
|-------------------------------------------------------------------------------------------------------------------------------------------------|---------|------------------------|-----------------------------|
| <b>tnxTower</b><br><br><b>DaVinci Engineering, Inc.</b><br>PO Box 1966<br>Santa Maria, CA 93456<br>Phone: (805) 922-5221<br>FAX: (805) 880-0402 | Job     | 9914267-011            | Page<br>6 of 11             |
|                                                                                                                                                 | Project | 30-ft Light Duty Tower | Date<br>16:20:09 01/21/14   |
|                                                                                                                                                 | Client  | Lea County, New Mexico | Designed by<br>Simon Leland |

### Maximum Reactions

| Location | Condition           | Gov.<br>Load<br>Comb. | Vertical<br>lb | Horizontal, X<br>lb | Horizontal, Z<br>lb |
|----------|---------------------|-----------------------|----------------|---------------------|---------------------|
| Leg C    | Max. Vert           | 18                    | 10768.40       | 134.62              | -123.19             |
|          | Max. H <sub>x</sub> | 21                    | 9452.26        | 167.49              | -40.24              |
|          | Max. H <sub>z</sub> | 4                     | -8573.09       | -108.95             | 258.59              |
|          | Min. Vert           | 7                     | -10074.48      | -201.14             | 183.85              |
|          | Min. H <sub>x</sub> | 8                     | -8935.86       | -236.86             | 53.90               |
|          | Min. H <sub>z</sub> | 15                    | 4968.00        | -4.87               | -188.64             |
| Leg B    | Max. Vert           | 10                    | 10691.46       | -137.04             | -123.88             |
|          | Max. H <sub>x</sub> | 20                    | -9012.30       | 232.85              | 53.58               |
|          | Max. H <sub>z</sub> | 24                    | -8650.09       | 131.09              | 232.95              |
|          | Min. Vert           | 23                    | -10131.87      | 213.76              | 167.35              |
|          | Min. H <sub>x</sub> | 9                     | 9394.53        | -158.06             | -54.45              |
|          | Min. H <sub>z</sub> | 15                    | 4910.40        | -13.42              | -177.22             |
| Leg A    | Max. Vert           | 2                     | 10589.11       | -24.14              | 179.66              |
|          | Max. H <sub>x</sub> | 20                    | 214.21         | 266.61              | -13.22              |
|          | Max. H <sub>z</sub> | 3                     | 10524.42       | -24.07              | 179.72              |
|          | Min. Vert           | 15                    | -9322.42       | 18.29               | -250.31             |
|          | Min. H <sub>x</sub> | 9                     | 162.46         | -271.99             | 0.70                |
|          | Min. H <sub>z</sub> | 14                    | -9281.26       | 18.37               | -250.45             |

### Tower Mast Reaction Summary

| Load<br>Combination                | Vertical<br>lb | Shear <sub>x</sub><br>lb | Shear <sub>z</sub><br>lb | Overturning<br>Moment, M <sub>x</sub><br>lb-ft | Overturning<br>Moment, M <sub>z</sub><br>lb-ft | Torque<br>lb-ft |
|------------------------------------|----------------|--------------------------|--------------------------|------------------------------------------------|------------------------------------------------|-----------------|
| Dead Only                          | 617.75         | 0.00                     | 0.00                     | 40.35                                          | 47.75                                          | 0.00            |
| 1.2 Dead+1.6 Wind 0 deg - No Ice   | 741.31         | -0.00                    | -654.46                  | -13434.66                                      | 57.94                                          | -51.18          |
| 0.9 Dead+1.6 Wind 0 deg - No Ice   | 555.98         | -0.00                    | -654.46                  | -13430.87                                      | 43.43                                          | -51.12          |
| 1.2 Dead+1.6 Wind 30 deg - No Ice  | 741.31         | 319.89                   | -569.91                  | -11722.96                                      | -6462.03                                       | -111.30         |
| 0.9 Dead+1.6 Wind 30 deg - No Ice  | 555.98         | 319.89                   | -569.91                  | -11721.15                                      | -6468.86                                       | -111.27         |
| 1.2 Dead+1.6 Wind 60 deg - No Ice  | 741.31         | 563.20                   | -327.87                  | -6713.09                                       | -11510.69                                      | -148.62         |
| 0.9 Dead+1.6 Wind 60 deg - No Ice  | 555.98         | 563.20                   | -327.87                  | -6717.22                                       | -11511.53                                      | -148.65         |
| 1.2 Dead+1.6 Wind 90 deg - No Ice  | 741.31         | 666.84                   | -0.20                    | 41.85                                          | -13798.61                                      | -145.80         |
| 0.9 Dead+1.6 Wind 90 deg - No Ice  | 555.98         | 666.84                   | -0.20                    | 29.71                                          | -13796.66                                      | -145.88         |
| 1.2 Dead+1.6 Wind 120 deg - No Ice | 741.31         | 574.08                   | 321.89                   | 6628.70                                        | -11839.46                                      | -100.43         |
| 0.9 Dead+1.6 Wind 120 deg - No Ice | 555.98         | 574.08                   | 321.89                   | 6608.73                                        | -11839.82                                      | -100.54         |
| 1.2 Dead+1.6 Wind 150 deg - No Ice | 741.31         | 326.44                   | 542.38                   | 10989.72                                       | -6660.33                                       | -38.60          |
| 0.9 Dead+1.6 Wind 150 deg - No Ice | 555.98         | 326.44                   | 542.38                   | 10964.59                                       | -6666.84                                       | -38.71          |
| 1.2 Dead+1.6 Wind 180 deg - No Ice | 741.31         | -0.00                    | 616.18                   | 12377.70                                       | 57.65                                          | 32.41           |
| 0.9 Dead+1.6 Wind 180 deg - No Ice | 555.98         | -0.00                    | 616.18                   | 12350.93                                       | 43.19                                          | 32.33           |
| 1.2 Dead+1.6 Wind 210 deg - No Ice | 741.31         | -326.44                  | 542.38                   | 10989.98                                       | 6775.54                                        | 102.31          |

|                                                                                                                                                 |         |                        |             |                   |
|-------------------------------------------------------------------------------------------------------------------------------------------------|---------|------------------------|-------------|-------------------|
| <b>tnxTower</b><br><br><b>DaVinci Engineering, Inc.</b><br>PO Box 1966<br>Santa Maria, CA 93456<br>Phone: (805) 922-5221<br>FAX: (805) 880-0402 | Job     | 9914267-011            | Page        | 7 of 11           |
|                                                                                                                                                 | Project | 30-ft Light Duty Tower | Date        | 16:20:09 01/21/14 |
|                                                                                                                                                 | Client  | Lea County, New Mexico | Designed by | Simon Leland      |

| Load Combination                   | Vertical<br>lb | Shear <sub>x</sub><br>lb | Shear <sub>y</sub><br>lb | Overturning<br>Moment, M <sub>x</sub><br>lb-ft | Overturning<br>Moment, M <sub>y</sub><br>lb-ft | Torque<br>lb-ft |
|------------------------------------|----------------|--------------------------|--------------------------|------------------------------------------------|------------------------------------------------|-----------------|
| 0.9 Dead+1.6 Wind 210 deg - No Ice | 555.98         | -326.44                  | 542.38                   | 10964.75                                       | 6753.16                                        | 102.28          |
| 1.2 Dead+1.6 Wind 240 deg - No Ice | 741.31         | -574.08                  | 321.88                   | 6629.26                                        | 11954.54                                       | 140.92          |
| 0.9 Dead+1.6 Wind 240 deg - No Ice | 555.98         | -574.08                  | 321.88                   | 6609.10                                        | 11926.00                                       | 140.95          |
| 1.2 Dead+1.6 Wind 270 deg - No Ice | 741.31         | -666.84                  | -0.20                    | 42.73                                          | 13913.76                                       | 127.89          |
| 0.9 Dead+1.6 Wind 270 deg - No Ice | 555.98         | -666.84                  | -0.20                    | 30.38                                          | 13882.86                                       | 127.97          |
| 1.2 Dead+1.6 Wind 300 deg - No Ice | 741.31         | -563.20                  | -327.87                  | -6712.22                                       | 11626.17                                       | 76.63           |
| 0.9 Dead+1.6 Wind 300 deg - No Ice | 555.98         | -563.20                  | -327.87                  | -6716.50                                       | 11598.01                                       | 76.74           |
| 1.2 Dead+1.6 Wind 330 deg - No Ice | 741.31         | -319.89                  | -569.91                  | -11722.47                                      | 6577.82                                        | 10.01           |
| 0.9 Dead+1.6 Wind 330 deg - No Ice | 555.98         | -319.89                  | -569.91                  | -11720.74                                      | 6555.63                                        | 10.12           |
| 1.2 Dead+1.0 Ice                   | 6502.00        | -0.00                    | -0.00                    | -316.34                                        | 213.84                                         | -0.00           |
| 1.2 Dead+1.0 Wind 0 deg+1.0 Ice    | 6502.00        | 0.00                     | -75.93                   | -1268.42                                       | 213.61                                         | -4.62           |
| 1.2 Dead+1.0 Wind 30 deg+1.0 Ice   | 6502.00        | 37.41                    | -65.99                   | -1063.42                                       | -560.89                                        | -11.03          |
| 1.2 Dead+1.0 Wind 60 deg+1.0 Ice   | 6502.00        | 65.49                    | -38.01                   | -476.38                                        | -1150.03                                       | -15.04          |
| 1.2 Dead+1.0 Wind 90 deg+1.0 Ice   | 6502.00        | 76.86                    | -0.01                    | 316.36                                         | -1400.66                                       | -14.94          |
| 1.2 Dead+1.0 Wind 120 deg+1.0 Ice  | 6502.00        | 66.31                    | 37.56                    | 1095.87                                        | -1175.80                                       | -10.62          |
| 1.2 Dead+1.0 Wind 150 deg+1.0 Ice  | 6502.00        | 37.90                    | 63.92                    | 1629.29                                        | -575.63                                        | -4.23           |
| 1.2 Dead+1.0 Wind 180 deg+1.0 Ice  | 6502.00        | -0.00                    | 73.04                    | 1807.15                                        | 215.09                                         | 3.20            |
| 1.2 Dead+1.0 Wind 210 deg+1.0 Ice  | 6502.00        | -37.90                   | 63.92                    | 1628.69                                        | 1005.12                                        | 10.34           |
| 1.2 Dead+1.0 Wind 240 deg+1.0 Ice  | 6502.00        | -66.31                   | 37.56                    | 1095.21                                        | 1604.30                                        | 14.46           |
| 1.2 Dead+1.0 Wind 270 deg+1.0 Ice  | 6502.00        | -76.86                   | -0.02                    | 315.13                                         | 1828.72                                        | 13.59           |
| 1.2 Dead+1.0 Wind 300 deg+1.0 Ice  | 6502.00        | -65.49                   | -38.01                   | -478.22                                        | 1577.03                                        | 8.81            |
| 1.2 Dead+1.0 Wind 330 deg+1.0 Ice  | 6502.00        | -37.41                   | -65.99                   | -1064.49                                       | 987.33                                         | 2.07            |
| Dead+Wind 0 deg - Service          | 617.75         | -0.00                    | -181.79                  | -3701.87                                       | 48.02                                          | -14.21          |
| Dead+Wind 30 deg - Service         | 617.75         | 88.86                    | -158.31                  | -3226.73                                       | -1761.71                                       | -30.91          |
| Dead+Wind 60 deg - Service         | 617.75         | 156.44                   | -91.08                   | -1836.13                                       | -3162.99                                       | -41.29          |
| Dead+Wind 90 deg - Service         | 617.75         | 185.23                   | -0.06                    | 38.79                                          | -3797.96                                       | -40.52          |
| Dead+Wind 120 deg - Service        | 617.75         | 159.47                   | 89.41                    | 1867.00                                        | -3254.15                                       | -27.93          |
| Dead+Wind 150 deg - Service        | 617.75         | 90.68                    | 150.66                   | 3077.41                                        | -1816.64                                       | -10.74          |
| Dead+Wind 180 deg - Service        | 617.75         | -0.00                    | 171.16                   | 3462.64                                        | 47.97                                          | 8.98            |
| Dead+Wind 210 deg - Service        | 617.75         | -90.68                   | 150.66                   | 3077.47                                        | 1912.56                                        | 28.42           |
| Dead+Wind 240 deg - Service        | 617.75         | -159.47                  | 89.41                    | 1867.15                                        | 3350.07                                        | 39.16           |
| Dead+Wind 270 deg - Service        | 617.75         | -185.23                  | -0.06                    | 38.98                                          | 3893.92                                        | 35.55           |
| Dead+Wind 300 deg - Service        | 617.75         | -156.44                  | -91.08                   | -1835.96                                       | 3259.00                                        | 21.31           |
| Dead+Wind 330 deg - Service        | 617.75         | -88.86                   | -158.31                  | -3226.63                                       | 1857.74                                        | 2.80            |

|                                                                                                                                                 |         |                        |                             |
|-------------------------------------------------------------------------------------------------------------------------------------------------|---------|------------------------|-----------------------------|
| <b>tnxTower</b><br><br><b>DaVinci Engineering, Inc.</b><br>PO Box 1966<br>Santa Maria, CA 93456<br>Phone: (805) 922-5221<br>FAX: (805) 880-0402 | Job     | 9914267-011            | Page<br>8 of 11             |
|                                                                                                                                                 | Project | 30-ft Light Duty Tower | Date<br>16:20:09 01/21/14   |
|                                                                                                                                                 | Client  | Lea County, New Mexico | Designed by<br>Simon Leland |

## Solution Summary

| Load<br>Comb. | Sum of Applied Forces |          |          | Sum of Reactions |          |          | % Error |
|---------------|-----------------------|----------|----------|------------------|----------|----------|---------|
|               | PX<br>lb              | PY<br>lb | PZ<br>lb | PX<br>lb         | PY<br>lb | PZ<br>lb |         |
| 1             | 0.00                  | -617.75  | 0.00     | 0.00             | 617.75   | 0.00     | 0.000%  |
| 2             | -0.00                 | -741.31  | -654.46  | 0.00             | 741.31   | 654.46   | 0.000%  |
| 3             | -0.00                 | -555.98  | -654.46  | 0.00             | 555.98   | 654.46   | 0.000%  |
| 4             | 319.89                | -741.31  | -569.91  | -319.89          | 741.31   | 569.91   | 0.000%  |
| 5             | 319.89                | -555.98  | -569.91  | -319.89          | 555.98   | 569.91   | 0.000%  |
| 6             | 563.20                | -741.31  | -327.87  | -563.20          | 741.31   | 327.87   | 0.000%  |
| 7             | 563.20                | -555.98  | -327.87  | -563.20          | 555.98   | 327.87   | 0.000%  |
| 8             | 666.84                | -741.31  | -0.20    | -666.84          | 741.31   | 0.20     | 0.000%  |
| 9             | 666.84                | -555.98  | -0.20    | -666.84          | 555.98   | 0.20     | 0.000%  |
| 10            | 574.08                | -741.31  | 321.89   | -574.08          | 741.31   | -321.89  | 0.000%  |
| 11            | 574.08                | -555.98  | 321.89   | -574.08          | 555.98   | -321.89  | 0.000%  |
| 12            | 326.44                | -741.31  | 542.38   | -326.44          | 741.31   | -542.38  | 0.000%  |
| 13            | 326.44                | -555.98  | 542.38   | -326.44          | 555.98   | -542.38  | 0.000%  |
| 14            | 0.00                  | -741.31  | 616.18   | 0.00             | 741.31   | -616.18  | 0.000%  |
| 15            | 0.00                  | -555.98  | 616.18   | 0.00             | 555.98   | -616.18  | 0.000%  |
| 16            | -326.44               | -741.31  | 542.38   | 326.44           | 741.31   | -542.38  | 0.000%  |
| 17            | -326.44               | -555.98  | 542.38   | 326.44           | 555.98   | -542.38  | 0.000%  |
| 18            | -574.08               | -741.31  | 321.89   | 574.08           | 741.31   | -321.88  | 0.000%  |
| 19            | -574.08               | -555.98  | 321.89   | 574.08           | 555.98   | -321.88  | 0.000%  |
| 20            | -666.84               | -741.31  | -0.20    | 666.84           | 741.31   | 0.20     | 0.000%  |
| 21            | -666.84               | -555.98  | -0.20    | 666.84           | 555.98   | 0.20     | 0.000%  |
| 22            | -563.20               | -741.31  | -327.87  | 563.20           | 741.31   | 327.87   | 0.000%  |
| 23            | -563.20               | -555.98  | -327.87  | 563.20           | 555.98   | 327.87   | 0.000%  |
| 24            | -319.89               | -741.31  | -569.91  | 319.89           | 741.31   | 569.91   | 0.000%  |
| 25            | -319.89               | -555.98  | -569.91  | 319.89           | 555.98   | 569.91   | 0.000%  |
| 26            | 0.00                  | -6502.00 | 0.00     | 0.00             | 6502.00  | 0.00     | 0.000%  |
| 27            | -0.00                 | -6502.00 | -75.93   | -0.00            | 6502.00  | 75.93    | 0.000%  |
| 28            | 37.41                 | -6502.00 | -65.99   | -37.41           | 6502.00  | 65.99    | 0.000%  |
| 29            | 65.49                 | -6502.00 | -38.01   | -65.49           | 6502.00  | 38.01    | 0.000%  |
| 30            | 76.86                 | -6502.00 | -0.01    | -76.86           | 6502.00  | 0.01     | 0.000%  |
| 31            | 66.31                 | -6502.00 | 37.56    | -66.31           | 6502.00  | -37.56   | 0.000%  |
| 32            | 37.90                 | -6502.00 | 63.92    | -37.90           | 6502.00  | -63.92   | 0.000%  |
| 33            | 0.00                  | -6502.00 | 73.04    | 0.00             | 6502.00  | -73.04   | 0.000%  |
| 34            | -37.90                | -6502.00 | 63.92    | 37.90            | 6502.00  | -63.92   | 0.000%  |
| 35            | -66.31                | -6502.00 | 37.56    | 66.31            | 6502.00  | -37.56   | 0.000%  |
| 36            | -76.86                | -6502.00 | -0.01    | 76.86            | 6502.00  | 0.02     | 0.000%  |
| 37            | -65.49                | -6502.00 | -38.01   | 65.49            | 6502.00  | 38.01    | 0.000%  |
| 38            | -37.41                | -6502.00 | -65.99   | 37.41            | 6502.00  | 65.99    | 0.000%  |
| 39            | 0.00                  | -617.75  | -181.79  | 0.00             | 617.75   | 181.79   | 0.000%  |
| 40            | 88.86                 | -617.75  | -158.31  | -88.86           | 617.75   | 158.31   | 0.000%  |
| 41            | 156.44                | -617.75  | -91.08   | -156.44          | 617.75   | 91.08    | 0.000%  |
| 42            | 185.23                | -617.75  | -0.06    | -185.23          | 617.75   | 0.06     | 0.000%  |
| 43            | 159.47                | -617.75  | 89.41    | -159.47          | 617.75   | -89.41   | 0.000%  |
| 44            | 90.68                 | -617.75  | 150.66   | -90.68           | 617.75   | -150.66  | 0.000%  |
| 45            | -0.00                 | -617.75  | 171.16   | 0.00             | 617.75   | -171.16  | 0.000%  |
| 46            | -90.68                | -617.75  | 150.66   | 90.68            | 617.75   | -150.66  | 0.000%  |
| 47            | -159.47               | -617.75  | 89.41    | 159.47           | 617.75   | -89.41   | 0.000%  |
| 48            | -185.23               | -617.75  | -0.06    | 185.23           | 617.75   | 0.06     | 0.000%  |
| 49            | -156.44               | -617.75  | -91.08   | 156.44           | 617.75   | 91.08    | 0.000%  |
| 50            | -88.86                | -617.75  | -158.31  | 88.86            | 617.75   | 158.31   | 0.000%  |

|                                                                                                                                                 |         |                        |             |                   |
|-------------------------------------------------------------------------------------------------------------------------------------------------|---------|------------------------|-------------|-------------------|
| <b>tnxTower</b><br><br><b>DaVinci Engineering, Inc.</b><br>PO Box 1966<br>Santa Maria, CA 93456<br>Phone: (805) 922-5221<br>FAX: (805) 880-0402 | Job     | 9914267-011            | Page        | 9 of 11           |
|                                                                                                                                                 | Project | 30-ft Light Duty Tower | Date        | 16:20:09 01/21/14 |
|                                                                                                                                                 | Client  | Lea County, New Mexico | Designed by | Simon Leland      |

### Maximum Tower Deflections - Service Wind

| Section No. | Elevation<br>ft | Horz.<br>Deflection<br>in | Gov.<br>Load<br>Comb. | Tilt<br>° | Twist<br>° |
|-------------|-----------------|---------------------------|-----------------------|-----------|------------|
| T1          | 30 - 20         | 0.523                     | 48                    | 0.1098    | 0.1310     |
| T2          | 20 - 10         | 0.290                     | 48                    | 0.1011    | 0.0986     |
| T3          | 10 - 0          | 0.095                     | 48                    | 0.0675    | 0.0506     |

### Maximum Tower Deflections - Design Wind

| Section No. | Elevation<br>ft | Horz.<br>Deflection<br>in | Gov.<br>Load<br>Comb. | Tilt<br>° | Twist<br>° |
|-------------|-----------------|---------------------------|-----------------------|-----------|------------|
| T1          | 30 - 20         | 1.862                     | 20                    | 0.3891    | 0.4243     |
| T2          | 20 - 10         | 1.036                     | 20                    | 0.3595    | 0.3177     |
| T3          | 10 - 0          | 0.340                     | 20                    | 0.2407    | 0.1610     |

### Leg Design Data (Compression)

| Section No. | Elevation<br>ft | Size | L<br>ft | L <sub>u</sub><br>ft | KL/r           | A<br>in <sup>2</sup> | P <sub>u</sub><br>lb | φP <sub>n</sub><br>lb | Ratio<br>$\frac{P_u}{\phi P_n}$ |
|-------------|-----------------|------|---------|----------------------|----------------|----------------------|----------------------|-----------------------|---------------------------------|
| T1          | 30 - 20         | 1    | 10.00   | 1.33                 | 64.0<br>K=1.00 | 0.7854               | -2472.09             | 26196.10              | 0.094 <sup>1</sup>              |
| T2          | 20 - 10         | 1    | 10.00   | 1.33                 | 64.0<br>K=1.00 | 0.7854               | -6088.07             | 26196.10              | 0.232 <sup>1</sup>              |
| T3          | 10 - 0          | 1    | 10.00   | 1.33                 | 64.0<br>K=1.00 | 0.7854               | -10767.40            | 26196.10              | 0.411 <sup>1</sup>              |

<sup>1</sup> P<sub>u</sub> / φP<sub>n</sub> controls

### Diagonal Design Data (Compression)

| Section No. | Elevation<br>ft | Size | L<br>ft | L <sub>u</sub><br>ft | KL/r            | A<br>in <sup>2</sup> | P <sub>u</sub><br>lb | φP <sub>n</sub><br>lb | Ratio<br>$\frac{P_u}{\phi P_n}$ |
|-------------|-----------------|------|---------|----------------------|-----------------|----------------------|----------------------|-----------------------|---------------------------------|
| T1          | 30 - 20         | 1/2  | 2.01    | 2.01                 | 134.9<br>K=0.70 | 0.1963               | -595.88              | 2438.74               | 0.244 <sup>1</sup>              |
| T2          | 20 - 10         | 1/2  | 2.01    | 2.01                 | 134.9<br>K=0.70 | 0.1963               | -761.58              | 2438.74               | 0.312 <sup>1</sup>              |
| T3          | 10 - 0          | 1/2  | 2.01    | 2.01                 | 134.9<br>K=0.70 | 0.1963               | -920.27              | 2438.74               | 0.377 <sup>1</sup>              |

<sup>1</sup> P<sub>u</sub> / φP<sub>n</sub> controls

|                                                                                                                                                 |         |                        |             |                   |
|-------------------------------------------------------------------------------------------------------------------------------------------------|---------|------------------------|-------------|-------------------|
| <b>tnxTower</b><br><br><b>DaVinci Engineering, Inc.</b><br>PO Box 1966<br>Santa Maria, CA 93456<br>Phone: (805) 922-5221<br>FAX: (805) 880-0402 | Job     | 9914267-011            | Page        | 10 of 11          |
|                                                                                                                                                 | Project | 30-ft Light Duty Tower | Date        | 16:20:09 01/21/14 |
|                                                                                                                                                 | Client  | Lea County, New Mexico | Designed by | Simon Leland      |

### Horizontal Design Data (Compression)

| Section No. | Elevation<br>ft | Size | L<br>ft | L <sub>u</sub><br>ft | Kl/r            | A<br>in <sup>2</sup> | P <sub>u</sub><br>lb | φP <sub>n</sub><br>lb | Ratio<br>$\frac{P_u}{\phi P_n}$ |
|-------------|-----------------|------|---------|----------------------|-----------------|----------------------|----------------------|-----------------------|---------------------------------|
| T1          | 30 - 20         | 1/2  | 1.50    | 1.50                 | 100.8<br>K=0.70 | 0.1963               | -378.33              | 3726.24               | 0.102 <sup>1</sup><br>✓         |
| T2          | 20 - 10         | 1/2  | 1.50    | 1.50                 | 100.8<br>K=0.70 | 0.1963               | -474.17              | 3726.24               | 0.127 <sup>1</sup><br>✓         |
| T3          | 10 - 0          | 1/2  | 1.50    | 1.50                 | 100.8<br>K=0.70 | 0.1963               | -568.53              | 3726.24               | 0.153 <sup>1</sup><br>✓         |

<sup>1</sup> P<sub>u</sub> / φP<sub>n</sub> controls

### Top Girt Design Data (Compression)

| Section No. | Elevation<br>ft | Size | L<br>ft | L <sub>u</sub><br>ft | Kl/r            | A<br>in <sup>2</sup> | P <sub>u</sub><br>lb | φP <sub>n</sub><br>lb | Ratio<br>$\frac{P_u}{\phi P_n}$ |
|-------------|-----------------|------|---------|----------------------|-----------------|----------------------|----------------------|-----------------------|---------------------------------|
| T1          | 30 - 20         | 1/2  | 1.50    | 1.50                 | 100.8<br>K=0.70 | 0.1963               | -120.42              | 3726.24               | 0.032 <sup>1</sup><br>✓         |
| T2          | 20 - 10         | 1/2  | 1.50    | 1.50                 | 100.8<br>K=0.70 | 0.1963               | -279.78              | 3726.24               | 0.075 <sup>1</sup><br>✓         |
| T3          | 10 - 0          | 1/2  | 1.50    | 1.50                 | 100.8<br>K=0.70 | 0.1963               | -358.07              | 3726.24               | 0.096 <sup>1</sup><br>✓         |

<sup>1</sup> P<sub>u</sub> / φP<sub>n</sub> controls

### Bottom Girt Design Data (Compression)

| Section No. | Elevation<br>ft | Size | L<br>ft | L <sub>u</sub><br>ft | Kl/r            | A<br>in <sup>2</sup> | P <sub>u</sub><br>lb | φP <sub>n</sub><br>lb | Ratio<br>$\frac{P_u}{\phi P_n}$ |
|-------------|-----------------|------|---------|----------------------|-----------------|----------------------|----------------------|-----------------------|---------------------------------|
| T1          | 30 - 20         | 1/2  | 1.50    | 1.50                 | 100.8<br>K=0.70 | 0.1963               | -239.23              | 3726.24               | 0.064 <sup>1</sup><br>✓         |
| T2          | 20 - 10         | 1/2  | 1.50    | 1.50                 | 100.8<br>K=0.70 | 0.1963               | -294.32              | 3726.24               | 0.079 <sup>1</sup><br>✓         |
| T3          | 10 - 0          | 1/2  | 1.50    | 1.50                 | 100.8<br>K=0.70 | 0.1963               | -342.11              | 3726.24               | 0.092 <sup>1</sup><br>✓         |


<sup>1</sup> P<sub>u</sub> / φP<sub>n</sub> controls

|                                                                                                                                                 |         |                        |                             |
|-------------------------------------------------------------------------------------------------------------------------------------------------|---------|------------------------|-----------------------------|
| <b>tnxTower</b><br><br><b>DaVinci Engineering, Inc.</b><br>PO Box 1966<br>Santa Maria, CA 93456<br>Phone: (805) 922-5221<br>FAX: (805) 880-0402 | Job     | 9914267-011            | Page<br>11 of 11            |
|                                                                                                                                                 | Project | 30-ft Light Duty Tower | Date<br>16:20:09 01/21/14   |
|                                                                                                                                                 | Client  | Lea County, New Mexico | Designed by<br>Simon Leland |

### Section Capacity Table

| Section No. | Elevation ft | Component Type | Size | Critical Element | P lb      | $\phi P_{allow}$ lb | % Capacity | Pass Fail |
|-------------|--------------|----------------|------|------------------|-----------|---------------------|------------|-----------|
| T1          | 30 - 20      | Leg            | 1    | 1                | -2472.09  | 26196.10            | 9.4        | Pass      |
|             |              | Diagonal       | 1/2  | 12               | -595.88   | 2438.74             | 24.4       | Pass      |
|             |              | Horizontal     | 1/2  | 15               | -378.33   | 3726.24             | 10.2       | Pass      |
|             |              | Top Girt       | 1/2  | 6                | -120.42   | 3726.24             | 3.2        | Pass      |
|             |              | Bottom Girt    | 1/2  | 8                | -239.23   | 3726.24             | 6.4        | Pass      |
| T2          | 20 - 10      | Leg            | 1    | 49               | -6088.07  | 26196.10            | 23.2       | Pass      |
|             |              | Diagonal       | 1/2  | 60               | -761.58   | 2438.74             | 31.2       | Pass      |
|             |              | Horizontal     | 1/2  | 63               | -474.17   | 3726.24             | 12.7       | Pass      |
|             |              | Top Girt       | 1/2  | 54               | -279.78   | 3726.24             | 7.5        | Pass      |
|             |              | Bottom Girt    | 1/2  | 56               | -294.32   | 3726.24             | 7.9        | Pass      |
| T3          | 10 - 0       | Leg            | 1    | 97               | -10767.40 | 26196.10            | 41.1       | Pass      |
|             |              | Diagonal       | 1/2  | 108              | -920.27   | 2438.74             | 37.7       | Pass      |
|             |              | Horizontal     | 1/2  | 111              | -568.53   | 3726.24             | 15.3       | Pass      |
|             |              | Top Girt       | 1/2  | 102              | -358.07   | 3726.24             | 9.6        | Pass      |
|             |              | Bottom Girt    | 1/2  | 104              | -342.11   | 3726.24             | 9.2        | Pass      |
| Summary     |              |                |      |                  |           |                     |            |           |
|             |              |                |      |                  |           | Leg (T3)            | 41.1       | Pass      |
|             |              |                |      |                  |           | Diagonal (T3)       | 37.7       | Pass      |
|             |              |                |      |                  |           | Horizontal (T3)     | 15.3       | Pass      |
|             |              |                |      |                  |           | Top Girt (T3)       | 9.6        | Pass      |
|             |              |                |      |                  |           | Bottom Girt (T3)    | 9.2        | Pass      |
|             |              |                |      |                  |           | Bolt Checks         | 18.8       | Pass      |
|             |              |                |      |                  |           | RATING =            | 41.1       | Pass      |

Feed Line Plan



|                                  |  |  |                                                                                  |                        |
|----------------------------------|--|--|----------------------------------------------------------------------------------|------------------------|
| <b>DaVinci Engineering, Inc.</b> |  |  | Job: <b>9914267-011</b>                                                          |                        |
| PO Box 1966                      |  |  | Project: <b>30-ft Light Duty Tower</b>                                           |                        |
| Santa Maria, CA 93456            |  |  | Client: Lea County, New Mexico                                                   | Drawn by: Simon Leland |
| Phone: (805) 922-5221            |  |  | Code: TIA-222-G                                                                  | Date: 01/21/14         |
| FAX: (805) 880-0402              |  |  | Path: R:\Engineering Documents\TNC TOWER Files\Dailey Tower 2570014\14267-011.ed | Scale: NTS             |
|                                  |  |  |                                                                                  | Dwg No. E-7            |

## Closed Loop System Design, Operating and Maintenance, and Closure Plan

ConocoPhillips Company

Well: War Hammer 25 Federal COM W1 3H

Location: Sec. 25, T26S, R32E

Date: 3/3/2014

ConocoPhillips proposes the following plan for design, operating and maintenance, and closure of our proposed closed loop system for the above named well:

1. We propose to use a closed loop system with steel pits, haul-off bins, and frac tanks for containing all cuttings, solids, mud, water, brine, and liquids. We will not dig a pit, nor will we use a drying pad, nor will we build an earth pit above ground level, nor will we dispose of or bury any waste on location.

All drilling waste and all drilling fluids (fresh water, brine, mud, cuttings, drill solids, cement returns, and any other liquid or solid that may be involved) will be contained on location in the rig's steel pits or in haul-off bins or in frac tanks as needed. The intent is as follows:

- We propose to use the rigs' steel pits for containing and maintaining the drilling fluids.
- We propose to remove cuttings and drilled solids from the mud by using solids control equipment and to contain such cuttings and drilled solids on location in haul-off bins.
- We propose that any excess water that may need to be stored on location will be stored in tanks.

**The closed loop system components will be inspected daily by each tour and any needed repairs will be made immediately. Any leak in the system will be repaired immediately, and any spilled liquids and/or solids will be cleaned immediately, and the area where any such spill occurred will be remediated immediately.**

2. Cuttings and solids will be removed from location in haul-off bins by an authorized contractor and disposed of at an authorized facility. For this well, we propose the following disposal facility:

R-360 Inc.  
4507 West Carlsbad Hwy, Hobbs, NM 88240,  
P.O. Box 388; Hobbs, New Mexico 88241  
Toll Free Phone: 877.505.4274, Local Phone Number: 432.638.4076

The physical address for the plant where the disposal facility is located is Highway 62/180 at mile marker 66 (33 miles East of Hobbs, NM and 32 miles West of Carlsbad, NM).

The Permit Number for R-360 is NM-01-0006.

A photograph showing the type of haul-off bins that will be used is attached.


3. Mud will be transported by vacuum truck and disposed of at R-360 Inc. at the facility described above.
4. Fresh Water and Brine will be hauled off by vacuum truck and disposed of at an authorized salt water disposal well. We propose the following for disposal of fresh water and brine as needed:
  - Nabors Well Services Company, 3221 NW County Rd; Hobbs, NM 88240, PO 5208 Hobbs, NM, 88241, Permit SWD 092. (Well Location: **Section 3, T19S R37E**)
  - Basic Energy Services, P.O. Box 1869; Eunice, NM 88231 Phone Number: 575.394.2545, Facility located at Hwy 18, Mile Marker 19; Eunice, NM.

Jason Levinson  
Drilling Engineer  
Office: 281-206-5334  
Cell: 281-682-2783


# SPECIFICATIONS

## Heavy Duty Split Metal Rolling Lid

FLOOR: 3/16" PL one piece  
 CROSS MEMBER: 3 x 4-1 channel 16" on center  
 WALLS: 3/16" PL solid welded with tubing top, inside liner hooks  
 DOOR: 3/16" PL with tubing frame  
 FRONT: 3/16" PL slant formed  
 PICK UP: Standard cable with 2" x 6" x 1/4" rails, gusset at each crossmember  
 WHEELS: 10 DIA x 9" long with rease fittings  
 DOOR LATCH: 3 Independent ratchet binders with chains, vertical second latch  
 GASKETS: Extruded rubber seal with metal retainers  
 WELDS: All welds continuous except sub structure crossmembers  
 FINISH: Coated inside and out with direct to metal, rust inhibiting acrylic enamel color coat  
 HYDROTESTING: Full capacity static test  
 DIMENSIONS: 22'-11" long (21'-8" inside), 99" wide (88" inside), see drawing for height  
 OPTIONS: Steel grill blast and special paint, Ampliroll, Heil and Dino pickup  
 ROOF: 3/16" PL roof panels with tubing and channel support frame  
 LIDS: (2) 68" x 90" metal rolling lids spring loaded, self raising  
 ROLLERS: 4" V-groove rollers with delrin bearings and grease fittings  
 OPENING: (2) 60" x 82" openings with 8" divider centered on container  
 LATCH: (2) independent ratchet binders with chains per lid  
 GASKETS: Extruded rubber seal with metal retainers



| CONT. | A  | B  |
|-------|----|----|
| 20 YD | 41 | 53 |
| 25 YD | 53 | 65 |
| 30 YD | 65 | 77 |





## H<sub>2</sub>S Contingency Plan

H<sub>2</sub>S Contingency Plan Holders:

Attached is an H<sub>2</sub>S Contingency Plan for COPC Permian Drilling working in the West Texas and Southeastern New Mexico areas operated by ConocoPhillips Company.

If you have any questions regarding this plan, please call Tom Samarripa at ConocoPhillips Company, 432.368.1263.

## **Table of Contents**

### **Section**

#### **I. Purpose**

#### **II. Scope**

#### **III. Procedures**

#### **IV. Emergency Equipment and Maintenance**

Emergency Equipment Suppliers

General Information

H<sub>2</sub>S Safety Equipment and Monitoring Systems

#### **V. Emergency Call List**

#### **VI. Public/Media Relations**

#### **VII. Public Notification/Evacuation**

#### **VIII. Forms/Reports**