

Carlsbad Field Office OCD Hobbs

14-32

Form 3160-3
(March 2012)FORM APPROVED
OMB No. 1004-0137
Expires October 31, 2014UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

HOBBS OCD

DEC 03 2014


APPLICATION FOR PERMIT TO DRILL OR REENTER

1a. Type of Work ☒ DRILL ☐ REENTER		RECEIVED	5. Lease Serial No. SHLABHL: NMNM017440	
1b. Type of Well ☒ Oil Well ☐ Gas Well ☐ Other ☒ Single Zone ☐ Multiple Zone			6. If Indian, Allottee or Tribe Name	
2. Name of Operator Cimarex Energy Co. (215099)		7. If Unit or CA Agreement, Name and No.		
3a. Address 202 S. Cheyenne Ave., Ste 1000, Tulsa, OK 74103		8. Lease Name and Well No. (313931) West Grama Ridge 7 Federal 2H		
3b. Phone No. (include area code) 918-585-1100		9. API Well No. 30-025-42304		
4. Location of Well (Report location clearly and in accordance with any State requirements. *) At Surface 330 FSL & 1980 FEL At proposed prod. Zone 330 FNL & 1980 FEL Bone Spring		10. Field and Pool, or Exploratory (28432) GRAMA RIDGE, BSS, WEST		
14. Distance in miles and direction from nearest town or post office* Approx 15 miles N of Carlsbad NM		11. Sec. T. R. M. or Blk. and Survey and Area 7, 22s, 34e		
15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line if any) 330'		12. County or Parish Lea		
16. No of acres in lease NMNM017440=1794.49 acres		13. State NM		
17. Spacing Unit dedicated to this well 160.00				
18. Distance from proposed* location to nearest well, drilling, completed, applied for, on this lease, ft. 1320' to the West Grama 7 Federal 3		20. BLM/BIA Bond No. on File NM2575 & NMB000835		
19. Proposed Depth Pilot Hole TD: N/A 15,374 MD 10,950 TVD				
21. Elevations (Show whether DF, KDB, RT, GL, etc.) 3510 GR		23. Estimated duration 35 days		
22. Approximate date work will start* 11/18/13				

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, shall be attached to this form:

- Well plat certified by a registered surveyor
- A Drilling Plan
- A Surface Use Plan (if the location is on National Forest System Lands, the SUPO shall be filed with the appropriate Forest Service Office).
- Bond to cover the operations unless covered by an existing bond on file (see Item 20 above).
- Operator Certification
- Such other site specific information and/or plans as may be required by the authorized officer.

25. Signature 	Name (Printed/Typed) Terri Stathem	Date 10/16/13
Title Regulatory Compliance		
Approved By (Signature) Steve Caffey	Name (Printed/Typed) Office CARLSBAD FIELD OFFICE	Date NOV 24 2014
Title FIELD MANAGER		

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.
Conditions of approval, if any, are attached.

APPROVAL FOR TWO YEARS

Title 18 U.S.S. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious, or fraudulent statements or representations as to any matter within its jurisdiction.

(Continued on page 2)

*(Instructions on page 2)

Capitan Controlled Water Basin

Approval Subject to General Requirements
& Special Stipulations AttachedSEE ATTACHED FOR
CONDITIONS OF APPROVAL

DEC 04 2014


West Grama Ridge 7 Federal 2H
Township 22 South, Range 34 East, N.M.P.M.
Section 7: ALL
Lea County, New Mexico
Federal Oil and Gas Lease No. NM 17440

HOBBS OCD

DEC 03 2014

RECEIVED

Sincerely,



Cimarex Energy Co.

Matt Hood
Landman

Application to Drill
West Grama Ridge 7 Federal 2H
 Cimarex Energy Co.
 UL: O, Sec. 7, 22s, 34e
 Lea Co., NM

HOBBS OCD

DEC 03 2014

RECEIVED

In response to questions asked under Section II B of Bulletin NTL-6, the following information is provided for your consideration:

1. **Location:** SHL 330 FSL & 1980 FEL
 BHL 330 FNL & 1980 FEL
2. **Elevation Above Sea Level:** 3,510' GR
3. **Geologic Name of Surface Formation:** Quaternary Alluvium Deposits
4. **Drilling Tools and Associated Equipment:** Conventional rotary drilling rig using fluid as a circulating medium for solids removal
5. **Proposed Drilling Depth:** 15,374 MD 10,950 TVD Pilot Hole TD: N/A
6. **Estimated Tops of Geological Markers:**

Formation	Est Top	Bearing
Rustler	1720	N/A
Salt	1875	N/A
Tansill	3638	N/A
Capitan	4200	N/A
Bell Canyon	5350	Hydrocarbons
Cherry Canyon	5950	N/A
Brushy Canyon	7300	N/A
Basal Brushy Canyon	8600	N/A
Bone Spring	8850	Hydrocarbons
Avalon Shale	9340	Hydrocarbons
1st BSS	10000	Hydrocarbons
2nd BSS	10600	Hydrocarbons
3rd BS Carbonate	11150	Hydrocarbons

7. **Possible Mineral Bearing Formation:** Shown above

7A. **OSE Ground Water Estimated Depth:** 200'

8. **Casing Program:**

Name	Casing Depth From (ft)	Casing Setting Depth (ft) MD	Casing Setting Depth (ft) TVD	Open Hole Size (inches)	Casing Size (inches)	Casing Weight (lb/ft)	Casing Grade	Thread	Condition	BHP (psig)	Anticipated Mud Weight (ppg)	Collapse SF at Full Evacuation (1.125)	Collapse SF at 1/3 Evacuation (1.125)	Burst SF (1.125)	Cumulative Air Weight	Cumulative Bouyed Weight (lbs)	Bouyant Tension SF (1.8)
Surface	0	1750	1750	17 1/2	13-3/8"	54.50	J-55	ST&C	New	755	8.3	1.50		3.63	95,375	83,289	6.17
Intermediate	0	5200	5200	12 1/4	9-5/8"	40.00	J-55	LT&C	New	2756	10.0		1.35	1.43	212,000	179,634	2.89
Production	0	10472	10472	8 1/2	5-1/2"	17.00	P-110	LT&C	New	4900	9.0	1.53		2.17	186,150	160,572	2.77
Production	10472	15374	10950	8 1/2	5-1/2"	17.00	P-110	BT&C	New	5124	9.0	1.46		2.08	8,126	7,009	77.89

Note: Operator may drill a 8-1/2" OH from end of curve to TD of the well. This is to reduce the need to ream the conventionally drilled curve to run a RSS assembly into the lateral.

Application to Drill
West Grama Ridge 7 Federal 2H
 Cimarex Energy Co.
 UL: O, Sec. 7, 22s, 34e
 Lea Co., NM

8A. Casing Design and Casing Loading Assumptions:

Surface	Tension	A 1.8 design factor with effects of buoyancy: 8.30 ppg.
	Collapse	A 1.125 design factor with full internal evacuation and a collapse force equal to a 8.30 ppg mud gradient.
	Burst	A 1.125 design with a surface pressure equal to the fracture gradient at setting depth less gas gradient to surface.
Intermediate	Tension	A 1.8 design factor with effects of buoyancy: 10.00 ppg.
	Collapse	A 1.125 design factor evacuated 1/3 TVD of next casing string with a collapse force equal to a 10.00 ppg mud gradient.
	Burst	A 1.125 design with a surface pressure equal to the fracture gradient at setting depth less gas gradient to surface.
Production	Tension	A 1.8 design factor with effects of buoyancy: 9.00 ppg.
	Collapse	A 1.125 design factor with full internal evacuation of next casing string with a collapse force equal to a 9.00 ppg mud gradient.
	Burst	A 1.125 design with a surface pressure equal to the fracture gradient at setting depth less gas gradient to surface.

9. Cementing Program:

Casing Type	Type	Sacks	Yield	Weight	Cubic Feet	Cement Blend
Surface	Lead	1112	1.75	13.50	1945	Class C + Bentonite + Calcium Chloride + LCM, 8.829 gps water
	Tail	227	1.34	14.80	303	Class C + LCM, 6.32 gps water
	TOC: 0	85% Excess				Centralizers per Onshore Order 2.III.B.1f
Intermediate	Lead	1142	1.88	12.90	2146	35:65 (poz/C) + Salt + Bentonite + LCM + retarder, 9.65 gps water
	Tail	292	1.34	14.80	391	Class C + retarder + LCM, 6.32 gps water
	TOC: 0	79% Excess				
Production	Lead	577	2.40	11.90	1384	35:65 (poz/H) + salt + Sodium Metasilicate + Bentonite + Fluid Loss + Dispersant + LCM + Retarder, 13.80 gps water
	Tail	1248	1.24	14.50	1547	50:50 (poz/H) + Bentonite + Salt + Fluid Loss + Dispersant + LCM + Retarder, 5.55 gps water
	TOC: 5208	25% Excess				No centralizers planned in the lateral section. 1 every jt from EOC to KOP. 1 every 4th joint from KOP to 500' inside previous casing.

Cement volumes will be adjusted depending on hole size

9a. Proposed Drilling Plan:

Pilot Hole TD: No Pilot KOP: 10,472' EOC: 11,222'

Set Surface and Intermediate casing strings. Drill production hole to KOP. Continue drilling lateral through the curve to TD. Run prod casing & cement.

10. Pressure Control Equipment:

Exhibit "E-1". A BOP consisting of two rams with blind rams and pipe rams, and one annular preventer. Below the surface casing, a 2M system will be used. Below the intermediate casing, a 3M system will be used. See attachments for BOP and choke manifold diagrams. An accumulator that meets the requirements in Onshore Order #2 for the pressure rating of the BOP stack. A Rotating head may be installed as needed. A kelly cock will be installed and maintained in operable condition and a drill string safety valve in the open position will be available on the rig floor.

BOP and associated equipment will be installed, used, maintained, and tested in a manner necessary to assure well control and shall be in place and operational prior to drilling the surface casing shoe. The Annular Preventer shall be functioned at least weekly. The pipe and blind rams will be operated each trip. No abnormal pressure or temperature is expected while drilling.

BOPS will be tested by an independent service company. The ram preventers, choke manifold, and safety valves will be tested as follows: On the surface casing, pressure tests will be made to 250 psi low and 2000 psi high. On the intermediate casing, pressure tests will be made to 250 psi low and 3000 psi high.

The Annular Preventer will be tested to 250 psi low and 1000 psi high on the surface casing, and 250 low and 1500 high on the intermediate casing.

See COA

Cimarex Energy Co. of Colorado requests a variance to drill this well using a co-flex line between the BOP and choke manifold. Certification for proposed co-flex hose is attached (please see Exhibit F, F-1, F-2, F-3). The hose is not required by the manufacturer to be anchored. In the event the specific hose is not available, one of equal or higher rating will be used.

Application to Drill
West Grama Ridge 7 Federal 2H
Cimarex Energy Co.
UL: O, Sec. 7, 22s, 34e
Lea Co., NM

11. Proposed Mud Circulating System:

Depth	Mud Weight	Visc	Fluid Loss	Type Mud
0' to 1750'	8.30	28	NC	FW Spud Mud
1750' to 5300'	10.00	30-32	NC	Brine Water
5300' to 15600'	9.00	30-32	NC	FW/Cut Brine

Sufficient mud materials will be kept on location at all times in order to combat lost circulation or unexpected kicks. In order to run DSTs, open hole logs, and casing, the viscosity and water loss may have to be adjusted in order to meet these needs.

The Mud Monitoring System is an electronic Pason System satisfying requirements of Onshore Order 1.

12. Testing, Logging and Coring Program:

- A. Mud logging program: 2 man unit from 5300 to TD
- B. Electric logging program: CNL / LDT / CAL / GR, DLL / GR -- Inter. Csg to TD
CNL / GR -- Surf to Inter. Csg
- C. No DSTs or cores are planned at this time
- D. CBL w/ CCL from as far as gravity will let it fall to TOC

13. Potential Hazards: *See COA*

No abnormal pressures or temperatures are expected. In accordance with Onshore Order 6, Cimarex does not anticipate that there will be enough H₂S from the surface to the Bone Spring formations to meet the BLM's minimum requirements for the submission of an "H₂S Drilling Operation Plan" or "Public Protection Plan" for the drilling and completion of this well. Since we have an H₂S Safety package on all wells, attached is an "H₂S Drilling Operations Plan." Adequate flare lines will be installed off the mud / gas separator where gas may be flared safely. All personnel will be familiar with all aspects of safe operation of equipment being used.

Estimated BHP: 4928 psi

Estimated BHT: 168°

14. Construction and Drilling:

Road and location construction will begin after BLM approval of APD. Anticipated spud date as soon as approved.

Drilling expected to take: 35 days.

If production casing is run an additional 30 days will be required to complete and construct surface facilities.

15. Other Facets of Operations:

If production casing is run an additional 30 days will be required to complete and construct surface facilities.

Bone Spring pay will be perforated and stimulated.

The proposed well will be tested and potentialized as **Oil**





Cimarex

PATHFINDER
A Schlumberger Company

WELL	FIELD	STRUCTURE
W Grama Ridge 7 Fed #2H	NM Lea County	TBD

Magnetic Parameters	Surface Location	Miscellaneous
Model: BIGM 2012	Lat: N 32 23 59.590	Sub: West Grama Ridge 7 Federal #2H Ref. Ground Level (35.108 above MSL)
Dip: 69.274°	Long: W 103 30 25.295	Plan: ST01 Rev0 RJS 25-Apr-13
Date: April 25, 2013	Heading: 910163.35 RUS	Grid Conv: 0.443°
Mag Dec: 7.445°	Easting: 796368.64 RUS	Scale Fact: 0.99998358
PS: 48519.3m		Grid Date: April 25, 2013



Critical Point	MD	INCL	AZIM	TVD	VSEC	N(+)/S(-)	E(+)/W(-)	DLS
Tie-In ST01	10400.00	0.00	359.66	10400.00	0.00	0.00	0.00	
KOP - Build @ 12°/100' DLS	10472.00	0.00	359.66	10472.00	0.00	0.00	0.00	0.00
Landing Point	11222.84	90.00	359.66	10950.00	478.00	477.99	-2.80	11.99
Cimarex West Grama Ridge 6 Federal #2H PBHL	15374.49	90.00	359.66	10950.00	4629.65	4629.57	-27.25	0.00



Cimarex West Grama Ridge 7 Federal #2H ST01 Rev0 RJS 25-Apr-13
Proposal Report
(Non-Def Plan)



Report Date:	April 25, 2013 - 07:03 PM	Survey / DLS Computation:	Minimum Curvature / Lubinski
Client:	Cimarex	Vertical Section Azimuth:	359.663 ° (Grid North)
Field:	NM Lea County (NAD 83)	Vertical Section Origin:	0.000 ft, 0.000 ft
Structure / Slot:	TBD / Cimarex West Grama Ridge 7 Federal #2H	TVD Reference Datum:	Ground Level
Well:	Cimarex West Grama Ridge 7 Federal #2H	TVD Reference Elevation:	3510.000 ft above MSL
Borehole:	ST01	Seabed / Ground Elevation:	3510.000 ft above MSL
UWI / API#:	Unknown / Unknown	Magnetic Declination:	7.445 °
Survey Name:	Cimarex West Grama Ridge 7 Federal #2H ST01 Rev0 RJS 25-Apr-13	Total Gravity Field Strength:	998.4917mgn (9.80665 Based)
Survey Date:	April 25, 2013	Total Magnetic Field Strength:	48519.334 nT
Tort / AHD / DDI / ERD Ratio:	90.003 ° / 4629.645 ft / 5.767 / 0.423	Magnetic Dip Angle:	60.274 °
Coordinate Reference System:	NAD83 New Mexico State Plane, Eastern Zone, US Feet	Declination Date:	April 25, 2013
Location Lat / Long:	N 32° 23' 59.58995", W 103° 30' 25.29508"	Magnetic Declination Model:	BGGM 2012
Location Grid N/E Y/X:	N 510195.350 ftUS, E 796368.640 ftUS	North Reference:	Grid North
CRS Grid Convergence Angle:	0.4428 °	Grid Convergence Used:	0.4428 °
Grid Scale Factor:	0.99998358	Total Corr Mag North->Grid North:	7.0024 °
		Local Coord Referenced To:	Structure Reference Point

Comments	MD (ft)	Incl (°)	Azim Grid (°)	TVD (ft)	VSEC (ft)	NS (ft)	EW (ft)	Northing (ftUS)	Easting (ftUS)	Latitude (N/S ° ' '')	Longitude (E/W ° ' '')	Closure (ft)	Closure Azimuth (°)	DLS (°/100ft)
SHL W Grama Ridge Fed #2H	0.00	0.00	0.00	0.00	0.00	0.00	0.00	510195.35	796368.64	N 32 23 59.59	W 103 30 25.30	0.00	0.00	N/A
	100.00	0.00	359.66	100.00	0.00	0.00	0.00	510195.35	796368.64	N 32 23 59.59	W 103 30 25.30	0.00	0.00	0.00
	200.00	0.00	359.66	200.00	0.00	0.00	0.00	510195.35	796368.64	N 32 23 59.59	W 103 30 25.30	0.00	0.00	0.00
	300.00	0.00	359.66	300.00	0.00	0.00	0.00	510195.35	796368.64	N 32 23 59.59	W 103 30 25.30	0.00	0.00	0.00
	400.00	0.00	359.66	400.00	0.00	0.00	0.00	510195.35	796368.64	N 32 23 59.59	W 103 30 25.30	0.00	0.00	0.00
	500.00	0.00	359.66	500.00	0.00	0.00	0.00	510195.35	796368.64	N 32 23 59.59	W 103 30 25.30	0.00	0.00	0.00
	600.00	0.00	359.66	600.00	0.00	0.00	0.00	510195.35	796368.64	N 32 23 59.59	W 103 30 25.30	0.00	0.00	0.00
	700.00	0.00	359.66	700.00	0.00	0.00	0.00	510195.35	796368.64	N 32 23 59.59	W 103 30 25.30	0.00	0.00	0.00
	800.00	0.00	359.66	800.00	0.00	0.00	0.00	510195.35	796368.64	N 32 23 59.59	W 103 30 25.30	0.00	0.00	0.00
	900.00	0.00	359.66	900.00	0.00	0.00	0.00	510195.35	796368.64	N 32 23 59.59	W 103 30 25.30	0.00	0.00	0.00
	1000.00	0.00	359.66	1000.00	0.00	0.00	0.00	510195.35	796368.64	N 32 23 59.59	W 103 30 25.30	0.00	0.00	0.00
	1100.00	0.00	359.66	1100.00	0.00	0.00	0.00	510195.35	796368.64	N 32 23 59.59	W 103 30 25.30	0.00	0.00	0.00
	1200.00	0.00	359.66	1200.00	0.00	0.00	0.00	510195.35	796368.64	N 32 23 59.59	W 103 30 25.30	0.00	0.00	0.00
	1300.00	0.00	359.66	1300.00	0.00	0.00	0.00	510195.35	796368.64	N 32 23 59.59	W 103 30 25.30	0.00	0.00	0.00
	1400.00	0.00	359.66	1400.00	0.00	0.00	0.00	510195.35	796368.64	N 32 23 59.59	W 103 30 25.30	0.00	0.00	0.00
	1500.00	0.00	359.66	1500.00	0.00	0.00	0.00	510195.35	796368.64	N 32 23 59.59	W 103 30 25.30	0.00	0.00	0.00
	1600.00	0.00	359.66	1600.00	0.00	0.00	0.00	510195.35	796368.64	N 32 23 59.59	W 103 30 25.30	0.00	0.00	0.00
	1700.00	0.00	359.66	1700.00	0.00	0.00	0.00	510195.35	796368.64	N 32 23 59.59	W 103 30 25.30	0.00	0.00	0.00
	1800.00	0.00	359.66	1800.00	0.00	0.00	0.00	510195.35	796368.64	N 32 23 59.59	W 103 30 25.30	0.00	0.00	0.00
	1900.00	0.00	359.66	1900.00	0.00	0.00	0.00	510195.35	796368.64	N 32 23 59.59	W 103 30 25.30	0.00	0.00	0.00
	2000.00	0.00	359.66	2000.00	0.00	0.00	0.00	510195.35	796368.64	N 32 23 59.59	W 103 30 25.30	0.00	0.00	0.00
	2100.00	0.00	359.66	2100.00	0.00	0.00	0.00	510195.35	796368.64	N 32 23 59.59	W 103 30 25.30	0.00	0.00	0.00
	2200.00	0.00	359.66	2200.00	0.00	0.00	0.00	510195.35	796368.64	N 32 23 59.59	W 103 30 25.30	0.00	0.00	0.00
	2300.00	0.00	359.66	2300.00	0.00	0.00	0.00	510195.35	796368.64	N 32 23 59.59	W 103 30 25.30	0.00	0.00	0.00
	2400.00	0.00	359.66	2400.00	0.00	0.00	0.00	510195.35	796368.64	N 32 23 59.59	W 103 30 25.30	0.00	0.00	0.00
	2500.00	0.00	359.66	2500.00	0.00	0.00	0.00	510195.35	796368.64	N 32 23 59.59	W 103 30 25.30	0.00	0.00	0.00
	2600.00	0.00	359.66	2600.00	0.00	0.00	0.00	510195.35	796368.64	N 32 23 59.59	W 103 30 25.30	0.00	0.00	0.00
	2700.00	0.00	359.66	2700.00	0.00	0.00	0.00	510195.35	796368.64	N 32 23 59.59	W 103 30 25.30	0.00	0.00	0.00

10/15/2013 4:57 PM Page 2 of 4

Comments	MD (ft)	Incl (°)	Azim Grid (°)	TVD (ft)	VSEC (ft)	NS (ft)	EW (ft)	Northing (ftUS)	Easting (ftUS)	Latitude (N/S ° ' ")	Longitude (E/W ° ' ")	Closure (ft)	Closure Azimuth (°)	DLS (°/100ft)
	8300.00	0.00	359.66	8300.00	0.00	0.00	0.00	510195.35	796368.64	N 32 23 59.59	W 103 30 25.30	0.00	0.00	0.00
	8400.00	0.00	359.66	8400.00	0.00	0.00	0.00	510195.35	796368.64	N 32 23 59.59	W 103 30 25.30	0.00	0.00	0.00
	8500.00	0.00	359.66	8500.00	0.00	0.00	0.00	510195.35	796368.64	N 32 23 59.59	W 103 30 25.30	0.00	0.00	0.00
	8600.00	0.00	359.66	8600.00	0.00	0.00	0.00	510195.35	796368.64	N 32 23 59.59	W 103 30 25.30	0.00	0.00	0.00
	8700.00	0.00	359.66	8700.00	0.00	0.00	0.00	510195.35	796368.64	N 32 23 59.59	W 103 30 25.30	0.00	0.00	0.00
	8800.00	0.00	359.66	8800.00	0.00	0.00	0.00	510195.35	796368.64	N 32 23 59.59	W 103 30 25.30	0.00	0.00	0.00
	8900.00	0.00	359.66	8900.00	0.00	0.00	0.00	510195.35	796368.64	N 32 23 59.59	W 103 30 25.30	0.00	0.00	0.00
	9000.00	0.00	359.66	9000.00	0.00	0.00	0.00	510195.35	796368.64	N 32 23 59.59	W 103 30 25.30	0.00	0.00	0.00
	9100.00	0.00	359.66	9100.00	0.00	0.00	0.00	510195.35	796368.64	N 32 23 59.59	W 103 30 25.30	0.00	0.00	0.00
	9200.00	0.00	359.66	9200.00	0.00	0.00	0.00	510195.35	796368.64	N 32 23 59.59	W 103 30 25.30	0.00	0.00	0.00
	9300.00	0.00	359.66	9300.00	0.00	0.00	0.00	510195.35	796368.64	N 32 23 59.59	W 103 30 25.30	0.00	0.00	0.00
	9400.00	0.00	359.66	9400.00	0.00	0.00	0.00	510195.35	796368.64	N 32 23 59.59	W 103 30 25.30	0.00	0.00	0.00
	9500.00	0.00	359.66	9500.00	0.00	0.00	0.00	510195.35	796368.64	N 32 23 59.59	W 103 30 25.30	0.00	0.00	0.00
	9600.00	0.00	359.66	9600.00	0.00	0.00	0.00	510195.35	796368.64	N 32 23 59.59	W 103 30 25.30	0.00	0.00	0.00
	9700.00	0.00	359.66	9700.00	0.00	0.00	0.00	510195.35	796368.64	N 32 23 59.59	W 103 30 25.30	0.00	0.00	0.00
	9800.00	0.00	359.66	9800.00	0.00	0.00	0.00	510195.35	796368.64	N 32 23 59.59	W 103 30 25.30	0.00	0.00	0.00
	9900.00	0.00	359.66	9900.00	0.00	0.00	0.00	510195.35	796368.64	N 32 23 59.59	W 103 30 25.30	0.00	0.00	0.00
	10000.00	0.00	359.66	10000.00	0.00	0.00	0.00	510195.35	796368.64	N 32 23 59.59	W 103 30 25.30	0.00	0.00	0.00
	10100.00	0.00	359.66	10100.00	0.00	0.00	0.00	510195.35	796368.64	N 32 23 59.59	W 103 30 25.30	0.00	0.00	0.00
	10200.00	0.00	359.66	10200.00	0.00	0.00	0.00	510195.35	796368.64	N 32 23 59.59	W 103 30 25.30	0.00	0.00	0.00
	10300.00	0.00	359.66	10300.00	0.00	0.00	0.00	510195.35	796368.64	N 32 23 59.59	W 103 30 25.30	0.00	0.00	0.00
Tie-In ST01	10400.00	0.00	359.66	10400.00	0.00	0.00	0.00	510195.35	796368.64	N 32 23 59.59	W 103 30 25.30	0.00	0.00	0.00
KOP - Build @ 12"/100' DLS	10472.00	0.00	359.66	10472.00	0.00	0.00	0.00	510195.35	796368.64	N 32 23 59.59	W 103 30 25.30	0.00	0.00	0.00
	10500.00	3.36	359.66	10499.98	0.82	0.82	0.00	510196.17	796368.64	N 32 23 59.60	W 103 30 25.30	0.82	359.66	11.99
	10600.00	15.34	359.66	10598.48	17.04	17.04	-0.10	510212.39	796368.54	N 32 23 59.76	W 103 30 25.29	17.04	359.66	11.99
	10700.00	27.33	359.66	10691.45	53.35	53.35	-0.31	510248.70	796368.33	N 32 24 0.12	W 103 30 25.29	53.35	359.66	11.99
	10800.00	39.32	359.66	10774.86	108.19	108.19	-0.63	510303.53	796368.01	N 32 24 0.66	W 103 30 25.29	108.19	359.66	11.99
	10900.00	51.30	359.66	10845.06	179.15	179.15	-1.05	510374.49	796367.59	N 32 24 1.36	W 103 30 25.29	179.15	359.66	11.99
	11000.00	63.29	359.66	10898.99	263.14	263.14	-1.54	510458.48	796367.10	N 32 24 2.19	W 103 30 25.29	263.14	359.66	11.99
	11100.00	75.28	359.66	10934.30	356.51	356.50	-2.09	510551.84	796366.55	N 32 24 3.12	W 103 30 25.29	356.51	359.66	11.99
	11200.00	87.26	359.66	10949.45	455.17	455.16	-2.67	510650.50	796365.97	N 32 24 4.09	W 103 30 25.29	455.17	359.66	11.99
Landing Point	11222.84	90.00	359.66	10950.00	478.00	477.99	-2.80	510673.33	796365.84	N 32 24 4.32	W 103 30 25.28	478.00	359.66	11.99
	11300.00	90.00	359.66	10950.00	555.16	555.15	-3.26	510750.49	796365.38	N 32 24 5.08	W 103 30 25.28	555.16	359.66	0.00
	11400.00	90.00	359.66	10950.00	655.16	655.15	-3.84	510850.49	796364.80	N 32 24 6.07	W 103 30 25.28	655.16	359.66	0.00
	11500.00	90.00	359.66	10950.00	755.16	755.15	-4.43	510950.48	796364.21	N 32 24 7.06	W 103 30 25.28	755.16	359.66	0.00
	11600.00	90.00	359.66	10950.00	855.16	855.14	-5.02	511050.48	796363.62	N 32 24 8.05	W 103 30 25.28	855.16	359.66	0.00
	11700.00	90.00	359.66	10950.00	955.16	955.14	-5.60	511150.48	796363.04	N 32 24 9.04	W 103 30 25.27	955.16	359.66	0.00
	11800.00	90.00	359.66	10950.00	1055.16	1055.14	-6.19	511250.47	796362.45	N 32 24 10.03	W 103 30 25.27	1055.16	359.66	0.00
	11900.00	90.00	359.66	10950.00	1155.16	1155.14	-6.78	511350.47	796361.86	N 32 24 11.02	W 103 30 25.27	1155.16	359.66	0.00
	12000.00	90.00	359.66	10950.00	1255.16	1255.14	-7.36	511450.46	796361.28	N 32 24 12.01	W 103 30 25.27	1255.16	359.66	0.00
	12100.00	90.00	359.66	10950.00	1355.16	1355.14	-7.95	511550.46	796360.69	N 32 24 13.00	W 103 30 25.27	1355.16	359.66	0.00
	12200.00	90.00	359.66	10950.00	1455.16	1455.13	-8.54	511650.46	796360.10	N 32 24 13.99	W 103 30 25.26	1455.16	359.66	0.00
	12300.00	90.00	359.66	10950.00	1555.16	1555.13	-9.13	511750.45	796359.51	N 32 24 14.98	W 103 30 25.26	1555.16	359.66	0.00
	12400.00	90.00	359.66	10950.00	1655.16	1655.13	-9.71	511850.45	796358.93	N 32 24 15.97	W 103 30 25.26	1655.16	359.66	0.00
	12500.00	90.00	359.66	10950.00	1755.16	1755.13	-10.30	511950.45	796358.34	N 32 24 16.96	W 103 30 25.26	1755.16	359.66	0.00
	12600.00	90.00	359.66	10950.00	1855.16	1855.13	-10.89	512050.44	796357.75	N 32 24 17.95	W 103 30 25.25	1855.16	359.66	0.00
	12700.00	90.00	359.66	10950.00	1955.16	1955.13	-11.48	512150.44	796357.16	N 32 24 18.94	W 103 30 25.25	1955.16	359.66	0.00
	12800.00	90.00	359.66	10950.00	2055.16	2055.12	-12.07	512250.44	796356.57	N 32 24 19.93	W 103 30 25.25	2055.16	359.66	0.00
	12900.00	90.00	359.66	10950.00	2155.16	2155.12	-12.65	512350.43	796355.99	N 32 24 20.91	W 103 30 25.25	2155.16	359.66	0.00
	13000.00	90.00	359.66	10950.00	2255.16	2255.12	-13.24	512450.43	796355.40	N 32 24 21.90	W 103 30 25.25	2255.16	359.66	0.00
	13100.00	90.00	359.66	10950.00	2355.16	2355.12	-13.83	512550.43	796354.81	N 32 24 22.89	W 103 30 25.24	2355.16	359.66	0.00
	13200.00	90.00	359.66	10950.00	2455.16	2455.12	-14.42	512650.42	796354.22	N 32 24 23.88	W 103 30 25.24	2455.16	359.66	0.00
	13300.00	90.00	359.66	10950.00	2555.16	2555.12	-15.01	512750.42	796353.63	N 32 24 24.87	W 103 30 25.24	2555.16	359.66	0.00
	13400.00	90.00	359.66	10950.00	2655.16	2655.11	-15.60	512850.41	796353.04	N 32 24 25.86	W 103 30 25.24	2655.16	359.66	0.00

Comments	MD (ft)	Incl (°)	Azim Grid (°)	TVD (ft)	VSEC (ft)	NS (ft)	EW (ft)	Northing (ftUS)	Easting (ftUS)	Latitude (N/S ° ' ")	Longitude (E/W ° ' ")	Closure (ft)	Closure Azimuth (°)	DLS (°/100ft)
	13500.00	90.00	359.66	10950.00	2755.16	2755.11	-16.19	512950.41	796352.45	N 32 24 26.85	W 103 30 25.24	2755.16	359.66	0.00
	13600.00	90.00	359.66	10950.00	2855.16	2855.11	-16.78	513050.41	796351.86	N 32 24 27.84	W 103 30 25.23	2855.16	359.66	0.00
	13700.00	90.00	359.66	10950.00	2955.16	2955.11	-17.37	513150.40	796351.27	N 32 24 28.83	W 103 30 25.23	2955.16	359.66	0.00
	13800.00	90.00	359.66	10950.00	3055.16	3055.11	-17.96	513250.40	796350.69	N 32 24 29.82	W 103 30 25.23	3055.16	359.66	0.00
	13900.00	90.00	359.66	10950.00	3155.16	3155.10	-18.54	513350.40	796350.10	N 32 24 30.81	W 103 30 25.23	3155.16	359.66	0.00
	14000.00	90.00	359.66	10950.00	3255.16	3255.10	-19.13	513450.39	796349.51	N 32 24 31.80	W 103 30 25.22	3255.16	359.66	0.00
	14100.00	90.00	359.66	10950.00	3355.16	3355.10	-19.72	513550.39	796348.92	N 32 24 32.79	W 103 30 25.22	3355.16	359.66	0.00
	14200.00	90.00	359.66	10950.00	3455.16	3455.10	-20.31	513650.39	796348.33	N 32 24 33.78	W 103 30 25.22	3455.16	359.66	0.00
	14300.00	90.00	359.66	10950.00	3555.16	3555.10	-20.90	513750.38	796347.74	N 32 24 34.77	W 103 30 25.22	3555.16	359.66	0.00
	14400.00	90.00	359.66	10950.00	3655.16	3655.10	-21.49	513850.38	796347.15	N 32 24 35.76	W 103 30 25.22	3655.16	359.66	0.00
	14500.00	90.00	359.66	10950.00	3755.16	3755.09	-22.08	513950.38	796346.56	N 32 24 36.75	W 103 30 25.21	3755.16	359.66	0.00
	14600.00	90.00	359.66	10950.00	3855.16	3855.09	-22.67	514050.37	796345.97	N 32 24 37.74	W 103 30 25.21	3855.16	359.66	0.00
	14700.00	90.00	359.66	10950.00	3955.16	3955.09	-23.26	514150.37	796345.38	N 32 24 38.73	W 103 30 25.21	3955.16	359.66	0.00
	14800.00	90.00	359.66	10950.00	4055.16	4055.09	-23.86	514250.36	796344.78	N 32 24 39.72	W 103 30 25.21	4055.16	359.66	0.00
	14900.00	90.00	359.66	10950.00	4155.16	4155.09	-24.45	514350.36	796344.19	N 32 24 40.70	W 103 30 25.21	4155.16	359.66	0.00
	15000.00	90.00	359.66	10950.00	4255.16	4255.09	-25.04	514450.36	796343.60	N 32 24 41.69	W 103 30 25.20	4255.16	359.66	0.00
	15100.00	90.00	359.66	10950.00	4355.16	4355.08	-25.63	514550.35	796343.01	N 32 24 42.68	W 103 30 25.20	4355.16	359.66	0.00
	15200.00	90.00	359.66	10950.00	4455.16	4455.08	-26.22	514650.35	796342.42	N 32 24 43.67	W 103 30 25.20	4455.16	359.66	0.00
	15300.00	90.00	359.66	10950.00	4555.16	4555.08	-26.81	514750.35	796341.83	N 32 24 44.66	W 103 30 25.20	4555.16	359.66	0.00
Cimarex West Grama Ridge 6 Federal #2H PBHL	15374.49	90.00	359.66	10950.00	4629.65	4629.57	-27.25	514824.83	796341.39	N 32 24 45.40	W 103 30 25.20	4629.65	359.66	0.00

Survey Type: Non-Def Plan

Survey Error Model: ISCWSA Rev 0 *** 3-D 95.000% Confidence 2.7955 sigma
Survey Program:

Description	MD From (ft)	MD To (ft)	EOU Freq (ft)	Hole Size (in)	Casing Diameter (in)	Survey Tool Type	Borehole / Survey
	0.000	10400.000	1/100.000	30.000	30.000	SLB_MWD-STD	Pilot Borehole / Cimarex West Grama Ridge 7 Federal #2H Pilot
	10400.000	15374.486	1/100.000	30.000	30.000	SLB_MWD-STD	ST01 / Cimarex West Grama Ridge 7 Federal #2H ST01 Rev0

Drilling 12-1/4" hole
below 13 3/8" Casing






Exhibit E-1 – 2000# BOP
West Grama Ridge 7 Fed #2H
Cimarex Energy Co.
7-22S-34E
SHL 330 FSL & 1980 FEL
BHL 330 FNL & 1980 FEL
Lea County, NM

Drilling 8-3/4" hole
below 9 5/8" Casing



SRR & A

Exhibit E-1 – 3000# BOP
West Grama Ridge 7 Fed #2H
Cimarex Energy Co.
7-22S-34E
SHL 330 FSL & 1980 FEL
BHL 330 FNL & 1980 FEL
Lea County, NM



2M: 1 Valve Minimum
 3M: 2 Valves Minimum
 HCR Valve is optional

REMOTELY
 OPERATED
 Adjustable
 Choke

Choke
 Isolation
 Valve

Exhibit E-1 – Choke Manifold Diagram
West Grama Ridge 7 Fed #2H
 Cimarex Energy Co.
 7-22S-34E
 SHL 330 FSL & 1980 FEL
 BHL 330 FNL & 1980 FEL
 Lea County, NM

Drilling Operations **Choke Manifold** **2M/3M Service**

Exhibit F – Co-Flex Hose
West Grama Ridge 7 Fed #2H

Cimarex Energy Co.

7-22S-34E

SHL 330 FSL & 1980 FEL

BHL 330 FNL & 1980 FEL

Lea County, NM




Exhibit F-1 – Co-Flex Hose Hydrostatic Test

West Grama Ridge 7 Fed #2H

Cimarex Energy Co.

7-22S-34E

SHL 330 FSL & 1980 FEL

BHL 330 FNL & 1980 FEL

Lea County, NM



Midwest Hose & Specialty, Inc.

INTERNAL HYDROSTATIC TEST REPORT

Customer: Oderco Inc		P.O. Number: odyd-271	
HOSE SPECIFICATIONS			
Type: Stainless Steel Armor Choke & Kill Hose		Hose Length: 45'ft.	
I.D. 4 INCHES		O.D. 9 INCHES	
WORKING PRESSURE 10,000 PSI	TEST PRESSURE 15,000 PSI	BURST PRESSURE 0 PSI	
COUPLINGS			
Stem Part No. OKC OKC		Ferrule No. OKC OKC	
Type of Coupling: Swage-It			
PROCEDURE			
<u>Hose assembly pressure tested with water at ambient temperature.</u>			
TIME HELD AT TEST PRESSURE 15 MIN.		ACTUAL BURST PRESSURE: 0 PSI	
Hose Assembly Serial Number: 79793		Hose Serial Number: OKC	
Comments:			
Date: 3/8/2011	Tested: <i>A. Joann Jones</i>	Approved: <i>Kevin J. [Signature]</i>	



Midwest Hose
& Specialty, Inc.

Internal Hydrostatic Test Graph

Customer: Houston

Pick Ticket #: 94260


Hose Specifications

Hose Type
C&K
I.D.
4"
Working Pressure
10000 PSI
Length
45'
O.D.
6.09"
Burst Pressure
Standard Safety Multiplier Applies

Verification

Type of Fittings
4 1/16 10K
Die Size
6.38"
Hose Serial #
5344
Coupling Method
Swage
Final O.D.
6.25"
Hose Assembly Serial #
79793

Pressure Test



Test Pressure 15000 PSI
Time Held at Test Pressure 11 Minutes
Actual Burst Pressure 15483 PSI
Peak Pressure 15483 PSI

Comments: Hose assembly pressure tested with water at ambient temperature.

Tested By: Zac McConnell

Approved By: Kim Thomas

[Signature]

[Signature]

March 3, 2011

Exhibit F-1 – Co-Flex Hose Hydrostatic Test
West Grama Ridge 7 Fed #2zh
Cimarex Energy Co.
7-22S-34E
SHL 330 FSL & 1980 FEL
BHL 330 FNL & 1980 FEL
Lea County, NM

Exhibit F-2 – Co-Flex Hose
West Grama Ridge 7 Fed #2H
Cimarex Energy Co.
7-22S-34E
SHL 330 FSL & 1980 FEL
BHL 330 FNL & 1980 FEL
Lea County, NM



Midwest Hose & Specialty, Inc.

Certificate of Conformity

Customer: DEM		PO ODYD-271
SPECIFICATIONS		
Sales Order 79793	Dated: 3/8/2011	
We hereby cerify that the material supplied for the referenced purchase order to be true according to the requirements of the purchase order and current industry standards Supplier: Midwest Hose & Specialty, Inc. 10640 Tanner Road Houston, Texas 77041		
Comments:		
Approved: <i>Samuel Garcia</i>		Date: 3/8/2011




Midwest Hose
& Specialty, Inc.

Exhibit F -3- Co-Flex Hose
West Grama Ridge 7 Fed #2H
Cimarex Energy Co.
7-22S-34E
SHL 330 FSL & 1980 FEL
BHL 330 FNL & 1980 FEL
Lea County, NM

Specification Sheet Choke & Kill Hose

The Midwest Hose & Specialty Choke & Kill hose is manufactured with only premium componets. The reinforcement cables, inner liner and cover are made of the highest quality material to handle the tough drilling applications of today's industry. The end connections are available with API flanges, API male threads, hubs, hammer unions or other special fittings upon request. Hose assembly is manufactured to API 7K. This assembly is wrapped with fire resistant vermiculite coated fiberglass insulation, rated at 2000 degrees with stainless steel armor cover.

Working Pressure:	5,000 or 10,000 psi working pressure
Test Pressure:	10,000 or 15,000 psi test pressure
Reinforcement:	Multiple steel cables
Cover:	Stainless Steel Armor
Inner Tube:	Petroleum resistant, Abrasion resistant
End Fitting:	API flanges, API male threads, threaded or butt weld hammer unions, unbolt and other special connections
Maximum Length:	110 Feet
ID:	2-1/2", 3", 3-1/2", 4"
Operating Temperature:	-22 deg F to +180 deg F (-30 deg C to +82 deg C)



-  Wind Direction Indicators (wind sock or streamers)
- H2S Monitors (alarms at bell nipple and shale shaker)
-  Briefing Areas



Exhibit D – Rig Diagram
West Grama Ridge 7 Fed #2H
 Cimarex Energy Co.
 7-22S-34E
 SHL 330 FSL & 1980 FEL
 BHL 330 FNL & 1980 FEL
 Lea County, NM