



EOG Resources - Midland

Lea County, NM (NAD 27 NME)

Dillon 31

#701H

OH

Plan: Plan #1

Standard Survey Report

04 February, 2015

FEB 12 2015



EOG Resources, Inc.

Survey Report

Company: EOG Resources - Midland
Project: Lea County, NM (NAD 27 NME)
Site: Dillon 31
Well: #701H
Wellbore: OH
Design: Plan #1

Local Co-ordinate Reference: Well #701H
TVD Reference: KB = 25' @ 3470.0usft
MD Reference: KB = 25' @ 3470.0usft
North Reference: Grid
Survey Calculation Method: Minimum Curvature
Database: EDM 5000.1 Single User Db

Project	Lea County, NM (NAD 27 NME)		
Map System:	US State Plane 1927 (Exact solution)	System Datum:	Mean Sea Level
Geo Datum:	NAD 1927 (NADCON CONUS)		
Map Zone:	New Mexico East 3001		

Site	Dillon 31		
Site Position:		Northing:	425,706.00 usft
From:	Map	Easting:	755,398.00 usft
Position Uncertainty:	0.0 usft	Slot Radius:	13-3/16 "
		Latitude:	32° 10' 3.685 N
		Longitude:	103° 30' 28.661 W
		Grid Convergence:	0.44 °

Well	#701H		
Well Position	+N/-S	0.0 usft	Northing: 425,676.00 usft
	+E/-W	0.0 usft	Easting: 755,398.00 usft
Position Uncertainty	0.0 usft	Wellhead Elevation:	0.0 usft
		Latitude:	32° 10' 3.388 N
		Longitude:	103° 30' 28.664 W
		Ground Level:	3,445.0 usft

Wellbore	OH				
Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	IGRF2015	2/4/2015	7.18	60.05	48,155

Design	Plan #1				
Audit Notes:					
Version:	Phase:	PLAN	Tie On Depth:	0.0	
Vertical Section:	Depth From (TVD) (usft)	+N/-S (usft)	+E/-W (usft)	Direction (°)	
	0.0	0.0	0.0	1.97	

Survey Tool Program	Date 2/4/2015				
From (usft)	To (usft)	Survey (Wellbore)	Tool Name	Description	
0.0	17,270.0	Plan #1 (OH)	MWD	MWD - Standard	

Planned Survey										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	
0.0	0.00	0.00	0.0	0.0	0.0	0.0	0.00	0.00	0.00	
100.0	0.00	0.00	100.0	0.0	0.0	0.0	0.00	0.00	0.00	
200.0	0.00	0.00	200.0	0.0	0.0	0.0	0.00	0.00	0.00	
300.0	0.00	0.00	300.0	0.0	0.0	0.0	0.00	0.00	0.00	
400.0	0.00	0.00	400.0	0.0	0.0	0.0	0.00	0.00	0.00	
500.0	0.00	0.00	500.0	0.0	0.0	0.0	0.00	0.00	0.00	
600.0	0.00	0.00	600.0	0.0	0.0	0.0	0.00	0.00	0.00	
700.0	0.00	0.00	700.0	0.0	0.0	0.0	0.00	0.00	0.00	
800.0	0.00	0.00	800.0	0.0	0.0	0.0	0.00	0.00	0.00	
900.0	0.00	0.00	900.0	0.0	0.0	0.0	0.00	0.00	0.00	



EOG Resources, Inc.

Survey Report

Company: EOG Resources - Midland
Project: Lea County, NM (NAD 27 NME)
Site: Dillon 31
Well: #701H
Wellbore: OH
Design: Plan #1

Local Co-ordinate Reference: Well #701H
TVD Reference: KB = 25' @ 3470.0usft
MD Reference: KB = 25' @ 3470.0usft
North Reference: Grid
Survey Calculation Method: Minimum Curvature
Database: EDM 5000.1 Single User Db

Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
1,000.0	0.00	0.00	1,000.0	0.0	0.0	0.0	0.00	0.00	0.00
1,100.0	0.00	0.00	1,100.0	0.0	0.0	0.0	0.00	0.00	0.00
1,200.0	0.00	0.00	1,200.0	0.0	0.0	0.0	0.00	0.00	0.00
1,300.0	0.00	0.00	1,300.0	0.0	0.0	0.0	0.00	0.00	0.00
1,400.0	0.00	0.00	1,400.0	0.0	0.0	0.0	0.00	0.00	0.00
1,500.0	0.00	0.00	1,500.0	0.0	0.0	0.0	0.00	0.00	0.00
1,600.0	0.00	0.00	1,600.0	0.0	0.0	0.0	0.00	0.00	0.00
1,700.0	0.00	0.00	1,700.0	0.0	0.0	0.0	0.00	0.00	0.00
1,800.0	0.00	0.00	1,800.0	0.0	0.0	0.0	0.00	0.00	0.00
1,900.0	0.00	0.00	1,900.0	0.0	0.0	0.0	0.00	0.00	0.00
2,000.0	0.00	0.00	2,000.0	0.0	0.0	0.0	0.00	0.00	0.00
2,100.0	0.00	0.00	2,100.0	0.0	0.0	0.0	0.00	0.00	0.00
2,200.0	0.00	0.00	2,200.0	0.0	0.0	0.0	0.00	0.00	0.00
2,300.0	0.00	0.00	2,300.0	0.0	0.0	0.0	0.00	0.00	0.00
2,400.0	0.00	0.00	2,400.0	0.0	0.0	0.0	0.00	0.00	0.00
2,500.0	0.00	0.00	2,500.0	0.0	0.0	0.0	0.00	0.00	0.00
2,600.0	0.00	0.00	2,600.0	0.0	0.0	0.0	0.00	0.00	0.00
2,700.0	0.00	0.00	2,700.0	0.0	0.0	0.0	0.00	0.00	0.00
2,800.0	0.00	0.00	2,800.0	0.0	0.0	0.0	0.00	0.00	0.00
2,900.0	0.00	0.00	2,900.0	0.0	0.0	0.0	0.00	0.00	0.00
3,000.0	0.00	0.00	3,000.0	0.0	0.0	0.0	0.00	0.00	0.00
3,100.0	0.00	0.00	3,100.0	0.0	0.0	0.0	0.00	0.00	0.00
3,200.0	0.00	0.00	3,200.0	0.0	0.0	0.0	0.00	0.00	0.00
3,300.0	0.00	0.00	3,300.0	0.0	0.0	0.0	0.00	0.00	0.00
3,400.0	0.00	0.00	3,400.0	0.0	0.0	0.0	0.00	0.00	0.00
3,500.0	0.00	0.00	3,500.0	0.0	0.0	0.0	0.00	0.00	0.00
3,600.0	0.00	0.00	3,600.0	0.0	0.0	0.0	0.00	0.00	0.00
3,700.0	0.00	0.00	3,700.0	0.0	0.0	0.0	0.00	0.00	0.00
3,800.0	0.00	0.00	3,800.0	0.0	0.0	0.0	0.00	0.00	0.00
3,900.0	0.00	0.00	3,900.0	0.0	0.0	0.0	0.00	0.00	0.00
4,000.0	0.00	0.00	4,000.0	0.0	0.0	0.0	0.00	0.00	0.00
4,100.0	0.00	0.00	4,100.0	0.0	0.0	0.0	0.00	0.00	0.00
4,200.0	0.00	0.00	4,200.0	0.0	0.0	0.0	0.00	0.00	0.00
4,300.0	0.00	0.00	4,300.0	0.0	0.0	0.0	0.00	0.00	0.00
4,400.0	0.00	0.00	4,400.0	0.0	0.0	0.0	0.00	0.00	0.00
4,500.0	0.00	0.00	4,500.0	0.0	0.0	0.0	0.00	0.00	0.00
4,600.0	0.00	0.00	4,600.0	0.0	0.0	0.0	0.00	0.00	0.00
4,700.0	0.00	0.00	4,700.0	0.0	0.0	0.0	0.00	0.00	0.00
4,800.0	0.00	0.00	4,800.0	0.0	0.0	0.0	0.00	0.00	0.00
4,900.0	0.00	0.00	4,900.0	0.0	0.0	0.0	0.00	0.00	0.00
5,000.0	0.00	0.00	5,000.0	0.0	0.0	0.0	0.00	0.00	0.00
5,100.0	0.00	0.00	5,100.0	0.0	0.0	0.0	0.00	0.00	0.00
5,200.0	0.00	0.00	5,200.0	0.0	0.0	0.0	0.00	0.00	0.00
5,300.0	0.00	0.00	5,300.0	0.0	0.0	0.0	0.00	0.00	0.00



EOG Resources, Inc.

Survey Report

Company: EOG Resources - Midland
Project: Lea County, NM (NAD 27 NME)
Site: Dillon 31
Well: #701H
Wellbore: OH
Design: Plan #1

Local Co-ordinate Reference: Well #701H
TVD Reference: KB = 25' @ 3470.0usft
MD Reference: KB = 25' @ 3470.0usft
North Reference: Grid
Survey Calculation Method: Minimum Curvature
Database: EDM 5000.1 Single User Db

Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
5,400.0	0.00	0.00	5,400.0	0.0	0.0	0.0	0.00	0.00	0.00
5,500.0	0.00	0.00	5,500.0	0.0	0.0	0.0	0.00	0.00	0.00
5,600.0	0.00	0.00	5,600.0	0.0	0.0	0.0	0.00	0.00	0.00
5,700.0	0.00	0.00	5,700.0	0.0	0.0	0.0	0.00	0.00	0.00
5,800.0	0.00	0.00	5,800.0	0.0	0.0	0.0	0.00	0.00	0.00
5,900.0	0.00	0.00	5,900.0	0.0	0.0	0.0	0.00	0.00	0.00
6,000.0	0.00	0.00	6,000.0	0.0	0.0	0.0	0.00	0.00	0.00
6,100.0	0.00	0.00	6,100.0	0.0	0.0	0.0	0.00	0.00	0.00
6,200.0	0.00	0.00	6,200.0	0.0	0.0	0.0	0.00	0.00	0.00
6,300.0	0.00	0.00	6,300.0	0.0	0.0	0.0	0.00	0.00	0.00
6,400.0	0.00	0.00	6,400.0	0.0	0.0	0.0	0.00	0.00	0.00
6,500.0	0.00	0.00	6,500.0	0.0	0.0	0.0	0.00	0.00	0.00
6,600.0	0.00	0.00	6,600.0	0.0	0.0	0.0	0.00	0.00	0.00
6,700.0	0.00	0.00	6,700.0	0.0	0.0	0.0	0.00	0.00	0.00
6,800.0	0.00	0.00	6,800.0	0.0	0.0	0.0	0.00	0.00	0.00
6,900.0	0.00	0.00	6,900.0	0.0	0.0	0.0	0.00	0.00	0.00
7,000.0	0.00	0.00	7,000.0	0.0	0.0	0.0	0.00	0.00	0.00
7,100.0	0.00	0.00	7,100.0	0.0	0.0	0.0	0.00	0.00	0.00
7,200.0	0.00	0.00	7,200.0	0.0	0.0	0.0	0.00	0.00	0.00
7,300.0	0.00	0.00	7,300.0	0.0	0.0	0.0	0.00	0.00	0.00
7,400.0	0.00	0.00	7,400.0	0.0	0.0	0.0	0.00	0.00	0.00
7,500.0	0.00	0.00	7,500.0	0.0	0.0	0.0	0.00	0.00	0.00
7,600.0	0.00	0.00	7,600.0	0.0	0.0	0.0	0.00	0.00	0.00
7,700.0	0.00	0.00	7,700.0	0.0	0.0	0.0	0.00	0.00	0.00
7,800.0	0.00	0.00	7,800.0	0.0	0.0	0.0	0.00	0.00	0.00
7,900.0	0.00	0.00	7,900.0	0.0	0.0	0.0	0.00	0.00	0.00
8,000.0	0.00	0.00	8,000.0	0.0	0.0	0.0	0.00	0.00	0.00
8,100.0	0.00	0.00	8,100.0	0.0	0.0	0.0	0.00	0.00	0.00
8,200.0	0.00	0.00	8,200.0	0.0	0.0	0.0	0.00	0.00	0.00
8,300.0	0.00	0.00	8,300.0	0.0	0.0	0.0	0.00	0.00	0.00
8,400.0	0.00	0.00	8,400.0	0.0	0.0	0.0	0.00	0.00	0.00
8,500.0	0.00	0.00	8,500.0	0.0	0.0	0.0	0.00	0.00	0.00
8,600.0	0.00	0.00	8,600.0	0.0	0.0	0.0	0.00	0.00	0.00
8,700.0	0.00	0.00	8,700.0	0.0	0.0	0.0	0.00	0.00	0.00
8,800.0	0.00	0.00	8,800.0	0.0	0.0	0.0	0.00	0.00	0.00
8,900.0	0.00	0.00	8,900.0	0.0	0.0	0.0	0.00	0.00	0.00
9,000.0	0.00	0.00	9,000.0	0.0	0.0	0.0	0.00	0.00	0.00
9,100.0	1.00	148.86	9,100.0	-0.7	0.5	-0.7	1.00	1.00	0.00
9,200.0	2.00	148.86	9,200.0	-3.0	1.8	-2.9	1.00	1.00	0.00
9,300.0	3.00	148.86	9,299.9	-6.7	4.1	-6.6	1.00	1.00	0.00
9,400.0	4.00	148.86	9,399.7	-11.9	7.2	-11.7	1.00	1.00	0.00
9,500.0	5.00	148.86	9,499.4	-18.7	11.3	-18.3	1.00	1.00	0.00
9,600.0	6.00	148.86	9,598.9	-26.9	16.2	-26.3	1.00	1.00	0.00



EOG Resources, Inc.

Survey Report

Company: EOG Resources - Midland
 Project: Lea County, NM (NAD 27 NME)
 Site: Dillon 31
 Well: #701H
 Wellbore: OH
 Design: Plan #1

Local Co-ordinate Reference: Well #701H
 TVD Reference: KB = 25' @ 3470.0usft
 MD Reference: KB = 25' @ 3470.0usft
 North Reference: Grid
 Survey Calculation Method: Minimum Curvature
 Database: EDM 5000.1 Single User Db

Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
9,700.0	7.00	148.86	9,698.3	-36.6	22.1	-35.8	1.00	1.00	0.00
9,766.2	7.66	148.86	9,763.9	-43.8	26.4	-42.8	1.00	1.00	0.00
9,800.0	7.66	148.86	9,797.4	-47.6	28.8	-46.6	0.00	0.00	0.00
9,900.0	7.66	148.86	9,898.5	-59.1	35.7	-57.8	0.00	0.00	0.00
10,000.0	7.66	148.86	9,995.6	-70.5	42.6	-69.0	0.00	0.00	0.00
10,100.0	7.66	148.86	10,094.7	-81.9	49.5	-80.1	0.00	0.00	0.00
10,200.0	7.66	148.86	10,193.8	-93.3	56.4	-91.3	0.00	0.00	0.00
10,300.0	7.66	148.86	10,293.0	-104.7	63.3	-102.5	0.00	0.00	0.00
10,400.0	7.66	148.86	10,392.1	-116.1	70.1	-113.6	0.00	0.00	0.00
10,500.0	7.66	148.86	10,491.2	-127.5	77.0	-124.8	0.00	0.00	0.00
10,600.0	7.66	148.86	10,590.3	-138.9	83.9	-136.0	0.00	0.00	0.00
10,700.0	7.66	148.86	10,689.4	-150.3	90.8	-147.1	0.00	0.00	0.00
10,800.0	7.66	148.86	10,788.5	-161.8	97.7	-158.3	0.00	0.00	0.00
10,900.0	7.66	148.86	10,887.6	-173.2	104.6	-169.5	0.00	0.00	0.00
11,000.0	7.66	148.86	10,986.7	-184.6	111.5	-180.6	0.00	0.00	0.00
11,100.0	7.66	148.86	11,085.8	-196.0	118.4	-191.8	0.00	0.00	0.00
11,200.0	7.66	148.86	11,184.9	-207.4	125.3	-203.0	0.00	0.00	0.00
11,300.0	7.66	148.86	11,284.0	-218.8	132.2	-214.1	0.00	0.00	0.00
11,400.0	7.66	148.86	11,383.1	-230.2	139.1	-225.3	0.00	0.00	0.00
11,500.0	7.66	148.86	11,482.2	-241.6	146.0	-236.5	0.00	0.00	0.00
11,600.0	7.66	148.86	11,581.3	-253.0	152.9	-247.6	0.00	0.00	0.00
11,700.0	7.66	148.86	11,680.5	-264.5	159.8	-258.8	0.00	0.00	0.00
11,800.0	7.66	148.86	11,779.6	-275.9	166.7	-270.0	0.00	0.00	0.00
11,883.9	7.66	148.86	11,862.7	-285.4	172.5	-279.3	0.00	0.00	0.00
11,900.0	6.33	141.38	11,878.7	-287.0	173.6	-280.9	10.00	-8.26	-46.48
11,950.0	3.91	89.17	11,928.5	-289.2	177.0	-282.9	10.00	-4.85	-104.42
12,000.0	6.35	37.22	11,978.3	-287.0	180.4	-280.6	10.00	4.89	-103.91
12,050.0	10.74	20.49	12,027.8	-280.4	183.7	-273.9	10.00	8.78	-33.47
12,100.0	15.50	13.64	12,076.5	-269.5	186.9	-262.9	10.00	9.52	-13.70
12,150.0	20.38	9.98	12,124.0	-254.4	190.0	-247.7	10.00	9.75	-7.32
12,200.0	25.30	7.69	12,170.1	-235.3	192.9	-228.5	10.00	9.84	-4.58
12,250.0	30.24	6.11	12,214.3	-212.1	195.7	-205.3	10.00	9.89	-3.16
12,300.0	35.20	4.94	12,256.4	-185.2	198.3	-178.3	10.00	9.92	-2.34
12,350.0	40.17	4.02	12,295.9	-154.8	200.6	-147.8	10.00	9.94	-1.83
12,400.0	45.15	3.28	12,332.7	-121.0	202.8	-113.9	10.00	9.95	-1.49
12,450.0	50.13	2.65	12,366.4	-84.1	204.7	-77.0	10.00	9.96	-1.25
12,500.0	55.11	2.11	12,396.7	-44.4	206.3	-37.3	10.00	9.96	-1.08
12,550.0	60.09	1.63	12,423.5	-2.2	207.7	4.9	10.00	9.97	-0.96
12,600.0	65.08	1.20	12,446.5	42.1	208.8	49.3	10.00	9.97	-0.87
12,650.0	70.06	0.80	12,465.6	88.3	209.6	95.5	10.00	9.97	-0.80
12,700.0	75.05	0.43	12,480.6	136.0	210.1	143.2	10.00	9.97	-0.75
12,750.0	80.04	0.07	12,491.3	184.8	210.3	191.9	10.00	9.98	-0.72
12,800.0	85.03	359.72	12,497.8	234.4	210.2	241.5	10.00	9.98	-0.69



EOG Resources, Inc.

Survey Report

Company: EOG Resources - Midland
Project: Lea County, NM (NAD 27 NME)
Site: Dillon 31
Well: #701H
Wellbore: OH
Design: Plan #1

Local Co-ordinate Reference: Well #701H
TVD Reference: KB = 25' @ 3470.0usft
MD Reference: KB = 25' @ 3470.0usft
North Reference: Grid
Survey Calculation Method: Minimum Curvature
Database: EDM 5000.1 Single User Db

Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
12,849.9	90.00	359.38	12,500.0	284.2	209.8	291.2	10.00	9.98	-0.68
12,900.0	90.00	359.38	12,500.0	334.3	209.3	341.3	0.00	0.00	0.00
13,000.0	90.00	359.38	12,500.0	434.3	208.2	441.2	0.00	0.00	0.00
13,100.0	90.00	359.38	12,500.0	534.3	207.1	541.1	0.00	0.00	0.00
13,200.0	90.00	359.38	12,500.0	634.3	206.0	641.0	0.00	0.00	0.00
13,300.0	90.00	359.38	12,500.0	734.3	205.0	740.9	0.00	0.00	0.00
13,400.0	90.00	359.38	12,500.0	834.3	203.9	840.8	0.00	0.00	0.00
13,500.0	90.00	359.38	12,500.0	934.3	202.8	940.7	0.00	0.00	0.00
13,600.0	90.00	359.38	12,500.0	1,034.3	201.7	1,040.6	0.00	0.00	0.00
13,700.0	90.00	359.38	12,500.0	1,134.3	200.6	1,140.5	0.00	0.00	0.00
13,800.0	90.00	359.38	12,500.0	1,234.3	199.5	1,240.4	0.00	0.00	0.00
13,900.0	90.00	359.38	12,500.0	1,334.2	198.5	1,340.3	0.00	0.00	0.00
14,000.0	90.00	359.38	12,500.0	1,434.2	197.4	1,440.2	0.00	0.00	0.00
14,100.0	90.00	359.38	12,500.0	1,534.2	196.3	1,540.1	0.00	0.00	0.00
14,200.0	90.00	359.38	12,500.0	1,634.2	195.2	1,640.0	0.00	0.00	0.00
14,300.0	90.00	359.38	12,500.0	1,734.2	194.1	1,739.9	0.00	0.00	0.00
14,400.0	90.00	359.38	12,500.0	1,834.2	193.1	1,839.8	0.00	0.00	0.00
14,500.0	90.00	359.38	12,500.0	1,934.2	192.0	1,939.7	0.00	0.00	0.00
14,600.0	90.00	359.38	12,500.0	2,034.2	190.9	2,039.6	0.00	0.00	0.00
14,700.0	90.00	359.38	12,500.0	2,134.2	189.8	2,139.5	0.00	0.00	0.00
14,800.0	90.00	359.38	12,500.0	2,234.2	188.7	2,239.4	0.00	0.00	0.00
14,900.0	90.00	359.38	12,500.0	2,334.2	187.6	2,339.3	0.00	0.00	0.00
15,000.0	90.00	359.38	12,500.0	2,434.2	186.6	2,439.2	0.00	0.00	0.00
15,100.0	90.00	359.38	12,500.0	2,534.2	185.5	2,539.1	0.00	0.00	0.00
15,200.0	90.00	359.38	12,500.0	2,634.2	184.4	2,639.0	0.00	0.00	0.00
15,300.0	90.00	359.38	12,500.0	2,734.2	183.3	2,738.9	0.00	0.00	0.00
15,400.0	90.00	359.38	12,500.0	2,834.2	182.2	2,838.8	0.00	0.00	0.00
15,500.0	90.00	359.38	12,500.0	2,934.2	181.2	2,938.6	0.00	0.00	0.00
15,600.0	90.00	359.38	12,500.0	3,034.1	180.1	3,038.5	0.00	0.00	0.00
15,700.0	90.00	359.38	12,500.0	3,134.1	179.0	3,138.4	0.00	0.00	0.00
15,800.0	90.00	359.38	12,500.0	3,234.1	177.9	3,238.3	0.00	0.00	0.00
15,900.0	90.00	359.38	12,500.0	3,334.1	176.8	3,338.2	0.00	0.00	0.00
16,000.0	90.00	359.38	12,500.0	3,434.1	175.7	3,438.1	0.00	0.00	0.00
16,100.0	90.00	359.38	12,500.0	3,534.1	174.7	3,538.0	0.00	0.00	0.00
16,200.0	90.00	359.38	12,500.0	3,634.1	173.6	3,637.9	0.00	0.00	0.00
16,300.0	90.00	359.38	12,500.0	3,734.1	172.5	3,737.8	0.00	0.00	0.00
16,400.0	90.00	359.38	12,500.0	3,834.1	171.4	3,837.7	0.00	0.00	0.00
16,500.0	90.00	359.38	12,500.0	3,934.1	170.3	3,937.6	0.00	0.00	0.00
16,600.0	90.00	359.38	12,500.0	4,034.1	169.2	4,037.5	0.00	0.00	0.00
16,700.0	90.00	359.38	12,500.0	4,134.1	168.2	4,137.4	0.00	0.00	0.00
16,800.0	90.00	359.38	12,500.0	4,234.1	167.1	4,237.3	0.00	0.00	0.00
16,900.0	90.00	359.38	12,500.0	4,334.1	166.0	4,337.2	0.00	0.00	0.00
17,000.0	90.00	359.38	12,500.0	4,434.1	164.9	4,437.1	0.00	0.00	0.00
17,100.0	90.00	359.38	12,500.0	4,534.1	163.8	4,537.0	0.00	0.00	0.00

**EOG Resources, Inc.**

Survey Report

Company: EOG Resources - Midland
Project: Lea County, NM (NAD 27 NME)
Site: Dillon 31
Well: #701H
Wellbore: OH
Design: Plan #1

Local Co-ordinate Reference: Well #701H
TVD Reference: KB = 25' @ 3470.0usft
MD Reference: KB = 25' @ 3470.0usft
North Reference: Grid
Survey Calculation Method: Minimum Curvature
Database: EDM 5000.1 Single User Db

Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
17,200.0	90.00	359.38	12,500.0	4,834.1	162.8	4,636.9	0.00	0.00	0.00
17,270.0	90.00	359.38	12,500.0	4,704.0	162.0	4,706.8	0.00	0.00	0.00

Design Targets

Target Name	Dip Angle (°)	Dip Dir. (°)	TVD (usft)	+N/-S (usft)	+E/-W (usft)	Northing (usft)	Easting (usft)	Latitude	Longitude
- hit/miss target									
- Shape									
FTP (Dillon 31 #701H)	0.00	0.00	12,500.0	-9.0	213.0	425,667.00	755,611.00	32° 10' 3.283 N	103° 30' 26.187 W
- plan misses target center by 70.7usft at 12579.3usft MD (12437.5 TVD, 23.6 N, 208.4 E)									
- Point									
PBHL (Dillon 31 #701H)	90.00	359.38	12,500.0	4,704.0	162.0	430,380.00	755,560.00	32° 10' 49.924 N	103° 30' 26.359 W
- plan hits target center									
- Rectangle (sides W50.0 H0.0 D4,713.0)									

Checked By: _____

Approved By: _____

Date: _____