

New Mexico Oil Conservation Division, District I
UNITED STATES **1625 N. French Drive**
DEPARTMENT OF THE INTERIOR **Hobbs, NM 88240**
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB NO. 1004-0137
Expires March 31, 2007

APPLICATION FOR PERMIT TO DRILL OR REENTER

1a. Type of Work <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER SUBJECT TO LIKE APPROVAL BY STATE		5. Lease Serial No. LC-032233(A)
1b. Type of Well <input type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input checked="" type="checkbox"/> Other <input checked="" type="checkbox"/> Single Zone <input type="checkbox"/> Multiple Zone Injector		6. If Indian, Allottee or Tribe Name
2. Name of Operator Occidental Permian Limited Partnership ATTN: Mark Stephens, Rm. 19.013		7. Unit or CA Agreement Name and No.
3a. Address P.O. Box 4294, Houston, TX 77210-4294	3b. Phone No. (include area code) (713) 366-5158	8. Lease Name and Well No. North Hobbs G/SA Unit No. 712
4. Location of Well (Report location clearly and in accordance with any State requirements)* At surface 2378' FNL & 1086' FWL At proposed prod. zone		9. API Well No. 30-02537558
14. Distance in miles and direction from nearest town or post office* 1 mile West from Hobbs, NM		10. Field and Pool, or Exploratory Hobbs; Grayburg - San Andres
15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drg. unit line, if any) 8200' FSL	16. No. of Acres in lease 10,649.53	11. Sec., T., R., M., or Blk. and Survey or Area Sec. 29, T-18-S, R-38-E
18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft. 559'	19. Proposed Depth 4600' TVD	12. County or Parish Lea
21. Elevations (Show whether DF, KDB, RT, GL, etc.) 3645' GL	22. Approximate date work will start* 11/4/05	13. State NM
20. BLM/BIA Bond No. on file NM2797		
23. Estimated duration 9 days		

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, shall be attached to this form:

- | | |
|---|--|
| 1. Well plat certified by a registered surveyor. | 4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above). |
| 2. A Drilling Plan | 5. Operator certification. |
| 3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO shall be filed with the appropriate Forest Service Office). | 6. Such other site specific information and/or plans as may be required by the authorized officer. |

25. Signature Mark Stephens	Name (Printed/Typed) Mark Stephens	Date 9/28/05
---------------------------------------	--	------------------------

Title

Regulatory Compliance Analyst

Approved by (Signature) /s/ Joe G. Lara	Name (Printed/Typed) /s/ Joe G. Lara	Date NOV 02 2005
---	--	----------------------------

Title

ACTING FIELD MANAGER

Office

CARLSBAD FIELD OFFICE

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.
Conditions of approval, if any, are attached.

APPROVAL FOR 1 YEAR

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*(Instructions on page 2)

"CONDITION FOR APPROVAL" Approval for Drilling only. CANNOT inject into well until Injection order is approved by the Santa Fe OCD Office.

APPROVAL SUBJECT TO GENERAL REQUIREMENTS AND SPECIAL STIPULATIONS ATTACHED

1625 N. FRENCH DR., HOBBS, NM 88240

State of New Mexico
Energy, Minerals and Natural Resources Department

DISTRICT II
1301 W. GRAND AVENUE, ARTESIA, NM 86210

DISTRICT III
1000 Rio Brazos Rd., Aztec, NM 87410

DISTRICT IV
1220 S. ST. FRANCIS DR., SANTA FE, NM 87505

OIL CONSERVATION DIVISION
1220 SOUTH ST. FRANCIS DR.
Santa Fe, New Mexico 87505

Form C-102
Revised JUNE 10, 2003
Submit to Appropriate District Office
State Lease - 4 Copies
Fee Lease - 3 Copies

WELL LOCATION AND ACREAGE DEDICATION PLAT

☐ AMENDED REPORT

API Number 30-025-37558	Pool Code 31920	Pool Name Hobbs; Grayburg-San Andres
Property Code 19520	Property Name NORTH HOBBS G/SA UNIT	Well Number 712
OGRID No. 157984	Operator Name OCCIDENTAL PERMIAN, LTD	Elevation 3645'


Surface Location

UL or lot No.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
E	29	18-S	38-E		2378	NORTH	1086	WEST	LEA

Bottom Hole Location If Different From Surface

UL or lot No.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
Dedicated Acres 40	Joint or Infill I	Consolidation Code U	Order No.						

NO ALLOWABLE WILL BE ASSIGNED TO THIS COMPLETION UNTIL ALL INTERESTS HAVE BEEN CONSOLIDATED
OR A NON-STANDARD UNIT HAS BEEN APPROVED BY THE DIVISION

 <div style="text-align: center; margin-top: 20px;"> <p>GEODETIC COORDINATES NAD 27 NME</p> <p>Y=627240.7 N X=856184.3 E</p> <p>LAT.=32°43'08.51" N LONG.=103°10'30.85" W</p> </div>	<div style="text-align: center; margin-bottom: 10px;"> <p>OPERATOR CERTIFICATION</p> <p><i>I hereby certify the the information contained herein is true and complete to the best of my knowledge and belief.</i></p> </div> <div style="margin-bottom: 10px;"> <p style="text-align: center;"><i>Mark Stephens</i></p> <p>Signature _____</p> <p>Mark Stephens</p> </div> <div style="margin-bottom: 10px;"> <p>Printed Name _____</p> <p>Reg. Comp. Analyst</p> </div> <div style="margin-bottom: 10px;"> <p>Title _____</p> <p>August 12, 2005</p> </div> <div style="margin-bottom: 10px;"> <p>Date _____</p> </div> <div style="text-align: center; margin-bottom: 10px;"> <p>SURVEYOR CERTIFICATION</p> <p>•</p> <p><i>I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief.</i></p> </div> <div style="text-align: center; margin-bottom: 10px;"> <p>JULY 15, 2005</p> </div> <div style="margin-bottom: 10px;"> <p>Date Surveyed _____ JR</p> </div> <div style="margin-bottom: 10px;"> <p>Signature _____ Seal of Professional Surveyor</p> </div> <div style="margin-bottom: 10px;"> <p>_____ GARY ELDSON NEW MEXICO REGISTERED PROFESSIONAL SURVEYOR 7/15/05 05.11.1085</p> </div> <div style="margin-bottom: 10px;"> <p>Certificate No. GARY ELDSON 12641</p> </div>
---	--

AFE No.	93001147	PayKey:	
Rig No.	Patterson 65	Date:	August 12, 2005
API #:	Not yet assigned	County:	Lea
Lease:	North Hobbs G/SA Unit	Well No.	712
Location:	2378' FNL & 1086' FWL, Sec. 29	Bottomhole Location:	Same as surface - No Target.
	T-18-S, R-38-E		
OBJECTIVE:	Primary: Grayburg / San Andres	Secondary:	None
METHOD OF DRILLING		APPROXIMATE DEPTHS OF GEOLOGICAL MARKER	
TYPE OF TOOLS	DEPTH OF DRILLING	Estimated Elev.	GL: 3645.00' KB: (13.0') 3658.00'
Rotary	4400' +/-	Marker	
LOG PROGRAM		Redbeds	265'
Depth Interval		Rustler	1515'
		Yates	2690'
		Grayburg	3770'
		San Andres	4070'
REMARKS:			
No core, cased hole logs			
		TD	4400' +/-
SPECIAL TESTS		# Probable completion interval	
TYPE	DEPTH INTERVAL, ETC	DRILL CUTTING SAMPLES	
		FREQUENCY	DEPTH
			DRILLING TIME
			FREQUENCY
			DEPTH
			Continuous
			0' - TD
Remarks:		Remarks:	
BLM and City well. Vertical. Permit to 4600'.			
Mud Program			
Approx Interval	Type Mud	Weight	Vis, sec/qt
0' - 1540'	Fresh Water Native Mud	8.6-9.5	32-36
1540' - 4400' +/-	Brine	10.0-10.2	28-29
		W/L, cc's/30 min	pH control
		No Control	None
		No Control	None
REMARKS:			
CASING PROGRAM:			
Casing String	Est. Depth	Casing	Hole Size
Surface	1540'	8.625", 24#, J-55, ST&C	12.25"
Production	4400' +/-	5.5", 15.5#, J-55, LT&C	7.875"
		Cu. Ft. Cement	Cement Recipe
			Landing Point
			Test Pressure
			See below
			Cut hole to fit pipe tally
			See below
			4400' +/-
			1500 psi
			1500 psi
Float Equipment, DV Tool, Flag Joint & Centralizers:			
Surface Hole Equipment:			
Guide Shoe, 1 shoe joint, Insert float, 11 centralizers			
Centralizers: One on each of bottom 3 joints, and thereafter every fourth joint to surface (total 13 centralizers).			
Production Hole Equipment:			
Guide Shoe, one shoe joint, Float Collar			
Centralizers: One 5' above guide shoe, One 5' above float collar, 2 at DV tool, and every fourth jt from 3725' to 4205' (total 8 centralizers)			
DV Tool set at 3500'. ECP set at 1400'. Also centralize Yates if active.			
Marker jt. @ 4000'			
Cement:			
Surface Hole:			
Lead Slurry		Tail Slurry	
550 sx PBCZ		300 sx Premium Plus	
13.5 ppg Slurry Weight		14.8 ppg Slurry Weight	
1.63 cuft/sx Slurry Yield		1.34 cuft/sx Slurry Yield	
8.37 gal/sx Fresh Water		6.31 gal/sx Fresh Water	
Production Hole:			
First Stage		Second Stage	
Lead Slurry		Lead Slurry	
250 sx Premium Plus		550 sx Interfill "C"	
.4% CFR-3, .25% D-AIR		.25 lb/sx Flocele	
.5% LAP-1		100 sx Premium Plus	
14.84 ppg Slurry Weight		2% Calcium Chloride	
1.32 cuft/sx Yield		11.9 ppg Slurry Wieght	
6.17 gal/sx Fresh Water		14.81 ppg Slurry Weight	
		2.46 cuft/sx Yield	
		1.34 cuft/sx Slurry Yield	
		14.22 gal/sx Fresh Water	
		6.29 gal/sx Fresh Water	
Samples:			
Cement: On all slurries for surface & production cement, 1 bag of dry cement of each blend			
Water: On all cement mix water for surface & production cement, 1 gal of mix water (1 from each tank being used)			
Chlorides: Cement Company - Check chlorides on each water sample. If Chlorides greater than 300 ppm notify company representative.			
GENERAL REMARKS:			
Safety equipment on location by 3000'.			
Surface wellhead set with BHO East & West.			
Logging program developed by:			
PREPARED BY: Mike Blackwell		APPROVED:	
		APPROVED:	

WELL BORE SKETCH

WELL HEAD 6" X 900

AFE #

93001147

WELL NO: 712

GL ELEVATION

3645.00'


FIELD: Hobbs

KB: (13.0')

OBJECTIVE: Grayburg / San Andres

KB ELEVATION

3658.00'



TD 4400' +/-

Expected Hazards and Proposed Mitigation Measures
Attachment to Drilling Plan
Onshore Oil and Gas Operations, 3162.3-1(e)

Hazard: Time and water-sensitive redbed shales slough into hole.

Mitigation: Maintain viscosity of at least 32 sec/qt. If tight hole is encountered, attempt to work through tight spot before circulating. Case-off redbeds immediately after drilling through them.

Hazard: Gas influx from Yates formation.

Mitigation: Maintain brine weight of at least 10 ppg. Utilize external casing packer to reduce gas migration through cement.


Hazard: H₂S influx from formations.

Mitigation: Maintain brine weight of at least 10 ppg. Observe H₂S precautions and bring H₂S safety equipment on site before drilling below 3000'. Utilize H₂S scavenger if H₂S encountered.

Hazard: Lost returns in Grayburg and San Andres formations.

Mitigation: Utilize LCM if lost returns occur. If LCM is unsuccessful at regaining returns, cement lost-return zone and re-drill.



Patterson/UTI 65



Drilling Rig Layout

NOTES REGARDING THE BLOWOUT PREVENTERS

- 1) Drilling nipple to be so constructed that it can be removed without use of a welder through rotary table opening, with minimum i.d. equal to preventer bore.
- 2) Blowout preventer (BOP) and all fittings must be in good condition, 3000 psi WP minimum. BOP, choke manifold, and all related equipment will be suitable for H₂S service per 43 CFR 3160 Onshore Oil and Gas Order No. 6, Hydrogen Sulfide Operations (III.C).
- 3) All fittings to be flanged.
- 4) Safety valve must be available on rig floor at all times with proper connections; valve to be full bore 3000 psi WP minimum.
- 5) All choke and kill lines to be securely anchored, especially ends of choke lines.
- 6) Equipment through which bit must pass shall be at least as large as the diameter of the casing being drilled through.
- 7) Kelly cock on kelly.
- 8) Extension wrenches and hand wheels to be properly installed.
- 9) Blow out preventer control to be located as close to driller's position as feasible.
- 10) BOP closing equipment to meet specifications of 43 CFR 3160 Onshore Oil and Gas Order No. 2, Drilling Operations (III.A.).



Request for Variance – BOP
Well Control Requirements
Onshore Oil and Gas Operating Order No. 2, Drilling Operations

Request: Utilize 3000 psi BOP stack, but test only to 1100 psi.

Logic: Surface casing will be set at approximately 1540' below grade. At this depth, the fracture gradient of the formation is estimated to be approximately 13.3 ppg. The formation at the casing shoe can therefore only hold $(13.3)(.052)(1540) = 1065$ psi without fracturing. Assuming cut brine in the wellbore, 1065 psi at the casing shoe translates into $1065 - (8.9)(.052)(1540) = 352$ psi at the wellhead. Assuming gas in the wellbore, 1065 psi at the casing shoe translates into $1065 - (0)(.052)(1540) = 1065$ psi at the wellhead. Thus, the BOP stack on this well is unlikely to be subjected to well-control pressures in excess of approximately 1065 psi.

**OXY Permian
Limited Partnership
PO Box 50250
Midland, TX 79710**

**Hydrogen Sulfide (H₂S)
Contingency Plan**

For

**OPL NHU 29-712
2378 ft FNL, 1086 ft FWL
Sec 29, T18S, R38E
Lea County, NM**

And

Patterson/UTI 65

TABLE OF CONTENTS

<u>ITEM</u>	<u>PAGE</u>
PREFACE	3
LOCATION MAP	4
RIG SKETCH.....	5
EMERGENCY RESPONSE ACTIVATION AND GENERAL RESPONSIBILITIES	6
SPECIFIC EMERGENCY GUIDANCE	
- H2S Release	8
- Well Control	10
PUBLIC RELATIONS	13
PHONE CONTACTS – OP DOWNHOLE SERVICES GROUP	14
EMERGENCY PERSONELL NOTIFICATION NUMBERS.....	15
PHONE CONTACTS – OP PRODUCTION AND PLANT PERSONNEL	16
PHONE CONTACTS – OP HES PERSONNEL	16

PREFACE



An effective and viable Contingency Plan is intended to provide prior planning and guidance in responding to emergency incidents. The primary considerations in its development are protection of personnel, the public, company and public property, and the environment.

Although the plan addresses varied emergency situations which may occur, it recognizes that flexibility and the use of the organization's knowledge and experience is critical to safe resolution of emergency incidents. Response actions outlined in the plan provide a framework, which may be placed into operation without confusion. These actions should promote quick and decisive actions during the critical initial period and immediately following an emergency. As the response progresses, additional guidelines and procedures may need to be implemented as the situation dictates. In addition, all emergency incidents must be properly reported per the Oxy Incident Reporting and Notification Policy, state and federal requirements, etc.

This Contingency Plan is intended for use on Oxy Downhole Services Group projects and the operations within their area of responsibility, such as drilling, critical well work, etc.


A copy of the Plan shall be maintained in the Top Dog House, Rig Managers trailer, and Company Representative's trailer if applicable.

Oxy Permian 29-712
Lat. 32°43'08.51" N
Long. 103°10'30.85" W
NAD 27 NME
Y = 627240.7 N
X = 856184.3 E



This location is approximately 250' North and 200' West of the intersection of West County Road and Mahan Road.

Patterson/UTI 65



Drilling Rig Layout

EMERGENCY RESPONSE ACTIVATION AND GENERAL RESPONSIBILITIES

Activation of the Emergency Action Plan

- A. In the event of any emergency situation, all personnel on location should first ensure that the following items are initiated. After that, they should refer to the appropriate Specific Emergency Guidance sections on pages ten (10) through twelve (12) in this document for further responsibilities:
 - 1. Notify the senior ranking contract representative on site.
 - 2. Notify Oxy representative in charge.
 - 3. Notify civil authorities if the Oxy Representative can not be contacted and the situation dictates.
 - 4. Perform rescue and first aid as required (without jeopardizing additional personnel).

General Responsibilities

Oxy Permian Personnel:

- A. Operations Specialist: The Oxy Drilling/Critical Well Servicing Operations Specialist or contract personnel serving in that capacity will serve as Operations Chief Officer for all emergency incidents. The Operations Chief Officer is responsible for:
 - 1. Notification to the Downhole Services Team Leader of the incident occurrence.
 - 2. Notification to the local RMT/PMT leader of the incident occurrence, and the need for the designated local RMT/PMT Incident Commander to act in that capacity for the response effort.
 - 3. Sole control of all tactical activities directed toward reducing the immediate hazard, establishing situational control and restoring the operations to a non-emergency state.
- B. Local RMT/PMT Designated Incident Commander: The Oxy local RMT/PMT Designated Incident Commander will serve as the overall Incident Commander for the drilling or critical well servicing emergency incident. The Incident Commander is responsible for:
 - 1. Coordinating with the Downhole Services Team Leader for notification to the Oxy Crisis Management team of the incident occurrence.
 - 2. Establishing and managing the overall incident command structure and response from inception through restoration of normal activities in the area.
- C. Downhole Services HES Tech: The Downhole Services HES Tech (or his designate) is responsible for reporting to the incident as soon as reasonably possible, to provide support to the response effort as required by the Operations Chief Officer or the Incident Commander.

Contract Drilling Personnel will immediately report to their assigned stations and perform their duties as outlined in the appropriate Specific Emergency Guidance sections on pages ten (10) through twelve (12) in this document.

Other Contractor Personnel will report to the safe briefing area to assist Oxy personnel and civil authorities as requested when it is safe to do so and if they have been adequately trained in their assigned duties.

Civil Authorities (Law Enforcement, Fire, and EMS) will be responsible for:

1. Establishing membership in the Unified Incident Command.
2. As directed by the Incident Commander and the Unified Command, control site access, re-route traffic, and provide escort services for response personnel.
3. Perform all fire control activities in coordination with the Unified Command.
4. Initiate public evacuation plans as instructed by the Incident Commander.
5. Perform rescue or recovery activities with coordination from the Unified Command.
6. Provide medical assistance as dictated by the situation at hand.

H2S RELEASE

The following procedures and responsibilities will be implemented on activation of the H2S siren and lights.

All Personnel:

1. On alarm, don escape unit (if available) and report to upwind briefing area.

Rig Manager/Tool Pusher:

1. Check that all personnel are accounted for and their condition.
2. Administer or arrange for first aid treatment, and /or call EMTs as needed.
3. Identify two people best suited to secure well and perform rescue, and instruct them to don SCBA.
4. Notify Contractor management and Oxy Representative.
5. Remain at the briefing area, assess and monitor personnel and overall situation for hazards or conditions that might warrant a change in the action plan.

Two People Responsible For Shut-in and Rescue:

1. Don SCBA and acquire tools to secure well and perform rescue, i.e., wrenches, retrieval ropes, etc.
2. Utilize the buddy system to secure well and perform rescue(s).
3. Return to the briefing area and stand by for further instructions.

All Other Personnel:

1. Isolate the area and prevent entry by other persons into the 100 ppm ROE. Additionally the first responder(s) must evacuate any public places encompassed by the 100 ppm ROE. First responder(s) must take care not to injure themselves during this operation. Company and/or local officials must be contacted to aid in this operation. Evacuation of the public should be beyond the 100 ppm ROE.

Oxy Representative:

1. Remain at the briefing area, assess and monitor personnel and overall situation for hazards or conditions that might warrant a change in the action plan.
2. Notify Operation Specialists or Team Leader and RMT Leader or Local Incident Commander, and Police, Fire Department, or other local emergency services as required.

Training

There will be an initial training session prior to encountering a known or probable H₂S zone (within 3 days or 500 feet) and weekly H₂S and well control drills for all personnel in each crew. The initial training session shall include a review of the site specific H₂S Drilling Operations Plan and the Public Protection Plan (Contingency Plan). This plan shall be available at the well site. All personnel will be required to carry documentation that they have received the proper training.

Ignition of Gas Source

Should control of the well be considered lost and ignition considered, take care to protect against exposure to Sulfur Dioxide (SO₂). Intentional ignition must be coordinated with the NMOCD and local officials. Additionally the NM State Police shall be the Incident Command of any major release. Ignition of the well will be with the concurrence of the drilling team leader and the Oxy Crisis Management Team as time allows.

Characteristics of H₂S and SO₂

Common Name	Chemical Formula	Specific Gravity	Threshold Limit	Hazardous Limit	Lethal Concentration
Hydrogen Sulfide	H ₂ S	1.189 Air = 1	10 ppm	100 ppm	600 ppm
Sulfur Dioxide	SO ₂	2.21 Air = 1	2 ppm	N/A	1000 ppm

Contacting Authorities

Oxy Permian personnel must liaison with local and state agencies to ensure a proper response to a major release. Additionally, the OCD must be notified of the release as soon as possible but no later than 4 hours. Agencies will ask for information such as; type and volume of release, wind direction, location of release, etc. Be prepared with all information available. The following call list of essential and potential responders has been prepared for use during a release. This response plan must be in coordination with the State of New Mexico's 'Hazardous Materials Emergency Response Plan' (HMER).

WELL CONTROL

The following procedures will be implemented when a loss of primary control is indicated. Indicators of loss of primary control are flow from the well, an increase in pit volume, or when the drilling fluid used to fill the hole on trips is less than the calculated pipe displacement volume. The emergency signal for well control procedures will be a single long blast of the rig air horn.

Kick While Drilling - Procedures And Responsibilities

Driller:

1. Stop the rotary and hoist the kelly above the rotary table.
2. Stop the mud pump(s).
3. Check for flow.
4. If flowing, sound the alarm immediately.
5. Ensure that all crew members fill their responsibilities to secure the well.
6. Record drill pipe and casing shut-in pressures and pit volume increase and begin kill sheet.

Derrickman:

1. Go to BOP/choke manifold area.
2. Open choke line valve on BOP.
3. Signal to Floorman #1 that the choke line is open.
4. Close chokes after annular or pipe rams are closed.
5. Record shut-in casing pressure and pit volume increase.
6. Report readings and observations to Driller.
7. Verify actual mud weight in suction pit and report to Driller.
8. Be readily available as required for additional tasks.

Floorman # 1:

1. Go to accumulator control station and await signal from Derrickman.
2. Close annular preventer and HCR on signal (if available, if not then close pipe rams).
3. Record accumulator pressures and check for leaks in the BOP or accumulator system.
4. Report to Driller, and be readily available as required for additional tasks.

Floorman # 2:

1. Start water on motor exhausts.
2. Notify Contractor Tool Pusher or Rig Manager of well control situation.
3. Check location for ignition sources and extinguish or turn off, and stop any welding in progress.
4. Report to Driller, and be readily available as required for additional tasks.

Floorman # 3:

1. Stand-by with Driller, and be readily available as required for additional tasks.

Tool Pusher/Rig Manager:

1. Notify Oxy Representative and report to rig floor.
2. Review and verify all pertinent information.
3. Communicate information to Oxy Representative, and confer on an action plan.
4. Finalize well control worksheets, calculations and preparatory work for action plan.
5. Initiate and ensure the action plan is carried out.
6. Communicate any changes in well or site conditions, or any indications that the action plan needs to be revised to the Oxy representative.

Oxy Representative:

1. Notify Operation Specialists or Team Leader and RMT Leader or Local Incident Commander, and Police, Fire Department, or other local emergency services as required.

Kick While Tripping - Procedures and Responsibilities

Driller:

1. Sound the alarm immediately when pipe displacement volume is less than 75% of calculated.
2. Position the upper tool joint just above rotary table and set slips.
3. Check for flow.
4. Ensure that all crew members fill their responsibilities to secure the well.
5. Record drill pipe and casing shut-in pressures and pit volume increase, and begin kill sheets.

Derrickman: (same as while drilling)

Floor Man # 1:

1. Install full opening valve (with help from Floorman #2) in top drill string connection.
2. Tighten valve with make up tongs.
3. Go to accumulator control station and await signal from Derrickman.
4. Close annular preventer and HCR valve on signal (if available, if not then close pipe rams).
5. Record accumulator pressures and check for leaks in the BOP and accumulator system.
6. Report to Driller, and be readily available as required for additional tasks.

Floor Man # 2:

1. Assist installing full opening valve in drill string.
2. Position back-up tongs for valve make-up.
3. Start water on motor exhausts.
4. Notify Contractor Tool Pusher or Rig Manager of well control situation.
5. Check location for ignition sources and extinguish or turn off, and stop any welding in progress.
6. Report to Driller, and be readily available as required for additional tasks.

Floorman # 3, Rig Manager/Tool Pusher, and Oxy Representative: (same as while drilling)

PUBLIC RELATIONS

Oxy recognizes that the news media have a legitimate interest in incidents at Oxy facilities that could affect the public. It is to the company's benefit to cooperate with the news media when incidents occur because these media are our best liaison with the public.

Our objective is to see that all reports of any emergency are factual and represent the company's position fairly and accurately. Cooperation with news media representatives is the most reliable guarantee that this objective will be met.

All contract and Oxy employees are instructed **NOT** to make any statement to the media concerning the emergency incident. If a media representative contacts any employee, they should refer them to the designated Emergency Command Center where they should contact the Incident Commander or his designated relief for any information concerning the incident.

Emergency Notification Numbers

Public Authorities		
New Mexico State Police	Artesia	505/746-2704
New Mexico State Police	Carlsbad	505/885-3137
New Mexico State Police	Hobbs	505/392-5588
Eddy County Sheriff's Office	Artesia	505/746-2704
Eddy County Sheriff's Office	Carlsbad	505/887-7551
Lea County Sheriff's Office	Hobbs	505/393-2515
Local Emergency Planning Center	Eddy County	505/887-9511
Local Emergency Planning Center	Lea County	505/397-9231
New Mexico Oil & Gas Commission	Artesia	505/748-1283
New Mexico Oil & Gas Commission	Hobbs	505/393-6161
NM Emergency Response Center	Hobbs	505/827-9222

Emergency Services		
Fire Fighting, Rescue, Ambulance, Police	Artesia	911
Fire Fighting, Rescue, Ambulance, Police	Carlsbad	911
Fire Fighting, Rescue, Ambulance, Police	Hobbs	911
Flight For Life	Lubbock	806/743-9911
Aerocare	Lubbock	806/7478923
Med Flight Air Ambulance	Albuquerque	505/842-4433

Other Emergency Services		
Boots and Coots		1/800-256-9688
Cudd Pressure Control	Midland	432/699-0139
B.J. Services	Artesia	505/746-3569
Halliburton	Artesia	505/746-2757

OXY PERMIAN DOWNHOLE SERVICES GROUP
--

	LOCATION	OFFICE	HOME	CELL	PAGER
Manager Operations Support					
Hardesty, Steve	Midland	432-685-5880	432/694-6441	713-560-8095	
Team Leader					
Pennington, Randy	Midland	432-685-5684	432/689-7642	432-556-0207	
			Toledo Bend =	318-590-2349	
Operations Specialists					
Mike Murray	Midland	432-685-5718	432-689-2592	432-556-6792	
HES Tech					
Thompson, Don	Midland	432-685-5719	432/684-3900	432-556-1505	

OXY Permian Production and Plant Personnel OXY Permian Crisis Team Hotline Notification (713) 935-7210

PERSON	LOCATION	OFFICE	FAX	CELL	PAGER
--------	----------	--------	-----	------	-------

Asset Management-Operations Areas					
OXY Permian General Manager: Tom Menges	Houston	(281) 552-1147	(281) 552-1484	(713) 560-8038	
North Permian Asset: Harry Hufft	Houston	(713) 3665002		(713) 560-8071	

PERSON	LOCATION	OFFICE	FAX	CELL	PAGER
Production Coordinators: S. Permian Asset					
Hobbs RMT: Gary Bullock	Hobbs	(505) 397-8203	(505) 397-8204	(505) 390-9144	
OXY Permian HES Personnel OXY Permian Crisis Team Hotline Notification (713) 935-7210					

PERSON	LOCATION	OFFICE	FAX	CELL	PAGER
HES Coordinators & Area of Responsibility					
Rickie Tyler	Midland	432 685-5707		432 556-6790	
HES Techs & Area of Responsibility					
Hobbs RMT: Steve Bishop	Hobbs	(505) 397-8251	(505) 397-8204	(505) 390-4784	(877) 339-1954- 1118#
Frontier-New Mexico: Rick Kerby	Hobbs	(505) 393-2174	(505) 393-2671	(505) 390-8639	(505) 370-6527

Request for Variance – Second Egress
Drilling/Completion/Workover Requirements (III.C.2.a)
Onshore Oil and Gas Order No. 6, Hydrogen Sulfide Operations

Request: Permit drilling pad to be built with only one ingress/egress road.

Logic: In the event of an H₂S release or other similar incident, a second-egress road or foot-path would be unlikely to provide additional routes of egress from the drilling pad. The area surrounding the drilling pad is relatively flat, and contains few obstructions (the perimeter of the drilling pad is not fenced, and essentially the only obstructions are scattered brush with significant clear areas between plants). In the event of an H₂S release or other similar incident, personnel on the drill pad would most likely exit the drill pad at the nearest point, regardless of whether the surrounding area at that point was cleared or uncleared. In the event of an H₂S-release or other similar incident, personnel on the drill pad would not be expected to travel back through some portion of the drill pad and exit the drill pad via one of the two cleared egress routes.

Further, a second egress route would disturb additional areas of the native environment.

Attachment 1
SURFACE USE AND OPERATING PLAN

Occidental Permian, Ltd.
North Hobbs G/SA Unit Well No. 29-712
2378 FNL & 1086 FWL
Unit Letter E, Section 29, T-18-S, R-38-E
Lea County, New Mexico

1. Existing Roads:

- A. Access to the location is shown in Attachment 2.
- B. The well site survey plat for the proposed well is shown in Attachment 3.
- C. Directions to location: From corner of Hwy 62/180 and West County Rd. Turn north on west County Rd. and go 1-1/2 miles. Turn left off West County onto Mahan and go approximately 1/10 of a mile. Turn north on lease road and go approximately 1/10 mile.

2. Location of Existing Wells:

Attachment 4 shows existing unit wells within a one-mile radius of this well operated by Occidental Permian, Ltd.

3. Location of Existing and/or Proposed Facilities:

The well will be connected to an existing facilities located approximately 2500 feet southwest of this proposed site by a flowline installed according to API specifications.

4. Location and Type of Water Supply:

The well will be drilled with a combination of brine and fresh water mud systems as outlined in the drilling program. The water will be obtained from commercial water stations in the area and hauled to the location by transport truck over the existing and proposed roads shown in Attachment 2. No water well will be drilled on the location.

5. Source of Construction Material:

All caliche required for construction of the drill pad and to maintain the access roads will be obtained from an approved caliche pit or from the construction of the reserve pit. All roads and pads will be constructed of 6 inches of rolled and compacted caliche.

6. Methods of Handling Waste Disposal:

- A. Drill cuttings will be disposed of into the reserve pit.
- B. Drilling fluids will be contained in steel mud tanks and the reserve pit. The reserve pit will contain any excess drilling fluid or flow from the well during drilling, cementing, and completion operations.
 - 1. The reserve pit will be an earthen pit, approximately 150 feet x 125 feet x 6 feet deep and fenced. The pit will be plastic-lined (12 mil thickness) to minimize loss of drilling fluids and saturation of the ground with brine water. The pit will be divided into two separate pits, one being for fresh water cuttings, and the other for brine water cuttings. At the completion of the well the pits will be allowed to dry, the brine cuttings will be removed and taken to a licensed disposal site, and the fresh water cuttings will be buried on site.

- C. Water produced from the well during completion may be disposed into the brine cuttings side of the reserve pit or a steel tank. After the well is permanently placed on production, produced water will be collected in existing facilities.
- D. A portable chemical toilet will be provided on the location for human waste during the drilling and completion operations.
- E. Garbage and trash produced during drilling and completion operations will be collected in a screened-in trailer. All waste material will be contained to prevent scattering by the wind. After drilling operations are complete the trash will be disposed of in a nearby landfill.
- F. After the rig is moved out and the well is either completed or abandoned, all waste materials will be cleaned up within 30 days. No adverse materials will be left on the location. The reserve pit will be completely fenced and kept closed until it has dried. In the event of a dry hole, only a dry hole marker will remain.

7. Ancillary Facilities:

No airstrip, campsite, or other facilities will be built as a result of the operations on this well.

8. Well Site Layout:

Attachment 5 shows a typical orientation for the rig and associated drilling equipment, reserve pit, and pipe racks. No permanent living facilities are planned, but a temporary foreman/toolpusher's trailer will be on location during the drilling operations.

9. Plans for Restoration of the Surface:

- A. Upon completion of the proposed operations, if the well is abandoned, the caliche will be removed from the location and road and returned to the pit from which it was taken. The pit area, after allowing to dry, will be broken out and leveled. The original topsoil will be returned to the entire location that will be leveled and contoured to as nearly the original topography as possible. Pit lining material will be buried or hauled away in order to leave the location in an aesthetically pleasing condition. All pits will be filled and the location leveled within 120 days after abandonment.
- B. The disturbed surface area will be restored per agreement with surface owners.

10. Surface Ownership:

The well site and lease is located entirely on privately owned surface.

11. Operator's Representative:

An Occidental representative responsible for assuring compliance with the surface use plan is as follows:

Drill Site Compliance:

Dusty Weaver
1017 W. Stanolind
Hobbs, NM 88240
Work Phone 806-893-3067


Well and Facilities Operations:

David Nelson
1017 W. Stanolind
Hobbs, NM 88240
Work Phone 505-397-8211

Certification:


I hereby certify that I, or persons under my direct supervision, have inspected the proposed drill site and access route; that I am familiar with the conditions which currently exist; that the statements made in this plan are to best of my knowledge, true and correct; and the work associated with the operations proposed herein will be performed by Occidental Permian, Ltd. and its contractors and subcontractors in conformity with this plan and the terms and conditions which is in approved. This statement is subject to the provisions of 18 U.S.C. 1001 for the filing of a false statement.

Date: 9/13/05

Signed: 
David Nelson
Hobbs RMT Engineering Advisor




SECTION 29, TOWNSHIP 18 SOUTH, RANGE 38 EAST, N.M.P.M.,
LEA COUNTY, NEW MEXICO



DIRECTIONS TO LOCATION

THIS LOCATION IS APPROX. 250' NORTH AND 200' WEST OF THE INTERSECTION OF WEST CO. RD. AND MAHAN RD.




PROVIDING SURVEYING SERVICES
SINCE 1946
JOHN WEST SURVEYING COMPANY
412 N. DAL PASO
HOBBS, N.M. 88240
(505) 383-3117

OCCIDENTAL PERMIAN, LTD


NORTH HOBBS G/SA UNIT #712 WELL
LOCATED 2378 FEET FROM THE NORTH LINE
AND 1086 FEET FROM THE WEST LINE OF SECTION 29,
TOWNSHIP 18 SOUTH, RANGE 38 EAST, N.M.P.M.,
LEA COUNTY, NEW MEXICO.

Survey Date: 07/15/05	Sheet 1 of 1 Sheets
W.O. Number: 05.11.1085	Dr By: J.R.
Date: 07/21/05	Disk: CD#5
05111085	Scale: 1"=100'



Attachment #4

Patterson/UTI 65



Drilling Rig Layout

STATEMENT ACCEPTING RESPONSIBILITY FOR OPERATIONS

The undersigned accepts all applicable terms, conditions, stipulations and restrictions concerning operations conducted on the leased land or portion thereof, as described below:

Lease No.: LC-032233(A)
Legal Description: Letter E, Section 29, T-18-S, R-38-E
Formation: Grayburg – San Andres
Bond Coverage: \$25,000.00 (Statewide Oil & Gas Bond)
BLM Bond No.: NM2797
Surety Bond No: 218975

Authorized Signature

Mark Stephens 9/28/05
Mark Stephens
Regulatory Compliance Analyst
Occidental Permian Limited Partnership

PRIVATE SURFACE OWNER'S AGREEMENT OR STATEMENT THAT AN
AGREEMENT HAS BEEN REACHED CONCERNING SURFACE USE

Occidental Permian Limited Partnership, P.O. Box 4294, Houston, TX 77210-4294
is both operator (North Hobbs G/SA Unit) and surface owner (Letter E, Section 29, T-18-S,
R-38-E, Lea Co. NM), and therefore, no surface agreement is necessary.

Authorized Signature

Mark Stephens


9/28/05

Mark Stephens
Regulatory Compliance Analyst
Occidental Permian Limited Partnership

COPY

Page 2

**North Hobbs G/SA Unit No. 712
Letter E, Sec. 29, T-18-S, R-38-E
Lea Co., NM**



Attachments to Application For Permit to Drill (6 copies each)

- BLM Form 3160-3
- OCD Form C-102 (Well Location and Acreage Dedication Plat)
- Unit plat with 1-mile radius shown
- Drilling Program
- Drilling Rig Layout
- BOP & Choke Manifold Diagrams (includes request for variance)
- Copy of OCD Form C-144 (Pit or Below-Grade Tank Registration or Closure) – the original has been filed with the OCD's Hobbs Office
- H2S Contingency Plan (includes request for variance)
- Surface Use and Operating Plan
- Lease Responsibility Statement
- Private Surface Owner's Agreement or Statement that an agreement has been reached concerning surface use

SPECIAL DRILLING STIPULATIONS

THE FOLLOWING DATA IS REQUIRED ON THE WELL SIGN

Operator's Name Occidental Permian Limited Partnership Well Name & No. North Hobbs G/SA Unit #712
Location 2378 F N L & 1086 F W L Sec. 29, T. 18 S, R. 38 E.
Lease No. LC-032233-A County Lea State New Mexico

The Special stipulations check marked below are applicable to the above described well and approval of this application to drill is conditioned upon compliance with such stipulations in addition to the General Requirements. The permittee should be familiar with the General Requirements, a copy of which is available from a Bureau of Land Management office. EACH PERMITTEE HAS THE RIGHT OF ADMINISTRATIVE APPEAL TO THESE STIPULATIONS PURSUANT TO TITLE 43 CRF 3165.3 AND 3165.4.

This permit is valid for a period of one year from the date of approval or until lease expiration or termination whichever is shorter.

I. SPECIAL ENVIRONMENT REQUIREMENTS

- () Lesser Prairie Chicken (stips attached) () Flood plain (stips attached)
() San Simon Swale (stips attached) () Other

II. ON LEASE - SURFACE REQUIREMENTS PRIOR TO DRILLING

(X) The BLM will monitor construction of this drill site. Notify the (X) Carlsbad Field Office at (505) 234-5972 () Hobbs Office (505) 393-3612, at least 3 working days prior to commencing construction.

(X) Roads and the drill pad for this well must be surfaced with 6 inches of compacted caliche upon completion of well and it is determined to be a producer.

() All topsoil and vegetation encountered during the construction of the drill site area will be stockpiled and made available for resurfacing of the disturbed area after completion of the drilling operation. Topsoil on the subject location is approximately _____ inches in depth. Approximately _____ cubic yards of topsoil material will be stockpiled for reclamation.

() Other.

III. WELL COMPLETION REQUIREMENTS

() A Communitization Agreement covering the acreage dedicated to the well must be filed for approval with the BLM. The effective date of the agreement must be prior to any sales.

(x) Surface Restoration: If the well is a producer, the reserve pit(s) will be backfilled when dry, and cut-and-fill slopes will be reduced to a slope of 3:1 or less. All areas of the pad not necessary for production must be re-contoured to resemble the original contours of the surrounding terrain, and topsoil must be re-distributed and re-seeded with a drill equipped with a depth indicator (set at depth of 1/2 inch) with the following seed mixture, in pounds of Pure Live Seed (PLS), per acre.

(X) A. Seed Mixture 1 (Loamy Sites)
Side Oats Grama (*Bouteloua curtipendula*) 5.0
Sand Dropseed (*Sporobolus cryptandrus*) 1.0

() B. Seed Mixture 2 (Sandy Sites)
Sand Dropseed (*Sporobolus crptandrus*) 1.0
Sand Lovegrass (*Eragostis trichodes*) 1.0
Plains Bristlegrass (*Setaria magrostachya*) 2.0

() C. Seed Mixture 3 (Shallow Sites)
Side oats Grama (*Boute curtipendula*) 1.0

() D. Seed Mixture 4 (Gypsum Sites)
Alkali Sacaton (*Sporobolud airoides*) 1.0
Four-Wing Saltbush (*Atriplex canescens*) 5.0

() OTHER SEE ATTACHED SEED MIXTURE

Seeding should be done either late in the fall (September 15 - November 15, before freeze up, or early as possible the following spring to take advantage of available ground moisture.

() Other.

RESERVE PIT CONSTRUCTION STANDARDS

- The reserve pit shall be constructed entirely in cut material and lined with 6 mil plastic. Mineral material extracted from within the boundary of the APD during construction of the well pad and reserve pits and be used for the construction of this well pad and its immediate access road only, as long as that portion of the access road it is use on remains on-lease. Removal of any additional material from this location for construction or improvement of other well pads and other access or lease roads must first be purchased from BLM.

Reclamation: Reclamation of this type of deep pit will consist of pushing the pit walls into the pit when sufficiently dry to support track equipment. The pit liner is NOT TO BE RUPTURED to facilitate drying; a ten month period after completion of the well is allowed for drying of the pit contents.

The pit area must be contoured to the natural terrain with all contaminated drilling mud buried with at least 3 feet of clean soil. The reclaimed area will then be seeded as specified in this permit.

OPTIONAL PIT CONSTRUCTION STANDARDS

The reserve pit may be constructed in predominantly fill material if:

- (1) Lined as specified above and
- (2) A temporary or emergency pit may be constructed immediately adjacent to the reserve pit as long as the pit remains within the APD boundary. Mineral material removed from this pit may be used for the construction of this well pad only and its immediate access road, as long as that portion of the access road the material is used on remains on-lease. Removal of any material from the APD boundary for use on other well locations or roads must first be purchased from BLM.

Reclamation of the reserve pit consists of bulldozing all reserve pit contents and contaminants into the borrow pit and covering with a minimum of 3 feet of clean soil material. The entire area must be recontoured, all trash removed, and reseeded as specified in this permit.

CULTURAL

Whether or not an archaeological survey has been completed and notwithstanding that operations are being conducted as approved, the lessee/operator/grantee shall notify the BLM immediately if previously unidentified cultural resources are observed during surface disturbing operations. From the time of the observation, the lessee/operator/grantee shall avoid operations that will result in disturbance to these cultural resources until directed to processed by BLM.

TRASH PIT STIPS

All trash, junk, and other waste material shall be contained in trash cages or bins to prevent scattering and will be removed and deposited in an approved sanitary landfill. Burial on site is not permitted.

CONDITIONS OF APPROVAL - DRILLING

Operator's Name: Occidental Permian Limited Partnership
Well Name & No: North Hobbs G/SA Unit No. 712
Location: Surface: 2378' FNL & 1086' FWL, Sec.29, T. 18 S. R. 38 E.
Lease: NMLC 032233-A
Lea County, New Mexico

.....

I. DRILLING OPERATIONS REQUIREMENTS:

1. The Bureau of Land Management (BLM) is to be notified at the Roswell Field Office, 2909 West Second St., Roswell, NM 88201, (505) 627-0272 for wells in Chaves and Roosevelt Counties; the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220, (505) 361-2822 for wells in Eddy County; and the Hobbs Field Station, 414 West Taylor, Hobbs NM 88240, (505) 393-3612 for wells in Lea County, in sufficient time for a representative to witness:
 - A. Spudding
 - B. Cementing casing: 8 5/8 inch; 5 1/2 inch;
 - C. BOP Tests
2. A Hydrogen Sulfide (H₂S) Drilling Plan shall be in operations three days or 500 feet prior to drilling into the Queen formation estimated to be at 3422 ft.
3. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval.
4. Submit a Sundry Notice (Form 3160-5, one original and five copies) for each casing string, describing the casing and cementing operations. Include pertinent information such as; spud date, hole size, casing (size, weight, grade and thread type), cement (type, quantity and top), water zones and problems or hazards encountered. The Sundry shall be submitted within 15 days of completion of each casing string. The reports may be combined into the same Sundry if they fall within the same 15 day time frame.
5. The API No. assigned to the well by NMOCD shall be included on the subsequent report of setting the first casing string.

II. CASING:

1. The 8 5/8 inch shall be set at 1540 Feet with cement circulated to the surface. If cement does not circulate to the surface the appropriate BLM office shall be notified and a temperature survey or cement bond log shall be run to verify the top of the cement. Remedial cementing shall be completed prior to drilling out that string.
2. The minimum required fill of cement behind the 5 1/2 inch Production casing is to circulate to surface.

III. PRESSURE CONTROL:

1. All BOP systems and related equipment shall comply with well control requirements as described in Onshore Oil and Gas Order No. 2. The BOP and related equipment shall be installed and operational before drilling below the 8 5/8 inch casing shoe and shall be tested as described in Onshore Order No. 2. Any equipment failing to test satisfactorily shall be repaired or replaced.
2. Minimum working pressure of the blowout preventer and related equipment (BOPE) shall be 2 M psi.

III. Pressure Control (continued):

3. The appropriate BLM office shall be notified in sufficient time for a representative to witness the test.

- The test shall be done by an independent service company
- The results of the test shall be reported to the appropriate BLM office.
- Testing fluid must be water or an appropriate clear liquid suitable for sub-freezing temperatures.
- Use of drilling mud for testing is not permitted since it can mask small leaks.
- Testing must be done in safe workman-like manner. Hard line connections shall be required.
- Both low pressure and high pressure testing of BOPE is required.

Ggourley 10/04/05

District I
1625 N. French Dr., Hobbs, NM 88240
District II
1301 W. Grand Avenue, Artesia, NM 88210
District III
1000 Rio Brazos Road, Aztec, NM 87410
District IV
1220 S. St. Francis Dr., Santa Fe, NM 87505

State of New Mexico
Energy Minerals and Natural Resources

Oil Conservation Division
1220 South St. Francis Dr.
Santa Fe, NM 87505

Form C-144
March 12, 2004

For drilling and production facilities, submit to appropriate NMOCD District Office.
For downstream facilities, submit to Santa Fe office

Pit or Below-Grade Tank Registration or Closure

Is pit or below-grade tank covered by a "general plan"? Yes ☐ No ☒

Type of action: Registration of a pit or below-grade tank ☒ Closure of a pit or below-grade tank ☐

Operator: Occidental Permian, LTD Telephone: 432.685.5683 e-mail address: fred_ray@oxy.com
Address: P.O. Box 50250, Midland, TX 79710
Facility or well name: NHU 29-712 API #: 30-025-37558 U/L "E" Sec 29 T 18-S R 38-E
County: Lea Latitude 32°43'08.51" N Longitude 103°10'30.85" W NAD: 1927 ☒ 1983 ☐ Surface Owner Federal ☒ State ☐ Private ☐ Indian ☐

Pit

Type: Drilling ☒ Production ☐ Disposal ☐

Workover ☐ Emergency ☐

Lined ☒ Unlined ☐

Liner type: Synthetic ☒ Thickness 12 mil Clay ☐ Volume 5,000 bbl

Below-grade tank

Volume: bbl Type of fluid:

Construction material:

Double-walled, with leak detection? Yes ☐ If not, explain why not.

Depth to ground water (vertical distance from bottom of pit to seasonal high water elevation of ground water.)

Less than 50 feet

(20 points)

50 feet or more, but less than 100 feet

(10 points) 10

100 feet or more

(0 points)

Wellhead protection area: (Less than 200 feet from a private domestic water source, or less than 1000 feet from all other water sources.)

Yes

(20 points) 20

No

(0 points)

Distance to surface water: (horizontal distance to all wetlands, playas, irrigation canals, ditches, and perennial and ephemeral watercourses.)

Less than 200 feet

(20 points)

200 feet or more, but less than 1000 feet

(10 points)

1000 feet or more

(0 points) 0

Ranking Score (Total Points)

30

If this is a pit closure: (1) attach a diagram of the facility showing the pit's relationship to other equipment and tanks. (2) Indicate disposal location:

onsite ☐ offsite ☐ If offsite, name of facility (3) Attach a general description of remedial action taken including remediation start date and end date. (4) Groundwater encountered: No ☐ Yes ☐ If yes, show depth below ground surface ft. and attach sample results. (5) Attach soil sample results and a diagram of sample locations and excavations.

I hereby certify that the information above is true and complete to the best of my knowledge and belief. I further certify that the above-described pit or below-grade tank has been/will be constructed or closed according to NMOCD guidelines ☒, a general permit ☐, or an (attached) alternative OCD-approved plan ☐.

Date: 08/15/2005

Printed Name/Title: Fred Ray / Drilling Specialist

Signature

Fred Ray

Your certification and NMOCD approval of this application/closure does not relieve the operator of liability should the contents of the pit or tank contaminate ground water or otherwise endanger public health or the environment. Nor does it relieve the operator of its responsibility for compliance with any other federal, state, or local laws and/or regulations

Approval:

Date: OCT 11 2005

ORIGINAL SIGNED BY:

PAUL F. KAUTZ

Printed Name/Title

PETROLEUM ENGINEER

Signature

Paul F. Kautz