

HOBBS OCD

MAY 16 2016

RECEIVED

SURFACE USE PLAN

Devon Energy Production Company, L.P.
Blue Krait 23 Fed 2H

- 1. Existing Roads:**
 - a. The well site and elevation plat for the proposed well are reflected on the "Site Map". The well was staked by Madron Surveying, Inc.
 - b. All roads into the location are depicted on the "Vicinity Map". The operator will repair pot holes, clear ditches, repair the crown, etc. All existing structures on the entire access route such as cattle guards, culverts, etc. will be properly repaired or replaced if they are damaged or have deteriorated beyond practical use. BLM written approval will be acquired before application of surfactants, binding agents, or other dust suppression chemicals on roadways.
 - c. Directions to Location: From State Highway 128 and CR J2 (Brininstool) go East on State Highway 128 1.9 miles, turn right on Caliche Road (Vaca) and go South-Southeast 1.1 miles, turn right and go West 265' to a proposed road survey and follow flags Northwest 117' then West 5396' to the proposed Southeast pad corner for this location.

- 2. New or Reconstructed Access Roads:**
 - a. The "Site Map" shows new constructed access road, which will be approximately 5513 LF from the existing Lease road.
 - b. The maximum driving width of the access road will be 14 feet. The maximum width of surface disturbance when constructing the access road will not exceed 25 feet. The road will be crowned and ditched with 2% slope from the tip of the crown to the edge of the driving surface. The ditches will be 3 feet wide with 3:1 slopes. The driving surface will be made of 6" rolled and compacted caliche.
 - c. No cattle guards, grates or fence cuts will be required. No turnouts are planned.

- 3. Location of Existing Wells:**

The attached "One Mile Radius Map" shows all existing and proposed wells within a one-mile radius of the proposed location.

- 4. Location of Existing and/or Proposed Production Facilities:**
 - a. In the event the well is found productive, a tank battery would be utilized and the necessary production equipment will be installed at the well site. The tank battery would be located at the Blue Krait 23 Fed 1H located in Sec 23-T24S-R33E. See "Proposed Plat Delaware Basin" diagram and "Proposed Interim Site Reclamation" diagram.
 - b. If necessary, the well will be operated by means of an electric prime mover. If electric power poles are needed, a plat and a sundry notice will be filed with your office.
 - c. All flow lines will adhere to API standards.
 - d. If the well is productive, rehabilitation plans are as follows:

- i. A closed loop system will be utilized.
- ii. The original topsoil from the well site will be returned to the location. The drill site will then be contoured as close as possible to the original state.

5. Location and Types of Water Supply:

This location will be drilled using a combination of water mud systems (outlined in the Drilling Program). The water will be obtained from commercial water stations in the area and hauled to location by transport truck using the existing and proposed roads described and depicted on the "Vicinity Map". On occasion, water will be obtained from a pre-existing water well, running a pump directly to the drill rig. In cases where a poly pipeline is used to transport water for drilling purposes, proper authorizations will be secured. If a poly pipeline is used, the size, distance, and map showing route will be provided to the BLM via sundry notice.

6. Construction Materials:

Obtaining caliche: One primary way of obtaining caliche to build locations and roads will be by "turning over" the location. This means caliche will be obtained from the actual well site. Actual amounts will vary for each pad. The procedure below has been approved by BLM personnel:

- a. The top 6 inches of topsoil is pushed off and stockpiled along the side of the location.
- b. Subsoil is removed and stockpiled within the surveyed well pad.
- c. When caliche is found, material will be stock piled within the pad site to build the location and road.
- d. Then subsoil is pushed back in the hole and caliche is spread accordingly across entire location and road.
- e. Once well is drilled, the stock piled top soil will be used for interim reclamation and spread along areas where caliche is picked up and the location size is reduced.
- f. Neither caliche, nor subsoil will be stock piled outside of the well pad. Topsoil will be stockpiled along the edge of the pad as depicted in the Well Site Layout or survey plat.

In the event that no caliche is found onsite, caliche will be hauled in from a BLM approved caliche pit or other established mineral pit. A BLM mineral material permit will be acquired prior to obtaining any mineral material from BLM pits or land.

7. Methods of Handling Waste Material:

- a. Drill cuttings will be safely contained in a closed loop system and disposed of properly at a NMOCD approved disposal site.
- b. All trash, junk and other waste material will be contained in trash cages or trash bins to prevent scattering. When the job is completed all contents will be removed and disposed of in an approved sanitary landfill.
- c. The supplier will pick up salts remaining after completion of well, including broken sacks.
- d. A Porto-john will be provided for the rig crews. This equipment will be properly maintained during the drilling and completion operations and will be removed when all operations are complete.
- e. Remaining drilling fluids will be sent to a closed loop system. Water produced during completion will be put into a closed loop system. Oil and condensate produced will be put into a storage tank and sold.

- f. Disposal of fluids to be transported by the following companies:
 - i. American Production Service Inc, Odessa TX
 - ii. Gandy Corporation, Lovington NM
 - iii. I & W Inc, Loco Hill NM
 - iv. Jims Water Service of Co Inc, Denver CO

8. **Ancillary Facilities:** No campsite or other facilities will be constructed as a result of this well.

9. **Well Site Layout**

- a. The Rig Location Layout attachment shows the proposed well site layout and pad dimensions.
- b. The Rig Location Layout attachment proposes location of sump pits and living facilities.
- c. Mud pits in the active circulating system will be steel pits.
- d. A closed loop system will be utilized.
- e. If a pit or closed loop system is utilized, Devon will provide a copy of the Design Plan to the BLM.

10. **Plans for Surface Reclamation:**

- a. After concluding the drilling and/or completion operations, if the well is found non-commercial, the caliche will be removed from the pad and transported to the original caliche pit or used for other drilling locations. The road will be reclaimed as directed by the BLM. The original top soil will again be returned to the pad and contoured, as close as possible, to the original topography.
- b. The location and road will be rehabilitated as recommended by the BLM.
- c. If the well is deemed commercially productive, caliche from areas of the pad site not required for operations will be reclaimed. The original top soil will be returned to the area of the drill pad not necessary to operate the well. These unused areas of the drill pad will be contoured, as close as possible, to match the original topography.
- d. All disturbed areas not needed for active support of production operations will undergo interim reclamation. The portions of the cleared well site not needed for operational and safety purposes will be recontoured to a final or intermediate contour that blends with the surrounding topography as much as possible. Topsoil will be respread over areas not needed for all-weather operations.

11. **Surface Ownership**

- a. The surface is owned by a Private Landowner and an agreement has been reached. The minerals are owned and administered by the U. S. Federal Government. The surface is multiple use with the primary uses of the region for the grazing of livestock and the production of oil and gas. Landowner information as follows:
 - Mark McCloy
 - PO BOX 1076
 - Jal, NM 88252
 - Telephone#: 432-940-4459
- b. The proposed road routes and the surface location will be restored as directed by the BLM.

12. Other Information:

- a. The area surrounding the well site is grassland. The topsoil is very sandy in nature. The vegetation is moderately sparse with native prairie grass, sage bush, yucca and miscellaneous weeds. No wildlife was observed but it is likely that deer, rabbits, coyotes, and rodents traverse the area.
- b. There is no permanent or live water in the general proximity of the location.
- c. There are no dwellings within 2 miles of location.
- d. A Cultural Resources Examination will be completed by Lone Mountain Archaeological Services, Inc. and forwarded to the BLM office in Carlsbad, New Mexico.

13. Bond Coverage:

Bond Coverage is Nationwide; Bond # is CO-1104 & NMB-000801.

Operators Representative:

The Devon Energy Production Company, L.P. representatives responsible for ensuring compliance of the surface use plan are listed below.

Trevor Klaassen - Completions Engineer
Devon Energy Production Company, L.P.
333 W. Sheridan
Oklahoma City, OK 73102-5010
(405) 552-5069 (office)
(405) 850-5870 (Cellular)

Don Mayberry - Superintendent
Devon Energy Production Company, L.P.
Post Office Box 250
Artesia, NM 88211-0250
(575) 748-3371 (office)
(575) 746-4945 (home)


Certification

I hereby certify that I, or persons under my direct supervision, have inspected the proposed drill site and access road proposed herein; that I am familiar with the conditions that presently exist; that I have full knowledge of State and Federal laws applicable to this operation; that the statements made in this APD package are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or Devon Energy Production Company, L.P. am responsible for the operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filing of false statements.

I hereby also certify that I, or Devon Energy Production Company, L.P. have made a good faith effort to provide the surface owner with a copy of the Surface Use Plan of Operations and any Conditions of Approval that are attached to the APD.

Executed this 20th day of January, 2015

Printed Name: David H. Cook

Signed Name: 

Position Title: Regulatory Compliance Professional

Address: 333 W. Sheridan, OKC OK 73102

Telephone: (405)-552-7848

Well-Site Evaluation Field Form

Operator: Devon Energy Production Company Fiscal Year: 2015 Onsite Type: Pre NOS

Well Name: Blue krait 23 Fed 2H Pre-NOS Date: 10/28/2014

SHL: S: 23, T.24S., R.33E., QTR/QTR: SHL: 200 FSL & 1980 FWL NOS Received Date: _____

BHL: S: 23, T.24S., R.33E., QTR/QTR: BHL: 200 FSL & 1980 FWL APD Received Date: _____

Project Lead: Dahal, Indra

Onsite Performed: 10/28/2014 Onsite Issues?: Yes No SME Contacted? Yes No Agency: BLM

Well Type: Oil Gas SWD Other: _____ Horizontal Vertical

Operator Representative: Joe Lara Contact Number: _____

BLM Onsite Representative: _____

Description of Topography (cut/fill):

Fairly flat along two tracks.

Soils: Sandy Loamy Gypsum Rocky

Vegetation:

Mesquite and grass

Cave/Karst: Critical High Medium Low

Hydrogeology (playas, floodplain, erosive soils, plant indicators):

There is private land owner's dirt tank to the east about 600-1000 of east.

Wildlife (LPC, SDL, Raptor Nest): LPC DSL Heronry Aplomado Falcon

Range Improvements (fences, etc.):

Pad Size: 350x420 V-door Direction: _____

Reserve Pit?: Yes No

Topsoil Placement: East NE North NW SE South SW West

Cut/Fill Diagram Required?: Yes No

New access road needed?: Yes No

Where will the access road enter the well pad?: SE Length of access road (ft): 1

Will the access road be crown and ditched?: Yes No

How many turnouts needed?: _____

How many cattleguards needed?: _____

Will a ROW be needed?: Yes Will a culvert be needed?: No

Will a low water crossing be needed?: No Will any lead-off ditches be needed?: No

Other info about the new road?: Yes

Explain: Party on private surface.

Two-track road need upgraded/reconstructed?: Yes No

Length of access road (ft): _____

Will the access road be crown ditched?: Yes No

Explain: _____

How many turnouts needed?: _____

How many cattleguards needed?: _____

Will a ROW be needed?: Yes No

Will a culvert be needed?: Yes No

Will a low water crossing be needed?: Yes No

Will any lead-off ditches be needed?: Yes No

How many lead-off ditches be needed?: _____

Other info about this road?: Yes No

Explain:

Will an existing road be used to access the well? (excludes county or state roads): Yes No

Is a tank battery planned to be located on site?: Yes No

Is a pipeline planned to be installed for this well?: Yes No

What sides of the well pad will receive interim reclamation?: E NE N NW SE S SW W

Other relevant information:

Private Surface- Mccloy.

Mitigation Measures/Stipulations:

Final Well Location: Same as Proposed Different Location

