

**XTOENERGY**

**XTO Energy Inc**

Lea County, NM (NAD27)

Ocioso 21 Federal Com

2H

Wellbore #2

Plan: Plan 1 05-01-15

**Standard Planning Report**

01 May, 2015

**HOBBS OCD**

**SEP 07 2016**

**RECEIVED**

**Database:** Compass 5000 GCR  
**Company:** XTO Energy Inc  
**Project:** Lea County, NM (NAD27)  
**Site:** Ocioso 21 Federal Com  
**Well:** 2H  
**Wellbore:** Wellbore #2  
**Design:** Plan 1 05-01-15

**Local Co-ordinate Reference:** Well 2H  
**TVD Reference:** RKB @ 3607.00usft (Noram 25)  
**MD Reference:** RKB @ 3607.00usft (Noram 25)  
**North Reference:** Grid  
**Survey Calculation Method:** Minimum Curvature

|                    |                                      |                      |                |
|--------------------|--------------------------------------|----------------------|----------------|
| <b>Project</b>     | Lea County, NM (NAD27)               |                      |                |
| <b>Map System:</b> | US State Plane 1927 (Exact solution) | <b>System Datum:</b> | Mean Sea Level |
| <b>Geo Datum:</b>  | NAD 1927 (NADCON CONUS)              |                      |                |
| <b>Map Zone:</b>   | New Mexico East 3001                 |                      |                |

|                              |                       |                     |                 |                          |                     |
|------------------------------|-----------------------|---------------------|-----------------|--------------------------|---------------------|
| <b>Site</b>                  | Ocioso 21 Federal Com |                     |                 |                          |                     |
| <b>Site Position:</b>        |                       | <b>Northing:</b>    | 595,808.50 usft | <b>Latitude:</b>         | 32° 38' 12.29691 N  |
| <b>From:</b>                 | Map                   | <b>Easting:</b>     | 671,150.90 usft | <b>Longitude:</b>        | 103° 46' 38.46509 W |
| <b>Position Uncertainty:</b> | 0.00 usft             | <b>Slot Radius:</b> | 13-3/16 "       | <b>Grid Convergence:</b> | 0.30 °              |

|                             |           |               |                            |                 |                                       |
|-----------------------------|-----------|---------------|----------------------------|-----------------|---------------------------------------|
| <b>Well</b>                 | 2H        |               |                            |                 |                                       |
| <b>Well Position</b>        | +N/-S     | 159.20 usft   | <b>Northing:</b>           | 595,967.70 usft | <b>Latitude:</b> 32° 38' 13.77913 N   |
|                             | +E/-W     | 1,788.50 usft | <b>Easting:</b>            | 672,939.40 usft | <b>Longitude:</b> 103° 46' 17.54038 W |
| <b>Position Uncertainty</b> | 0.00 usft |               | <b>Wellhead Elevation:</b> | 0.00 usft       | <b>Ground Level:</b> 3,582.00 usft    |

|                  |                   |                    |                            |                          |                                |
|------------------|-------------------|--------------------|----------------------------|--------------------------|--------------------------------|
| <b>Wellbore</b>  | Wellbore #2       |                    |                            |                          |                                |
| <b>Magnetics</b> | <b>Model Name</b> | <b>Sample Date</b> | <b>Declination<br/>(°)</b> | <b>Dip Angle<br/>(°)</b> | <b>Field Strength<br/>(nT)</b> |
|                  | HDGM              | 5/1/2015           | 7.40                       | 60.67                    | 48,622                         |

|                          |                                    |                         |                         |                          |      |
|--------------------------|------------------------------------|-------------------------|-------------------------|--------------------------|------|
| <b>Design</b>            | Plan 1 05-01-15                    |                         |                         |                          |      |
| <b>Audit Notes:</b>      |                                    |                         |                         |                          |      |
| <b>Version:</b>          | <b>Phase:</b>                      | PROTOTYPE               |                         | <b>Tie On Depth:</b>     | 0.00 |
| <b>Vertical Section:</b> | <b>Depth From (TVD)<br/>(usft)</b> | <b>+N/-S<br/>(usft)</b> | <b>+E/-W<br/>(usft)</b> | <b>Direction<br/>(°)</b> |      |
|                          | 0.00                               | 0.00                    | 0.00                    | 353.72                   |      |

| <b>Plan Sections</b>        |                    |                |                             |                 |                 |                               |                              |                             |            |        |
|-----------------------------|--------------------|----------------|-----------------------------|-----------------|-----------------|-------------------------------|------------------------------|-----------------------------|------------|--------|
| Measured<br>Depth<br>(usft) | Inclination<br>(°) | Azimuth<br>(°) | Vertical<br>Depth<br>(usft) | +N/-S<br>(usft) | +E/-W<br>(usft) | Dogleg<br>Rate<br>(°/100usft) | Build<br>Rate<br>(°/100usft) | Turn<br>Rate<br>(°/100usft) | TFO<br>(°) | Target |
| 0.00                        | 0.00               | 0.00           | 0.00                        | 0.00            | 0.00            | 0.00                          | 0.00                         | 0.00                        | 0.00       |        |
| 8,845.06                    | 0.00               | 0.00           | 8,845.06                    | 0.00            | 0.00            | 0.00                          | 0.00                         | 0.00                        | 0.00       |        |
| 9,749.66                    | 90.46              | 353.72         | 9,418.00                    | 574.09          | -63.20          | 10.00                         | 10.00                        | 0.00                        | 353.72     |        |
| 14,791.10                   | 90.46              | 353.72         | 9,377.52                    | 5,585.10        | -614.80         | 0.00                          | 0.00                         | 0.00                        | 0.00       | BHL_2H |

Database: Compass 5000 GCR  
 Company: XTO Energy Inc  
 Project: Lea County, NM (NAD27)  
 Site: Ocioco 21 Federal Com  
 Well: 2H  
 Wellbore: Wellbore #2  
 Design: Plan 1 05-01-15

Local Co-ordinate Reference: Well 2H  
 TVD Reference: RKB @ 3607.00usft (Noram 25)  
 MD Reference: RKB @ 3607.00usft (Noram 25)  
 North Reference: Grid  
 Survey Calculation Method: Minimum Curvature

## Planned Survey

| Measured Depth (usft)               | Inclination (°) | Azimuth (°) | Vertical Depth (usft) | +N/-S (usft) | +E/-W (usft) | Vertical Section (usft) | Dogleg Rate (°/100usft) | Build Rate (°/100usft) | Turn Rate (°/100usft) |
|-------------------------------------|-----------------|-------------|-----------------------|--------------|--------------|-------------------------|-------------------------|------------------------|-----------------------|
| 0.00                                | 0.00            | 0.00        | 0.00                  | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                   | 0.00                  |
| 880.00                              | 0.00            | 0.00        | 880.00                | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                   | 0.00                  |
| <b>Rustler</b>                      |                 |             |                       |              |              |                         |                         |                        |                       |
| 1,005.00                            | 0.00            | 0.00        | 1,005.00              | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                   | 0.00                  |
| <b>Top Salt</b>                     |                 |             |                       |              |              |                         |                         |                        |                       |
| 2,491.00                            | 0.00            | 0.00        | 2,491.00              | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                   | 0.00                  |
| <b>Base Salt</b>                    |                 |             |                       |              |              |                         |                         |                        |                       |
| 2,668.00                            | 0.00            | 0.00        | 2,668.00              | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                   | 0.00                  |
| <b>Yates</b>                        |                 |             |                       |              |              |                         |                         |                        |                       |
| 2,990.00                            | 0.00            | 0.00        | 2,990.00              | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                   | 0.00                  |
| <b>Seven Rivers</b>                 |                 |             |                       |              |              |                         |                         |                        |                       |
| 4,760.00                            | 0.00            | 0.00        | 4,760.00              | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                   | 0.00                  |
| <b>Delaware</b>                     |                 |             |                       |              |              |                         |                         |                        |                       |
| 5,817.00                            | 0.00            | 0.00        | 5,817.00              | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                   | 0.00                  |
| <b>Brushy Canyon</b>                |                 |             |                       |              |              |                         |                         |                        |                       |
| 7,293.00                            | 0.00            | 0.00        | 7,293.00              | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                   | 0.00                  |
| <b>Bone Spring</b>                  |                 |             |                       |              |              |                         |                         |                        |                       |
| 8,488.00                            | 0.00            | 0.00        | 8,488.00              | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                   | 0.00                  |
| <b>First Bone Spring Sand</b>       |                 |             |                       |              |              |                         |                         |                        |                       |
| 8,845.06                            | 0.00            | 0.00        | 8,845.06              | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                   | 0.00                  |
| <b>KOP, Begin 10.00°/100' Build</b> |                 |             |                       |              |              |                         |                         |                        |                       |
| 8,900.00                            | 5.49            | 353.72      | 8,899.92              | 2.62         | -0.29        | 2.63                    | 10.00                   | 10.00                  | 0.00                  |
| 9,000.00                            | 15.49           | 353.72      | 8,998.12              | 20.70        | -2.28        | 20.82                   | 10.00                   | 10.00                  | 0.00                  |
| 9,100.00                            | 25.49           | 353.72      | 9,091.67              | 55.45        | -6.10        | 55.79                   | 10.00                   | 10.00                  | 0.00                  |
| 9,200.00                            | 35.49           | 353.72      | 9,177.73              | 105.83       | -11.65       | 106.47                  | 10.00                   | 10.00                  | 0.00                  |
| 9,206.64                            | 36.16           | 353.72      | 9,183.11              | 109.69       | -12.07       | 110.36                  | 10.00                   | 10.00                  | 0.00                  |
| <b>Second Bone Spring Sand</b>      |                 |             |                       |              |              |                         |                         |                        |                       |
| 9,300.00                            | 45.49           | 353.72      | 9,253.68              | 170.29       | -18.75       | 171.32                  | 10.00                   | 10.00                  | 0.00                  |
| 9,400.00                            | 55.49           | 353.72      | 9,317.22              | 246.89       | -27.18       | 248.38                  | 10.00                   | 10.00                  | 0.00                  |
| 9,500.00                            | 65.49           | 353.72      | 9,366.40              | 333.29       | -36.69       | 335.30                  | 10.00                   | 10.00                  | 0.00                  |
| 9,600.00                            | 75.49           | 353.72      | 9,399.75              | 426.86       | -46.99       | 429.44                  | 10.00                   | 10.00                  | 0.00                  |
| 9,700.00                            | 85.49           | 353.72      | 9,416.25              | 524.77       | -57.77       | 527.94                  | 10.00                   | 10.00                  | 0.00                  |
| 9,749.66                            | 90.46           | 353.72      | 9,418.00              | 574.09       | -63.20       | 577.56                  | 10.00                   | 10.00                  | 0.00                  |
| <b>LP, Hold 90.46° Inc</b>          |                 |             |                       |              |              |                         |                         |                        |                       |
| 9,800.00                            | 90.46           | 353.72      | 9,417.60              | 624.13       | -68.70       | 627.90                  | 0.00                    | 0.00                   | 0.00                  |
| 9,900.00                            | 90.46           | 353.72      | 9,416.79              | 723.52       | -79.64       | 727.89                  | 0.00                    | 0.00                   | 0.00                  |
| 10,000.00                           | 90.46           | 353.72      | 9,415.99              | 822.92       | -90.59       | 827.89                  | 0.00                    | 0.00                   | 0.00                  |
| 10,100.00                           | 90.46           | 353.72      | 9,415.19              | 922.32       | -101.53      | 927.89                  | 0.00                    | 0.00                   | 0.00                  |
| 10,200.00                           | 90.46           | 353.72      | 9,414.38              | 1,021.71     | -112.47      | 1,027.88                | 0.00                    | 0.00                   | 0.00                  |
| 10,300.00                           | 90.46           | 353.72      | 9,413.58              | 1,121.11     | -123.41      | 1,127.88                | 0.00                    | 0.00                   | 0.00                  |
| 10,400.00                           | 90.46           | 353.72      | 9,412.78              | 1,220.50     | -134.35      | 1,227.88                | 0.00                    | 0.00                   | 0.00                  |
| 10,500.00                           | 90.46           | 353.72      | 9,411.97              | 1,319.90     | -145.29      | 1,327.87                | 0.00                    | 0.00                   | 0.00                  |
| 10,600.00                           | 90.46           | 353.72      | 9,411.17              | 1,419.30     | -156.23      | 1,427.87                | 0.00                    | 0.00                   | 0.00                  |
| 10,700.00                           | 90.46           | 353.72      | 9,410.37              | 1,518.69     | -167.18      | 1,527.87                | 0.00                    | 0.00                   | 0.00                  |
| 10,800.00                           | 90.46           | 353.72      | 9,409.57              | 1,618.09     | -178.12      | 1,627.86                | 0.00                    | 0.00                   | 0.00                  |
| 10,900.00                           | 90.46           | 353.72      | 9,408.76              | 1,717.49     | -189.06      | 1,727.86                | 0.00                    | 0.00                   | 0.00                  |
| 11,000.00                           | 90.46           | 353.72      | 9,407.96              | 1,816.88     | -200.00      | 1,827.86                | 0.00                    | 0.00                   | 0.00                  |
| 11,100.00                           | 90.46           | 353.72      | 9,407.16              | 1,916.28     | -210.94      | 1,927.85                | 0.00                    | 0.00                   | 0.00                  |
| 11,200.00                           | 90.46           | 353.72      | 9,406.35              | 2,015.68     | -221.88      | 2,027.85                | 0.00                    | 0.00                   | 0.00                  |
| 11,300.00                           | 90.46           | 353.72      | 9,405.55              | 2,115.07     | -232.82      | 2,127.85                | 0.00                    | 0.00                   | 0.00                  |
| 11,400.00                           | 90.46           | 353.72      | 9,404.75              | 2,214.47     | -243.77      | 2,227.84                | 0.00                    | 0.00                   | 0.00                  |
| 11,500.00                           | 90.46           | 353.72      | 9,403.95              | 2,313.86     | -254.71      | 2,327.84                | 0.00                    | 0.00                   | 0.00                  |

Database: Compass 5000 GCR  
 Company: XTO Energy Inc  
 Project: Lea County, NM (NAD27)  
 Site: Ocioco 21 Federal Com  
 Well: 2H  
 Wellbore: Wellbore #2  
 Design: Plan 1 05-01-15

Local Co-ordinate Reference: Well 2H  
 TVD Reference: RKB @ 3607.00usft (Noram 25)  
 MD Reference: RKB @ 3607.00usft (Noram 25)  
 North Reference: Grid  
 Survey Calculation Method: Minimum Curvature

## Planned Survey

| Measured Depth (usft) | Inclination (°) | Azimuth (°) | Vertical Depth (usft) | +N/-S (usft) | +E/-W (usft) | Vertical Section (usft) | Dogleg Rate (°/100usft) | Build Rate (°/100usft) | Turn Rate (°/100usft) |
|-----------------------|-----------------|-------------|-----------------------|--------------|--------------|-------------------------|-------------------------|------------------------|-----------------------|
| 11,600.00             | 90.46           | 353.72      | 9,403.14              | 2,413.26     | -265.65      | 2,427.84                | 0.00                    | 0.00                   | 0.00                  |
| 11,700.00             | 90.46           | 353.72      | 9,402.34              | 2,512.66     | -276.59      | 2,527.83                | 0.00                    | 0.00                   | 0.00                  |
| 11,800.00             | 90.46           | 353.72      | 9,401.54              | 2,612.05     | -287.53      | 2,627.83                | 0.00                    | 0.00                   | 0.00                  |
| 11,900.00             | 90.46           | 353.72      | 9,400.73              | 2,711.45     | -298.47      | 2,727.83                | 0.00                    | 0.00                   | 0.00                  |
| 12,000.00             | 90.46           | 353.72      | 9,399.93              | 2,810.85     | -309.41      | 2,827.83                | 0.00                    | 0.00                   | 0.00                  |
| 12,100.00             | 90.46           | 353.72      | 9,399.13              | 2,910.24     | -320.36      | 2,927.82                | 0.00                    | 0.00                   | 0.00                  |
| 12,200.00             | 90.46           | 353.72      | 9,398.32              | 3,009.64     | -331.30      | 3,027.82                | 0.00                    | 0.00                   | 0.00                  |
| 12,300.00             | 90.46           | 353.72      | 9,397.52              | 3,109.04     | -342.24      | 3,127.82                | 0.00                    | 0.00                   | 0.00                  |
| 12,400.00             | 90.46           | 353.72      | 9,396.72              | 3,208.43     | -353.18      | 3,227.81                | 0.00                    | 0.00                   | 0.00                  |
| 12,500.00             | 90.46           | 353.72      | 9,395.92              | 3,307.83     | -364.12      | 3,327.81                | 0.00                    | 0.00                   | 0.00                  |
| 12,600.00             | 90.46           | 353.72      | 9,395.11              | 3,407.22     | -375.06      | 3,427.81                | 0.00                    | 0.00                   | 0.00                  |
| 12,700.00             | 90.46           | 353.72      | 9,394.31              | 3,506.62     | -386.00      | 3,527.80                | 0.00                    | 0.00                   | 0.00                  |
| 12,800.00             | 90.46           | 353.72      | 9,393.51              | 3,606.02     | -396.95      | 3,627.80                | 0.00                    | 0.00                   | 0.00                  |
| 12,900.00             | 90.46           | 353.72      | 9,392.70              | 3,705.41     | -407.89      | 3,727.80                | 0.00                    | 0.00                   | 0.00                  |
| 13,000.00             | 90.46           | 353.72      | 9,391.90              | 3,804.81     | -418.83      | 3,827.79                | 0.00                    | 0.00                   | 0.00                  |
| 13,100.00             | 90.46           | 353.72      | 9,391.10              | 3,904.21     | -429.77      | 3,927.79                | 0.00                    | 0.00                   | 0.00                  |
| 13,200.00             | 90.46           | 353.72      | 9,390.30              | 4,003.60     | -440.71      | 4,027.79                | 0.00                    | 0.00                   | 0.00                  |
| 13,300.00             | 90.46           | 353.72      | 9,389.49              | 4,103.00     | -451.65      | 4,127.78                | 0.00                    | 0.00                   | 0.00                  |
| 13,400.00             | 90.46           | 353.72      | 9,388.69              | 4,202.40     | -462.59      | 4,227.78                | 0.00                    | 0.00                   | 0.00                  |
| 13,500.00             | 90.46           | 353.72      | 9,387.89              | 4,301.79     | -473.54      | 4,327.78                | 0.00                    | 0.00                   | 0.00                  |
| 13,600.00             | 90.46           | 353.72      | 9,387.08              | 4,401.19     | -484.48      | 4,427.77                | 0.00                    | 0.00                   | 0.00                  |
| 13,700.00             | 90.46           | 353.72      | 9,386.28              | 4,500.59     | -495.42      | 4,527.77                | 0.00                    | 0.00                   | 0.00                  |
| 13,800.00             | 90.46           | 353.72      | 9,385.48              | 4,599.98     | -506.36      | 4,627.77                | 0.00                    | 0.00                   | 0.00                  |
| 13,900.00             | 90.46           | 353.72      | 9,384.68              | 4,699.38     | -517.30      | 4,727.76                | 0.00                    | 0.00                   | 0.00                  |
| 14,000.00             | 90.46           | 353.72      | 9,383.87              | 4,798.77     | -528.24      | 4,827.76                | 0.00                    | 0.00                   | 0.00                  |
| 14,100.00             | 90.46           | 353.72      | 9,383.07              | 4,898.17     | -539.18      | 4,927.76                | 0.00                    | 0.00                   | 0.00                  |
| 14,200.00             | 90.46           | 353.72      | 9,382.27              | 4,997.57     | -550.13      | 5,027.75                | 0.00                    | 0.00                   | 0.00                  |
| 14,300.00             | 90.46           | 353.72      | 9,381.46              | 5,096.96     | -561.07      | 5,127.75                | 0.00                    | 0.00                   | 0.00                  |
| 14,400.00             | 90.46           | 353.72      | 9,380.66              | 5,196.36     | -572.01      | 5,227.75                | 0.00                    | 0.00                   | 0.00                  |
| 14,500.00             | 90.46           | 353.72      | 9,379.86              | 5,295.76     | -582.95      | 5,327.74                | 0.00                    | 0.00                   | 0.00                  |
| 14,600.00             | 90.46           | 353.72      | 9,379.05              | 5,395.15     | -593.89      | 5,427.74                | 0.00                    | 0.00                   | 0.00                  |
| 14,700.00             | 90.46           | 353.72      | 9,378.25              | 5,494.55     | -604.83      | 5,527.74                | 0.00                    | 0.00                   | 0.00                  |
| 14,791.10             | 90.46           | 353.72      | 9,377.52              | 5,585.10     | -614.80      | 5,618.84                | 0.00                    | 0.00                   | 0.00                  |
| TD at 14791.10' MD    |                 |             |                       |              |              |                         |                         |                        |                       |

## Design Targets

| Target Name                                                                                  | Dip Angle (°) | Dip Dir. (°) | TVD (usft) | +N/-S (usft) | +E/-W (usft) | Northing (usft) | Easting (usft) | Latitude           | Longitude           |
|----------------------------------------------------------------------------------------------|---------------|--------------|------------|--------------|--------------|-----------------|----------------|--------------------|---------------------|
| - hit/miss target                                                                            |               |              |            |              |              |                 |                |                    |                     |
| - Shape                                                                                      |               |              |            |              |              |                 |                |                    |                     |
| BHL_2H                                                                                       | -0.46         | 353.72       | 9,377.52   | 5,585.10     | -614.80      | 601,552.80      | 672,324.60     | 32° 39' 9.07715 N  | 103° 46' 24.38564 W |
| - plan hits target center                                                                    |               |              |            |              |              |                 |                |                    |                     |
| - Rectangle (sides W100.00 H5,041.44 D0.00)                                                  |               |              |            |              |              |                 |                |                    |                     |
| TP2_2H                                                                                       | 0.00          | 0.01         | 9,378.57   | 5,455.20     | -600.50      | 601,422.90      | 672,338.90     | 32° 39' 7.79101 N  | 103° 46' 24.22640 W |
| - plan hits target center                                                                    |               |              |            |              |              |                 |                |                    |                     |
| - Point                                                                                      |               |              |            |              |              |                 |                |                    |                     |
| TP1_2H                                                                                       | 0.00          | 0.00         | 9,415.94   | 829.60       | -91.30       | 596,797.30      | 672,848.10     | 32° 38' 21.99300 N | 103° 46' 18.55678 W |
| - plan misses target center by 0.02usft at 10006.72usft MD (9415.94 TVD, 829.60 N, -91.32 E) |               |              |            |              |              |                 |                |                    |                     |
| - Point                                                                                      |               |              |            |              |              |                 |                |                    |                     |

Database: Compass 5000 GCR  
 Company: XTO Energy Inc  
 Project: Lea County, NM (NAD27)  
 Site: Ocio 21 Federal Com  
 Well: 2H  
 Wellbore: Wellbore #2  
 Design: Plan 1 05-01-15

Local Co-ordinate Reference: Well 2H  
 TVD Reference: RKB @ 3607.00usft (Noram 25)  
 MD Reference: RKB @ 3607.00usft (Noram 25)  
 North Reference: Grid  
 Survey Calculation Method: Minimum Curvature

Formations

| Measured Depth (usft) | Vertical Depth (usft) | Name                    | Lithology | Dip (°) | Dip Direction (°) |
|-----------------------|-----------------------|-------------------------|-----------|---------|-------------------|
| 880.00                | 880.00                | Rustler                 |           | -0.46   | 353.72            |
| 1,005.00              | 1,005.00              | Top Salt                |           | -0.46   | 353.72            |
| 2,491.00              | 2,491.00              | Base Salt               |           | -0.46   | 353.72            |
| 2,668.00              | 2,668.00              | Yates                   |           | -0.46   | 353.72            |
| 2,990.00              | 2,990.00              | Seven Rivers            |           | -0.46   | 353.72            |
| 4,760.00              | 4,760.00              | Delaware                |           | -0.46   | 353.72            |
| 5,817.00              | 5,817.00              | Brushy Canyon           |           | -0.46   | 353.72            |
| 7,293.00              | 7,293.00              | Bone Spring             |           | -0.46   | 353.72            |
| 8,488.00              | 8,488.00              | First Bone Spring Sand  |           | -0.46   | 353.72            |
| 9,206.64              | 9,183.11              | Second Bone Spring Sand |           | -0.46   | 353.72            |

Plan Annotations

| Measured Depth (usft) | Vertical Depth (usft) | Local Coordinates |              | Comment                      |
|-----------------------|-----------------------|-------------------|--------------|------------------------------|
|                       |                       | +N/-S (usft)      | +E/-W (usft) |                              |
| 8,845.06              | 8,845.06              | 0.00              | 0.00         | KOP, Begin 10.00°/100' Build |
| 9,749.66              | 9,418.00              | 574.09            | -63.20       | LP, Hold 90.46° Inc          |
| 14,791.10             | 9,377.52              | 5,585.10          | -614.80      | TD at 14791.10' MD           |