

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

OCD Hobbs

FORM APPROVED  
OMB NO. 1004-0137  
Expires: January 31, 2018

**SUNDRY NOTICES AND REPORTS ON WELLS**  
*Do not use this form for proposals to drill or to re-enter an abandoned well. Use form 3160-3 (APD) for such proposals.*

5. Lease Serial No.  
NMLC032096A

6. If Indian, Allottee or Tribe Name

**SUBMIT IN TRIPLICATE - Other instructions on page 2**

7. If Unit or CA/Agreement, Name and/or No.  
NMMN120042X

1. Type of Well  
 Oil Well  Gas Well  Other

8. Well Name and No.  
WEST BLINEBRY DRINKARD UNIT 221 ✓

2. Name of Operator  
APACHE CORPORATION

Contact: **SORINA FLORES**  
E-Mail: **sorina.flores@apachecorp.com**

9. API Well No.  
30-025-42496-00-X1

3a. Address  
303 VETERANS AIRPARK LANE SUITE 3000  
MIDLAND, TX 79705

3b. Phone No. (include area code)  
Ph: 432-818-1167

10. Field and Pool or Exploratory Area  
EUNICE

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)  
Sec 17 T21S R37E NESE 2300FSL 500FEL  
32.477865 N Lat, 103.177746 W Lon

11. County or Parish, State  
LEA COUNTY, NM

**12. CHECK THE APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA**

TYPE OF SUBMISSION	TYPE OF ACTION			
<input checked="" type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Hydraulic Fracturing	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other Onshore Order Variance
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operation: Clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomplete horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports must be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 must be filed once testing has been completed. Final Abandonment Notices must be filed only after all requirements, including reclamation, have been completed and the operator has determined that the site is ready for final inspection.

BLM-CO-1463 NATIONWIDE; NMB000736

APACHE REQUESTS A VARIANCE TO USE A FLEX LINE BETWEEN BOP AND CHOKE MANIFOLD

Manufacturer: Midwest Hose & Specialty, Inc  
Length: 20'  
LD: 4" OD: 5.80" Die Size: 6.38"  
WP rating: 5000psi  
Test Pressure: 7500psi

See Attachment for additional information.

SEE ATTACHED FOR  
CONDITIONS OF APPROVAL

14. I hereby certify that the foregoing is true and correct.

Electronic Submission #365817 verified by the BLM Well Information System  
For APACHE CORPORATION, sent to the Hobbs  
Committed to AFMSS for processing by PRISCILLA PEREZ on 02/06/2017 (17PP0204SE)

Name (Printed/Typed) **SORINA FLORES**

Title **SUBMITTING CONTACT**

Signature (Electronic Submission)

Date **02/03/2017**

**THIS SPACE FOR FEDERAL OR STATE OFFICE USE**

Approved By *[Signature]*

Title **Eng**

Date **2/7/17**

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office **CFO**

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on page 2)

**\*\* BLM REVISED \*\* BLM REVISED \*\* BLM REVISED \*\* BLM REVISED \*\* BLM REVISED \*\***

*[Signature]*



Midwest Hose  
& Specialty, Inc.

## Internal Hydrostatic Test Graph

January 30, 2017

Customer: Odessa


Pick Ticket #: 381942

### Hose Specifications

Hose Type	Length
Ck	20'
I.D.	Q.D.
4"	5.80"
<u>Working Pressure</u>	<u>Burst Pressure</u>
5000 PSI	Standard Safety Multiplier Applies

### Verification

Type of Fitting	Coupling Method
4" T	Swage
<u>Die Size</u>	<u>Final O.D.</u>
6.38"	6.43"
<u>Hose Serial #</u>	<u>Hose Assembly Serial #</u>
12442	381942



Test Pressure  
7500 PSI

Time Held at Test Pressure  
10 2/4 Minutes

Actual Burst Pressure

Peak Pressure  
8173 PSI

**Comments:** Hose assembly pressure tested with water at ambient temperature.

**Tested By:** Richard Davis

**Approved By:** Charles Ash

x

x



Midwest Hose  
& Specialty, Inc.

### Certificate of Conformity

Customer: <b>ODESSA</b>	Customer P.O.# <b>354159</b>
Sales Order # <b>316492</b>	Date Assembled: <b>1/30/2017</b>

### Specifications

Hose Assembly Type: <b>Choke &amp; Kill</b>	Rig #
Assembly Serial # <b>381942</b>	Hose Lot # and Date Code <b>12442-12/15</b>
Hose Working Pressure (psi) <b>5000</b>	Test Pressure (psi) <b>7500</b>
Hose Assembly Description:	<b>CK64-SS-5K-164-164-20.00' FT</b>

We hereby certify that the above material supplied for the referenced purchase order to be true according to the requirements of the purchase order and current industry standards.

Supplier:

**Midwest Hose & Specialty, Inc.**  
**3312 S I-35 Service Rd**  
**Oklahoma City, OK 73129**

Comments:

Approved By	Date
<i>Charles Ash</i>	<b>1/31/2017</b>



Midwest Hose  
& Specialty, Inc.

### Internal Hydrostatic Test Certificate

General Information		Hose Specifications	
Customer	ODESSA	Hose Assembly Type	Choke & Kill
MWH Sales Representative	CHARLES ASH	Certification	API 7K/FSL LEVEL2
Date Assembled	1/30/2017	Hose Grade	D
Location Assembled	OKC	Hose Working Pressure	5000
Sales Order #	316492	Hose Lot # and Date Code	12442-12/15
Customer Purchase Order #	354159	Hose I.D. (Inches)	4"
Assembly Serial # (Pick Ticket #)	381942	Hose O.D. (Inches)	6.30"
Hose Assembly Length	20FT	Armor (yes/no)	YES
Fittings			
End A		End B	
Stem (Part and Revision #)	R4.OX64T	Stem (Part and Revision #)	R4.OX64T
Stem (Heat #)	40832490	Stem (Heat #)	40832490
Ferrule (Part and Revision #)	RF4.OX6370	Ferrule (Part and Revision #)	RF4.OX6370
Ferrule (Heat #)	12607	Ferrule (Heat #)	12607
Connection . Flange Hammer Union Part		Connection (Part #)	
Connection (Heat #)		Connection (Heat #)	
Nut (Part #)		Nut (Part #)	
Nut (Heat #)		Nut (Heat #)	
Dies Used	6.38"	Dies Used	6.38"
Hydrostatic Test Requirements			
Test Pressure (psi)	7,500	Hose assembly was tested with ambient water temperature.	
Test Pressure Hold Time (minutes)	10 1/2		
<b>Date Tested</b>	<b>Tested By</b>	<b>Approved By</b>	
1/30/2017	<i>Pieheres Davis</i>	<i>Charles Ash</i>	

Co-Flex line  
Conditions of Approval

Variance approved to use flex line from BOP to choke manifold. Check condition of flexible line from BOP to choke manifold, replace if exterior is damaged or if line fails test. Line to be as straight as possible with no hard bends and is to be anchored according to Manufacturer's requirements. The flexible hose can be exchanged with a hose of equal size and equal or greater pressure rating. **Anchor requirements, specification sheet and hydrostatic pressure test certification matching the hose in service, to be onsite for review.** If the BLM inspector questions the straightness of the hose, a BLM engineer will be contacted and will review in the field or via picture supplied by inspector to determine if changes are required (operator shall expect delays if this occurs).