

30-025-48492

PRIDE ENERGY COMPANY
LEADING THE OIL AND GAS INDUSTRY

Pride Energy Company

Lea County, New Mexico (NAD 83)

Paduca "16" State

703H

Wellbore #1

Plan: Design #1

Standard Planning Report

15 February, 2018



Database:	5000.1 Conroe DB	Local Co-ordinate Reference:	Well 703H
Company:	Pride Energy Company	TVD Reference:	WELL @ 3447.00usft
Project:	Lea County, New Mexico (NAD 83)	MD Reference:	WELL @ 3447.00usft
Site:	Paduca "16" State	North Reference:	Grid
Well:	703H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Design #1		

Project	Lea County, New Mexico (NAD 83)		
Map System:	US State Plane 1983	System Datum:	Mean Sea Level
Geo Datum:	North American Datum 1983		
Map Zone:	New Mexico Central Zone		

Well	703H			
Well Position	+N/-S	-12.52 usft	Northing:	414,231.50 usft
	+E/-W	-1,023.12 usft	Easting:	742,991.46 usft
Position Uncertainty	0.00 usft		Wellhead Elevation:	
			Latitude:	32° 6' 20.292 N
			Longitude:	109° 8' 52.239 W
			Ground Level:	3,427.00 usft

Wellbore	Wellbore #1				
Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	BGGM2017	2/2/2018	9.16	58.91	47,089

Design	Design #1			
Audit Notes:				
Version:	Phase:	PLAN	Tie On Depth:	0.00
Vertical Section:	Depth From (TVD) (usft)	+N/-S (usft)	+E/-W (usft)	Direction (°)
	0.00	0.00	0.00	177.25

Plan Survey Tool Program	Date 2/15/2018			
Depth From (usft)	Depth To (usft)	Survey (Wellbore)	Tool Name	Remarks
1	0.00	16,766.39	Design #1 (Wellbore #1)	MWD
				OWSG MWD - Standard

Plan Sections										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	TFO (°)	Target
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
2,000.00	0.00	0.00	2,000.00	0.00	0.00	0.00	0.00	0.00	0.00	
2,100.00	2.00	360.00	2,099.98	1.75	0.00	2.00	2.00	0.00	360.00	
5,400.00	2.00	360.00	5,397.97	116.91	0.00	0.00	0.00	0.00	0.00	
5,533.33	0.00	0.00	5,531.28	119.24	0.00	1.50	-1.50	0.00	180.00	
8,669.00	0.00	0.00	8,666.94	119.24	0.00	0.00	0.00	0.00	0.00	
8,919.17	5.00	73.07	8,916.80	122.42	10.44	2.00	2.00	0.00	73.07	
11,125.29	5.00	73.07	11,114.51	178.46	194.51	0.00	0.00	0.00	0.00	
11,458.86	0.00	0.00	11,447.65	182.70	208.44	1.50	-1.50	0.00	180.00	VP - Paduca "16" S
11,558.86	0.00	0.00	11,547.65	182.70	208.44	0.00	0.00	0.00	0.00	
12,298.17	88.72	179.77	12,025.00	-284.08	210.27	12.00	12.00	24.32	179.77	
16,766.39	88.72	179.77	12,125.00	-4,751.15	227.85	0.00	0.00	0.00	0.00	PBHL - Paduca "16"

Database:	5000.1 Conroe DB	Local Co-ordinate Reference:	Well 703H
Company:	Pride Energy Company	TVD Reference:	WELL @ 3447.00usft
Project:	Lea County, New Mexico (NAD 83)	MD Reference:	WELL @ 3447.00usft
Site:	Paduca "16" State	North Reference:	Grid
Well:	703H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Design #1		

Planned Survey									
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
100.00	0.00	0.00	100.00	0.00	0.00	0.00	0.00	0.00	0.00
200.00	0.00	0.00	200.00	0.00	0.00	0.00	0.00	0.00	0.00
300.00	0.00	0.00	300.00	0.00	0.00	0.00	0.00	0.00	0.00
400.00	0.00	0.00	400.00	0.00	0.00	0.00	0.00	0.00	0.00
500.00	0.00	0.00	500.00	0.00	0.00	0.00	0.00	0.00	0.00
600.00	0.00	0.00	600.00	0.00	0.00	0.00	0.00	0.00	0.00
700.00	0.00	0.00	700.00	0.00	0.00	0.00	0.00	0.00	0.00
800.00	0.00	0.00	800.00	0.00	0.00	0.00	0.00	0.00	0.00
900.00	0.00	0.00	900.00	0.00	0.00	0.00	0.00	0.00	0.00
1,000.00	0.00	0.00	1,000.00	0.00	0.00	0.00	0.00	0.00	0.00
1,100.00	0.00	0.00	1,100.00	0.00	0.00	0.00	0.00	0.00	0.00
1,200.00	0.00	0.00	1,200.00	0.00	0.00	0.00	0.00	0.00	0.00
1,300.00	0.00	0.00	1,300.00	0.00	0.00	0.00	0.00	0.00	0.00
1,400.00	0.00	0.00	1,400.00	0.00	0.00	0.00	0.00	0.00	0.00
1,500.00	0.00	0.00	1,500.00	0.00	0.00	0.00	0.00	0.00	0.00
1,600.00	0.00	0.00	1,600.00	0.00	0.00	0.00	0.00	0.00	0.00
1,700.00	0.00	0.00	1,700.00	0.00	0.00	0.00	0.00	0.00	0.00
1,800.00	0.00	0.00	1,800.00	0.00	0.00	0.00	0.00	0.00	0.00
1,900.00	0.00	0.00	1,900.00	0.00	0.00	0.00	0.00	0.00	0.00
2,000.00	0.00	0.00	2,000.00	0.00	0.00	0.00	0.00	0.00	0.00
KOP, 2.00°/100' Build									
2,100.00	2.00	360.00	2,099.98	1.75	0.00	-1.74	2.00	2.00	0.00
Hold 2.00° Inc, 360.00° Azm									
2,200.00	2.00	360.00	2,199.92	5.24	0.00	-5.23	0.00	0.00	0.00
2,300.00	2.00	360.00	2,299.86	8.73	0.00	-8.72	0.00	0.00	0.00
2,400.00	2.00	360.00	2,399.80	12.22	0.00	-12.20	0.00	0.00	0.00
2,500.00	2.00	360.00	2,499.74	15.70	0.00	-15.69	0.00	0.00	0.00
2,600.00	2.00	360.00	2,599.68	19.19	0.00	-19.17	0.00	0.00	0.00
2,700.00	2.00	360.00	2,699.61	22.68	0.00	-22.66	0.00	0.00	0.00
2,800.00	2.00	360.00	2,799.55	26.17	0.00	-26.14	0.00	0.00	0.00
2,900.00	2.00	360.00	2,899.49	29.66	0.00	-29.63	0.00	0.00	0.00
3,000.00	2.00	360.00	2,999.43	33.15	0.00	-33.12	0.00	0.00	0.00
3,100.00	2.00	360.00	3,099.37	36.64	0.00	-36.60	0.00	0.00	0.00
3,200.00	2.00	360.00	3,199.31	40.13	0.00	-40.09	0.00	0.00	0.00
3,300.00	2.00	360.00	3,299.25	43.62	0.00	-43.57	0.00	0.00	0.00
3,400.00	2.00	360.00	3,399.19	47.11	0.00	-47.06	0.00	0.00	0.00
3,500.00	2.00	360.00	3,499.13	50.60	0.00	-50.55	0.00	0.00	0.00
3,600.00	2.00	360.00	3,599.07	54.09	0.00	-54.03	0.00	0.00	0.00
3,700.00	2.00	360.00	3,699.01	57.58	0.00	-57.52	0.00	0.00	0.00
3,800.00	2.00	360.00	3,798.94	61.07	0.00	-61.00	0.00	0.00	0.00
3,900.00	2.00	360.00	3,898.88	64.56	0.00	-64.49	0.00	0.00	0.00
4,000.00	2.00	360.00	3,998.82	68.05	0.00	-67.98	0.00	0.00	0.00
4,100.00	2.00	360.00	4,098.76	71.54	0.00	-71.46	0.00	0.00	0.00
4,200.00	2.00	360.00	4,198.70	75.03	0.00	-74.95	0.00	0.00	0.00
4,300.00	2.00	360.00	4,298.64	78.52	0.00	-78.43	0.00	0.00	0.00
4,400.00	2.00	360.00	4,398.58	82.01	0.00	-81.92	0.00	0.00	0.00
4,500.00	2.00	360.00	4,498.52	85.50	0.00	-85.41	0.00	0.00	0.00
4,600.00	2.00	360.00	4,598.46	88.99	0.00	-88.89	0.00	0.00	0.00
4,700.00	2.00	360.00	4,698.40	92.48	0.00	-92.38	0.00	0.00	0.00
4,800.00	2.00	360.00	4,798.34	95.97	0.00	-95.86	0.00	0.00	0.00
4,900.00	2.00	360.00	4,898.27	99.46	0.00	-99.35	0.00	0.00	0.00
5,000.00	2.00	360.00	4,998.21	102.95	0.00	-102.84	0.00	0.00	0.00

Database: 5000.1 Conroe DB
Company: Pride Energy Company
Project: Lea County, New Mexico (NAD 83)
Site: Paduca "16" State
Well: 703H
Wellbore: Wellbore #1
Design: Design #1

Local Co-ordinate Reference: Well 703H
TVD Reference: WELL @ 3447.00usft
MD Reference: WELL @ 3447.00usft
North Reference: Grid
Survey Calculation Method: Minimum Curvature

Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
5,100.00	2.00	360.00	5,098.15	106.44	0.00	-106.32	0.00	0.00	0.00
5,200.00	2.00	360.00	5,198.09	109.93	0.00	-109.81	0.00	0.00	0.00
5,300.00	2.00	360.00	5,298.03	113.42	0.00	-113.29	0.00	0.00	0.00
5,400.00	2.00	360.00	5,397.97	116.91	0.00	-116.78	0.00	0.00	0.00
Begin 1.50°/100' Drop									
5,500.00	0.50	360.00	5,497.94	119.09	0.00	-118.96	1.50	-1.50	0.00
5,533.33	0.00	0.00	5,531.28	119.24	0.00	-119.10	1.50	-1.50	0.00
Begin Vertical Hold									
5,600.00	0.00	0.00	5,597.94	119.24	0.00	-119.10	0.00	0.00	0.00
5,700.00	0.00	0.00	5,697.94	119.24	0.00	-119.10	0.00	0.00	0.00
5,800.00	0.00	0.00	5,797.94	119.24	0.00	-119.10	0.00	0.00	0.00
5,900.00	0.00	0.00	5,897.94	119.24	0.00	-119.10	0.00	0.00	0.00
6,000.00	0.00	0.00	5,997.94	119.24	0.00	-119.10	0.00	0.00	0.00
6,100.00	0.00	0.00	6,097.94	119.24	0.00	-119.10	0.00	0.00	0.00
6,200.00	0.00	0.00	6,197.94	119.24	0.00	-119.10	0.00	0.00	0.00
6,300.00	0.00	0.00	6,297.94	119.24	0.00	-119.10	0.00	0.00	0.00
6,400.00	0.00	0.00	6,397.94	119.24	0.00	-119.10	0.00	0.00	0.00
6,500.00	0.00	0.00	6,497.94	119.24	0.00	-119.10	0.00	0.00	0.00
6,600.00	0.00	0.00	6,597.94	119.24	0.00	-119.10	0.00	0.00	0.00
6,700.00	0.00	0.00	6,697.94	119.24	0.00	-119.10	0.00	0.00	0.00
6,800.00	0.00	0.00	6,797.94	119.24	0.00	-119.10	0.00	0.00	0.00
6,900.00	0.00	0.00	6,897.94	119.24	0.00	-119.10	0.00	0.00	0.00
7,000.00	0.00	0.00	6,997.94	119.24	0.00	-119.10	0.00	0.00	0.00
7,100.00	0.00	0.00	7,097.94	119.24	0.00	-119.10	0.00	0.00	0.00
7,200.00	0.00	0.00	7,197.94	119.24	0.00	-119.10	0.00	0.00	0.00
7,300.00	0.00	0.00	7,297.94	119.24	0.00	-119.10	0.00	0.00	0.00
7,400.00	0.00	0.00	7,397.94	119.24	0.00	-119.10	0.00	0.00	0.00
7,500.00	0.00	0.00	7,497.94	119.24	0.00	-119.10	0.00	0.00	0.00
7,600.00	0.00	0.00	7,597.94	119.24	0.00	-119.10	0.00	0.00	0.00
7,700.00	0.00	0.00	7,697.94	119.24	0.00	-119.10	0.00	0.00	0.00
7,800.00	0.00	0.00	7,797.94	119.24	0.00	-119.10	0.00	0.00	0.00
7,900.00	0.00	0.00	7,897.94	119.24	0.00	-119.10	0.00	0.00	0.00
8,000.00	0.00	0.00	7,997.94	119.24	0.00	-119.10	0.00	0.00	0.00
8,100.00	0.00	0.00	8,097.94	119.24	0.00	-119.10	0.00	0.00	0.00
8,200.00	0.00	0.00	8,197.94	119.24	0.00	-119.10	0.00	0.00	0.00
8,300.00	0.00	0.00	8,297.94	119.24	0.00	-119.10	0.00	0.00	0.00
8,400.00	0.00	0.00	8,397.94	119.24	0.00	-119.10	0.00	0.00	0.00
8,500.00	0.00	0.00	8,497.94	119.24	0.00	-119.10	0.00	0.00	0.00
8,600.00	0.00	0.00	8,597.94	119.24	0.00	-119.10	0.00	0.00	0.00
8,669.00	0.00	0.00	8,666.94	119.24	0.00	-119.10	0.00	0.00	0.00
Begin 2.00°/100' Build									
8,700.00	0.62	73.07	8,697.94	119.29	0.16	-119.14	2.00	2.00	0.00
8,800.00	2.62	73.07	8,797.90	120.11	2.86	-119.84	2.00	2.00	0.00
8,900.00	4.62	73.07	8,897.69	121.95	8.90	-121.38	2.00	2.00	0.00
8,919.17	5.00	73.07	8,916.80	122.42	10.44	-121.78	2.00	2.00	0.00
Hold 5.00° Inc, 73.07° Azm									
9,000.00	5.00	73.07	8,997.32	124.47	17.19	-123.51	0.00	0.00	0.00
9,100.00	5.00	73.07	9,096.94	127.01	25.53	-125.64	0.00	0.00	0.00
9,200.00	5.00	73.07	9,196.55	129.55	33.87	-127.78	0.00	0.00	0.00
9,300.00	5.00	73.07	9,296.17	132.09	42.22	-129.92	0.00	0.00	0.00
9,400.00	5.00	73.07	9,395.79	134.63	50.56	-132.06	0.00	0.00	0.00
9,500.00	5.00	73.07	9,495.41	137.17	58.90	-134.19	0.00	0.00	0.00
9,600.00	5.00	73.07	9,595.03	139.71	67.25	-136.33	0.00	0.00	0.00

Database:	5000.1 Conroe DB	Local Co-ordinate Reference:	Well 703H
Company:	Pride Energy Company	TVD Reference:	WELL @ 3447.00usft
Project:	Lea County, New Mexico (NAD 83)	MD Reference:	WELL @ 3447.00usft
Site:	Paduca "16" State	North Reference:	Grid
Well:	703H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Design #1		

Planned Survey									
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
9,700.00	5.00	73.07	9,694.65	142.25	75.59	-138.47	0.00	0.00	0.00
9,800.00	5.00	73.07	9,794.27	144.79	83.94	-140.61	0.00	0.00	0.00
9,900.00	5.00	73.07	9,893.89	147.33	92.28	-142.74	0.00	0.00	0.00
10,000.00	5.00	73.07	9,993.51	149.87	100.62	-144.88	0.00	0.00	0.00
10,100.00	5.00	73.07	10,093.13	152.41	108.97	-147.02	0.00	0.00	0.00
10,200.00	5.00	73.07	10,192.74	154.95	117.31	-149.16	0.00	0.00	0.00
10,300.00	5.00	73.07	10,292.36	157.49	125.65	-151.29	0.00	0.00	0.00
10,400.00	5.00	73.07	10,391.98	160.03	134.00	-153.43	0.00	0.00	0.00
10,500.00	5.00	73.07	10,491.60	162.57	142.34	-155.57	0.00	0.00	0.00
10,600.00	5.00	73.07	10,591.22	165.11	150.68	-157.71	0.00	0.00	0.00
10,700.00	5.00	73.07	10,690.84	167.65	159.03	-159.84	0.00	0.00	0.00
10,800.00	5.00	73.07	10,790.46	170.19	167.37	-161.98	0.00	0.00	0.00
10,900.00	5.00	73.07	10,890.08	172.73	175.71	-164.12	0.00	0.00	0.00
11,000.00	5.00	73.07	10,989.70	175.27	184.06	-166.26	0.00	0.00	0.00
11,100.00	5.00	73.07	11,089.31	177.81	192.40	-168.39	0.00	0.00	0.00
11,125.29	5.00	73.07	11,114.51	178.46	194.51	-168.93	0.00	0.00	0.00
Begin 1.50°/100' Drop									
11,200.00	3.88	73.07	11,188.99	180.14	200.05	-170.35	1.50	-1.50	0.00
11,300.00	2.38	73.07	11,288.84	181.73	205.28	-171.69	1.50	-1.50	0.00
11,400.00	0.88	73.07	11,388.80	182.56	208.00	-172.39	1.50	-1.50	0.00
11,458.86	0.00	0.00	11,447.65	182.70	208.44	-172.50	1.50	-1.50	0.00
Begin Vertical Hold									
11,500.00	0.00	0.00	11,488.79	182.70	208.44	-172.50	0.00	0.00	0.00
11,558.86	0.00	0.00	11,547.65	182.70	208.44	-172.50	0.00	0.00	0.00
Begin 12.00°/100' Build									
11,575.00	1.94	179.77	11,563.79	182.42	208.44	-172.23	12.00	12.00	0.00
11,600.00	4.94	179.77	11,588.74	180.92	208.44	-170.73	12.00	12.00	0.00
11,625.00	7.94	179.77	11,613.58	178.12	208.45	-167.93	12.00	12.00	0.00
11,650.00	10.94	179.77	11,638.24	174.02	208.47	-163.84	12.00	12.00	0.00
11,675.00	13.94	179.77	11,662.65	168.64	208.49	-158.46	12.00	12.00	0.00
11,700.00	16.94	179.77	11,686.75	161.99	208.52	-151.81	12.00	12.00	0.00
11,725.00	19.94	179.77	11,710.46	154.08	208.55	-143.91	12.00	12.00	0.00
11,750.00	22.94	179.77	11,733.73	144.94	208.58	-134.79	12.00	12.00	0.00
11,775.00	25.94	179.77	11,756.49	134.60	208.62	-124.46	12.00	12.00	0.00
11,800.00	28.94	179.77	11,778.67	123.09	208.67	-112.95	12.00	12.00	0.00
11,825.00	31.94	179.77	11,800.22	110.42	208.72	-100.30	12.00	12.00	0.00
11,850.00	34.94	179.77	11,821.08	96.65	208.77	-86.54	12.00	12.00	0.00
11,875.00	37.94	179.77	11,841.20	81.80	208.83	-71.70	12.00	12.00	0.00
11,900.00	40.94	179.77	11,860.50	65.92	208.89	-55.84	12.00	12.00	0.00
11,925.00	43.94	179.77	11,878.95	49.05	208.96	-38.99	12.00	12.00	0.00
11,950.00	46.94	179.77	11,896.49	31.24	209.03	-21.20	12.00	12.00	0.00
11,975.00	49.94	179.77	11,913.07	12.54	209.10	-2.51	12.00	12.00	0.00
12,000.00	52.94	179.77	11,928.66	-7.00	209.18	17.02	12.00	12.00	0.00
12,025.00	55.94	179.77	11,943.19	-27.34	209.26	37.33	12.00	12.00	0.00
12,050.00	58.94	179.77	11,956.65	-48.41	209.34	58.38	12.00	12.00	0.00
12,075.00	61.94	179.77	11,968.98	-70.15	209.43	80.10	12.00	12.00	0.00
12,100.00	64.94	179.77	11,980.16	-92.51	209.52	102.44	12.00	12.00	0.00
12,125.00	67.94	179.77	11,990.15	-115.42	209.61	125.33	12.00	12.00	0.00
12,150.00	70.94	179.77	11,998.93	-138.82	209.70	148.71	12.00	12.00	0.00
12,175.00	73.94	179.77	12,006.47	-162.66	209.79	172.52	12.00	12.00	0.00
12,200.00	76.94	179.77	12,012.76	-186.85	209.89	196.69	12.00	12.00	0.00
12,225.00	79.94	179.77	12,017.77	-211.34	209.99	221.16	12.00	12.00	0.00
12,250.00	82.94	179.77	12,021.49	-236.06	210.08	245.85	12.00	12.00	0.00

Database: 5000.1 Conroe DB
Company: Pride Energy Company
Project: Lea County, New Mexico (NAD 83)
Site: Paduca "16" State
Well: 703H
Wellbore: Wellbore #1
Design: Design #1

Local Co-ordinate Reference: Well 703H
TVD Reference: WELL @ 3447.00usft
MD Reference: WELL @ 3447.00usft
North Reference: Grid
Survey Calculation Method: Minimum Curvature

Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
12,275.00	85.94	179.77	12,023.92	-260.94	210.18	270.71	12.00	12.00	0.00
12,298.17	88.72	179.77	12,025.00	-284.08	210.27	293.82	12.00	12.00	0.00
Begin 88.72° Lateral									
12,300.00	88.72	179.77	12,025.04	-285.91	210.28	295.65	0.00	0.00	0.00
12,400.00	88.72	179.77	12,027.27	-385.88	210.67	395.53	0.00	0.00	0.00
12,500.00	88.72	179.77	12,029.51	-485.86	211.07	495.41	0.00	0.00	0.00
12,600.00	88.72	179.77	12,031.75	-585.83	211.46	595.29	0.00	0.00	0.00
12,700.00	88.72	179.77	12,033.99	-685.81	211.85	695.17	0.00	0.00	0.00
12,800.00	88.72	179.77	12,036.23	-785.78	212.25	795.05	0.00	0.00	0.00
12,900.00	88.72	179.77	12,038.47	-885.75	212.64	894.92	0.00	0.00	0.00
13,000.00	88.72	179.77	12,040.70	-985.73	213.03	994.80	0.00	0.00	0.00
13,100.00	88.72	179.77	12,042.94	-1,085.70	213.43	1,094.68	0.00	0.00	0.00
13,200.00	88.72	179.77	12,045.18	-1,185.68	213.82	1,194.56	0.00	0.00	0.00
13,300.00	88.72	179.77	12,047.42	-1,285.65	214.21	1,294.44	0.00	0.00	0.00
13,400.00	88.72	179.77	12,049.66	-1,385.63	214.61	1,394.31	0.00	0.00	0.00
13,500.00	88.72	179.77	12,051.89	-1,485.60	215.00	1,494.19	0.00	0.00	0.00
13,600.00	88.72	179.77	12,054.13	-1,585.57	215.39	1,594.07	0.00	0.00	0.00
13,700.00	88.72	179.77	12,056.37	-1,685.55	215.79	1,693.95	0.00	0.00	0.00
13,800.00	88.72	179.77	12,058.61	-1,785.52	216.18	1,793.83	0.00	0.00	0.00
13,900.00	88.72	179.77	12,060.85	-1,885.50	216.57	1,893.71	0.00	0.00	0.00
14,000.00	88.72	179.77	12,063.08	-1,985.47	216.97	1,993.58	0.00	0.00	0.00
14,100.00	88.72	179.77	12,065.32	-2,085.44	217.36	2,093.46	0.00	0.00	0.00
14,200.00	88.72	179.77	12,067.56	-2,185.42	217.75	2,193.34	0.00	0.00	0.00
14,300.00	88.72	179.77	12,069.80	-2,285.39	218.15	2,293.22	0.00	0.00	0.00
14,400.00	88.72	179.77	12,072.04	-2,385.37	218.54	2,393.10	0.00	0.00	0.00
14,500.00	88.72	179.77	12,074.28	-2,485.34	218.93	2,492.98	0.00	0.00	0.00
14,600.00	88.72	179.77	12,076.51	-2,585.32	219.33	2,592.85	0.00	0.00	0.00
14,700.00	88.72	179.77	12,078.75	-2,685.29	219.72	2,692.73	0.00	0.00	0.00
14,800.00	88.72	179.77	12,080.99	-2,785.26	220.11	2,792.61	0.00	0.00	0.00
14,900.00	88.72	179.77	12,083.23	-2,885.24	220.51	2,892.49	0.00	0.00	0.00
15,000.00	88.72	179.77	12,085.47	-2,985.21	220.90	2,992.37	0.00	0.00	0.00
15,100.00	88.72	179.77	12,087.70	-3,085.19	221.30	3,092.25	0.00	0.00	0.00
15,200.00	88.72	179.77	12,089.94	-3,185.16	221.69	3,192.12	0.00	0.00	0.00
15,300.00	88.72	179.77	12,092.18	-3,285.13	222.08	3,292.00	0.00	0.00	0.00
15,400.00	88.72	179.77	12,094.42	-3,385.11	222.48	3,391.88	0.00	0.00	0.00
15,500.00	88.72	179.77	12,096.66	-3,485.08	222.87	3,491.76	0.00	0.00	0.00
15,600.00	88.72	179.77	12,098.89	-3,585.06	223.26	3,591.64	0.00	0.00	0.00
15,700.00	88.72	179.77	12,101.13	-3,685.03	223.66	3,691.51	0.00	0.00	0.00
15,800.00	88.72	179.77	12,103.37	-3,785.01	224.05	3,791.39	0.00	0.00	0.00
15,900.00	88.72	179.77	12,105.61	-3,884.98	224.44	3,891.27	0.00	0.00	0.00
16,000.00	88.72	179.77	12,107.85	-3,984.95	224.84	3,991.15	0.00	0.00	0.00
16,100.00	88.72	179.77	12,110.09	-4,084.93	225.23	4,091.03	0.00	0.00	0.00
16,200.00	88.72	179.77	12,112.32	-4,184.90	225.62	4,190.91	0.00	0.00	0.00
16,300.00	88.72	179.77	12,114.56	-4,284.88	226.02	4,290.78	0.00	0.00	0.00
16,400.00	88.72	179.77	12,116.80	-4,384.85	226.41	4,390.66	0.00	0.00	0.00
16,500.00	88.72	179.77	12,119.04	-4,484.82	226.80	4,490.54	0.00	0.00	0.00
16,600.00	88.72	179.77	12,121.28	-4,584.80	227.20	4,590.42	0.00	0.00	0.00
16,700.00	88.72	179.77	12,123.51	-4,684.77	227.59	4,690.30	0.00	0.00	0.00
16,766.39	88.72	179.77	12,125.00	-4,751.15	227.85	4,756.61	0.00	0.00	0.00
PBHL									