

PECOS DISTRICT DRILLING CONDITIONS OF APPROVAL

OPERATOR'S NAME:	COG OPERATING
LEASE NO.:	NMNM125658
WELL NAME & NO.:	FEZ FEDERAL COM 704H
SURFACE HOLE FOOTAGE:	280'/S & 480'/W
BOTTOM HOLE FOOTAGE:	200'/N & 660'/W
LOCATION:	SECTION 09, T25S, R35E, NMPM
COUNTY:	LEA

Potash	☒ None	☐ Secretary	☐ R-111-P
Cave/Karst Potential	☒ Low	☐ Medium	☐ High
Variance	☐ None	☒ Flex Hose	☐ Other
Wellhead	☒ Conventional	☐ Multibowl	
Other	☐ 4 String Area	☐ Capitan Reef	☐ WIPP

A. Hydrogen Sulfide

1. Hydrogen Sulfide (H₂S) monitors shall be installed prior to drilling out the surface shoe. If H₂S is detected in concentrations greater than 100 ppm, the Hydrogen Sulfide area shall meet Onshore Order 6 requirements, which includes equipment and personnel/public protection items. If Hydrogen Sulfide is encountered, provide measured values and formations to the BLM.

B. CASING

1. The 13 3/8 inch surface casing shall be set at approximately 1100 feet (a minimum of 25 feet into the Rustler Anhydrite and above the salt) and cemented to the surface.
 - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.
 - b. Wait on cement (WOC) time for a primary cement job will be a minimum of 8 hours or 500 pounds compressive strength, whichever is greater. (This is to include the lead cement)
 - c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.

- d. If cement falls back, remedial cementing will be done prior to drilling out that string.
2. The minimum required fill of cement behind the **9 5/8** inch intermediate casing is:

Operator has proposed a DV tool at a depth of **5325'**, the depth may be adjusted as long as the cement is changed proportionally. The DV tool may be cancelled if cement circulates to surface on the first stage.

 - a. First stage to DV tool: Cement to circulate. If cement does not circulate off the DV tool, contact the appropriate BLM office before proceeding with second stage cement job.
 - b. Second stage above DV tool:
 - Cement to surface. If cement does not circulate, contact the appropriate BLM office.
3. The minimum required fill of cement behind the **5 1/2** inch production casing is:
 - Cement should tie-back at least **200** feet into previous casing string. Operator shall provide method of verification.

C. PRESSURE CONTROL

1. Variance approved to use flex line from BOP to choke manifold. Manufacturer's specification to be readily available. No external damage to flex line. Flex line to be installed as straight as possible (no hard bends).
2. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be **5000 (5M) psi**.
3. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the **9 5/8** inch intermediate casing shoe shall be **10,000 (10M) psi**. **Variance is approved to use 5M Annular which shall be tested to 5000 psi.**

D. SPECIAL REQUIREMENT(S)

Communitization Agreement

- The operator will submit a Communitization Agreement to the Carlsbad Field Office, 620 E Greene St. Carlsbad, New Mexico 88220, at least 90 days before the anticipated date of first production from a well subject to a spacing order issued by the New Mexico Oil Conservation Division. The Communitization Agreement will

include the signatures of all working interest owners in all Federal and Indian leases subject to the Communitization Agreement (i.e., operating rights owners and lessees of record), or certification that the operator has obtained the written signatures of all such owners and will make those signatures available to the BLM immediately upon request.

- If the operator does not comply with this condition of approval, the BLM may take enforcement actions that include, but are not limited to, those specified in 43 CFR 3163.1.
- In addition, the well sign shall include the surface and bottom hole lease numbers. When the Communitization Agreement number is known, it shall also be on the sign.

Waste Minimization Plan (WMP)

In the interest of resource development, submission of additional well gas capture development plan information is deferred but may be required by the BLM Authorized Officer at a later date.

MHH 09152018

GENERAL REQUIREMENTS

The BLM is to be notified in advance for a representative to witness:

- a. Spudding well (minimum of 24 hours)
- b. Setting and/or Cementing of all casing strings (minimum of 4 hours)
- c. BOPE tests (minimum of 4 hours)

☒ Chaves and Roosevelt Counties
Call the Roswell Field Office, 2909 West Second St., Roswell NM 88201.
During office hours call (575) 627-0272.
After office hours call (575)

☒ Eddy County
Call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220,
(575) 361-2822

☒ Lea County
Call the Hobbs Field Station, 414 West Taylor, Hobbs NM 88240, (575)
393-3612

1. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval.
 - a. In the event the operator has proposed to drill multiple wells utilizing a skid/walking rig. Operator shall secure the wellbore on the current well, after installing and testing the wellhead, by installing a blind flange of like pressure rating to the wellhead and a pressure gauge that can be monitored while drilling is performed on the other well(s).
 - b. When the operator proposes to set surface casing with Spudder Rig
 - Notify the BLM when moving in and removing the Spudder Rig.
 - Notify the BLM when moving in the 2nd Rig. Rig to be moved in within 90 days of notification that Spudder Rig has left the location.
 - BOP/BOPE test to be conducted per Onshore Oil and Gas Order No. 2 as soon as 2nd Rig is rigged up on well.
2. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works are located, this does not include the dog house or stairway area.

3. The record of the drilling rate along with the GR/N well log run from TD to surface (horizontal well – vertical portion of hole) shall be submitted to the BLM office as well as all other logs run on the borehole 30 days from completion. If available, a digital copy of the logs is to be submitted in addition to the paper copies. The Rustler top and top and bottom of Salt are to be recorded on the Completion Report.

A. CASING

1. Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size or are Non-API. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.). The initial wellhead installed on the well will remain on the well with spools used as needed.
2. Wait on cement (WOC) for Potash Areas: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi for all cement blends, 2) until cement has been in place at least 24 hours. WOC time will be recorded in the driller's log.
3. Wait on cement (WOC) for Water Basin: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi at the shoe, 2) until cement has been in place at least 8 hours. WOC time will be recorded in the driller's log. See individual casing strings for details regarding lead cement slurry requirements.
4. Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. Have well specific cement details onsite prior to pumping the cement for each casing string.
5. No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.
6. On that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Formation at the shoe shall be tested to a minimum of the mud weight equivalent anticipated to control the formation pressure to the next casing depth or at total depth of the well. This test shall be performed before drilling more than 20 feet of new hole.
7. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.

8. Whenever a casing string is cemented in the R-111-P potash area, the NMOCD requirements shall be followed.

B. PRESSURE CONTROL

1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in Onshore Oil and Gas Order No. 2 and API RP 53 Sec. 17.
2. If a variance is approved for a flexible hose to be installed from the BOP to the choke manifold, the following requirements apply: Check condition of flexible line from BOP to choke manifold, replace if exterior is damaged or if line fails test. Line to be as straight as possible with no hard bends and is to be anchored according to Manufacturer's requirements. The flexible hose can be exchanged with a hose of equal size and equal or greater pressure rating. Anchor requirements, specification sheet and hydrostatic pressure test certification matching the hose in service, to be onsite for review. These documents shall be posted in the company man's trailer and on the rig floor.
3. 5M or higher system requires an HCR valve, remote kill line and annular to match. The remote kill line is to be installed prior to testing the system and tested to stack pressure.
4. If the operator has proposed a multi-bowl wellhead assembly in the APD. The following requirements must be met:
 - a. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
 - b. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
 - c. Manufacturer representative shall install the test plug for the initial BOP test.
 - d. Operator shall perform the intermediate casing integrity test to 70% of the casing burst. This will test the multi-bowl seals.
 - e. If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
5. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.
 - a. In a water basin, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. The casing cut-off and BOP installation can be initiated four hours after installing the slips, which will be approximately six hours after bumping the

plug. For those casing strings not using slips, the minimum wait time before cut-off is eight hours after bumping the plug. BOP/BOPE testing can begin after cut-off or once cement reaches 500 psi compressive strength (including lead when specified), whichever is greater. However, if the float does not hold, cut-off cannot be initiated until cement reaches 500 psi compressive strength (including lead when specified).

- b. In potash areas, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. For all casing strings, casing cut-off and BOP installation can be initiated at twelve hours after bumping the plug. However, **no tests** shall commence until the cement has had a minimum of 24 hours setup time.
- c. The tests shall be done by an independent service company utilizing a test plug not a cup or J-packer. The operator also has the option of utilizing an independent tester to test without a plug (i.e. against the casing) pursuant to Onshore Order 2 with the pressure not to exceed 70% of the burst rating for the casing. Any test against the casing must meet the WOC time for water basin (8 hours) or potash (24 hours) or 500 pounds compressive strength, whichever is greater, prior to initiating the test (see casing segment as lead cement may be critical item).
- d. The test shall be run on a 5000 psi chart for a 2-3M BOP/BOP, on a 10000 psi chart for a 5M BOP/BOPE and on a 15000 psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one hour chart. A circular chart shall have a maximum 2 hour clock. If a twelve hour or twenty-four hour chart is used, tester shall make a notation that it is run with a two hour clock.
- e. The results of the test shall be reported to the appropriate BLM office.
- f. All tests are required to be recorded on a calibrated test chart. A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.
- g. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug. This test shall be performed prior to the test at full stack pressure.
- h. BOP/BOPE must be tested by an independent service company within 500 feet of the top of the Wolfcamp formation if the time between the setting of the intermediate casing and reaching this depth exceeds 20 days. This test does not exclude the test prior to drilling out the casing shoe as per Onshore Order No. 2.

C. DRILLING MUD

Mud system monitoring equipment, with derrick floor indicators and visual and audio alarms, shall be operating before drilling into the Wolfcamp formation, and shall be used until production casing is run and cemented.

D. WASTE MATERIAL AND FLUIDS

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area.

Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.

**PECOS DISTRICT
SURFACE USE
CONDITIONS OF APPROVAL**

HOBBS OCD
OCT 17 2018
RECEIVED

OPERATOR'S NAME:	COG OPERATING
LEASE NO.:	NMNM125658
WELL NAME & NO.:	FEZ FEDERAL COM 704H
SURFACE HOLE FOOTAGE:	280'/S & 480'/W
BOTTOM HOLE FOOTAGE	200'/N & 660'/W
LOCATION:	SECTION 09, T25S, R35E, NMPM
COUNTY:	LEA

TABLE OF CONTENTS

Standard Conditions of Approval (COA) apply to this APD. If any deviations to these standards exist or special COAs are required, the section with the deviation or requirement will be checked below.

- ☐ **General Provisions**
- ☐ **Permit Expiration**
- ☐ **Archaeology, Paleontology, and Historical Sites**
- ☐ **Noxious Weeds**
- ☒ **Special Requirements**
 - Lesser Prairie-Chicken Timing Stipulations
 - Below Ground-level Abandoned Well Marker
 - Hydrology
 - Range
- ☐ **Construction**
 - Notification
 - Topsoil
 - Closed Loop System
 - Federal Mineral Material Pits
 - Well Pads
 - Roads
- ☐ **Road Section Diagram**
- ☐ **Production (Post Drilling)**
 - Well Structures & Facilities
- ☐ **Interim Reclamation**
- ☐ **Final Abandonment & Reclamation**

I. GENERAL PROVISIONS

The approval of the Application For Permit To Drill (APD) is in compliance with all applicable laws and regulations: 43 Code of Federal Regulations 3160, the lease terms, Onshore Oil and Gas Orders, Notices To Lessees, New Mexico Oil Conservation Division (NMOCD) Rules, National Historical Preservation Act As Amended, and instructions and orders of the Authorized Officer. Any request for a variance shall be submitted to the Authorized Officer on Form 3160-5, Sundry Notices and Report on Wells.

II. PERMIT EXPIRATION

If the permit terminates prior to drilling and drilling cannot be commenced within 60 days after expiration, an operator is required to submit Form 3160-5, Sundry Notices and Reports on Wells, requesting surface reclamation requirements for any surface disturbance. However, if the operator will be able to initiate drilling within 60 days after the expiration of the permit, the operator must have set the conductor pipe in order to allow for an extension of 60 days beyond the expiration date of the APD. (Filing of a Sundry Notice is required for this 60 day extension.)

III. ARCHAEOLOGICAL, PALEONTOLOGY & HISTORICAL SITES

Any cultural and/or paleontological resource discovered by the operator or by any person working on the operator's behalf shall immediately report such findings to the Authorized Officer. The operator is fully accountable for the actions of their contractors and subcontractors. The operator shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery shall be made by the Authorized Officer to determine the appropriate actions that shall be required to prevent the loss of significant cultural or scientific values of the discovery. The operator shall be held responsible for the cost of the proper mitigation measures that the Authorized Officer assesses after consultation with the operator on the evaluation and decisions of the discovery. Any unauthorized collection or disturbance of cultural or paleontological resources may result in a shutdown order by the Authorized Officer.

IV. NOXIOUS WEEDS

The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes the roads, pads, associated pipeline corridor, and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

V. SPECIAL REQUIREMENT(S)

Timing Limitation Stipulation / Condition of Approval for lesser prairie-chicken:

Oil and gas activities including 3-D geophysical exploration, and drilling will not be allowed in lesser prairie-chicken habitat during the period from March 1st through June 15th annually. During that period, other activities that produce noise or involve human activity, such as the maintenance of oil and gas facilities, pipeline, road, and well pad construction, will be allowed except between 3:00 am and 9:00 am. The 3:00 am to 9:00 am restriction will not apply to normal, around-the-clock operations, such as venting, flaring, or pumping, which do not require a human presence during this period. Additionally, no new drilling will be allowed within up to 200 meters of leks known at the time of permitting. Normal vehicle use on existing roads will not be restricted. Exhaust noise from pump jack engines must be muffled or otherwise controlled so as not to exceed 75 db measured at 30 feet from the source of the noise.

Below Ground-level Abandoned Well Marker to avoid raptor perching: Upon the plugging and subsequent abandonment of the well, the well marker will be installed at ground level on a plate containing the pertinent information for the plugged well. For more installation details, contact the Carlsbad Field Office at 575-234-5972.

Timing Limitation Exceptions:

The Carlsbad Field Office will publish an annual map of where the LPC timing and noise stipulations and conditions of approval (Limitations) will apply for the identified year (between March 1 and June 15) based on the latest survey information. The LPC Timing Area map will identify areas which are Habitat Areas (HA), Isolated Population Area (IPA), and Primary Population Area (PPA). The LPC Timing Area map will also have an area in red crosshatch. The red crosshatch area is the only area where an operator is required to submit a request for exception to the LPC Limitations. If an operator is operating outside the red crosshatch area, the LPC Limitations do not apply for that year and an exception to LPC Limitations is not required.

Hydrology

The entire well pad will be bermed to prevent oil, salt, and other chemical contaminants from leaving the well pad. Topsoil shall not be used to construct the berm. No water flow from the uphill side(s) of the pad shall be allowed to enter the well pad. The berm shall be maintained through the life of the well and after interim reclamation has been completed. Any water erosion that may occur due to the construction of the well pad during the life of the well will be quickly corrected and proper measures will be taken to prevent future erosion.

Tank battery locations will be lined and bermed. A 20 mil permanent liner will be installed with a 4 oz. felt backing to prevent tears or punctures. Tank battery berms must be large enough to contain 1 ½ times the content of the largest tank or 24 hour production, whichever is greater. Automatic shut off, check valves, or similar systems

will be installed for tanks to minimize the effects of catastrophic line failures used in production or drilling.

A leak detection plan will be submitted to the BLM Carlsbad Field Office for approval prior to pipeline installation. The method could incorporate gauges to detect pressure drops, situating valves and lines so they can be visually inspected periodically or installing electronic sensors to alarm when a leak is present. The leak detection plan will incorporate an automatic shut off system that will be installed for proposed pipelines to minimize the effects of an undesirable event.

Range

The proponent would not damage the allotment fence during construction of the pads or roads. If fence is damaged the blm must be contacted immediately and all work must cease till the fence has been repaired back to its original condition or better.

VI. CONSTRUCTION

A. NOTIFICATION

The BLM shall administer compliance and monitor construction of the access road and well pad. Notify the Carlsbad Field Office at (575) 234-5909 at least 3 working days prior to commencing construction of the access road and/or well pad.

When construction operations are being conducted on this well, the operator shall have the approved APD and Conditions of Approval (COA) on the well site and they shall be made available upon request by the Authorized Officer.

B. TOPSOIL

The operator shall strip the top portion of the soil (root zone) from the entire well pad area and stockpile the topsoil along the edge of the well pad as depicted in the APD. The root zone is typically six (6) inches in depth. All the stockpiled topsoil will be redistributed over the interim reclamation areas. Topsoil shall not be used for berming the pad or facilities. For final reclamation, the topsoil shall be spread over the entire pad area for seeding preparation.

Other subsoil (below six inches) stockpiles must be completely segregated from the topsoil stockpile. Large rocks or subsoil clods (not evident in the surrounding terrain) must be buried within the approved area for interim and final reclamation.

C. CLOSED LOOP SYSTEM

Tanks are required for drilling operations: No Pits.

The operator shall properly dispose of drilling contents at an authorized disposal site.

D. FEDERAL MINERAL MATERIALS PIT

Payment shall be made to the BLM prior to removal of any federal mineral materials. Call the Carlsbad Field Office at (575) 234-5972.

E. WELL PAD SURFACING

Surfacing of the well pad is not required.

If the operator elects to surface the well pad, the surfacing material may be required to be removed at the time of reclamation. The well pad shall be constructed in a manner which creates the smallest possible surface disturbance, consistent with safety and operational needs.

F. EXCLOSURE FENCING (CELLARS & PITS)

Exclosure Fencing

The operator will install and maintain exclosure fencing for all open well cellars to prevent access to public, livestock, and large forms of wildlife before and after drilling operations until the pit is free of fluids and the operator initiates backfilling. (For examples of exclosure fencing design, refer to BLM's Oil and Gas Gold Book, Exclosure Fence Illustrations, Figure 1, Page 18.)

G. ON LEASE ACCESS ROADS**Road Width**

The access road shall have a driving surface that creates the smallest possible surface disturbance and does not exceed fourteen (14) feet in width. The maximum width of surface disturbance, when constructing the access road, shall not exceed twenty-five (25) feet.

Surfacing

Surfacing material is not required on the new access road driving surface. If the operator elects to surface the new access road or pad, the surfacing material may be required to be removed at the time of reclamation.

Where possible, no improvements should be made on the unsurfaced access road other than to remove vegetation as necessary, road irregularities, safety issues, or to fill low areas that may sustain standing water.

The Authorized Officer reserves the right to require surfacing of any portion of the access road at any time deemed necessary. Surfacing may be required in the event the road deteriorates, erodes, road traffic increases, or it is determined to be beneficial for future field development. The surfacing depth and type of material will be determined at the time of notification.

Crowning

Crowning shall be done on the access road driving surface. The road crown shall have a grade of approximately 2% (i.e., a 1" crown on a 14' wide road). The road shall conform to Figure 1; cross section and plans for typical road construction.

Ditching

Ditching shall be required on both sides of the road.

Turnouts


Vehicle turnouts shall be constructed on the road. Turnouts shall be intervisible with interval spacing distance less than 1000 feet. Turnouts shall conform to Figure 1; cross section and plans for typical road construction.

Drainage

Drainage control systems shall be constructed on the entire length of road (e.g. ditches, sidehill outslowing and insloping, lead-off ditches, culvert installation, and low water crossings).

A typical lead-off ditch has a minimum depth of 1 foot below and a berm of 6 inches above natural ground level. The berm shall be on the down-slope side of the lead-off ditch.

Cross Section of a Typical Lead-off Ditch



All lead-off ditches shall be graded to drain water with a 1 percent minimum to 3 percent maximum ditch slope. The spacing interval are variable for lead-off ditches and shall be determined according to the formula for spacing intervals of lead-off ditches, but may be amended depending upon existing soil types and centerline road slope (in %);

Formula for Spacing Interval of Lead-off Ditches

Example - On a 4% road slope that is 400 feet long, the water flow shall drain water into a lead-off ditch. Spacing interval shall be determined by the following formula:

$$400 \text{ foot road with } 4\% \text{ road slope: } \frac{400'}{4\%} + 100' = 200' \text{ lead-off ditch interval}$$

Cattle guards

An appropriately sized cattle guard sufficient to carry out the project shall be installed and maintained at fence/road crossings. Any existing cattle guards on the access road route shall be repaired or replaced if they are damaged or have deteriorated beyond practical use. The operator shall be responsible for the condition of the existing cattle guards that are in place and are utilized during lease operations.

Fence Requirement

Where entry is granted across a fence line, the fence shall be braced and tied off on both sides of the passageway prior to cutting. The operator shall notify the private surface landowner or the grazing allotment holder prior to crossing any fences.

Public Access

Public access on this road shall not be restricted by the operator without specific written approval granted by the Authorized Officer.

Construction Steps

1. Salvage topsoil
2. Construct road

3. Redistribute topsoil
4. Revegetate slopes




Figure 1. Cross-sections and plans for typical road sections representative of BLM resource or FS local and higher-class roads.

VII. PRODUCTION (POST DRILLING)

A. WELL STRUCTURES & FACILITIES

Placement of Production Facilities

Production facilities should be placed on the well pad to allow for maximum interim recontouring and revegetation of the well location.

Exclosure Netting (Open-top Tanks)

Immediately following active drilling or completion operations, the operator will take actions necessary to prevent wildlife and livestock access, including avian wildlife, to all open-topped tanks that contain or have the potential to contain salinity sufficient to cause harm to wildlife or livestock, hydrocarbons, or Resource Conservation and Recovery Act of 1976-exempt hazardous substances. At a minimum, the operator will net, screen, or cover open-topped tanks to exclude wildlife and livestock and prevent mortality. If the operator uses netting, the operator will cover and secure the open portion of the tank to prevent wildlife entry. The operator will net, screen, or cover the tanks until the operator removes the tanks from the location or the tanks no longer contain substances that could be harmful to wildlife or livestock. Use a maximum netting mesh size of 1 ½ inches. The netting must not be in contact with fluids and must not have holes or gaps.

Chemical and Fuel Secondary Containment and Exclosure Screening

The operator will prevent all hazardous, poisonous, flammable, and toxic substances from coming into contact with soil and water. At a minimum, the operator will install and maintain an impervious secondary containment system for any tank or barrel containing hazardous, poisonous, flammable, or toxic substances sufficient to contain the contents of the tank or barrel and any drips, leaks, and anticipated precipitation. The operator will dispose of fluids within the containment system that do not meet applicable state or U. S. Environmental Protection Agency livestock water standards in accordance with state law; the operator must not drain the fluids to the soil or ground. The operator will design, construct, and maintain all secondary containment systems to prevent wildlife and livestock exposure to harmful substances. At a minimum, the operator will install effective wildlife and livestock exclosure systems such as fencing, netting, expanded metal mesh, lids, and grate covers. Use a maximum netting mesh size of 1 ½ inches.

Open-Vent Exhaust Stack Exclosures

The operator will construct, modify, equip, and maintain all open-vent exhaust stacks on production equipment to prevent birds and bats from entering, and to discourage perching, roosting, and nesting. (*Recommended exclosure structures on open-vent exhaust stacks are in the shape of a cone.*) Production equipment includes, but may not be limited to, tanks, heater-treaters, separators, dehydrators, flare stacks, in-line units, and compressor mufflers.

Containment Structures

Proposed production facilities such as storage tanks and other vessels will have a secondary containment structure that is constructed to hold the capacity of 1.5 times the largest tank, plus freeboard to account for precipitation, unless more stringent protective requirements are deemed necessary.

Painting Requirement

All above-ground structures including meter housing that are not subject to safety requirements shall be painted a flat non-reflective paint color, **Shale Green** from the BLM Standard Environmental Color Chart (CC-001: June 2008).

VIII. INTERIM RECLAMATION

During the life of the development, all disturbed areas not needed for active support of production operations should undergo interim reclamation in order to minimize the environmental impacts of development on other resources and uses.

Within six (6) months of well completion, operators should work with BLM surface management specialists (Jim Amos: 575-234-5909) to devise the best strategies to reduce the size of the location. Interim reclamation should allow for remedial well operations, as well as safe and efficient removal of oil and gas.

During reclamation, the removal of caliche is important to increasing the success of revegetating the site. Removed caliche that is free of contaminants may be used for road repairs, fire walls or for building other roads and locations. In order to operate the well or complete workover operations, it may be necessary to drive, park and operate on restored interim vegetation within the previously disturbed area. Disturbing revegetated areas for production or workover operations will be allowed. If there is significant disturbance and loss of vegetation, the area will need to be revegetated. Communicate with the appropriate BLM office for any exceptions/exemptions if needed.

All disturbed areas after they have been satisfactorily prepared need to be reseeded with the seed mixture provided below.

Upon completion of interim reclamation, the operator shall submit a Sundry Notices and Reports on Wells, Subsequent Report of Reclamation (Form 3160-5).

IX. FINAL ABANDONMENT & RECLAMATION

At final abandonment, well locations, production facilities, and access roads must undergo "final" reclamation so that the character and productivity of the land are restored.

Earthwork for final reclamation must be completed within six (6) months of well plugging. All pads, pits, facility locations and roads must be reclaimed to a satisfactory revegetated, safe, and stable condition, unless an agreement is made with the landowner or BLM to keep the road and/or pad intact.

After all disturbed areas have been satisfactorily prepared, these areas need to be revegetated with the seed mixture provided below. Seeding should be accomplished by drilling on the contour whenever practical or by other approved methods. Seeding may need to be repeated until revegetation is successful, as determined by the BLM.

Operators shall contact a BLM surface protection specialist prior to surface abandonment operations for site specific objectives (Jim Amos: 575-234-5909).

Below Ground-level Abandoned Well Marker to avoid raptor perching: Upon the plugging and subsequent abandonment of the well, the well marker will be installed at ground level on a plate containing the pertinent information for the plugged well.

Seed Mixture for LPC Sand/Shinnery Sites

Holder shall seed all disturbed areas with the seed mixture listed below. The seed mixture shall be planted in the amounts specified in pounds of pure live seed (PLS)* per acre. There shall be no primary or secondary noxious weeds in the seed mixture. Seed will be tested and the viability testing of seed shall be done in accordance with State law(s) and within nine (9) months prior to purchase. Commercial seed shall be either certified or registered seed. The seed container shall be tagged in accordance with State law(s) and available for inspection by the Authorized Officer.

Seed will be planted using a drill equipped with a depth regulator to ensure proper depth of planting where drilling is possible. The seed mixture will be evenly and uniformly planted over the disturbed area (smaller/heavier seeds have a tendency to drop the bottom of the drill and are planted first). Holder shall take appropriate measures to ensure this does not occur. Where drilling is not possible, seed will be broadcast and the area shall be raked or chained to cover the seed. When broadcasting the seed, the pounds per acre are to be doubled. Seeding shall be repeated until a satisfactory stand is established as determined by the Authorized Officer. Evaluation of growth may not be made before completion of at least one full growing season after seeding.

Species to be planted in pounds of pure live seed* per acre:

<u>Species</u>	<u>lb/acre</u>
Plains Bristlegrass	5lbs/A
Sand Bluestem	5lbs/A
Little Bluestem	3lbs/A
Big Bluestem	6lbs/A
Plains Coreopsis	2lbs/A
Sand Dropseed	1lbs/A

*Pounds of pure live seed:

Pounds of seed x percent purity x percent germination = pounds pure live seed

COG OPERATING LLC
HYDROGEN SULFIDE DRILLING OPERATIONS PLAN

1. HYDROGEN SULFIDE TRAINING

All personnel, whether regularly assigned, contracted, or employed on an unscheduled basis, will receive training from a qualified instructor in the following areas prior to commencing drilling operations on this well:

- a. The hazards and characteristics of hydrogen sulfide (H₂S).
- b. The proper use and maintenance of personal protective equipment and life support systems.
- c. The proper use of H₂S detectors, alarms, warning systems, briefing areas, evacuation procedures, and prevailing winds.
- d. The proper techniques for first aid and rescue procedures.

In addition, supervisory personnel will be trained in the following areas:

- a. The effects of H₂S on metal components. If high tensile tubulars are to be used, personnel will be trained in their special maintenance requirements.
- b. Corrective action and shut-in procedures when drilling or reworking a well and blowout prevention and well control procedures.
- c. The contents and requirements of the H₂S Drilling Operations Plan and the Public Protection Plan.

There will be an initial training session just prior to encountering a known or probable H₂S zone (within 3 days or 500 feet) and weekly H₂S and well control drills for all personnel in each crew. The initial training session shall include a review of the site specific H₂S Drilling Operations Plan and the Public Protection Plan. This plan shall be available at the well site. All personnel will be required to carry documentation that they have received the proper training.

2. H₂S SAFETY EQUIPMENT AND SYSTEMS

Note: All H₂S safety equipment and systems will be installed, tested, and operational when drilling reaches a depth of 500 feet above, or three days prior to penetrating the first zone containing or reasonably expected to contain H₂S. If H₂S greater than 100 ppm is encountered in the gas stream we will shut in and install H₂S equipment.

- a. Well Control Equipment:
 - Flare line.
 - Choke manifold with remotely operated choke.
 - Blind rams and pipe rams to accommodate all pipe sizes with properly sized closing unit.
 - Auxiliary equipment to include: annular preventer, mud-gas separator, rotating head.

- b. Protective equipment for essential personnel:
Mark II Surviveair 30-minute units located in the dog house and at briefing areas.
- c. H2S detection and monitoring equipment:
2 - portable H2S monitor positioned on location for best coverage and response. These units have warning lights and audible sirens when H2S levels of 20 ppm are reached.
- d. Visual warning systems:
Caution/Danger signs shall be posted on roads providing direct access to location. Signs will be painted a high visibility yellow with black lettering of sufficient size to be readable at a reasonable distance from the immediate location. Bilingual signs will be used, when appropriate. See example attached.
- e. Mud Program:
The mud program has been designed to minimize the volume of H2S circulated to the surface.
- f. Metallurgy:
All drill strings, casings, tubing, wellhead, blowout preventers, drilling spool, kill lines, choke manifold and lines, and valves shall be suitable for H2S service.
- g. Communication:
Company vehicles equipped with cellular telephone.

COG OPERATING LLC has conducted a review to determine if an H2S contingency plan is required for the above referenced well. We were able to conclude that any potential hazardous volume would be minimal. H2S concentrations of wells in this area from surface to TD are low enough; therefore, we do not believe that an H2S contingency plan is necessary.

W A R N I N G

**YOU ARE ENTERING AN H₂S AREA
AUTHORIZED PERSONNEL ONLY**

- 1. BEARDS OR CONTACT LENSES NOT ALLOWED***
- 2. HARD HATS REQUIRED***
- 3. SMOKING IN DESIGNATED AREAS ONLY***
- 4. BE WIND CONSCIOUS AT ALL TIMES***
- 5. CK WITH COG OPERATING LLC FOREMAN AT MAIN OFFICE***

COG OPERATING LLC

1-575-748-6940

EMERGENCY CALL LIST


	<u>OFFICE</u>	<u>MOBILE</u>
COG OPERATING LLC OFFICE	575-748-6940	
SETH WILD	432-683-7443	432-528-3633
WALTER ROYE	575-748-6940	432-934-1886

EMERGENCY RESPONSE NUMBERS

	<u>OFFICE</u>
STATE POLICE	575-748-9718
EDDY COUNTY SHERIFF	575-746-2701
EMERGENCY MEDICAL SERVICES (AMBULANCE)	911 or 575-746-2701
EDDY COUNTY EMERGENCY MANAGEMENT (HARRY BURGESS)	575-887-9511
STATE EMERGENCY RESPONSE CENTER (SERC)	575-476-9620
CARLSBAD POLICE DEPARTMENT	575-885-2111
CARLSBAD FIRE DEPARTMENT	575-885-3125
NEW MEXICO OIL CONSERVATION DIVISION	575-748-1283
INDIAN FIRE & SAFETY	800-530-8693
HALLIBURTON SERVICES	800-844-8451

COG Operating LLC
H₂S Equipment Schematic
Terrain: Shinnery sand hills.

Well pad will be 400' x 400'
with cellar in center of pad





COG Operating, LLC

Lea County, NM

Sec 9, T25-S, R35-E

Fez Federal Com #704H

Wellbore #1

Plan: Design #1

QES Well Planning Report

28 February, 2018



Database:	EDM 5000.1 Single User Db	Local Co-ordinate Reference:	Well Fez Federal Com #704H
Company:	COG Operating, LLC	TVD Reference:	well @ 3289.0usft (Noram #21)
Project:	Lea County, NM	MD Reference:	well @ 3289.0usft (Noram #21)
Site:	Sec 9, T25-S, R35-E	North Reference:	Grid
Well:	Fez Federal Com #704H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Design #1		

Project	Lea County, NM		
Map System:	US State Plane 1927 (Exact solution)	System Datum:	Mean Sea Level
Geo Datum:	NAD 1927 (NADCON CONUS)		
Map Zone:	New Mexico East 3001		

Site	Sec 9, T25-S, R35-E		
Site Position:		Northing:	419,852.10 usft
From:	Map	Easting:	795,067.30 usft
Position Uncertainty:	0.0 usft	Slot Radius:	13-3/16 "
		Latitude:	32° 9' 2.515 N
		Longitude:	103° 22' 47.797 W
		Grid Convergence:	0.51 °

Well	Fez Federal Com #704H		
Well Position	+N/-S	-4,514.8 usft	Northing: 415,337.26 usft
	+E/-W	330.2 usft	Easting: 795,397.53 usft
Position Uncertainty	0.0 usft	Wellhead Elevation:	Latitude: 32° 8' 17.812 N
			Longitude: 103° 22' 44.422 W
			Ground Level: 3,260.0 usft

Wellbore	Wellbore #1				
Magnetics	Model Name	Sample Date	Declination	Dip Angle	Field Strength
			(°)	(°)	(nT)
	IGRF2015	2/21/2018	6.78	60.01	47,838.36321018

Design	Design #1			
Audit Notes:				
Version:	Phase:	PLAN	Tie On Depth:	0.0
Vertical Section:	Depth From (TVD)	+N/-S	+E/-W	Direction
	(usft)	(usft)	(usft)	(°)
	0.0	0.0	0.0	357.81

Plan Sections										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	TFO (°)	Target
0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.00	0.00	
2,700.0	0.00	0.00	2,700.0	0.0	0.0	0.00	0.00	0.00	0.00	
2,900.0	4.00	105.00	2,899.8	-1.8	6.7	2.00	2.00	0.00	105.00	
3,400.0	4.00	105.00	3,398.6	-10.8	40.4	0.00	0.00	0.00	0.00	
3,503.8	6.07	104.25	3,502.0	-13.1	49.2	2.00	2.00	-0.72	-2.20	
4,631.5	6.07	104.25	4,623.4	-42.5	164.9	0.00	0.00	0.00	0.00	
4,935.2	0.00	0.00	4,926.5	-46.4	180.5	2.00	-2.00	0.00	180.00	
12,010.2	0.00	0.00	12,001.5	-46.4	180.5	0.00	0.00	0.00	0.00	
12,761.7	90.18	359.57	12,479.0	432.5	176.9	12.00	12.00	-0.06	359.57	
22,434.0	90.18	359.57	12,449.0	10,104.5	104.4	0.00	0.00	0.00	0.00	PBHL - Fez Fed Co

Database:	EDM 5000.1 Single User Db	Local Co-ordinate Reference:	Well Fez Federal Com #704H
Company:	COG Operating, LLC	TVD Reference:	well @ 3289.0usft (Noram #21)
Project:	Lea County, NM	MD Reference:	well @ 3289.0usft (Noram #21)
Site:	Sec 9, T25-S, R35-E	North Reference:	Grid
Well:	Fez Federal Com #704H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Design #1		

Planned Survey									
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
0.0	0.00	0.00	0.0	0.0	0.0	0.0	0.00	0.00	0.00
100.0	0.00	0.00	100.0	0.0	0.0	0.0	0.00	0.00	0.00
200.0	0.00	0.00	200.0	0.0	0.0	0.0	0.00	0.00	0.00
300.0	0.00	0.00	300.0	0.0	0.0	0.0	0.00	0.00	0.00
400.0	0.00	0.00	400.0	0.0	0.0	0.0	0.00	0.00	0.00
500.0	0.00	0.00	500.0	0.0	0.0	0.0	0.00	0.00	0.00
600.0	0.00	0.00	600.0	0.0	0.0	0.0	0.00	0.00	0.00
700.0	0.00	0.00	700.0	0.0	0.0	0.0	0.00	0.00	0.00
800.0	0.00	0.00	800.0	0.0	0.0	0.0	0.00	0.00	0.00
Rustler									
870.0	0.00	0.00	870.0	0.0	0.0	0.0	0.00	0.00	0.00
900.0	0.00	0.00	900.0	0.0	0.0	0.0	0.00	0.00	0.00
1,000.0	0.00	0.00	1,000.0	0.0	0.0	0.0	0.00	0.00	0.00
1,100.0	0.00	0.00	1,100.0	0.0	0.0	0.0	0.00	0.00	0.00
1,200.0	0.00	0.00	1,200.0	0.0	0.0	0.0	0.00	0.00	0.00
TOS									
1,211.0	0.00	0.00	1,211.0	0.0	0.0	0.0	0.00	0.00	0.00
1,300.0	0.00	0.00	1,300.0	0.0	0.0	0.0	0.00	0.00	0.00
1,400.0	0.00	0.00	1,400.0	0.0	0.0	0.0	0.00	0.00	0.00
1,500.0	0.00	0.00	1,500.0	0.0	0.0	0.0	0.00	0.00	0.00
1,600.0	0.00	0.00	1,600.0	0.0	0.0	0.0	0.00	0.00	0.00
1,700.0	0.00	0.00	1,700.0	0.0	0.0	0.0	0.00	0.00	0.00
1,800.0	0.00	0.00	1,800.0	0.0	0.0	0.0	0.00	0.00	0.00
1,900.0	0.00	0.00	1,900.0	0.0	0.0	0.0	0.00	0.00	0.00
2,000.0	0.00	0.00	2,000.0	0.0	0.0	0.0	0.00	0.00	0.00
2,100.0	0.00	0.00	2,100.0	0.0	0.0	0.0	0.00	0.00	0.00
2,200.0	0.00	0.00	2,200.0	0.0	0.0	0.0	0.00	0.00	0.00
2,300.0	0.00	0.00	2,300.0	0.0	0.0	0.0	0.00	0.00	0.00
2,400.0	0.00	0.00	2,400.0	0.0	0.0	0.0	0.00	0.00	0.00
2,500.0	0.00	0.00	2,500.0	0.0	0.0	0.0	0.00	0.00	0.00
2,600.0	0.00	0.00	2,600.0	0.0	0.0	0.0	0.00	0.00	0.00
Build 2.00°/100'									
2,700.0	0.00	0.00	2,700.0	0.0	0.0	0.0	0.00	0.00	0.00
2,800.0	2.00	105.00	2,800.0	-0.5	1.7	-0.5	2.00	2.00	0.00
EOB: 4.00° Inc, 105.00° Azi									
2,900.0	4.00	105.00	2,899.8	-1.8	6.7	-2.1	2.00	2.00	0.00
3,000.0	4.00	105.00	2,999.6	-3.6	13.5	-4.1	0.00	0.00	0.00
3,100.0	4.00	105.00	3,099.4	-5.4	20.2	-6.2	0.00	0.00	0.00
3,200.0	4.00	105.00	3,199.1	-7.2	27.0	-8.2	0.00	0.00	0.00
3,300.0	4.00	105.00	3,298.9	-9.0	33.7	-10.3	0.00	0.00	0.00
Build/Turn 2.00°/100'									
3,400.0	4.00	105.00	3,398.6	-10.8	40.4	-12.4	0.00	0.00	0.00
EOBT: 6.07° Inc, 104.25° Azi									
3,503.8	6.07	104.25	3,502.0	-13.1	49.2	-15.0	2.00	2.00	-0.72
3,600.0	6.07	104.25	3,597.7	-15.6	59.1	-17.9	0.00	0.00	0.00
3,700.0	6.07	104.25	3,697.1	-18.2	69.4	-20.9	0.00	0.00	0.00
3,800.0	6.07	104.25	3,796.5	-20.8	79.6	-23.9	0.00	0.00	0.00
3,900.0	6.07	104.25	3,896.0	-23.4	89.9	-26.9	0.00	0.00	0.00
4,000.0	6.07	104.25	3,995.4	-26.0	100.1	-29.9	0.00	0.00	0.00
4,100.0	6.07	104.25	4,094.9	-28.6	110.4	-32.8	0.00	0.00	0.00
4,200.0	6.07	104.25	4,194.3	-31.3	120.7	-35.8	0.00	0.00	0.00
4,300.0	6.07	104.25	4,293.7	-33.9	130.9	-38.8	0.00	0.00	0.00
4,400.0	6.07	104.25	4,393.2	-36.5	141.2	-41.8	0.00	0.00	0.00

Database:	EDM 5000.1 Single User Db	Local Co-ordinate Reference:	Well Fez Federal Com #704H
Company:	COG Operating, LLC	TVD Reference:	well @ 3289.0usft (Noram #21)
Project:	Lea County, NM	MD Reference:	well @ 3289.0usft (Noram #21)
Site:	Sec 9, T25-S, R35-E	North Reference:	Grid
Well:	Fez Federal Com #704H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Design #1		

Planned Survey									
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
4,500.0	6.07	104.25	4,492.6	-39.1	151.4	-44.8	0.00	0.00	0.00
4,600.0	6.07	104.25	4,592.1	-41.7	161.7	-47.8	0.00	0.00	0.00
Drop 2.00°/100'									
4,631.5	6.07	104.25	4,623.4	-42.5	164.9	-48.8	0.00	0.00	0.00
4,700.0	4.70	104.25	4,691.6	-44.1	171.1	-50.6	2.00	-2.00	0.00
4,800.0	2.70	104.25	4,791.4	-45.7	177.4	-52.4	2.00	-2.00	0.00
4,900.0	0.70	104.25	4,891.3	-46.4	180.3	-53.3	2.00	-2.00	0.00
EOD: 0.00° Inc, 0.00° Azi									
4,935.2	0.00	0.00	4,926.5	-46.4	180.5	-53.3	2.00	-2.00	0.00
5,000.0	0.00	0.00	4,991.3	-46.4	180.5	-53.3	0.00	0.00	0.00
BOS (Fletcher)									
5,014.7	0.00	0.00	5,006.0	-46.4	180.5	-53.3	0.00	0.00	0.00
5,100.0	0.00	0.00	5,091.3	-46.4	180.5	-53.3	0.00	0.00	0.00
5,200.0	0.00	0.00	5,191.3	-46.4	180.5	-53.3	0.00	0.00	0.00
5,300.0	0.00	0.00	5,291.3	-46.4	180.5	-53.3	0.00	0.00	0.00
LMAR (Top Delaware)									
5,345.7	0.00	0.00	5,337.0	-46.4	180.5	-53.3	0.00	0.00	0.00
BLCN									
5,377.7	0.00	0.00	5,369.0	-46.4	180.5	-53.3	0.00	0.00	0.00
5,400.0	0.00	0.00	5,391.3	-46.4	180.5	-53.3	0.00	0.00	0.00
5,500.0	0.00	0.00	5,491.3	-46.4	180.5	-53.3	0.00	0.00	0.00
5,600.0	0.00	0.00	5,591.3	-46.4	180.5	-53.3	0.00	0.00	0.00
5,700.0	0.00	0.00	5,691.3	-46.4	180.5	-53.3	0.00	0.00	0.00
5,800.0	0.00	0.00	5,791.3	-46.4	180.5	-53.3	0.00	0.00	0.00
5,900.0	0.00	0.00	5,891.3	-46.4	180.5	-53.3	0.00	0.00	0.00
6,000.0	0.00	0.00	5,991.3	-46.4	180.5	-53.3	0.00	0.00	0.00
6,100.0	0.00	0.00	6,091.3	-46.4	180.5	-53.3	0.00	0.00	0.00
6,200.0	0.00	0.00	6,191.3	-46.4	180.5	-53.3	0.00	0.00	0.00
6,300.0	0.00	0.00	6,291.3	-46.4	180.5	-53.3	0.00	0.00	0.00
CYCN									
6,316.7	0.00	0.00	6,308.0	-46.4	180.5	-53.3	0.00	0.00	0.00
6,400.0	0.00	0.00	6,391.3	-46.4	180.5	-53.3	0.00	0.00	0.00
6,500.0	0.00	0.00	6,491.3	-46.4	180.5	-53.3	0.00	0.00	0.00
6,600.0	0.00	0.00	6,591.3	-46.4	180.5	-53.3	0.00	0.00	0.00
6,700.0	0.00	0.00	6,691.3	-46.4	180.5	-53.3	0.00	0.00	0.00
6,800.0	0.00	0.00	6,791.3	-46.4	180.5	-53.3	0.00	0.00	0.00
6,900.0	0.00	0.00	6,891.3	-46.4	180.5	-53.3	0.00	0.00	0.00
7,000.0	0.00	0.00	6,991.3	-46.4	180.5	-53.3	0.00	0.00	0.00
7,100.0	0.00	0.00	7,091.3	-46.4	180.5	-53.3	0.00	0.00	0.00
7,200.0	0.00	0.00	7,191.3	-46.4	180.5	-53.3	0.00	0.00	0.00
7,300.0	0.00	0.00	7,291.3	-46.4	180.5	-53.3	0.00	0.00	0.00
7,400.0	0.00	0.00	7,391.3	-46.4	180.5	-53.3	0.00	0.00	0.00
7,500.0	0.00	0.00	7,491.3	-46.4	180.5	-53.3	0.00	0.00	0.00
7,600.0	0.00	0.00	7,591.3	-46.4	180.5	-53.3	0.00	0.00	0.00
7,700.0	0.00	0.00	7,691.3	-46.4	180.5	-53.3	0.00	0.00	0.00
BYCN									
7,776.7	0.00	0.00	7,768.0	-46.4	180.5	-53.3	0.00	0.00	0.00
7,800.0	0.00	0.00	7,791.3	-46.4	180.5	-53.3	0.00	0.00	0.00
7,900.0	0.00	0.00	7,891.3	-46.4	180.5	-53.3	0.00	0.00	0.00
8,000.0	0.00	0.00	7,991.3	-46.4	180.5	-53.3	0.00	0.00	0.00
8,100.0	0.00	0.00	8,091.3	-46.4	180.5	-53.3	0.00	0.00	0.00
8,200.0	0.00	0.00	8,191.3	-46.4	180.5	-53.3	0.00	0.00	0.00
8,300.0	0.00	0.00	8,291.3	-46.4	180.5	-53.3	0.00	0.00	0.00

Database:	EDM 5000.1 Single User Db	Local Co-ordinate Reference:	Well Fez Federal Com #704H
Company:	COG Operating, LLC	TVD Reference:	well @ 3289.0usft (Noram #21)
Project:	Lea County, NM	MD Reference:	well @ 3289.0usft (Noram #21)
Site:	Sec 9, T25-S, R35-E	North Reference:	Grid
Well:	Fez Federal Com #704H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Design #1		

Planned Survey									
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
8,400.0	0.00	0.00	8,391.3	-46.4	180.5	-53.3	0.00	0.00	0.00
8,500.0	0.00	0.00	8,491.3	-46.4	180.5	-53.3	0.00	0.00	0.00
8,600.0	0.00	0.00	8,591.3	-46.4	180.5	-53.3	0.00	0.00	0.00
8,700.0	0.00	0.00	8,691.3	-46.4	180.5	-53.3	0.00	0.00	0.00
8,800.0	0.00	0.00	8,791.3	-46.4	180.5	-53.3	0.00	0.00	0.00
8,900.0	0.00	0.00	8,891.3	-46.4	180.5	-53.3	0.00	0.00	0.00
9,000.0	0.00	0.00	8,991.3	-46.4	180.5	-53.3	0.00	0.00	0.00
Bone Sprg (BSGL)									
9,007.7	0.00	0.00	8,999.0	-46.4	180.5	-53.3	0.00	0.00	0.00
9,100.0	0.00	0.00	9,091.3	-46.4	180.5	-53.3	0.00	0.00	0.00
9,200.0	0.00	0.00	9,191.3	-46.4	180.5	-53.3	0.00	0.00	0.00
U Avalon Sh									
9,224.7	0.00	0.00	9,216.0	-46.4	180.5	-53.3	0.00	0.00	0.00
9,300.0	0.00	0.00	9,291.3	-46.4	180.5	-53.3	0.00	0.00	0.00
9,400.0	0.00	0.00	9,391.3	-46.4	180.5	-53.3	0.00	0.00	0.00
9,500.0	0.00	0.00	9,491.3	-46.4	180.5	-53.3	0.00	0.00	0.00
L Avalon Sh									
9,588.7	0.00	0.00	9,580.0	-46.4	180.5	-53.3	0.00	0.00	0.00
9,600.0	0.00	0.00	9,591.3	-46.4	180.5	-53.3	0.00	0.00	0.00
9,700.0	0.00	0.00	9,691.3	-46.4	180.5	-53.3	0.00	0.00	0.00
9,800.0	0.00	0.00	9,791.3	-46.4	180.5	-53.3	0.00	0.00	0.00
9,900.0	0.00	0.00	9,891.3	-46.4	180.5	-53.3	0.00	0.00	0.00
10,000.0	0.00	0.00	9,991.3	-46.4	180.5	-53.3	0.00	0.00	0.00
10,100.0	0.00	0.00	10,091.3	-46.4	180.5	-53.3	0.00	0.00	0.00
10,200.0	0.00	0.00	10,191.3	-46.4	180.5	-53.3	0.00	0.00	0.00
10,300.0	0.00	0.00	10,291.3	-46.4	180.5	-53.3	0.00	0.00	0.00
10,400.0	0.00	0.00	10,391.3	-46.4	180.5	-53.3	0.00	0.00	0.00
FBSG_sand									
10,405.7	0.00	0.00	10,397.0	-46.4	180.5	-53.3	0.00	0.00	0.00
10,500.0	0.00	0.00	10,491.3	-46.4	180.5	-53.3	0.00	0.00	0.00
10,600.0	0.00	0.00	10,591.3	-46.4	180.5	-53.3	0.00	0.00	0.00
10,700.0	0.00	0.00	10,691.3	-46.4	180.5	-53.3	0.00	0.00	0.00
10,800.0	0.00	0.00	10,791.3	-46.4	180.5	-53.3	0.00	0.00	0.00
10,900.0	0.00	0.00	10,891.3	-46.4	180.5	-53.3	0.00	0.00	0.00
SBSG_sand									
10,925.7	0.00	0.00	10,917.0	-46.4	180.5	-53.3	0.00	0.00	0.00
11,000.0	0.00	0.00	10,991.3	-46.4	180.5	-53.3	0.00	0.00	0.00
11,100.0	0.00	0.00	11,091.3	-46.4	180.5	-53.3	0.00	0.00	0.00
11,200.0	0.00	0.00	11,191.3	-46.4	180.5	-53.3	0.00	0.00	0.00
11,300.0	0.00	0.00	11,291.3	-46.4	180.5	-53.3	0.00	0.00	0.00
SBSG_sand base									
11,399.7	0.00	0.00	11,391.0	-46.4	180.5	-53.3	0.00	0.00	0.00
11,400.0	0.00	0.00	11,391.3	-46.4	180.5	-53.3	0.00	0.00	0.00
11,500.0	0.00	0.00	11,491.3	-46.4	180.5	-53.3	0.00	0.00	0.00
11,600.0	0.00	0.00	11,591.3	-46.4	180.5	-53.3	0.00	0.00	0.00
11,700.0	0.00	0.00	11,691.3	-46.4	180.5	-53.3	0.00	0.00	0.00
11,800.0	0.00	0.00	11,791.3	-46.4	180.5	-53.3	0.00	0.00	0.00
11,900.0	0.00	0.00	11,891.3	-46.4	180.5	-53.3	0.00	0.00	0.00
TBSG_sand									
11,982.7	0.00	0.00	11,974.0	-46.4	180.5	-53.3	0.00	0.00	0.00
12,000.0	0.00	0.00	11,991.3	-46.4	180.5	-53.3	0.00	0.00	0.00
KOP : Build 12.00°/100'									
12,010.2	0.00	0.00	12,001.5	-46.4	180.5	-53.3	0.00	0.00	0.00

Database:	EDM 5000.1 Single User Db	Local Co-ordinate Reference:	Well Fez Federal Com #704H
Company:	COG Operating, LLC	TVD Reference:	well @ 3289.0usft (Noram #21)
Project:	Lea County, NM	MD Reference:	well @ 3289.0usft (Noram #21)
Site:	Sec 9, T25-S, R35-E	North Reference:	Grid
Well:	Fez Federal Com #704H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Design #1		

Planned Survey									
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
12,025.0	1.78	359.57	12,016.3	-46.2	180.5	-53.1	12.00	12.00	0.00
12,050.0	4.78	359.57	12,041.3	-44.8	180.5	-51.7	12.00	12.00	0.00
12,075.0	7.78	359.57	12,066.1	-42.1	180.5	-48.9	12.00	12.00	0.00
12,100.0	10.78	359.57	12,090.8	-38.0	180.4	-44.9	12.00	12.00	0.00
12,125.0	13.78	359.57	12,115.2	-32.7	180.4	-39.6	12.00	12.00	0.00
12,150.0	16.78	359.57	12,139.3	-26.1	180.3	-33.0	12.00	12.00	0.00
12,175.0	19.78	359.57	12,163.1	-18.3	180.3	-25.2	12.00	12.00	0.00
12,200.0	22.78	359.57	12,186.4	-9.2	180.2	-16.1	12.00	12.00	0.00
12,225.0	25.78	359.57	12,209.1	1.1	180.1	-5.8	12.00	12.00	0.00
12,250.0	28.78	359.57	12,231.4	12.5	180.1	5.6	12.00	12.00	0.00
12,275.0	31.78	359.57	12,252.9	25.1	180.0	18.2	12.00	12.00	0.00
12,300.0	34.78	359.57	12,273.8	38.8	179.9	31.9	12.00	12.00	0.00
12,325.0	37.78	359.57	12,294.0	53.6	179.7	46.7	12.00	12.00	0.00
12,350.0	40.78	359.57	12,313.3	69.5	179.6	62.5	12.00	12.00	0.00
12,375.0	43.78	359.57	12,331.8	86.3	179.5	79.3	12.00	12.00	0.00
12,400.0	46.78	359.57	12,349.4	104.0	179.4	97.1	12.00	12.00	0.00
12,425.0	49.78	359.57	12,366.1	122.7	179.2	115.7	12.00	12.00	0.00
WFMP									
12,443.9	52.05	359.57	12,378.0	137.4	179.1	130.4	12.00	12.00	0.00
12,450.0	52.78	359.57	12,381.7	142.2	179.1	135.2	12.00	12.00	0.00
12,475.0	55.78	359.57	12,396.3	162.5	178.9	155.5	12.00	12.00	0.00
12,500.0	58.78	359.57	12,409.8	183.5	178.8	176.5	12.00	12.00	0.00
12,525.0	61.78	359.57	12,422.2	205.2	178.6	198.2	12.00	12.00	0.00
12,550.0	64.78	359.57	12,433.4	227.5	178.4	220.6	12.00	12.00	0.00
12,575.0	67.78	359.57	12,443.5	250.4	178.3	243.4	12.00	12.00	0.00
12,600.0	70.78	359.57	12,452.3	273.8	178.1	266.8	12.00	12.00	0.00
12,625.0	73.78	359.57	12,460.0	297.6	177.9	290.6	12.00	12.00	0.00
12,650.0	76.78	359.57	12,466.3	321.8	177.7	314.8	12.00	12.00	0.00
WFMP Lith									
12,662.5	78.27	359.57	12,469.0	334.0	177.6	326.9	12.00	12.00	0.00
12,675.0	79.78	359.57	12,471.4	346.3	177.6	339.2	12.00	12.00	0.00
12,700.0	82.78	359.57	12,475.2	371.0	177.4	363.9	12.00	12.00	0.00
12,725.0	85.78	359.57	12,477.7	395.8	177.2	388.8	12.00	12.00	0.00
12,750.0	88.78	359.57	12,478.9	420.8	177.0	413.7	12.00	12.00	0.00
EOC: 90.18° Inc, 359.57° Azi, 12479.0' TVD									
12,761.7	90.18	359.57	12,479.0	432.5	176.9	425.4	12.00	12.00	0.00
12,800.0	90.18	359.57	12,478.8	470.8	176.6	463.7	0.00	0.00	0.00
12,900.0	90.18	359.57	12,478.5	570.8	175.9	563.7	0.00	0.00	0.00
13,000.0	90.18	359.57	12,478.2	670.8	175.1	663.6	0.00	0.00	0.00
13,100.0	90.18	359.57	12,477.9	770.8	174.4	763.6	0.00	0.00	0.00
13,200.0	90.18	359.57	12,477.6	870.8	173.6	863.5	0.00	0.00	0.00
13,300.0	90.18	359.57	12,477.3	970.8	172.9	963.5	0.00	0.00	0.00
13,400.0	90.18	359.57	12,477.0	1,070.8	172.1	1,063.4	0.00	0.00	0.00
13,500.0	90.18	359.57	12,476.7	1,170.8	171.4	1,163.4	0.00	0.00	0.00
13,600.0	90.18	359.57	12,476.4	1,270.8	170.6	1,263.3	0.00	0.00	0.00
13,700.0	90.18	359.57	12,476.1	1,370.8	169.9	1,363.3	0.00	0.00	0.00
13,800.0	90.18	359.57	12,475.7	1,470.8	169.1	1,463.2	0.00	0.00	0.00
13,900.0	90.18	359.57	12,475.4	1,570.8	168.4	1,563.2	0.00	0.00	0.00
14,000.0	90.18	359.57	12,475.1	1,670.8	167.6	1,663.1	0.00	0.00	0.00
14,100.0	90.18	359.57	12,474.8	1,770.8	166.9	1,763.1	0.00	0.00	0.00
14,200.0	90.18	359.57	12,474.5	1,870.8	166.1	1,863.1	0.00	0.00	0.00
14,300.0	90.18	359.57	12,474.2	1,970.8	165.4	1,963.0	0.00	0.00	0.00
14,400.0	90.18	359.57	12,473.9	2,070.8	164.6	2,063.0	0.00	0.00	0.00

Database:	EDM 5000.1 Single User Db	Local Co-ordinate Reference:	Well Fez Federal Com #704H
Company:	COG Operating, LLC	TVD Reference:	well @ 3289.0usft (Noram #21)
Project:	Lea County, NM	MD Reference:	well @ 3289.0usft (Noram #21)
Site:	Sec 9, T25-S, R35-E	North Reference:	Grid
Well:	Fez Federal Com #704H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Design #1		

Planned Survey									
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
14,500.0	90.18	359.57	12,473.6	2,170.8	163.9	2,162.9	0.00	0.00	0.00
14,600.0	90.18	359.57	12,473.3	2,270.8	163.1	2,262.9	0.00	0.00	0.00
14,700.0	90.18	359.57	12,473.0	2,370.8	162.4	2,362.8	0.00	0.00	0.00
14,800.0	90.18	359.57	12,472.6	2,470.7	161.6	2,462.8	0.00	0.00	0.00
14,900.0	90.18	359.57	12,472.3	2,570.7	160.9	2,562.7	0.00	0.00	0.00
15,000.0	90.18	359.57	12,472.0	2,670.7	160.1	2,662.7	0.00	0.00	0.00
15,100.0	90.18	359.57	12,471.7	2,770.7	159.4	2,762.6	0.00	0.00	0.00
15,200.0	90.18	359.57	12,471.4	2,870.7	158.6	2,862.6	0.00	0.00	0.00
15,300.0	90.18	359.57	12,471.1	2,970.7	157.9	2,962.5	0.00	0.00	0.00
15,400.0	90.18	359.57	12,470.8	3,070.7	157.1	3,062.5	0.00	0.00	0.00
15,500.0	90.18	359.57	12,470.5	3,170.7	156.4	3,162.4	0.00	0.00	0.00
15,600.0	90.18	359.57	12,470.2	3,270.7	155.6	3,262.4	0.00	0.00	0.00
15,700.0	90.18	359.57	12,469.9	3,370.7	154.9	3,362.3	0.00	0.00	0.00
15,800.0	90.18	359.57	12,469.6	3,470.7	154.1	3,462.3	0.00	0.00	0.00
15,900.0	90.18	359.57	12,469.2	3,570.7	153.4	3,562.2	0.00	0.00	0.00
16,000.0	90.18	359.57	12,468.9	3,670.7	152.6	3,662.2	0.00	0.00	0.00
16,100.0	90.18	359.57	12,468.6	3,770.7	151.9	3,762.1	0.00	0.00	0.00
16,200.0	90.18	359.57	12,468.3	3,870.7	151.1	3,862.1	0.00	0.00	0.00
16,300.0	90.18	359.57	12,468.0	3,970.7	150.4	3,962.1	0.00	0.00	0.00
16,400.0	90.18	359.57	12,467.7	4,070.7	149.6	4,062.0	0.00	0.00	0.00
16,500.0	90.18	359.57	12,467.4	4,170.7	148.9	4,162.0	0.00	0.00	0.00
16,600.0	90.18	359.57	12,467.1	4,270.7	148.1	4,261.9	0.00	0.00	0.00
16,700.0	90.18	359.57	12,466.8	4,370.7	147.4	4,361.9	0.00	0.00	0.00
16,800.0	90.18	359.57	12,466.5	4,470.7	146.6	4,461.8	0.00	0.00	0.00
16,900.0	90.18	359.57	12,466.1	4,570.7	145.9	4,561.8	0.00	0.00	0.00
17,000.0	90.18	359.57	12,465.8	4,670.7	145.1	4,661.7	0.00	0.00	0.00
17,100.0	90.18	359.57	12,465.5	4,770.7	144.4	4,761.7	0.00	0.00	0.00
17,200.0	90.18	359.57	12,465.2	4,870.7	143.6	4,861.6	0.00	0.00	0.00
17,300.0	90.18	359.57	12,464.9	4,970.7	142.9	4,961.6	0.00	0.00	0.00
17,400.0	90.18	359.57	12,464.6	5,070.7	142.1	5,061.5	0.00	0.00	0.00
17,500.0	90.18	359.57	12,464.3	5,170.7	141.4	5,161.5	0.00	0.00	0.00
17,600.0	90.18	359.57	12,464.0	5,270.7	140.6	5,261.4	0.00	0.00	0.00
17,700.0	90.18	359.57	12,463.7	5,370.7	139.9	5,361.4	0.00	0.00	0.00
17,800.0	90.18	359.57	12,463.4	5,470.6	139.1	5,461.3	0.00	0.00	0.00
17,900.0	90.18	359.57	12,463.0	5,570.6	138.4	5,561.3	0.00	0.00	0.00
18,000.0	90.18	359.57	12,462.7	5,670.6	137.6	5,661.2	0.00	0.00	0.00
18,100.0	90.18	359.57	12,462.4	5,770.6	136.9	5,761.2	0.00	0.00	0.00
18,200.0	90.18	359.57	12,462.1	5,870.6	136.1	5,861.1	0.00	0.00	0.00
18,300.0	90.18	359.57	12,461.8	5,970.6	135.4	5,961.1	0.00	0.00	0.00
18,400.0	90.18	359.57	12,461.5	6,070.6	134.6	6,061.1	0.00	0.00	0.00
18,500.0	90.18	359.57	12,461.2	6,170.6	133.9	6,161.0	0.00	0.00	0.00
18,600.0	90.18	359.57	12,460.9	6,270.6	133.1	6,261.0	0.00	0.00	0.00
18,700.0	90.18	359.57	12,460.6	6,370.6	132.4	6,360.9	0.00	0.00	0.00
18,800.0	90.18	359.57	12,460.3	6,470.6	131.6	6,460.9	0.00	0.00	0.00
18,900.0	90.18	359.57	12,459.9	6,570.6	130.9	6,560.8	0.00	0.00	0.00
19,000.0	90.18	359.57	12,459.6	6,670.6	130.1	6,660.8	0.00	0.00	0.00
19,100.0	90.18	359.57	12,459.3	6,770.6	129.4	6,760.7	0.00	0.00	0.00
19,200.0	90.18	359.57	12,459.0	6,870.6	128.6	6,860.7	0.00	0.00	0.00
19,300.0	90.18	359.57	12,458.7	6,970.6	127.9	6,960.6	0.00	0.00	0.00
19,400.0	90.18	359.57	12,458.4	7,070.6	127.1	7,060.6	0.00	0.00	0.00
19,500.0	90.18	359.57	12,458.1	7,170.6	126.4	7,160.5	0.00	0.00	0.00
19,600.0	90.18	359.57	12,457.8	7,270.6	125.6	7,260.5	0.00	0.00	0.00
19,700.0	90.18	359.57	12,457.5	7,370.6	124.9	7,360.4	0.00	0.00	0.00
19,800.0	90.18	359.57	12,457.2	7,470.6	124.1	7,460.4	0.00	0.00	0.00

Database:	EDM 5000.1 Single User Db	Local Co-ordinate Reference:	Well Fez Federal Com #704H
Company:	COG Operating, LLC	TVD Reference:	well @ 3289.0usft (Noram #21)
Project:	Lea County, NM	MD Reference:	well @ 3289.0usft (Noram #21)
Site:	Sec 9, T25-S, R35-E	North Reference:	Grid
Well:	Fez Federal Com #704H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Design #1		

Planned Survey									
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
19,900.0	90.18	359.57	12,456.8	7,570.6	123.4	7,560.3	0.00	0.00	0.00
20,000.0	90.18	359.57	12,456.5	7,670.6	122.6	7,660.3	0.00	0.00	0.00
20,100.0	90.18	359.57	12,456.2	7,770.6	121.9	7,760.2	0.00	0.00	0.00
20,200.0	90.18	359.57	12,455.9	7,870.6	121.1	7,860.2	0.00	0.00	0.00
20,300.0	90.18	359.57	12,455.6	7,970.6	120.4	7,960.1	0.00	0.00	0.00
20,400.0	90.18	359.57	12,455.3	8,070.6	119.6	8,060.1	0.00	0.00	0.00
20,500.0	90.18	359.57	12,455.0	8,170.6	118.9	8,160.0	0.00	0.00	0.00
20,600.0	90.18	359.57	12,454.7	8,270.6	118.1	8,260.0	0.00	0.00	0.00
20,700.0	90.18	359.57	12,454.4	8,370.6	117.4	8,360.0	0.00	0.00	0.00
20,800.0	90.18	359.57	12,454.1	8,470.5	116.6	8,459.9	0.00	0.00	0.00
20,900.0	90.18	359.57	12,453.8	8,570.5	115.9	8,559.9	0.00	0.00	0.00
21,000.0	90.18	359.57	12,453.4	8,670.5	115.1	8,659.8	0.00	0.00	0.00
21,100.0	90.18	359.57	12,453.1	8,770.5	114.4	8,759.8	0.00	0.00	0.00
21,200.0	90.18	359.57	12,452.8	8,870.5	113.6	8,859.7	0.00	0.00	0.00
21,300.0	90.18	359.57	12,452.5	8,970.5	112.9	8,959.7	0.00	0.00	0.00
21,400.0	90.18	359.57	12,452.2	9,070.5	112.1	9,059.6	0.00	0.00	0.00
21,500.0	90.18	359.57	12,451.9	9,170.5	111.4	9,159.6	0.00	0.00	0.00
21,600.0	90.18	359.57	12,451.6	9,270.5	110.6	9,259.5	0.00	0.00	0.00
21,700.0	90.18	359.57	12,451.3	9,370.5	109.9	9,359.5	0.00	0.00	0.00
21,800.0	90.18	359.57	12,451.0	9,470.5	109.1	9,459.4	0.00	0.00	0.00
21,900.0	90.18	359.57	12,450.7	9,570.5	108.4	9,559.4	0.00	0.00	0.00
22,000.0	90.18	359.57	12,450.3	9,670.5	107.6	9,659.3	0.00	0.00	0.00
22,100.0	90.18	359.57	12,450.0	9,770.5	106.9	9,759.3	0.00	0.00	0.00
22,200.0	90.18	359.57	12,449.7	9,870.5	106.1	9,859.2	0.00	0.00	0.00
22,300.0	90.18	359.57	12,449.4	9,970.5	105.4	9,959.2	0.00	0.00	0.00
22,400.0	90.18	359.57	12,449.1	10,070.5	104.6	10,059.1	0.00	0.00	0.00
TD @ 22434.0' MD, 12449.0' TVD									
22,434.0	90.18	359.57	12,449.0	10,104.5	104.4	10,093.2	0.00	0.00	0.00

Design Targets									
Target Name	Dip Angle (°)	Dip Dir. (°)	TVD (usft)	+N/-S (usft)	+E/-W (usft)	Northing (usft)	Easting (usft)	Latitude	Longitude
- hit/miss target									
- Shape									
PBHL - Fez Fed Com	0.00	0.00	12,449.0	10,104.5	104.4	425,441.80	795,501.90	32° 9' 57.788 N	103° 22' 42.166 W
- plan hits target center									
- Point									
LTP - Fez Fed Com #	0.00	0.00	12,449.0	9,974.6	105.3	425,311.84	795,502.84	32° 9' 56.502 N	103° 22' 42.168 W
- plan misses target center by 0.4usft at 22304.1usft MD (12449.4 TVD, 9974.6 N, 105.3 E)									
- Point									
FTP - Fez Fed Com #	0.00	0.00	12,479.0	51.4	179.7	415,388.69	795,577.25	32° 8' 18.305 N	103° 22' 42.326 W
- plan misses target center by 132.5usft at 12440.9usft MD (12376.1 TVD, 135.0 N, 179.1 E)									
- Point									

Sec 9, T25-S, R35-E
Fez Federal Com #704H
Q180*** & WT-180***
Design #1

Company Name: COG Operating, LLC
Fez Federal Com #704H
Lea County, NM
Rig: Noram #21
Created by: Keith Noack
Date: 9-26, February 28 2018



PROJECT DETAILS: Lea County, NM

Geodetic System: US State Plane 1927 (Exact solution)
Datum: NAD 1927 (NADCON CONUS)
Ellipsoid: Clarke 1866
Zone: New Mexico East 3001
System Datum: Mean Sea Level

WELL DETAILS: Fez Federal Com #704H



3250.0
+N-S +E-W Northing Easting Latitude Longitude
0.0 0.0 416337.28 795397.53 32° 8' 17.812 N 103° 22' 44.422 W

DESIGN TARGET DETAILS

Name	TVD	+N-S	+E-W	Northing	Easting	Latitude	Longitude
LTP - Fez Fed Com #704H	12449.0	9974.6	106.3	425311.84	795502.85	32° 8' 56.502 N	103° 22' 42.168 W
PBM - Fez Fed Com #704H	12449.0	10104.6	104.4	425441.80	795501.90	32° 8' 67.788 N	103° 22' 42.166 W
FTP - Fez Fed Com #704H	12479.0	61.4	179.7	415388.70	785877.25	32° 8' 18.305 N	103° 22' 42.326 W

SECTION DETAILS

MD	Inc	Azi	TVD	+N-S	+E-W	Dleg	TFace	VSet	Annotation
0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.0	
2700.0	0.00	0.00	2700.0	0.0	0.0	0.00	0.00	0.0	Build 2.00"/100'
2900.0	4.00	105.00	2899.8	-1.8	8.7	2.00	105.00	-2.1	EOB: 4.00" Inc, 105.00° Azi
3400.0	4.00	105.00	3399.6	-10.9	40.4	0.00	0.00	-12.4	Build/Turn 2.00"/100'
3503.8	6.07	104.25	3502.0	-13.1	49.2	2.00	-2.20	-15.0	EOBT: 6.07" Inc, 104.25° Azi
4631.5	6.07	104.25	4623.4	-42.5	164.5	0.00	0.00	-48.8	Drop 2.00"/100'
4935.2	0.00	0.00	4926.6	-46.5	180.5	2.00	180.00	-53.3	EOD: 0.00" Inc, 0.00° Azi
12018.2	0.00	0.00	12001.6	-46.5	180.5	0.00	0.00	-53.3	KOP: Build 12.00"/100'
12761.7	90.18	359.67	12479.0	432.5	176.9	12.00	359.67	435.4	EOC: 90.18" Inc, 359.67° Azi, 12479.0' TVD
22434.0	90.18	359.67	12449.0	10104.6	104.4	0.00	0.00	10093.2	TD @ 22434.0' MD, 12449.0' TVD



Vertical Section at 357.91' (200 wt/vv)

Database:	EDM 5000.1 Single User Db	Local Co-ordinate Reference:	Well Fez Federal Com #704H
Company:	COG Operating, LLC	TVD Reference:	well @ 3289.0usft (Noram #21)
Project:	Lea County, NM	MD Reference:	well @ 3289.0usft (Noram #21)
Site:	Sec 9, T25-S, R35-E	North Reference:	Grid
Well:	Fez Federal Com #704H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Design #1		

Formations					
Measured Depth (usft)	Vertical Depth (usft)	Name	Lithology	Dip (°)	Dip Direction (°)
870.0	870.0	Rustler			
1,211.0	1,211.0	TOS			
5,014.7	5,006.0	BOS (Fletcher)			
5,345.7	5,337.0	LMAR (Top Delaware)			
5,377.7	5,369.0	BLCN			
6,316.7	6,308.0	CYCN			
7,776.7	7,768.0	BYCN			
9,007.7	8,999.0	Bone Sprg (BSGL)			
9,224.7	9,216.0	U Avalon Sh			
9,588.7	9,580.0	L Avalon Sh			
10,405.7	10,397.0	FBSG_sand			
10,925.7	10,917.0	SBSG_sand			
11,399.7	11,391.0	SBSG_sand base			
11,982.7	11,974.0	TBSG_sand			
12,443.9	12,378.0	WFMP			
12,662.5	12,469.0	WFMP Lith			

Plan Annotations					
Measured Depth (usft)	Vertical Depth (usft)	Local Coordinates			
		+N/-S (usft)	+E/-W (usft)	Comment	
2,700.0	2,700.0	0.0	0.0	Build 2.00°/100'	
2,900.0	2,899.8	-1.8	6.7	EOB: 4.00° Inc, 105.00° Azi	
3,400.0	3,398.6	-10.8	40.4	Build/Turn 2.00°/100'	
3,503.8	3,502.0	-13.1	49.2	EOBT: 6.07° Inc, 104.25° Azi	
4,631.5	4,623.4	-42.5	164.9	Drop 2.00°/100'	
4,935.2	4,926.5	-46.4	180.5	EOD: 0.00° Inc, 0.00° Azi	
12,010.2	12,001.5	-46.4	180.5	KOP : Build 12.00°/100'	
12,761.7	12,479.0	432.5	176.9	EOC: 90.18° Inc, 359.57° Azi, 12479.0' TVD	
22,434.0	12,449.0	10,104.5	104.4	TD @ 22434.0' MD, 12449.0' TVD	



COG Operating, LLC

Lea County, NM

Sec 9, T25-S, R35-E

Fez Federal Com #704H

Wellbore #1

Design #1

QES Anticollision Report

28 February, 2018



Company:	COG Operating, LLC	Local Co-ordinate Reference:	Well Fez Federal Com #704H
Project:	Lea County, NM	TVD Reference:	well @ 3289.0usft (Noram #21)
Reference Site:	Sec 9, T25-S, R35-E	MD Reference:	well @ 3289.0usft (Noram #21)
Site Error:	0.0 usft	North Reference:	Grid
Reference Well:	Fez Federal Com #704H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.0 usft	Output errors are at	2.00 sigma
Reference Wellbore	Wellbore #1	Database:	EDM 5000.1 Single User Db
Reference Design:	Design #1	Offset TVD Reference:	Offset Datum

Reference Design #1

Filter type: NO GLOBAL FILTER: Using user defined selection & filtering criteria
Interpolation Method: Stations Error Model: ISCWSA
Depth Range: Unlimited Scan Method: Closest Approach 3D
Results Limited by: Maximum center-center distance of 5,000.0 usft Error Surface: Pedal Curve
Warning Levels Evaluated at: 2.00 Sigma

Survey Tool Program Date: 2/28/2018

From (usft)	To (usft)	Survey (Wellbore)	Tool Name	Description
0.0	22,434.0	Design #1 (Wellbore #1)	MWD	OWSG MWD - Standard

Summary

Site Name	Reference Measured Depth (usft)	Offset Measured Depth (usft)	Distance Between Centres (usft)	Distance Between Ellipses (usft)	Separation Factor	Warning
Offset Well - Wellbore - Design						
Sec 9, T25-S, R35-E						
Fez Federal Com #604H - Wellbore #1 - Design #1	2,700.0	2,703.0	30.0	11.1	1.588 CC	
Fez Federal Com #705H - Wellbore #1 - Design #1	916.0	918.0	60.1	53.9	9.826 CC	
Fez Fee #11H - Wellbore #1 - Wellbore #1	16,872.6	9,689.0	3,158.1	3,099.4	53.795 CC	
Fez Fee #11H - Wellbore #1 - Wellbore #1	16,900.0	9,689.0	3,158.2	3,099.3	53.628 ES	
Fez Fee #11H - Wellbore #1 - Wellbore #1	18,000.0	9,689.0	3,353.3	3,286.3	50.060 SF	

Offset Design Sec 9, T25-S, R35-E - Fez Federal Com #604H - Wellbore #1 - Design #1

Survey Program: 0-MWD

Offset Site Error: 0.0 usft.

Offset Well Error: 0.0 usft.

Reference Measured Depth (usft)	Vertical Depth (usft)	Offset Measured Depth (usft)	Vertical Depth (usft)	Semi Major Axis Reference (usft)	Semi Major Axis Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	Offset Wellbore Centre +E/-W (usft)	Distance Between Centres (usft)	Distance Between Ellipses (usft)	Separation Factor	Warning
0.0	0.0	3.0	3.0	0.0	0.0	-90.51	-0.3	-30.0	30.0			
100.0	100.0	103.0	103.0	0.1	0.1	-90.51	-0.3	-30.0	30.0	29.8	113.195	
200.0	200.0	203.0	203.0	0.5	0.5	-90.51	-0.3	-30.0	30.0	29.0	30.571	
300.0	300.0	303.0	303.0	0.8	0.9	-90.51	-0.3	-30.0	30.0	28.3	17.672	
400.0	400.0	403.0	403.0	1.2	1.2	-90.51	-0.3	-30.0	30.0	27.6	12.428	
500.0	500.0	503.0	503.0	1.6	1.6	-90.51	-0.3	-30.0	30.0	26.9	9.584	
600.0	600.0	603.0	603.0	1.9	1.9	-90.51	-0.3	-30.0	30.0	26.2	7.799	
700.0	700.0	703.0	703.0	2.3	2.3	-90.51	-0.3	-30.0	30.0	25.5	6.575	
800.0	800.0	803.0	803.0	2.6	2.6	-90.51	-0.3	-30.0	30.0	24.7	5.683	
900.0	900.0	903.0	903.0	3.0	3.0	-90.51	-0.3	-30.0	30.0	24.0	5.004	
1,000.0	1,000.0	1,003.0	1,003.0	3.4	3.4	-90.51	-0.3	-30.0	30.0	23.3	4.470	
1,100.0	1,100.0	1,103.0	1,103.0	3.7	3.7	-90.51	-0.3	-30.0	30.0	22.6	4.039	
1,200.0	1,200.0	1,203.0	1,203.0	4.1	4.1	-90.51	-0.3	-30.0	30.0	21.9	3.684	
1,300.0	1,300.0	1,303.0	1,303.0	4.4	4.4	-90.51	-0.3	-30.0	30.0	21.2	3.386	
1,400.0	1,400.0	1,403.0	1,403.0	4.8	4.8	-90.51	-0.3	-30.0	30.0	20.4	3.133	
1,500.0	1,500.0	1,503.0	1,503.0	5.1	5.2	-90.51	-0.3	-30.0	30.0	19.7	2.915	
1,600.0	1,600.0	1,603.0	1,603.0	5.5	5.5	-90.51	-0.3	-30.0	30.0	19.0	2.725	
1,700.0	1,700.0	1,703.0	1,703.0	5.9	5.9	-90.51	-0.3	-30.0	30.0	18.3	2.558	
1,800.0	1,800.0	1,803.0	1,803.0	6.2	6.2	-90.51	-0.3	-30.0	30.0	17.6	2.411	
1,900.0	1,900.0	1,903.0	1,903.0	6.6	6.6	-90.51	-0.3	-30.0	30.0	16.9	2.280	
2,000.0	2,000.0	2,003.0	2,003.0	6.9	6.9	-90.51	-0.3	-30.0	30.0	16.1	2.162	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

Company:	COG Operating, LLC	Local Co-ordinate Reference:	Well Fez Federal Com #704H
Project:	Lea County, NM	TVD Reference:	well @ 3289.0usft (Noram #21)
Reference Site:	Sec 9, T25-S, R35-E	MD Reference:	well @ 3289.0usft (Noram #21)
Site Error:	0.0 usft	North Reference:	Grid
Reference Well:	Fez Federal Com #704H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.0 usft	Output errors are at	2.00 sigma
Reference Wellbore	Wellbore #1	Database:	EDM 5000.1 Single User Db
Reference Design:	Design #1	Offset TVD Reference:	Offset Datum

Offset Design												Offset Site Error:	0.0 usft
Survey Program: 0-MWD												Offset Well Error:	0.0 usft
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Semi Major Axis Reference (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	Offset Wellbore Centre +E/-W (usft)	Distance Between Centres (usft)	Distance Between Ellipses (usft)	Separation Factor	Warning	
2,100.0	2,100.0	2,103.0	2,103.0	7.3	7.3	-90.51	-0.3	-30.0	30.0	15.4	2.056		
2,200.0	2,200.0	2,203.0	2,203.0	7.7	7.7	-90.51	-0.3	-30.0	30.0	14.7	1.960		
2,300.0	2,300.0	2,303.0	2,303.0	8.0	8.0	-90.51	-0.3	-30.0	30.0	14.0	1.872		
2,400.0	2,400.0	2,403.0	2,403.0	8.4	8.4	-90.51	-0.3	-30.0	30.0	13.3	1.792		
2,500.0	2,500.0	2,503.0	2,503.0	8.7	8.7	-90.51	-0.3	-30.0	30.0	12.6	1.719		
2,600.0	2,600.0	2,603.0	2,603.0	9.1	9.1	-90.51	-0.3	-30.0	30.0	11.8	1.651		
2,700.0	2,700.0	2,703.0	2,703.0	9.4	9.5	-90.51	-0.3	-30.0	30.0	11.1	1.588 CC		
2,800.0	2,800.0	2,803.0	2,803.0	9.8	9.8	165.33	-0.3	-30.0	31.7	12.1	1.617		
2,900.0	2,899.8	2,902.8	2,902.8	10.1	10.2	167.37	-0.3	-30.0	36.8	16.5	1.812		
3,000.0	2,999.6	3,002.6	3,002.6	10.5	10.5	169.37	-0.3	-30.0	43.6	22.6	2.078		
3,100.0	3,099.4	3,102.4	3,102.4	10.8	10.9	170.83	-0.3	-30.0	50.5	28.8	2.328		
3,200.0	3,199.1	3,202.1	3,202.1	11.2	11.2	171.94	-0.3	-30.0	57.4	35.0	2.563		
3,300.0	3,298.9	3,301.9	3,301.9	11.5	11.6	172.81	-0.3	-30.0	64.3	41.2	2.785		
3,400.0	3,398.6	3,401.6	3,401.6	11.9	12.0	173.51	-0.3	-30.0	71.2	47.5	2.994		
3,503.8	3,502.0	3,505.0	3,505.0	12.2	12.3	174.93	-0.3	-30.0	80.3	55.8	3.275		
3,600.0	3,597.7	3,600.7	3,600.7	12.6	12.7	175.50	-0.3	-30.0	90.5	65.3	3.590		
3,700.0	3,697.1	3,700.1	3,700.1	12.9	13.0	175.97	-0.3	-30.0	101.0	75.1	3.901		
3,800.0	3,796.5	3,799.5	3,799.5	13.3	13.4	176.36	-0.3	-30.0	111.6	85.0	4.195		
3,900.0	3,896.0	3,899.0	3,899.0	13.7	13.7	176.67	-0.3	-30.0	122.1	94.8	4.473		
4,000.0	3,995.4	3,998.4	3,998.4	14.0	14.1	176.94	-0.3	-30.0	132.7	104.7	4.738		
4,100.0	4,094.9	4,097.9	4,097.9	14.4	14.5	177.16	-0.3	-30.0	143.3	114.6	4.990		
4,200.0	4,194.3	4,197.3	4,197.3	14.8	14.8	177.36	-0.3	-30.0	153.8	124.4	5.230		
4,300.0	4,293.7	4,296.7	4,296.7	15.1	15.2	177.53	-0.3	-30.0	164.4	134.3	5.458		
4,400.0	4,393.2	4,396.2	4,396.2	15.5	15.5	177.68	-0.3	-30.0	175.0	144.1	5.676		
4,500.0	4,492.6	4,495.6	4,495.6	15.9	15.9	177.81	-0.3	-30.0	185.6	154.0	5.883		
4,600.0	4,592.1	4,595.1	4,595.1	16.2	16.2	177.93	-0.3	-30.0	196.1	163.9	6.082		
4,631.5	4,623.4	4,626.4	4,626.4	16.4	16.4	177.96	-0.3	-30.0	199.5	167.0	6.143		
4,700.0	4,691.6	4,694.6	4,694.6	16.6	16.6	178.03	-0.3	-30.0	205.9	172.9	6.247		
4,800.0	4,791.4	4,794.4	4,794.4	17.0	17.0	178.10	-0.3	-30.0	212.3	178.7	6.307		
4,900.0	4,891.3	4,894.3	4,894.3	17.3	17.3	178.12	-0.3	-30.0	215.3	180.9	6.264		
4,935.2	4,926.5	4,929.5	4,929.5	17.5	17.4	-77.63	-0.3	-30.0	215.5	180.9	6.225		
5,000.0	4,991.3	4,994.3	4,994.3	17.7	17.7	-77.63	-0.3	-30.0	215.5	180.4	6.143		
5,100.0	5,091.3	5,094.3	5,094.3	18.0	18.0	-77.63	-0.3	-30.0	215.5	179.7	6.021		
5,200.0	5,191.3	5,194.3	5,194.3	18.4	18.4	-77.63	-0.3	-30.0	215.5	179.0	5.904		
5,300.0	5,291.3	5,294.3	5,294.3	18.7	18.7	-77.63	-0.3	-30.0	215.5	178.3	5.791		
5,400.0	5,391.3	5,394.3	5,394.3	19.1	19.1	-77.63	-0.3	-30.0	215.5	177.6	5.682		
5,500.0	5,491.3	5,494.3	5,494.3	19.4	19.5	-77.63	-0.3	-30.0	215.5	176.9	5.577		
5,600.0	5,591.3	5,594.3	5,594.3	19.8	19.8	-77.63	-0.3	-30.0	215.5	176.2	5.476		
5,700.0	5,691.3	5,694.3	5,694.3	20.1	20.2	-77.63	-0.3	-30.0	215.5	175.5	5.379		
5,800.0	5,791.3	5,794.3	5,794.3	20.5	20.5	-77.63	-0.3	-30.0	215.5	174.8	5.285		
5,900.0	5,891.3	5,894.3	5,894.3	20.8	20.9	-77.63	-0.3	-30.0	215.5	174.0	5.194		
6,000.0	5,991.3	5,994.3	5,994.3	21.2	21.3	-77.63	-0.3	-30.0	215.5	173.3	5.107		
6,100.0	6,091.3	6,094.3	6,094.3	21.5	21.6	-77.63	-0.3	-30.0	215.5	172.6	5.022		
6,200.0	6,191.3	6,194.3	6,194.3	21.9	22.0	-77.63	-0.3	-30.0	215.5	171.9	4.940		
6,300.0	6,291.3	6,294.3	6,294.3	22.2	22.3	-77.63	-0.3	-30.0	215.5	171.2	4.860		
6,400.0	6,391.3	6,394.3	6,394.3	22.6	22.7	-77.63	-0.3	-30.0	215.5	170.5	4.783		
6,500.0	6,491.3	6,494.3	6,494.3	22.9	23.0	-77.63	-0.3	-30.0	215.5	169.8	4.709		
6,600.0	6,591.3	6,594.3	6,594.3	23.3	23.4	-77.63	-0.3	-30.0	215.5	169.0	4.636		
6,700.0	6,691.3	6,694.3	6,694.3	23.7	23.8	-77.63	-0.3	-30.0	215.5	168.3	4.566		
6,800.0	6,791.3	6,794.3	6,794.3	24.0	24.1	-77.63	-0.3	-30.0	215.5	167.6	4.498		
6,900.0	6,891.3	6,894.3	6,894.3	24.4	24.5	-77.63	-0.3	-30.0	215.5	166.9	4.432		
7,000.0	6,991.3	6,994.3	6,994.3	24.7	24.8	-77.63	-0.3	-30.0	215.5	166.2	4.368		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

Company:	COG Operating, LLC	Local Co-ordinate Reference:	Well Fez Federal Com #704H
Project:	Lea County, NM	TVD Reference:	well @ 3289.0usft (Noram #21)
Reference Site:	Sec 9, T25-S, R35-E	MD Reference:	well @ 3289.0usft (Noram #21)
Site Error:	0.0 usft	North Reference:	Grid
Reference Well:	Fez Federal Com #704H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.0 usft	Output errors are at	2.00 sigma
Reference Wellbore	Wellbore #1	Database:	EDM 5000.1 Single User Db
Reference Design:	Design #1	Offset TVD Reference:	Offset Datum

Offset Design Sec 9, T25-S, R35-E - Fez Federal Com #604H - Wellbore #1 - Design #1												Offset Site Error:	0.0 usft
Survey Program: Q-MWD												Offset Well Error:	0.0 usft
Reference Measured Depth (usft)	Vertical Depth (usft)	Offset Measured Depth (usft)	Vertical Depth (usft)	Semi Major Axis Reference (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	+E/-W (usft)	Distance Between Centres (usft)	Between Ellipses (usft)	Separation Factor	Warning	
7,100.0	7,091.3	7,094.3	7,094.3	25.1	25.2	-77.63	-0.3	-30.0	215.5	165.5	4.306		
7,200.0	7,191.3	7,194.3	7,194.3	25.4	25.6	-77.63	-0.3	-30.0	215.5	164.8	4.245		
7,300.0	7,291.3	7,294.3	7,294.3	25.8	25.9	-77.63	-0.3	-30.0	215.5	164.0	4.186		
7,400.0	7,391.3	7,394.3	7,394.3	26.1	26.3	-77.63	-0.3	-30.0	215.5	163.3	4.129		
7,500.0	7,491.3	7,494.3	7,494.3	26.5	26.6	-77.63	-0.3	-30.0	215.5	162.6	4.073		
7,600.0	7,591.3	7,594.3	7,594.3	26.8	27.0	-77.63	-0.3	-30.0	215.5	161.9	4.019		
7,700.0	7,691.3	7,694.3	7,694.3	27.2	27.4	-77.63	-0.3	-30.0	215.5	161.2	3.966		
7,800.0	7,791.3	7,794.3	7,794.3	27.5	27.7	-77.63	-0.3	-30.0	215.5	160.5	3.915		
7,900.0	7,891.3	7,894.3	7,894.3	27.9	28.1	-77.63	-0.3	-30.0	215.5	159.8	3.865		
8,000.0	7,991.3	7,994.3	7,994.3	28.3	28.4	-77.63	-0.3	-30.0	215.5	159.0	3.816		
8,100.0	8,091.3	8,094.3	8,094.3	28.6	28.8	-77.63	-0.3	-30.0	215.5	158.3	3.768		
8,200.0	8,191.3	8,194.3	8,194.3	29.0	29.1	-77.63	-0.3	-30.0	215.5	157.6	3.722		
8,300.0	8,291.3	8,294.3	8,294.3	29.3	29.5	-77.63	-0.3	-30.0	215.5	156.9	3.676		
8,400.0	8,391.3	8,394.3	8,394.3	29.7	29.9	-77.63	-0.3	-30.0	215.5	156.2	3.632		
8,500.0	8,491.3	8,494.3	8,494.3	30.0	30.2	-77.63	-0.3	-30.0	215.5	155.5	3.589		
8,600.0	8,591.3	8,594.3	8,594.3	30.4	30.6	-77.63	-0.3	-30.0	215.5	154.8	3.546		
8,700.0	8,691.3	8,694.3	8,694.3	30.7	30.9	-77.63	-0.3	-30.0	215.5	154.0	3.505		
8,800.0	8,791.3	8,794.3	8,794.3	31.1	31.3	-77.63	-0.3	-30.0	215.5	153.3	3.465		
8,900.0	8,891.3	8,894.3	8,894.3	31.5	31.7	-77.63	-0.3	-30.0	215.5	152.6	3.426		
9,000.0	8,991.3	8,994.3	8,994.3	31.8	32.0	-77.63	-0.3	-30.0	215.5	151.9	3.387		
9,100.0	9,091.3	9,094.3	9,094.3	32.2	32.4	-77.63	-0.3	-30.0	215.5	151.2	3.349		
9,200.0	9,191.3	9,194.3	9,194.3	32.5	32.7	-77.63	-0.3	-30.0	215.5	150.5	3.313		
9,300.0	9,291.3	9,294.3	9,294.3	32.9	33.1	-77.63	-0.3	-30.0	215.5	149.8	3.277		
9,400.0	9,391.3	9,394.3	9,394.3	33.2	33.4	-77.63	-0.3	-30.0	215.5	149.0	3.241		
9,500.0	9,491.3	9,494.3	9,494.3	33.6	33.8	-77.63	-0.3	-30.0	215.5	148.3	3.207		
9,600.0	9,591.3	9,594.3	9,594.3	33.9	34.2	-77.63	-0.3	-30.0	215.5	147.6	3.173		
9,700.0	9,691.3	9,694.3	9,694.3	34.3	34.5	-77.63	-0.3	-30.0	215.5	146.9	3.140		
9,800.0	9,791.3	9,794.3	9,794.3	34.7	34.9	-77.63	-0.3	-30.0	215.5	146.2	3.108		
9,900.0	9,891.3	9,894.3	9,894.3	35.0	35.2	-77.63	-0.3	-30.0	215.5	145.5	3.076		
10,000.0	9,991.3	9,994.3	9,994.3	35.4	35.6	-77.63	-0.3	-30.0	215.5	144.7	3.045		
10,100.0	10,091.3	10,094.3	10,094.3	35.7	36.0	-77.63	-0.3	-30.0	215.5	144.0	3.014		
10,200.0	10,191.3	10,194.3	10,194.3	36.1	36.3	-77.63	-0.3	-30.0	215.5	143.3	2.984		
10,300.0	10,291.3	10,294.3	10,294.3	36.4	36.7	-77.63	-0.3	-30.0	215.5	142.6	2.955		
10,400.0	10,391.3	10,394.3	10,394.3	36.8	37.0	-77.63	-0.3	-30.0	215.5	141.9	2.926		
10,500.0	10,491.3	10,494.3	10,494.3	37.1	37.4	-77.63	-0.3	-30.0	215.5	141.2	2.898		
10,600.0	10,591.3	10,594.3	10,594.3	37.5	37.7	-77.63	-0.3	-30.0	215.5	140.5	2.871		
10,700.0	10,691.3	10,694.3	10,694.3	37.9	38.1	-77.63	-0.3	-30.0	215.5	139.7	2.844		
10,800.0	10,791.3	10,794.3	10,794.3	38.2	38.5	-77.63	-0.3	-30.0	215.5	139.0	2.817		
10,900.0	10,891.3	10,894.3	10,894.3	38.6	38.8	-77.63	-0.3	-30.0	215.5	138.3	2.791		
11,000.0	10,991.3	10,994.3	10,994.3	38.9	39.2	-77.63	-0.3	-30.0	215.5	137.6	2.765		
11,100.0	11,091.3	11,094.3	11,094.3	39.3	39.5	-77.63	-0.3	-30.0	215.5	136.9	2.740		
11,200.0	11,191.3	11,194.3	11,194.3	39.6	39.9	-77.63	-0.3	-30.0	215.5	136.2	2.715		
11,300.0	11,291.3	11,294.3	11,294.3	40.0	40.3	-77.63	-0.3	-30.0	215.5	135.4	2.691		
11,400.0	11,391.3	11,394.3	11,394.3	40.4	40.6	-77.63	-0.3	-30.0	215.5	134.7	2.667		
11,500.0	11,491.3	11,494.3	11,494.3	40.7	41.0	-77.63	-0.3	-30.0	215.5	134.0	2.644		
11,600.0	11,591.3	11,594.3	11,594.3	41.1	41.3	-77.63	-0.3	-30.0	215.5	133.3	2.621		
11,700.0	11,691.3	11,694.3	11,694.3	41.4	41.7	-77.63	-0.3	-30.0	215.5	132.6	2.598		
11,800.0	11,791.3	11,794.3	11,794.3	41.8	42.0	-77.63	-0.3	-30.0	215.5	131.9	2.576		
11,805.2	11,796.5	11,799.5	11,799.5	41.8	42.1	-77.63	-0.3	-30.0	215.5	131.8	2.575		
11,900.0	11,891.3	11,889.7	11,889.6	42.1	42.4	-77.08	1.8	-30.0	216.1	131.7	2.562		
12,000.0	11,991.3	11,977.2	11,975.5	42.5	42.7	-72.99	18.0	-30.2	221.1	136.3	2.607		
12,010.2	12,001.5	11,985.7	11,983.7	42.5	42.7	-72.40	20.4	-30.2	222.0	137.2	2.617		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

Company:	COG Operating, LLC	Local Co-ordinate Reference:	Well Fez Federal Com #704H
Project:	Lea County, NM	TVD Reference:	well @ 3289.0usft (Noram #21)
Reference Site:	Sec 9, T25-S, R35-E	MD Reference:	well @ 3289.0usft (Noram #21)
Site Error:	0.0 usft	North Reference:	Grid
Reference Well:	Fez Federal Com #704H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.0 usft	Output errors are at	2.00 sigma
Reference Wellbore	Wellbore #1	Database:	EDM 5000.1 Single User Db
Reference Design:	Design #1	Offset TVD Reference:	Offset Datum

Offset Design												Offset Site Error:	0.0 usft
Survey Program: 0-MVVD												Offset Well Error:	0.0 usft
Reference Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Semi Major Axis Reference (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	+E/-W (usft)	Distance Between Centres (usft)	Between Ellipses (usft)	Separation Factor	Warning	
12,025.0	12,016.3	11,998.0	11,995.4	42.6	42.8	-70.94	24.1	-30.2	223.4	138.6	2.634		
12,050.0	12,041.3	12,018.6	12,014.8	42.7	42.8	-69.26	31.0	-30.3	225.9	141.1	2.663		
12,075.0	12,066.1	12,039.0	12,033.7	42.8	42.9	-67.66	38.7	-30.3	228.5	143.7	2.695		
12,100.0	12,090.8	12,059.2	12,052.0	42.9	43.0	-66.14	47.1	-30.4	231.1	146.4	2.729		
12,125.0	12,115.2	12,079.2	12,069.9	42.9	43.0	-64.70	56.1	-30.4	233.8	149.3	2.765		
12,150.0	12,139.3	12,100.0	12,088.0	43.0	43.1	-63.30	66.3	-30.5	236.6	152.1	2.802		
12,175.0	12,163.1	12,118.8	12,104.0	43.1	43.2	-62.07	76.2	-30.6	239.3	155.1	2.843		
12,200.0	12,186.4	12,138.3	12,120.2	43.2	43.2	-60.87	87.2	-30.7	242.0	158.1	2.885		
12,225.0	12,209.1	12,157.8	12,135.8	43.3	43.3	-59.76	98.7	-30.8	244.6	161.0	2.927		
12,250.0	12,231.4	12,175.0	12,149.3	43.3	43.3	-58.80	109.4	-30.8	247.2	164.1	2.975		
12,275.0	12,252.9	12,196.3	12,165.4	43.4	43.4	-57.76	123.4	-31.0	249.7	166.8	3.013		
12,300.0	12,273.8	12,215.5	12,179.3	43.5	43.4	-56.87	136.5	-31.0	252.1	169.6	3.056		
12,325.0	12,294.0	12,234.5	12,192.6	43.5	43.5	-56.06	150.2	-31.2	254.3	172.3	3.099		
12,350.0	12,313.3	12,253.5	12,205.4	43.6	43.6	-55.32	164.2	-31.3	256.5	174.8	3.142		
12,375.0	12,331.8	12,275.0	12,219.1	43.6	43.6	-54.58	180.8	-31.4	258.5	177.1	3.177		
12,400.0	12,349.4	12,291.2	12,228.9	43.7	43.7	-54.04	193.6	-31.5	260.3	179.5	3.223		
12,425.0	12,366.1	12,309.9	12,239.8	43.7	43.7	-53.51	208.9	-31.6	261.9	181.6	3.262		
12,450.0	12,381.7	12,328.6	12,250.0	43.8	43.8	-53.05	224.6	-31.7	263.4	183.5	3.298		
12,475.0	12,396.3	12,350.0	12,260.9	43.8	43.8	-52.61	243.0	-31.8	264.7	185.1	3.324		
12,500.0	12,409.8	12,365.9	12,268.4	43.9	43.9	-52.31	257.0	-32.0	265.8	186.7	3.361		
12,525.0	12,422.2	12,384.5	12,276.7	44.0	43.9	-52.04	273.6	-32.1	266.7	188.0	3.388		
12,550.0	12,433.4	12,400.0	12,283.1	44.0	44.0	-51.85	287.8	-32.2	267.4	189.2	3.419		
12,575.0	12,443.5	12,421.6	12,291.2	44.1	44.0	-51.68	307.8	-32.3	267.9	189.8	3.430		
12,600.0	12,452.3	12,440.1	12,297.4	44.2	44.1	-51.60	325.2	-32.5	268.2	190.3	3.444		
12,625.0	12,460.0	12,458.7	12,303.0	44.2	44.1	-51.58	342.9	-32.6	268.3	190.6	3.453		
12,650.0	12,466.3	12,475.0	12,307.3	44.3	44.2	-51.61	358.7	-32.7	268.1	190.7	3.461		
12,675.0	12,471.4	12,495.7	12,312.0	44.4	44.2	-51.72	378.9	-32.9	267.8	190.3	3.456		
12,700.0	12,475.2	12,514.3	12,315.5	44.4	44.3	-51.88	397.1	-33.0	267.2	189.8	3.449		
12,725.0	12,477.7	12,532.9	12,318.2	44.5	44.3	-52.11	415.5	-33.1	266.5	188.9	3.437		
12,750.0	12,478.9	12,550.0	12,320.1	44.5	44.4	-52.38	432.5	-33.3	265.5	187.9	3.420		
12,761.7	12,479.0	12,560.2	12,321.0	44.6	44.4	-52.56	442.6	-33.3	265.0	187.3	3.409		
12,800.0	12,478.8	12,588.8	12,322.2	44.7	44.5	-52.78	471.2	-33.6	263.9	186.0	3.386		
12,811.4	12,478.8	12,597.7	12,322.2	44.7	44.5	-52.79	480.1	-33.6	263.9	185.9	3.383		
12,900.0	12,478.5	12,686.3	12,322.0	45.0	44.7	-52.79	568.7	-34.3	263.9	185.5	3.365		
13,000.0	12,478.2	12,786.3	12,321.6	45.3	45.1	-52.79	668.7	-35.0	263.9	184.9	3.342		
13,100.0	12,477.9	12,886.3	12,321.3	45.7	45.5	-52.79	768.7	-35.8	263.9	184.3	3.314		
13,200.0	12,477.6	12,986.3	12,321.0	46.2	45.9	-52.79	868.7	-36.5	263.9	183.5	3.284		
13,300.0	12,477.3	13,086.3	12,320.7	46.7	46.5	-52.79	968.7	-37.3	263.9	182.7	3.250		
13,400.0	12,477.0	13,186.3	12,320.4	47.3	47.0	-52.78	1,068.7	-38.0	263.9	181.8	3.214		
13,500.0	12,476.7	13,286.3	12,320.1	47.9	47.6	-52.78	1,168.7	-38.8	263.9	180.8	3.175		
13,600.0	12,476.4	13,386.3	12,319.8	48.6	48.3	-52.78	1,268.7	-39.5	263.9	179.7	3.134		
13,700.0	12,476.1	13,486.3	12,319.4	49.3	49.0	-52.78	1,368.7	-40.3	263.9	178.5	3.092		
13,800.0	12,475.7	13,586.3	12,319.1	50.1	49.8	-52.78	1,468.7	-41.0	263.9	177.3	3.048		
13,900.0	12,475.4	13,686.3	12,318.8	50.9	50.6	-52.78	1,568.7	-41.8	263.9	176.0	3.002		
14,000.0	12,475.1	13,786.3	12,318.5	51.7	51.4	-52.78	1,668.7	-42.5	263.9	174.6	2.956		
14,100.0	12,474.8	13,886.3	12,318.2	52.6	52.3	-52.78	1,768.7	-43.3	263.9	173.2	2.909		
14,200.0	12,474.5	13,986.3	12,317.9	53.5	53.2	-52.78	1,868.7	-44.0	263.9	171.7	2.862		
14,300.0	12,474.2	14,086.3	12,317.6	54.5	54.1	-52.78	1,968.7	-44.8	263.9	170.1	2.814		
14,400.0	12,473.9	14,186.3	12,317.2	55.5	55.1	-52.78	2,068.7	-45.5	263.9	168.5	2.766		
14,500.0	12,473.6	14,286.3	12,316.9	56.5	56.1	-52.77	2,168.7	-46.3	263.9	166.8	2.719		
14,600.0	12,473.3	14,386.3	12,316.6	57.5	57.2	-52.77	2,268.7	-47.0	263.9	165.1	2.671		
14,700.0	12,473.0	14,486.3	12,316.3	58.6	58.2	-52.77	2,368.7	-47.8	263.9	163.4	2.624		

CC - Min centre to center distance or covergent point, SF - min separation factor, ES - min ellipse separation

Company:	COG Operating, LLC	Local Co-ordinate Reference:	Well Fez Federal Com #704H
Project:	Lea County, NM	TVD Reference:	well @ 3289.0usft (Noram #21)
Reference Site:	Sec 9, T25-S, R35-E	MD Reference:	well @ 3289.0usft (Noram #21)
Site Error:	0.0 usft	North Reference:	Grid
Reference Well:	Fez Federal Com #704H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.0 usft	Output errors are at	2.00 sigma
Reference Wellbore	Wellbore #1	Database:	EDM 5000.1 Single User Db
Reference Design:	Design #1	Offset TVD Reference:	Offset Datum

Offset Design	Sec 9, T25-S, R35-E - Fez Federal Com #604H - Wellbore #1 - Design #1	Offset Site Error:	0.0 usft
Survey Program:	0-MWD	Offset Well Error:	0.0 usft

Reference Measured Depth (usft)	Vertical Depth (usft)	Offset Measured Depth (usft)	Vertical Depth (usft)	Semi Major Axis Reference (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	Distance Between Centres (usft)	Between Ellipses (usft)	Separation Factor	Warning
14,800.0	12,472.6	14,586.3	12,316.0	59.7	59.3	-52.77	2,468.7	-48.5	263.9	161.5	2.578
14,900.0	12,472.3	14,686.3	12,315.7	60.8	60.5	-52.77	2,568.7	-49.3	263.9	159.7	2.532
15,000.0	12,472.0	14,786.3	12,315.4	62.0	61.6	-52.77	2,668.7	-50.0	263.9	157.8	2.487
15,100.0	12,471.7	14,886.3	12,315.0	63.2	62.8	-52.77	2,768.7	-50.7	263.9	155.8	2.442
15,200.0	12,471.4	14,986.3	12,314.7	64.4	64.0	-52.77	2,868.7	-51.5	263.9	153.9	2.398
15,300.0	12,471.1	15,086.3	12,314.4	65.6	65.2	-52.77	2,968.7	-52.2	263.9	151.9	2.355
15,400.0	12,470.8	15,186.3	12,314.1	66.8	66.4	-52.77	3,068.7	-53.0	263.9	149.8	2.313
15,500.0	12,470.5	15,286.3	12,313.8	68.0	67.7	-52.76	3,168.6	-53.7	263.9	147.7	2.272
15,600.0	12,470.2	15,386.3	12,313.5	69.3	68.9	-52.76	3,268.6	-54.5	263.9	145.6	2.231
15,700.0	12,469.9	15,486.3	12,313.2	70.6	70.2	-52.76	3,368.6	-55.2	263.9	143.5	2.192
15,800.0	12,469.6	15,586.3	12,312.8	71.9	71.5	-52.76	3,468.6	-56.0	263.9	141.3	2.153
15,900.0	12,469.2	15,686.3	12,312.5	73.2	72.8	-52.76	3,568.6	-56.7	263.9	139.2	2.115
16,000.0	12,468.9	15,786.3	12,312.2	74.5	74.1	-52.76	3,668.6	-57.5	263.9	137.0	2.079
16,100.0	12,468.6	15,886.3	12,311.9	75.9	75.5	-52.76	3,768.6	-58.2	263.9	134.7	2.043
16,200.0	12,468.3	15,986.3	12,311.6	77.2	76.8	-52.76	3,868.6	-59.0	263.9	132.5	2.008
16,300.0	12,468.0	16,086.3	12,311.3	78.6	78.2	-52.76	3,968.6	-59.7	263.9	130.2	1.974
16,400.0	12,467.7	16,186.3	12,311.0	79.9	79.6	-52.76	4,068.6	-60.5	263.9	127.9	1.940
16,500.0	12,467.4	16,286.3	12,310.6	81.3	80.9	-52.75	4,168.6	-61.2	263.9	125.6	1.908
16,600.0	12,467.1	16,386.3	12,310.3	82.7	82.3	-52.75	4,268.6	-62.0	263.9	123.3	1.876
16,700.0	12,466.8	16,486.3	12,310.0	84.1	83.7	-52.75	4,368.6	-62.7	263.9	120.9	1.846
16,800.0	12,466.5	16,586.3	12,309.7	85.5	85.1	-52.75	4,468.6	-63.5	263.9	118.6	1.816
16,900.0	12,466.1	16,686.3	12,309.4	87.0	86.6	-52.75	4,568.6	-64.2	263.9	116.2	1.786
17,000.0	12,465.8	16,786.3	12,309.1	88.4	88.0	-52.75	4,668.6	-65.0	263.9	113.8	1.758
17,100.0	12,465.5	16,886.3	12,308.8	89.8	89.4	-52.75	4,768.6	-65.7	263.9	111.4	1.730
17,200.0	12,465.2	16,986.3	12,308.4	91.3	90.9	-52.75	4,868.6	-66.5	263.9	109.0	1.703
17,300.0	12,464.9	17,086.3	12,308.1	92.7	92.3	-52.75	4,968.6	-67.2	263.9	106.6	1.677
17,400.0	12,464.6	17,186.3	12,307.8	94.2	93.8	-52.75	5,068.6	-68.0	263.9	104.1	1.651
17,500.0	12,464.3	17,286.3	12,307.5	95.6	95.2	-52.75	5,168.6	-68.7	263.9	101.7	1.627
17,600.0	12,464.0	17,386.3	12,307.2	97.1	96.7	-52.74	5,268.6	-69.5	263.9	99.2	1.602
17,700.0	12,463.7	17,486.3	12,306.9	98.6	98.2	-52.74	5,368.6	-70.2	264.0	96.7	1.579
17,800.0	12,463.4	17,586.3	12,306.6	100.1	99.7	-52.74	5,468.6	-71.0	264.0	94.3	1.555
17,900.0	12,463.0	17,686.3	12,306.2	101.5	101.1	-52.74	5,568.6	-71.7	264.0	91.8	1.533
18,000.0	12,462.7	17,786.3	12,305.9	103.0	102.6	-52.74	5,668.6	-72.5	264.0	89.3	1.511
18,100.0	12,462.4	17,886.3	12,305.6	104.5	104.1	-52.74	5,768.6	-73.2	264.0	86.8	1.490 Level 3
18,200.0	12,462.1	17,986.3	12,305.3	106.0	105.6	-52.74	5,868.6	-73.9	264.0	84.2	1.469 Level 3
18,300.0	12,461.8	18,086.3	12,305.0	107.5	107.1	-52.74	5,968.6	-74.7	264.0	81.7	1.448 Level 3
18,400.0	12,461.5	18,186.3	12,304.7	109.0	108.6	-52.74	6,068.6	-75.4	264.0	79.2	1.428 Level 3
18,500.0	12,461.2	18,286.3	12,304.4	110.5	110.2	-52.74	6,168.6	-76.2	264.0	76.6	1.409 Level 3
18,600.0	12,460.9	18,386.3	12,304.0	112.1	111.7	-52.73	6,268.5	-76.9	264.0	74.1	1.390 Level 3
18,700.0	12,460.6	18,486.3	12,303.7	113.6	113.2	-52.73	6,368.5	-77.7	264.0	71.5	1.372 Level 3
18,800.0	12,460.3	18,586.3	12,303.4	115.1	114.7	-52.73	6,468.5	-78.4	264.0	69.0	1.354 Level 3
18,900.0	12,459.9	18,686.3	12,303.1	116.6	116.2	-52.73	6,568.5	-79.2	264.0	66.4	1.336 Level 3
19,000.0	12,459.6	18,786.3	12,302.8	118.2	117.8	-52.73	6,668.5	-79.9	264.0	63.8	1.319 Level 3
19,100.0	12,459.3	18,886.3	12,302.5	119.7	119.3	-52.73	6,768.5	-80.7	264.0	61.3	1.302 Level 3
19,200.0	12,459.0	18,986.3	12,302.2	121.2	120.8	-52.73	6,868.5	-81.4	264.0	58.7	1.286 Level 3
19,300.0	12,458.7	19,086.3	12,301.8	122.8	122.4	-52.73	6,968.5	-82.2	264.0	56.1	1.270 Level 3
19,400.0	12,458.4	19,186.3	12,301.5	124.3	123.9	-52.73	7,068.5	-82.9	264.0	53.5	1.254 Level 3
19,500.0	12,458.1	19,286.3	12,301.2	125.9	125.5	-52.73	7,168.5	-83.7	264.0	50.9	1.239 Level 2
19,600.0	12,457.8	19,386.3	12,300.9	127.4	127.0	-52.72	7,268.5	-84.4	264.0	48.3	1.224 Level 2
19,700.0	12,457.5	19,486.3	12,300.6	129.0	128.6	-52.72	7,368.5	-85.2	264.0	45.7	1.209 Level 2
19,800.0	12,457.2	19,586.3	12,300.3	130.5	130.1	-52.72	7,468.5	-85.9	264.0	43.1	1.195 Level 2
19,900.0	12,456.8	19,686.3	12,300.0	132.1	131.7	-52.72	7,568.5	-86.7	264.0	40.4	1.181 Level 2

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

Company:	COG Operating, LLC	Local Co-ordinate Reference:	Well Fez Federal Com #704H
Project:	Lea County, NM	TVD Reference:	well @ 3289.0usft (Noram #21)
Reference Site:	Sec 9, T25-S, R35-E	MD Reference:	well @ 3289.0usft (Noram #21)
Site Error:	0.0 usft	North Reference:	Grid
Reference Well:	Fez Federal Com #704H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.0 usft	Output errors are at	2.00 sigma
Reference Wellbore	Wellbore #1	Database:	EDM 5000.1 Single User Db
Reference Design:	Design #1	Offset TVD Reference:	Offset Datum

Offset Design Sec 9, T25-S, R35-E - Fez Federal Com #604H - Wellbore #1 - Design #1											Offset Site Error:	0.0 usft
Survey Program: 0-MVD											Offset Well Error:	0.0 usft
Reference Measured Depth (usft)	Vertical Depth (usft)	Offset Measured Depth (usft)	Vertical Depth (usft)	Semi Major Axis Reference (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	Offset Wellbore Centre +E/-W (usft)	Distance Between Centres (usft)	Distance Between Ellipses (usft)	Separation Factor	Warning
20,000.0	12,456.5	19,786.3	12,299.6	133.6	133.2	-52.72	7,668.5	-87.4	264.0	37.8	1.167	Level 2
20,100.0	12,456.2	19,886.3	12,299.3	135.2	134.8	-52.72	7,768.5	-88.2	264.0	35.2	1.154	Level 2
20,200.0	12,455.9	19,986.3	12,299.0	136.8	136.4	-52.72	7,868.5	-88.9	264.0	32.6	1.141	Level 2
20,300.0	12,455.6	20,086.3	12,298.7	138.3	137.9	-52.72	7,968.5	-89.7	264.0	29.9	1.128	Level 2
20,400.0	12,455.3	20,186.3	12,298.4	139.9	139.5	-52.72	8,068.5	-90.4	264.0	27.3	1.115	Level 2
20,500.0	12,455.0	20,286.3	12,298.1	141.5	141.1	-52.72	8,168.5	-91.2	264.0	24.7	1.103	Level 2
20,600.0	12,454.7	20,386.3	12,297.8	143.0	142.6	-52.71	8,268.5	-91.9	264.0	22.0	1.091	Level 2
20,700.0	12,454.4	20,486.3	12,297.4	144.6	144.2	-52.71	8,368.5	-92.7	264.0	19.4	1.079	Level 2
20,800.0	12,454.1	20,586.3	12,297.1	146.2	145.8	-52.71	8,468.5	-93.4	264.0	16.7	1.068	Level 2
20,900.0	12,453.8	20,686.3	12,296.8	147.7	147.4	-52.71	8,568.5	-94.2	264.0	14.1	1.056	Level 2
21,000.0	12,453.4	20,786.3	12,296.5	149.3	148.9	-52.71	8,668.5	-94.9	264.0	11.4	1.045	Level 2
21,100.0	12,453.1	20,886.3	12,296.2	150.9	150.5	-52.71	8,768.5	-95.6	264.0	8.7	1.034	Level 2
21,200.0	12,452.8	20,986.3	12,295.9	152.5	152.1	-52.71	8,868.5	-96.4	264.0	6.1	1.024	Level 2
21,300.0	12,452.5	21,086.3	12,295.6	154.1	153.7	-52.71	8,968.5	-97.1	264.0	3.4	1.013	Level 2
21,400.0	12,452.2	21,186.3	12,295.2	155.6	155.3	-52.71	9,068.5	-97.9	264.0	0.8	1.003	Level 2
21,500.0	12,451.9	21,286.3	12,294.9	157.2	156.8	-52.71	9,168.5	-98.6	264.0	-1.9	0.993	Level 1
21,600.0	12,451.6	21,386.3	12,294.6	158.8	158.4	-52.71	9,268.4	-99.4	264.0	-4.6	0.983	Level 1
21,700.0	12,451.3	21,486.3	12,294.3	160.4	160.0	-52.70	9,368.4	-100.1	264.0	-7.3	0.973	Level 1
21,800.0	12,451.0	21,586.3	12,294.0	162.0	161.6	-52.70	9,468.4	-100.9	264.0	-9.9	0.964	Level 1
21,900.0	12,450.7	21,686.3	12,293.7	163.6	163.2	-52.70	9,568.4	-101.6	264.0	-12.6	0.954	Level 1
22,000.0	12,450.3	21,786.3	12,293.4	165.2	164.8	-52.70	9,668.4	-102.4	264.0	-15.3	0.945	Level 1
22,100.0	12,450.0	21,886.3	12,293.0	166.8	166.4	-52.70	9,768.4	-103.1	264.0	-18.0	0.936	Level 1
22,200.0	12,449.7	21,986.3	12,292.7	168.4	168.0	-52.70	9,868.4	-103.9	264.0	-20.7	0.927	Level 1
22,300.0	12,449.4	22,086.3	12,292.4	170.0	169.6	-52.70	9,968.4	-104.6	264.0	-23.4	0.919	Level 1
22,400.0	12,449.1	22,186.3	12,292.1	171.6	171.2	-52.70	10,068.4	-105.4	264.0	-26.0	0.910	Level 1
22,434.0	12,449.0	22,220.4	12,292.0	172.1	171.7	-52.70	10,102.5	-105.6	264.0	-27.0	0.907	Level 1, ES, SF

Company:	COG Operating, LLC	Local Co-ordinate Reference:	Well Fez Federal Com #704H
Project:	Lea County, NM	TVD Reference:	well @ 3289.0usft (Noram #21)
Reference Site:	Sec 9, T25-S, R35-E	MD Reference:	well @ 3289.0usft (Noram #21)
Site Error:	0.0 usft	North Reference:	Grid
Reference Well:	Fez Federal Com #704H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.0 usft	Output errors are at	2.00 sigma
Reference Wellbore	Wellbore #1	Database:	EDM 5000.1 Single User Db
Reference Design:	Design #1	Offset TVD Reference:	Offset Datum

Offset Design Sec 9, T25-S, R35-E - Fez Federal Com #705H - Wellbore #1 - Design #1												Offset Site Error:	0.0 usft
Survey Program: 0-MWD												Offset Well Error:	0.0 usft
Reference Measured Depth (usft)	Vertical Depth (usft)	Offset Measured Depth (usft)	Vertical Depth (usft)	Semi Major Axis Reference (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	Distance Between Centres (usft)	Between Ellipses (usft)	Separation Factor	Warning		
0.0	0.0	2.0	2.0	0.0	0.0	-90.51	-0.5	-60.1	60.1				
100.0	100.0	102.0	102.0	0.1	0.1	-90.51	-0.5	-60.1	60.1	59.8	229.492		
200.0	200.0	202.0	202.0	0.5	0.5	-90.51	-0.5	-60.1	60.1	59.1	61.366		
300.0	300.0	302.0	302.0	0.8	0.9	-90.51	-0.5	-60.1	60.1	58.4	35.418		
400.0	400.0	402.0	402.0	1.2	1.2	-90.51	-0.5	-60.1	60.1	57.6	24.893		
500.0	500.0	502.0	502.0	1.6	1.6	-90.51	-0.5	-60.1	60.1	56.9	19.190		
600.0	600.0	602.0	602.0	1.9	1.9	-90.51	-0.5	-60.1	60.1	56.2	15.613		
700.0	700.0	702.0	702.0	2.3	2.3	-90.51	-0.5	-60.1	60.1	55.5	13.160		
800.0	800.0	802.0	802.0	2.6	2.6	-90.51	-0.5	-60.1	60.1	54.8	11.373		
900.0	900.0	902.0	902.0	3.0	3.0	-90.51	-0.5	-60.1	60.1	54.1	10.014		
916.0	916.0	918.0	918.0	3.1	3.1	-90.51	-0.5	-60.1	60.1	53.9	9.826 CC		
1,000.0	1,000.0	1,002.0	1,002.0	3.4	3.4	-90.51	-0.5	-60.1	60.1	53.3	8.945		
1,100.0	1,100.0	1,100.0	1,100.0	3.7	3.7	-90.63	-0.7	-61.8	61.8	54.4	8.342		
1,200.0	1,200.0	1,199.8	1,199.7	4.1	4.0	-90.87	-1.0	-65.3	65.3	57.2	8.052		
1,300.0	1,300.0	1,299.7	1,299.6	4.4	4.4	-91.08	-1.3	-68.7	68.8	60.0	7.805		
1,400.0	1,400.0	1,399.7	1,399.5	4.8	4.7	-91.27	-1.6	-72.2	72.3	62.8	7.593		
1,500.0	1,500.0	1,499.6	1,499.4	5.1	5.1	-91.44	-1.9	-75.7	75.8	65.5	7.409		
1,600.0	1,600.0	1,599.6	1,599.2	5.5	5.4	-91.59	-2.2	-79.2	79.2	68.3	7.248		
1,700.0	1,700.0	1,699.5	1,699.1	5.9	5.8	-91.74	-2.5	-82.6	82.7	71.1	7.106		
1,800.0	1,800.0	1,799.4	1,799.0	6.2	6.2	-91.87	-2.8	-86.1	86.2	73.9	6.979		
1,900.0	1,900.0	1,899.4	1,898.9	6.6	6.5	-91.99	-3.1	-89.6	89.7	76.6	6.866		
2,000.0	2,000.0	1,999.3	1,998.8	6.9	6.9	-92.10	-3.4	-93.1	93.2	79.4	6.765		
2,100.0	2,100.0	2,099.0	2,095.3	7.3	7.2	-92.25	-3.9	-98.0	98.3	83.8	6.799		
2,200.0	2,200.0	2,195.6	2,194.7	7.7	7.6	-92.43	-4.5	-104.9	105.3	90.1	6.940		
2,300.0	2,300.0	2,295.4	2,294.2	8.0	7.9	-92.59	-5.1	-111.9	112.2	96.4	7.067		
2,400.0	2,400.0	2,395.1	2,393.7	8.4	8.3	-92.73	-5.7	-118.8	119.2	102.6	7.184		
2,500.0	2,500.0	2,494.9	2,493.2	8.7	8.7	-92.86	-6.3	-125.7	126.2	108.9	7.290		
2,600.0	2,600.0	2,594.6	2,592.7	9.1	9.0	-92.97	-6.9	-132.6	133.1	115.1	7.388		
2,700.0	2,700.0	2,694.4	2,692.2	9.4	9.4	-93.07	-7.5	-139.6	140.1	121.4	7.479		
2,800.0	2,800.0	2,796.8	2,794.5	9.8	9.8	162.01	-8.1	-146.2	148.3	128.8	7.617		
2,900.0	2,899.8	2,902.1	2,899.6	10.1	10.2	162.54	-8.4	-149.6	156.5	136.3	7.752		
3,000.0	2,999.6	3,004.0	3,001.6	10.5	10.5	163.29	-8.4	-149.9	163.4	142.5	7.827		
3,100.0	3,099.4	3,103.8	3,101.4	10.8	10.9	163.96	-8.4	-149.9	170.1	148.5	7.888		
3,200.0	3,199.1	3,203.5	3,201.1	11.2	11.2	164.59	-8.4	-149.9	176.8	154.6	7.945		
3,300.0	3,298.9	3,303.3	3,300.9	11.5	11.6	165.16	-8.4	-149.9	183.6	160.6	7.999		
3,400.0	3,398.6	3,403.1	3,400.6	11.9	11.9	165.70	-8.4	-149.9	190.3	166.7	8.050		
3,503.8	3,502.0	3,506.4	3,504.0	12.2	12.3	167.04	-8.4	-149.9	199.2	174.8	8.176		
3,600.0	3,597.7	3,602.1	3,599.7	12.6	12.6	167.67	-8.4	-149.9	209.1	184.1	8.354		
3,700.0	3,697.1	3,701.5	3,699.1	12.9	12.9	168.26	-8.4	-149.9	219.5	193.7	8.531		
3,800.0	3,796.5	3,801.0	3,798.5	13.3	13.3	168.80	-8.4	-149.9	229.8	203.4	8.698		
3,900.0	3,896.0	3,900.4	3,898.0	13.7	13.6	169.29	-8.4	-149.9	240.2	213.1	8.857		
4,000.0	3,995.4	3,999.9	3,997.4	14.0	14.0	169.74	-8.4	-149.9	250.6	222.8	9.009		
4,100.0	4,094.9	4,099.3	4,096.9	14.4	14.3	170.15	-8.4	-149.9	261.0	232.5	9.153		
4,200.0	4,194.3	4,198.7	4,196.3	14.8	14.7	170.53	-8.4	-149.9	271.5	242.3	9.290		
4,300.0	4,293.7	4,298.2	4,295.7	15.1	15.0	170.89	-8.4	-149.9	281.9	252.0	9.421		
4,400.0	4,393.2	4,397.6	4,395.2	15.5	15.4	171.21	-8.4	-149.9	292.4	261.8	9.546		
4,500.0	4,492.6	4,497.1	4,494.6	15.9	15.7	171.52	-8.4	-149.9	302.8	271.5	9.665		
4,600.0	4,592.1	4,596.5	4,594.1	16.2	16.1	171.80	-8.4	-149.9	313.3	281.3	9.779		
4,631.5	4,623.4	4,627.8	4,625.4	16.4	16.2	171.89	-8.4	-149.9	316.6	284.4	9.814		
4,700.0	4,691.6	4,696.0	4,693.6	16.6	16.5	172.07	-8.4	-149.9	323.0	290.2	9.864		
4,800.0	4,791.4	4,795.8	4,793.4	17.0	16.8	172.24	-8.4	-149.9	329.4	295.9	9.847		
4,900.0	4,891.3	4,895.8	4,893.3	17.3	17.2	172.32	-8.4	-149.9	332.3	298.2	9.730		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

Company:	COG Operating, LLC	Local Co-ordinate Reference:	Well Fez Federal Com #704H
Project:	Lea County, NM	TVD Reference:	well @ 3289.0usft (Noram #21)
Reference Site:	Sec 9, T25-S, R35-E	MD Reference:	well @ 3289.0usft (Noram #21)
Site Error:	0.0 usft	North Reference:	Grid
Reference Well:	Fez Federal Com #704H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.0 usft	Output errors are at	2.00 sigma
Reference Wellbore:	Wellbore #1	Database:	EDM 5000.1 Single User Db
Reference Design:	Design #1	Offset TVD Reference:	Offset Datum

Offset Design: Sec 9, T25-S, R35-E - Fez Federal Com #705H - Wellbore #1 - Design #1											Offset Site Error:	0.0 usft
Survey Program: 0-MWD											Offset Well Error:	0.0 usft
Reference Measured Depth (usft)	Vertical Depth (usft)	Offset Measured Depth (usft)	Vertical Depth (usft)	Semi Major Axis Reference (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	+E/-W (usft)	Distance Between Centres (usft)	Between Ellipses (usft)	Separation Factor	Warning
4,935.2	4,926.5	4,930.9	4,928.5	17.5	17.3	-83.43	-8.4	-149.9	332.5	298.1	9.666	
5,000.0	4,991.3	4,995.7	4,993.3	17.7	17.5	-83.43	-8.4	-149.9	332.5	297.7	9.539	
5,100.0	5,091.3	5,095.7	5,093.3	18.0	17.9	-83.43	-8.4	-149.9	332.5	297.0	9.349	
5,200.0	5,191.3	5,195.7	5,193.3	18.4	18.2	-83.43	-8.4	-149.9	332.5	296.3	9.166	
5,300.0	5,291.3	5,295.7	5,293.3	18.7	18.6	-83.43	-8.4	-149.9	332.5	295.6	8.991	
5,400.0	5,391.3	5,395.7	5,393.3	19.1	18.9	-83.43	-8.4	-149.9	332.5	294.8	8.822	
5,500.0	5,491.3	5,495.7	5,493.3	19.4	19.3	-83.43	-8.4	-149.9	332.5	294.1	8.659	
5,600.0	5,591.3	5,595.7	5,593.3	19.8	19.6	-83.43	-8.4	-149.9	332.5	293.4	8.502	
5,700.0	5,691.3	5,695.7	5,693.3	20.1	20.0	-83.43	-8.4	-149.9	332.5	292.7	8.350	
5,800.0	5,791.3	5,795.7	5,793.3	20.5	20.4	-83.43	-8.4	-149.9	332.5	292.0	8.204	
5,900.0	5,891.3	5,895.7	5,893.3	20.8	20.7	-83.43	-8.4	-149.9	332.5	291.3	8.063	
6,000.0	5,991.3	5,995.7	5,993.3	21.2	21.1	-83.43	-8.4	-149.9	332.5	290.6	7.926	
6,100.0	6,091.3	6,095.7	6,093.3	21.5	21.4	-83.43	-8.4	-149.9	332.5	289.9	7.794	
6,200.0	6,191.3	6,195.7	6,193.3	21.9	21.8	-83.43	-8.4	-149.9	332.5	289.2	7.666	
6,300.0	6,291.3	6,295.7	6,293.3	22.2	22.1	-83.43	-8.4	-149.9	332.5	288.5	7.543	
6,400.0	6,391.3	6,395.7	6,393.3	22.6	22.5	-83.43	-8.4	-149.9	332.5	287.7	7.423	
6,500.0	6,491.3	6,495.7	6,493.3	22.9	22.8	-83.43	-8.4	-149.9	332.5	287.0	7.307	
6,600.0	6,591.3	6,595.7	6,593.3	23.3	23.2	-83.43	-8.4	-149.9	332.5	286.3	7.194	
6,700.0	6,691.3	6,695.7	6,693.3	23.7	23.6	-83.43	-8.4	-149.9	332.5	285.6	7.085	
6,800.0	6,791.3	6,795.7	6,793.3	24.0	23.9	-83.43	-8.4	-149.9	332.5	284.9	6.979	
6,900.0	6,891.3	6,895.7	6,893.3	24.4	24.3	-83.43	-8.4	-149.9	332.5	284.2	6.877	
7,000.0	6,991.3	6,995.7	6,993.3	24.7	24.6	-83.43	-8.4	-149.9	332.5	283.5	6.777	
7,100.0	7,091.3	7,095.7	7,093.3	25.1	25.0	-83.43	-8.4	-149.9	332.5	282.8	6.680	
7,200.0	7,191.3	7,195.7	7,193.3	25.4	25.3	-83.43	-8.4	-149.9	332.5	282.0	6.586	
7,300.0	7,291.3	7,295.7	7,293.3	25.8	25.7	-83.43	-8.4	-149.9	332.5	281.3	6.494	
7,400.0	7,391.3	7,395.7	7,393.3	26.1	26.1	-83.43	-8.4	-149.9	332.5	280.6	6.405	
7,500.0	7,491.3	7,495.7	7,493.3	26.5	26.4	-83.43	-8.4	-149.9	332.5	279.9	6.318	
7,600.0	7,591.3	7,595.7	7,593.3	26.8	26.8	-83.43	-8.4	-149.9	332.5	279.2	6.234	
7,700.0	7,691.3	7,695.7	7,693.3	27.2	27.1	-83.43	-8.4	-149.9	332.5	278.5	6.151	
7,800.0	7,791.3	7,795.7	7,793.3	27.5	27.5	-83.43	-8.4	-149.9	332.5	277.8	6.071	
7,900.0	7,891.3	7,895.7	7,893.3	27.9	27.8	-83.43	-8.4	-149.9	332.5	277.1	5.993	
8,000.0	7,991.3	7,995.7	7,993.3	28.3	28.2	-83.43	-8.4	-149.9	332.5	276.3	5.917	
8,100.0	8,091.3	8,095.7	8,093.3	28.6	28.6	-83.43	-8.4	-149.9	332.5	275.6	5.843	
8,200.0	8,191.3	8,195.7	8,193.3	29.0	28.9	-83.43	-8.4	-149.9	332.5	274.9	5.771	
8,300.0	8,291.3	8,295.7	8,293.3	29.3	29.3	-83.43	-8.4	-149.9	332.5	274.2	5.700	
8,400.0	8,391.3	8,395.7	8,393.3	29.7	29.6	-83.43	-8.4	-149.9	332.5	273.5	5.631	
8,500.0	8,491.3	8,495.7	8,493.3	30.0	30.0	-83.43	-8.4	-149.9	332.5	272.8	5.564	
8,600.0	8,591.3	8,595.7	8,593.3	30.4	30.3	-83.43	-8.4	-149.9	332.5	272.1	5.498	
8,700.0	8,691.3	8,695.7	8,693.3	30.7	30.7	-83.43	-8.4	-149.9	332.5	271.3	5.434	
8,800.0	8,791.3	8,795.7	8,793.3	31.1	31.1	-83.43	-8.4	-149.9	332.5	270.6	5.372	
8,900.0	8,891.3	8,895.7	8,893.3	31.5	31.4	-83.43	-8.4	-149.9	332.5	269.9	5.310	
9,000.0	8,991.3	8,995.7	8,993.3	31.8	31.8	-83.43	-8.4	-149.9	332.5	269.2	5.250	
9,100.0	9,091.3	9,095.7	9,093.3	32.2	32.1	-83.43	-8.4	-149.9	332.5	268.5	5.192	
9,200.0	9,191.3	9,195.7	9,193.3	32.5	32.5	-83.43	-8.4	-149.9	332.5	267.8	5.135	
9,300.0	9,291.3	9,295.7	9,293.3	32.9	32.8	-83.43	-8.4	-149.9	332.5	267.1	5.079	
9,400.0	9,391.3	9,395.7	9,393.3	33.2	33.2	-83.43	-8.4	-149.9	332.5	266.4	5.024	
9,500.0	9,491.3	9,495.7	9,493.3	33.6	33.6	-83.43	-8.4	-149.9	332.5	265.6	4.970	
9,600.0	9,591.3	9,595.7	9,593.3	33.9	33.9	-83.43	-8.4	-149.9	332.5	264.9	4.918	
9,700.0	9,691.3	9,695.7	9,693.3	34.3	34.3	-83.43	-8.4	-149.9	332.5	264.2	4.866	
9,800.0	9,791.3	9,795.7	9,793.3	34.7	34.6	-83.43	-8.4	-149.9	332.5	263.5	4.816	
9,900.0	9,891.3	9,895.7	9,893.3	35.0	35.0	-83.43	-8.4	-149.9	332.5	262.8	4.767	
10,000.0	9,991.3	9,995.7	9,993.3	35.4	35.3	-83.43	-8.4	-149.9	332.5	262.1	4.718	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

Company:	COG Operating, LLC	Local Co-ordinate Reference:	Well Fez Federal Com #704H
Project:	Lea County, NM	TVD Reference:	well @ 3289.0usft (Noram #21)
Reference Site:	Sec 9, T25-S, R35-E	MD Reference:	well @ 3289.0usft (Noram #21)
Site Error:	0.0 usft	North Reference:	Grid
Reference Well:	Fez Federal Com #704H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.0 usft	Output errors are at	2.00 sigma
Reference Wellbore	Wellbore #1	Database:	EDM 5000.1 Single User Db
Reference Design:	Design #1	Offset TVD Reference:	Offset Datum

Offset Design Sec 9, T25-S, R35-E - Fez Federal Com #705H - Wellbore #1 - Design #1												Offset Site Error:	0.0 usft
Survey Program: Q-MWD												Offset Well Error:	0.0 usft
Reference Measured Depth (usft)	Vertical Depth (usft)	Reference Measured Depth (usft)	Vertical Depth (usft)	Semi Major Axis Reference (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre N-S (usft)	Offset Wellbore Centre E-W (usft)	Distance Between Centres (usft)	Distance Between Ellipses (usft)	Separation Factor	Warning	
10,100.0	10,091.3	10,095.7	10,093.3	35.7	35.7	-83.43	-8.4	-149.9	332.5	261.3	4.671		
10,200.0	10,191.3	10,195.7	10,193.3	36.1	36.1	-83.43	-8.4	-149.9	332.5	260.6	4.624		
10,300.0	10,291.3	10,295.7	10,293.3	36.4	36.4	-83.43	-8.4	-149.9	332.5	259.9	4.579		
10,400.0	10,391.3	10,395.7	10,393.3	36.8	36.8	-83.43	-8.4	-149.9	332.5	259.2	4.534		
10,500.0	10,491.3	10,495.7	10,493.3	37.1	37.1	-83.43	-8.4	-149.9	332.5	258.5	4.491		
10,600.0	10,591.3	10,595.7	10,593.3	37.5	37.5	-83.43	-8.4	-149.9	332.5	257.8	4.448		
10,700.0	10,691.3	10,695.7	10,693.3	37.9	37.8	-83.43	-8.4	-149.9	332.5	257.1	4.405		
10,800.0	10,791.3	10,795.7	10,793.3	38.2	38.2	-83.43	-8.4	-149.9	332.5	256.3	4.364		
10,900.0	10,891.3	10,895.7	10,893.3	38.6	38.6	-83.43	-8.4	-149.9	332.5	255.6	4.324		
11,000.0	10,991.3	10,995.7	10,993.3	38.9	38.9	-83.43	-8.4	-149.9	332.5	254.9	4.284		
11,100.0	11,091.3	11,095.7	11,093.3	39.3	39.3	-83.43	-8.4	-149.9	332.5	254.2	4.245		
11,200.0	11,191.3	11,195.7	11,193.3	39.6	39.6	-83.43	-8.4	-149.9	332.5	253.5	4.206		
11,300.0	11,291.3	11,295.7	11,293.3	40.0	40.0	-83.43	-8.4	-149.9	332.5	252.8	4.169		
11,400.0	11,391.3	11,395.7	11,393.3	40.4	40.3	-83.43	-8.4	-149.9	332.5	252.1	4.131		
11,500.0	11,491.3	11,495.7	11,493.3	40.7	40.7	-83.43	-8.4	-149.9	332.5	251.3	4.095		
11,600.0	11,591.3	11,595.7	11,593.3	41.1	41.1	-83.43	-8.4	-149.9	332.5	250.6	4.059		
11,700.0	11,691.3	11,695.7	11,693.3	41.4	41.4	-83.43	-8.4	-149.9	332.5	249.9	4.024		
11,800.0	11,791.3	11,795.7	11,793.3	41.8	41.8	-83.43	-8.4	-149.9	332.5	249.2	3.990		
11,900.0	11,891.3	11,895.7	11,893.3	42.1	42.1	-83.43	-8.4	-149.9	332.5	248.5	3.956		
12,000.0	11,991.3	11,995.7	11,993.3	42.5	42.5	-83.43	-8.4	-149.9	332.5	247.8	3.922		
12,010.2	12,001.5	12,005.9	12,003.5	42.5	42.5	-83.43	-8.4	-149.9	332.5	247.7	3.919		
12,025.0	12,016.3	12,020.7	12,018.3	42.6	42.6	-83.04	-8.4	-149.9	332.5	247.6	3.914		
12,050.0	12,041.3	12,045.7	12,043.3	42.7	42.7	-83.31	-8.4	-149.9	332.3	247.2	3.904		
12,075.0	12,066.1	12,070.6	12,068.1	42.8	42.8	-83.81	-8.4	-149.9	332.0	246.7	3.892		
12,100.0	12,090.8	12,095.2	12,092.8	42.9	42.8	-84.54	-8.4	-149.9	331.6	246.1	3.879		
12,125.0	12,115.2	12,118.6	12,116.2	42.9	42.9	-85.39	-8.1	-149.9	331.2	245.5	3.866		
12,150.0	12,139.3	12,141.9	12,139.4	43.0	43.0	-86.26	-6.6	-149.9	330.8	245.0	3.854		
12,175.0	12,163.1	12,165.4	12,162.8	43.1	43.1	-87.14	-4.0	-149.9	330.5	244.5	3.843		
12,200.0	12,186.4	12,189.2	12,186.2	43.2	43.2	-88.03	-0.3	-149.9	330.3	244.1	3.833		
12,225.0	12,209.1	12,213.1	12,209.7	43.3	43.3	-88.93	4.7	-150.0	330.1	243.8	3.825		
12,250.0	12,231.4	12,237.4	12,233.1	43.3	43.3	-89.84	11.0	-150.0	330.1	243.6	3.817		
12,254.5	12,235.3	12,241.8	12,237.3	43.3	43.4	-90.00	12.2	-150.0	330.1	243.6	3.815		
12,275.0	12,252.9	12,261.9	12,256.4	43.4	43.4	-90.75	18.5	-150.1	330.1	243.5	3.810		
12,300.0	12,273.8	12,286.7	12,279.6	43.5	43.5	-91.66	27.3	-150.1	330.2	243.4	3.804		
12,325.0	12,294.0	12,311.7	12,302.5	43.5	43.6	-92.58	37.4	-150.2	330.4	243.5	3.800		
12,350.0	12,313.3	12,337.1	12,325.1	43.6	43.7	-93.49	48.8	-150.3	330.7	243.6	3.797		
12,375.0	12,331.8	12,362.8	12,347.4	43.6	43.7	-94.40	61.6	-150.4	331.1	243.9	3.796		
12,400.0	12,349.4	12,388.7	12,369.2	43.7	43.8	-95.30	75.8	-150.5	331.5	244.2	3.796		
12,425.0	12,366.1	12,415.0	12,390.4	43.7	43.9	-96.19	91.3	-150.6	332.1	244.6	3.798		
12,450.0	12,381.7	12,441.7	12,411.1	43.8	44.0	-97.06	108.1	-150.7	332.7	245.2	3.801		
12,475.0	12,396.3	12,468.7	12,430.9	43.8	44.0	-97.92	126.4	-150.9	333.4	245.8	3.805		
12,500.0	12,409.8	12,496.0	12,450.0	43.9	44.1	-98.76	145.9	-151.0	334.1	246.5	3.811		
12,525.0	12,422.2	12,523.7	12,468.1	44.0	44.2	-99.58	166.8	-151.2	334.9	247.2	3.819		
12,550.0	12,433.4	12,551.7	12,485.2	44.0	44.3	-100.37	189.0	-151.3	335.7	248.0	3.828		
12,575.0	12,443.5	12,580.1	12,501.2	44.1	44.3	-101.13	212.5	-151.5	336.6	248.9	3.838		
12,600.0	12,452.3	12,608.8	12,515.9	44.2	44.4	-101.86	237.2	-151.7	337.5	249.8	3.848		
12,625.0	12,460.0	12,637.8	12,529.2	44.2	44.5	-102.56	263.0	-151.9	338.4	250.7	3.860		
12,650.0	12,466.3	12,667.2	12,541.1	44.3	44.6	-103.22	289.9	-152.1	339.3	251.6	3.872		
12,675.0	12,471.4	12,697.0	12,551.4	44.4	44.7	-103.85	317.7	-152.3	340.1	252.6	3.883		
12,700.0	12,475.2	12,727.0	12,560.0	44.4	44.7	-104.43	346.5	-152.5	341.0	253.4	3.895		
12,725.0	12,477.7	12,757.3	12,566.8	44.5	44.8	-104.96	376.1	-152.7	341.8	254.3	3.905		
12,750.0	12,478.9	12,788.0	12,571.8	44.5	44.9	-105.45	406.3	-153.0	342.6	255.1	3.914		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

Company:	COG Operating, LLC	Local Co-ordinate Reference:	Well Fez Federal Com #704H
Project:	Lea County, NM	TVD Reference:	well @ 3289.0usft (Noram #21)
Reference Site:	Sec 9, T25-S, R35-E	MD Reference:	well @ 3289.0usft (Noram #21)
Site Error:	0.0 usft	North Reference:	Grid
Reference Well:	Fez Federal Com #704H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.0 usft	Output errors are at	2.00 sigma
Reference Wellbore:	Wellbore #1	Database:	EDM 5000.1 Single User Db
Reference Design:	Design #1	Offset TVD Reference:	Offset Datum

Offset Design Sec 9, T25-S, R35-E - Fez Federal Com #705H - Wellbore #1 - Design #1												Offset Site Error:	0.0 usft
Survey Program: 0-MWVD												Offset Well Error:	0.0 usft
Measured Depth (usft)	Vertical Depth (usft)	Reference Depth (usft)	Offset Depth (usft)	Semi-Major Axis Reference (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Separation Factor	Warning	
12,761.7	12,479.0	12,802.3	12,573.5	44.6	44.9	-105.66	420.6	-153.1	342.9	255.4	3.918		
12,800.0	12,478.8	12,850.0	12,576.0	44.7	45.1	-106.08	468.2	-153.4	343.5	255.9	3.920		
12,900.0	12,478.5	12,950.5	12,575.7	45.0	45.4	-106.08	568.6	-154.2	343.5	255.3	3.895		
13,000.0	12,478.2	13,050.5	12,575.3	45.3	45.7	-106.08	668.6	-154.9	343.5	254.6	3.865		
13,100.0	12,477.9	13,150.5	12,575.0	45.7	46.1	-106.08	768.6	-155.7	343.5	253.8	3.831		
13,200.0	12,477.6	13,250.5	12,574.7	46.2	46.6	-106.08	868.6	-156.4	343.5	252.9	3.793		
13,300.0	12,477.3	13,350.5	12,574.4	46.7	47.1	-106.08	968.6	-157.2	343.5	251.9	3.752		
13,400.0	12,477.0	13,450.5	12,574.1	47.3	47.6	-106.08	1,068.6	-157.9	343.5	250.8	3.708		
13,500.0	12,476.7	13,550.5	12,573.8	47.9	48.2	-106.08	1,168.6	-158.7	343.5	249.7	3.660		
13,600.0	12,476.4	13,650.5	12,573.5	48.6	48.9	-106.08	1,268.6	-159.4	343.5	248.4	3.611		
13,700.0	12,476.1	13,750.5	12,573.2	49.3	49.6	-106.08	1,368.6	-160.2	343.5	247.0	3.560		
13,800.0	12,475.7	13,850.5	12,572.9	50.1	50.4	-106.08	1,468.6	-160.9	343.5	245.5	3.506		
13,900.0	12,475.4	13,950.5	12,572.5	50.9	51.2	-106.08	1,568.6	-161.7	343.5	244.0	3.452		
14,000.0	12,475.1	14,050.5	12,572.2	51.7	52.0	-106.07	1,668.6	-162.4	343.5	242.4	3.397		
14,100.0	12,474.8	14,150.5	12,571.9	52.6	52.9	-106.07	1,768.6	-163.2	343.5	240.7	3.341		
14,200.0	12,474.5	14,250.5	12,571.6	53.5	53.8	-106.07	1,868.6	-163.9	343.5	238.9	3.284		
14,300.0	12,474.2	14,350.5	12,571.3	54.5	54.7	-106.07	1,968.6	-164.7	343.5	237.1	3.228		
14,400.0	12,473.9	14,450.5	12,571.0	55.5	55.7	-106.07	2,068.6	-165.4	343.5	235.2	3.171		
14,500.0	12,473.6	14,550.5	12,570.7	56.5	56.7	-106.07	2,168.6	-166.2	343.5	233.2	3.115		
14,600.0	12,473.3	14,650.5	12,570.4	57.5	57.7	-106.07	2,268.6	-166.9	343.5	231.2	3.059		
14,700.0	12,473.0	14,750.5	12,570.1	58.6	58.8	-106.07	2,368.6	-167.7	343.5	229.1	3.004		
14,800.0	12,472.6	14,850.5	12,569.7	59.7	59.9	-106.07	2,468.6	-168.4	343.5	227.0	2.949		
14,900.0	12,472.3	14,950.5	12,569.4	60.8	61.0	-106.07	2,568.6	-169.2	343.5	224.8	2.895		
15,000.0	12,472.0	15,050.5	12,569.1	62.0	62.1	-106.07	2,668.6	-169.9	343.5	222.6	2.842		
15,100.0	12,471.7	15,150.5	12,568.8	63.2	63.3	-106.07	2,768.6	-170.7	343.5	220.4	2.790		
15,200.0	12,471.4	15,250.5	12,568.5	64.4	64.5	-106.07	2,868.6	-171.4	343.5	218.1	2.739		
15,300.0	12,471.1	15,350.5	12,568.2	65.6	65.7	-106.07	2,968.6	-172.2	343.5	215.7	2.689		
15,400.0	12,470.8	15,450.5	12,567.9	66.8	66.9	-106.07	3,068.6	-172.9	343.5	213.3	2.639		
15,500.0	12,470.5	15,550.5	12,567.6	68.0	68.2	-106.07	3,168.5	-173.7	343.5	210.9	2.591		
15,600.0	12,470.2	15,650.5	12,567.3	69.3	69.4	-106.07	3,268.5	-174.4	343.5	208.5	2.544		
15,700.0	12,469.9	15,750.5	12,566.9	70.6	70.7	-106.07	3,368.5	-175.2	343.5	206.0	2.499		
15,800.0	12,469.6	15,850.5	12,566.6	71.9	72.0	-106.07	3,468.5	-175.9	343.5	203.5	2.454		
15,900.0	12,469.2	15,950.5	12,566.3	73.2	73.3	-106.07	3,568.5	-176.7	343.5	201.0	2.410		
16,000.0	12,468.9	16,050.5	12,566.0	74.5	74.6	-106.07	3,668.5	-177.4	343.5	198.4	2.368		
16,100.0	12,468.6	16,150.5	12,565.7	75.9	75.9	-106.07	3,768.5	-178.2	343.5	195.8	2.326		
16,200.0	12,468.3	16,250.5	12,565.4	77.2	77.3	-106.07	3,868.5	-178.9	343.5	193.2	2.286		
16,300.0	12,468.0	16,350.5	12,565.1	78.6	78.6	-106.07	3,968.5	-179.7	343.5	190.6	2.247		
16,400.0	12,467.7	16,450.5	12,564.8	79.9	80.0	-106.07	4,068.5	-180.4	343.5	187.9	2.208		
16,500.0	12,467.4	16,550.5	12,564.5	81.3	81.4	-106.07	4,168.5	-181.2	343.5	185.3	2.171		
16,600.0	12,467.1	16,650.5	12,564.1	82.7	82.8	-106.07	4,268.5	-181.9	343.5	182.6	2.135		
16,700.0	12,466.8	16,750.5	12,563.8	84.1	84.2	-106.07	4,368.5	-182.7	343.5	179.9	2.099		
16,800.0	12,466.5	16,850.5	12,563.5	85.5	85.6	-106.07	4,468.5	-183.4	343.5	177.1	2.065		
16,900.0	12,466.1	16,950.5	12,563.2	87.0	87.0	-106.07	4,568.5	-184.2	343.5	174.4	2.031		
17,000.0	12,465.8	17,050.5	12,562.9	88.4	88.4	-106.07	4,668.5	-184.9	343.5	171.6	1.999		
17,100.0	12,465.5	17,150.5	12,562.6	89.8	89.9	-106.07	4,768.5	-185.7	343.5	168.8	1.967		
17,200.0	12,465.2	17,250.5	12,562.3	91.3	91.3	-106.07	4,868.5	-186.4	343.5	166.0	1.936		
17,300.0	12,464.9	17,350.5	12,562.0	92.7	92.7	-106.07	4,968.5	-187.2	343.5	163.2	1.906		
17,400.0	12,464.6	17,450.5	12,561.7	94.2	94.2	-106.07	5,068.5	-187.9	343.5	160.4	1.876		
17,500.0	12,464.3	17,550.5	12,561.3	95.6	95.6	-106.07	5,168.5	-188.7	343.5	157.6	1.848		
17,600.0	12,464.0	17,650.5	12,561.0	97.1	97.1	-106.07	5,268.5	-189.4	343.5	154.7	1.820		
17,700.0	12,463.7	17,750.5	12,560.7	98.6	98.6	-106.07	5,368.5	-190.2	343.5	151.9	1.793		
17,800.0	12,463.4	17,850.5	12,560.4	100.1	100.1	-106.07	5,468.5	-190.9	343.5	149.0	1.767		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

Company:	COG Operating, LLC	Local Co-ordinate Reference:	Well Fez Federal Com #704H
Project:	Lea County, NM	TVD Reference:	well @ 3289.0usft (Noram #21)
Reference Site:	Sec 9, T25-S, R35-E	MD Reference:	well @ 3289.0usft (Noram #21)
Site Error:	0.0 usft	North Reference:	Grid
Reference Well:	Fez Federal Com #704H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.0 usft	Output errors are at	2.00 sigma
Reference Wellbore	Wellbore #1	Database:	EDM 5000.1 Single User Db
Reference Design:	Design #1	Offset TVD Reference:	Offset Datum

Offset Design Sec 9, T25-S, R35-E - Fez Federal Com #705H - Wellbore #1 - Design #1												Offset Site Error:	0.0 usft
Survey Program: 0-MWD												Offset Well Error:	0.0 usft
Reference Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Offset Vertical Depth (usft)	Semi Major Axis Reference (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	Distance Between Centres (usft)	Between Ellipses (usft)	Separation Factor	Warning		
17,900.0	12,463.0	17,950.5	12,560.1	101.5	101.5	-106.07	5,568.5	-191.7	343.5	146.2	1.741		
18,000.0	12,462.7	18,050.5	12,559.8	103.0	103.0	-106.07	5,668.5	-192.4	343.5	143.3	1.716		
18,100.0	12,462.4	18,150.5	12,559.5	104.5	104.5	-106.07	5,768.5	-193.2	343.5	140.4	1.691		
18,200.0	12,462.1	18,250.5	12,559.2	106.0	106.0	-106.07	5,868.5	-193.9	343.5	137.5	1.667		
18,300.0	12,461.8	18,350.5	12,558.9	107.5	107.5	-106.07	5,968.5	-194.7	343.4	134.6	1.644		
18,400.0	12,461.5	18,450.5	12,558.5	109.0	109.0	-106.07	6,068.5	-195.4	343.4	131.6	1.621		
18,500.0	12,461.2	18,550.5	12,558.2	110.5	110.5	-106.07	6,168.4	-196.2	343.4	128.7	1.599		
18,600.0	12,460.9	18,650.5	12,557.9	112.1	112.0	-106.07	6,268.4	-196.9	343.4	125.8	1.578		
18,700.0	12,460.6	18,750.5	12,557.6	113.6	113.6	-106.07	6,368.4	-197.7	343.4	122.8	1.557		
18,800.0	12,460.3	18,850.5	12,557.3	115.1	115.1	-106.07	6,468.4	-198.4	343.4	119.9	1.536		
18,900.0	12,459.9	18,950.5	12,557.0	116.6	116.6	-106.07	6,568.4	-199.2	343.4	116.9	1.516		
19,000.0	12,459.6	19,050.5	12,556.7	118.2	118.1	-106.07	6,668.4	-199.9	343.4	113.9	1.496 Level 3		
19,100.0	12,459.3	19,150.5	12,556.4	119.7	119.7	-106.07	6,768.4	-200.7	343.4	111.0	1.477 Level 3		
19,200.0	12,459.0	19,250.5	12,556.1	121.2	121.2	-106.07	6,868.4	-201.4	343.4	108.0	1.459 Level 3		
19,300.0	12,458.7	19,350.5	12,555.7	122.8	122.7	-106.06	6,968.4	-202.2	343.4	105.0	1.440 Level 3		
19,400.0	12,458.4	19,450.5	12,555.4	124.3	124.3	-106.06	7,068.4	-202.9	343.4	102.0	1.423 Level 3		
19,500.0	12,458.1	19,550.5	12,555.1	125.9	125.8	-106.06	7,168.4	-203.7	343.4	99.0	1.405 Level 3		
19,600.0	12,457.8	19,650.5	12,554.8	127.4	127.4	-106.06	7,268.4	-204.4	343.4	96.0	1.388 Level 3		
19,700.0	12,457.5	19,750.5	12,554.5	129.0	128.9	-106.06	7,368.4	-205.1	343.4	93.0	1.371 Level 3		
19,800.0	12,457.2	19,850.5	12,554.2	130.5	130.5	-106.06	7,468.4	-205.9	343.4	90.0	1.355 Level 3		
19,900.0	12,456.8	19,950.5	12,553.9	132.1	132.0	-106.06	7,568.4	-206.6	343.4	87.0	1.339 Level 3		
20,000.0	12,456.5	20,050.5	12,553.6	133.6	133.6	-106.06	7,668.4	-207.4	343.4	84.0	1.324 Level 3		
20,100.0	12,456.2	20,150.5	12,553.3	135.2	135.1	-106.06	7,768.4	-208.1	343.4	80.9	1.308 Level 3		
20,200.0	12,455.9	20,250.5	12,552.9	136.8	136.7	-106.06	7,868.4	-208.9	343.4	77.9	1.293 Level 3		
20,300.0	12,455.6	20,350.5	12,552.6	138.3	138.3	-106.06	7,968.4	-209.6	343.4	74.9	1.279 Level 3		
20,400.0	12,455.3	20,450.5	12,552.3	139.9	139.8	-106.06	8,068.4	-210.4	343.4	71.8	1.265 Level 3		
20,500.0	12,455.0	20,550.5	12,552.0	141.5	141.4	-106.06	8,168.4	-211.1	343.4	68.8	1.251 Level 3		
20,600.0	12,454.7	20,650.5	12,551.7	143.0	143.0	-106.06	8,268.4	-211.9	343.4	65.8	1.237 Level 2		
20,700.0	12,454.4	20,750.5	12,551.4	144.6	144.5	-106.06	8,368.4	-212.6	343.4	62.7	1.223 Level 2		
20,800.0	12,454.1	20,850.5	12,551.1	146.2	146.1	-106.06	8,468.4	-213.4	343.4	59.7	1.210 Level 2		
20,900.0	12,453.8	20,950.5	12,550.8	147.7	147.7	-106.06	8,568.4	-214.1	343.4	56.6	1.197 Level 2		
21,000.0	12,453.4	21,050.5	12,550.5	149.3	149.3	-106.06	8,668.4	-214.9	343.4	53.5	1.185 Level 2		
21,100.0	12,453.1	21,150.5	12,550.1	150.9	150.8	-106.06	8,768.4	-215.6	343.4	50.5	1.172 Level 2		
21,200.0	12,452.8	21,250.5	12,549.8	152.5	152.4	-106.06	8,868.4	-216.4	343.4	47.4	1.160 Level 2		
21,300.0	12,452.5	21,350.5	12,549.5	154.1	154.0	-106.06	8,968.4	-217.1	343.4	44.4	1.148 Level 2		
21,400.0	12,452.2	21,450.5	12,549.2	155.6	155.6	-106.06	9,068.4	-217.9	343.4	41.3	1.137 Level 2		
21,500.0	12,451.9	21,550.5	12,548.9	157.2	157.2	-106.06	9,168.3	-218.6	343.4	38.2	1.125 Level 2		
21,600.0	12,451.6	21,650.5	12,548.6	158.8	158.7	-106.06	9,268.3	-219.4	343.4	35.1	1.114 Level 2		
21,700.0	12,451.3	21,750.5	12,548.3	160.4	160.3	-106.06	9,368.3	-220.1	343.4	32.1	1.103 Level 2		
21,800.0	12,451.0	21,850.5	12,548.0	162.0	161.9	-106.06	9,468.3	-220.9	343.4	29.0	1.092 Level 2		
21,900.0	12,450.7	21,950.5	12,547.7	163.6	163.5	-106.06	9,568.3	-221.6	343.4	25.9	1.082 Level 2		
22,000.0	12,450.3	22,050.5	12,547.3	165.2	165.1	-106.06	9,668.3	-222.4	343.4	22.8	1.071 Level 2		
22,100.0	12,450.0	22,150.5	12,547.0	166.8	166.7	-106.06	9,768.3	-223.1	343.4	19.7	1.061 Level 2		
22,200.0	12,449.7	22,250.5	12,546.7	168.4	168.3	-106.06	9,868.3	-223.9	343.4	16.6	1.051 Level 2		
22,300.0	12,449.4	22,350.5	12,546.4	170.0	169.9	-106.06	9,968.3	-224.6	343.4	13.5	1.041 Level 2		
22,400.0	12,449.1	22,450.5	12,546.1	171.6	171.5	-106.06	10,068.3	-225.4	343.4	10.4	1.031 Level 2		
22,432.8	12,449.0	22,483.3	12,546.0	172.1	172.0	-106.06	10,101.1	-225.6	343.4	9.4	1.028 Level 2		
22,434.0	12,449.0	22,483.7	12,546.0	172.1	172.0	-106.06	10,101.5	-225.6	343.4	9.4	1.028 Level 2, ES, SF		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

Company:	COG Operating, LLC	Local Co-ordinate Reference:	Well Fez Federal Com #704H
Project:	Lea County, NM	TVD Reference:	well @ 3289.0usft (Noram #21)
Reference Site:	Sec 9, T25-S, R35-E	MD Reference:	well @ 3289.0usft (Noram #21)
Site Error:	0.0 usft	North Reference:	Grid
Reference Well:	Fez Federal Com #704H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.0 usft	Output errors are at	2.00 sigma
Reference Wellbore:	Wellbore #1	Database:	EDM 5000.1 Single User Db
Reference Design:	Design #1	Offset TVD Reference:	Offset Datum

Offset Design Sec 9, T25-S, R35-E - Fez Fee #11H - Wellbore #1 - Wellbore #1												Offset Site Error:	0.0 usft
Survey Program: 100-Good_gyro, 8700-MWD default												Offset Well Error:	0.0 usft
Reference Measured Depth (usft)	Vertical Depth (usft)	Offset Measured Depth (usft)	Vertical Depth (usft)	Semi Major Axis Reference (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N-S (usft)	+E-W (usft)	Distance Between Centres (usft)	Between Ellipses (usft)	Separation Factor	Warning	
0.0	0.0	0.0	0.0	0.0	0.0	-4.18	4,514.8	-330.2	4,526.9				
100.0	100.0	78.0	78.0	0.1	0.0	-4.18	4,515.0	-330.3	4,527.1	4,527.0	N/A		
200.0	200.0	158.2	158.2	0.5	0.1	-4.18	4,515.6	-330.1	4,527.8	4,527.3	8,186.686		
300.0	300.0	253.4	253.4	0.8	0.1	-4.17	4,516.6	-329.3	4,528.9	4,527.9	4,707.001		
400.0	400.0	364.3	364.3	1.2	0.2	-4.15	4,517.7	-327.8	4,529.7	4,528.4	3,281.958		
500.0	500.0	465.2	465.1	1.6	0.2	-4.13	4,518.6	-326.1	4,530.5	4,528.7	2,525.297		
600.0	600.0	576.2	576.2	1.9	0.3	-4.10	4,519.5	-323.8	4,531.1	4,528.9	2,046.800		
700.0	700.0	689.8	689.7	2.3	0.4	-4.07	4,520.1	-321.6	4,531.5	4,528.9	1,719.947		
800.0	800.0	786.3	786.2	2.6	0.4	-4.04	4,520.4	-319.5	4,531.7	4,528.7	1,487.062		
900.0	900.0	900.2	900.0	3.0	0.5	-4.01	4,520.8	-316.6	4,531.9	4,528.4	1,305.879		
1,000.0	1,000.0	1,022.5	1,022.3	3.4	0.5	-3.96	4,520.7	-312.6	4,531.6	4,527.7	1,161.575		
1,100.0	1,100.0	1,139.5	1,139.3	3.7	0.6	-3.92	4,520.2	-309.6	4,530.9	4,526.6	1,047.645		
1,200.0	1,200.0	1,279.9	1,279.6	4.1	0.7	-3.88	4,518.6	-306.1	4,529.7	4,524.9	951.087		
1,300.0	1,300.0	1,388.6	1,388.2	4.4	0.8	-3.84	4,516.7	-303.2	4,527.7	4,522.5	873.645		
1,400.0	1,400.0	1,488.0	1,487.6	4.8	0.8	-3.81	4,514.9	-301.1	4,525.8	4,520.2	808.950		
1,500.0	1,500.0	1,629.4	1,628.9	5.1	0.9	-3.79	4,511.7	-298.8	4,523.4	4,517.4	750.365		
1,600.0	1,600.0	1,733.8	1,733.3	5.5	0.9	-3.77	4,508.4	-297.2	4,520.2	4,513.8	701.711		
1,700.0	1,700.0	1,800.0	1,799.4	5.9	1.0	-3.77	4,506.8	-296.7	4,517.7	4,510.9	660.999		
1,800.0	1,800.0	1,869.5	1,868.9	6.2	1.0	-3.76	4,505.6	-296.5	4,515.9	4,508.7	624.774		
1,900.0	1,900.0	1,968.7	1,968.1	6.6	1.1	-3.77	4,504.2	-296.6	4,514.5	4,506.8	591.241		
2,000.0	2,000.0	2,079.7	2,079.1	6.9	1.1	-3.77	4,502.3	-297.0	4,512.8	4,504.8	560.696		
2,100.0	2,100.0	2,201.4	2,200.8	7.3	1.2	-3.79	4,499.8	-297.7	4,510.8	4,502.4	532.786		
2,200.0	2,200.0	2,341.3	2,340.7	7.7	1.3	-3.81	4,495.8	-299.0	4,508.0	4,499.1	506.975		
2,300.0	2,300.0	2,429.1	2,428.4	8.0	1.3	-3.82	4,493.0	-300.1	4,504.9	4,495.6	484.717		
2,400.0	2,400.0	2,500.0	2,499.2	8.4	1.3	-3.84	4,491.2	-301.2	4,502.4	4,492.7	464.746		
2,500.0	2,500.0	2,588.4	2,587.6	8.7	1.4	-3.86	4,489.4	-302.6	4,500.5	4,490.4	446.022		
2,600.0	2,600.0	2,704.8	2,703.9	9.1	1.4	-3.88	4,486.8	-304.6	4,498.3	4,487.8	428.190		
2,700.0	2,700.0	2,800.0	2,799.1	9.4	1.5	-3.91	4,484.5	-306.3	4,496.1	4,485.2	412.029		
2,800.0	2,800.0	2,853.3	2,852.5	9.8	1.5	-108.95	4,483.5	-307.0	4,494.9	4,483.6	398.204		
2,802.6	2,802.6	2,854.7	2,853.8	9.8	1.5	-108.95	4,483.5	-307.0	4,494.9	4,483.6	397.871		
2,900.0	2,899.8	2,910.8	2,909.9	10.1	1.5	-108.97	4,483.1	-307.5	4,496.0	4,484.3	385.719		
3,000.0	2,999.6	3,000.0	2,999.1	10.5	1.6	-109.06	4,483.0	-308.4	4,498.1	4,486.1	373.526		
3,100.0	3,099.4	3,080.8	3,079.9	10.8	1.6	-109.14	4,483.0	-309.2	4,500.6	4,488.1	362.186		
3,200.0	3,199.1	3,162.1	3,161.2	11.2	1.7	-109.22	4,483.5	-310.2	4,503.5	4,490.7	351.510		
3,300.0	3,298.9	3,240.2	3,239.3	11.5	1.7	-109.30	4,484.2	-311.3	4,506.8	4,493.6	341.500		
3,400.0	3,398.6	3,317.0	3,316.0	11.9	1.7	-109.38	4,485.3	-312.8	4,510.7	4,497.1	332.086		
3,503.8	3,502.0	3,400.0	3,399.0	12.2	1.8	-108.64	4,486.8	-314.3	4,515.8	4,501.8	322.818		
3,600.0	3,597.7	3,469.7	3,468.7	12.6	1.8	-108.74	4,488.5	-315.6	4,521.5	4,507.1	314.781		
3,700.0	3,697.1	3,530.3	3,529.2	12.9	1.8	-108.83	4,490.3	-316.8	4,528.1	4,513.4	307.033		
3,800.0	3,796.5	3,600.0	3,598.9	13.3	1.9	-108.94	4,493.2	-318.5	4,535.8	4,520.7	299.621		
3,900.0	3,896.0	3,651.5	3,650.2	13.7	2.1	-109.39	4,499.1	-320.0	4,541.4	4,525.7	289.331		
4,000.0	3,995.4	4,160.2	4,158.8	14.0	2.2	-109.65	4,494.2	-318.9	4,542.6	4,526.4	281.030		
4,100.0	4,094.9	4,283.4	4,281.9	14.4	2.2	-109.79	4,489.3	-317.6	4,542.1	4,525.5	273.756		
4,200.0	4,194.3	4,373.4	4,371.9	14.8	2.3	-109.90	4,485.8	-316.5	4,541.6	4,524.6	267.057		
4,300.0	4,293.7	4,460.6	4,459.0	15.1	2.3	-110.00	4,482.6	-315.3	4,541.5	4,524.0	260.690		
4,314.9	4,308.5	4,473.6	4,472.0	15.2	2.4	-110.01	4,482.1	-315.1	4,541.5	4,524.0	259.768		
4,400.0	4,393.2	4,538.3	4,536.6	15.5	2.4	-110.08	4,480.0	-313.9	4,541.6	4,523.8	254.687		
4,500.0	4,492.6	4,612.4	4,610.8	15.9	2.4	-110.16	4,478.0	-312.6	4,542.4	4,524.2	249.000		
4,600.0	4,592.1	4,727.8	4,726.0	16.2	2.5	-110.26	4,475.2	-308.7	4,543.3	4,524.6	243.274		
4,631.5	4,623.4	4,773.3	4,771.4	16.4	2.5	-110.29	4,474.0	-306.4	4,543.5	4,524.7	241.451		
4,700.0	4,691.6	4,831.8	4,829.8	16.6	2.6	-110.31	4,472.5	-302.8	4,543.5	4,524.4	237.830		
4,800.0	4,791.4	4,900.0	4,897.9	17.0	2.6	-110.31	4,471.1	-299.0	4,543.1	4,523.5	232.905		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

Company:	COG Operating, LLC	Local Co-ordinate Reference:	Well Fez Federal Com #704H
Project:	Lea County, NM	TVD Reference:	well @ 3289.0usft (Noram #21)
Reference Site:	Sec 9, T25-S, R35-E	MD Reference:	well @ 3289.0usft (Noram #21)
Site Error:	0.0 usft	North Reference:	Grid
Reference Well:	Fez Federal Com #704H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.0 usft	Output errors are at	2.00 sigma
Reference Wellbore	Wellbore #1	Database:	EDM 5000.1 Single User Db
Reference Design:	Design #1	Offset TVD Reference:	Offset Datum

Offset Design Sec 9, T25-S, R35-E - Fez Fee #11H - Wellbore #1 - Wellbore #1												Offset Site Error:	0.0 usft
Survey Program: 100-Good_gyro, 8700-MWD default												Offset Well Error:	0.0 usft
Reference Measured Depth (usft)	Vertical Depth (usft)	Offset Measured Depth (usft)	Vertical Depth (usft)	Semi Major Axis Reference (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbore +N-S (usft)	Distance Between Centres +E-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Separation Factor	Warning	
4,900.0	4,891.3	4,946.2	4,944.1	17.3	2.6	-110.28	4,470.5	-296.8	4,542.3	4,522.5	228.422		
4,935.2	4,926.5	4,963.8	4,961.6	17.5	2.6	-6.02	4,470.4	-296.0	4,542.1	4,522.1	226.897		
5,000.0	4,991.3	5,000.0	4,997.8	17.7	2.7	-6.01	4,470.4	-294.7	4,541.8	4,521.5	224.129		
5,007.5	4,998.8	5,000.0	4,997.8	17.7	2.7	-6.01	4,470.4	-294.7	4,541.8	4,521.5	223.842		
5,100.0	5,091.3	5,079.9	5,077.7	18.0	2.7	-5.98	4,470.7	-292.7	4,541.9	4,521.3	219.882		
5,200.0	5,191.3	5,130.3	5,128.1	18.4	2.7	-5.97	4,471.1	-292.0	4,542.6	4,521.6	216.017		
5,300.0	5,291.3	5,200.0	5,197.7	18.7	2.8	-5.97	4,472.9	-292.3	4,544.9	4,523.5	212.265		
5,400.0	5,391.3	5,237.8	5,235.5	19.1	2.8	-5.98	4,474.2	-293.0	4,548.0	4,526.2	208.884		
5,500.0	5,491.3	5,371.7	5,369.4	19.4	2.8	-6.02	4,477.8	-296.5	4,550.9	4,528.7	205.044		
5,600.0	5,591.3	5,466.1	5,463.7	19.8	2.9	-6.05	4,480.0	-299.3	4,553.6	4,531.0	201.557		
5,700.0	5,691.3	5,561.6	5,559.0	20.1	2.9	-6.09	4,482.4	-302.4	4,556.4	4,533.4	198.189		
5,800.0	5,791.3	5,658.4	5,655.8	20.5	3.0	-6.12	4,484.9	-305.4	4,559.3	4,535.9	194.925		
5,900.0	5,891.3	5,759.7	5,757.0	20.8	3.0	-6.16	4,487.6	-308.5	4,562.3	4,538.5	191.746		
6,000.0	5,991.3	5,853.5	5,850.7	21.2	3.1	-6.19	4,490.0	-311.4	4,565.2	4,541.0	188.707		
6,100.0	6,091.3	5,944.2	5,941.3	21.5	3.1	-6.23	4,492.6	-314.7	4,568.4	4,543.8	185.790		
6,200.0	6,191.3	6,039.5	6,036.5	21.9	3.2	-6.27	4,495.4	-318.3	4,571.7	4,546.7	182.945		
6,300.0	6,291.3	6,138.3	6,135.2	22.2	3.2	-6.31	4,498.3	-322.0	4,575.1	4,549.7	180.172		
6,400.0	6,391.3	6,249.0	6,245.8	22.6	3.3	-6.36	4,501.5	-326.4	4,578.4	4,552.6	177.422		
6,500.0	6,491.3	6,353.2	6,349.9	22.9	3.3	-6.40	4,504.3	-330.2	4,581.5	4,555.3	174.776		
6,600.0	6,591.3	6,449.5	6,446.0	23.3	3.4	-6.44	4,506.9	-333.8	4,584.6	4,558.0	172.245		
6,700.0	6,691.3	6,546.7	6,543.1	23.7	3.4	-6.48	4,509.6	-337.2	4,587.8	4,560.7	169.785		
6,800.0	6,791.3	6,641.0	6,637.4	24.0	3.5	-6.52	4,512.3	-340.5	4,591.0	4,563.6	167.411		
6,900.0	6,891.3	6,734.9	6,731.2	24.4	3.5	-6.56	4,515.2	-343.8	4,594.4	4,566.6	165.112		
7,000.0	6,991.3	6,833.2	6,829.4	24.7	3.6	-6.59	4,518.3	-347.1	4,597.9	4,569.7	162.860		
7,100.0	7,091.3	6,939.8	6,935.8	25.1	3.6	-6.63	4,521.6	-350.6	4,601.4	4,572.8	160.639		
7,200.0	7,191.3	7,046.4	7,042.4	25.4	3.7	-6.67	4,524.6	-353.9	4,604.6	4,575.5	158.467		
7,300.0	7,291.3	7,143.3	7,139.2	25.8	3.7	-6.70	4,527.5	-357.1	4,607.9	4,578.4	156.396		
7,400.0	7,391.3	7,243.5	7,239.3	26.1	3.8	-6.74	4,530.4	-360.2	4,611.1	4,581.3	154.365		
7,500.0	7,491.3	7,339.5	7,335.2	26.5	3.8	-6.77	4,533.3	-363.2	4,614.5	4,584.2	152.408		
7,600.0	7,591.3	7,455.0	7,450.6	26.8	3.9	-6.81	4,536.6	-366.5	4,617.7	4,587.0	150.430		
7,700.0	7,691.3	7,560.5	7,556.1	27.2	4.0	-6.84	4,539.4	-369.2	4,620.6	4,589.5	148.527		
7,800.0	7,791.3	7,670.1	7,665.5	27.5	4.0	-6.86	4,542.2	-371.9	4,623.5	4,592.0	146.661		
7,900.0	7,891.3	7,782.5	7,777.9	27.9	4.1	-6.89	4,544.8	-374.7	4,626.0	4,594.1	144.823		
8,000.0	7,991.3	7,884.0	7,879.3	28.3	4.1	-6.92	4,546.9	-377.3	4,628.4	4,596.1	143.061		
8,100.0	8,091.3	8,029.7	8,025.0	28.6	4.2	-6.96	4,549.3	-380.9	4,630.4	4,597.6	141.203		
8,200.0	8,191.3	8,160.2	8,155.5	29.0	4.3	-7.00	4,550.3	-384.0	4,631.4	4,598.2	139.411		
8,300.0	8,291.3	8,286.6	8,281.8	29.3	4.4	-7.03	4,550.6	-386.6	4,631.9	4,598.3	137.667		
8,400.0	8,391.3	8,398.1	8,393.3	29.7	4.4	-7.06	4,550.4	-388.8	4,631.9	4,597.9	135.986		
8,500.0	8,491.3	8,532.1	8,527.2	30.0	4.5	-7.10	4,549.4	-392.0	4,631.5	4,597.0	134.282		
8,600.0	8,591.3	9,261.6	9,181.9	30.4	6.9	-4.09	4,528.1	-146.3	4,624.2	4,587.1	124.785		
8,700.0	8,691.3	9,284.0	9,196.1	30.7	7.2	-3.87	4,527.5	-129.0	4,612.2	4,574.3	121.557		
8,800.0	8,791.3	9,316.0	9,214.9	31.1	7.7	-3.55	4,527.4	-103.1	4,602.2	4,563.2	117.856		
8,900.0	8,891.3	9,316.0	9,214.9	31.5	7.7	-3.55	4,527.4	-103.1	4,594.1	4,554.5	115.988		
9,000.0	8,991.3	9,347.0	9,231.3	31.8	8.2	-3.22	4,528.0	-76.8	4,588.0	4,547.2	112.595		
9,100.0	9,091.3	9,355.2	9,235.3	32.2	8.3	-3.13	4,528.2	-69.6	4,583.8	4,542.4	110.567		
9,200.0	9,191.3	9,378.0	9,245.8	32.5	8.7	-2.88	4,529.1	-49.4	4,581.6	4,539.2	107.898		
9,300.0	9,291.3	9,665.4	9,307.8	32.9	14.9	0.61	4,534.5	229.3	4,581.3	4,530.7	90.578		
9,317.6	9,308.9	9,666.9	9,307.9	32.9	14.9	0.63	4,534.5	230.8	4,581.2	4,530.5	90.340		
9,400.0	9,391.3	9,672.9	9,308.2	33.2	15.0	0.70	4,534.4	236.7	4,582.0	4,530.7	89.314		
9,500.0	9,491.3	9,678.7	9,308.5	33.6	15.2	0.78	4,534.4	242.6	4,584.9	4,532.9	88.236		
9,600.0	9,591.3	9,683.5	9,308.8	33.9	15.3	0.84	4,534.3	247.4	4,589.9	4,537.3	87.311		
9,700.0	9,691.3	9,687.4	9,308.9	34.3	15.4	0.89	4,534.3	251.3	4,597.1	4,544.0	86.519		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

Company:	COG Operating, LLC	Local Co-ordinate Reference:	Well Fez Federal Com #704H
Project:	Lea County, NM	TVD Reference:	well @ 3289.0usft (Noram #21)
Reference Site:	Sec 9, T25-S, R35-E	MD Reference:	well @ 3289.0usft (Noram #21)
Site Error:	0.0 usft	North Reference:	Grid
Reference Well:	Fez Federal Com #704H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.0 usft	Output errors are at	2.00 sigma
Reference Wellbore	Wellbore #1	Database:	EDM 5000.1 Single User Db
Reference Design:	Design #1	Offset TVD Reference:	Offset Datum

Offset Design Sec 9, T25-S, R35-E - Fez Fee #11H - Wellbore #1 - Wellbore #1												Offset Site Error: 0.0 usft	
Survey Program: 100-Good_gyro, 8700-MWD default												Offset Well Error: 0.0 usft	
Reference Measured Depth (usft)	Vertical Depth (usft)	Offset Measured Depth (usft)	Vertical Depth (usft)	Semi-Major Axis Reference (usft)	Offset (usft)	Highside Tooface ('')	Offset Wellbore Centre +N/-S (usft)		Distance Between Centres (usft)	Between Ellipses (usft)	Separation Factor	Warning:	
9,800.0	9,791.3	9,689.0	9,309.0	34.7	15.4	0.90	4,534.3	252.8	4,606.5	4,552.9	85.925		
9,900.0	9,891.3	9,689.0	9,309.0	35.0	15.4	0.90	4,534.3	252.8	4,618.0	4,564.0	85.484		
10,000.0	9,991.3	9,689.0	9,309.0	35.4	15.4	0.90	4,534.3	252.8	4,631.7	4,577.3	85.120		
10,100.0	10,091.3	9,689.0	9,309.0	35.7	15.4	0.90	4,534.3	252.8	4,647.4	4,592.6	84.829		
10,200.0	10,191.3	9,700.4	9,309.4	36.1	15.7	1.05	4,534.1	264.3	4,665.3	4,609.8	84.111		
10,300.0	10,291.3	9,702.8	9,309.5	36.4	15.7	1.08	4,534.1	266.6	4,685.2	4,629.3	83.866		
10,400.0	10,391.3	9,705.1	9,309.6	36.8	15.8	1.11	4,534.1	268.9	4,707.1	4,650.9	83.690		
10,500.0	10,491.3	9,707.4	9,309.7	37.1	15.8	1.13	4,534.0	271.2	4,731.1	4,674.5	83.583		
10,600.0	10,591.3	9,709.6	9,309.7	37.5	15.9	1.16	4,534.0	273.4	4,757.0	4,700.1	83.540		
10,700.0	10,691.3	9,711.8	9,309.8	37.9	15.9	1.19	4,534.0	275.6	4,784.9	4,727.6	83.559		
10,800.0	10,791.3	9,713.9	9,309.9	38.2	16.0	1.22	4,534.0	277.7	4,814.7	4,757.1	83.637		
10,900.0	10,891.3	9,716.0	9,310.0	38.6	16.0	1.24	4,534.0	279.8	4,846.4	4,788.5	83.771		
11,000.0	10,991.3	9,718.0	9,310.0	38.9	16.1	1.27	4,533.9	281.8	4,879.9	4,821.8	83.960		
11,100.0	11,091.3	9,720.0	9,310.1	39.3	16.1	1.29	4,533.9	283.8	4,915.2	4,856.9	84.200		
11,200.0	11,191.3	9,722.0	9,310.2	39.6	16.2	1.32	4,533.9	285.8	4,952.3	4,893.7	84.490		
11,300.0	11,291.3	9,723.9	9,310.2	40.0	16.2	1.34	4,533.9	287.7	4,991.2	4,932.3	84.826		
13,000.0	12,478.2	9,752.0	9,311.1	45.3	16.9	3.08	4,533.7	315.8	4,996.6	4,937.4	84.370		
13,100.0	12,477.9	9,737.5	9,310.6	45.7	16.6	2.82	4,533.8	301.3	4,919.5	4,860.8	83.910		
13,200.0	12,477.6	9,736.6	9,310.6	46.2	16.5	2.80	4,533.8	300.4	4,843.2	4,784.9	83.017		
13,300.0	12,477.3	9,735.7	9,310.6	46.7	16.5	2.78	4,533.8	299.6	4,767.9	4,709.8	82.133		
13,400.0	12,477.0	9,734.9	9,310.6	47.3	16.5	2.77	4,533.8	298.7	4,693.4	4,635.7	81.258		
13,500.0	12,476.7	9,734.0	9,310.5	47.9	16.5	2.75	4,533.8	297.8	4,619.9	4,562.5	80.391		
13,600.0	12,476.4	9,733.1	9,310.5	48.6	16.5	2.74	4,533.8	296.9	4,547.5	4,490.3	79.534		
13,700.0	12,476.1	9,732.2	9,310.5	49.3	16.4	2.72	4,533.8	296.0	4,476.1	4,419.2	78.685		
13,800.0	12,475.7	9,731.3	9,310.5	50.1	16.4	2.70	4,533.8	295.1	4,405.8	4,349.2	77.845		
13,900.0	12,475.4	9,730.3	9,310.4	50.9	16.4	2.69	4,533.8	294.2	4,336.6	4,280.3	77.012		
14,000.0	12,475.1	9,729.4	9,310.4	51.7	16.4	2.67	4,533.8	293.2	4,268.7	4,212.7	76.187		
14,100.0	12,474.8	9,728.5	9,310.4	52.6	16.3	2.65	4,533.8	292.3	4,202.1	4,146.4	75.368		
14,200.0	12,474.5	9,727.5	9,310.3	53.5	16.3	2.64	4,533.8	291.4	4,136.8	4,081.3	74.555		
14,300.0	12,474.2	9,726.6	9,310.3	54.5	16.3	2.62	4,533.9	290.4	4,073.0	4,017.7	73.747		
14,400.0	12,473.9	9,725.6	9,310.3	55.5	16.3	2.60	4,533.9	289.4	4,010.6	3,955.6	72.943		
14,500.0	12,473.6	9,724.6	9,310.2	56.5	16.3	2.58	4,533.9	288.5	3,949.7	3,895.0	72.143		
14,600.0	12,473.3	9,723.7	9,310.2	57.5	16.2	2.56	4,533.9	287.5	3,890.5	3,836.0	71.345		
14,700.0	12,473.0	9,722.7	9,310.2	58.6	16.2	2.55	4,533.9	286.5	3,832.9	3,778.6	70.548		
14,800.0	12,472.6	9,721.7	9,310.1	59.7	16.2	2.53	4,533.9	285.5	3,777.2	3,723.0	69.751		
14,900.0	12,472.3	9,720.7	9,310.1	60.8	16.2	2.51	4,533.9	284.5	3,723.3	3,669.3	68.954		
15,000.0	12,472.0	9,719.6	9,310.1	62.0	16.1	2.49	4,533.9	283.5	3,671.3	3,617.4	68.155		
15,100.0	12,471.7	9,718.6	9,310.0	63.2	16.1	2.47	4,533.9	282.4	3,621.3	3,567.5	67.354		
15,200.0	12,471.4	9,717.6	9,310.0	64.4	16.1	2.45	4,533.9	281.4	3,573.4	3,519.7	66.550		
15,300.0	12,471.1	9,716.5	9,310.0	65.6	16.1	2.44	4,534.0	280.3	3,527.8	3,474.1	65.744		
15,400.0	12,470.8	9,715.4	9,309.9	66.8	16.0	2.42	4,534.0	279.3	3,484.3	3,430.7	64.935		
15,500.0	12,470.5	9,714.4	9,309.9	68.0	16.0	2.40	4,534.0	278.2	3,443.3	3,389.6	64.123		
15,600.0	12,470.2	9,713.3	9,309.9	69.3	16.0	2.38	4,534.0	277.1	3,404.7	3,350.9	63.310		
15,700.0	12,469.9	9,712.2	9,309.8	70.6	16.0	2.36	4,534.0	276.0	3,368.6	3,314.7	62.497		
15,800.0	12,469.6	9,711.1	9,309.8	71.9	15.9	2.34	4,534.0	274.9	3,335.1	3,281.0	61.685		
15,900.0	12,469.2	9,710.0	9,309.7	73.2	15.9	2.32	4,534.0	273.8	3,304.3	3,250.0	60.876		
16,000.0	12,468.9	9,708.8	9,309.7	74.5	15.9	2.30	4,534.0	272.7	3,276.3	3,221.8	60.073		
16,100.0	12,468.6	9,707.7	9,309.7	75.9	15.9	2.28	4,534.0	271.5	3,251.1	3,196.3	59.277		
16,200.0	12,468.3	9,706.5	9,309.6	77.2	15.8	2.25	4,534.1	270.4	3,228.8	3,173.6	58.493		
16,300.0	12,468.0	9,705.4	9,309.6	78.6	15.8	2.23	4,534.1	269.2	3,209.5	3,153.9	57.721		
16,400.0	12,467.7	9,704.2	9,309.5	79.9	15.8	2.21	4,534.1	268.0	3,193.2	3,137.1	56.967		
16,500.0	12,467.4	9,703.0	9,309.5	81.3	15.7	2.19	4,534.1	266.8	3,179.9	3,123.4	56.233		

CC - Min centre to center distance or covergent point, SF - min separation factor, ES - min ellipse separation


Company:	COG Operating, LLC	Local Co-ordinate Reference:	Well Fez Federal Com #704H
Project:	Lea County, NM	TVD Reference:	well @ 3289.0usft (Noram #21)
Reference Site:	Sec 9, T25-S, R35-E	MD Reference:	well @ 3289.0usft (Noram #21)
Site Error:	0.0 usft	North Reference:	Grid
Reference Well:	Fez Federal Com #704H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.0 usft	Output errors are at	2.00 sigma
Reference Wellbore	Wellbore #1	Database:	EDM 5000.1 Single User Db
Reference Design:	Design #1	Offset TVD Reference:	Offset Datum

Offset Design Sec 9, T25-S, R35-E - Fez Fee #11H - Wellbore #1 - Wellbore #1												Offset Site Error:	0.0 usft
Survey Program: 100-Good_gyro, 8700-MWD default												Offset Well Error:	0.0 usft
Reference Measured Depth (usft)	Vertical Depth (usft)	Offset Measured Depth (usft)	Vertical Depth (usft)	Semi Major Axis Reference (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	Offset Wellbore Centre +E/-W (usft)	Distance Between Centres (usft)	Distance Between Ellipses (usft)	Separation Factor	Warning	
16,600.0	12,467.1	9,701.8	9,309.5	82.7	15.7	2.17	4,534.1	265.6	3,169.8	3,112.7	55.523		
16,700.0	12,466.8	9,700.6	9,309.4	84.1	15.7	2.15	4,534.1	264.4	3,162.7	3,105.1	54.841		
16,800.0	12,466.5	9,699.0	9,309.0	85.5	15.4	1.94	4,534.3	252.8	3,158.9	3,100.7	54.253		
16,872.6	12,466.2	9,689.0	9,309.0	86.6	15.4	1.94	4,534.3	252.8	3,158.1	3,099.4	53.795 CC		
16,900.0	12,466.1	9,689.0	9,309.0	87.0	15.4	1.94	4,534.3	252.8	3,158.2	3,099.3	53.628 ES		
17,000.0	12,465.8	9,689.0	9,309.0	88.4	15.4	1.94	4,534.3	252.8	3,160.6	3,101.1	53.043		
17,100.0	12,465.5	9,689.0	9,309.0	89.8	15.4	1.94	4,534.3	252.8	3,166.2	3,105.9	52.503		
17,200.0	12,465.2	9,689.0	9,309.0	91.3	15.4	1.94	4,534.3	252.8	3,175.0	3,114.0	52.011		
17,300.0	12,464.9	9,689.0	9,309.0	92.7	15.4	1.94	4,534.3	252.8	3,186.9	3,125.1	51.569		
17,400.0	12,464.6	9,689.0	9,309.0	94.2	15.4	1.94	4,534.3	252.8	3,201.8	3,139.3	51.182		
17,500.0	12,464.3	9,689.0	9,309.0	95.6	15.4	1.94	4,534.3	252.8	3,219.8	3,156.5	50.849		
17,600.0	12,464.0	9,689.0	9,309.0	97.1	15.4	1.94	4,534.3	252.8	3,240.8	3,176.7	50.574		
17,700.0	12,463.7	9,689.0	9,309.0	98.6	15.4	1.94	4,534.3	252.8	3,264.7	3,199.8	50.358		
17,800.0	12,463.4	9,689.0	9,309.0	100.1	15.4	1.94	4,534.3	252.8	3,291.4	3,225.9	50.200		
17,900.0	12,463.0	9,689.0	9,309.0	101.5	15.4	1.94	4,534.3	252.8	3,321.0	3,254.7	50.101		
18,000.0	12,462.7	9,689.0	9,309.0	103.0	15.4	1.94	4,534.3	252.8	3,353.3	3,286.3	50.060 SF		
18,100.0	12,462.4	9,689.0	9,309.0	104.5	15.4	1.94	4,534.3	252.8	3,388.2	3,320.6	50.076		
18,200.0	12,462.1	9,689.0	9,309.0	106.0	15.4	1.94	4,534.3	252.8	3,425.7	3,357.4	50.149		
18,300.0	12,461.8	9,689.0	9,309.0	107.5	15.4	1.94	4,534.3	252.8	3,465.7	3,396.8	50.276		
18,400.0	12,461.5	9,689.0	9,309.0	109.0	15.4	1.94	4,534.3	252.8	3,508.1	3,438.5	50.456		
18,500.0	12,461.2	9,689.0	9,309.0	110.5	15.4	1.94	4,534.3	252.8	3,552.7	3,482.6	50.686		
18,600.0	12,460.9	9,689.0	9,309.0	112.1	15.4	1.94	4,534.3	252.8	3,599.6	3,529.0	50.966		
18,700.0	12,460.6	9,689.0	9,309.0	113.6	15.4	1.94	4,534.3	252.8	3,648.7	3,577.6	51.293		
18,800.0	12,460.3	9,689.0	9,309.0	115.1	15.4	1.94	4,534.3	252.8	3,699.8	3,628.2	51.665		
18,900.0	12,459.9	9,689.0	9,309.0	116.6	15.4	1.94	4,534.3	252.8	3,752.9	3,680.8	52.080		
19,000.0	12,459.6	9,689.0	9,309.0	118.2	15.4	1.94	4,534.3	252.8	3,807.8	3,735.3	52.535		
19,100.0	12,459.3	9,689.0	9,309.0	119.7	15.4	1.94	4,534.3	252.8	3,864.6	3,791.7	53.030		
19,200.0	12,459.0	9,689.0	9,309.0	121.2	15.4	1.94	4,534.3	252.8	3,923.1	3,849.8	53.561		
19,300.0	12,458.7	9,689.0	9,309.0	122.8	15.4	1.94	4,534.3	252.8	3,983.2	3,909.6	54.128		
19,400.0	12,458.4	9,689.0	9,309.0	124.3	15.4	1.94	4,534.3	252.8	4,044.9	3,971.0	54.728		
19,500.0	12,458.1	9,689.0	9,309.0	125.9	15.4	1.94	4,534.3	252.8	4,108.1	4,033.9	55.360		
19,600.0	12,457.8	9,689.0	9,309.0	127.4	15.4	1.94	4,534.3	252.8	4,172.8	4,098.3	56.021		
19,700.0	12,457.5	9,689.0	9,309.0	129.0	15.4	1.94	4,534.3	252.8	4,238.8	4,164.1	56.711		
19,800.0	12,457.2	9,689.0	9,309.0	130.5	15.4	1.94	4,534.3	252.8	4,306.2	4,231.2	57.428		
19,900.0	12,456.8	9,689.0	9,309.0	132.1	15.4	1.94	4,534.3	252.8	4,374.8	4,299.6	58.169		
20,000.0	12,456.5	9,689.0	9,309.0	133.6	15.4	1.94	4,534.3	252.8	4,444.6	4,369.2	58.935		
20,100.0	12,456.2	9,677.2	9,308.5	135.2	15.1	1.72	4,534.4	241.0	4,515.4	4,440.0	59.857		
20,200.0	12,455.9	9,676.7	9,308.4	136.8	15.1	1.71	4,534.4	240.6	4,587.4	4,511.8	60.675		
20,300.0	12,455.6	9,676.3	9,308.4	138.3	15.1	1.71	4,534.4	240.1	4,660.5	4,584.7	61.513		
20,400.0	12,455.3	9,675.8	9,308.4	139.9	15.1	1.70	4,534.4	239.7	4,734.5	4,658.6	62.371		
20,500.0	12,455.0	9,675.4	9,308.4	141.5	15.1	1.69	4,534.4	239.2	4,809.5	4,733.4	63.247		
20,600.0	12,454.7	9,674.9	9,308.3	143.0	15.1	1.68	4,534.4	238.8	4,885.3	4,809.2	64.140		
20,700.0	12,454.4	9,674.5	9,308.3	144.6	15.1	1.67	4,534.4	238.3	4,962.0	4,885.8	65.049		

Company:	COG Operating, LLC	Local Co-ordinate Reference:	Well Fez Federal Com #704H
Project:	Lea County, NM	TVD Reference:	well @ 3289.0usft (Noram #21)
Reference Site:	Sec 9, T25-S, R35-E	MD Reference:	well @ 3289.0usft (Noram #21)
Site Error:	0.0 usft	North Reference:	Grid
Reference Well:	Fez Federal Com #704H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.0 usft	Output errors are at	2.00 sigma
Reference Wellbore	Wellbore #1	Database:	EDM 5000.1 Single User Db
Reference Design:	Design #1	Offset TVD Reference:	Offset Datum

Reference Depths are relative to well @ 3289.0usft (Noram #21)
Offset Depths are relative to Offset Datum
Central Meridian is 104° 20' 0.000 W

Coordinates are relative to: Fez Federal Com #704H
Coordinate System is US State Plane 1927 (Exact solution), New Mexico East 30
Grid Convergence at Surface is: 0.51°




Company: COG Operating, LLC
Project: Lea County, NM
Reference Site: Sec 9, T25-S, R35-E
Site Error: 0.0 usft
Reference Well: Fez Federal Com #704H
Well Error: 0.0 usft
Reference Wellbore: Wellbore #1
Reference Design: Design #1

Local Co-ordinate Reference: Well Fez Federal Com #704H
TVD Reference: well @ 3289.0usft (Noram #21)
MD Reference: well @ 3289.0usft (Noram #21)
North Reference: Grid
Survey Calculation Method: Minimum Curvature
Output errors are at 2.00 sigma
Database: EDM 5000.1 Single User Db
Offset TVD Reference: Offset Datum

Reference Depths are relative to well @ 3289.0usft (Noram #21)
 Offset Depths are relative to Offset Datum
 Central Meridian is 104° 20' 0.000 W

Coordinates are relative to: Fez Federal Com #704H
 Coordinate System is US State Plane 1927 (Exact solution), New Mexico East 30
 Grid Convergence at Surface is: 0.51°

Separation Factor Plot



LEGEND

Fez Federal Com #705H, Wellbore #1, Design #1 V0 —◆— Fez Fee #11H, Wellbore #1, Wellbore #1 V0

—■— Fez Federal Com #604H, Wellbore #1, Design #1 V0

COG Operating, LLC - Fez Federal Com 704H

Geologic Formations

TVD of target	12,449' EOL	Pilot hole depth	NA
MD at TD:	22,434'	Deepest expected fresh water:	207'

Formation	Depth (TVD) from KB	Water/Mineral Bearing/ Target Zone?	Hazards*
Quaternary Fill	Surface	Water	
Rustler	870	Water	
Top of Salt	1211	Salt	
Base of Salt	5006	Salt	
Lamar	5337	Salt Water	
Bell Canyon	5369	Salt Water	
Cherry Canyon	6308	Oil/Gas	
Brushy Canyon	7768	Oil/Gas	
Bone Spring Lime	8999	Oil/Gas	
U. Avalon Shale	9216	Oil/Gas	
L. Avalon Shale	9580	Oil/Gas	
1st Bone Spring Sand	10397	Oil/Gas	
2nd Bone Spring Sand	10917	Oil/Gas	
3rd Bone Spring Sand	11974	Oil/Gas	
Wolfcamp	12378	Target Oil/Gas	

Casing Program

Hole Size	Casing		Csg. Size	Weight (lbs)	Grade	Conn.	SF Collapse	SF Burst	SF Tension
	From	To							
17.5"	0	1100	13.375"	54.5	J55	STC	2.30	6.87	8.57
12.25"	0	11850	9.625"	47	HCL80	BTC	1.57	1.05	2.01
8.75"	0	22,434	5.5"	23	P110	BTC	1.80	2.12	2.53
BLM Minimum Safety Factor							1.125	1	1.6 Dry 1.8 Wet

Intermediate casing will be kept at least 1/3 full while running casing to mitigate collapse. Intermediate burst based on 0.7 frac gradient at the shoe with Gas Gradient 0.1 psi/ft to surface.

All casing strings will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.h

COG Operating, LLC - Fez Federal Com 704H

7. Drilling Conditions

Condition	Specify what type and where?
BH Pressure at deepest TVD	8095 psi at 12449' TVD
Abnormal Temperature	NO 180 Deg. F.

No abnormal pressure or temperature conditions are anticipated. Sufficient mud materials to maintain mud properties and weight increase requirements will be kept on location at all times.

Sufficient supplies of Paper/LCM for periodic sweeps to control seepage and losses will be maintained on location.

Hydrogen Sulfide (H₂S) monitors will be installed prior to drilling out the surface shoe. If H₂S is detected in concentrations greater than 100 ppm, the operator will comply with the provisions of Onshore Oil and Gas Order #6. If Hydrogen Sulfide is encountered, measured values and formations will be provided to the BLM.

N H₂S is present

Y H₂S Plan attached

8. Other Facets of Operation

Y	Is it a walking operation?
N	Is casing pre-set?

x	H ₂ S Plan.
x	BOP & Choke Schematics.
x	Directional Plan
x	5M Annular Variance