

**PECOS DISTRICT
DRILLING CONDITIONS OF APPROVAL**

HOBBS OCD
NOV 07 2018

RECEIVED

OPERATOR'S NAME:	COG Operating LLC
LEASE NO.:	NMNM125658
WELL NAME & NO.:	Fez Federal Com 705H
SURFACE HOLE FOOTAGE:	280'/S & 420'/W
BOTTOM HOLE FOOTAGE	200'/N & 330'/W
LOCATION:	Section 9, T.25 S., R.35 E., NMPM
COUNTY:	Lea County, New Mexico

Potash	☒ None	☐ Secretary	☐ R-111-P
Cave/Karst Potential	☒ Low	☐ Medium	☐ High
Variance	☐ None	☒ Flex Hose	☐ Other
Wellhead	☒ Conventional	☐ Multibowl	
Other	☐ 4 String Area	☐ Capitan Reef	☐ WIPP

A. Hydrogen Sulfide

1. Hydrogen Sulfide (H₂S) monitors shall be installed prior to drilling out the surface shoe. If H₂S is detected in concentrations greater than 100 ppm, the Hydrogen Sulfide area shall meet Onshore Order 6 requirements, which includes equipment and personnel/public protection items. If Hydrogen Sulfide is encountered, provide measured values and formations to the BLM.

B. CASING

1. The 13 3/8 inch surface casing shall be set at approximately 1100 feet (a minimum of 25 feet into the Rustler Anhydrite and above the salt) and cemented to the surface.
 - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.
 - b. Wait on cement (WOC) time for a primary cement job will be a minimum of 8 hours or 500 pounds compressive strength, whichever is greater. (This is to include the lead cement)
 - c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.

- d. If cement falls back, remedial cementing will be done prior to drilling out that string.
2. The minimum required fill of cement behind the **9 5/8** inch intermediate casing is:

Operator has proposed a DV tool at a depth of **5325'**, the depth may be adjusted as long as the cement is changed proportionally. The DV tool may be cancelled if cement circulates to surface on the first stage.

 - a. First stage to DV tool: Cement to circulate. If cement does not circulate off the DV tool, contact the appropriate BLM office before proceeding with second stage cement job.
 - b. Second stage above DV tool:
 - Cement to surface. If cement does not circulate, contact the appropriate BLM office.
3. The minimum required fill of cement behind the **5 1/2** inch production casing is:
 - Cement should tie-back at least **200** feet into previous casing string. Operator shall provide method of verification.

C. PRESSURE CONTROL

1. Variance approved to use flex line from BOP to choke manifold. Manufacturer's specification to be readily available. No external damage to flex line. Flex line to be installed as straight as possible (no hard bends).
2. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be **5000 (5M) psi**.
3. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the **9 5/8** inch intermediate casing shoe shall be **10,000 (10M) psi**. **Variance is approved to use 5M Annular which shall be tested to 5000 psi.**

D. SPECIAL REQUIREMENT(S)

Communitization Agreement

- The operator will submit a Communitization Agreement to the Carlsbad Field Office, 620 E Greene St. Carlsbad, New Mexico 88220, at least 90 days before the anticipated date of first production from a well subject to a spacing order issued by the New Mexico Oil Conservation Division. The Communitization Agreement will

include the signatures of all working interest owners in all Federal and Indian leases subject to the Communitization Agreement (i.e., operating rights owners and lessees of record), or certification that the operator has obtained the written signatures of all such owners and will make those signatures available to the BLM immediately upon request.

- If the operator does not comply with this condition of approval, the BLM may take enforcement actions that include, but are not limited to, those specified in 43 CFR 3163.1.
- In addition, the well sign shall include the surface and bottom hole lease numbers. When the Communitization Agreement number is known, it shall also be on the sign.

Waste Minimization Plan (WMP)

In the interest of resource development, submission of additional well gas capture development plan information is deferred but may be required by the BLM Authorized Officer at a later date.

MHH 10152018

GENERAL REQUIREMENTS

The BLM is to be notified in advance for a representative to witness:

- a. Spudding well (minimum of 24 hours)
- b. Setting and/or Cementing of all casing strings (minimum of 4 hours)
- c. BOPE tests (minimum of 4 hours)

☒ Chaves and Roosevelt Counties

Call the Roswell Field Office, 2909 West Second St., Roswell NM 88201.
During office hours call (575) 627-0272.
After office hours call (575)

☒ Eddy County

Call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220,
(575) 361-2822

☒ Lea County

Call the Hobbs Field Station, 414 West Taylor, Hobbs NM 88240, (575)
393-3612

1. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval.
 - a. In the event the operator has proposed to drill multiple wells utilizing a skid/walking rig. Operator shall secure the wellbore on the current well, after installing and testing the wellhead, by installing a blind flange of like pressure rating to the wellhead and a pressure gauge that can be monitored while drilling is performed on the other well(s).
 - b. When the operator proposes to set surface casing with Spudder Rig
 - Notify the BLM when moving in and removing the Spudder Rig.
 - Notify the BLM when moving in the 2nd Rig. Rig to be moved in within 90 days of notification that Spudder Rig has left the location.
 - BOP/BOPE test to be conducted per Onshore Oil and Gas Order No. 2 as soon as 2nd Rig is rigged up on well.
2. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works are located, this does not include the dog house or stairway area.

3. The record of the drilling rate along with the GR/N well log run from TD to surface (horizontal well – vertical portion of hole) shall be submitted to the BLM office as well as all other logs run on the borehole 30 days from completion. If available, a digital copy of the logs is to be submitted in addition to the paper copies. The Rustler top and bottom of Salt are to be recorded on the Completion Report.

A. CASING

1. Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size or are Non-API. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.). The initial wellhead installed on the well will remain on the well with spools used as needed.
2. Wait on cement (WOC) for Potash Areas: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi for all cement blends, 2) until cement has been in place at least 24 hours. WOC time will be recorded in the driller's log.
3. Wait on cement (WOC) for Water Basin: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi at the shoe, 2) until cement has been in place at least 8 hours. WOC time will be recorded in the driller's log. See individual casing strings for details regarding lead cement slurry requirements.
4. Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. Have well specific cement details onsite prior to pumping the cement for each casing string.
5. No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.
6. On that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Formation at the shoe shall be tested to a minimum of the mud weight equivalent anticipated to control the formation pressure to the next casing depth or at total depth of the well. This test shall be performed before drilling more than 20 feet of new hole.
7. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.

8. Whenever a casing string is cemented in the R-111-P potash area, the NMOC requirements shall be followed.

B. PRESSURE CONTROL

1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in Onshore Oil and Gas Order No. 2 and API RP 53 Sec. 17.
2. If a variance is approved for a flexible hose to be installed from the BOP to the choke manifold, the following requirements apply: Check condition of flexible line from BOP to choke manifold, replace if exterior is damaged or if line fails test. Line to be as straight as possible with no hard bends and is to be anchored according to Manufacturer's requirements. The flexible hose can be exchanged with a hose of equal size and equal or greater pressure rating. Anchor requirements, specification sheet and hydrostatic pressure test certification matching the hose in service, to be onsite for review. These documents shall be posted in the company man's trailer and on the rig floor.
3. 5M or higher system requires an HCR valve, remote kill line and annular to match. The remote kill line is to be installed prior to testing the system and tested to stack pressure.
4. If the operator has proposed a multi-bowl wellhead assembly in the APD. The following requirements must be met:
 - a. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
 - b. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
 - c. Manufacturer representative shall install the test plug for the initial BOP test.
 - d. Operator shall perform the intermediate casing integrity test to 70% of the casing burst. This will test the multi-bowl seals.
 - e. If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
5. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.
 - a. In a water basin, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. The casing cut-off and BOP installation can be initiated four hours after installing the slips, which will be approximately six hours after bumping the

plug. For those casing strings not using slips, the minimum wait time before cut-off is eight hours after bumping the plug. BOP/BOPE testing can begin after cut-off or once cement reaches 500 psi compressive strength (including lead when specified), whichever is greater. However, if the float does not hold, cut-off cannot be initiated until cement reaches 500 psi compressive strength (including lead when specified).

- b. In potash areas, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. For all casing strings, casing cut-off and BOP installation can be initiated at twelve hours after bumping the plug. However, **no tests** shall commence until the cement has had a minimum of 24 hours setup time.
- c. The tests shall be done by an independent service company utilizing a test plug not a cup or J-packer. The operator also has the option of utilizing an independent tester to test without a plug (i.e. against the casing) pursuant to Onshore Order 2 with the pressure not to exceed 70% of the burst rating for the casing. Any test against the casing must meet the WOC time for water basin (8 hours) or potash (24 hours) or 500 pounds compressive strength, whichever is greater, prior to initiating the test (see casing segment as lead cement may be critical item).
- d. The test shall be run on a 5000 psi chart for a 2-3M BOP/BOP, on a 10000 psi chart for a 5M BOP/BOPE and on a 15000 psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one hour chart. A circular chart shall have a maximum 2 hour clock. If a twelve hour or twenty-four hour chart is used, tester shall make a notation that it is run with a two hour clock.
- e. The results of the test shall be reported to the appropriate BLM office.
- f. All tests are required to be recorded on a calibrated test chart. A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.
- g. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug. This test shall be performed prior to the test at full stack pressure.
- h. BOP/BOPE must be tested by an independent service company within 500 feet of the top of the Wolfcamp formation if the time between the setting of the intermediate casing and reaching this depth exceeds 20 days. This test does not exclude the test prior to drilling out the casing shoe as per Onshore Order No. 2.

C. DRILLING MUD

Mud system monitoring equipment, with derrick floor indicators and visual and audio alarms, shall be operating before drilling into the Wolfcamp formation, and shall be used until production casing is run and cemented.

D. WASTE MATERIAL AND FLUIDS

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area.

Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.

**PECOS DISTRICT
SURFACE USE
CONDITIONS OF APPROVAL**

OPERATOR'S NAME:	COG Operating LLC
LEASE NO.:	NMNM125658
WELL NAME & NO.:	Fez Federal Com 705H
SURFACE HOLE FOOTAGE:	280'/S & 420'/W
BOTTOM HOLE FOOTAGE	200'/N & 330'/W
LOCATION:	Section 9, T.25 S., R.35 E., NMPM
COUNTY:	Lea County, New Mexico

TABLE OF CONTENTS

Standard Conditions of Approval (COA) apply to this APD. If any deviations to these standards exist or special COAs are required, the section with the deviation or requirement will be checked below.

- ☐ **General Provisions**
- ☐ **Permit Expiration**
- ☐ **Archaeology, Paleontology, and Historical Sites**
- ☐ **Noxious Weeds**
- ☒ **Special Requirements**
 - Lesser Prairie-Chicken Timing Stipulations
 - Below Ground-level Abandoned Well Marker
 - Hydrology
 - Range
- ☐ **Construction**
 - Notification
 - Topsoil
 - Closed Loop System
 - Federal Mineral Material Pits
 - Well Pads
 - Roads
- ☐ **Road Section Diagram**
- ☐ **Production (Post Drilling)**
 - Well Structures & Facilities
- ☐ **Interim Reclamation**
- ☐ **Final Abandonment & Reclamation**

I. GENERAL PROVISIONS

The approval of the Application For Permit To Drill (APD) is in compliance with all applicable laws and regulations: 43 Code of Federal Regulations 3160, the lease terms, Onshore Oil and Gas Orders, Notices To Lessees, New Mexico Oil Conservation Division (NMOCD) Rules, National Historical Preservation Act As Amended, and instructions and orders of the Authorized Officer. Any request for a variance shall be submitted to the Authorized Officer on Form 3160-5, Sundry Notices and Report on Wells.

II. PERMIT EXPIRATION

If the permit terminates prior to drilling and drilling cannot be commenced within 60 days after expiration, an operator is required to submit Form 3160-5, Sundry Notices and Reports on Wells, requesting surface reclamation requirements for any surface disturbance. However, if the operator will be able to initiate drilling within 60 days after the expiration of the permit, the operator must have set the conductor pipe in order to allow for an extension of 60 days beyond the expiration date of the APD. (Filing of a Sundry Notice is required for this 60 day extension.)

III. ARCHAEOLOGICAL, PALEONTOLOGY & HISTORICAL SITES

Any cultural and/or paleontological resource discovered by the operator or by any person working on the operator's behalf shall immediately report such findings to the Authorized Officer. The operator is fully accountable for the actions of their contractors and subcontractors. The operator shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery shall be made by the Authorized Officer to determine the appropriate actions that shall be required to prevent the loss of significant cultural or scientific values of the discovery. The operator shall be held responsible for the cost of the proper mitigation measures that the Authorized Officer assesses after consultation with the operator on the evaluation and decisions of the discovery. Any unauthorized collection or disturbance of cultural or paleontological resources may result in a shutdown order by the Authorized Officer.

IV. NOXIOUS WEEDS

The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes the roads, pads, associated pipeline corridor, and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

V. SPECIAL REQUIREMENT(S)

Timing Limitation Stipulation / Condition of Approval for lesser prairie-chicken:

Oil and gas activities including 3-D geophysical exploration, and drilling will not be allowed in lesser prairie-chicken habitat during the period from March 1st through June 15th annually. During that period, other activities that produce noise or involve human activity, such as the maintenance of oil and gas facilities, pipeline, road, and well pad construction, will be allowed except between 3:00 am and 9:00 am. The 3:00 am to 9:00 am restriction will not apply to normal, around-the-clock operations, such as venting, flaring, or pumping, which do not require a human presence during this period. Additionally, no new drilling will be allowed within up to 200 meters of leks known at the time of permitting. Normal vehicle use on existing roads will not be restricted. Exhaust noise from pump jack engines must be muffled or otherwise controlled so as not to exceed 75 db measured at 30 feet from the source of the noise.

Below Ground-level Abandoned Well Marker to avoid raptor perching: Upon the plugging and subsequent abandonment of the well, the well marker will be installed at ground level on a plate containing the pertinent information for the plugged well. For more installation details, contact the Carlsbad Field Office at 575-234-5972.

Timing Limitation Exceptions:

The Carlsbad Field Office will publish an annual map of where the LPC timing and noise stipulations and conditions of approval (Limitations) will apply for the identified year (between March 1 and June 15) based on the latest survey information. The LPC Timing Area map will identify areas which are Habitat Areas (HA), Isolated Population Area (IPA), and Primary Population Area (PPA). The LPC Timing Area map will also have an area in red crosshatch. The red crosshatch area is the only area where an operator is required to submit a request for exception to the LPC Limitations. If an operator is operating outside the red crosshatch area, the LPC Limitations do not apply for that year and an exception to LPC Limitations is not required.

Hydrology

The entire well pad will be bermed to prevent oil, salt, and other chemical contaminants from leaving the well pad. Topsoil shall not be used to construct the berm. No water flow from the uphill side(s) of the pad shall be allowed to enter the well pad. The berm shall be maintained through the life of the well and after interim reclamation has been completed. Any water erosion that may occur due to the construction of the well pad during the life of the well will be quickly corrected and proper measures will be taken to prevent future erosion.

Tank battery locations will be lined and bermed. A 20 mil permanent liner will be installed with a 4 oz. felt backing to prevent tears or punctures. Tank battery berms must be large enough to contain 1 ½ times the content of the largest tank or 24 hour

production, whichever is greater. Automatic shut off, check valves, or similar systems will be installed for tanks to minimize the effects of catastrophic line failures used in production or drilling.

A leak detection plan will be submitted to the BLM Carlsbad Field Office for approval prior to pipeline installation. The method could incorporate gauges to detect pressure drops, siting valves and lines so they can be visually inspected periodically or installing electronic sensors to alarm when a leak is present. The leak detection plan will incorporate an automatic shut off system that will be installed for proposed pipelines to minimize the effects of an undesirable event.

Range

The proponent would not damage the allotment fence during construction of the pads or roads. If fence is damaged the blm must be contacted immediately and all work must cease till the fence has been repaired back to its original condition or better.

VI. CONSTRUCTION

A. NOTIFICATION

The BLM shall administer compliance and monitor construction of the access road and well pad. Notify the Carlsbad Field Office at (575) 234-5909 at least 3 working days prior to commencing construction of the access road and/or well pad.

When construction operations are being conducted on this well, the operator shall have the approved APD and Conditions of Approval (COA) on the well site and they shall be made available upon request by the Authorized Officer.

B. TOPSOIL

The operator shall strip the top portion of the soil (root zone) from the entire well pad area and stockpile the topsoil along the edge of the well pad as depicted in the APD. The root zone is typically six (6) inches in depth. All the stockpiled topsoil will be redistributed over the interim reclamation areas. Topsoil shall not be used for berming the pad or facilities. For final reclamation, the topsoil shall be spread over the entire pad area for seeding preparation.

Other subsoil (below six inches) stockpiles must be completely segregated from the topsoil stockpile. Large rocks or subsoil clods (not evident in the surrounding terrain) must be buried within the approved area for interim and final reclamation.

C. CLOSED LOOP SYSTEM

Tanks are required for drilling operations: No Pits.

The operator shall properly dispose of drilling contents at an authorized disposal site.

D. FEDERAL MINERAL MATERIALS PIT

Payment shall be made to the BLM prior to removal of any federal mineral materials. Call the Carlsbad Field Office at (575) 234-5972.

E. WELL PAD SURFACING

Surfacing of the well pad is not required.

If the operator elects to surface the well pad, the surfacing material may be required to be removed at the time of reclamation. The well pad shall be constructed in a manner which creates the smallest possible surface disturbance, consistent with safety and operational needs.

F. EXCLOSURE FENCING (CELLARS & PITS)

Exclosure Fencing

The operator will install and maintain exclosure fencing for all open well cellars to prevent access to public, livestock, and large forms of wildlife before and after drilling operations until the pit is free of fluids and the operator initiates backfilling. (For examples of exclosure fencing design, refer to BLM's Oil and Gas Gold Book, Exclosure Fence Illustrations, Figure 1, Page 18.)

G. ON LEASE ACCESS ROADS**Road Width**

The access road shall have a driving surface that creates the smallest possible surface disturbance and does not exceed fourteen (14) feet in width. The maximum width of surface disturbance, when constructing the access road, shall not exceed twenty-five (25) feet.

Surfacing

Surfacing material is not required on the new access road driving surface. If the operator elects to surface the new access road or pad, the surfacing material may be required to be removed at the time of reclamation.

Where possible, no improvements should be made on the unsurfaced access road other than to remove vegetation as necessary, road irregularities, safety issues, or to fill low areas that may sustain standing water.

The Authorized Officer reserves the right to require surfacing of any portion of the access road at any time deemed necessary. Surfacing may be required in the event the road deteriorates, erodes, road traffic increases, or it is determined to be beneficial for future field development. The surfacing depth and type of material will be determined at the time of notification.

Crowning

Crowning shall be done on the access road driving surface. The road crown shall have a grade of approximately 2% (i.e., a 1" crown on a 14' wide road). The road shall conform to Figure 1; cross section and plans for typical road construction.

Ditching

Ditching shall be required on both sides of the road.

Turnouts


Vehicle turnouts shall be constructed on the road. Turnouts shall be intervisible with interval spacing distance less than 1000 feet. Turnouts shall conform to Figure 1; cross section and plans for typical road construction.

Drainage

Drainage control systems shall be constructed on the entire length of road (e.g. ditches, sidehill outslowing and insloping, lead-off ditches, culvert installation, and low water crossings).

A typical lead-off ditch has a minimum depth of 1 foot below and a berm of 6 inches above natural ground level. The berm shall be on the down-slope side of the lead-off ditch.

Cross Section of a Typical Lead-off Ditch



All lead-off ditches shall be graded to drain water with a 1 percent minimum to 3 percent maximum ditch slope. The spacing interval are variable for lead-off ditches and shall be determined according to the formula for spacing intervals of lead-off ditches, but may be amended depending upon existing soil types and centerline road slope (in %);

Formula for Spacing Interval of Lead-off Ditches

Example - On a 4% road slope that is 400 feet long, the water flow shall drain water into a lead-off ditch. Spacing interval shall be determined by the following formula:

$$400 \text{ foot road with } 4\% \text{ road slope: } \frac{400'}{4\%} + 100' = 200' \text{ lead-off ditch interval}$$

Cattle guards

An appropriately sized cattle guard sufficient to carry out the project shall be installed and maintained at fence/road crossings. Any existing cattle guards on the access road route shall be repaired or replaced if they are damaged or have deteriorated beyond practical use. The operator shall be responsible for the condition of the existing cattle guards that are in place and are utilized during lease operations.

Fence Requirement

Where entry is granted across a fence line, the fence shall be braced and tied off on both sides of the passageway prior to cutting. The operator shall notify the private surface landowner or the grazing allotment holder prior to crossing any fences.

Public Access

Public access on this road shall not be restricted by the operator without specific written approval granted by the Authorized Officer.

Construction Steps

1. Salvage topsoil
2. Construct road

3. Redistribute topsoil
4. Revegetate slopes




Figure 1. Cross-sections and plans for typical road sections representative of BLM resource or FS local and higher-class roads.

VII. PRODUCTION (POST DRILLING)

A. WELL STRUCTURES & FACILITIES

Placement of Production Facilities

Production facilities should be placed on the well pad to allow for maximum interim recontouring and revegetation of the well location.

Exclosure Netting (Open-top Tanks)

Immediately following active drilling or completion operations, the operator will take actions necessary to prevent wildlife and livestock access, including avian wildlife, to all open-topped tanks that contain or have the potential to contain salinity sufficient to cause harm to wildlife or livestock, hydrocarbons, or Resource Conservation and Recovery Act of 1976-exempt hazardous substances. At a minimum, the operator will net, screen, or cover open-topped tanks to exclude wildlife and livestock and prevent mortality. If the operator uses netting, the operator will cover and secure the open portion of the tank to prevent wildlife entry. The operator will net, screen, or cover the tanks until the operator removes the tanks from the location or the tanks no longer contain substances that could be harmful to wildlife or livestock. Use a maximum netting mesh size of 1 ½ inches. The netting must not be in contact with fluids and must not have holes or gaps.

Chemical and Fuel Secondary Containment and Exclosure Screening

The operator will prevent all hazardous, poisonous, flammable, and toxic substances from coming into contact with soil and water. At a minimum, the operator will install and maintain an impervious secondary containment system for any tank or barrel containing hazardous, poisonous, flammable, or toxic substances sufficient to contain the contents of the tank or barrel and any drips, leaks, and anticipated precipitation. The operator will dispose of fluids within the containment system that do not meet applicable state or U. S. Environmental Protection Agency livestock water standards in accordance with state law; the operator must not drain the fluids to the soil or ground. The operator will design, construct, and maintain all secondary containment systems to prevent wildlife and livestock exposure to harmful substances. At a minimum, the operator will install effective wildlife and livestock exclosure systems such as fencing, netting, expanded metal mesh, lids, and grate covers. Use a maximum netting mesh size of 1 ½ inches.

Open-Vent Exhaust Stack Exclosures

The operator will construct, modify, equip, and maintain all open-vent exhaust stacks on production equipment to prevent birds and bats from entering, and to discourage perching, roosting, and nesting. (*Recommended exclosure structures on open-vent exhaust stacks are in the shape of a cone.*) Production equipment includes, but may not be limited to, tanks, heater-treaters, separators, dehydrators, flare stacks, in-line units, and compressor mufflers.

Containment Structures

Proposed production facilities such as storage tanks and other vessels will have a secondary containment structure that is constructed to hold the capacity of 1.5 times the largest tank, plus freeboard to account for precipitation, unless more stringent protective requirements are deemed necessary.

Painting Requirement

All above-ground structures including meter housing that are not subject to safety requirements shall be painted a flat non-reflective paint color, **Shale Green** from the BLM Standard Environmental Color Chart (CC-001: June 2008).

VIII. INTERIM RECLAMATION

During the life of the development, all disturbed areas not needed for active support of production operations should undergo interim reclamation in order to minimize the environmental impacts of development on other resources and uses.

Within six (6) months of well completion, operators should work with BLM surface management specialists (Jim Amos: 575-234-5909) to devise the best strategies to reduce the size of the location. Interim reclamation should allow for remedial well operations, as well as safe and efficient removal of oil and gas.

During reclamation, the removal of caliche is important to increasing the success of revegetating the site. Removed caliche that is free of contaminants may be used for road repairs, fire walls or for building other roads and locations. In order to operate the well or complete workover operations, it may be necessary to drive, park and operate on restored interim vegetation within the previously disturbed area. Disturbing revegetated areas for production or workover operations will be allowed. If there is significant disturbance and loss of vegetation, the area will need to be revegetated. Communicate with the appropriate BLM office for any exceptions/exemptions if needed.

All disturbed areas after they have been satisfactorily prepared need to be reseeded with the seed mixture provided below.

Upon completion of interim reclamation, the operator shall submit a Sundry Notices and Reports on Wells, Subsequent Report of Reclamation (Form 3160-5).

IX. FINAL ABANDONMENT & RECLAMATION

At final abandonment, well locations, production facilities, and access roads must undergo "final" reclamation so that the character and productivity of the land are restored.

Earthwork for final reclamation must be completed within six (6) months of well plugging. All pads, pits, facility locations and roads must be reclaimed to a satisfactory revegetated, safe, and stable condition, unless an agreement is made with the landowner or BLM to keep the road and/or pad intact.

After all disturbed areas have been satisfactorily prepared, these areas need to be revegetated with the seed mixture provided below. Seeding should be accomplished by drilling on the contour whenever practical or by other approved methods. Seeding may need to be repeated until revegetation is successful, as determined by the BLM.

Operators shall contact a BLM surface protection specialist prior to surface abandonment operations for site specific objectives (Jim Amos: 575-234-5909).

Below Ground-level Abandoned Well Marker to avoid raptor perching: Upon the plugging and subsequent abandonment of the well, the well marker will be installed at ground level on a plate containing the pertinent information for the plugged well.

Seed Mixture for LPC Sand/Shinnery Sites

Holder shall seed all disturbed areas with the seed mixture listed below. The seed mixture shall be planted in the amounts specified in pounds of pure live seed (PLS)* per acre. There shall be no primary or secondary noxious weeds in the seed mixture. Seed will be tested and the viability testing of seed shall be done in accordance with State law(s) and within nine (9) months prior to purchase. Commercial seed shall be either certified or registered seed. The seed container shall be tagged in accordance with State law(s) and available for inspection by the Authorized Officer.

Seed will be planted using a drill equipped with a depth regulator to ensure proper depth of planting where drilling is possible. The seed mixture will be evenly and uniformly planted over the disturbed area (smaller/heavier seeds have a tendency to drop the bottom of the drill and are planted first). Holder shall take appropriate measures to ensure this does not occur. Where drilling is not possible, seed will be broadcast and the area shall be raked or chained to cover the seed. When broadcasting the seed, the pounds per acre are to be doubled. Seeding shall be repeated until a satisfactory stand is established as determined by the Authorized Officer. Evaluation of growth may not be made before completion of at least one full growing season after seeding.

Species to be planted in pounds of pure live seed* per acre:

<u>Species</u>	<u>lb/acre</u>
Plains Bristlegrass	5lbs/A
Sand Bluestem	5lbs/A
Little Bluestem	3lbs/A
Big Bluestem	6lbs/A
Plains Coreopsis	2lbs/A
Sand Dropseed	1lbs/A

*Pounds of pure live seed:

Pounds of seed x percent purity x percent germination = pounds pure live seed

COG OPERATING LLC
HYDROGEN SULFIDE DRILLING OPERATIONS PLAN

1. HYDROGEN SULFIDE TRAINING

All personnel, whether regularly assigned, contracted, or employed on an unscheduled basis, will receive training from a qualified instructor in the following areas prior to commencing drilling operations on this well:

- a. The hazards and characteristics of hydrogen sulfide (H₂S).
- b. The proper use and maintenance of personal protective equipment and life support systems.
- c. The proper use of H₂S detectors, alarms, warning systems, briefing areas, evacuation procedures, and prevailing winds.
- d. The proper techniques for first aid and rescue procedures.

In addition, supervisory personnel will be trained in the following areas:

- a. The effects of H₂S on metal components. If high tensile tubulars are to be used, personnel will be trained in their special maintenance requirements.
- b. Corrective action and shut-in procedures when drilling or reworking a well and blowout prevention and well control procedures.
- c. The contents and requirements of the H₂S Drilling Operations Plan and the Public Protection Plan.

There will be an initial training session just prior to encountering a known or probable H₂S zone (within 3 days or 500 feet) and weekly H₂S and well control drills for all personnel in each crew. The initial training session shall include a review of the site specific H₂S Drilling Operations Plan and the Public Protection Plan. This plan shall be available at the well site. All personnel will be required to carry documentation that they have received the proper training.


2. H₂S SAFETY EQUIPMENT AND SYSTEMS

Note: All H₂S safety equipment and systems will be installed, tested, and operational when drilling reaches a depth of 500 feet above, or three days prior to penetrating the first zone containing or reasonably expected to contain H₂S. If H₂S greater than 100 ppm is encountered in the gas stream we will shut in and install H₂S equipment.

- a. Well Control Equipment:
 - Flare line.
 - Choke manifold with remotely operated choke.
 - Blind rams and pipe rams to accommodate all pipe sizes with properly sized closing unit.
 - Auxiliary equipment to include: annular preventer, mud-gas separator, rotating head.

COG Operating LLC
H₂S Equipment Schematic
Terrain: Shinnery sand hills.

Well pad will be 400' x 400'
with cellar in center of pad



- b. Protective equipment for essential personnel:
Mark II Surviveair 30-minute units located in the dog house and at briefing areas.
- c. H2S detection and monitoring equipment:
2 - portable H2S monitor positioned on location for best coverage and response. These units have warning lights and audible sirens when H2S levels of 20 ppm are reached.
- d. Visual warning systems:
Caution/Danger signs shall be posted on roads providing direct access to location. Signs will be painted a high visibility yellow with black lettering of sufficient size to be readable at a reasonable distance from the immediate location. Bilingual signs will be used, when appropriate. See example attached.
- e. Mud Program:
The mud program has been designed to minimize the volume of H2S circulated to the surface.
- f. Metallurgy:
All drill strings, casings, tubing, wellhead, blowout preventers, drilling spool, kill lines, choke manifold and lines, and valves shall be suitable for H2S service.
- g. Communication:
Company vehicles equipped with cellular telephone.

COG OPERATING LLC has conducted a review to determine if an H2S contingency plan is required for the above referenced well. We were able to conclude that any potential hazardous volume would be minimal. H2S concentrations of wells in this area from surface to TD are low enough; therefore, we do not believe that an H2S contingency plan is necessary.

W A R N I N G

**YOU ARE ENTERING AN H₂S AREA
AUTHORIZED PERSONNEL ONLY**

- 1. BEARDS OR CONTACT LENSES NOT ALLOWED***
- 2. HARD HATS REQUIRED***
- 3. SMOKING IN DESIGNATED AREAS ONLY***
- 4. BE WIND CONSCIOUS AT ALL TIMES***
- 5. CK WITH COG OPERATING LLC FOREMAN AT MAIN OFFICE***

COG OPERATING LLC

1-575-748-6940

EMERGENCY CALL LIST

	<u>OFFICE</u>	<u>MOBILE</u>
COG OPERATING LLC OFFICE	575-748-6940	
SETH WILD	432-683-7443	432-528-3633
WALTER ROYE	575-748-6940	432-934-1886

EMERGENCY RESPONSE NUMBERS

	<u>OFFICE</u>
STATE POLICE	575-748-9718
EDDY COUNTY SHERIFF	575-746-2701
EMERGENCY MEDICAL SERVICES (AMBULANCE)	911 or 575-746-2701
EDDY COUNTY EMERGENCY MANAGEMENT (HARRY BURGESS)	575-887-9511
STATE EMERGENCY RESPONSE CENTER (SERC)	575-476-9620
CARLSBAD POLICE DEPARTMENT	575-885-2111
CARLSBAD FIRE DEPARTMENT	575-885-3125
NEW MEXICO OIL CONSERVATION DIVISION	575-748-1283
INDIAN FIRE & SAFETY	800-530-8693
HALLIBURTON SERVICES	800-844-8451



COG Operating, LLC

Lea County, NM

Sec 9, T25-S, R35-E

Fez Federal Com #705H

Wellbore #1

Design #1

QES Anticollision Report

28 February, 2018



Company:	COG Operating, LLC	Local Co-ordinate Reference:	Well Fez Federal Com #705H
Project:	Lea County, NM	TVD Reference:	well @ 3291.0usft (Noram #21)
Reference Site:	Sec 9, T25-S, R35-E	MD Reference:	well @ 3291.0usft (Noram #21)
Site Error:	0.0 usft	North Reference:	Grid
Reference Well:	Fez Federal Com #705H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.0 usft	Output errors are at	2.00 sigma
Reference Wellbore	Wellbore #1	Database:	EDM 5000.1 Single User Db
Reference Design:	Design #1	Offset TVD Reference:	Offset Datum

Reference	Design #1
Filter type:	NO GLOBAL FILTER: Using user defined selection & filtering criteria
Interpolation Method:	Stations
Depth Range:	Unlimited
Results Limited by:	Maximum center-center distance of 5,000.0 usft
Warning Levels Evaluated at:	2.00 Sigma
Error Model:	ISCWSA
Scan Method:	Closest Approach 3D
Error Surface:	Pedal Curve

Survey Tool Program		Date 2/28/2018		
From (usft)	To (usft)	Survey (Wellbore)	Tool Name	Description
0.0	22,483.7	Design #1 (Wellbore #1)	MWD	OWSG MWD - Standard

Summary						
Site Name	Reference Measured Depth (usft)	Offset Measured Depth (usft)	Distance Between Centres (usft)	Distance Between Ellipses (usft)	Separation Factor	Warning
Offset Well - Wellbore - Design						
Sec 9, T25-S, R35-E						
Fez Federal Com #604H - Wellbore #1 - Design #1	1,000.0	1,001.0	30.0	23.3	4.475 CC, ES	
Fez Federal Com #704H - Wellbore #1 - Design #1	1,000.0	998.0	60.1	53.4	8.964 CC	
Fez Fee #11H - Wellbore #1 - Wellbore #1	16,924.5	9,612.1	3,276.6	3,217.7	55.710 CC, ES	
Fez Fee #11H - Wellbore #1 - Wellbore #1	18,100.0	9,609.9	3,481.0	3,414.0	51.894 SF	

Offset Design Sec 9, T25-S, R35-E - Fez Federal Com #604H - Wellbore #1 - Design #1												Offset Site Error:	0.0 usft
Survey Program: 0-MWD												Offset Well Error:	0.0 usft
Reference Measured Depth (usft)	Vertical Depth (usft)	Offset Measured Depth (usft)	Vertical Depth (usft)	Semi Major Axis Reference (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	Offset Wellbore Centre +E/-W (usft)	Distance Between Centres (usft)	Distance Between Ellipses (usft)	Separation Factor	Warning	
0.0	0.0	1.0	1.0	0.0	0.0	89.49	0.3	30.0	30.0				
100.0	100.0	101.0	101.0	0.1	0.1	89.49	0.3	30.0	30.0	29.8	116.340		
200.0	200.0	201.0	201.0	0.5	0.5	89.49	0.3	30.0	30.0	29.1	30.796		
300.0	300.0	301.0	301.0	0.8	0.8	89.49	0.3	30.0	30.0	28.3	17.747		
400.0	400.0	401.0	401.0	1.2	1.2	89.49	0.3	30.0	30.0	27.6	12.465		
500.0	500.0	501.0	501.0	1.6	1.6	89.49	0.3	30.0	30.0	26.9	9.606		
600.0	600.0	601.0	601.0	1.9	1.9	89.49	0.3	30.0	30.0	26.2	7.814		
700.0	700.0	701.0	701.0	2.3	2.3	89.49	0.3	30.0	30.0	25.5	6.585		
800.0	800.0	801.0	801.0	2.6	2.6	89.49	0.3	30.0	30.0	24.8	5.691		
900.0	900.0	901.0	901.0	3.0	3.0	89.49	0.3	30.0	30.0	24.0	5.010		
1,000.0	1,000.0	1,001.0	1,001.0	3.4	3.4	89.49	0.3	30.0	30.0	23.3	4.475	CC, ES	
1,100.0	1,100.0	1,101.0	1,101.0	3.7	3.7	-175.75	0.3	30.0	31.8	24.3	4.282		
1,200.0	1,199.9	1,200.9	1,200.9	4.0	4.1	-176.17	0.3	30.0	35.2	27.1	4.342		
1,300.0	1,299.9	1,300.9	1,300.9	4.4	4.4	-176.52	0.3	30.0	38.7	29.9	4.391		
1,400.0	1,399.8	1,400.8	1,400.8	4.7	4.8	-176.80	0.3	30.0	42.2	32.7	4.432		
1,500.0	1,499.7	1,500.7	1,500.7	5.1	5.1	-177.05	0.3	30.0	45.7	35.5	4.466		
1,600.0	1,599.7	1,600.7	1,600.7	5.4	5.5	-177.26	0.3	30.0	49.2	38.2	4.496		
1,700.0	1,699.6	1,700.6	1,700.6	5.8	5.9	-177.44	0.3	30.0	52.7	41.0	4.522		
1,800.0	1,799.6	1,800.6	1,800.6	6.2	6.2	-177.60	0.3	30.0	56.2	43.8	4.544		
1,900.0	1,899.5	1,900.5	1,900.5	6.5	6.6	-177.74	0.3	30.0	59.6	46.6	4.564		
2,000.6	2,000.0	2,001.0	2,001.0	6.9	6.9	-177.86	0.3	30.0	63.2	49.4	4.581		

CC - Min centre to center distance or covergent point, SF - min separation factor, ES - min ellipse separation

Company:	COG Operating, LLC	Local Co-ordinate Reference:	Well Fez Federal Com #705H
Project:	Lea County, NM	TVD Reference:	well @ 3291.0usft (Noram #21)
Reference Site:	Sec 9, T25-S, R35-E	MD Reference:	well @ 3291.0usft (Noram #21)
Site Error:	0.0 usft	North Reference:	Grid
Reference Well:	Fez Federal Com #705H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.0 usft	Output errors are at	2.00 sigma
Reference Wellbore	Wellbore #1	Database:	EDM 5000.1 Single User Db
Reference Design:	Design #1	Offset TVD Reference:	Offset Datum

Offset Design Sec 9, T25-S, R35-E - Fez Federal Com #604H - Wellbore #1 - Design #1												Offset Site Error:	0.0 usft
Survey Program: 0-MWD												Offset Well Error:	0.0 usft
Reference Measured Depth (usft)	Vertical Depth (usft)	Offset Measured Depth (usft)	Vertical Depth (usft)	Semi Major Axis Reference (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	Distance Between Centres (usft)	Between Ellipses (usft)	Separation Factor	Warning		
2,100.6	2,099.9	2,100.9	2,100.9	7.2	7.3	-178.02	0.3	30.0	68.4	53.9	4.717		
2,200.0	2,199.0	2,200.0	2,200.0	7.6	7.7	-178.21	0.3	30.0	75.3	60.1	4.953		
2,300.0	2,298.8	2,299.8	2,299.8	8.0	8.0	-178.36	0.3	30.0	82.3	66.4	5.169		
2,400.0	2,398.6	2,399.6	2,399.6	8.3	8.4	-178.49	0.3	30.0	89.3	72.6	5.367		
2,500.0	2,498.3	2,499.3	2,499.3	8.7	8.7	-178.60	0.3	30.0	96.2	78.9	5.548		
2,600.0	2,598.1	2,599.1	2,599.1	9.1	9.1	-178.69	0.3	30.0	103.2	85.1	5.715		
2,700.0	2,697.8	2,698.8	2,698.8	9.4	9.4	-178.77	0.3	30.0	110.2	91.4	5.869		
2,742.3	2,740.0	2,741.0	2,741.0	9.6	9.6	-178.81	0.3	30.0	113.1	94.1	5.930		
2,800.0	2,797.6	2,798.6	2,798.6	9.8	9.8	-178.84	0.3	30.0	116.6	97.1	5.982		
2,900.0	2,897.6	2,898.6	2,898.6	10.1	10.2	-178.87	0.3	30.0	119.8	99.6	5.930		
2,942.3	2,939.8	2,940.8	2,940.8	10.3	10.3	86.12	0.3	30.0	120.1	99.6	5.858		
3,000.0	2,997.6	2,998.6	2,998.6	10.5	10.5	86.12	0.3	30.0	120.1	99.2	5.744		
3,100.0	3,097.6	3,098.6	3,098.6	10.8	10.9	86.12	0.3	30.0	120.1	98.5	5.555		
3,200.0	3,197.6	3,198.6	3,198.6	11.2	11.2	86.12	0.3	30.0	120.1	97.8	5.379		
3,300.0	3,297.6	3,298.6	3,298.6	11.5	11.6	86.12	0.3	30.0	120.1	97.1	5.214		
3,400.0	3,397.6	3,398.6	3,398.6	11.9	12.0	86.12	0.3	30.0	120.1	96.4	5.058		
3,500.0	3,497.6	3,498.6	3,498.6	12.2	12.3	86.12	0.3	30.0	120.1	95.7	4.911		
3,600.0	3,597.6	3,598.6	3,598.6	12.6	12.7	86.12	0.3	30.0	120.1	94.9	4.772		
3,700.0	3,697.6	3,698.6	3,698.6	12.9	13.0	86.12	0.3	30.0	120.1	94.2	4.641		
3,800.0	3,797.6	3,798.6	3,798.6	13.3	13.4	86.12	0.3	30.0	120.1	93.5	4.517		
3,900.0	3,897.6	3,898.6	3,898.6	13.6	13.7	86.12	0.3	30.0	120.1	92.8	4.399		
4,000.0	3,997.6	3,998.6	3,998.6	14.0	14.1	86.12	0.3	30.0	120.1	92.1	4.288		
4,100.0	4,097.6	4,098.6	4,098.6	14.3	14.5	86.12	0.3	30.0	120.1	91.4	4.181		
4,200.0	4,197.6	4,198.6	4,198.6	14.7	14.8	86.12	0.3	30.0	120.1	90.7	4.080		
4,300.0	4,297.6	4,298.6	4,298.6	15.1	15.2	86.12	0.3	30.0	120.1	90.0	3.984		
4,400.0	4,397.6	4,398.6	4,398.6	15.4	15.5	86.12	0.3	30.0	120.1	89.2	3.892		
4,500.0	4,497.6	4,498.6	4,498.6	15.8	15.9	86.12	0.3	30.0	120.1	88.5	3.804		
4,600.0	4,597.6	4,598.6	4,598.6	16.1	16.3	86.12	0.3	30.0	120.1	87.8	3.720		
4,700.0	4,697.6	4,698.6	4,698.6	16.5	16.6	86.12	0.3	30.0	120.1	87.1	3.639		
4,800.0	4,797.6	4,798.6	4,798.6	16.8	17.0	86.12	0.3	30.0	120.1	86.4	3.562		
4,900.0	4,897.6	4,898.6	4,898.6	17.2	17.3	86.12	0.3	30.0	120.1	85.7	3.489		
5,000.0	4,997.6	4,998.6	4,998.6	17.5	17.7	86.12	0.3	30.0	120.1	85.0	3.418		
5,100.0	5,097.6	5,098.6	5,098.6	17.9	18.0	86.12	0.3	30.0	120.1	84.3	3.350		
5,200.0	5,197.6	5,198.6	5,198.6	18.2	18.4	86.12	0.3	30.0	120.1	83.5	3.284		
5,300.0	5,297.6	5,298.6	5,298.6	18.6	18.8	86.12	0.3	30.0	120.1	82.8	3.221		
5,400.0	5,397.6	5,398.6	5,398.6	18.9	19.1	86.12	0.3	30.0	120.1	82.1	3.161		
5,500.0	5,497.6	5,498.6	5,498.6	19.3	19.5	86.12	0.3	30.0	120.1	81.4	3.103		
5,600.0	5,597.6	5,598.6	5,598.6	19.7	19.8	86.12	0.3	30.0	120.1	80.7	3.046		
5,700.0	5,697.6	5,698.6	5,698.6	20.0	20.2	86.12	0.3	30.0	120.1	80.0	2.992		
5,800.0	5,797.6	5,798.6	5,798.6	20.4	20.6	86.12	0.3	30.0	120.1	79.3	2.940		
5,900.0	5,897.6	5,898.6	5,898.6	20.7	20.9	86.12	0.3	30.0	120.1	78.5	2.889		
6,000.0	5,997.6	5,998.6	5,998.6	21.1	21.3	86.12	0.3	30.0	120.1	77.8	2.840		
6,100.0	6,097.6	6,098.6	6,098.6	21.4	21.6	86.12	0.3	30.0	120.1	77.1	2.793		
6,200.0	6,197.6	6,198.6	6,198.6	21.8	22.0	86.12	0.3	30.0	120.1	76.4	2.748		
6,300.0	6,297.6	6,298.6	6,298.6	22.1	22.3	86.12	0.3	30.0	120.1	75.7	2.703		
6,400.0	6,397.6	6,398.6	6,398.6	22.5	22.7	86.12	0.3	30.0	120.1	75.0	2.661		
6,500.0	6,497.6	6,498.6	6,498.6	22.9	23.1	86.12	0.3	30.0	120.1	74.2	2.619		
6,600.0	6,597.6	6,598.6	6,598.6	23.2	23.4	86.12	0.3	30.0	120.1	73.5	2.579		
6,700.0	6,697.6	6,698.6	6,698.6	23.6	23.8	86.12	0.3	30.0	120.1	72.8	2.540		
6,800.0	6,797.6	6,798.6	6,798.6	23.9	24.1	86.12	0.3	30.0	120.1	72.1	2.502		
6,900.0	6,897.6	6,898.6	6,898.6	24.3	24.5	86.12	0.3	30.0	120.1	71.4	2.465		
7,000.0	6,997.6	6,998.6	6,998.6	24.6	24.9	86.12	0.3	30.0	120.1	70.7	2.430		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Anticollision Report



Company:	COG Operating, LLC	Local Co-ordinate Reference:	Well Fez Federal Com #705H
Project:	Lea County, NM	TVD Reference:	well @ 3291.0usft (Noram #21)
Reference Site:	Sec 9, T25-S, R35-E	MD Reference:	well @ 3291.0usft (Noram #21)
Site Error:	0.0 usft	North Reference:	Grid
Reference Well:	Fez Federal Com #705H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.0 usft	Output errors are at	2.00 sigma
Reference Wellbore	Wellbore #1	Database:	EDM 5000.1 Single User Db
Reference Design:	Design #1	Offset TVD Reference:	Offset Datum

Offset Design Sec 9, T25-S, R35-E - Fez Federal Com #604H - Wellbore #1 - Design #1												Offset Site Error:	0.0 usft
Survey Program: 0-MWD												Offset Well Error:	0.0 usft
Reference Measured Depth (usft)	Vertical Depth (usft)	Offset Measured Depth (usft)	Vertical Depth (usft)	Semi Major Axis Reference (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	+E/-W (usft)	Distance Between Centres (usft)	Between Ellipses (usft)	Separation Factor	Warning	
7,100.0	7,097.6	7,098.6	7,098.6	25.0	25.2	86.12	0.3	30.0	120.1	70.0	2.395		
7,200.0	7,197.6	7,198.6	7,198.6	25.4	25.6	86.12	0.3	30.0	120.1	69.2	2.361		
7,300.0	7,297.6	7,298.6	7,298.6	25.7	25.9	86.12	0.3	30.0	120.1	68.5	2.329		
7,400.0	7,397.6	7,398.6	7,398.6	26.1	26.3	86.12	0.3	30.0	120.1	67.8	2.297		
7,500.0	7,497.6	7,498.6	7,498.6	26.4	26.6	86.12	0.3	30.0	120.1	67.1	2.266		
7,600.0	7,597.6	7,598.6	7,598.6	26.8	27.0	86.12	0.3	30.0	120.1	66.4	2.235		
7,700.0	7,697.6	7,698.6	7,698.6	27.1	27.4	86.12	0.3	30.0	120.1	65.7	2.206		
7,800.0	7,797.6	7,798.6	7,798.6	27.5	27.7	86.12	0.3	30.0	120.1	64.9	2.177		
7,900.0	7,897.6	7,898.6	7,898.6	27.9	28.1	86.12	0.3	30.0	120.1	64.2	2.150		
8,000.0	7,997.6	7,998.6	7,998.6	28.2	28.4	86.12	0.3	30.0	120.1	63.5	2.122		
8,100.0	8,097.6	8,098.6	8,098.6	28.6	28.8	86.12	0.3	30.0	120.1	62.8	2.096		
8,200.0	8,197.6	8,198.6	8,198.6	28.9	29.2	86.12	0.3	30.0	120.1	62.1	2.070		
8,300.0	8,297.6	8,298.6	8,298.6	29.3	29.5	86.12	0.3	30.0	120.1	61.4	2.045		
8,400.0	8,397.6	8,398.6	8,398.6	29.6	29.9	86.12	0.3	30.0	120.1	60.7	2.020		
8,500.0	8,497.6	8,498.6	8,498.6	30.0	30.2	86.12	0.3	30.0	120.1	59.9	1.996		
8,600.0	8,597.6	8,598.6	8,598.6	30.4	30.6	86.12	0.3	30.0	120.1	59.2	1.973		
8,700.0	8,697.6	8,698.6	8,698.6	30.7	31.0	86.12	0.3	30.0	120.1	58.5	1.950		
8,800.0	8,797.6	8,798.6	8,798.6	31.1	31.3	86.12	0.3	30.0	120.1	57.8	1.927		
8,900.0	8,897.6	8,898.6	8,898.6	31.4	31.7	86.12	0.3	30.0	120.1	57.1	1.905		
9,000.0	8,997.6	8,998.6	8,998.6	31.8	32.0	86.12	0.3	30.0	120.1	56.4	1.884		
9,100.0	9,097.6	9,098.6	9,098.6	32.1	32.4	86.12	0.3	30.0	120.1	55.6	1.863		
9,200.0	9,197.6	9,198.6	9,198.6	32.5	32.7	86.12	0.3	30.0	120.1	54.9	1.843		
9,300.0	9,297.6	9,298.6	9,298.6	32.9	33.1	86.12	0.3	30.0	120.1	54.2	1.823		
9,400.0	9,397.6	9,398.6	9,398.6	33.2	33.5	86.12	0.3	30.0	120.1	53.5	1.803		
9,500.0	9,497.6	9,498.6	9,498.6	33.6	33.8	86.12	0.3	30.0	120.1	52.8	1.784		
9,600.0	9,597.6	9,598.6	9,598.6	33.9	34.2	86.12	0.3	30.0	120.1	52.1	1.765		
9,700.0	9,697.6	9,698.6	9,698.6	34.3	34.5	86.12	0.3	30.0	120.1	51.3	1.747		
9,800.0	9,797.6	9,798.6	9,798.6	34.6	34.9	86.12	0.3	30.0	120.1	50.6	1.729		
9,900.0	9,897.6	9,898.6	9,898.6	35.0	35.3	86.12	0.3	30.0	120.1	49.9	1.711		
10,000.0	9,997.6	9,998.6	9,998.6	35.4	35.6	86.12	0.3	30.0	120.1	49.2	1.694		
10,100.0	10,097.6	10,098.6	10,098.6	35.7	36.0	86.12	0.3	30.0	120.1	48.5	1.677		
10,200.0	10,197.6	10,198.6	10,198.6	36.1	36.3	86.12	0.3	30.0	120.1	47.8	1.660		
10,300.0	10,297.6	10,298.6	10,298.6	36.4	36.7	86.12	0.3	30.0	120.1	47.0	1.644		
10,400.0	10,397.6	10,398.6	10,398.6	36.8	37.0	86.12	0.3	30.0	120.1	46.3	1.628		
10,500.0	10,497.6	10,498.6	10,498.6	37.1	37.4	86.12	0.3	30.0	120.1	45.6	1.612		
10,600.0	10,597.6	10,598.6	10,598.6	37.5	37.8	86.12	0.3	30.0	120.1	44.9	1.597		
10,700.0	10,697.6	10,698.6	10,698.6	37.9	38.1	86.12	0.3	30.0	120.1	44.2	1.582		
10,800.0	10,797.6	10,798.6	10,798.6	38.2	38.5	86.12	0.3	30.0	120.1	43.5	1.567		
10,900.0	10,897.6	10,898.6	10,898.6	38.6	38.8	86.12	0.3	30.0	120.1	42.8	1.553		
11,000.0	10,997.6	10,998.6	10,998.6	38.9	39.2	86.12	0.3	30.0	120.1	42.0	1.538		
11,100.0	11,097.6	11,098.6	11,098.6	39.3	39.6	86.12	0.3	30.0	120.1	41.3	1.524		
11,200.0	11,197.6	11,198.6	11,198.6	39.6	39.9	86.12	0.3	30.0	120.1	40.6	1.511		
11,300.0	11,297.6	11,298.6	11,298.6	40.0	40.3	86.12	0.3	30.0	120.1	39.9	1.497	Level 3	
11,400.0	11,397.6	11,398.6	11,398.6	40.4	40.6	86.12	0.3	30.0	120.1	39.2	1.484	Level 3	
11,500.0	11,497.6	11,498.6	11,498.6	40.7	41.0	86.12	0.3	30.0	120.1	38.5	1.471	Level 3	
11,600.0	11,597.6	11,598.6	11,598.6	41.1	41.3	86.12	0.3	30.0	120.1	37.7	1.458	Level 3	
11,700.0	11,697.6	11,698.6	11,698.6	41.4	41.7	86.12	0.3	30.0	120.1	37.0	1.446	Level 3	
11,800.0	11,797.6	11,798.6	11,798.6	41.8	42.1	86.12	0.3	30.0	120.1	36.3	1.433	Level 3	
11,900.0	11,807.6	11,808.6	11,808.6	41.8	42.1	86.12	0.3	30.0	120.1	36.2	1.432	Level 3	
11,900.0	11,897.6	11,897.5	11,897.4	42.1	42.4	84.74	3.2	30.0	120.3	35.8	1.424	Level 3	
12,000.0	11,997.6	11,991.5	11,989.2	42.5	42.7	75.71	22.6	29.9	123.8	38.8	1.457	Level 3	
12,100.9	12,098.5	12,075.0	12,066.2	42.9	43.0	62.35	54.7	29.6	138.9	54.7	1.649		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

Company:	COG Operating, LLC	Local Co-ordinate Reference:	Well Fez Federal Com #705H
Project:	Lea County, NM	TVD Reference:	well @ 3291.0usft (Noram #21)
Reference Site:	Sec 9, T25-S, R35-E	MD Reference:	well @ 3291.0usft (Noram #21)
Site Error:	0.0 usft	North Reference:	Grid
Reference Well:	Fez Federal Com #705H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.0 usft	Output errors are at	2.00 sigma
Reference Wellbore	Wellbore #1	Database:	EDM 5000.1 Single User Db
Reference Design:	Design #1	Offset TVD Reference:	Offset Datum

Offset Design Sec 9, T25-S, R35-E - Fez Federal Com #604H - Wellbore #1 - Design #1												Offset Site Error:	0.0 usft
Survey Program: 0-MWD												Offset Well Error:	0.0 usft
Reference Measured Depth (usft)	Vertical Depth (usft)	Offset Measured Depth (usft)	Vertical Depth (usft)	Semi Major Axis Reference (usft)	Offset (usft)	Highside Tooface (")	Offset Wellbore Centre +N/-S (usft)	+E/-W (usft)	Distance Between Centres (usft)	Between Ellipses (usft)	Separation Factor	Warning	
12,125.0	12,122.6	12,094.3	12,083.1	43.0	43.1	58.92	64.0	29.5	144.8	61.0	1.728		
12,150.0	12,147.5	12,113.2	12,099.2	43.0	43.1	55.37	73.7	29.5	151.4	68.2	1.820		
12,175.0	12,172.3	12,131.8	12,114.8	43.1	43.2	52.14	84.0	29.4	158.3	75.8	1.920		
12,200.0	12,196.9	12,150.0	12,129.6	43.2	43.2	49.23	94.5	29.3	165.4	83.8	2.027		
12,225.0	12,221.2	12,168.5	12,144.2	43.3	43.3	46.55	105.8	29.2	172.7	91.9	2.137		
12,250.0	12,245.2	12,186.5	12,158.1	43.4	43.4	44.16	117.4	29.1	180.0	100.1	2.253		
12,275.0	12,268.7	12,204.4	12,171.3	43.5	43.4	42.00	129.4	29.1	187.3	108.4	2.373		
12,300.0	12,291.8	12,225.0	12,186.1	43.6	43.5	39.84	143.8	29.0	194.6	116.3	2.485		
12,325.0	12,314.4	12,239.6	12,196.1	43.6	43.5	38.29	154.4	28.9	201.6	124.7	2.621		
12,350.0	12,336.4	12,257.0	12,207.7	43.7	43.6	36.71	167.5	28.8	208.6	132.7	2.748		
12,375.0	12,357.8	12,275.0	12,219.1	43.8	43.6	35.24	181.3	28.7	215.3	140.4	2.872		
12,400.0	12,378.4	12,291.5	12,229.1	43.8	43.7	33.99	194.4	28.6	221.9	148.0	3.004		
12,425.0	12,398.2	12,308.6	12,239.0	43.9	43.7	32.83	208.4	28.5	228.1	155.3	3.132		
12,450.0	12,417.3	12,325.0	12,248.0	44.0	43.8	31.80	222.1	28.4	234.1	162.3	3.261		
12,475.0	12,435.5	12,342.4	12,257.1	44.0	43.8	30.84	237.0	28.3	239.8	169.0	3.384		
12,500.0	12,452.7	12,359.2	12,265.3	44.1	43.8	30.00	251.6	28.1	245.2	175.3	3.508		
12,525.0	12,469.0	12,375.0	12,272.5	44.2	43.9	29.26	265.6	28.0	250.3	181.4	3.633		
12,550.0	12,484.2	12,392.6	12,280.1	44.3	43.9	28.56	281.5	27.9	255.0	186.9	3.744		
12,575.0	12,498.4	12,409.2	12,286.6	44.3	44.0	27.96	296.8	27.8	259.3	192.1	3.856		
12,600.0	12,511.5	12,425.0	12,292.4	44.4	44.0	27.44	311.5	27.7	263.3	196.9	3.965		
12,625.0	12,523.5	12,442.3	12,298.1	44.5	44.1	26.96	327.8	27.6	266.9	201.2	4.061		
12,650.0	12,534.3	12,458.7	12,303.0	44.5	44.1	26.56	343.5	27.5	270.1	205.1	4.153		
12,675.0	12,543.9	12,475.0	12,307.3	44.6	44.2	26.21	359.2	27.3	273.0	208.5	4.236		
12,700.0	12,552.3	12,491.5	12,311.1	44.7	44.2	25.92	375.3	27.2	275.4	211.5	4.310		
12,725.0	12,559.5	12,507.9	12,314.4	44.7	44.2	25.68	391.3	27.1	277.5	214.0	4.373		
12,750.0	12,565.3	12,525.0	12,317.1	44.8	44.3	25.48	408.2	27.0	279.1	216.0	4.423		
12,775.0	12,569.9	12,540.5	12,319.2	44.9	44.3	25.34	423.6	26.9	280.3	217.6	4.465		
12,800.0	12,573.3	12,556.8	12,320.7	44.9	44.4	25.25	439.8	26.7	281.2	218.6	4.493		
12,825.0	12,575.3	12,575.0	12,321.8	45.0	44.4	25.20	458.0	26.6	281.6	219.1	4.506		
12,852.4	12,576.0	12,591.0	12,322.2	45.1	44.5	25.21	474.0	26.5	281.6	219.1	4.508		
12,860.5	12,575.9	12,596.3	12,322.2	45.1	44.5	25.21	479.2	26.4	281.5	219.0	4.507		
12,900.0	12,575.8	12,635.8	12,322.1	45.2	44.6	25.21	518.8	26.1	281.5	218.9	4.499		
13,000.0	12,575.5	12,735.8	12,321.8	45.5	44.9	25.21	618.7	25.4	281.5	218.6	4.477		
13,100.0	12,575.2	12,835.8	12,321.5	45.9	45.3	25.21	718.7	24.6	281.5	218.3	4.451		
13,200.0	12,574.9	12,935.8	12,321.2	46.3	45.7	25.21	818.7	23.9	281.5	217.8	4.421		
13,300.0	12,574.6	13,035.8	12,320.9	46.8	46.2	25.21	918.7	23.2	281.5	217.3	4.387		
13,400.0	12,574.3	13,135.8	12,320.5	47.3	46.7	25.21	1,018.7	22.4	281.5	216.8	4.350		
13,500.0	12,573.9	13,235.8	12,320.2	47.9	47.3	25.21	1,118.7	21.7	281.5	216.2	4.309		
13,600.0	12,573.6	13,335.8	12,319.9	48.6	48.0	25.21	1,218.7	20.9	281.5	215.5	4.266		
13,700.0	12,573.3	13,435.8	12,319.6	49.2	48.6	25.21	1,318.7	20.2	281.5	214.8	4.221		
13,800.0	12,573.0	13,535.8	12,319.3	50.0	49.4	25.21	1,418.7	19.4	281.5	214.1	4.173		
13,900.0	12,572.7	13,635.8	12,319.0	50.7	50.2	25.21	1,518.7	18.7	281.5	213.3	4.123		
14,000.0	12,572.4	13,735.8	12,318.7	51.6	51.0	25.21	1,618.7	17.9	281.5	212.4	4.071		
14,100.0	12,572.1	13,835.8	12,318.3	52.4	51.8	25.21	1,718.7	17.2	281.6	211.5	4.018		
14,200.0	12,571.8	13,935.8	12,318.0	53.3	52.7	25.21	1,818.7	16.4	281.6	210.5	3.964		
14,300.0	12,571.5	14,035.8	12,317.7	54.2	53.7	25.21	1,918.7	15.7	281.6	209.5	3.910		
14,400.0	12,571.1	14,135.8	12,317.4	55.2	54.6	25.21	2,018.7	14.9	281.6	208.5	3.854		
14,500.0	12,570.8	14,235.8	12,317.1	56.2	55.6	25.21	2,118.7	14.2	281.6	207.4	3.798		
14,600.0	12,570.5	14,335.8	12,316.8	57.2	56.6	25.21	2,218.7	13.4	281.6	206.3	3.742		
14,700.0	12,570.2	14,435.8	12,316.5	58.3	57.7	25.21	2,318.7	12.7	281.6	205.2	3.685		
14,800.0	12,569.9	14,535.8	12,316.1	59.3	58.8	25.21	2,418.7	11.9	281.6	204.0	3.629		
14,900.0	12,569.6	14,635.8	12,315.8	60.4	59.9	25.21	2,518.7	11.2	281.6	202.8	3.573		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

Company:	COG Operating, LLC	Local Co-ordinate Reference:	Well Fez Federal Com #705H
Project:	Lea County, NM	TVD Reference:	well @ 3291.0usft (Noram #21)
Reference Site:	Sec 9, T25-S, R35-E	MD Reference:	well @ 3291.0usft (Noram #21)
Site Error:	0.0 usft	North Reference:	Grid
Reference Well:	Fez Federal Com #705H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.0 usft	Output errors are at	2.00 sigma
Reference Wellbore:	Wellbore #1	Database:	EDM 5000.1 Single User Db
Reference Design:	Design #1	Offset TVD Reference:	Offset Datum

Offset Design Sec 9, T25-S, R35-E - Fez Federal Com #604H - Wellbore #1 - Design #1												Offset Site Error:	0.0 usft
Survey Program: 0-MWD												Offset Well Error:	0.0 usft
Reference Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Semi Major Axis Reference (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	+E/-W (usft)	Distance Between Centres (usft)	Between Ellipses (usft)	Separation Factor	Warning	
15,000.0	12,569.3	14,735.8	12,315.5	61.6	61.0	25.21	2,618.7	10.4	281.6	201.5	3.517		
15,100.0	12,569.0	14,835.8	12,315.2	62.7	62.2	25.21	2,718.7	9.7	281.6	200.2	3.462		
15,200.0	12,568.7	14,935.8	12,314.9	63.9	63.4	25.21	2,818.7	8.9	281.6	198.9	3.407		
15,300.0	12,568.3	15,035.8	12,314.6	65.1	64.6	25.21	2,918.7	8.2	281.6	197.6	3.353		
15,400.0	12,568.0	15,135.8	12,314.3	66.3	65.8	25.21	3,018.7	7.4	281.6	196.2	3.299		
15,500.0	12,567.7	15,235.8	12,313.9	67.5	67.0	25.21	3,118.7	6.7	281.6	194.9	3.246		
15,600.0	12,567.4	15,335.8	12,313.6	68.8	68.3	25.21	3,218.7	5.9	281.6	193.4	3.194		
15,700.0	12,567.1	15,435.8	12,313.3	70.1	69.6	25.21	3,318.7	5.2	281.6	192.0	3.143		
15,800.0	12,566.8	15,535.8	12,313.0	71.3	70.8	25.21	3,418.7	4.4	281.6	190.6	3.093		
15,900.0	12,566.5	15,635.8	12,312.7	72.6	72.1	25.21	3,518.7	3.7	281.6	189.1	3.044		
16,000.0	12,566.2	15,735.8	12,312.4	73.9	73.5	25.21	3,618.7	2.9	281.6	187.6	2.996		
16,100.0	12,565.9	15,835.8	12,312.1	75.3	74.8	25.21	3,718.6	2.2	281.6	186.1	2.948		
16,200.0	12,565.5	15,935.8	12,311.7	76.6	76.1	25.21	3,818.6	1.4	281.6	184.6	2.902		
16,300.0	12,565.2	16,035.8	12,311.4	78.0	77.5	25.21	3,918.6	0.7	281.6	183.0	2.856		
16,400.0	12,564.9	16,135.8	12,311.1	79.3	78.9	25.21	4,018.6	0.0	281.6	181.5	2.812		
16,500.0	12,564.6	16,235.8	12,310.8	80.7	80.2	25.21	4,118.6	-0.8	281.6	179.9	2.768		
16,600.0	12,564.3	16,335.8	12,310.5	82.1	81.6	25.21	4,218.6	-1.5	281.6	178.3	2.725		
16,700.0	12,564.0	16,435.8	12,310.2	83.5	83.0	25.21	4,318.6	-2.3	281.6	176.7	2.684		
16,800.0	12,563.7	16,535.8	12,309.9	84.9	84.4	25.21	4,418.6	-3.0	281.6	175.1	2.643		
16,900.0	12,563.4	16,635.8	12,309.5	86.3	85.8	25.21	4,518.6	-3.8	281.6	173.4	2.603		
17,000.0	12,563.1	16,735.8	12,309.2	87.7	87.3	25.21	4,618.6	-4.5	281.6	171.8	2.564		
17,100.0	12,562.7	16,835.8	12,308.9	89.1	88.7	25.21	4,718.6	-5.3	281.6	170.1	2.526		
17,200.0	12,562.4	16,935.8	12,308.6	90.6	90.1	25.21	4,818.6	-6.0	281.7	168.5	2.489		
17,300.0	12,562.1	17,035.8	12,308.3	92.0	91.6	25.21	4,918.6	-6.8	281.7	166.8	2.452		
17,400.0	12,561.8	17,135.8	12,308.0	93.5	93.0	25.21	5,018.6	-7.5	281.7	165.1	2.417		
17,500.0	12,561.5	17,235.8	12,307.7	94.9	94.5	25.20	5,118.6	-8.3	281.7	163.4	2.382		
17,600.0	12,561.2	17,335.8	12,307.3	96.4	96.0	25.20	5,218.6	-9.0	281.7	161.7	2.348		
17,700.0	12,560.9	17,435.8	12,307.0	97.8	97.4	25.20	5,318.6	-9.8	281.7	160.0	2.315		
17,800.0	12,560.6	17,535.8	12,306.7	99.3	98.9	25.20	5,418.6	-10.5	281.7	158.3	2.283		
17,900.0	12,560.3	17,635.8	12,306.4	100.8	100.4	25.20	5,518.6	-11.3	281.7	156.6	2.251		
18,000.0	12,559.9	17,735.8	12,306.1	102.3	101.9	25.20	5,618.6	-12.0	281.7	154.8	2.220		
18,100.0	12,559.6	17,835.8	12,305.8	103.8	103.4	25.20	5,718.6	-12.8	281.7	153.1	2.190		
18,200.0	12,559.3	17,935.8	12,305.5	105.3	104.9	25.20	5,818.6	-13.5	281.7	151.3	2.161		
18,300.0	12,559.0	18,035.8	12,305.1	106.8	106.4	25.20	5,918.6	-14.3	281.7	149.6	2.132		
18,400.0	12,558.7	18,135.8	12,304.8	108.3	107.9	25.20	6,018.6	-15.0	281.7	147.8	2.104		
18,500.0	12,558.4	18,235.8	12,304.5	109.8	109.4	25.20	6,118.6	-15.8	281.7	146.0	2.076		
18,600.0	12,558.1	18,335.8	12,304.2	111.3	110.9	25.20	6,218.6	-16.5	281.7	144.2	2.049		
18,700.0	12,557.8	18,435.8	12,303.9	112.8	112.4	25.20	6,318.6	-17.3	281.7	142.5	2.023		
18,800.0	12,557.5	18,535.8	12,303.6	114.3	113.9	25.20	6,418.6	-18.0	281.7	140.7	1.997		
18,900.0	12,557.1	18,635.8	12,303.3	115.8	115.5	25.20	6,518.6	-18.8	281.7	138.9	1.972		
19,000.0	12,556.8	18,735.8	12,302.9	117.4	117.0	25.20	6,618.6	-19.5	281.7	137.1	1.948		
19,100.0	12,556.5	18,835.8	12,302.6	118.9	118.5	25.20	6,718.5	-20.3	281.7	135.3	1.924		
19,200.0	12,556.2	18,935.8	12,302.3	120.4	120.1	25.20	6,818.5	-21.0	281.7	133.5	1.900		
19,300.0	12,555.9	19,035.8	12,302.0	122.0	121.6	25.20	6,918.5	-21.7	281.7	131.6	1.877		
19,400.0	12,555.6	19,135.8	12,301.7	123.5	123.1	25.20	7,018.5	-22.5	281.7	129.8	1.855		
19,500.0	12,555.3	19,235.8	12,301.4	125.1	124.7	25.20	7,118.5	-23.2	281.7	128.0	1.833		
19,600.0	12,555.0	19,335.8	12,301.1	126.6	126.2	25.20	7,218.5	-24.0	281.7	126.2	1.811		
19,700.0	12,554.7	19,435.8	12,300.7	128.1	127.8	25.20	7,318.5	-24.7	281.7	124.3	1.790		
19,800.0	12,554.3	19,535.8	12,300.4	129.7	129.3	25.20	7,418.5	-25.5	281.7	122.5	1.769		
19,900.0	12,554.0	19,635.8	12,300.1	131.2	130.9	25.20	7,518.5	-26.2	281.7	120.6	1.749		
20,000.0	12,553.7	19,735.8	12,299.8	132.8	132.5	25.20	7,618.5	-27.0	281.7	118.8	1.729		
20,100.0	12,553.4	19,835.8	12,299.5	134.4	134.0	25.20	7,718.5	-27.7	281.7	117.0	1.710		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

Company:	COG Operating, LLC	Local Co-ordinate Reference:	Well Fez Federal Com #705H
Project:	Lea County, NM	TVD Reference:	well @ 3291.0usft (Noram #21)
Reference Site:	Sec 9, T25-S, R35-E	MD Reference:	well @ 3291.0usft (Noram #21)
Site Error:	0.0 usft	North Reference:	Grid
Reference Well:	Fez Federal Com #705H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.0 usft	Output errors are at	2.00 sigma
Reference Wellbore	Wellbore #1	Database:	EDM 5000.1 Single User Db
Reference Design:	Design #1	Offset TVD Reference:	Offset Datum

Offset Design: Sec 9, T25-S, R35-E - Fez Federal Com #604H - Wellbore #1 - Design #1												Offset Site Error:	0.0 usft
Survey Program: 0-MWD												Offset Well Error:	0.0 usft
Reference Measured Depth (usft)	Vertical Depth (usft)	Offset Measured Depth (usft)	Vertical Depth (usft)	Semi Major Axis Reference (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	+E/-W (usft)	Distance Between Centres (usft)	Distance Between Ellipses (usft)	Separation Factor	Warning	
20,200.0	12,553.1	19,935.8	12,299.2	135.9	135.6	25.20	7,818.5	-28.5	281.8	115.1	1.691		
20,300.0	12,552.8	20,035.8	12,298.9	137.5	137.1	25.20	7,918.5	-29.2	281.8	113.3	1.672		
20,400.0	12,552.5	20,135.8	12,298.5	139.0	138.7	25.20	8,018.5	-30.0	281.8	111.4	1.654		
20,500.0	12,552.2	20,235.8	12,298.2	140.6	140.3	25.20	8,118.5	-30.7	281.8	109.5	1.636		
20,600.0	12,551.9	20,335.8	12,297.9	142.2	141.8	25.20	8,218.5	-31.5	281.8	107.7	1.618		
20,700.0	12,551.5	20,435.8	12,297.6	143.7	143.4	25.20	8,318.5	-32.2	281.8	105.8	1.601		
20,800.0	12,551.2	20,535.8	12,297.3	145.3	145.0	25.20	8,418.5	-33.0	281.8	103.9	1.584		
20,900.0	12,550.9	20,635.8	12,297.0	146.9	146.6	25.20	8,518.5	-33.7	281.8	102.1	1.568		
21,000.0	12,550.6	20,735.8	12,296.7	148.5	148.1	25.20	8,618.5	-34.5	281.8	100.2	1.552		
21,100.0	12,550.3	20,835.8	12,296.4	150.0	149.7	25.20	8,718.5	-35.2	281.8	98.3	1.536		
21,200.0	12,550.0	20,935.8	12,296.0	151.6	151.3	25.20	8,818.5	-36.0	281.8	96.4	1.520		
21,300.0	12,549.7	21,035.8	12,295.7	153.2	152.9	25.20	8,918.5	-36.7	281.8	94.5	1.505		
21,400.0	12,549.4	21,135.8	12,295.4	154.8	154.5	25.20	9,018.5	-37.5	281.8	92.7	1.490	Level 3	
21,500.0	12,549.1	21,235.8	12,295.1	156.4	156.0	25.20	9,118.5	-38.2	281.8	90.8	1.475	Level 3	
21,600.0	12,548.7	21,335.8	12,294.8	157.9	157.6	25.20	9,218.5	-39.0	281.8	88.9	1.461	Level 3	
21,700.0	12,548.4	21,435.8	12,294.5	159.5	159.2	25.20	9,318.5	-39.7	281.8	87.0	1.447	Level 3	
21,800.0	12,548.1	21,535.8	12,294.2	161.1	160.8	25.20	9,418.5	-40.5	281.8	85.1	1.433	Level 3	
21,900.0	12,547.8	21,635.8	12,293.8	162.7	162.4	25.20	9,518.5	-41.2	281.8	83.2	1.419	Level 3	
22,000.0	12,547.5	21,735.8	12,293.5	164.3	164.0	25.20	9,618.5	-42.0	281.8	81.3	1.405	Level 3	
22,100.0	12,547.2	21,835.8	12,293.2	165.9	165.6	25.20	9,718.5	-42.7	281.8	79.4	1.392	Level 3	
22,200.0	12,546.9	21,935.8	12,292.9	167.5	167.2	25.20	9,818.4	-43.5	281.8	77.5	1.379	Level 3	
22,300.0	12,546.6	22,035.8	12,292.6	169.1	168.8	25.20	9,918.4	-44.2	281.8	75.6	1.367	Level 3	
22,400.0	12,546.3	22,135.8	12,292.3	170.7	170.4	25.20	10,018.4	-44.9	281.8	73.7	1.354	Level 3	
22,483.7	12,546.0	22,219.5	12,292.0	172.0	171.7	25.20	10,102.2	-45.6	281.8	72.1	1.344	Level 3, SF	

Company:	COG Operating, LLC	Local Co-ordinate Reference:	Well Fez Federal Com #705H
Project:	Lea County, NM	TVD Reference:	well @ 3291.0usft (Noram #21)
Reference Site:	Sec 9, T25-S, R35-E	MD Reference:	well @ 3291.0usft (Noram #21)
Site Error:	0.0 usft	North Reference:	Grid
Reference Well:	Fez Federal Com #705H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.0 usft	Output errors are at	2.00 sigma
Reference Wellbore	Wellbore #1	Database:	EDM 5000.1 Single User Db
Reference Design:	Design #1	Offset TVD Reference:	Offset Datum

Offset Design Sec 9, T25-S, R35-E - Fez Federal Com #704H - Wellbore #1 - Design #1													Offset Site Error:	0.0 usft
Survey Program: O-MWD													Offset Well Error:	0.0 usft
Reference Measured Depth (usft)	Vertical Depth (usft)	Offset Measured Depth (usft)	Vertical Depth (usft)	Semi Major Reference (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	Offset Wellbore Centre +E/-W (usft)	Distance Between Centres (usft)	Distance Between Ellipses (usft)	Separation Factor	Warning		
0.0	0.0	0.0	0.0	0.0	0.0	89.49	0.5	60.1	60.1					
100.0	100.0	98.0	98.0	0.1	0.1	89.49	0.5	60.1	60.1	59.8	238.340			
200.0	200.0	198.0	198.0	0.5	0.5	89.49	0.5	60.1	60.1	59.1	62.279			
300.0	300.0	298.0	298.0	0.8	0.8	89.49	0.5	60.1	60.1	58.4	35.721			
400.0	400.0	398.0	398.0	1.2	1.2	89.49	0.5	60.1	60.1	57.7	25.042			
500.0	500.0	498.0	498.0	1.6	1.6	89.49	0.5	60.1	60.1	56.9	19.278			
600.0	600.0	598.0	598.0	1.9	1.9	89.49	0.5	60.1	60.1	56.2	15.672			
700.0	700.0	698.0	698.0	2.3	2.3	89.49	0.5	60.1	60.1	55.5	13.202			
800.0	800.0	798.0	798.0	2.6	2.6	89.49	0.5	60.1	60.1	54.8	11.404			
900.0	900.0	898.0	898.0	3.0	3.0	89.49	0.5	60.1	60.1	54.1	10.038			
1,000.0	1,000.0	998.0	998.0	3.4	3.3	89.49	0.5	60.1	60.1	53.4	8.964 CC			
1,100.0	1,100.0	1,098.0	1,098.0	3.7	3.7	-175.63	0.5	60.1	61.8	54.4	8.342			
1,200.0	1,199.9	1,197.9	1,197.9	4.0	4.1	-175.87	0.5	60.1	65.3	57.2	8.051			
1,300.0	1,299.9	1,297.9	1,297.9	4.4	4.4	-176.07	0.5	60.1	68.8	59.9	7.804			
1,400.0	1,399.8	1,397.8	1,397.8	4.7	4.8	-176.26	0.5	60.1	72.2	62.7	7.592			
1,500.0	1,499.7	1,497.7	1,497.7	5.1	5.1	-176.44	0.5	60.1	75.7	65.5	7.408			
1,600.0	1,599.7	1,597.7	1,597.7	5.4	5.5	-176.59	0.5	60.1	79.2	68.3	7.247			
1,700.0	1,699.6	1,697.6	1,697.6	5.8	5.9	-176.74	0.5	60.1	82.7	71.1	7.105			
1,800.0	1,799.6	1,797.6	1,797.6	6.2	6.2	-176.87	0.5	60.1	86.2	73.8	6.978			
1,900.0	1,899.5	1,897.5	1,897.5	6.5	6.6	-176.99	0.5	60.1	89.7	76.6	6.865			
2,000.6	2,000.0	1,998.0	1,998.0	6.9	6.9	-177.10	0.5	60.1	93.2	79.4	6.763			
2,100.6	2,099.9	2,097.9	2,097.9	7.2	7.3	-177.25	0.5	60.1	98.4	83.9	6.791			
2,200.0	2,199.0	2,197.0	2,197.0	7.6	7.6	-177.43	0.5	60.1	105.3	90.1	6.931			
2,300.0	2,298.8	2,296.8	2,296.8	8.0	8.0	-177.59	0.5	60.1	112.3	96.4	7.058			
2,400.0	2,398.6	2,396.6	2,396.6	8.3	8.4	-177.73	0.5	60.1	119.3	102.6	7.175			
2,500.0	2,498.3	2,496.3	2,496.3	8.7	8.7	-177.86	0.5	60.1	126.2	108.9	7.282			
2,600.0	2,598.1	2,596.1	2,596.1	9.1	9.1	-177.97	0.5	60.1	133.2	115.2	7.380			
2,700.0	2,697.8	2,695.8	2,695.8	9.4	9.4	-178.07	0.5	60.1	140.2	121.4	7.470			
2,742.3	2,740.0	2,736.3	2,736.3	9.6	9.6	-178.08	0.5	60.3	143.3	124.3	7.524			
2,800.0	2,797.6	2,791.2	2,791.1	9.8	9.8	-177.98	0.2	61.5	148.0	128.6	7.615			
2,900.0	2,897.6	2,886.0	2,885.9	10.1	10.1	-177.50	-1.0	65.9	155.8	135.7	7.761			
2,942.3	2,939.8	2,927.5	2,927.2	10.3	10.2	87.80	-1.8	68.6	158.9	138.6	7.805			
3,000.0	2,997.6	2,985.1	2,984.7	10.5	10.4	88.22	-2.8	72.5	162.8	142.0	7.842			
3,100.0	3,097.6	3,084.8	3,084.2	10.8	10.8	88.90	-4.6	79.2	169.5	148.0	7.903			
3,200.0	3,197.6	3,184.6	3,183.7	11.2	11.1	89.53	-6.4	86.0	176.2	154.0	7.960			
3,300.0	3,297.6	3,284.3	3,283.2	11.5	11.5	90.11	-8.2	92.7	182.9	160.1	8.014			
3,400.0	3,397.6	3,384.1	3,382.7	11.9	11.8	90.65	-10.0	99.4	189.7	166.1	8.065			
3,500.0	3,497.6	3,478.5	3,476.9	12.2	12.1	91.19	-12.0	106.8	197.6	173.4	8.182			
3,600.0	3,597.6	3,576.3	3,574.1	12.6	12.5	91.84	-14.5	116.7	207.8	183.0	8.373			
3,700.0	3,697.6	3,675.7	3,673.0	12.9	12.8	92.43	-17.1	126.9	218.1	192.6	8.551			
3,800.0	3,797.6	3,775.2	3,771.8	13.3	13.2	92.98	-19.7	137.1	228.5	202.3	8.719			
3,900.0	3,897.6	3,874.6	3,870.7	13.6	13.6	93.47	-22.2	147.3	238.9	212.0	8.879			
4,000.0	3,997.6	3,974.0	3,969.6	14.0	13.9	93.93	-24.8	157.5	249.3	221.7	9.031			
4,100.0	4,097.6	4,073.5	4,068.5	14.3	14.3	94.35	-27.4	167.7	259.7	231.4	9.176			
4,200.0	4,197.6	4,172.9	4,167.4	14.7	14.7	94.73	-30.0	177.9	270.1	241.1	9.313			
4,300.0	4,297.6	4,272.4	4,266.2	15.1	15.0	95.09	-32.6	188.1	280.6	250.9	9.445			
4,400.0	4,397.6	4,371.8	4,365.1	15.4	15.4	95.42	-35.2	198.3	291.0	260.6	9.570			
4,500.0	4,497.6	4,471.2	4,464.0	15.8	15.8	95.73	-37.8	208.5	301.5	270.4	9.690			
4,600.0	4,597.6	4,570.7	4,562.9	16.1	16.1	96.02	-40.4	218.7	312.0	280.1	9.804			
4,700.0	4,697.6	4,674.9	4,666.6	16.5	16.5	96.29	-43.0	229.1	322.1	289.6	9.888			
4,800.0	4,797.6	4,787.4	4,778.7	16.8	16.9	96.48	-45.0	236.9	329.2	295.8	9.857			
4,900.0	4,897.6	4,900.2	4,891.5	17.2	17.3	96.57	-45.9	240.3	332.4	298.2	9.726			

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Anticollision Report



Company:	COG Operating, LLC	Local Co-ordinate Reference:	Well Fez Federal Com #705H
Project:	Lea County, NM	TVD Reference:	well @ 3291.0usft (Noram #21)
Reference Site:	Sec 9, T2S-S, R35-E	MD Reference:	well @ 3291.0usft (Noram #21)
Site Error:	0.0 usft	North Reference:	Grid
Reference Well:	Fez Federal Com #705H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.0 usft	Output errors are at	2.00 sigma
Reference Wellbore	Wellbore #1	Database:	EDM 5000.1 Single User Db
Reference Design:	Design #1	Offset TVD Reference:	Offset Datum

Offset Design: Sec 9, T2S-S, R35-E - Fez Federal Com #704H - Wellbore #1 - Design #1											Offset Site Error:	0.0 usft
Survey Program: 0-MWD											Offset Well Error:	0.0 usft
Reference Measured Depth (usft)	Vertical Depth (usft)	Offset Measured Depth (usft)	Vertical Depth (usft)	Semi-Major Reference (usft)	Axis Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	Between Centres (usft)	Distance Between Ellipses (usft)	Separation Factor	Warning	
5,000.0	4,997.6	5,004.3	4,995.6	17.5	17.7	96.57	-45.9	240.6	332.5	297.7	9.530	
5,100.0	5,097.6	5,104.3	5,095.6	17.9	18.0	96.57	-45.9	240.6	332.5	296.9	9.341	
5,200.0	5,197.6	5,204.3	5,195.6	18.2	18.4	96.57	-45.9	240.6	332.5	296.2	9.159	
5,300.0	5,297.6	5,304.3	5,295.6	18.6	18.7	96.57	-45.9	240.6	332.5	295.5	8.983	
5,400.0	5,397.6	5,404.3	5,395.6	18.9	19.1	96.57	-45.9	240.6	332.5	294.8	8.815	
5,500.0	5,497.6	5,504.3	5,495.6	19.3	19.4	96.57	-45.9	240.6	332.5	294.1	8.652	
5,600.0	5,597.6	5,604.3	5,595.6	19.7	19.8	96.57	-45.9	240.6	332.5	293.4	8.495	
5,700.0	5,697.6	5,704.3	5,695.6	20.0	20.1	96.57	-45.9	240.6	332.5	292.7	8.344	
5,800.0	5,797.6	5,804.3	5,795.6	20.4	20.5	96.57	-45.9	240.6	332.5	292.0	8.198	
5,900.0	5,897.6	5,904.3	5,895.6	20.7	20.8	96.57	-45.9	240.6	332.5	291.3	8.057	
6,000.0	5,997.6	6,004.3	5,995.6	21.1	21.2	96.57	-45.9	240.6	332.5	290.6	7.920	
6,100.0	6,097.6	6,104.3	6,095.6	21.4	21.6	96.57	-45.9	240.6	332.5	289.8	7.789	
6,200.0	6,197.6	6,204.3	6,195.6	21.8	21.9	96.57	-45.9	240.6	332.5	289.1	7.661	
6,300.0	6,297.6	6,304.3	6,295.6	22.1	22.3	96.57	-45.9	240.6	332.5	288.4	7.538	
6,400.0	6,397.6	6,404.3	6,395.6	22.5	22.6	96.57	-45.9	240.6	332.5	287.7	7.418	
6,500.0	6,497.6	6,504.3	6,495.6	22.9	23.0	96.57	-45.9	240.6	332.5	287.0	7.302	
6,600.0	6,597.6	6,604.3	6,595.6	23.2	23.3	96.57	-45.9	240.6	332.5	286.3	7.190	
6,700.0	6,697.6	6,704.3	6,695.6	23.6	23.7	96.57	-45.9	240.6	332.5	285.6	7.081	
6,800.0	6,797.6	6,804.3	6,795.6	23.9	24.0	96.57	-45.9	240.6	332.5	284.9	6.975	
6,900.0	6,897.6	6,904.3	6,895.6	24.3	24.4	96.57	-45.9	240.6	332.5	284.2	6.872	
7,000.0	6,997.6	7,004.3	6,995.6	24.6	24.7	96.57	-45.9	240.6	332.5	283.4	6.773	
7,100.0	7,097.6	7,104.3	7,095.6	25.0	25.1	96.57	-45.9	240.6	332.5	282.7	6.676	
7,200.0	7,197.6	7,204.3	7,195.6	25.4	25.4	96.57	-45.9	240.6	332.5	282.0	6.582	
7,300.0	7,297.6	7,304.3	7,295.6	25.7	25.8	96.57	-45.9	240.6	332.5	281.3	6.490	
7,400.0	7,397.6	7,404.3	7,395.6	26.1	26.1	96.57	-45.9	240.6	332.5	280.6	6.401	
7,500.0	7,497.6	7,504.3	7,495.6	26.4	26.5	96.57	-45.9	240.6	332.5	279.9	6.315	
7,600.0	7,597.6	7,604.3	7,595.6	26.8	26.9	96.57	-45.9	240.6	332.5	279.2	6.230	
7,700.0	7,697.6	7,704.3	7,695.6	27.1	27.2	96.57	-45.9	240.6	332.5	278.5	6.148	
7,800.0	7,797.6	7,804.3	7,795.6	27.5	27.6	96.57	-45.9	240.6	332.5	277.7	6.068	
7,900.0	7,897.6	7,904.3	7,895.6	27.9	27.9	96.57	-45.9	240.6	332.5	277.0	5.990	
8,000.0	7,997.6	8,004.3	7,995.6	28.2	28.3	96.57	-45.9	240.6	332.5	276.3	5.914	
8,100.0	8,097.6	8,104.3	8,095.6	28.6	28.6	96.57	-45.9	240.6	332.5	275.6	5.840	
8,200.0	8,197.6	8,204.3	8,195.6	28.9	29.0	96.57	-45.9	240.6	332.5	274.9	5.768	
8,300.0	8,297.6	8,304.3	8,295.6	29.3	29.3	96.57	-45.9	240.6	332.5	274.2	5.697	
8,400.0	8,397.6	8,404.3	8,395.6	29.6	29.7	96.57	-45.9	240.6	332.5	273.5	5.628	
8,500.0	8,497.6	8,504.3	8,495.6	30.0	30.0	96.57	-45.9	240.6	332.5	272.7	5.561	
8,600.0	8,597.6	8,604.3	8,595.6	30.4	30.4	96.57	-45.9	240.6	332.5	272.0	5.496	
8,700.0	8,697.6	8,704.3	8,695.6	30.7	30.8	96.57	-45.9	240.6	332.5	271.3	5.432	
8,800.0	8,797.6	8,804.3	8,795.6	31.1	31.1	96.57	-45.9	240.6	332.5	270.6	5.369	
8,900.0	8,897.6	8,904.3	8,895.6	31.4	31.5	96.57	-45.9	240.6	332.5	269.9	5.308	
9,000.0	8,997.6	9,004.3	8,995.6	31.8	31.8	96.57	-45.9	240.6	332.5	269.2	5.248	
9,100.0	9,097.6	9,104.3	9,095.6	32.1	32.2	96.57	-45.9	240.6	332.5	268.5	5.189	
9,200.0	9,197.6	9,204.3	9,195.6	32.5	32.5	96.57	-45.9	240.6	332.5	267.7	5.132	
9,300.0	9,297.6	9,304.3	9,295.6	32.9	32.9	96.57	-45.9	240.6	332.5	267.0	5.076	
9,400.0	9,397.6	9,404.3	9,395.6	33.2	33.2	96.57	-45.9	240.6	332.5	266.3	5.021	
9,500.0	9,497.6	9,504.3	9,495.6	33.6	33.6	96.57	-45.9	240.6	332.5	265.6	4.968	
9,600.0	9,597.6	9,604.3	9,595.6	33.9	34.0	96.57	-45.9	240.6	332.5	264.9	4.915	
9,700.0	9,697.6	9,704.3	9,695.6	34.3	34.3	96.57	-45.9	240.6	332.5	264.2	4.864	
9,800.0	9,797.6	9,804.3	9,795.6	34.6	34.7	96.57	-45.9	240.6	332.5	263.5	4.814	
9,900.0	9,897.6	9,904.3	9,895.6	35.0	35.0	96.57	-45.9	240.6	332.5	262.7	4.764	
10,000.0	9,997.6	10,004.3	9,995.6	35.4	35.4	96.57	-45.9	240.6	332.5	262.0	4.716	
10,100.0	10,097.6	10,104.3	10,095.6	35.7	35.7	96.57	-45.9	240.6	332.5	261.3	4.669	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

Company:	COG Operating, LLC	Local Co-ordinate Reference:	Well Fez Federal Com #705H
Project:	Lea County, NM	TVD Reference:	well @ 3291.0usft (Noram #21)
Reference Site:	Sec 9, T25-S, R35-E	MD Reference:	well @ 3291.0usft (Noram #21)
Site Error:	0.0 usft	North Reference:	Grid
Reference Well:	Fez Federal Com #705H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.0 usft	Output errors are at	2.00 sigma
Reference Wellbore	Wellbore #1	Database:	EDM 5000.1 Single User Db
Reference Design:	Design #1	Offset TVD Reference:	Offset Datum

Offset Design Sec 9, T25-S, R35-E - Fez Federal Com #704H - Wellbore #1 - Design #1												Offset Site Error:	0.0 usft
Survey Program: 0-MWD												Offset Well Error:	0.0 usft
Reference Measured Depth (usft)	Vertical Depth (usft)	Offset Measured Depth (usft)	Vertical Depth (usft)	Semi Major Axis Reference (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	+E/-W (usft)	Distance Between Centres (usft)	Between Ellipses (usft)	Separation Factor	Warning	
10,200.0	10,197.6	10,204.3	10,195.6	36.1	36.1	96.57	-45.9	240.6	332.5	260.6	4.622		
10,300.0	10,297.6	10,304.3	10,295.6	36.4	36.5	96.57	-45.9	240.6	332.5	259.9	4.577		
10,400.0	10,397.6	10,404.3	10,395.6	36.8	36.8	96.57	-45.9	240.6	332.5	259.2	4.532		
10,500.0	10,497.6	10,504.3	10,495.6	37.1	37.2	96.57	-45.9	240.6	332.5	258.5	4.489		
10,600.0	10,597.6	10,604.3	10,595.6	37.5	37.5	96.57	-45.9	240.6	332.5	257.7	4.446		
10,700.0	10,697.6	10,704.3	10,695.6	37.9	37.9	96.57	-45.9	240.6	332.5	257.0	4.404		
10,800.0	10,797.6	10,804.3	10,795.6	38.2	38.2	96.57	-45.9	240.6	332.5	256.3	4.362		
10,900.0	10,897.6	10,904.3	10,895.6	38.6	38.6	96.57	-45.9	240.6	332.5	255.6	4.322		
11,000.0	10,997.6	11,004.3	10,995.6	38.9	38.9	96.57	-45.9	240.6	332.5	254.9	4.282		
11,100.0	11,097.6	11,104.3	11,095.6	39.3	39.3	96.57	-45.9	240.6	332.5	254.2	4.243		
11,200.0	11,197.6	11,204.3	11,195.6	39.6	39.7	96.57	-45.9	240.6	332.5	253.5	4.205		
11,300.0	11,297.6	11,304.3	11,295.6	40.0	40.0	96.57	-45.9	240.6	332.5	252.7	4.167		
11,400.0	11,397.6	11,404.3	11,395.6	40.4	40.4	96.57	-45.9	240.6	332.5	252.0	4.130		
11,500.0	11,497.6	11,504.3	11,495.6	40.7	40.7	96.57	-45.9	240.6	332.5	251.3	4.094		
11,600.0	11,597.6	11,604.3	11,595.6	41.1	41.1	96.57	-45.9	240.6	332.5	250.6	4.058		
11,700.0	11,697.6	11,704.3	11,695.6	41.4	41.4	96.57	-45.9	240.6	332.5	249.9	4.023		
11,800.0	11,797.6	11,804.3	11,795.6	41.8	41.8	96.57	-45.9	240.6	332.5	249.2	3.988		
11,900.0	11,897.6	11,904.3	11,895.6	42.1	42.2	96.57	-45.9	240.6	332.5	248.4	3.954		
12,000.0	11,997.6	12,004.3	11,995.6	42.5	42.5	96.57	-45.9	240.6	332.5	247.7	3.921		
12,100.9	12,098.5	12,112.4	12,102.9	42.9	42.9	94.70	-35.0	240.5	331.5	245.9	3.875		
12,125.0	12,122.6	12,137.4	12,127.2	43.0	43.0	94.26	-29.1	240.4	331.0	245.3	3.862		
12,150.0	12,147.5	12,163.0	12,151.7	43.0	43.1	93.36	-21.7	240.4	330.7	244.8	3.850		
12,175.0	12,172.3	12,188.3	12,175.5	43.1	43.1	92.44	-13.1	240.3	330.4	244.3	3.839		
12,200.0	12,196.9	12,213.3	12,198.6	43.2	43.2	91.53	-3.4	240.2	330.2	244.0	3.829		
12,225.0	12,221.2	12,238.1	12,220.8	43.3	43.3	90.61	7.4	240.2	330.1	243.7	3.820		
12,241.8	12,237.3	12,254.5	12,235.3	43.4	43.3	90.00	15.2	240.1	330.1	243.6	3.815		
12,250.0	12,245.2	12,262.5	12,242.3	43.4	43.4	89.70	19.2	240.1	330.1	243.5	3.813		
12,275.0	12,268.7	12,286.7	12,262.8	43.5	43.4	88.79	32.0	240.0	330.1	243.4	3.807		
12,300.0	12,291.8	12,310.7	12,282.5	43.6	43.5	87.89	45.6	239.9	330.3	243.4	3.803		
12,325.0	12,314.4	12,334.4	12,301.3	43.6	43.5	87.01	60.0	239.8	330.5	243.5	3.799		
12,350.0	12,336.4	12,357.8	12,319.2	43.7	43.6	86.13	75.1	239.6	330.9	243.7	3.798		
12,375.0	12,357.8	12,381.1	12,336.2	43.8	43.6	85.27	91.0	239.5	331.2	244.0	3.797		
12,400.0	12,378.4	12,404.1	12,352.2	43.8	43.7	84.42	107.6	239.4	331.7	244.4	3.798		
12,425.0	12,398.2	12,426.9	12,367.3	43.9	43.7	83.59	124.7	239.3	332.2	244.8	3.801		
12,450.0	12,417.3	12,450.0	12,381.7	44.0	43.8	82.77	142.7	239.1	332.8	245.3	3.805		
12,475.0	12,435.5	12,472.0	12,394.6	44.0	43.8	82.00	160.6	239.0	333.4	245.9	3.810		
12,500.0	12,452.7	12,494.3	12,406.8	44.1	43.9	81.24	179.2	238.9	334.1	246.5	3.816		
12,525.0	12,469.0	12,516.4	12,418.1	44.2	44.0	80.51	198.2	238.7	334.8	247.2	3.823		
12,550.0	12,484.2	12,538.4	12,428.4	44.3	44.0	79.80	217.7	238.6	335.5	247.9	3.831		
12,575.0	12,498.4	12,560.2	12,437.7	44.3	44.1	79.12	237.4	238.4	336.3	248.7	3.840		
12,600.0	12,511.5	12,581.9	12,446.1	44.4	44.1	78.46	257.4	238.3	337.0	249.5	3.849		
12,625.0	12,523.5	12,603.5	12,453.5	44.5	44.2	77.84	277.6	238.1	337.8	250.2	3.858		
12,650.0	12,534.3	12,625.0	12,460.0	44.5	44.2	77.25	298.1	238.0	338.6	251.0	3.868		
12,675.0	12,543.9	12,646.3	12,465.4	44.6	44.3	76.70	318.7	237.8	339.3	251.8	3.877		
12,700.0	12,552.3	12,667.5	12,470.0	44.7	44.3	76.17	339.4	237.7	340.1	252.6	3.887		
12,725.0	12,559.5	12,688.6	12,473.6	44.7	44.4	75.68	360.3	237.5	340.8	253.3	3.895		
12,750.0	12,565.3	12,709.7	12,476.3	44.8	44.4	75.23	381.1	237.3	341.5	254.0	3.904		
12,775.0	12,569.9	12,730.7	12,478.1	44.9	44.5	74.81	402.0	237.2	342.1	254.6	3.911		
12,800.0	12,573.3	12,751.6	12,478.9	44.9	44.6	74.42	422.9	237.0	342.7	255.3	3.917		
12,825.0	12,575.3	12,774.5	12,478.9	45.0	44.6	74.07	445.9	236.9	343.3	255.7	3.922		
12,852.4	12,576.0	12,801.9	12,478.8	45.1	44.7	73.92	473.3	236.7	343.5	255.9	3.920		
12,900.0	12,575.8	12,849.5	12,478.7	45.2	44.8	73.92	520.8	236.3	343.5	255.6	3.908		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

Company:	COG Operating, LLC	Local Co-ordinate Reference:	Well Fez Federal Com #705H
Project:	Lea County, NM	TVD Reference:	well @ 3291.0usft (Noram #21)
Reference Site:	Sec 9, T25-S, R35-E	MD Reference:	well @ 3291.0usft (Noram #21)
Site Error:	0.0 usft	North Reference:	Grid
Reference Well:	Fez Federal Com #705H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.0 usft	Output errors are at	2.00 sigma
Reference Wellbore	Wellbore #1	Database:	EDM 5000.1 Single User Db
Reference Design:	Design #1	Offset TVD Reference:	Offset Datum

Offset Design Sec 9, T25-S, R35-E - Fez Federal Com #704H - Wellbore #1 - Design #1												Offset Site Error:	0.0 usft
Survey Program: 0-MWD												Offset Well Error:	0.0 usft
Reference Measured Depth (usft)	Vertical Depth (usft)	Offset Measured Depth (usft)	Vertical Depth (usft)	Semi Major Reference (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	+E/-W (usft)	Distance Between Centres (usft)	Between Ellipses (usft)	Separation Factor	Warning	
13,000.0	12,575.5	12,949.5	12,478.4	45.5	45.2	73.92	620.8	235.6	343.5	255.0	3.881		
13,100.0	12,575.2	13,049.5	12,478.1	45.9	45.5	73.92	720.8	234.8	343.5	254.2	3.849		
13,200.0	12,574.9	13,149.5	12,477.8	46.3	46.0	73.92	820.8	234.1	343.5	253.4	3.813		
13,300.0	12,574.6	13,249.5	12,477.5	46.8	46.5	73.92	920.8	233.3	343.5	252.5	3.773		
13,400.0	12,574.3	13,349.5	12,477.1	47.3	47.0	73.92	1,020.8	232.6	343.5	251.4	3.730		
13,500.0	12,573.9	13,449.5	12,476.8	47.9	47.6	73.92	1,120.8	231.8	343.5	250.3	3.685		
13,600.0	12,573.6	13,549.5	12,476.5	48.6	48.3	73.92	1,220.8	231.1	343.5	249.0	3.636		
13,700.0	12,573.3	13,649.5	12,476.2	49.2	49.0	73.92	1,320.8	230.3	343.5	247.7	3.586		
13,800.0	12,573.0	13,749.5	12,475.9	50.0	49.7	73.92	1,420.8	229.6	343.5	246.3	3.533		
13,900.0	12,572.7	13,849.5	12,475.6	50.7	50.5	73.92	1,520.8	228.8	343.5	244.8	3.480		
14,000.0	12,572.4	13,949.5	12,475.3	51.6	51.3	73.92	1,620.8	228.1	343.5	243.2	3.425		
14,100.0	12,572.1	14,049.5	12,475.0	52.4	52.2	73.93	1,720.8	227.3	343.5	241.5	3.369		
14,200.0	12,571.8	14,149.5	12,474.7	53.3	53.1	73.93	1,820.8	226.6	343.5	239.8	3.313		
14,300.0	12,571.5	14,249.5	12,474.4	54.2	54.0	73.93	1,920.8	225.8	343.5	238.0	3.256		
14,400.0	12,571.1	14,349.5	12,474.0	55.2	55.0	73.93	2,020.8	225.1	343.5	236.1	3.200		
14,500.0	12,570.8	14,449.5	12,473.7	56.2	56.0	73.93	2,120.8	224.3	343.5	234.2	3.143		
14,600.0	12,570.5	14,549.5	12,473.4	57.2	57.0	73.93	2,220.8	223.6	343.5	232.2	3.087		
14,700.0	12,570.2	14,649.5	12,473.1	58.3	58.1	73.93	2,320.8	222.8	343.5	230.2	3.032		
14,800.0	12,569.9	14,749.5	12,472.8	59.3	59.2	73.93	2,420.8	222.1	343.5	228.1	2.976		
14,900.0	12,569.6	14,849.5	12,472.5	60.4	60.3	73.93	2,520.8	221.3	343.5	225.9	2.922		
15,000.0	12,569.3	14,949.5	12,472.2	61.6	61.4	73.93	2,620.8	220.6	343.5	223.7	2.869		
15,100.0	12,569.0	15,049.5	12,471.9	62.7	62.6	73.93	2,720.8	219.8	343.5	221.5	2.816		
15,200.0	12,568.7	15,149.5	12,471.6	63.9	63.8	73.93	2,820.8	219.1	343.5	219.2	2.764		
15,300.0	12,568.3	15,249.5	12,471.3	65.1	65.0	73.93	2,920.8	218.3	343.5	216.9	2.714		
15,400.0	12,568.0	15,349.5	12,470.9	66.3	66.2	73.93	3,020.8	217.6	343.5	214.5	2.664		
15,500.0	12,567.7	15,449.5	12,470.6	67.5	67.4	73.93	3,120.8	216.8	343.5	212.2	2.616		
15,600.0	12,567.4	15,549.5	12,470.3	68.8	68.7	73.93	3,220.7	216.1	343.5	209.7	2.568		
15,700.0	12,567.1	15,649.5	12,470.0	70.1	69.9	73.93	3,320.7	215.3	343.5	207.3	2.522		
15,800.0	12,566.8	15,749.5	12,469.7	71.3	71.2	73.93	3,420.7	214.6	343.5	204.8	2.476		
15,900.0	12,566.5	15,849.5	12,469.4	72.6	72.5	73.93	3,520.7	213.8	343.5	202.3	2.432		
16,000.0	12,566.2	15,949.5	12,469.1	73.9	73.9	73.93	3,620.7	213.1	343.5	199.7	2.389		
16,100.0	12,565.9	16,049.5	12,468.8	75.3	75.2	73.93	3,720.7	212.3	343.5	197.1	2.347		
16,200.0	12,565.5	16,149.5	12,468.5	76.6	76.5	73.93	3,820.7	211.6	343.5	194.5	2.306		
16,300.0	12,565.2	16,249.5	12,468.2	78.0	77.9	73.93	3,920.7	210.8	343.5	191.9	2.266		
16,400.0	12,564.9	16,349.5	12,467.8	79.3	79.3	73.93	4,020.7	210.1	343.5	189.3	2.228		
16,500.0	12,564.6	16,449.5	12,467.5	80.7	80.6	73.93	4,120.7	209.3	343.5	186.6	2.190		
16,600.0	12,564.3	16,549.5	12,467.2	82.1	82.0	73.93	4,220.7	208.6	343.5	183.9	2.153		
16,700.0	12,564.0	16,649.5	12,466.9	83.5	83.4	73.93	4,320.7	207.8	343.5	181.2	2.117		
16,800.0	12,563.7	16,749.5	12,466.6	84.9	84.8	73.93	4,420.7	207.1	343.5	178.5	2.082		
16,900.0	12,563.4	16,849.5	12,466.3	86.3	86.2	73.93	4,520.7	206.3	343.5	175.8	2.048		
17,000.0	12,563.1	16,949.5	12,466.0	87.7	87.7	73.93	4,620.7	205.6	343.5	173.0	2.015		
17,100.0	12,562.7	17,049.5	12,465.7	89.1	89.1	73.93	4,720.7	204.8	343.5	170.2	1.983		
17,200.0	12,562.4	17,149.5	12,465.4	90.6	90.5	73.93	4,820.7	204.1	343.5	167.5	1.951		
17,300.0	12,562.1	17,249.5	12,465.1	92.0	92.0	73.93	4,920.7	203.3	343.5	164.7	1.921		
17,400.0	12,561.8	17,349.5	12,464.8	93.5	93.4	73.93	5,020.7	202.6	343.5	161.8	1.891		
17,500.0	12,561.5	17,449.5	12,464.4	94.9	94.9	73.93	5,120.7	201.8	343.5	159.0	1.862		
17,600.0	12,561.2	17,549.5	12,464.1	96.4	96.4	73.93	5,220.7	201.1	343.5	156.2	1.834		
17,700.0	12,560.9	17,649.5	12,463.8	97.8	97.8	73.93	5,320.7	200.3	343.5	153.3	1.807		
17,800.0	12,560.6	17,749.5	12,463.5	99.3	99.3	73.93	5,420.7	199.6	343.5	150.5	1.780		
17,900.0	12,560.3	17,849.5	12,463.2	100.8	100.8	73.93	5,520.7	198.8	343.5	147.6	1.754		
18,000.0	12,559.9	17,949.5	12,462.9	102.3	102.3	73.93	5,620.7	198.1	343.5	144.7	1.728		
18,100.0	12,559.6	18,049.5	12,462.6	103.8	103.8	73.93	5,720.7	197.3	343.5	141.8	1.703		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

Company:	COG Operating, LLC	Local Co-ordinate Reference:	Well Fez Federal Com #705H
Project:	Lea County, NM	TVD Reference:	well @ 3291.0usft (Noram #21)
Reference Site:	Sec 9, T25-S, R35-E	MD Reference:	well @ 3291.0usft (Noram #21)
Site Error:	0.0 usft	North Reference:	Grid
Reference Well:	Fez Federal Com #705H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.0 usft	Output errors are at	2.00 sigma
Reference Wellbore	Wellbore #1	Database:	EDM 5000.1 Single User Db
Reference Design:	Design #1	Offset TVD Reference:	Offset Datum

Offset Design Sec 9, T25-S, R35-E - Fez Federal Com #704H - Wellbore #1 - Design #1												Offset Site Error:	0.0 usft
Survey Program: 0-MWD												Offset Well Error:	0.0 usft
Reference Measured Depth (usft)	Vertical Depth (usft)	Offset Measured Depth (usft)	Vertical Depth (usft)	Semi Major Axis Reference (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N-S (usft)	+E-W (usft)	Distance Between Centres (usft)	Between Ellipses (usft)	Separation Factor	Warning	
18,200.0	12,559.3	18,149.5	12,462.3	105.3	105.3	73.93	5,820.7	196.6	343.5	138.9	1.679		
18,300.0	12,559.0	18,249.5	12,462.0	106.8	106.8	73.93	5,920.7	195.8	343.4	136.0	1.656		
18,400.0	12,558.7	18,349.5	12,461.7	108.3	108.3	73.93	6,020.7	195.1	343.4	133.1	1.633		
18,500.0	12,558.4	18,449.5	12,461.3	109.8	109.8	73.93	6,120.7	194.3	343.4	130.2	1.610		
18,600.0	12,558.1	18,549.5	12,461.0	111.3	111.3	73.93	6,220.6	193.6	343.4	127.2	1.589		
18,700.0	12,557.8	18,649.5	12,460.7	112.8	112.8	73.93	6,320.6	192.8	343.4	124.3	1.567		
18,800.0	12,557.5	18,749.5	12,460.4	114.3	114.3	73.93	6,420.6	192.1	343.4	121.4	1.546		
18,900.0	12,557.1	18,849.5	12,460.1	115.8	115.9	73.93	6,520.6	191.3	343.4	118.4	1.526		
19,000.0	12,556.8	18,949.5	12,459.8	117.4	117.4	73.93	6,620.6	190.6	343.4	115.4	1.506		
19,100.0	12,556.5	19,049.5	12,459.5	118.9	118.9	73.93	6,720.6	189.8	343.4	112.5	1.487 Level 3		
19,200.0	12,556.2	19,149.5	12,459.2	120.4	120.5	73.93	6,820.6	189.1	343.4	109.5	1.468 Level 3		
19,300.0	12,555.9	19,249.5	12,458.9	122.0	122.0	73.93	6,920.6	188.3	343.4	106.5	1.450 Level 3		
19,400.0	12,555.6	19,349.5	12,458.6	123.5	123.5	73.94	7,020.6	187.6	343.4	103.5	1.432 Level 3		
19,500.0	12,555.3	19,449.5	12,458.2	125.1	125.1	73.94	7,120.6	186.8	343.4	100.5	1.414 Level 3		
19,600.0	12,555.0	19,549.5	12,457.9	126.6	126.6	73.94	7,220.6	186.1	343.4	97.5	1.397 Level 3		
19,700.0	12,554.7	19,649.5	12,457.6	128.1	128.2	73.94	7,320.6	185.3	343.4	94.5	1.380 Level 3		
19,800.0	12,554.3	19,749.5	12,457.3	129.7	129.7	73.94	7,420.6	184.6	343.4	91.5	1.363 Level 3		
19,900.0	12,554.0	19,849.5	12,457.0	131.2	131.3	73.94	7,520.6	183.8	343.4	88.5	1.347 Level 3		
20,000.0	12,553.7	19,949.5	12,456.7	132.8	132.8	73.94	7,620.6	183.1	343.4	85.5	1.331 Level 3		
20,100.0	12,553.4	20,049.5	12,456.4	134.4	134.4	73.94	7,720.6	182.3	343.4	82.5	1.316 Level 3		
20,200.0	12,553.1	20,149.5	12,456.1	135.9	136.0	73.94	7,820.6	181.6	343.4	79.4	1.301 Level 3		
20,300.0	12,552.8	20,249.5	12,455.8	137.5	137.5	73.94	7,920.6	180.8	343.4	76.4	1.286 Level 3		
20,400.0	12,552.5	20,349.5	12,455.5	139.0	139.1	73.94	8,020.6	180.1	343.4	73.4	1.272 Level 3		
20,500.0	12,552.2	20,449.5	12,455.1	140.6	140.7	73.94	8,120.6	179.3	343.4	70.3	1.258 Level 3		
20,600.0	12,551.9	20,549.5	12,454.8	142.2	142.2	73.94	8,220.6	178.6	343.4	67.3	1.244 Level 2		
20,700.0	12,551.5	20,649.5	12,454.5	143.7	143.8	73.94	8,320.6	177.8	343.4	64.3	1.230 Level 2		
20,800.0	12,551.2	20,749.5	12,454.2	145.3	145.4	73.94	8,420.6	177.1	343.4	61.2	1.217 Level 2		
20,900.0	12,550.9	20,849.5	12,453.9	146.9	146.9	73.94	8,520.6	176.3	343.4	58.2	1.204 Level 2		
21,000.0	12,550.6	20,949.5	12,453.6	148.5	148.5	73.94	8,620.6	175.6	343.4	55.1	1.191 Level 2		
21,100.0	12,550.3	21,049.5	12,453.3	150.0	150.1	73.94	8,720.6	174.8	343.4	52.0	1.179 Level 2		
21,200.0	12,550.0	21,149.5	12,453.0	151.6	151.7	73.94	8,820.6	174.1	343.4	49.0	1.166 Level 2		
21,300.0	12,549.7	21,249.5	12,452.7	153.2	153.3	73.94	8,920.6	173.3	343.4	45.9	1.154 Level 2		
21,400.0	12,549.4	21,349.5	12,452.4	154.8	154.8	73.94	9,020.6	172.6	343.4	42.8	1.143 Level 2		
21,500.0	12,549.1	21,449.5	12,452.0	156.4	156.4	73.94	9,120.6	171.8	343.4	39.8	1.131 Level 2		
21,600.0	12,548.7	21,549.5	12,451.7	157.9	158.0	73.94	9,220.6	171.1	343.4	36.7	1.120 Level 2		
21,700.0	12,548.4	21,649.5	12,451.4	159.5	159.6	73.94	9,320.5	170.3	343.4	33.6	1.109 Level 2		
21,800.0	12,548.1	21,749.5	12,451.1	161.1	161.2	73.94	9,420.5	169.6	343.4	30.5	1.098 Level 2		
21,900.0	12,547.8	21,849.5	12,450.8	162.7	162.8	73.94	9,520.5	168.8	343.4	27.5	1.087 Level 2		
22,000.0	12,547.5	21,949.5	12,450.5	164.3	164.4	73.94	9,620.5	168.1	343.4	24.4	1.076 Level 2		
22,100.0	12,547.2	22,049.5	12,450.2	165.9	166.0	73.94	9,720.5	167.3	343.4	21.3	1.066 Level 2		
22,200.0	12,546.9	22,149.5	12,449.9	167.5	167.6	73.94	9,820.5	166.6	343.4	18.2	1.056 Level 2		
22,300.0	12,546.6	22,249.5	12,449.6	169.1	169.2	73.94	9,920.5	165.8	343.4	15.1	1.046 Level 2		
22,400.0	12,546.3	22,349.5	12,449.3	170.7	170.7	73.94	10,020.5	165.1	343.4	12.0	1.036 Level 2		
22,483.7	12,546.0	22,433.2	12,449.0	172.0	172.1	73.94	10,104.3	164.4	343.4	9.4	1.028 Level 2, ES, SF		

Company:	COG Operating, LLC	Local Co-ordinate Reference:	Well Fez Federal Com #705H
Project:	Lea County, NM	TVD Reference:	well @ 3291.0usft (Noram #21)
Reference Site:	Sec 9, T25-S, R35-E	MD Reference:	well @ 3291.0usft (Noram #21)
Site Error:	0.0 usft	North Reference:	Grid
Reference Well:	Fez Federal Com #705H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.0 usft	Output errors are at	2.00 sigma
Reference Wellbore	Wellbore #1	Database:	EDM 5000.1 Single User Db
Reference Design:	Design #1	Offset TVD Reference:	Offset Datum

Offset Design Sec 9, T25-S, R35-E - Fez Fee #11H - Wellbore #1 - Wellbore #1												Offset Site Error:	0.0 usft
Survey Program: 100-Good gyro, 8700-MWD default												Offset Well Error:	0.0 usft
Reference Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Semi Major Axis Reference (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	+E/-W (usft)	Distance Between Centres (usft)	Between Ellipses (usft)	Separation Factor	Warning	
0.0	0.0	0.0	0.0	0.0	0.0	-3.42	4,515.4	-270.2	4,523.4				
100.0	100.0	76.5	76.5	0.1	0.0	-3.42	4,515.5	-270.2	4,523.7	4,523.5	N/A		
200.0	200.0	156.3	156.3	0.5	0.1	-3.42	4,516.1	-270.1	4,524.3	4,523.8	8,195.005		
300.0	300.0	250.4	250.4	0.8	0.1	-3.41	4,517.1	-269.3	4,525.4	4,524.4	4,711.255		
400.0	400.0	361.1	361.1	1.2	0.2	-3.39	4,518.2	-267.8	4,526.3	4,524.9	3,283.685		
500.0	500.0	462.1	462.1	1.6	0.2	-3.37	4,519.1	-266.2	4,527.1	4,525.3	2,525.878		
600.0	600.0	572.4	572.3	1.9	0.3	-3.34	4,520.0	-263.8	4,527.8	4,525.6	2,047.338		
700.0	700.0	686.3	686.2	2.3	0.4	-3.31	4,520.6	-261.6	4,528.2	4,525.5	1,720.022		
800.0	800.0	783.0	782.9	2.6	0.4	-3.29	4,520.9	-259.5	4,528.4	4,525.4	1,486.938		
900.0	900.0	896.0	895.8	3.0	0.5	-3.25	4,521.3	-256.7	4,528.6	4,525.1	1,305.878		
1,000.0	1,000.0	1,017.8	1,017.6	3.4	0.5	-3.20	4,521.3	-252.7	4,528.4	4,524.5	1,161.563		
1,100.0	1,100.0	1,135.3	1,135.0	3.7	0.6	91.88	4,520.7	-249.6	4,527.8	4,523.5	1,049.736		
1,200.0	1,199.9	1,274.0	1,273.7	4.0	0.7	91.98	4,519.2	-246.2	4,526.7	4,522.0	956.028		
1,300.0	1,299.9	1,384.6	1,384.2	4.4	0.8	92.07	4,517.3	-243.3	4,525.0	4,519.8	879.653		
1,400.0	1,399.8	1,484.7	1,484.3	4.7	0.8	92.14	4,515.5	-241.1	4,523.2	4,517.6	815.420		
1,500.0	1,499.7	1,623.7	1,623.2	5.1	0.9	92.22	4,512.4	-238.9	4,521.0	4,515.1	757.031		
1,600.0	1,599.7	1,731.9	1,731.4	5.4	0.9	92.29	4,509.0	-237.2	4,518.0	4,511.6	707.974		
1,700.0	1,699.6	1,800.0	1,799.4	5.8	1.0	92.33	4,507.4	-236.6	4,515.6	4,508.8	666.928		
1,800.0	1,799.6	1,867.6	1,867.0	6.2	1.0	92.36	4,506.2	-236.4	4,513.9	4,506.8	630.474		
1,900.0	1,899.5	1,966.2	1,965.6	6.5	1.1	92.40	4,504.8	-236.6	4,512.6	4,505.1	596.586		
2,000.0	2,000.0	2,078.0	2,077.4	6.9	1.1	92.44	4,502.9	-237.0	4,511.1	4,503.1	565.476		
2,100.0	2,099.9	2,199.4	2,198.8	7.2	1.2	92.55	4,500.4	-237.7	4,509.3	4,500.9	537.059		
2,200.0	2,199.0	2,339.6	2,338.9	7.6	1.3	92.65	4,496.4	-238.9	4,506.8	4,498.0	510.717		
2,300.0	2,298.8	2,428.2	2,427.5	8.0	1.3	92.72	4,493.5	-240.1	4,504.0	4,494.7	487.839		
2,400.0	2,398.6	2,500.0	2,499.2	8.3	1.3	92.77	4,491.8	-241.1	4,501.8	4,492.2	467.295		
2,500.0	2,498.3	2,586.7	2,585.9	8.7	1.4	92.83	4,490.0	-242.5	4,500.1	4,490.1	448.090		
2,600.0	2,598.1	2,703.4	2,702.6	9.1	1.4	92.90	4,487.4	-244.5	4,498.3	4,487.8	429.777		
2,700.0	2,697.8	2,800.0	2,799.1	9.4	1.5	92.97	4,485.0	-246.2	4,496.3	4,485.4	413.160		
2,742.3	2,740.0	2,800.0	2,799.1	9.6	1.5	92.97	4,485.0	-246.2	4,495.7	4,484.7	407.233		
2,800.0	2,797.6	2,852.0	2,851.1	9.8	1.5	92.98	4,484.1	-246.9	4,494.9	4,483.6	398.574		
2,900.0	2,897.6	2,908.2	2,907.3	10.1	1.5	92.99	4,483.7	-247.5	4,494.3	4,482.6	385.244		
2,942.3	2,939.8	2,946.5	2,945.6	10.3	1.6	-2.01	4,483.6	-247.8	4,494.2	4,482.4	379.769		
3,000.0	2,997.6	3,000.0	2,999.1	10.5	1.6	-2.02	4,483.5	-248.3	4,494.1	4,482.1	372.600		
3,018.0	3,015.6	3,013.5	3,012.6	10.6	1.6	-2.02	4,483.5	-248.5	4,494.1	4,482.0	370.466		
3,100.0	3,097.6	3,079.2	3,078.3	10.8	1.6	-2.03	4,483.6	-249.1	4,494.3	4,481.8	361.006		
3,200.0	3,197.6	3,161.1	3,160.2	11.2	1.7	-2.04	4,484.0	-250.1	4,494.8	4,482.0	350.099		
3,300.0	3,297.6	3,240.0	3,239.1	11.5	1.7	-2.06	4,484.7	-251.3	4,495.8	4,482.6	339.899		
3,400.0	3,397.6	3,317.6	3,316.6	11.9	1.7	-2.08	4,485.8	-252.7	4,497.3	4,483.7	330.330		
3,500.0	3,497.6	3,400.0	3,399.0	12.2	1.8	-2.10	4,487.4	-254.3	4,499.2	4,485.2	321.249		
3,600.0	3,597.6	3,471.1	3,470.1	12.6	1.8	-2.11	4,489.0	-255.6	4,501.7	4,487.3	312.829		
3,700.0	3,697.6	3,532.2	3,531.2	12.9	1.8	-2.13	4,490.9	-256.8	4,504.8	4,490.1	305.024		
3,800.0	3,797.6	3,600.0	3,598.9	13.3	1.9	-2.15	4,493.7	-258.5	4,509.0	4,493.8	297.607		
3,900.0	3,897.6	3,648.8	3,647.6	13.6	2.1	-2.16	4,499.7	-259.9	4,511.1	4,495.4	287.422		
4,000.0	3,997.6	4,155.5	4,154.2	14.0	2.2	-2.15	4,494.9	-258.9	4,508.7	4,492.6	279.187		
4,100.0	4,097.6	4,279.7	4,278.3	14.3	2.2	-2.14	4,490.0	-257.6	4,504.8	4,488.2	271.937		
4,200.0	4,197.6	4,370.8	4,369.3	14.7	2.3	-2.12	4,486.4	-256.4	4,500.7	4,483.8	265.259		
4,300.0	4,297.6	4,457.6	4,456.0	15.1	2.3	-2.11	4,483.2	-255.3	4,497.0	4,479.6	258.925		
4,400.0	4,397.6	4,535.6	4,534.0	15.4	2.4	-2.09	4,480.6	-253.9	4,493.6	4,475.8	252.948		
4,500.0	4,497.6	4,608.5	4,606.9	15.8	2.4	-2.08	4,478.6	-252.6	4,490.8	4,472.7	247.297		
4,600.0	4,597.6	4,712.2	4,710.4	16.1	2.5	-2.04	4,476.1	-249.4	4,488.3	4,469.8	241.693		
4,700.0	4,697.6	4,821.3	4,819.4	16.5	2.6	-1.96	4,473.3	-243.4	4,485.5	4,466.5	236.251		
4,800.0	4,797.6	4,900.0	4,897.9	16.8	2.6	-1.91	4,471.6	-239.0	4,483.1	4,463.7	231.246		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Anticollision Report



Company:	COG Operating, LLC	Local Co-ordinate Reference:	Well Fez Federal Com #705H
Project:	Lea County, NM	TVD Reference:	well @ 3291.0usft (Noram #21)
Reference Site:	Sec 9, T25-S, R35-E	MD Reference:	well @ 3291.0usft (Noram #21)
Site Error:	0.0 usft	North Reference:	Grid
Reference Well:	Fez Federal Com #705H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.0 usft	Output errors are at	2.00 sigma
Reference Wellbore	Wellbore #1	Database:	EDM 5000.1 Single User Db
Reference Design:	Design #1	Offset TVD Reference:	Offset Datum

Offset Design Sec 9, T25-S, R35-E - Fez Fee #11H - Wellbore #1 - Wellbore #1												Offset Site Error:	0.0 usft
Survey Program: 100-Good_gyro, 8700-MWD default												Offset Well Error:	0.0 usft
Reference Measured Depth (usft)	Vertical Depth (usft)	Offset Measured Depth (usft)	Vertical Depth (usft)	Semi Major Reference (usft)	Axis Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	+E/-W (usft)	Distance Between Centres (usft)	Between Ellipses (usft)	Separation Factor	Warning	
4,900.0	4,897.6	4,940.9	4,938.7	17.2	2.6	-1.88	4,471.1	-237.0	4,481.6	4,461.8	226.724		
5,000.0	4,997.6	5,000.0	4,997.8	17.5	2.7	-1.85	4,470.9	-234.7	4,481.1	4,461.0	222.341		
5,003.2	5,000.8	5,000.0	4,997.8	17.5	2.7	-1.85	4,470.9	-234.7	4,481.1	4,461.0	222.215		
5,100.0	5,097.6	5,078.2	5,076.0	17.9	2.7	-1.83	4,471.3	-232.7	4,481.4	4,460.9	218.068		
5,200.0	5,197.6	5,131.5	5,129.2	18.2	2.7	-1.82	4,471.7	-231.9	4,482.3	4,461.3	214.144		
5,300.0	5,297.6	5,200.0	5,197.7	18.6	2.8	-1.82	4,473.4	-232.3	4,484.6	4,463.3	210.367		
5,400.0	5,397.6	5,258.5	5,256.2	18.9	2.8	-1.83	4,475.3	-233.4	4,487.6	4,465.9	206.827		
5,500.0	5,497.6	5,389.0	5,386.6	19.3	2.8	-1.88	4,478.7	-237.0	4,490.3	4,468.1	203.000		
5,600.0	5,597.6	5,479.7	5,477.2	19.7	2.9	-1.91	4,480.8	-239.7	4,492.7	4,470.2	199.514		
5,700.0	5,697.6	5,577.5	5,574.9	20.0	2.9	-1.95	4,483.3	-242.8	4,495.4	4,472.5	196.118		
5,800.0	5,797.6	5,672.9	5,670.3	20.4	3.0	-1.99	4,485.8	-245.8	4,498.1	4,474.8	192.848		
5,900.0	5,897.6	5,776.0	5,773.3	20.7	3.0	-2.03	4,488.6	-248.9	4,500.9	4,477.1	189.651		
6,000.0	5,997.6	5,867.8	5,865.0	21.1	3.1	-2.06	4,491.0	-251.9	4,503.6	4,479.5	186.613		
6,100.0	6,097.6	5,961.3	5,958.4	21.4	3.1	-2.11	4,493.6	-255.3	4,506.6	4,482.0	183.674		
6,200.0	6,197.6	6,056.4	6,053.4	21.8	3.2	-2.15	4,496.4	-258.9	4,509.6	4,484.7	180.824		
6,300.0	6,297.6	6,157.8	6,154.7	22.1	3.2	-2.20	4,499.5	-262.7	4,512.8	4,487.5	178.035		
6,400.0	6,397.6	6,269.5	6,266.3	22.5	3.3	-2.25	4,502.6	-267.1	4,515.8	4,490.0	175.281		
6,500.0	6,497.6	6,369.8	6,366.4	22.9	3.3	-2.30	4,505.3	-270.8	4,518.6	4,492.4	172.652		
6,600.0	6,597.6	6,466.2	6,462.8	23.2	3.4	-2.34	4,507.9	-274.3	4,521.5	4,494.9	170.120		
6,700.0	6,697.6	6,563.1	6,559.5	23.6	3.4	-2.38	4,510.6	-277.8	4,524.4	4,497.4	167.663		
6,800.0	6,797.6	6,656.4	6,652.7	23.9	3.5	-2.42	4,513.3	-281.0	4,527.5	4,500.1	165.296		
6,900.0	6,897.6	6,751.5	6,747.7	24.3	3.5	-2.46	4,516.2	-284.3	4,530.7	4,502.9	162.994		
7,000.0	6,997.6	6,849.2	6,845.4	24.6	3.6	-2.50	4,519.3	-287.6	4,533.9	4,505.7	160.750		
7,100.0	7,097.6	6,959.7	6,955.7	25.0	3.6	-2.54	4,522.7	-291.1	4,537.2	4,508.6	158.521		
7,200.0	7,197.6	7,060.6	7,056.6	25.4	3.7	-2.58	4,525.6	-294.3	4,540.1	4,511.1	156.378		
7,300.0	7,297.6	7,160.5	7,156.4	25.7	3.7	-2.62	4,528.5	-297.5	4,543.2	4,513.8	154.303		
7,400.0	7,397.6	7,257.7	7,253.5	26.1	3.8	-2.66	4,531.3	-300.6	4,546.3	4,516.4	152.291		
7,500.0	7,497.6	7,356.6	7,351.3	26.4	3.9	-2.70	4,534.3	-303.6	4,549.4	4,519.2	150.334		
7,600.0	7,597.6	7,473.2	7,468.8	26.8	3.9	-2.73	4,537.7	-306.9	4,552.4	4,521.8	148.361		
7,700.0	7,697.6	7,573.1	7,568.6	27.1	4.0	-2.77	4,540.2	-309.5	4,555.1	4,524.0	146.488		
7,800.0	7,797.6	7,685.8	7,681.3	27.5	4.0	-2.80	4,543.1	-312.2	4,557.8	4,526.3	144.624		
7,900.0	7,897.6	7,797.5	7,792.9	27.9	4.1	-2.83	4,545.6	-315.0	4,560.2	4,528.2	142.800		
8,000.0	7,997.6	7,897.7	7,893.0	28.2	4.2	-2.86	4,547.7	-317.6	4,562.4	4,530.1	141.052		
8,100.0	8,097.6	8,048.0	8,043.2	28.6	4.2	-2.91	4,550.1	-321.2	4,564.1	4,531.3	139.199		
8,200.0	8,197.6	8,173.9	8,169.1	28.9	4.3	-2.94	4,550.9	-324.2	4,564.8	4,531.6	137.435		
8,300.0	8,297.6	8,299.8	8,295.0	29.3	4.4	-2.98	4,551.1	-326.7	4,565.1	4,531.5	135.708		
8,400.0	8,397.6	8,414.1	8,409.2	29.6	4.4	-3.00	4,550.9	-329.1	4,565.0	4,530.9	134.034		
8,500.0	8,497.6	8,545.6	8,540.7	30.0	4.5	-3.05	4,549.7	-332.3	4,564.3	4,529.8	132.351		
8,600.0	8,597.6	8,676.0	8,666.0	30.4	4.6	-2.67	4,538.8	-301.9	4,559.7	4,524.8	130.641		
8,700.0	8,697.6	8,907.0	8,894.4	30.7	4.6	-2.52	4,537.8	-289.6	4,554.4	4,519.1	128.938		
8,800.0	8,797.6	8,939.0	8,923.2	31.1	4.7	-2.34	4,537.5	-275.6	4,550.9	4,515.1	127.160		
8,900.0	8,897.6	9,253.0	9,176.2	31.4	6.8	-0.04	4,528.9	-92.7	4,545.5	4,506.9	117.793		
9,000.0	8,997.6	9,265.5	9,184.5	31.8	7.0	0.08	4,528.5	-83.2	4,540.3	4,501.0	115.459		
9,100.0	9,097.6	9,284.0	9,196.1	32.1	7.2	0.26	4,528.1	-68.9	4,537.1	4,497.0	113.028		
9,200.0	9,197.6	9,297.3	9,204.1	32.5	7.4	0.40	4,527.9	-58.3	4,535.9	4,495.0	110.917		
9,210.3	9,207.9	9,298.6	9,204.9	32.5	7.4	0.41	4,527.9	-57.3	4,535.9	4,494.9	110.712		
9,300.0	9,297.6	9,316.0	9,214.9	32.9	7.7	0.59	4,527.9	-43.0	4,536.7	4,495.0	108.714		
9,400.0	9,397.6	9,316.0	9,214.9	33.2	7.7	0.59	4,527.9	-43.0	4,536.7	4,495.0	107.499		
9,500.0	9,497.6	9,332.2	9,223.7	33.6	7.9	0.76	4,528.1	-29.4	4,544.5	4,501.5	105.618		
9,600.0	9,597.6	9,347.0	9,231.3	33.9	8.2	0.92	4,528.5	-16.7	4,551.5	4,507.7	103.953		
9,700.0	9,697.6	9,347.0	9,231.3	34.3	8.2	0.92	4,528.5	-16.7	4,560.6	4,516.3	103.088		
9,800.0	9,797.6	9,378.0	9,245.8	34.6	8.7	1.27	4,529.6	10.7	4,571.6	4,526.3	100.843		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Anticollision Report



Company:	COG Operating, LLC	Local Co-ordinate Reference:	Well Fez Federal Com #705H
Project:	Lea County, NM	TVD Reference:	well @ 3291.0usft (Noram #21)
Reference Site:	Sec 9, T25-S, R35-E	MD Reference:	well @ 3291.0usft (Noram #21)
Site Error:	0.0 usft	North Reference:	Grid
Reference Well:	Fez Federal Com #705H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.0 usft	Output errors are at	2.00 sigma
Reference Wellbore	Wellbore #1	Database:	EDM 5000.1 Single User Db
Reference Design:	Design #1	Offset TVD Reference:	Offset Datum

Offset Design Sec 9, T25-S, R35-E - Fez Fee #11H - Wellbore #1 - Wellbore #1											Offset Site Error:	0.0 usft
Survey Program: 100-Good_gyro, 8700-MWD default											Offset Well Error:	0.0 usft
Reference Measured Depth (usft)	Vertical Depth (usft)	Offset Measured Depth (usft)	Vertical Depth (usft)	Semi Major Axis Reference (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N-S (usft)	Distance Between Centres (usft)	Between Ellipses (usft)	Separation Factor	Warning	
9,900.0	9,897.6	9,378.0	9,245.8	35.0	8.7	1.27	4,529.6	10.7	4,584.7	4,538.9	100.194	
10,000.0	9,997.6	9,398.6	9,254.5	35.4	9.1	1.50	4,530.4	29.3	4,599.8	4,553.1	98.642	
10,100.0	10,097.6	9,410.0	9,259.0	35.7	9.3	1.64	4,530.9	39.8	4,616.9	4,569.6	97.650	
10,200.0	10,197.6	9,442.0	9,270.2	36.1	9.9	2.01	4,532.1	69.7	4,635.9	4,587.5	95.746	
10,300.0	10,297.6	9,442.0	9,270.2	36.4	9.9	2.01	4,532.1	69.7	4,656.9	4,608.1	95.473	
10,400.0	10,397.6	9,457.3	9,274.8	36.8	10.2	2.20	4,532.6	84.2	4,679.8	4,630.3	94.544	
10,500.0	10,497.6	9,473.0	9,279.0	37.1	10.6	2.39	4,533.2	99.4	4,704.7	4,654.5	93.693	
10,600.0	10,597.6	9,473.0	9,279.0	37.5	10.6	2.39	4,533.2	99.4	4,731.5	4,681.0	93.651	
10,700.0	10,697.6	9,473.0	9,279.0	37.9	10.6	2.39	4,533.2	99.4	4,760.3	4,709.5	93.675	
10,800.0	10,797.6	9,487.4	9,282.4	38.2	10.9	2.56	4,533.6	113.4	4,790.9	4,739.5	93.097	
10,900.0	10,897.6	9,504.0	9,285.9	38.6	11.2	2.77	4,534.1	129.6	4,823.4	4,771.3	92.502	
11,000.0	10,997.6	9,504.0	9,285.9	38.9	11.2	2.77	4,534.1	129.6	4,857.7	4,805.3	92.715	
11,100.0	11,097.6	9,504.0	9,285.9	39.3	11.2	2.77	4,534.1	129.6	4,893.8	4,841.1	92.981	
11,200.0	11,197.6	9,516.1	9,288.2	39.6	11.5	2.91	4,534.5	141.4	4,931.6	4,878.4	92.764	
11,300.0	11,297.6	9,591.4	9,300.9	40.0	13.2	3.85	4,535.7	215.7	4,971.1	4,915.8	89.926	
13,200.0	12,574.9	9,626.0	9,304.9	46.3	13.9	6.55	4,535.5	250.0	4,960.6	4,904.4	88.308	
13,300.0	12,574.6	9,626.0	9,304.9	46.8	13.9	6.55	4,535.5	250.0	4,886.0	4,830.0	87.352	
13,400.0	12,574.3	9,626.0	9,304.9	47.3	13.9	6.55	4,535.5	250.0	4,812.3	4,756.6	86.404	
13,500.0	12,573.9	9,626.0	9,304.9	47.9	13.9	6.55	4,535.5	250.0	4,739.5	4,684.1	85.464	
13,600.0	12,573.6	9,626.0	9,304.9	48.6	13.9	6.55	4,535.5	250.0	4,667.8	4,612.6	84.531	
13,700.0	12,573.3	9,626.0	9,304.9	49.2	13.9	6.55	4,535.5	250.0	4,597.1	4,542.1	83.606	
13,800.0	12,573.0	9,626.0	9,304.9	50.0	13.9	6.55	4,535.5	250.0	4,527.5	4,472.8	82.687	
13,900.0	12,572.7	9,626.0	9,304.9	50.7	13.9	6.55	4,535.5	250.0	4,459.1	4,404.6	81.775	
14,000.0	12,572.4	9,626.0	9,304.9	51.6	13.9	6.55	4,535.5	250.0	4,391.9	4,337.6	80.868	
14,100.0	12,572.1	9,626.0	9,304.9	52.4	13.9	6.55	4,535.5	250.0	4,325.9	4,271.9	79.966	
14,200.0	12,571.8	9,626.0	9,304.9	53.3	13.9	6.55	4,535.5	250.0	4,261.3	4,207.4	79.068	
14,300.0	12,571.5	9,626.0	9,304.9	54.2	13.9	6.55	4,535.5	250.0	4,198.1	4,144.4	78.174	
14,400.0	12,571.1	9,626.0	9,304.9	55.2	13.9	6.55	4,535.5	250.0	4,136.3	4,082.8	77.281	
14,500.0	12,570.8	9,626.0	9,304.9	56.2	13.9	6.55	4,535.5	250.0	4,076.1	4,022.7	76.390	
14,600.0	12,570.5	9,626.0	9,304.9	57.2	13.9	6.55	4,535.5	250.0	4,017.4	3,964.2	75.499	
14,700.0	12,570.2	9,626.0	9,304.9	58.3	13.9	6.55	4,535.5	250.0	3,960.4	3,907.3	74.608	
14,800.0	12,569.9	9,626.0	9,304.9	59.3	13.9	6.55	4,535.5	250.0	3,905.1	3,852.1	73.715	
14,900.0	12,569.6	9,626.0	9,304.9	60.4	13.9	6.55	4,535.5	250.0	3,851.6	3,798.7	72.820	
15,000.0	12,569.3	9,626.0	9,304.9	61.6	13.9	6.55	4,535.5	250.0	3,800.0	3,747.2	71.923	
15,100.0	12,569.0	9,626.0	9,304.9	62.7	13.9	6.55	4,535.5	250.0	3,750.4	3,697.6	71.022	
15,200.0	12,568.7	9,626.0	9,304.9	63.9	13.9	6.55	4,535.5	250.0	3,702.8	3,650.0	70.118	
15,300.0	12,568.3	9,626.0	9,304.9	65.1	13.9	6.55	4,535.5	250.0	3,657.3	3,604.4	69.211	
15,400.0	12,568.0	9,626.0	9,304.9	66.3	13.9	6.55	4,535.5	250.0	3,614.0	3,561.0	68.302	
15,500.0	12,567.7	9,626.0	9,304.9	67.5	13.9	6.55	4,535.5	250.0	3,572.9	3,519.9	67.391	
15,600.0	12,567.4	9,626.0	9,304.9	68.8	13.9	6.55	4,535.5	250.0	3,534.3	3,481.1	66.479	
15,700.0	12,567.1	9,626.0	9,304.9	70.1	13.9	6.55	4,535.5	250.0	3,498.0	3,444.7	65.569	
15,800.0	12,566.8	9,626.0	9,304.9	71.3	13.9	6.55	4,535.5	250.0	3,464.3	3,410.7	64.662	
15,900.0	12,566.5	9,626.0	9,304.9	72.6	13.9	6.55	4,535.5	250.0	3,433.1	3,379.3	63.761	
16,000.0	12,566.2	9,626.0	9,304.9	73.9	13.9	6.55	4,535.5	250.0	3,404.6	3,350.5	62.868	
16,100.0	12,565.9	9,626.0	9,304.9	75.3	13.9	6.55	4,535.5	250.0	3,378.9	3,324.4	61.987	
16,200.0	12,565.5	9,626.0	9,304.9	76.6	13.9	6.55	4,535.5	250.0	3,355.9	3,301.0	61.121	
16,300.0	12,565.2	9,626.0	9,304.9	78.0	13.9	6.55	4,535.5	250.0	3,335.7	3,280.4	60.273	
16,400.0	12,564.9	9,626.0	9,304.9	79.3	13.9	6.55	4,535.5	250.0	3,318.5	3,262.6	59.447	
16,500.0	12,564.6	9,626.0	9,304.9	80.7	13.9	6.55	4,535.5	250.0	3,304.1	3,247.8	58.647	
16,600.0	12,564.3	9,626.0	9,304.9	82.1	13.9	6.55	4,535.5	250.0	3,292.8	3,235.9	57.875	
16,700.0	12,564.0	9,626.0	9,304.9	83.5	13.9	6.55	4,535.5	250.0	3,284.4	3,227.0	57.136	
16,800.0	12,563.7	9,612.4	9,303.6	84.9	13.6	6.31	4,535.6	236.5	3,278.9	3,220.9	56.534	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Anticollision Report



Company:	COG Operating, LLC	Local Co-ordinate Reference:	Well Fez Federal Com #705H
Project:	Lea County, NM	TVD Reference:	well @ 3291.0usft (Noram #21)
Reference Site:	Sec 9, T25-S, R35-E	MD Reference:	well @ 3291.0usft (Noram #21)
Site Error:	0.0 usft	North Reference:	Grid
Reference Well:	Fez Federal Com #705H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.0 usft	Output errors are at	2.00 sigma
Reference Wellbore:	Wellbore #1	Database:	EDM 5000.1 Single User Db
Reference Design:	Design #1	Offset TVD Reference:	Offset Datum


Offset Design:	Sec 9, T25-S, R35-E - Fez Fee #11H - Wellbore #1 - Wellbore #1										Offset Site Error:	0.0 usft
Survey Program:	100-Good gyro, 8700-MWD default										Offset Well Error:	0.0 usft
Reference Measured Depth (usft)	Vertical Depth (usft)	Offset Measured Depth (usft)	Vertical Depth (usft)	Semi Major Axis Reference (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	+E/-W (usft)	Distance Between Centres (usft)	Between Ellipses (usft)	Separation Factor	Warning
16,900.0	12,563.4	9,612.2	9,303.6	86.3	13.6	6.31	4,535.6	236.3	3,276.6	3,218.0	55.867	
16,924.5	12,563.3	9,612.1	9,303.6	86.6	13.6	6.31	4,535.6	236.2	3,276.6	3,217.7	55.710	CC, ES
17,000.0	12,563.1	9,612.0	9,303.6	87.7	13.6	6.31	4,535.6	236.1	3,277.4	3,218.1	55.244	
17,100.0	12,562.7	9,611.8	9,303.6	89.1	13.6	6.30	4,535.6	235.9	3,281.3	3,221.2	54.668	
17,200.0	12,562.4	9,611.6	9,303.5	90.6	13.6	6.30	4,535.6	235.7	3,288.1	3,227.4	54.141	
17,300.0	12,562.1	9,611.4	9,303.5	92.0	13.6	6.30	4,535.6	235.5	3,298.0	3,236.5	53.667	
17,400.0	12,561.8	9,611.2	9,303.5	93.5	13.6	6.29	4,535.6	235.3	3,310.9	3,248.7	53.246	
17,500.0	12,561.5	9,611.0	9,303.5	94.9	13.6	6.29	4,535.6	235.1	3,326.7	3,263.8	52.881	
17,600.0	12,561.2	9,610.8	9,303.5	96.4	13.6	6.29	4,535.6	234.9	3,345.5	3,281.8	52.572	
17,700.0	12,560.9	9,610.6	9,303.4	97.8	13.6	6.28	4,535.6	234.7	3,367.1	3,302.7	52.322	
17,800.0	12,560.6	9,610.4	9,303.4	99.3	13.6	6.28	4,535.6	234.6	3,391.5	3,326.4	52.129	
17,900.0	12,560.3	9,610.2	9,303.4	100.8	13.6	6.28	4,535.6	234.4	3,418.7	3,352.9	51.994	
18,000.0	12,559.9	9,610.1	9,303.4	102.3	13.6	6.27	4,535.6	234.2	3,448.5	3,382.1	51.916	
18,100.0	12,559.6	9,609.9	9,303.3	103.8	13.6	6.27	4,535.6	234.0	3,481.0	3,414.0	51.894	SF
18,200.0	12,559.3	9,609.7	9,303.3	105.3	13.6	6.27	4,535.6	233.8	3,516.1	3,448.3	51.929	
18,300.0	12,559.0	9,609.5	9,303.3	106.8	13.6	6.26	4,535.6	233.6	3,553.6	3,485.2	52.017	
18,400.0	12,558.7	9,609.3	9,303.3	108.3	13.6	6.26	4,535.6	233.5	3,593.4	3,524.5	52.157	
18,500.0	12,558.4	9,609.1	9,303.3	109.8	13.6	6.26	4,535.6	233.3	3,635.6	3,566.2	52.349	
18,600.0	12,558.1	9,609.0	9,303.2	111.3	13.6	6.25	4,535.6	233.1	3,680.1	3,610.1	52.589	
18,700.0	12,557.8	9,608.8	9,303.2	112.8	13.6	6.25	4,535.6	232.9	3,726.7	3,656.2	52.877	
18,800.0	12,557.5	9,608.6	9,303.2	114.3	13.5	6.25	4,535.6	232.7	3,775.3	3,704.4	53.210	
18,900.0	12,557.1	9,595.0	9,301.4	115.8	13.2	6.01	4,535.7	219.2	3,826.2	3,755.0	53.709	
19,000.0	12,556.8	9,595.0	9,301.4	117.4	13.2	6.01	4,535.7	219.2	3,878.8	3,807.1	54.129	
19,100.0	12,556.5	9,595.0	9,301.4	118.9	13.2	6.01	4,535.7	219.2	3,933.2	3,861.1	54.588	
19,200.0	12,556.2	9,595.0	9,301.4	120.4	13.2	6.01	4,535.7	219.2	3,989.3	3,916.9	55.085	
19,300.0	12,555.9	9,595.0	9,301.4	122.0	13.2	6.01	4,535.7	219.2	4,047.2	3,974.4	55.618	
19,400.0	12,555.6	9,595.0	9,301.4	123.5	13.2	6.01	4,535.7	219.2	4,106.7	4,033.6	56.185	
19,500.0	12,555.3	9,595.0	9,301.4	125.1	13.2	6.01	4,535.7	219.2	4,167.7	4,094.3	56.785	
19,600.0	12,555.0	9,595.0	9,301.4	126.6	13.2	6.01	4,535.7	219.2	4,230.3	4,156.6	57.416	
19,700.0	12,554.7	9,595.0	9,301.4	128.1	13.2	6.01	4,535.7	219.2	4,294.2	4,220.3	58.076	
19,800.0	12,554.3	9,595.0	9,301.4	129.7	13.2	6.01	4,535.7	219.2	4,359.5	4,285.3	58.764	
19,900.0	12,554.0	9,595.0	9,301.4	131.2	13.2	6.01	4,535.7	219.2	4,426.1	4,351.7	59.479	
20,000.0	12,553.7	9,595.0	9,301.4	132.8	13.2	6.01	4,535.7	219.2	4,493.9	4,419.3	60.218	
20,100.0	12,553.4	9,595.0	9,301.4	134.4	13.2	6.01	4,535.7	219.2	4,562.9	4,488.1	60.981	
20,200.0	12,553.1	9,595.0	9,301.4	135.9	13.2	6.01	4,535.7	219.2	4,633.1	4,558.1	61.767	
20,300.0	12,552.8	9,595.0	9,301.4	137.5	13.2	6.01	4,535.7	219.2	4,704.3	4,629.1	62.574	
20,400.0	12,552.5	9,595.0	9,301.4	139.0	13.2	6.01	4,535.7	219.2	4,776.6	4,701.2	63.400	
20,500.0	12,552.2	9,595.0	9,301.4	140.6	13.2	6.01	4,535.7	219.2	4,849.8	4,774.3	64.246	
20,600.0	12,551.9	9,595.0	9,301.4	142.2	13.2	6.01	4,535.7	219.2	4,924.0	4,848.4	65.110	
20,700.0	12,551.5	9,595.0	9,301.4	143.7	13.2	6.01	4,535.7	219.2	4,999.1	4,923.3	65.991	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

Company:	COG Operating, LLC	Local Co-ordinate Reference:	Well Fez Federal Com #705H
Project:	Lea County, NM	TVD Reference:	well @ 3291.0usft (Noram #21)
Reference Site:	Sec 9, T25-S, R35-E	MD Reference:	well @ 3291.0usft (Noram #21)
Site Error:	0.0 usft	North Reference:	Grid
Reference Well:	Fez Federal Com #705H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.0 usft	Output errors are at	2.00 sigma
Reference Wellbore	Wellbore #1	Database:	EDM 5000.1 Single User Db
Reference Design:	Design #1	Offset TVD Reference:	Offset Datum

Reference Depths are relative to well @ 3291.0usft (Noram #21)
 Offset Depths are relative to Offset Datum
 Central Meridian is 104° 20' 0.000 W

Coordinates are relative to: Fez Federal Com #705H
 Coordinate System is US State Plane 1927 (Exact solution), New Mexico East 30
 Grid Convergence at Surface is: 0.51°




Company: COG Operating, LLC
Project: Lea County, NM
Reference Site: Sec 9, T25-S, R35-E
Site Error: 0.0 usft
Reference Well: Fez Federal Com #705H
Well Error: 0.0 usft
Reference Wellbore: Wellbore #1
Reference Design: Design #1

Local Co-ordinate Reference: Well Fez Federal Com #705H
TVD Reference: well @ 3291.0usft (Noram #21)
MD Reference: well @ 3291.0usft (Noram #21)
North Reference: Grid
Survey Calculation Method: Minimum Curvature
Output errors are at: 2.00 sigma
Database: EDM 5000.1 Single User Db
Offset TVD Reference: Offset Datum

Reference Depths are relative to well @ 3291.0usft (Noram #21)
 Offset Depths are relative to Offset Datum
 Central Meridian is 104° 20' 0.000 W

Coordinates are relative to: Fez Federal Com #705H
 Coordinate System is US State Plane 1927 (Exact solution), New Mexico East 30
 Grid Convergence at Surface is: 0.51°

Separation Factor Plot



LEGEND

Fez Federal Com #704H, Wellbore #1, Design #1 V0  Fez Federal Com #604H, Wellbore #1, Design #1 V0  Fez Fee #11H, Wellbore #1, Wellbore #1 V0



COG Operating, LLC

Lea County, NM

Sec 9, T25-S, R35-E

Fez Federal Com #705H

Wellbore #1

Plan: Design #1

QES Well Planning Report

28 February, 2018





Well Planning Report



Database:	EDM 5000.1 Single User Db	Local Co-ordinate Reference:	Well Fez Federal Com #705H
Company:	COG Operating, LLC	TVD Reference:	well @ 3291.0usft (Noram #21)
Project:	Lea County, NM	MD Reference:	well @ 3291.0usft (Noram #21)
Site:	Sec 9, T25-S, R35-E	North Reference:	Grid
Well:	Fez Federal Com #705H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Design #1		

Project	Lea County, NM		
Map System:	US State Plane 1927 (Exact solution)	System Datum:	Mean Sea Level
Geo Datum:	NAD 1927 (NADCON CONUS)		
Map Zone:	New Mexico East 3001		

Site	Sec 9, T25-S, R35-E		
Site Position:		Northing:	419,852.10 usft
From:	Map	Easting:	795,067.30 usft
Position Uncertainty:	0.0 usft	Slot Radius:	13-3/16"
		Latitude:	32° 9' 2.515 N
		Longitude:	103° 22' 47.797 W
		Grid Convergence:	0.51°

Well	Fez Federal Com #705H		
Well Position	+N/-S	-4,515.4 usft	Northing: 415,336.73 usft
	+E/-W	270.2 usft	Easting: 795,337.48 usft
Position Uncertainty	0.0 usft	Wellhead Elevation:	Ground Level: 3,262.0 usft
		Latitude:	32° 8' 17.812 N
		Longitude:	103° 22' 45.120 W

Wellbore	Wellbore #1		
Magnetics	Model Name	Sample Date	Declination
			(°)
	IGRF2015	2/22/2018	6.78
			Dip Angle (°)
			60.01
			Field Strength (nT)
			47,838.04758685

Design	Design #1		
Audit Notes:			
Version:	Phase:	PLAN	Tie On Depth: 0.0
Vertical Section:	Depth From (TVD)	+N/-S	+E/-W
	(usft)	(usft)	(usft)
	0.0	0.0	0.0
			Direction (°)
			359.06

Plan Sections										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	TFO (°)	Target
0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.00	0.00	
1,000.0	0.00	0.00	1,000.0	0.0	0.0	0.00	0.00	0.00	0.00	
1,100.0	2.00	265.00	1,100.0	-0.2	-1.7	2.00	2.00	0.00	265.00	
2,000.6	2.00	265.00	2,000.0	-2.9	-33.0	0.00	0.00	0.00	0.00	
2,100.6	4.00	265.00	2,099.9	-3.3	-38.3	2.00	2.00	0.00	0.00	
2,742.3	4.00	265.00	2,740.0	-7.2	-82.9	0.00	0.00	0.00	0.00	
2,942.3	0.00	0.00	2,939.8	-7.9	-89.8	2.00	-2.00	0.00	180.00	
12,100.9	0.00	0.00	12,098.5	-7.9	-89.8	0.00	0.00	0.00	0.00	
12,852.4	90.18	359.57	12,576.0	471.1	-93.4	12.00	12.00	-0.06	359.57	
22,483.7	90.18	359.57	12,546.0	10,102.1	-165.6	0.00	0.00	0.00	0.00	PBHL- Fez Fed Coi

Database:	EDM 5000.1 Single User Db	Local Co-ordinate Reference:	Well Fez Federal Com #705H
Company:	COG Operating, LLC	TVD Reference:	well @ 3291.0usft (Noram #21)
Project:	Lea County, NM	MD Reference:	well @ 3291.0usft (Noram #21)
Site:	Sec 9, T25-S, R35-E	North Reference:	Grid
Well:	Fez Federal Com #705H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Design #1		

Planned Survey									
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
0.0	0.00	0.00	0.0	0.0	0.0	0.0	0.00	0.00	0.00
100.0	0.00	0.00	100.0	0.0	0.0	0.0	0.00	0.00	0.00
200.0	0.00	0.00	200.0	0.0	0.0	0.0	0.00	0.00	0.00
300.0	0.00	0.00	300.0	0.0	0.0	0.0	0.00	0.00	0.00
400.0	0.00	0.00	400.0	0.0	0.0	0.0	0.00	0.00	0.00
500.0	0.00	0.00	500.0	0.0	0.0	0.0	0.00	0.00	0.00
600.0	0.00	0.00	600.0	0.0	0.0	0.0	0.00	0.00	0.00
700.0	0.00	0.00	700.0	0.0	0.0	0.0	0.00	0.00	0.00
800.0	0.00	0.00	800.0	0.0	0.0	0.0	0.00	0.00	0.00
Rustler									
872.0	0.00	0.00	872.0	0.0	0.0	0.0	0.00	0.00	0.00
900.0	0.00	0.00	900.0	0.0	0.0	0.0	0.00	0.00	0.00
Build 2.00°/100'									
1,000.0	0.00	0.00	1,000.0	0.0	0.0	0.0	0.00	0.00	0.00
EOB: 2.00° Inc, 265.00° Azi									
1,100.0	2.00	265.00	1,100.0	-0.2	-1.7	-0.1	2.00	2.00	0.00
1,200.0	2.00	265.00	1,199.9	-0.5	-5.2	-0.4	0.00	0.00	0.00
TOS									
1,213.1	2.00	265.00	1,213.0	-0.5	-5.7	-0.4	0.00	0.00	0.00
1,300.0	2.00	265.00	1,299.9	-0.8	-8.7	-0.6	0.00	0.00	0.00
1,400.0	2.00	265.00	1,399.8	-1.1	-12.2	-0.9	0.00	0.00	0.00
1,500.0	2.00	265.00	1,499.7	-1.4	-15.6	-1.1	0.00	0.00	0.00
1,600.0	2.00	265.00	1,599.7	-1.7	-19.1	-1.4	0.00	0.00	0.00
1,700.0	2.00	265.00	1,699.6	-2.0	-22.6	-1.6	0.00	0.00	0.00
1,800.0	2.00	265.00	1,799.6	-2.3	-26.1	-1.9	0.00	0.00	0.00
1,900.0	2.00	265.00	1,899.5	-2.6	-29.6	-2.1	0.00	0.00	0.00
Build/Turn 2.00°/100'									
2,000.6	2.00	265.00	2,000.0	-2.9	-33.0	-2.3	0.00	0.00	0.00
EOBT: 4.00° Inc, 265.00° Azi									
2,100.6	4.00	265.00	2,099.9	-3.3	-38.3	-2.7	2.00	2.00	0.00
2,200.0	4.00	265.00	2,199.0	-4.0	-45.2	-3.2	0.00	0.00	0.00
2,300.0	4.00	265.00	2,298.8	-4.6	-52.1	-3.7	0.00	0.00	0.00
2,400.0	4.00	265.00	2,398.6	-5.2	-59.1	-4.2	0.00	0.00	0.00
2,500.0	4.00	265.00	2,498.3	-5.8	-66.0	-4.7	0.00	0.00	0.00
2,600.0	4.00	265.00	2,598.1	-6.4	-73.0	-5.2	0.00	0.00	0.00
2,700.0	4.00	265.00	2,697.8	-7.0	-79.9	-5.7	0.00	0.00	0.00
Drop 2.00°/100'									
2,742.3	4.00	265.00	2,740.0	-7.2	-82.9	-5.9	0.00	0.00	0.00
2,800.0	2.85	265.00	2,797.6	-7.5	-86.3	-6.1	2.00	-2.00	0.00
2,900.0	0.85	265.00	2,897.6	-7.8	-89.5	-6.4	2.00	-2.00	0.00
EOD: 0.00° Inc, 0.00° Azi									
2,942.3	0.00	0.00	2,939.8	-7.9	-89.8	-6.4	2.00	-2.00	0.00
3,000.0	0.00	0.00	2,997.6	-7.9	-89.8	-6.4	0.00	0.00	0.00
3,100.0	0.00	0.00	3,097.6	-7.9	-89.8	-6.4	0.00	0.00	0.00
3,200.0	0.00	0.00	3,197.6	-7.9	-89.8	-6.4	0.00	0.00	0.00
3,300.0	0.00	0.00	3,297.6	-7.9	-89.8	-6.4	0.00	0.00	0.00
3,400.0	0.00	0.00	3,397.6	-7.9	-89.8	-6.4	0.00	0.00	0.00
3,500.0	0.00	0.00	3,497.6	-7.9	-89.8	-6.4	0.00	0.00	0.00
3,600.0	0.00	0.00	3,597.6	-7.9	-89.8	-6.4	0.00	0.00	0.00
3,700.0	0.00	0.00	3,697.6	-7.9	-89.8	-6.4	0.00	0.00	0.00
3,800.0	0.00	0.00	3,797.6	-7.9	-89.8	-6.4	0.00	0.00	0.00
3,900.0	0.00	0.00	3,897.6	-7.9	-89.8	-6.4	0.00	0.00	0.00
4,000.0	0.00	0.00	3,997.6	-7.9	-89.8	-6.4	0.00	0.00	0.00

Database:	EDM 5000.1 Single User Db	Local Co-ordinate Reference:	Well Fez Federal Com #705H
Company:	COG Operating, LLC	TVD Reference:	well @ 3291.0usft (Noram #21)
Project:	Lea County, NM	MD Reference:	well @ 3291.0usft (Noram #21)
Site:	Sec 9, T25-S, R35-E	North Reference:	Grid
Well:	Fez Federal Com #705H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Design #1		

Planned Survey										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	
4,100.0	0.00	0.00	4,097.6	-7.9	-89.8	-6.4	0.00	0.00	0.00	
4,200.0	0.00	0.00	4,197.6	-7.9	-89.8	-6.4	0.00	0.00	0.00	
4,300.0	0.00	0.00	4,297.6	-7.9	-89.8	-6.4	0.00	0.00	0.00	
4,400.0	0.00	0.00	4,397.6	-7.9	-89.8	-6.4	0.00	0.00	0.00	
4,500.0	0.00	0.00	4,497.6	-7.9	-89.8	-6.4	0.00	0.00	0.00	
4,600.0	0.00	0.00	4,597.6	-7.9	-89.8	-6.4	0.00	0.00	0.00	
4,700.0	0.00	0.00	4,697.6	-7.9	-89.8	-6.4	0.00	0.00	0.00	
4,800.0	0.00	0.00	4,797.6	-7.9	-89.8	-6.4	0.00	0.00	0.00	
4,900.0	0.00	0.00	4,897.6	-7.9	-89.8	-6.4	0.00	0.00	0.00	
5,000.0	0.00	0.00	4,997.6	-7.9	-89.8	-6.4	0.00	0.00	0.00	
BOS (Fletcher)										
5,010.4	0.00	0.00	5,008.0	-7.9	-89.8	-6.4	0.00	0.00	0.00	
5,100.0	0.00	0.00	5,097.6	-7.9	-89.8	-6.4	0.00	0.00	0.00	
5,200.0	0.00	0.00	5,197.6	-7.9	-89.8	-6.4	0.00	0.00	0.00	
5,300.0	0.00	0.00	5,297.6	-7.9	-89.8	-6.4	0.00	0.00	0.00	
LMAR (Top Delaware)										
5,341.4	0.00	0.00	5,339.0	-7.9	-89.8	-6.4	0.00	0.00	0.00	
BLCN										
5,373.4	0.00	0.00	5,371.0	-7.9	-89.8	-6.4	0.00	0.00	0.00	
5,400.0	0.00	0.00	5,397.6	-7.9	-89.8	-6.4	0.00	0.00	0.00	
5,500.0	0.00	0.00	5,497.6	-7.9	-89.8	-6.4	0.00	0.00	0.00	
5,600.0	0.00	0.00	5,597.6	-7.9	-89.8	-6.4	0.00	0.00	0.00	
5,700.0	0.00	0.00	5,697.6	-7.9	-89.8	-6.4	0.00	0.00	0.00	
5,800.0	0.00	0.00	5,797.6	-7.9	-89.8	-6.4	0.00	0.00	0.00	
5,900.0	0.00	0.00	5,897.6	-7.9	-89.8	-6.4	0.00	0.00	0.00	
6,000.0	0.00	0.00	5,997.6	-7.9	-89.8	-6.4	0.00	0.00	0.00	
6,100.0	0.00	0.00	6,097.6	-7.9	-89.8	-6.4	0.00	0.00	0.00	
6,200.0	0.00	0.00	6,197.6	-7.9	-89.8	-6.4	0.00	0.00	0.00	
6,300.0	0.00	0.00	6,297.6	-7.9	-89.8	-6.4	0.00	0.00	0.00	
CYCN										
6,312.4	0.00	0.00	6,310.0	-7.9	-89.8	-6.4	0.00	0.00	0.00	
6,400.0	0.00	0.00	6,397.6	-7.9	-89.8	-6.4	0.00	0.00	0.00	
6,500.0	0.00	0.00	6,497.6	-7.9	-89.8	-6.4	0.00	0.00	0.00	
6,600.0	0.00	0.00	6,597.6	-7.9	-89.8	-6.4	0.00	0.00	0.00	
6,700.0	0.00	0.00	6,697.6	-7.9	-89.8	-6.4	0.00	0.00	0.00	
6,800.0	0.00	0.00	6,797.6	-7.9	-89.8	-6.4	0.00	0.00	0.00	
6,900.0	0.00	0.00	6,897.6	-7.9	-89.8	-6.4	0.00	0.00	0.00	
7,000.0	0.00	0.00	6,997.6	-7.9	-89.8	-6.4	0.00	0.00	0.00	
7,100.0	0.00	0.00	7,097.6	-7.9	-89.8	-6.4	0.00	0.00	0.00	
7,200.0	0.00	0.00	7,197.6	-7.9	-89.8	-6.4	0.00	0.00	0.00	
7,300.0	0.00	0.00	7,297.6	-7.9	-89.8	-6.4	0.00	0.00	0.00	
7,400.0	0.00	0.00	7,397.6	-7.9	-89.8	-6.4	0.00	0.00	0.00	
7,500.0	0.00	0.00	7,497.6	-7.9	-89.8	-6.4	0.00	0.00	0.00	
7,600.0	0.00	0.00	7,597.6	-7.9	-89.8	-6.4	0.00	0.00	0.00	
7,700.0	0.00	0.00	7,697.6	-7.9	-89.8	-6.4	0.00	0.00	0.00	
BYCN										
7,772.4	0.00	0.00	7,770.0	-7.9	-89.8	-6.4	0.00	0.00	0.00	
7,800.0	0.00	0.00	7,797.6	-7.9	-89.8	-6.4	0.00	0.00	0.00	
7,900.0	0.00	0.00	7,897.6	-7.9	-89.8	-6.4	0.00	0.00	0.00	
8,000.0	0.00	0.00	7,997.6	-7.9	-89.8	-6.4	0.00	0.00	0.00	
8,100.0	0.00	0.00	8,097.6	-7.9	-89.8	-6.4	0.00	0.00	0.00	
8,200.0	0.00	0.00	8,197.6	-7.9	-89.8	-6.4	0.00	0.00	0.00	
8,300.0	0.00	0.00	8,297.6	-7.9	-89.8	-6.4	0.00	0.00	0.00	
8,400.0	0.00	0.00	8,397.6	-7.9	-89.8	-6.4	0.00	0.00	0.00	

Database:	EDM 5000.1 Single User Db	Local Co-ordinate Reference:	Well Fez Federal Com #705H
Company:	COG Operating, LLC	TVD Reference:	well @ 3291.0usft (Noram #21)
Project:	Lea County, NM	MD Reference:	well @ 3291.0usft (Noram #21)
Site:	Sec 9, T25-S, R35-E	North Reference:	Grid
Well:	Fez Federal Com #705H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Design #1		

Planned Survey									
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
8,500.0	0.00	0.00	8,497.6	-7.9	-89.8	-6.4	0.00	0.00	0.00
8,600.0	0.00	0.00	8,597.6	-7.9	-89.8	-6.4	0.00	0.00	0.00
8,700.0	0.00	0.00	8,697.6	-7.9	-89.8	-6.4	0.00	0.00	0.00
8,800.0	0.00	0.00	8,797.6	-7.9	-89.8	-6.4	0.00	0.00	0.00
8,900.0	0.00	0.00	8,897.6	-7.9	-89.8	-6.4	0.00	0.00	0.00
9,000.0	0.00	0.00	8,997.6	-7.9	-89.8	-6.4	0.00	0.00	0.00
Bone Sprg (BSGL)									
9,003.4	0.00	0.00	9,001.0	-7.9	-89.8	-6.4	0.00	0.00	0.00
9,100.0	0.00	0.00	9,097.6	-7.9	-89.8	-6.4	0.00	0.00	0.00
9,200.0	0.00	0.00	9,197.6	-7.9	-89.8	-6.4	0.00	0.00	0.00
U Avalon Sh									
9,220.4	0.00	0.00	9,218.0	-7.9	-89.8	-6.4	0.00	0.00	0.00
9,300.0	0.00	0.00	9,297.6	-7.9	-89.8	-6.4	0.00	0.00	0.00
9,400.0	0.00	0.00	9,397.6	-7.9	-89.8	-6.4	0.00	0.00	0.00
9,500.0	0.00	0.00	9,497.6	-7.9	-89.8	-6.4	0.00	0.00	0.00
L Avalon Sh									
9,584.4	0.00	0.00	9,582.0	-7.9	-89.8	-6.4	0.00	0.00	0.00
9,600.0	0.00	0.00	9,597.6	-7.9	-89.8	-6.4	0.00	0.00	0.00
9,700.0	0.00	0.00	9,697.6	-7.9	-89.8	-6.4	0.00	0.00	0.00
9,800.0	0.00	0.00	9,797.6	-7.9	-89.8	-6.4	0.00	0.00	0.00
9,900.0	0.00	0.00	9,897.6	-7.9	-89.8	-6.4	0.00	0.00	0.00
10,000.0	0.00	0.00	9,997.6	-7.9	-89.8	-6.4	0.00	0.00	0.00
10,100.0	0.00	0.00	10,097.6	-7.9	-89.8	-6.4	0.00	0.00	0.00
10,200.0	0.00	0.00	10,197.6	-7.9	-89.8	-6.4	0.00	0.00	0.00
10,300.0	0.00	0.00	10,297.6	-7.9	-89.8	-6.4	0.00	0.00	0.00
10,400.0	0.00	0.00	10,397.6	-7.9	-89.8	-6.4	0.00	0.00	0.00
FBSG_sand									
10,401.4	0.00	0.00	10,399.0	-7.9	-89.8	-6.4	0.00	0.00	0.00
10,500.0	0.00	0.00	10,497.6	-7.9	-89.8	-6.4	0.00	0.00	0.00
10,600.0	0.00	0.00	10,597.6	-7.9	-89.8	-6.4	0.00	0.00	0.00
10,700.0	0.00	0.00	10,697.6	-7.9	-89.8	-6.4	0.00	0.00	0.00
10,800.0	0.00	0.00	10,797.6	-7.9	-89.8	-6.4	0.00	0.00	0.00
10,900.0	0.00	0.00	10,897.6	-7.9	-89.8	-6.4	0.00	0.00	0.00
SBSG_sand									
10,921.4	0.00	0.00	10,919.0	-7.9	-89.8	-6.4	0.00	0.00	0.00
11,000.0	0.00	0.00	10,997.6	-7.9	-89.8	-6.4	0.00	0.00	0.00
11,100.0	0.00	0.00	11,097.6	-7.9	-89.8	-6.4	0.00	0.00	0.00
11,200.0	0.00	0.00	11,197.6	-7.9	-89.8	-6.4	0.00	0.00	0.00
11,300.0	0.00	0.00	11,297.6	-7.9	-89.8	-6.4	0.00	0.00	0.00
SBSG_sand base									
11,395.4	0.00	0.00	11,393.0	-7.9	-89.8	-6.4	0.00	0.00	0.00
11,400.0	0.00	0.00	11,397.6	-7.9	-89.8	-6.4	0.00	0.00	0.00
11,500.0	0.00	0.00	11,497.6	-7.9	-89.8	-6.4	0.00	0.00	0.00
11,600.0	0.00	0.00	11,597.6	-7.9	-89.8	-6.4	0.00	0.00	0.00
11,700.0	0.00	0.00	11,697.6	-7.9	-89.8	-6.4	0.00	0.00	0.00
11,800.0	0.00	0.00	11,797.6	-7.9	-89.8	-6.4	0.00	0.00	0.00
11,900.0	0.00	0.00	11,897.6	-7.9	-89.8	-6.4	0.00	0.00	0.00
TBSG_sand									
11,978.4	0.00	0.00	11,976.0	-7.9	-89.8	-6.4	0.00	0.00	0.00
12,000.0	0.00	0.00	11,997.6	-7.9	-89.8	-6.4	0.00	0.00	0.00
KOP : Build 12.00°/100'									
12,100.9	0.00	0.00	12,098.5	-7.9	-89.8	-6.4	0.00	0.00	0.00
12,125.0	2.89	359.57	12,122.6	-7.3	-89.8	-5.8	12.00	12.00	0.00

Database:	EDM 5000.1 Single User Db	Local Co-ordinate Reference:	Well Fez Federal Com #705H
Company:	COG Operating, LLC	TVD Reference:	well @ 3291.0usft (Noram #21)
Project:	Lea County, NM	MD Reference:	well @ 3291.0usft (Noram #21)
Site:	Sec 9, T25-S, R35-E	North Reference:	Grid
Well:	Fez Federal Com #705H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Design #1		

Planned Survey									
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
12,150.0	5.89	359.57	12,147.5	-5.3	-89.8	-3.9	12.00	12.00	0.00
12,175.0	8.89	359.57	12,172.3	-2.1	-89.8	-0.7	12.00	12.00	0.00
12,200.0	11.89	359.57	12,196.9	2.4	-89.9	3.9	12.00	12.00	0.00
12,225.0	14.89	359.57	12,221.2	8.2	-89.9	9.6	12.00	12.00	0.00
12,250.0	17.89	359.57	12,245.2	15.2	-90.0	16.7	12.00	12.00	0.00
12,275.0	20.89	359.57	12,268.7	23.5	-90.0	25.0	12.00	12.00	0.00
12,300.0	23.89	359.57	12,291.8	33.0	-90.1	34.5	12.00	12.00	0.00
12,325.0	26.89	359.57	12,314.4	43.8	-90.2	45.2	12.00	12.00	0.00
12,350.0	29.89	359.57	12,336.4	55.6	-90.3	57.1	12.00	12.00	0.00
12,375.0	32.89	359.57	12,357.8	68.7	-90.4	70.1	12.00	12.00	0.00
12,400.0	35.89	359.57	12,378.4	82.8	-90.5	84.3	12.00	12.00	0.00
WFMP									
12,402.0	36.13	359.57	12,380.0	83.9	-90.5	85.4	12.00	12.00	0.00
12,425.0	38.89	359.57	12,398.2	98.0	-90.6	99.4	12.00	12.00	0.00
12,450.0	41.89	359.57	12,417.3	114.2	-90.7	115.6	12.00	12.00	0.00
12,475.0	44.89	359.57	12,435.5	131.3	-90.8	132.8	12.00	12.00	0.00
12,500.0	47.89	359.57	12,452.7	149.4	-91.0	150.9	12.00	12.00	0.00
12,525.0	50.89	359.57	12,469.0	168.4	-91.1	169.9	12.00	12.00	0.00
WFMP Lith									
12,528.2	51.28	359.57	12,471.0	170.9	-91.1	172.4	12.00	12.00	0.00
12,550.0	53.89	359.57	12,484.2	188.2	-91.3	189.7	12.00	12.00	0.00
12,575.0	56.89	359.57	12,498.4	208.8	-91.4	210.2	12.00	12.00	0.00
12,600.0	59.89	359.57	12,511.5	230.1	-91.6	231.5	12.00	12.00	0.00
12,625.0	62.89	359.57	12,523.5	252.0	-91.8	253.5	12.00	12.00	0.00
12,650.0	65.89	359.57	12,534.3	274.5	-91.9	276.0	12.00	12.00	0.00
12,675.0	68.89	359.57	12,543.9	297.6	-92.1	299.1	12.00	12.00	0.00
12,700.0	71.89	359.57	12,552.3	321.2	-92.3	322.6	12.00	12.00	0.00
12,725.0	74.89	359.57	12,559.5	345.1	-92.5	346.6	12.00	12.00	0.00
12,750.0	77.89	359.57	12,565.3	369.4	-92.6	370.9	12.00	12.00	0.00
12,775.0	80.89	359.57	12,569.9	394.0	-92.8	395.4	12.00	12.00	0.00
12,800.0	83.89	359.57	12,573.3	418.8	-93.0	420.2	12.00	12.00	0.00
12,825.0	86.89	359.57	12,575.3	443.7	-93.2	445.1	12.00	12.00	0.00
EOC: 90.18° Inc, 359.57° Azi, 12576.0' TVD									
12,852.4	90.18	359.57	12,576.0	471.1	-93.4	472.5	12.00	12.00	0.00
12,900.0	90.18	359.57	12,575.8	518.7	-93.8	520.1	0.00	0.00	0.00
13,000.0	90.18	359.57	12,575.5	618.7	-94.5	620.1	0.00	0.00	0.00
13,100.0	90.18	359.57	12,575.2	718.6	-95.3	720.1	0.00	0.00	0.00
13,200.0	90.18	359.57	12,574.9	818.6	-96.0	820.1	0.00	0.00	0.00
13,300.0	90.18	359.57	12,574.6	918.6	-96.8	920.1	0.00	0.00	0.00
13,400.0	90.18	359.57	12,574.3	1,018.6	-97.5	1,020.1	0.00	0.00	0.00
13,500.0	90.18	359.57	12,573.9	1,118.6	-98.2	1,120.1	0.00	0.00	0.00
13,600.0	90.18	359.57	12,573.6	1,218.6	-99.0	1,220.1	0.00	0.00	0.00
13,700.0	90.18	359.57	12,573.3	1,318.6	-99.7	1,320.1	0.00	0.00	0.00
13,800.0	90.18	359.57	12,573.0	1,418.6	-100.5	1,420.1	0.00	0.00	0.00
13,900.0	90.18	359.57	12,572.7	1,518.6	-101.2	1,520.1	0.00	0.00	0.00
14,000.0	90.18	359.57	12,572.4	1,618.6	-102.0	1,620.1	0.00	0.00	0.00
14,100.0	90.18	359.57	12,572.1	1,718.6	-102.7	1,720.1	0.00	0.00	0.00
14,200.0	90.18	359.57	12,571.8	1,818.6	-103.5	1,820.1	0.00	0.00	0.00
14,300.0	90.18	359.57	12,571.5	1,918.6	-104.2	1,920.1	0.00	0.00	0.00
14,400.0	90.18	359.57	12,571.1	2,018.6	-105.0	2,020.1	0.00	0.00	0.00
14,500.0	90.18	359.57	12,570.8	2,118.6	-105.7	2,120.1	0.00	0.00	0.00
14,600.0	90.18	359.57	12,570.5	2,218.6	-106.5	2,220.1	0.00	0.00	0.00
14,700.0	90.18	359.57	12,570.2	2,318.6	-107.2	2,320.1	0.00	0.00	0.00



Well Planning Report



Database:	EDM 5000.1 Single User Db	Local Co-ordinate Reference:	Well Fez Federal Com #705H
Company:	COG Operating, LLC	TVD Reference:	well @ 3291.0usft (Noram #21)
Project:	Lea County, NM	MD Reference:	well @ 3291.0usft (Noram #21)
Site:	Sec 9, T25-S, R35-E	North Reference:	Grid
Well:	Fez Federal Com #705H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Design #1		

Planned Survey									
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
14,800.0	90.18	359.57	12,569.9	2,418.6	-108.0	2,420.0	0.00	0.00	0.00
14,900.0	90.18	359.57	12,569.6	2,518.6	-108.7	2,520.0	0.00	0.00	0.00
15,000.0	90.18	359.57	12,569.3	2,618.6	-109.5	2,620.0	0.00	0.00	0.00
15,100.0	90.18	359.57	12,569.0	2,718.6	-110.2	2,720.0	0.00	0.00	0.00
15,200.0	90.18	359.57	12,568.7	2,818.6	-111.0	2,820.0	0.00	0.00	0.00
15,300.0	90.18	359.57	12,568.3	2,918.6	-111.7	2,920.0	0.00	0.00	0.00
15,400.0	90.18	359.57	12,568.0	3,018.6	-112.5	3,020.0	0.00	0.00	0.00
15,500.0	90.18	359.57	12,567.7	3,118.6	-113.2	3,120.0	0.00	0.00	0.00
15,600.0	90.18	359.57	12,567.4	3,218.6	-114.0	3,220.0	0.00	0.00	0.00
15,700.0	90.18	359.57	12,567.1	3,318.6	-114.7	3,320.0	0.00	0.00	0.00
15,800.0	90.18	359.57	12,566.8	3,418.6	-115.5	3,420.0	0.00	0.00	0.00
15,900.0	90.18	359.57	12,566.5	3,518.6	-116.2	3,520.0	0.00	0.00	0.00
16,000.0	90.18	359.57	12,566.2	3,618.6	-117.0	3,620.0	0.00	0.00	0.00
16,100.0	90.18	359.57	12,565.9	3,718.6	-117.7	3,720.0	0.00	0.00	0.00
16,200.0	90.18	359.57	12,565.5	3,818.5	-118.5	3,820.0	0.00	0.00	0.00
16,300.0	90.18	359.57	12,565.2	3,918.5	-119.2	3,920.0	0.00	0.00	0.00
16,400.0	90.18	359.57	12,564.9	4,018.5	-120.0	4,020.0	0.00	0.00	0.00
16,500.0	90.18	359.57	12,564.6	4,118.5	-120.7	4,120.0	0.00	0.00	0.00
16,600.0	90.18	359.57	12,564.3	4,218.5	-121.5	4,220.0	0.00	0.00	0.00
16,700.0	90.18	359.57	12,564.0	4,318.5	-122.2	4,320.0	0.00	0.00	0.00
16,800.0	90.18	359.57	12,563.7	4,418.5	-123.0	4,419.9	0.00	0.00	0.00
16,900.0	90.18	359.57	12,563.4	4,518.5	-123.7	4,519.9	0.00	0.00	0.00
17,000.0	90.18	359.57	12,563.1	4,618.5	-124.5	4,619.9	0.00	0.00	0.00
17,100.0	90.18	359.57	12,562.7	4,718.5	-125.2	4,719.9	0.00	0.00	0.00
17,200.0	90.18	359.57	12,562.4	4,818.5	-126.0	4,819.9	0.00	0.00	0.00
17,300.0	90.18	359.57	12,562.1	4,918.5	-126.7	4,919.9	0.00	0.00	0.00
17,400.0	90.18	359.57	12,561.8	5,018.5	-127.5	5,019.9	0.00	0.00	0.00
17,500.0	90.18	359.57	12,561.5	5,118.5	-128.2	5,119.9	0.00	0.00	0.00
17,600.0	90.18	359.57	12,561.2	5,218.5	-129.0	5,219.9	0.00	0.00	0.00
17,700.0	90.18	359.57	12,560.9	5,318.5	-129.7	5,319.9	0.00	0.00	0.00
17,800.0	90.18	359.57	12,560.6	5,418.5	-130.5	5,419.9	0.00	0.00	0.00
17,900.0	90.18	359.57	12,560.3	5,518.5	-131.2	5,519.9	0.00	0.00	0.00
18,000.0	90.18	359.57	12,559.9	5,618.5	-132.0	5,619.9	0.00	0.00	0.00
18,100.0	90.18	359.57	12,559.6	5,718.5	-132.7	5,719.9	0.00	0.00	0.00
18,200.0	90.18	359.57	12,559.3	5,818.5	-133.5	5,819.9	0.00	0.00	0.00
18,300.0	90.18	359.57	12,559.0	5,918.5	-134.2	5,919.9	0.00	0.00	0.00
18,400.0	90.18	359.57	12,558.7	6,018.5	-135.0	6,019.9	0.00	0.00	0.00
18,500.0	90.18	359.57	12,558.4	6,118.5	-135.7	6,119.9	0.00	0.00	0.00
18,600.0	90.18	359.57	12,558.1	6,218.5	-136.5	6,219.9	0.00	0.00	0.00
18,700.0	90.18	359.57	12,557.8	6,318.5	-137.2	6,319.9	0.00	0.00	0.00
18,800.0	90.18	359.57	12,557.5	6,418.5	-138.0	6,419.9	0.00	0.00	0.00
18,900.0	90.18	359.57	12,557.1	6,518.5	-138.7	6,519.9	0.00	0.00	0.00
19,000.0	90.18	359.57	12,556.8	6,618.5	-139.5	6,619.9	0.00	0.00	0.00
19,100.0	90.18	359.57	12,556.5	6,718.5	-140.2	6,719.8	0.00	0.00	0.00
19,200.0	90.18	359.57	12,556.2	6,818.4	-141.0	6,819.8	0.00	0.00	0.00
19,300.0	90.18	359.57	12,555.9	6,918.4	-141.7	6,919.8	0.00	0.00	0.00
19,400.0	90.18	359.57	12,555.6	7,018.4	-142.5	7,019.8	0.00	0.00	0.00
19,500.0	90.18	359.57	12,555.3	7,118.4	-143.2	7,119.8	0.00	0.00	0.00
19,600.0	90.18	359.57	12,555.0	7,218.4	-144.0	7,219.8	0.00	0.00	0.00
19,700.0	90.18	359.57	12,554.7	7,318.4	-144.7	7,319.8	0.00	0.00	0.00
19,800.0	90.18	359.57	12,554.3	7,418.4	-145.5	7,419.8	0.00	0.00	0.00
19,900.0	90.18	359.57	12,554.0	7,518.4	-146.2	7,519.8	0.00	0.00	0.00
20,000.0	90.18	359.57	12,553.7	7,618.4	-147.0	7,619.8	0.00	0.00	0.00
20,100.0	90.18	359.57	12,553.4	7,718.4	-147.7	7,719.8	0.00	0.00	0.00

Database:	EDM 5000.1 Single User Db	Local Co-ordinate Reference:	Well Fez Federal Com #705H
Company:	COG Operating, LLC	TVD Reference:	well @ 3291.0usft (Noram #21)
Project:	Lea County, NM	MD Reference:	well @ 3291.0usft (Noram #21)
Site:	Sec 9, T25-S, R35-E	North Reference:	Grid
Well:	Fez Federal Com #705H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Design #1		

Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
20,200.0	90.18	359.57	12,553.1	7,818.4	-148.5	7,819.8	0.00	0.00	0.00
20,300.0	90.18	359.57	12,552.8	7,918.4	-149.2	7,919.8	0.00	0.00	0.00
20,400.0	90.18	359.57	12,552.5	8,018.4	-150.0	8,019.8	0.00	0.00	0.00
20,500.0	90.18	359.57	12,552.2	8,118.4	-150.7	8,119.8	0.00	0.00	0.00
20,600.0	90.18	359.57	12,551.9	8,218.4	-151.5	8,219.8	0.00	0.00	0.00
20,700.0	90.18	359.57	12,551.5	8,318.4	-152.2	8,319.8	0.00	0.00	0.00
20,800.0	90.18	359.57	12,551.2	8,418.4	-153.0	8,419.8	0.00	0.00	0.00
20,900.0	90.18	359.57	12,550.9	8,518.4	-153.7	8,519.8	0.00	0.00	0.00
21,000.0	90.18	359.57	12,550.6	8,618.4	-154.5	8,619.8	0.00	0.00	0.00
21,100.0	90.18	359.57	12,550.3	8,718.4	-155.2	8,719.8	0.00	0.00	0.00
21,200.0	90.18	359.57	12,550.0	8,818.4	-156.0	8,819.8	0.00	0.00	0.00
21,300.0	90.18	359.57	12,549.7	8,918.4	-156.7	8,919.7	0.00	0.00	0.00
21,400.0	90.18	359.57	12,549.4	9,018.4	-157.5	9,019.7	0.00	0.00	0.00
21,500.0	90.18	359.57	12,549.1	9,118.4	-158.2	9,119.7	0.00	0.00	0.00
21,600.0	90.18	359.57	12,548.7	9,218.4	-159.0	9,219.7	0.00	0.00	0.00
21,700.0	90.18	359.57	12,548.4	9,318.4	-159.7	9,319.7	0.00	0.00	0.00
21,800.0	90.18	359.57	12,548.1	9,418.4	-160.5	9,419.7	0.00	0.00	0.00
21,900.0	90.18	359.57	12,547.8	9,518.4	-161.2	9,519.7	0.00	0.00	0.00
22,000.0	90.18	359.57	12,547.5	9,618.4	-162.0	9,619.7	0.00	0.00	0.00
22,100.0	90.18	359.57	12,547.2	9,718.4	-162.7	9,719.7	0.00	0.00	0.00
22,200.0	90.18	359.57	12,546.9	9,818.3	-163.5	9,819.7	0.00	0.00	0.00
22,300.0	90.18	359.57	12,546.6	9,918.3	-164.2	9,919.7	0.00	0.00	0.00
22,400.0	90.18	359.57	12,546.3	10,018.3	-165.0	10,019.7	0.00	0.00	0.00
TD @ 22483.7' MD, 12546.0' TVD									
22,483.7	90.18	359.57	12,546.0	10,102.1	-165.6	10,103.4	0.00	0.00	0.00

Design Targets

Target Name - hit/miss target - Shape	Dip Angle (°)	Dip Dir. (°)	TVD (usft)	+N/-S (usft)	+E/-W (usft)	Northing (usft)	Easting (usft)	Latitude	Longitude
LTP- Fez Fed Com #7 - plan misses target center by 0.4usft at 22353.8usft MD (12546.4 TVD, 9972.2 N, -164.6 E) - Point	0.00	0.00	12,546.0	9,972.2	-164.5	425,308.91	795,172.97	32° 9' 56.502 N	103° 22' 46.006 W
PBHL- Fez Fed Com : - plan hits target center - Point	0.00	0.01	12,546.0	10,102.1	-165.6	425,438.80	795,171.90	32° 9' 57.787 N	103° 22' 46.005 W
FTP- Fez Fed Com #7 - plan misses target center by 158.6usft at 12504.3usft MD (12455.6 TVD, 152.7 N, -91.0 E) - Point	0.00	0.00	12,576.0	49.4	-90.2	415,386.13	795,247.27	32° 8' 18.308 N	103° 22' 46.164 W

Sec 9, T25-S, R35-E
Fez Federal Com #705H
Q180*** & WT-180***
Design #1

Company Name: COG Operating, LLC
Fez Federal Com #705H
Rig: Naran #21
Created by: Keith Noack
Date: 9-23, February 28 2018



PROJECT DETAILS: Lea County, NM

Geodetic System: US State Plane 1927 (Exact solution)
Datum: NAD 1927 (NADCON CONUS)
Ellipsoid: Clarke 1866
Zone: New Mexico East 3001
System Datum: Mean Sea Level

WELL DETAILS: Fez Federal Com #705H


3262.0
+N/-S +E/-W Northing Easting Latitude Longitude
0.0 0.0 415336.73 795337.48 32° 8' 17.812 N 103° 22' 46.126 W

DESIGN TARGET DETAILS

Name	TVD	+N/-S	+E/-W	Northing	Easting	Latitude	Longitude
LTP- Fez Fed Com #705H	12546.0	8972.2	-164.5	426308.91	795172.97	32° 8' 56.502 N	103° 22' 46.006 W
PBHL- Fez Fed Com #705H	12546.0	19102.1	-165.6	425438.00	795171.90	32° 8' 57.797 N	103° 22' 46.006 W
FTP- Fez Fed Com #705H	12576.0	49.4	-80.2	415386.14	795247.27	32° 8' 18.308 N	103° 22' 46.164 W

SECTION DETAILS

MD	Inc	Azi	TVD	+N/-S	+E/-W	Deg	TFace	Vsect	Annotation
0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.0	Build 2.00"/100'
1000.0	0.00	0.00	1000.0	0.0	0.0	0.00	0.00	0.0	EOB: 2.00" Inc, 368.00" Azi
1100.0	2.00	265.00	1100.0	-0.2	-1.7	2.00	265.00	-0.1	Build/Turn 2.00"/100'
2000.0	2.00	265.00	2000.0	-2.9	-33.0	0.00	0.00	-2.3	EOBT: 4.00" Inc, 265.00" Azi
2100.0	4.00	265.00	2099.9	-3.3	-38.3	2.00	0.00	-2.7	Drop 2.00"/100'
2742.3	4.00	265.00	2740.0	-7.2	-42.9	0.00	0.00	-6.9	EOB: 0.00" Inc, 0.00" Azi
2942.3	0.00	0.00	2938.8	-7.9	-49.8	2.00	180.00	-4.4	KOP: 8.00" 12.00"/100'
12190.9	0.00	0.00	12098.5	-7.9	-49.8	0.00	0.00	-3.4	EOC: 80.18" Inc, 353.57" Azi, 12576.0" TVD
12852.4	80.18	359.57	12576.0	471.1	-83.4	12.00	359.57	472.5	TD @ 23483.7 MD, 12546.0" TVD
22483.7	80.18	359.57	12546.0	10102.1	-165.6	0.00	0.00	10103.4	



Vertical Section at 359.06' (200 us/in)

EOC 80.18" Inc, 353.57" Azi, 12576.0" TVD

Vertical Section at 359.06' (200 us/in)

Database:	EDM 5000.1 Single User Db	Local Co-ordinate Reference:	Well Fez Federal Com #705H
Company:	COG Operating, LLC	TVD Reference:	well @ 3291.0usft (Noram #21)
Project:	Lea County, NM	MD Reference:	well @ 3291.0usft (Noram #21)
Site:	Sec 9, T25-S, R35-E	North Reference:	Grid
Well:	Fez Federal Com #705H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Design #1		

Formations						
Measured Depth (usft)	Vertical Depth (usft)	Name	Lithology	Dip (°)	Dip Direction (°)	
872.0	872.0	Rustler				
1,213.1	1,213.0	TOS				
5,010.4	5,008.0	BOS (Fletcher)				
5,341.4	5,339.0	LMAR (Top Delaware)				
5,373.4	5,371.0	BLCN				
6,312.4	6,310.0	CYCN				
7,772.4	7,770.0	BYCN				
9,003.4	9,001.0	Bone Sprg (BSGL)				
9,220.4	9,218.0	U Avalon Sh				
9,584.4	9,582.0	L Avalon Sh				
10,401.4	10,399.0	FBSG_sand				
10,921.4	10,919.0	SBSG_sand				
11,395.4	11,393.0	SBSG_sand base				
11,978.4	11,976.0	TBSG_sand				
12,402.0	12,380.0	WFMP				
12,528.2	12,471.0	WFMP Lith				

Plan Annotations					
Measured Depth (usft)	Vertical Depth (usft)	Local Coordinates			
		+N/-S (usft)	+E/-W (usft)	Comment	
1,000.0	1,000.0	0.0	0.0	Build 2.00°/100'	
1,100.0	1,100.0	-0.2	-1.7	EOB: 2.00° Inc, 265.00° Azi	
2,000.6	2,000.0	-2.9	-33.0	Build/Turn 2.00°/100'	
2,100.6	2,099.9	-3.3	-38.3	EOBT: 4.00° Inc, 265.00° Azi	
2,742.3	2,740.0	-7.2	-82.9	Drop 2.00°/100'	
2,942.3	2,939.8	-7.9	-89.8	EOD: 0.00° Inc, 0.00° Azi	
12,100.9	12,098.5	-7.9	-89.8	KOP: Build 12.00°/100'	
12,852.4	12,576.0	471.1	-93.4	EOC: 90.18° Inc, 359.57° Azi, 12576.0' TVD	
22,483.7	12,546.0	10,102.1	-165.6	TD @ 22483.7' MD, 12546.0' TVD	