

(H)  
F/S

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT  
APPLICATION FOR PERMIT TO DRILL OR REENTER

OCD Hobbs

RECEIVED  
JAN 16 2019

FORM APPROVED  
OMB No. 1004-0137  
Expires: January 31, 2018

1a. Type of work:  DRILL  REENTER  
1b. Type of Well:  Oil Well  Gas Well  Other  
1c. Type of Completion:  Hydraulic Fracturing  Single Zone  Multiple Zone

5. Lease Serial No.  
NMNM0106040A

If Indian, Allottee or Tribe Name

7. If Unit or CA Agreement, Name and No.

8. Lease Name and Well No.

RED HILLS UNIT  
131H (323150)

9. API Well No.

30-025-45503

10. Field and Pool, or Exploratory  
BONE SPRING / BONE SPRING (96682)

2. Name of Operator  
CIMAREX ENERGY COMPANY (215099)

3a. Address  
600 N. Marienfeld St., Suite 600 Midland OK 79701

3b. Phone No. (include area code)  
(432)620-1936

11. Sec., T. R. M. or Blk. and Survey or Area  
SEC 32 / T25S / R33E / NMP

4. Location of Well (Report location clearly and in accordance with any State requirements. \*)  
At surface NWNW / 330 FNL / 410 FWL / LAT 32.093413 / LONG -103.601531  
At proposed prod. zone SWSW / 330 FSL / 660 FWL / LAT 32.066204 / LONG -103.600721

14. Distance in miles and direction from nearest town or post office\*  
24 miles

12. County or Parish  
LEA

13. State  
NM

15. Distance from proposed\* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any)  
330 feet

16. No of acres in lease  
240

17. Spacing Unit dedicated to this well  
320

18. Distance from proposed location\* to nearest well, drilling, completed, applied for, on this lease, ft.  
20 feet

19. Proposed Depth  
12040 feet / 21744 feet

20. BLM/BIA Bond No. in file  
FED: NMB001188

21. Elevations (Show whether DF, KDB, RT, GL, etc.)  
3396 feet

22. Approximate date work will start\*  
11/01/2018

23. Estimated duration  
30 days

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, and the Hydraulic Fracturing rule per 43 CFR 3162.3-3 (as applicable)

- 1. Well plat certified by a registered surveyor.
- 2. A Drilling Plan.
- 3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO must be filed with the appropriate Forest Service Office).
- 4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above).
- 5. Operator certification.
- 6. Such other site specific information and/or plans as may be requested by the BLM.

25. Signature  
(Electronic Submission)

Name (Printed/Typed)  
Aricka Easterling / Ph: (918)560-7060

Date  
05/31/2018

Title  
Regulatory Analyst

Approved by (Signature)  
(Electronic Submission)

Name (Printed/Typed)  
Ty Allen / Ph: (575)234-5978

Date  
11/30/2018

Title  
Wildlife Biologist

Office  
CARLSBAD

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.  
Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

SEP 2019 01/17/19

KA 01/17/19

APPROVED WITH CONDITIONS  
Approval Date: 11/30/2018

Double checked

## INSTRUCTIONS

**GENERAL:** This form is designed for submitting proposals to perform certain well operations, as indicated on Federal and Indian lands and leases for action by appropriate Federal agencies, pursuant to applicable Federal laws and regulations. Any necessary special instructions concerning the use of this form and the number of copies to be submitted, particularly with regard to local, area, or regional procedures and practices, either are shown below or will be issued by, or may be obtained from local Federal offices.

**ITEM I:** If the proposal is to redrill to the same reservoir at a different subsurface location or to a new reservoir, use this form with appropriate notations. Consult applicable Federal regulations concerning subsequent work proposals or reports on the well.

**ITEM 4:** Locations on Federal or Indian land should be described in accordance with Federal requirements. Consult local Federal offices for specific instructions.

**ITEM 14:** Needed only when location of well cannot readily be found by road from the land or lease description. A plat, or plats, separate or on the reverse side, showing the roads to, and the surveyed location of, the well, and any other required information, should be furnished when required by Federal agency offices.

**ITEMS 15 AND 18:** If well is to be, or has been directionally drilled, give distances for subsurface location of hole in any present or objective productive zone.

**ITEM 22:** Consult applicable Federal regulations, or appropriate officials, concerning approval of the proposal before operations are started.

**ITEM 24:** If the proposal will involve hydraulic fracturing operations, you must comply with 43 CFR 3162.3-3, including providing information about the protection of usable water. Operators should provide the best available information about all formations containing water and their depths. This information could include data and interpretation of resistivity logs run on nearby wells. Information may also be obtained from state or tribal regulatory agencies and from local BLM offices.

## NOTICES

The Privacy Act of 1974 and regulation in 43 CFR 2.48(d) provide that you be furnished the following information in connection with information required by this application.

**AUTHORITY:** 30 U.S.C. 181 et seq., 25 U.S.C. 396; 43 CFR 3160

**PRINCIPAL PURPOSES:** The information will be used to: (1) process and evaluate your application for a permit to drill a new oil, gas, or service well or to reenter a plugged and abandoned well; and (2) document, for administrative use, information for the management, disposal and use of National Resource Lands and resources including (a) analyzing your proposal to discover and extract the Federal or Indian resources encountered; (b) reviewing procedures and equipment and the projected impact on the land involved; and (c) evaluating the effects of the proposed operation on the surface and subsurface water and other environmental impacts.

**ROUTINE USE:** Information from the record and/or the record will be transferred to appropriate Federal, State, and local or foreign agencies, when relevant to civil, criminal or regulatory investigations or prosecution, in connection with congressional inquiries and for regulatory responsibilities.

**EFFECT OF NOT PROVIDING INFORMATION:** Filing of this application and disclosure of the information is mandatory only if you elect to initiate a drilling or reentry operation on an oil and gas lease.

The Paperwork Reduction Act of 1995 requires us to inform you that:

The BLM collects this information to allow evaluation of the technical, safety, and environmental factors involved with drilling for oil and/or gas on Federal and Indian oil and gas leases. This information will be used to analyze and approve applications. Response to this request is mandatory only if the operator elects to initiate drilling or reentry operations on an oil and gas lease. The BLM would like you to know that you do not have to respond to this or any other Federal agency-sponsored information collection unless it displays a currently valid OMB control number.

**BURDEN HOURS STATEMENT:** Public reporting burden for this form is estimated to average 8 hours per response, including the time for reviewing instructions, gathering and maintaining data, and completing and reviewing the form. Direct comments regarding the burden estimate or any other aspect of this form to U.S. Department of the Interior, Bureau of Land Management (1004-0137), Bureau Information Connection Clearance Officer (WO-630), 1849 C Street, N.W., Mail Stop 401 LS, Washington, D.C. 20240.

## Additional Operator Remarks

### Location of Well

1. SHL: NWNW / 330 FNL / 410 FWL / TWSP: 25S / RANGE: 33E / SECTION: 32 / LAT: 32.093413 / LONG: -103.601531 ( TVD: 0 feet, MD: 0 feet )  
PPP: NWSW / 1320 FNL / 660 FWL / TWSP: 26S / RANGE: 33E / SECTION: 5 / LAT: 32.076222 / LONG: -103.6007167 ( TVD: 12040 feet, MD: 18100 feet )  
BHL: SWSW / 330 FSL / 660 FWL / TWSP: 26S / RANGE: 33E / SECTION: 5 / LAT: 32.066204 / LONG: -103.600721 ( TVD: 12040 feet, MD: 21744 feet )

### BLM Point of Contact

Name: Tenille Ortiz  
Title: Legal Instruments Examiner  
Phone: 5752342224  
Email: tortiz@blm.gov

CONFIDENTIAL

## **Review and Appeal Rights**

A person contesting a decision shall request a State Director review. This request must be filed within 20 working days of receipt of the Notice with the appropriate State Director (see 43 CFR 3165.3). The State Director review decision may be appealed to the Interior Board of Land Appeals, 801 North Quincy Street, Suite 300, Arlington, VA 22203 (see 43 CFR 3165.4). Contact the above listed Bureau of Land Management office for further information.

CONFIDENTIAL

**PECOS DISTRICT  
DRILLING CONDITIONS OF APPROVAL**

<b>OPERATOR'S NAME:</b>	<b>CIMAREX ENERGY COMPANY</b>
<b>LEASE NO.:</b>	<b>NMNM0106040 A</b>
<b>WELL NAME &amp; NO.:</b>	<b>RED HILLS UNIT 131H</b>
<b>SURFACE HOLE FOOTAGE:</b>	<b>330'/N &amp; 410'/W</b>
<b>BOTTOM HOLE FOOTAGE</b>	<b>330'/S &amp; 660'/W</b>
<b>LOCATION:</b>	<b>SECTION 32, T25S, R33E, NMPM</b>
<b>COUNTY:</b>	<b>LEA</b>

COA

H2S	<input type="radio"/> Yes	<input checked="" type="radio"/> No	
Potash	<input checked="" type="radio"/> None	<input type="radio"/> Secretary	<input type="radio"/> R-111-P
Cave/Karst Potential	<input checked="" type="radio"/> Low	<input type="radio"/> Medium	<input type="radio"/> High
Variance	<input type="radio"/> None	<input checked="" type="radio"/> Flex Hose	<input type="radio"/> Other
Wellhead	<input type="radio"/> Conventional	<input checked="" type="radio"/> Multibowl	<input type="radio"/> Both
Other	<input type="checkbox"/> 4 String Area	<input type="checkbox"/> Capitan Reef	<input type="checkbox"/> WIPP

**A. Hydrogen Sulfide**

Hydrogen Sulfide (H2S) monitors shall be installed prior to drilling out the surface shoe. If H2S is detected in concentrations greater than 100 ppm, the Hydrogen Sulfide area shall meet Onshore Order 6 requirements, which includes equipment and personnel/public protection items. If Hydrogen Sulfide is encountered, provide measured values and formations to the BLM.

**B. CASING**

1. The 13-3/8 inch surface casing shall be set at approximately 1050 feet (a minimum of 25 feet into the Rustler Anhydrite and above the salt) and cemented to the surface.
  - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.
  - b. Wait on cement (WOC) time for a primary cement job will be a minimum of 8 hours or 500 pounds compressive strength, whichever is greater. (This is to include the lead cement)

- c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.
- d. If cement falls back, remedial cementing will be done prior to drilling out that string.

**Operator shall filled 1/3<sup>rd</sup> casing with fluid while running intermediate casing to maintain collapse safety factor.**

- 2. The minimum required fill of cement behind the 9-5/8 inch intermediate casing is:
  - Cement to surface. If cement does not circulate see B.1.a, c-d above.

Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to cave/karst or potash.

- 3. The minimum required fill of cement behind the 5-1/2 inch production casing is:
  - Cement should tie-back at least 200 feet into previous casing string. Operator shall provide method of verification. **Additional cement maybe required. Excess calculates to 16%.**

### **C. PRESSURE CONTROL**

- 1. Variance approved to use flex line from BOP to choke manifold. Manufacturer's specification to be readily available. No external damage to flex line. Flex line to be installed as straight as possible (no hard bends).
- 2. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be **2000 (2M) psi**.
- 3. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the intermediate casing shoe shall be **10,000 (10M) psi**.

## **GENERAL REQUIREMENTS**

The BLM is to be notified in advance for a representative to witness:

- a. Spudding well (minimum of 24 hours)
- b. Setting and/or Cementing of all casing strings (minimum of 4 hours)
- c. BOPE tests (minimum of 4 hours)

Chaves and Roosevelt Counties  
 Call the Roswell Field Office, 2909 West Second St., Roswell NM 88201.  
 During office hours call (575) 627-0272.  
 After office hours call (575)

Eddy County  
 Call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220,  
 (575) 361-2822

Lea County

Call the Hobbs Field Station, 414 West Taylor, Hobbs NM 88240, (575)  
393-3612

1. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval.
  - a. In the event the operator has proposed to drill multiple wells utilizing a skid/walking rig. Operator shall secure the wellbore on the current well, after installing and testing the wellhead, by installing a blind flange of like pressure rating to the wellhead and a pressure gauge that can be monitored while drilling is performed on the other well(s).
  - b. When the operator proposes to set surface casing with Spudder Rig
    - Notify the BLM when moving in and removing the Spudder Rig.
    - Notify the BLM when moving in the 2<sup>nd</sup> Rig. Rig to be moved in within 90 days of notification that Spudder Rig has left the location.
    - BOP/BOPE test to be conducted per Onshore Oil and Gas Order No. 2 as soon as 2nd Rig is rigged up on well.
2. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works are located, this does not include the dog house or stairway area.
3. The record of the drilling rate along with the GR/N well log (one log per well pad is acceptable) run from TD to surface (horizontal well – vertical portion of hole) shall be submitted to the BLM office as well as all other logs run on the borehole 30 days from completion. If available, a digital copy of the logs is to be submitted in addition to the paper copies. The Rustler top and top and bottom of Salt are to be recorded on the Completion Report.

#### A. CASING

1. Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size or are Non-API. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.). The initial wellhead installed on the well will remain on the well with spools used as needed.
2. Wait on cement (WOC) for Potash Areas: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the

following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi for all cement blends, 2) until cement has been in place at least 24 hours. WOC time will be recorded in the driller's log. The casing integrity test can be done (prior to the cement setting up) immediately after bumping the plug.

3. Wait on cement (WOC) for Water Basin: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi at the shoe, 2) until cement has been in place at least 8 hours. WOC time will be recorded in the driller's log. See individual casing strings for details regarding lead cement slurry requirements. The casing integrity test can be done (prior to the cement setting up) immediately after bumping the plug.
4. Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. Have well specific cement details onsite prior to pumping the cement for each casing string.
5. No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.
6. On that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Formation at the shoe shall be tested to a minimum of the mud weight equivalent anticipated to control the formation pressure to the next casing depth or at total depth of the well. This test shall be performed before drilling more than 20 feet of new hole.
7. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.
8. Whenever a casing string is cemented in the R-111-P potash area, the NMOCD requirements shall be followed.

#### **B. PRESSURE CONTROL**

1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in Onshore Oil and Gas Order No. 2 and API RP 53 Sec. 17.
2. If a variance is approved for a flexible hose to be installed from the BOP to the choke manifold, the following requirements apply: The flex line must meet the requirements of API 16C. Check condition of flexible line from BOP to choke manifold, replace if exterior is damaged or if line fails test. Line to be as straight as possible with no hard bends and is to be anchored according to Manufacturer's requirements. The flexible hose can be exchanged with a hose of equal size and equal or greater pressure rating.

Anchor requirements, specification sheet and hydrostatic pressure test certification matching the hose in service, to be onsite for review. These documents shall be posted in the company man's trailer and on the rig floor.

3. 5M or higher system requires an HCR valve, remote kill line and annular to match. The remote kill line is to be installed prior to testing the system and tested to stack pressure.
4. If the operator has proposed a multi-bowl wellhead assembly in the APD. The following requirements must be met:
  - a. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
  - b. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
  - c. Manufacturer representative shall install the test plug for the initial BOP test.
  - d. If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
  - e. Whenever any seal subject to test pressure is broken, all the tests in OOGO2.III.A.2.i must be followed.
5. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.
  - a. In a water basin, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. The casing cut-off and BOP installation can be initiated four hours after installing the slips, which will be approximately six hours after bumping the plug. For those casing strings not using slips, the minimum wait time before cut-off is eight hours after bumping the plug. BOP/BOPE testing can begin after cut-off or once cement reaches 500 psi compressive strength (including lead when specified), whichever is greater. However, if the float does not hold, cut-off cannot be initiated until cement reaches 500 psi compressive strength (including lead when specified).
  - b. In potash areas, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. For all casing strings, casing cut-off and BOP installation can be initiated at twelve hours after bumping the plug. However, **no tests** shall commence until the cement has had a minimum of 24 hours setup time, except the casing pressure test can be initiated immediately after bumping the plug (only applies to single stage cement jobs).
  - c. The tests shall be done by an independent service company utilizing a test

plug. The results of the test shall be reported to the appropriate BLM office.

- d. The test shall be run on a 5000 psi chart for a 2-3M BOP/BOP, on a 10000 psi chart for a 5M BOP/BOPE and on a 15000 psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one hour chart. A circular chart shall have a maximum 2 hour clock. If a twelve hour or twenty-four hour chart is used, tester shall make a notation that it is run with a two hour clock.
- e. All tests are required to be recorded on a calibrated test chart. A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.
- f. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes. This test shall be performed prior to the test at full stack pressure.
- g. BOP/BOPE must be tested by an independent service company within 500 feet of the top of the Wolfcamp formation if the time between the setting of the intermediate casing and reaching this depth exceeds 20 days. This test does not exclude the test prior to drilling out the casing shoe as per Onshore Order No. 2.

#### C. DRILLING MUD

Mud system monitoring equipment, with derrick floor indicators and visual and audio alarms, shall be operating before drilling into the Wolfcamp formation, and shall be used until production casing is run and cemented.

#### D. WASTE MATERIAL AND FLUIDS

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area.

Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.

#### **Waste Minimization Plan (WMP)**

In the interest of resource development, submission of additional well gas capture development plan information is deferred but may be required by the BLM Authorized Officer at a later date.

**ZS 111918**

**PECOS DISTRICT  
SURFACE USE  
CONDITIONS OF APPROVAL**

OPERATOR'S NAME:	CIMAREX ENERGY COMPANY
LEASE NO.:	NMNM0106040 A
WELL NAME & NO.:	RED HILLS UNIT 131H
SURFACE HOLE FOOTAGE:	330'/N & 410'/W
BOTTOM HOLE FOOTAGE:	330'/S & 660'/W
LOCATION:	SECTION 32, T25S, R33E, NMPM
COUNTY:	LEA

**TABLE OF CONTENTS**

Standard Conditions of Approval (COA) apply to this APD. If any deviations to these standards exist or special COAs are required, the section with the deviation or requirement will be checked below.

- General Provisions**
- Permit Expiration**
- Archaeology, Paleontology, and Historical Sites**
- Noxious Weeds**
- Special Requirements**
  - Cave/Karst
  - Hydrology
- Construction**
  - Notification
  - Topsoil
  - Closed Loop System
  - Federal Mineral Material Pits
  - Well Pads
  - Roads
- Road Section Diagram**
- Production (Post Drilling)**
  - Well Structures & Facilities
  - Pipelines
  - Electric Lines
- Interim Reclamation**
- Final Abandonment & Reclamation**

## **I. GENERAL PROVISIONS**

The approval of the Application For Permit To Drill (APD) is in compliance with all applicable laws and regulations: 43 Code of Federal Regulations 3160, the lease terms, Onshore Oil and Gas Orders, Notices To Lessees, New Mexico Oil Conservation Division (NMOCD) Rules, National Historical Preservation Act As Amended, and instructions and orders of the Authorized Officer. Any request for a variance shall be submitted to the Authorized Officer on Form 3160-5, Sundry Notices and Report on Wells.

## **II. PERMIT EXPIRATION**

If the permit terminates prior to drilling and drilling cannot be commenced within 60 days after expiration, an operator is required to submit Form 3160-5, Sundry Notices and Reports on Wells, requesting surface reclamation requirements for any surface disturbance. However, if the operator will be able to initiate drilling within 60 days after the expiration of the permit, the operator must have set the conductor pipe in order to allow for an extension of 60 days beyond the expiration date of the APD. (Filing of a Sundry Notice is required for this 60 day extension.)

## **III. ARCHAEOLOGICAL, PALEONTOLOGY & HISTORICAL SITES**

Any cultural and/or paleontological resource discovered by the operator or by any person working on the operator's behalf shall immediately report such findings to the Authorized Officer. The operator is fully accountable for the actions of their contractors and subcontractors. The operator shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery shall be made by the Authorized Officer to determine the appropriate actions that shall be required to prevent the loss of significant cultural or scientific values of the discovery. The operator shall be held responsible for the cost of the proper mitigation measures that the Authorized Officer assesses after consultation with the operator on the evaluation and decisions of the discovery. Any unauthorized collection or disturbance of cultural or paleontological resources may result in a shutdown order by the Authorized Officer.

## **IV. NOXIOUS WEEDS**

The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes the roads, pads, associated pipeline corridor, and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

## V. SPECIAL REQUIREMENT(S)

### Hydrology

#### *Tank Battery COAs Only:*

- Tank battery locations will be lined and bermed. A 20 mil permanent liner will be installed with a 4 oz. felt backing to prevent tears or punctures. Tank battery berms must be large enough to contain 1 ½ times the content of the largest tank.
- Automatic shut off, check vales, or similar systems will be installed for tanks to minimize the effects of catastrophic line failures used in production or drilling.

#### *Surface Pipeline COAs Only:*

- A leak detection plan will be submitted to the BLM Carlsbad Field Office for approval prior to pipeline installation. The method could incorporate gauges to detect pressure drops, situating values and lines so they can be visually inspected periodically or installing electronic sensors to alarm when a leak is present. The leak detection plan will incorporate an automatic shut off system that will be installed for proposed pipelines to minimize the effects of an undesirable event.

### Cave Karst

#### Production Facilities

In order to mitigate the impacts from production activities and due to the nature of karst terrain, the following Conditions of Approval will apply to this APD:

- Tank battery liners and berms to minimize the impact resulting from leaks.
- Leak detection system to provide an early alert to operators when a leak has occurred.
- Automatic shut off, check values, or similar systems will be installed for pipelines and tanks to minimize the effects of line failures used in production or drilling.

#### Roads

- Roads will be routed around sinkholes and other karst features to avoid or lessen the possibility of encountering near surface voids and to minimize changes to runoff or possible leaks and spills from entering karst systems.
- The BLM, Carlsbad Field Office, will be informed immediately if any subsurface drainage channels, cave passages, or voids are penetrated during construction and no further construction will be done until clearance has been issued by the Authorized Officer.
- Turnout ditches and drainage leadoffs will not be constructed in such a manner as to increase or decrease the natural flow of water into or out of cave or karst features.
- Special restoration stipulations or realignment may be required.
- All spills or leaks will be reported to the BLM immediately for their immediate and proper treatment.

#### Powerlines

- Smaller powerlines will be routed around sinkholes and other karst features to avoid or lessen the possibility of encountering near surface voids and to minimize changes to runoff or possible leaks and spills from entering karst systems. Larger powerlines will adjust their pole spacing to avoid cave and karst features.
- The BLM, Carlsbad Field Office, will be informed immediately if any subsurface drainage channels, cave passages, or voids are penetrated during construction.
- No further construction will be done until clearance has been issued by the Authorized Officer.
- Special restoration stipulations or realignment may be required.

#### Buried Pipelines

- The BLM, Carlsbad Field Office, will be informed immediately if any subsurface drainage channels, passages, or voids are intersected by trenching, and no pipe will be laid in the trench at that point until clearance has been issued by the Authorized Officer.
- If a void is encountered, alignments may be rerouted to avoid the karst feature and lessen the potential of subsidence or collapse of karst features, buildup of toxic or combustible gas, or other possible impacts to cave and karst resources from the buried pipeline.
- Special restoration stipulations or realignment may be required at such intersections, if any.
- A leak detection plan **will be submitted to the BLM Carlsbad Field Office for approval** prior to pipeline installation. The method could incorporate gauges to detect pressure drops, situating valves and lines so they can be visually inspected periodically, or installing electronic sensors to alarm when a leak is present. The leak detection plan will incorporate an automatic shut off system that will be installed for proposed pipelines to minimize the effects of an undesirable event.
- Regular monitoring is required to quickly identify leaks for their immediate and proper treatment.

## **VI. CONSTRUCTION**

### **A. NOTIFICATION**

The BLM shall administer compliance and monitor construction of the access road and well pad. Notify the Carlsbad Field Office at (575) 234-5909 at least 3 working days prior to commencing construction of the access road and/or well pad.

When construction operations are being conducted on this well, the operator shall have the approved APD and Conditions of Approval (COA) on the well site and they shall be made available upon request by the Authorized Officer.

### **B. TOPSOIL**

The operator shall strip the top portion of the soil (root zone) from the entire well pad area and stockpile the topsoil along the edge of the well pad as depicted in the APD. The root zone is typically six (6) inches in depth. All the stockpiled topsoil will be redistributed over the interim reclamation areas. Topsoil shall not be used for berming the pad or facilities. For final reclamation, the topsoil shall be spread over the entire pad area for seeding preparation.

Other subsoil (below six inches) stockpiles must be completely segregated from the topsoil stockpile. Large rocks or subsoil clods (not evident in the surrounding terrain) must be buried within the approved area for interim and final reclamation.

### **C. CLOSED LOOP SYSTEM**

Tanks are required for drilling operations: No Pits.

The operator shall properly dispose of drilling contents at an authorized disposal site.

### **D. FEDERAL MINERAL MATERIALS PIT**

Payment shall be made to the BLM prior to removal of any federal mineral materials. Call the Carlsbad Field Office at (575) 234-5972.

### **E. WELL PAD SURFACING**

Surfacing of the well pad is not required.

If the operator elects to surface the well pad, the surfacing material may be required to be removed at the time of reclamation. The well pad shall be constructed in a manner which creates the smallest possible surface disturbance, consistent with safety and operational needs.

### **F. EXCLOSURE FENCING (CELLARS & PITS)**

**Exclosure Fencing**

The operator will install and maintain exclosure fencing for all open well cellars to prevent access to public, livestock, and large forms of wildlife before and after drilling operations until the pit is free of fluids and the operator initiates backfilling. (For examples of exclosure fencing design, refer to BLM's Oil and Gas Gold Book, Exclosure Fence Illustrations, Figure 1, Page 18.)

**G. ON LEASE ACCESS ROADS****Road Width**

The access road shall have a driving surface that creates the smallest possible surface disturbance and does not exceed fourteen (14) feet in width. The maximum width of surface disturbance, when constructing the access road, shall not exceed twenty-five (25) feet.

**Surfacing**

Surfacing material is not required on the new access road driving surface. If the operator elects to surface the new access road or pad, the surfacing material may be required to be removed at the time of reclamation.

Where possible, no improvements should be made on the unsurfaced access road other than to remove vegetation as necessary, road irregularities, safety issues, or to fill low areas that may sustain standing water.

The Authorized Officer reserves the right to require surfacing of any portion of the access road at any time deemed necessary. Surfacing may be required in the event the road deteriorates, erodes, road traffic increases, or it is determined to be beneficial for future field development. The surfacing depth and type of material will be determined at the time of notification.

**Crowning**

Crowning shall be done on the access road driving surface. The road crown shall have a grade of approximately 2% (i.e., a 1" crown on a 14' wide road). The road shall conform to Figure 1; cross section and plans for typical road construction.

**Ditching**

Ditching shall be required on both sides of the road.

**Turnouts**


Vehicle turnouts shall be constructed on the road. Turnouts shall be intervisible with interval spacing distance less than 1000 feet. Turnouts shall conform to Figure 1; cross section and plans for typical road construction.

**Drainage**

Drainage control systems shall be constructed on the entire length of road (e.g. ditches, sidehill outsloping and insloping, lead-off ditches, culvert installation, and low water crossings).

A typical lead-off ditch has a minimum depth of 1 foot below and a berm of 6 inches above natural ground level. The berm shall be on the down-slope side of the lead-off ditch.

### Cross Section of a Typical Lead-off Ditch



All lead-off ditches shall be graded to drain water with a 1 percent minimum to 3 percent maximum ditch slope. The spacing interval are variable for lead-off ditches and shall be determined according to the formula for spacing intervals of lead-off ditches, but may be amended depending upon existing soil types and centerline road slope (in %);

### Formula for Spacing Interval of Lead-off Ditches

Example - On a 4% road slope that is 400 feet long, the water flow shall drain water into a lead-off ditch. Spacing interval shall be determined by the following formula:

$$400 \text{ foot road with } 4\% \text{ road slope: } \frac{400'}{4\%} + 100' = 200' \text{ lead-off ditch interval}$$

### Cattle guards

An appropriately sized cattle guard sufficient to carry out the project shall be installed and maintained at fence/road crossings. Any existing cattle guards on the access road route shall be repaired or replaced if they are damaged or have deteriorated beyond practical use. The operator shall be responsible for the condition of the existing cattle guards that are in place and are utilized during lease operations.

### Fence Requirement

Where entry is granted across a fence line, the fence shall be braced and tied off on both sides of the passageway prior to cutting. The operator shall notify the private surface landowner or the grazing allotment holder prior to crossing any fences.

### Public Access

Public access on this road shall not be restricted by the operator without specific written approval granted by the Authorized Officer.

**Construction Steps**

1. Salvage topsoil
2. Construct road

3. Redistribute topsoil
4. Revegetate slopes




Figure 1. Cross-sections and plans for typical road sections representative of BLM resource or FS local and higher-class roads.

## **VII. PRODUCTION (POST DRILLING)**

### **A. WELL STRUCTURES & FACILITIES**

#### **Placement of Production Facilities**

Production facilities should be placed on the well pad to allow for maximum interim recontouring and revegetation of the well location.

#### **Exclosure Netting (Open-top Tanks)**

Immediately following active drilling or completion operations, the operator will take actions necessary to prevent wildlife and livestock access, including avian wildlife, to all open-topped tanks that contain or have the potential to contain salinity sufficient to cause harm to wildlife or livestock, hydrocarbons, or Resource Conservation and Recovery Act of 1976-exempt hazardous substances. At a minimum, the operator will net, screen, or cover open-topped tanks to exclude wildlife and livestock and prevent mortality. If the operator uses netting, the operator will cover and secure the open portion of the tank to prevent wildlife entry. The operator will net, screen, or cover the tanks until the operator removes the tanks from the location or the tanks no longer contain substances that could be harmful to wildlife or livestock. Use a maximum netting mesh size of 1 ½ inches. The netting must not be in contact with fluids and must not have holes or gaps.

#### **Chemical and Fuel Secondary Containment and Exclosure Screening**

The operator will prevent all hazardous, poisonous, flammable, and toxic substances from coming into contact with soil and water. At a minimum, the operator will install and maintain an impervious secondary containment system for any tank or barrel containing hazardous, poisonous, flammable, or toxic substances sufficient to contain the contents of the tank or barrel and any drips, leaks, and anticipated precipitation. The operator will dispose of fluids within the containment system that do not meet applicable state or U. S. Environmental Protection Agency livestock water standards in accordance with state law; the operator must not drain the fluids to the soil or ground. The operator will design, construct, and maintain all secondary containment systems to prevent wildlife and livestock exposure to harmful substances. At a minimum, the operator will install effective wildlife and livestock exclosure systems such as fencing, netting, expanded metal mesh, lids, and grate covers. Use a maximum netting mesh size of 1 ½ inches.

#### **Open-Vent Exhaust Stack Exclosures**

The operator will construct, modify, equip, and maintain all open-vent exhaust stacks on production equipment to prevent birds and bats from entering, and to discourage perching, roosting, and nesting. (*Recommended exclosure structures on open-vent exhaust stacks are in the shape of a cone.*) Production equipment includes, but may not be limited to, tanks, heater-treaters, separators, dehydrators, flare stacks, in-line units, and compressor mufflers.

#### **Containment Structures**

Proposed production facilities such as storage tanks and other vessels will have a secondary containment structure that is constructed to hold the capacity of 1.5 times the largest tank, plus freeboard to account for precipitation, unless more stringent protective requirements are deemed necessary.

**Painting Requirement**

All above-ground structures including meter housing that are not subject to safety requirements shall be painted a flat non-reflective paint color, **Shale Green** from the BLM Standard Environmental Color Chart (CC-001: June 2008).

**B. PIPELINES**

**STANDARD STIPULATIONS FOR SURFACE INSTALLED PIPELINES**

**A copy of the Grant and attachments, including stipulations, survey plat(s) and/or map(s), shall be on location during construction. BLM personnel may request to review a copy of your permit during construction to ensure compliance with all stipulations.**

Holder agrees to comply with the following stipulations to the satisfaction of the Authorized Officer:

1. Holder shall indemnify the United States against any liability for damage to life or property arising from the occupancy or use of public lands under this grant.
2. Holder shall comply with all applicable Federal laws and regulations existing or hereafter enacted or promulgated. In any event, Holder shall comply with the Toxic Substances Control Act of 1976 as amended, 15 USC § 2601 *et seq.* (1982) with regard to any toxic substances that are used, generated by or stored on the right-of-way or on facilities authorized under this right-of-way grant (*see* 40 CFR, Part 702-799 and in particular, provisions on polychlorinated biphenyls, 40 CFR 761.1-761.193). Additionally, any release of toxic substances (leaks, spills, etc.) in excess of the reportable quantity established by 40 CFR, Part 117 shall be reported as required by the Comprehensive Environmental Response, Compensation, and Liability Act, section 102b. A copy of any report required or requested by any Federal agency or State government as a result of a reportable release or spill of any toxic substances shall be furnished to the Authorized Officer concurrent with the filing of the reports to the involved Federal agency or State government.
3. Holder agrees to indemnify the United States against any liability arising from the release of any hazardous substance or hazardous waste (as these terms are defined in the Comprehensive Environmental Response, Compensation and Liability Act of 1980, 42 U.S.C. § 9601, *et seq.* or the Resource Conservation and Recovery Act, 42 U.S.C. 6901, *et seq.*) on the Right-of-Way (unless the release or threatened release is wholly unrelated to activity of the Right-of-Way Holder's activity on the Right-of-Way), or resulting from the activity of the Right-of-Way Holder on the Right-of-Way. This provision applies without regard to whether a release is caused by Holder, its agent, or unrelated third parties.

4. Holder shall be liable for damage or injury to the United States to the extent provided by 43 CFR Sec. 2883.1-4. Holder shall be held to a standard of strict liability for damage or injury to the United States resulting from pipe rupture, fire, or spills caused or substantially aggravated by any of the following within the right-of-way or permit area:

- a. Activities of Holder including, but not limited to: construction, operation, maintenance, and termination of the facility;
- b. Activities of other parties including, but not limited to:
  - (1) Land clearing
  - (2) Earth-disturbing and earth-moving work
  - (3) Blasting
  - (4) Vandalism and sabotage;

c. Acts of God.

The maximum limitation for such strict liability damages shall not exceed one million dollars (\$1,000,000) for any one event, and any liability in excess of such amount shall be determined by the ordinary rules of negligence of the jurisdiction in which the damage or injury occurred.

This section shall not impose strict liability for damage or injury resulting primarily from an act of war or from the negligent acts or omissions of the United States.

5. If, during any phase of the construction, operation, maintenance, or termination of the pipeline, any oil, salt water, or other pollutant should be discharged from the pipeline system, impacting Federal lands, the control and total removal, disposal, and cleaning up of such oil, salt water, or other pollutant, wherever found, shall be the responsibility of Holder, regardless of fault. Upon failure of Holder to control, dispose of, or clean up such discharge on or affecting Federal lands, or to repair all damages resulting therefrom, on the Federal lands, the Authorized Officer may take such measures as he/she deems necessary to control and clean up the discharge and restore the area, including, where appropriate, the aquatic environment and fish and wildlife habitats, at the full expense of Holder. Such action by the Authorized Officer shall not relieve Holder of any responsibility as provided herein.

6. All construction and maintenance activity shall be confined to the authorized right-of-way width of 20 feet. If the pipeline route follows an existing road or buried pipeline right-of-way, the surface pipeline shall be installed no farther than 10 feet from the edge of the road or buried pipeline right-of-way. If existing surface pipelines prevent this distance, the proposed surface pipeline shall be installed immediately adjacent to the outer surface pipeline. All construction and maintenance activity shall be confined to existing roads or right-of-ways.

7. No blading or clearing of any vegetation shall be allowed unless approved in writing by the Authorized Officer.

8. Holder shall install the pipeline on the surface in such a manner that will minimize suspension of the pipeline across low areas in the terrain. In hummocky or dune areas, the pipeline shall be "snaked" around hummocks and dunes rather than suspended across these features.

9. The pipeline shall be buried with a minimum of 24 inches under all roads, "two-tracks," and trails. Burial of the pipe will continue for 20 feet on each side of each crossing. The condition of the road, upon completion of construction, shall be returned to at least its former state with no bumps or dips remaining in the road surface.

10. The holder shall minimize disturbance to existing fences and other improvements on public lands. The holder is required to promptly repair improvements to at least their former state. Functional use of these improvements will be maintained at all times. The holder will contact the owner of any improvements prior to disturbing them. When necessary to pass through a fence line, the fence shall be braced on both sides of the passageway prior to cutting of the fence. No permanent gates will be allowed unless approved by the Authorized Officer.

11. In those areas where erosion control structures are required to stabilize soil conditions, the holder will install such structures as are suitable for the specific soil conditions being encountered and which are in accordance with sound resource management practices.

12. Excluding the pipe, all above-ground structures not subject to safety requirement shall be painted by the holder to blend with the natural color of the landscape. The paint used shall be a color which simulates "Standard Environmental Colors" – **Shale Green**, Munsell Soil Color No. 5Y 4/2; designated by the Rocky Mountain Five State Interagency Committee.

13. The pipeline will be identified by signs at the point of origin and completion of the right-of-way and at all road crossings. At a minimum, signs will state the holder's name, BLM serial number, and the product being transported. Signs will be maintained in a legible condition for the life of the pipeline.

14. The holder shall not use the pipeline route as a road for purposes other than routine maintenance as determined necessary by the Authorized Officer in consultation with the holder. The holder will take whatever steps are necessary to ensure that the pipeline route is not used as a roadway.

15. Any cultural and/or paleontological resource (historic or prehistoric site or object) discovered by the holder, or any person working on his behalf, on public or Federal land shall be immediately reported to the authorized officer. Holder shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the authorized officer. An evaluation of the discovery will be made by the authorized officer to determine appropriate cultural or scientific values. The holder will be responsible for the cost of evaluation and any decision as to proper mitigation measures will be made

by the authorized officer after consulting with the holder.

16. The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes the roads, powerline corridor, and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

17. Surface pipelines shall be less than or equal to 4 inches and a working pressure below 125 psi.

### BURIED PIPELINE STIPULATIONS

A copy of the application (Grant, APD, or Sundry Notice) and attachments, including conditions of approval, survey plat and/or map, will be on location during construction. BLM personnel may request to you a copy of your permit during construction to ensure compliance with all stipulations.

Holder agrees to comply with the following stipulations to the satisfaction of the Authorized Officer:

1. The Holder shall indemnify the United States against any liability for damage to life or property arising from the occupancy or use of public lands under this grant.
2. The Holder shall comply with all applicable Federal laws and regulations existing or hereafter enacted or promulgated. In any event, the holder shall comply with the Toxic Substances Control Act of 1976 as amended, 15 USC 2601 et seq. (1982) with regards to any toxic substances that are used, generated by or stored on the right-of-way or on facilities authorized under this right-of-way grant. (See 40 CFR Part 702-799 and especially, provisions on polychlorinated biphenyls, 40 CFR 761.1-761.193.) Additionally, any release of toxic substances (leaks, spills, etc.) in excess of the reportable quantity established by 40 CFR Part 117 shall be reported as required by the Comprehensive Environmental Response, Compensation, and Liability Act, section 102b. A copy of any report required or requested by any Federal agency or State government as a result of a reportable release or spill of any toxic substances shall be furnished to the authorized officer concurrent with the filing of the reports to the involved Federal agency or State government.
3. The holder agrees to indemnify the United States against any liability arising from the release of any hazardous substance or hazardous waste (as these terms are defined in the Comprehensive Environmental Response, Compensation and Liability Act of 1980, 42 U.S.C. 9601, et seq. or the Resource Conservation and Recovery Act, 42 U.S.C.6901, et

seq.) on the Right-of-Way (unless the release or threatened release is wholly unrelated to the Right-of-Way holder's activity on the Right-of-Way), or resulting from the activity of the Right-of-Way holder on the Right-of-Way. This agreement applies without regard to whether a release is caused by the holder, its agent, or unrelated third parties.

4. If, during any phase of the construction, operation, maintenance, or termination of the pipeline, any oil or other pollutant should be discharged from the pipeline system, impacting Federal lands, the control and total removal, disposal, and cleaning up of such oil or other pollutant, wherever found, shall be the responsibility of holder, regardless of fault. Upon failure of holder to control, dispose of, or clean up such discharge on or affecting Federal lands, or to repair all damages resulting therefrom, on the Federal lands, the Authorized Officer may take such measures as he deems necessary to control and clean up the discharge and restore the area, including where appropriate, the aquatic environment and fish and wildlife habitats, at the full expense of the holder. Such action by the Authorized Officer shall not relieve holder of any responsibility as provided herein.

5. All construction and maintenance activity will be confined to the authorized right-of-way.

6. The pipeline will be buried with a minimum cover of 36 inches between the top of the pipe and ground level.

7. The maximum allowable disturbance for construction in this right-of-way will be 30 feet:

- Blading of vegetation within the right-of-way will be allowed: maximum width of blading operations will not exceed 20 feet. The trench is included in this area. (*Blading is defined as the complete removal of brush and ground vegetation.*)
- Clearing of brush species within the right-of-way will be allowed: maximum width of clearing operations will not exceed 30 feet. The trench and bladed area are included in this area. (*Clearing is defined as the removal of brush while leaving ground vegetation (grasses, weeds, etc.) intact. Clearing is best accomplished by holding the blade 4 to 6 inches above the ground surface.*)
- The remaining area of the right-of-way (if any) shall only be disturbed by compressing the vegetation. (*Compressing can be caused by vehicle tires, placement of equipment, etc.*)

8. The holder shall stockpile an adequate amount of topsoil where blading is allowed. The topsoil to be stripped is approximately 6 inches in depth. The topsoil will be

segregated from other spoil piles from trench construction. The topsoil will be evenly distributed over the bladed area for the preparation of seeding.

9. The holder shall minimize disturbance to existing fences and other improvements on public lands. The holder is required to promptly repair improvements to at least their former state. Functional use of these improvements will be maintained at all times. The holder will contact the owner of any improvements prior to disturbing them. When necessary to pass through a fence line, the fence shall be braced on both sides of the passageway prior to cutting of the fence. No permanent gates will be allowed unless approved by the Authorized Officer.

10. Vegetation, soil, and rocks left as a result of construction or maintenance activity will be randomly scattered on this right-of-way and will not be left in rows, piles, or berms, unless otherwise approved by the Authorized Officer. The entire right-of-way shall be recontoured to match the surrounding landscape. The backfilled soil shall be compacted and a 6 inch berm will be left over the ditch line to allow for settling back to grade.

11. In those areas where erosion control structures are required to stabilize soil conditions, the holder will install such structures as are suitable for the specific soil conditions being encountered and which are in accordance with sound resource management practices.

12. The holder will reseed all disturbed areas. Seeding will be done according to the attached seeding requirements, using the following seed mix.

- |  |  |
|--|--|
| <input type="checkbox"/> seed mixture 1            | <input type="checkbox"/> seed mixture 3          |
| <input checked="" type="checkbox"/> seed mixture 2 | <input type="checkbox"/> seed mixture 4          |
| <input type="checkbox"/> seed mixture 2/LPC        | <input type="checkbox"/> Aplomado Falcon Mixture |

13. All above-ground structures not subject to safety requirements shall be painted by the holder to blend with the natural color of the landscape. The paint used shall be color which simulates "Standard Environmental Colors" – **Shale Green**, Munsell Soil Color No. 5Y 4/2.

14. The pipeline will be identified by signs at the point of origin and completion of the right-of-way and at all road crossings. At a minimum, signs will state the holder's name, BLM serial number, and the product being transported. All signs and information thereon will be posted in a permanent, conspicuous manner, and will be maintained in a legible condition for the life of the pipeline.

15. The holder shall not use the pipeline route as a road for purposes other than routine maintenance as determined necessary by the Authorized Officer in consultation with the holder before maintenance begins. The holder will take whatever steps are necessary to ensure that the pipeline route is not used as a roadway. As determined necessary during the life of the pipeline, the Authorized Officer may ask the holder to construct temporary deterrence structures.

16. Any cultural and/or paleontological resources (historic or prehistoric site or object) discovered by the holder, or any person working on his behalf, on public or Federal land shall be immediately reported to the Authorized Officer. Holder shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery will be made by the Authorized Officer to determine appropriate actions to prevent the loss of significant cultural or scientific values. The holder will be responsible for the cost of evaluation and any decision as to proper mitigation measures will be made by the Authorized Officer after consulting with the holder.

17. The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes associated roads, pipeline corridor and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

18. Escape Ramps - The operator will construct and maintain pipeline/utility trenches [that are not otherwise fenced, screened, or netted] to prevent livestock, wildlife, and humans from becoming entrapped. At a minimum, the operator will construct and maintain escape ramps, ladders, or other methods of avian and terrestrial wildlife escape in the trenches according to the following criteria:

- a. Any trench left open for eight (8) hours or less is not required to have escape ramps; however, before the trench is backfilled, the contractor/operator shall inspect the trench for wildlife, remove all trapped wildlife, and release them at least 100 yards from the trench.
- b. For trenches left open for eight (8) hours or more, earthen escape ramps (built at no more than a 30 degree slope and spaced no more than 500 feet apart) shall be placed in the trench.

**C. ELECTRIC LINES**  
STANDARD STIPULATIONS FOR OVERHEAD ELECTRIC DISTRIBUTION  
LINES

**A copy of the grant and attachments, including stipulations, survey plat and/or map, will be on location during construction. BLM personnel may request to you a copy of your permit during construction to ensure compliance with all stipulations.**

Holder agrees to comply with the following stipulations to the satisfaction of the Authorized Officer:

1. The holder shall indemnify the United States against any liability for damage to life or property arising from the occupancy or use of public lands under this grant.
2. The holder shall comply with all applicable Federal laws and regulations existing or hereafter enacted or promulgated. In any event, the holder shall comply with the Toxic Substances Control Act of 1976 as amended, 15 USC 2601 et seq. (1982) with regards to any toxic substances that are used, generated by or stored on the right-of-way or on facilities authorized under this right-of-way grant. (See 40 CFR, Part 702-799 and especially, provisions on polychlorinated biphenyls, 40 CFR 761.1-761.193.) Additionally, any release of toxic substances (leaks, spills, etc.) in excess of the reportable quantity established by 40 CFR, Part 117 shall be reported as required by the Comprehensive Environmental Response, Compensation, and Liability Act, section 102b. A copy of any report required or requested by any Federal agency or State government as a result of a reportable release or spill of any toxic substances shall be furnished to the authorized officer concurrent with the filing of the reports to the involved Federal agency or State government.
3. The holder agrees to indemnify the United States against any liability arising from the release of any hazardous substance or hazardous waste (as these terms are defined in the Comprehensive Environmental Response, Compensation and Liability Act of 1980, 42 U.S.C. 9601, et seq. or the Resource Conservation and Recovery Act, 42 U.S.C. 6901, et seq.) on the Right-of-Way (unless the release or threatened release is wholly unrelated to the Right-of-Way holder's activity on the Right-of-Way), or resulting from the activity of the Right-of-Way holder on the Right-of-Way. This agreement applies without regard to whether a release is caused by the holder, its agent, or unrelated third parties.
4. There will be no clearing or blading of the right-of-way unless otherwise agreed to in writing by the Authorized Officer.
5. Power lines shall be constructed and designed in accordance to standards outlined in "Suggested Practices for Avian Protection on Power lines: The State of the Art in 2006" Edison Electric Institute, APLIC, and the California Energy Commission 2006 . The holder shall assume the burden and expense of proving that pole designs not shown in the above publication deter raptor perching, roosting, and nesting. Such proof shall be provided by a raptor expert approved by the Authorized Officer. The BLM reserves the right to require modification or additions to all powerline structures placed on this right-of-way, should they be necessary to ensure the safety of large perching birds. Such modifications and/or additions shall be made by the holder without liability or expense to the United States.

Raptor deterrence will consist of but not limited to the following: triangle perch discouragers shall be placed on each side of the cross arms and a nonconductive perching deterrence shall be placed on all vertical poles that extend past the cross arms.

6. The holder shall minimize disturbance to existing fences and other improvements on public lands. The holder is required to promptly repair improvements to at least their former state. Functional use of these improvements will be maintained at all times. The holder will contact the owner of any improvements prior to disturbing them. When necessary to pass through a fence line, the fence shall be braced on both sides of the passageway prior to cutting the fence. No permanent gates will be allowed unless approved by the Authorized Officer.

7. The BLM serial number assigned to this authorization shall be posted in a permanent, conspicuous manner where the power line crosses roads and at all serviced facilities. Numbers will be at least two inches high and will be affixed to the pole nearest the road crossing and at the facilities served.

8. Upon cancellation, relinquishment, or expiration of this grant, the holder shall comply with those abandonment procedures as prescribed by the Authorized Officer.

9. All surface structures (poles, lines, transformers, etc.) shall be removed within 180 days of abandonment, relinquishment, or termination of use of the serviced facility or facilities or within 180 days of abandonment, relinquishment, cancellation, or expiration of this grant, whichever comes first. This will not apply where the power line extends service to an active, adjoining facility or facilities.

10. Any cultural and/or paleontological resource (historic or prehistoric site or object) discovered by the holder, or any person working on his behalf, on public or Federal land shall be immediately reported to the Authorized Officer. Holder shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery will be made by the Authorized Officer to determine appropriate actions to prevent the loss of significant cultural or scientific values. The holder will be responsible for the cost of evaluation and any decision as to proper mitigation measures will be made by the Authorized Officer after consulting with the holder.

11. Special Stipulations:

- For reclamation remove poles, lines, transformer, etc. and dispose of properly.
- Fill in any holes from the poles removed.

## **VIII. INTERIM RECLAMATION**

During the life of the development, all disturbed areas not needed for active support of production operations should undergo interim reclamation in order to minimize the environmental impacts of development on other resources and uses.

Within six (6) months of well completion, operators should work with BLM surface management specialists (Jim Amos: 575-234-5909) to devise the best strategies to reduce the size of the location. Interim reclamation should allow for remedial well operations, as well as safe and efficient removal of oil and gas.

During reclamation, the removal of caliche is important to increasing the success of revegetating the site. Removed caliche that is free of contaminants may be used for road repairs, fire walls or for building other roads and locations. In order to operate the well or complete workover operations, it may be necessary to drive, park and operate on restored interim vegetation within the previously disturbed area. Disturbing revegetated areas for production or workover operations will be allowed. If there is significant disturbance and loss of vegetation, the area will need to be revegetated. Communicate with the appropriate BLM office for any exceptions/exemptions if needed.

All disturbed areas after they have been satisfactorily prepared need to be reseeded with the seed mixture provided below.

Upon completion of interim reclamation, the operator shall submit a Sundry Notices and Reports on Wells, Subsequent Report of Reclamation (Form 3160-5).

## **IX. FINAL ABANDONMENT & RECLAMATION**

At final abandonment, well locations, production facilities, and access roads must undergo "final" reclamation so that the character and productivity of the land are restored.

Earthwork for final reclamation must be completed within six (6) months of well plugging. All pads, pits, facility locations and roads must be reclaimed to a satisfactory revegetated, safe, and stable condition, unless an agreement is made with the landowner or BLM to keep the road and/or pad intact.

After all disturbed areas have been satisfactorily prepared, these areas need to be revegetated with the seed mixture provided below. Seeding should be accomplished by drilling on the contour whenever practical or by other approved methods. Seeding may need to be repeated until revegetation is successful, as determined by the BLM.

Operators shall contact a BLM surface protection specialist prior to surface abandonment operations for site specific objectives (Jim Amos: 575-234-5909).

## Seed Mixture 2, for Sandy Sites

The holder shall seed all disturbed areas with the seed mixture listed below. The seed mixture shall be planted in the amounts specified in pounds of pure live seed (PLS)\* per acre. There shall be no primary or secondary noxious weeds in the seed mixture. Seed will be tested and the viability testing of seed will be done in accordance with State law (s) and within nine (9) months prior to purchase. Commercial seed will be either certified or registered seed. The seed container will be tagged in accordance with State law(s) and available for inspection by the authorized officer.

Seed will be planted using a drill equipped with a depth regulator to ensure proper depth of planting where drilling is possible. The seed mixture will be evenly and uniformly planted over the disturbed area (smaller/heavier seeds have a tendency to drop the bottom of the drill and are planted first). The holder shall take appropriate measures to ensure this does not occur. Where drilling is not possible, seed will be broadcast and the area shall be raked or chained to cover the seed. When broadcasting the seed, the pounds per acre are to be doubled. The seeding will be repeated until a satisfactory stand is established as determined by the authorized officer. Evaluation of growth will not be made before completion of at least one full growing season after seeding.

Species to be planted in pounds of pure live seed\* per acre:

<u>Species</u>	<u>lb/acre</u>
Sand dropseed ( <i>Sporobolus cryptandrus</i> )	1.0
Sand love grass ( <i>Eragrostis trichodes</i> )	1.0
Plains bristlegrass ( <i>Setaria macrostachya</i> )	2.0

\*Pounds of pure live seed:

Pounds of seed x percent purity x percent germination = pounds pure live seed



U.S. Department of the Interior  
BUREAU OF LAND MANAGEMENT

# Operator Certification Data Report

11/30/2018

## Operator Certification

*I hereby certify that I, or someone under my direct supervision, have inspected the drill site and access route proposed herein; that I am familiar with the conditions which currently exist; that I have full knowledge of state and Federal laws applicable to this operation; that the statements made in this APD package are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for the operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filing of false statements.*

**NAME:** Aricka Easterling

**Signed on:** 05/31/2018

**Title:** Regulatory Analyst

**Street Address:** 202 S. Cheyenne Ave, Ste 1000

**City:** Tulsa

**State:** OK

**Zip:** 74103

**Phone:** (918)560-7060

**Email address:** aeasterling@cimarex.com

## Field Representative

**Representative Name:**

**Street Address:**

**City:**

**State:**

**Zip:**

**Phone:**

**Email address:**



APD ID: 10400030762

Submission Date: 05/31/2018

Operator Name: CIMAREX ENERGY COMPANY

Well Name: RED HILLS UNIT

Well Number: 131H



[Show Final Text](#)

Well Type: CONVENTIONAL GAS WELL

Well Work Type: Drill

### Section 1 - General

APD ID: 10400030762

Tie to previous NOS? 10400028237 Submission Date: 05/31/2018

BLM Office: CARLSBAD

User: Aricka Easterling

Title: Regulatory Analyst

Federal/Indian APD: FED

Is the first lease penetrated for production Federal or Indian? FED

Lease number: NMNM0106040A

Lease Acres: 240

Surface access agreement in place?

Allotted?

Reservation:

Agreement in place? NO

Federal or Indian agreement:

Agreement number:

Agreement name:

Keep application confidential? YES

Permitting Agent? NO

APD Operator: CIMAREX ENERGY COMPANY

Operator letter of designation:

### Operator Info

Operator Organization Name: CIMAREX ENERGY COMPANY

Operator Address: 600 N. Marienfeld St., Suite 600

Zip: 79701

Operator PO Box:

Operator City: Midland

State: OK

Operator Phone: (432)620-1936

Operator Internet Address: [tstathem@cimarex.com](mailto:tstathem@cimarex.com)

### Section 2 - Well Information

Well in Master Development Plan? NO

Mater Development Plan name:

Well in Master SUPO? NO

Master SUPO name:

Well in Master Drilling Plan? NO

Master Drilling Plan name:

Well Name: RED HILLS UNIT

Well Number: 131H

Well API Number:

Field/Pool or Exploratory? Field and Pool

Field Name: BONE SPRING

Pool Name: BONE SPRING

Is the proposed well in an area containing other mineral resources? USEABLE WATER,NATURAL GAS,OIL

**Operator Name:** CIMAREX ENERGY COMPANY

**Well Name:** RED HILLS UNIT

**Well Number:** 131H

**Describe other minerals:**

**Is the proposed well in a Helium production area?** N    **Use Existing Well Pad?** NO    **New surface disturbance?**

**Type of Well Pad:** MULTIPLE WELL

**Multiple Well Pad Name:** RED HILLS UNIT 32-5 W2W2    **Number:** PAD 1

**Well Class:** HORIZONTAL

**Number of Legs:** 1

**Well Work Type:** Drill

**Well Type:** CONVENTIONAL GAS WELL

**Describe Well Type:**

**Well sub-Type:** EXPLORATORY (WILDCAT)

**Describe sub-type:**

**Distance to town:** 24 Miles

**Distance to nearest well:** 20 FT

**Distance to lease line:** 330 FT

**Reservoir well spacing assigned acres Measurement:** 320 Acres

**Well plat:** Red\_Hills\_Unit\_131H\_C102\_Plat\_20180531145849.pdf

**Well work start Date:** 11/01/2018

**Duration:** 30 DAYS

**Section 3 - Well Location Table**

**Survey Type:** RECTANGULAR

**Describe Survey Type:**

**Datum:** NAD83

**Vertical Datum:** NAVD88

**Survey number:**

	NS-Foot	NS Indicator	EW-Foot	EW Indicator	Twsp	Range	Section	Aliquot/Lot/Tract	Latitude	Longitude	County	State	Meridian	Lease Type	Lease Number	Elevation	MD	TVD
SHL Leg #1	330	FNL	410	FWL	25S	33E	32	Aliquot NWN W	32.093413	-103.601531	LEA	NEW MEXI CO	NEW MEXI CO	S	STATE	3396	0	0
KOP Leg #1	330	FNL	663	FWL	25S	33E	32	Aliquot NWN W	32.0934083	-103.6007111	LEA	NEW MEXI CO	NEW MEXI CO	S	STATE	-8166	11574	11562
PPP Leg #1	1320	FNL	660	FWL	26S	33E	5	Aliquot NWS W	32.076222	-103.6007167	LEA	NEW MEXI CO	NEW MEXI CO	F	NMNM 010604 0A	-8644	18100	12040

**Operator Name: CIMAREX ENERGY COMPANY**

**Well Name: RED HILLS UNIT**

**Well Number: 131H**

	NS-Foot	NS Indicator	EW-Foot	EW Indicator	Twsp	Range	Section	Aliquot/Lot/Tract	Latitude	Longitude	County	State	Meridian	Lease Type	Lease Number	Elevation	MD	TVD
EXIT Leg #1	263 0	FSL	660	FWL	26S	33E	5	Aliquot SWN W	32.07264 72	- 103.6007 167	LEA	NEW MEXI CO	NEW MEXI CO	F	NMNM 010604 0A	- 864 4	194 00	120 40
BHL Leg #1	330	FSL	660	FWL	26S	33E	5	Aliquot SWS W	32.06620 4	- 103.6007 21	LEA	NEW MEXI CO	NEW MEXI CO	F	NMNM 016097 3	- 864 4	217 44	120 40

**Operator Name:** CIMAREX ENERGY COMPANY

**Well Name:** RED HILLS UNIT

**Well Number:** 131H

intermediate casing. After installation the pack-off and lower flange will be pressure tested to 3000 psi. The surface casing string will be tested as per Onshore Order No. 2 to at least 0.22 psi/ft or 1500 psi, whichever is greater. The casing string utilizing steel body pack-off will be tested to 70% of casing burst. If well conditions dictate conventional slips will be set and BOPE will be tested to appropriate pressures based on permitted pressure requirements.

**Choke Diagram Attachment:**

Red\_Hills\_Unit\_131H\_Choke\_2M3M\_20180531151000.pdf

**BOP Diagram Attachment:**

Red\_Hills\_Unit\_131H\_BOP\_2M\_20180531151017.pdf

**Pressure Rating (PSI):** 3M

**Rating Depth:** 21744

**Equipment:** A BOP consisting of three rams, including one blind ram and two pipe rams and one annular preventer. An accumulator that meets the requirements in Onshore Order #2 for the pressure rating of the BOP stack. A rotating head may be installed as needed. A Kelly clock will be installed and maintained in operable condition and a drill string safety valve in the open position will be available on the rig floor.

**Requesting Variance?** YES

**Variance request:** Co-flex line between the BOP and choke manifold. Certification for proposed co-flex hose is attached. The hose is not required by the manufacturer to be anchored. In the event the specific hose is not available, one of equal or higher rating will be used. Variance to include Hammer Union connections on lines downstream of the buffer tank only.

**Testing Procedure:** A multi-bowl wellhead system will be utilized. After running the 13-3/8" surface casing, a 13 5/8" BOP/BOPE system with a minimum working pressure of 3000 psi will be installed on the wellhead system and will be pressure tested to 250 psi low followed by a 3000 psi test. Annular will be tested to 50% of working pressure. The pressure test will be repeated at least every 30 days, as per Onshore Order No. 2. The multi-bowl wellhead will be installed by vendor's representative. A copy of the installation instructions has been sent to the BLM field office. The wellhead will be installed by a third-party welder while being monitored by the wellhead vendor representative. All BOP equipment will be tested utilizing a conventional test plug. Not a cup or J-packer type. A solid steel body pack-off will be utilized after running and cementing the intermediate casing. After installation the pack-off and lower flange will be pressure tested to 3000 psi. The surface casing string will be tested as per Onshore Order No. 2 to at least 0.22 psi/ft or 1500 psi, whichever is greater. The casing string utilizing steel body pack-off will be tested to 70% of casing burst. If well conditions dictate conventional slips will be set and BOPE will be tested to appropriate pressures based on permitted pressure requirements.

**Choke Diagram Attachment:**

Red\_Hills\_Unit\_131H\_Choke\_2M3M\_20180531151056.pdf

**BOP Diagram Attachment:**

Red\_Hills\_Unit\_131H\_BOP\_3M\_20180531151106.pdf

**Section 3 - Casing**

Casing ID	String Type	Hole Size	Csg Size	Condition	Standard	Tapered String	Top Set MD	Bottom Set MD	Top Set TVD	Bottom Set TVD	Top Set MSL	Bottom Set MSL	Calculated casing length MD	Grade	Weight	Joint Type	Collapse SF	Burst SF	Joint SF Type	Joint SF	Body SF Type	Body SF
-----------	-------------	-----------	----------	-----------	----------	----------------	------------	---------------	-------------	----------------	-------------	----------------	-----------------------------	-------	--------	------------	-------------	----------	---------------	----------	--------------	---------

Operator Name: CIMAREX ENERGY COMPANY

Well Name: RED HILLS UNIT

Well Number: 131H

Casing ID	String Type	Hole Size	Csg Size	Condition	Standard	Tapered String	Top Set MD	Bottom Set MD	Top Set TVD	Bottom Set TVD	Top Set MSL	Bottom Set MSL	Calculated casing length MD	Grade	Weight	Joint Type	Collapse SF	Burst SF	Joint SF Type	Joint SF	Body SF Type	Body SF
1	SURFACE	17.5	13.375	NEW	NON API	N	0	1050	0	1050	0	1050	1050	H-40	48	STC	1.54	3.6	BUOY	6.39	BUOY	6.39
2	INTERMEDIATE	12.25	9.625	NEW	API	N	0	4875	0	4875	0	4875	4875	J-55	40	LTC	1.21	1.53	BUOY	2.67	BUOY	2.67
3	PRODUCTION	8.75	5.5	NEW	API	N	0	11575	0	11575	0	11575	11575	L-80	20	LTC	1.63	1.7	BUOY	1.73	BUOY	1.73
4	PRODUCTION	8.75	5.5	NEW	API	N	11575	21744	11575	21744	11575	21744	10169	L-80	20	BUTT	1.57	1.6	BUOY	50.11	BUOY	50.11

#### Casing Attachments

Casing ID: 1 String Type: SURFACE

Inspection Document:

Spec Document:

Red\_Hills\_Unit\_131H\_Spec\_Sheet\_20180531151243.pdf

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

Red\_Hills\_Unit\_131H\_Casing\_Assumptions\_20180531151309.pdf

Casing ID: 2 String Type: INTERMEDIATE

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

Red\_Hills\_Unit\_131H\_Casing\_Assumptions\_20180531151339.pdf

Operator Name: CIMAREX ENERGY COMPANY

Well Name: RED HILLS UNIT

Well Number: 131H

**Casing Attachments**

Casing ID: 3 String Type: PRODUCTION

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

Red\_Hills\_Unit\_131H\_Casing\_Assumptions\_20180531151503.pdf

Casing ID: 4 String Type: PRODUCTION

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

Red\_Hills\_Unit\_131H\_Casing\_Assumptions\_20180531151556.pdf

**Section 4 - Cement**

String Type	Lead/Tail	Stage Tool Depth	Top MD	Bottom MD	Quantity(sx)	Yield	Density	Cu Ft	Excess%	Cement type	Additives
SURFACE	Lead		0	1050	509	1.72	13.5	875	50	Class C	Bentonite
SURFACE	Tail		0	1050	136	1.34	14.8	182	25	Class C	LCM
INTERMEDIATE	Lead		0	4875	923	1.88	12.9	1735	50	35:65 (Poz:C)	Salt, Bentonite
INTERMEDIATE	Tail		0	4875	285	1.34	14.8	381	25	Class C	LCM
PRODUCTION	Lead		0	1157 5	596	3.64	10.3	2168	25	Tuned Light	LCM

**Operator Name:** CIMAREX ENERGY COMPANY

**Well Name:** RED HILLS UNIT

**Well Number:** 131H

String Type	Lead/Tail	Stage Tool Depth	Top MD	Bottom MD	Quantity(sx)	Yield	Density	Cu Ft	Excess%	Cement type	Additives
PRODUCTION	Tail		0	1157 5	2174	1.3	14.2	2826	10	50:50 (Poz:H)	Salt, Bentonite, Fluid Loss, Dispersant, SMS
PRODUCTION	Lead		1157 5	2174 4	596	3.64	10.3	2168	25	Tuned Light	LCM
PRODUCTION	Tail		1157 5	2174 4	2174	1.3	14.2	2826	10	50:50 (Poz:H)	Salt, Bentonite, Fluid Loss, Dispersant, SMS

### Section 5 - Circulating Medium

**Mud System Type:** Closed

**Will an air or gas system be Used?** NO

**Description of the equipment for the circulating system in accordance with Onshore Order #2:**

**Diagram of the equipment for the circulating system in accordance with Onshore Order #2:**

**Describe what will be on location to control well or mitigate other conditions:** Sufficient mud materials will be kept on location at all times in order to combat lost circulation or unexpected kicks. In order to run DSTs, open hole logs, and casing, the viscosity and water loss may have to be adjusted in order to meet these needs.

**Describe the mud monitoring system utilized:** PVT/Pason/Visual Monitoring

### Circulating Medium Table

Top Depth	Bottom Depth	Mud Type	Min Weight (lbs/gal)	Max Weight (lbs/gal)	Density (lbs/cu ft)	Gel Strength (lbs/100 sqft)	PH	Viscosity (CP)	Salinity (ppm)	Filtration (cc)	Additional Characteristics
0	1050	SPUD MUD	8.3	8.8							
1050	4875	SALT SATURATED	9.7	10.2							
4875	2174 4	OTHER : FW/Cut Brine	8.5	9							

**Operator Name:** CIMAREX ENERGY COMPANY

**Well Name:** RED HILLS UNIT

**Well Number:** 131H

### Section 6 - Test, Logging, Coring

**List of production tests including testing procedures, equipment and safety measures:**

No DST Planned

**List of open and cased hole logs run in the well:**

CNL,DS,GR

**Coring operation description for the well:**

n/a

### Section 7 - Pressure

**Anticipated Bottom Hole Pressure:** 5634

**Anticipated Surface Pressure:** 2088.2

**Anticipated Bottom Hole Temperature(F):** 188

**Anticipated abnormal pressures, temperatures, or potential geologic hazards? YES**

**Describe:**

Lost circulation may be encountered in the Delaware mountain group. Abnormal pressure as well as hole stability issues may be encountered in the Wolfcamp.

**Contingency Plans geohazards description:**

Lost circulation material will be available, as well as additional drilling fluid along with the fluid volume in the drilling rig pit system. Drilling fluid can be mixed on location or mixed in vendor mud plant and trucked to location if needed. Sufficient barite will be available to maintain appropriate mud weight for the Wolfcamp interval.

**Contingency Plans geohazards attachment:**

**Hydrogen Sulfide drilling operations plan required? YES**

**Hydrogen sulfide drilling operations plan:**

Red\_Hills\_Unit\_131H\_H2S\_Plan\_20180531152009.pdf

### Section 8 - Other Information

**Proposed horizontal/directional/multi-lateral plan submission:**

Red\_Hills\_Unit\_131H\_AC\_Report\_20180531152027.pdf

Red\_Hills\_Unit\_131H\_Directional\_Plan\_20180531152028.pdf

**Other proposed operations facets description:**

**Other proposed operations facets attachment:**

Red\_Hills\_Unit\_131H\_Gas\_Capture\_Plan\_20180531152101.pdf

Red\_Hills\_Unit\_131H\_Flex\_Hose\_20180531152101.pdf

Red\_Hills\_Unit\_131H\_Multibowl\_Wellhead\_20180531152102.pdf


Red\_Hills\_Unit\_131H\_Drilling\_Plan\_20180531153215.pdf

**Other Variance attachment:**

**Operator Name:** CIMAREX ENERGY COMPANY

**Well Name:** RED HILLS UNIT


**Well Number:** 131H



**Drilling Operations  
 Choke Manifold  
 2M/3M Service**

2M: 1 Valve Minimum  
 3M: 2 Valves Minimum  
 HCR Valve is optional

**Choke Manifold Diagram  
 Red Hills Unit 131H  
 Cimarex Energy Co.  
 32-25S-33E  
 Lea Co., NM**



2M: 1 Valve Minimum  
 3M: 2 Valves Minimum  
 HCR Valve is optional


REMOTELY OPERATED Adjustable Choke

Choke Isolation Valve




Choke Manifold Diagram  
 Red Hills Unit 131H  
 Cimarex Energy Co.  
 32-25S-33E  
 Lea Co., NM

**Drilling Operations  
 Choke Manifold  
 2M/3M Service**

Drilling 8-3/4" hole  
below 9 5/8" Casing



SRR & A



3000# BOP  
Red Hills Unit 131H  
Cimarex Energy Co.  
32-25S-33E  
Lea Co., NM

Drilling 12-1/4" hole  
below 13 3/8" Casing

Fill Line

Flowline

2000# (2M)  
BOP

SRR & A

Annular Preventer

Pipe Rams

Blind Rams

2" Minimum Kill Line

2" Minimum Choke Line

Kill Line

Choke Line


Drilling Spool

1 Kill Line Valve  
(Minimum)

1 Choke Line Valve  
(Minimum)

13-5/8" 3000 psi x 13 3/8 SOW Slip-on Casing Head

2000# BOP  
Red Hills Unit 131H  
Cimarex Energy Co.  
32-25S-33E  
Lea Co., NM



[Print](#)



## Red Hills Unit 131H Surface Casing Spec Sheet

### OCTG Performance Data

#### Casing Performance

Availability: ERW

##### Pipe Body Geometry

Outside Diameter:	13.375 in	Inside Diameter:	12.715 in
Wall Thickness:	0.330 in	Cross Section Area:	13.524 sq in
Nominal Weight:	48.00 lb/ft	Drift Diameter:	12.559 in
Plain End Weight:	46.02 lb/ft	Alternate Drift Diameter:	-

##### Pipe Body Performance

Grade:	H40	Collapse Strength (ERW):	740 psi
Pipe Body Yield Strength:	541000 lbf	Collapse Strength (SMLS):	-

#### SC Connection

##### Connection Geometry

	Optimum	Minimum	Maximum
Make Up Torque:	3220 lb-ft	2420 lb-ft	4030 lb-ft
Coupling Outside Diameter:	14.375 in		

##### Connection Performance

Grade:	H40	Minimum Internal Yield Pressure:	1730 psi
Joint Strength:	322000 lbf		

#### LC Connection

##### Connection Geometry

	Optimum	Minimum	Maximum
Make Up Torque:	-	-	-
Coupling Outside Diameter:	14.375 in		

##### Connection Performance

Grade:	H40	Minimum Internal Yield Pressure:	-
Joint Strength:	-		

#### BC Connection

##### Connection Geometry

	Optimum	Minimum	Maximum
Make Up Torque:	-	-	-
Coupling Outside Diameter:	14.375 in		

##### Connection Performance

Grade:	H40	Minimum Internal Yield Pressure:	-
Joint Strength:	-		

#### PE Connection

##### Connection Geometry

	Optimum	Minimum	Maximum
Make Up Torque:	-	-	-
Coupling Outside Diameter:	14.375 in		

### Connection Performance

Grade:	H40	Minimum Internal Yield Pressure:	1730 psi
Joint Strength:	-		

## Red Hills Unit 131H Casing Assumptions

### Casing Program

Hole Size	Casing Depth From	Casing Depth To	Casing Size	Weight (lb/ft)	Grade	Conn.	SF Collapse	SF Burst	SF Tension
17 1/2	0	1050	13-3/8"	48.00	H-40/J-55 Hybrid	ST&C	1.54	3.60	6.39
12 1/4	0	4875	9-5/8"	40.00	J-55	LT&C	1.21	1.53	2.67
8 3/4	0	11575	5-1/2"	20.00	L-80	LT&C	1.63	1.70	1.73
8 3/4	11575	21744	5-1/2"	20.00	L-80	BT&C	1.57	1.60	50.11
BLM Minimum Safety Factor							1.125	1	1.6 Dry 1.8 Wet

TVD was used on all calculations.

All casing strings will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.h

## Red Hills Unit 131H Casing Assumptions

### Casing Program

Hole Size	Casing Depth From	Casing Depth To	Casing Size	Weight (lb/ft)	Grade	Conn.	SF Collapse	SF Burst	SF Tension
17 1/2	0	1050	13-3/8"	48.00	H-40/J-55 Hybrid	ST&C	1.54	3.60	6.39
12 1/4	0	4875	9-5/8"	40.00	J-55	LT&C	1.21	1.53	2.67
8 3/4	0	11575	5-1/2"	20.00	L-80	LT&C	1.63	1.70	1.73
8 3/4	11575	21744	5-1/2"	20.00	L-80	BT&C	1.57	1.60	50.11
BLM Minimum Safety Factor							1.125	1	1.6 Dry 1.8 Wet

TVD was used on all calculations.

All casing strings will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.h

**Red Hills Unit 131H**  
**Casing Assumptions**

**Casing Program**

Hole Size	Casing Depth From	Casing Depth To	Casing Size	Weight (lb/ft)	Grade	Conn.	SF Collapse	SF Burst	SF Tension
17 1/2	0	1050	13-3/8"	48.00	H-40/J-55 Hybrid	ST&C	1.54	3.60	6.39
12 1/4	0	4875	9-5/8"	40.00	J-55	LT&C	1.21	1.53	2.67
8 3/4	0	11575	5-1/2"	20.00	L-80	LT&C	1.63	1.70	1.73
8 3/4	11575	21744	5-1/2"	20.00	L-80	BT&C	1.57	1.60	50.11
BLM Minimum Safety Factor							1.125	1	1.6 Dry 1.8 Wet

TVD was used on all calculations.

All casing strings will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.h

**Red Hills Unit 131H**  
Casing Assumptions

**Casing Program**

Hole Size	Casing Depth From	Casing Depth To	Casing Size	Weight (lb/ft)	Grade	Conn.	SF Collapse	SF Burst	SF Tension
17 1/2	0	1050	13-3/8"	48.00	H-40/J-55 Hybrid	ST&C	1.54	3.60	6.39
12 1/4	0	4875	9-5/8"	40.00	J-55	LT&C	1.21	1.53	2.67
8 3/4	0	11575	5-1/2"	20.00	L-80	LT&C	1.63	1.70	1.73
8 3/4	11575	21744	5-1/2"	20.00	L-80	BT&C	1.57	1.60	50.11
BLM Minimum Safety Factor							1.125	1	1.6 Dry 1.8 Wet

TVD was used on all calculations.

All casing strings will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.h

Hydrogen Sulfide Drilling Operations Plan  
**Red Hills Unit 131H**  
Cimarex Energy Co.  
UL: D, Sec. 32, 25S, 33E  
Lea Co., NM

- 1 All Company and Contract personnel admitted on location must be trained by a qualified H2S safety instructor to the following:
  - A. Characteristics of H<sub>2</sub>S
  - B. Physical effects and hazards
  - C. Principal and operation of H<sub>2</sub>S detectors, warning system and briefing areas.
  - D. Evacuation procedure, routes and first aid.
  - E. Proper use of safety equipment & life support systems
  - F. Essential personnel meeting Medical Evaluation criteria will receive additional training on the proper use of 30 minute pressure demand air packs.

H<sub>2</sub>S Detection and Alarm Systems:

  - A. H<sub>2</sub>S sensors/detectors to be located on the drilling rig floor, in the base of the sub structure/cellar area, on the mud pits in the shale shaker area. Additional H<sub>2</sub>S detectors may play placed as deemed necessary.
  - B. An audio alarm system will be installed on the derrick floor and in the top doghouse.
- 3 Windsock and/or wind streamers:
  - A. Windsock at mudpit area should be high enough to be visible.
  - B. Windsock on the rig floor and / or top doghouse should be high enough to be visible.
- 4 Condition Flags and Signs
  - A. Warning sign on access road to location.
  - B. Flags to be displayed on sign at entrance to location. Green flag indicates normal safe condition. Yellow flag indicates potential pressure and danger. Red flag indicates danger (H<sub>2</sub>S present in dangerous concentration). Only H<sub>2</sub>S trained and certified personnel admitted to location.
- 5 Well control equipment:
  - A. See exhibit "E-1"
- 6 Communication:
  - A. While working under masks chalkboards will be used for communication.
  - B. Hand signals will be used where chalk board is inappropriate.
  - C. Two way radio will be used to communicate off location in case of emergency help is required. In most cases cellular telephones will be available at most drilling foreman's trailer or living quarters.
- 7 Drillstem Testing:

No DSTs r cores are planned at this time.
- 8 Drilling contractor supervisor will be required to be familiar with the effects H<sub>2</sub>S has on tubular goods and other mechanical equipment.
- 9 If H<sub>2</sub>S is encountered, mud system will be altered if necessary to maintain control of formation. A mud gas separator will be brought into service along with H<sub>2</sub>S scavengers if necessary.

H<sub>2</sub>S Contingency Plan  
**Red Hills Unit 131H**  
Cimarex Energy Co.  
UL: D, Sec. 32, 25S, 33E  
Lea Co., NM

**Emergency Procedures**

In the event of a release of gas containing H<sub>2</sub>S, the first responder(s) must:

- « Isolate the area and prevent entry by other persons into the 100 ppm ROE.
- « Evacuate any public places encompassed by the 100 ppm ROE.
- « Be equipped with H<sub>2</sub>S monitors and air packs in order to control the release.
- « Use the "buddy system" to ensure no injuries occur during the 432-620-1975
- « Take precautions to avoid personal injury during this operation.
- « Contact operator and/or local officials to aid in operation. See list of phone numbers attached.
- « Have received training in the:
  - Detection of H<sub>2</sub>S, and
  - Measures for protection against the gas,
  - Equipment used for protection and emergency response.

**Ignition of Gas Source**

Should control of the well be considered lost and ignition considered, take care to protect against exposure to Sulfur Dioxide (SO<sub>2</sub>). Intentional ignition must be coordinated with the NMOCD and local officials. Additionally, the NM State Police may become involved. NM State Police shall be the Incident Command on scene of any major release. Take care to protect downwind whenever there is an ignition of the gas.

**Characteristics of H<sub>2</sub>S and SO<sub>2</sub>**

Please see attached International Chemical Safety Cards.

**Contacting Authorities**

Cimarex Energy Co. of Colorado's personnel must liaise with local and state agencies to ensure a proper response to a major release. Additionally, the OCD must be notified of the release as soon as possible but no later than 4 hours. Agencies will ask for information such as type and volume of release, wind direction, location of release, etc. Be prepared with all information available including directions to site. The following call list of essential and potential responders has been prepared for use during a release. Cimarex Energy Co. of Colorado's response must be in coordination with the State of New Mexico's "Hazardous Materials Emergency Response Plan" (HMER).

H<sub>2</sub>S Contingency Plan Emergency Contacts

**Red Hills Unit 131H**

Cimarex Energy Co.

UL: D, Sec. 32, 25S, 33E

Lea Co., NM

<b>Company Office</b>			
Cimarex Energy Co. of Colorado		800-969-4789	
Co. Office and After-Hours Menu			
<b>Key Personnel</b>			
<b>Name</b>	<b>Title</b>	<b>Office</b>	<b>Mobile</b>
Larry Seigrist	Drilling Manager	432-620-1934	580-243-8485
Charlie Pritchard	Drilling Superintendent	432-620-1975	432-238-7084
Roy Shirley	Construction Superintendent		432-634-2136
<b>Artesia</b>			
Ambulance		911	
State Police		575-746-2703	
City Police		575-746-2703	
Sheriff's Office		575-746-9888	
<b>Fire Department</b>		<b>575-746-2701</b>	
Local Emergency Planning Committee		575-746-2122	
New Mexico Oil Conservation Division		575-748-1283	
<b>Carlsbad</b>			
Ambulance		911	
State Police		575-885-3137	
City Police		575-885-2111	
Sheriff's Office		575-887-7551	
<b>Fire Department</b>		<b>575-887-3798</b>	
Local Emergency Planning Committee		575-887-6544	
US Bureau of Land Management		575-887-6544	
<b>Santa Fe</b>			
New Mexico Emergency Response Commission (Santa Fe)		505-476-9600	
New Mexico Emergency Response Commission (Santa Fe) 24 Hrs		505-827-9126	
New Mexico State Emergency Operations Center		505-476-9635	
<b>National</b>			
National Emergency Response Center (Washington, D.C.)		800-424-8802	
<b>Medical</b>			
Flight for Life - 4000 24th St.; Lubbock, TX		806-743-9911	
Aerocare - R3, Box 49F; Lubbock, TX		806-747-8923	
Med Flight Air Amb - 2301 Yale Blvd S.E., #D3; Albuquerque, NM		505-842-4433	
SB Air Med Service - 2505 Clark Carr Loop S.E.; Albuquerque, NM		505-842-4949	
<b>Other</b>			
Boots & Coots IWC		800-256-9688	or 281-931-8884
Cudd Pressure Control		432-699-0139	or 432-563-3356
Halliburton		575-746-2757	
B.J. Services		575-746-3569	

### Cimarex Red Hills Unit #131H Rev0 RM 10May18 Anti-Collision Summary Report

Analysis Date-24hr Time: May 11, 2018 - 09:22  
 Client: Cimarex  
 Field: NM Lea County (NAD 83)  
 Structure: Cimarex Red Hills Unit #131H  
 Slot: Cimarex Red Hills Unit #131H  
 Well: Cimarex Red Hills Unit #131H  
 Borehole: Original Borehole  
 Scan MD Range: 0.00ft - 21744.48ft

Analysis Method: 3D Least Distance  
 Reference Trajectory: Cimarex Red Hills Unit #131H Rev0 RM 10May18 (Non-Def Plan)  
 Depth Interval: Every 10.00 Measured Depth (ft)  
 Rule Set: NAL Procedure: D&M Anti-Collision Standard S002  
 Min Pts: All local minima indicated.  
 Version / Patch: 2.10.715.0  
 Database \ Project: US1153APP452.dir.slb.com\drilling-NM Lea County 2.10

ISCWSA0 3-D 95.000% Confidence 2.7955 sigma, for subject well. For offset wells, error model version is specified with each well respectively.

**Trajectory Error Model:**

**Offset Trajectories Summary**

**Offset Selection Criteria**

Wellhead distance scan: Not performed!  
 Selection filters: Definitive Surveys - Definitive Plans - Definitive surveys exclude definitive plans  
 - All Non-Def Surveys when no Def-Survey is set in a borehole - All Non-Def Plans when no Def-Plan is set in a borehole

Offset Trajectory	Separation			Allow Dev. (ft)	Sep. Fact.	Controlling Rule	Reference Trajectory		Risk Level			Alert	Status
	Ct-Ct (ft)	MAS (ft)	EOU (ft)				MD (ft)	TVD (ft)	Alert	Minor	Major		

Results highlighted: Sep-Factor separation <= 1.50 ft

Cimarex Red Hills Unit #127H Rev0 RM 10May18 (Non-Def Plan)

Offset Trajectory	Ct-Ct (ft)	MAS (ft)	EOU (ft)	Allow Dev. (ft)	Sep. Fact.	Controlling Rule	Reference Trajectory MD (ft)	Reference Trajectory TVD (ft)	Risk Level	Alert	Status
	116.80	32.81	114.10	83.79	N/A	MAS = 10.00 (m)	0.00	0.00			Fail Major
	116.80	32.81	114.10	83.79	73383.87	MAS = 10.00 (m)	26.00	26.00			Surface WRP
	64.85	32.81	49.74	32.05	4.95	MAS = 10.00 (m)	2220.00	2220.00	OSF<5.00		Enter Alert
	32.13	32.81	15.00	-0.88	2.03	MAS = 10.00 (m)	2620.00	2819.96		StcRul<10.00	Enter Major
	25.46	32.81	8.02	-7.35	1.54	MAS = 10.00 (m)	2750.00	2749.68			MinPts
	32.00	32.81	14.34	-0.81	1.95	MAS = 10.00 (m)	2850.00	2849.20		StcRul>10.00	Exit Major
	79.07	32.81	61.00	46.26	4.92	MAS = 10.00 (m)	3170.00	3167.56	OSF>5.00		Exit Alert
	280.19	85.82	222.14	194.37	5.00	OSF1.50	10750.00	10737.64	OSF<5.00		Enter Alert
	279.05	93.57	216.74	186.38	4.57	OSF1.50	11680.00	11666.80			MinPts
	279.99	93.58	216.75	186.39	4.57	OSF1.50	11990.00	11978.53			MinPt-O-SF
	304.68	93.41	241.57	211.27	4.99	OSF1.50	11940.00	11893.09	OSF>5.00		Exit Alert
	436.04	132.58	346.82	303.46	5.00	OSF1.50	15890.00	12040.00	OSF<5.00		Enter Alert
	436.04	308.29	229.69	127.75	2.13	OSF1.50	21744.48	12040.00			MinPts

Cimarex Red Hills Unit #130H Rev0 RM 10May18 (Non-Def Plan)

Offset Trajectory	Ct-Ct (ft)	MAS (ft)	EOU (ft)	Allow Dev. (ft)	Sep. Fact.	Controlling Rule	Reference Trajectory MD (ft)	Reference Trajectory TVD (ft)	Risk Level	Alert	Status
	20.00	16.50	17.50	3.50	N/A	MAS = 5.03 (m)	0.00	0.00	CtCt<=15m<15.00		Fail Minor
	20.00	16.50	17.50	3.50	78768.80	MAS = 5.03 (m)	26.00	26.00			Enter Alert
	20.00	16.50	8.53	3.50	1.95	MAS = 5.03 (m)	1490.00	1490.00			WRP
	20.02	16.50	8.44	3.52	1.93	MAS = 5.03 (m)	1510.00	1510.00			MinPts
	20.07	16.50	8.45	3.57	1.93	MAS = 5.03 (m)	1520.00	1520.00			MINPT-O-EOU
	56.28	18.66	43.01	37.62	4.99	OSF1.50	2020.00	2020.00	OSF>5.00		MinPt-O-SF
	116.06	23.36	99.66	92.71	8.17	OSF1.50	3030.00	3028.28			Exit Alert
	117.31	26.46	98.82	90.83	7.18	OSF1.50	3680.00	3674.95			MinPt-CtCt
	93.02	29.89	72.26	63.14	4.96	OSF1.50	4480.00	4470.86	OSF<5.00		MINPT-O-EOU
	62.65	33.42	39.53	29.23	2.92	OSF1.50	5210.00	5197.66			Enter Alert
											MinPt-O-SF

Offset Trajectory	Separation			Allow Dev. (ft)	Sep. Fact.	Controlling Rule	Reference Trajectory		Risk Level			Alert	Status
	Ct-Ct (ft)	MAS (ft)	EOU (ft)				MD (ft)	TVD (ft)	Alert	Minor	Major		
02.03	33.41	36.53	20.22	2.92	OSF1.50	5230.00	5217.65					MinPt-O-ADP	
02.03	33.41	30.52	20.22	2.92	OSF1.50	5240.00	5227.65					MINPT-O-EQU	
02.02	02.70	10.99	-0.08	1.50	OSF1.50	9050.00	9037.64			OSF<1.50		Enter Minor	
02.02	75.27	11.60	-12.65	1.24	OSF1.50	10470.00	10457.64					MinPt-CtCt	
02.05	75.32	11.60	-12.67	1.24	OSF1.50	10480.00	10467.64					MinPts	
72.77	73.92	22.86	-1.15	1.48	OSF1.50	10580.00	10567.64			OSF>1.50		Exit Minor	
197.73	01.67	155.78	136.06	4.95	OSF1.50	10880.00	10867.64			OSF>5.00		Exit Alert	
1100.10	305.19	895.81	794.91	5.44	OSF1.50	21744.48	12040.00					MinPts	



## Cimarex Red Hills Unit #131H Rev0 RM 10May18 Proposal Geodetic Report (Non-Def Plan)



**Report Date:** May 11, 2018 - 09:21 AM  
**Client:** Cimarex  
**Field:** NM Lea County (NAD 83)  
**Structure / Slot:** Cimarex Red Hills Unit #131H / Cimarex Red Hills Unit #131H  
**Well:** Cimarex Red Hills Unit #131H  
**Borehole:** Original Borehole  
**UWI / API#:** Unknown / Unknown  
**Survey Name:** Cimarex Red Hills Unit #131H Rev0 RM 10May18  
**Survey Date:** May 10, 2018  
**Tort / AHD / DDI / ERD Ratio:** 101.596° / 10150.834 ft / 6.270 / 0.843  
**Coordinate Reference System:** NAD83 New Mexico State Plane, Eastern Zone, US Feet  
**Location Lat / Long:** N 32° 5' 36.28880", W 103° 36' 5.51219"  
**Location Grid N/E Y/X:** N 398489.400 RUS, E 767959.850 RUS  
**CRS Grid Convergence Angle:** 0.3888°  
**Grid Scale Factor:** 0.99996791  
**Version / Patch:** 2.10.715.0

**Survey / DLS Computation:** Minimum Curvature / Lubinski  
**Vertical Section Azimuth:** 179.627° (Grid North)  
**Vertical Section Origin:** 0.000 ft, 0.000 ft  
**TVD Reference Datum:** RKB  
**TVD Reference Elevation:** 3422.100 ft above MSL  
**Seabed / Ground Elevation:** 3396.100 ft above MSL  
**Magnetic Declination:** 6.763°  
**Total Gravity Field Strength:** 998.4291mgN (9.80665 Based)  
**Gravity Model:** GARM  
**Total Magnetic Field Strength:** 47869.477 nT  
**Magnetic Dip Angle:** 59.752°  
**Declination Date:** May 10, 2018  
**Magnetic Declination Model:** HDGM 2018  
**North Reference:** Grid North  
**Grid Convergence Used:** 0.3888°  
**Total Corr Mag North->Grid North:** 6.3741°  
**Local Coord Referenced To:** Structure Reference Point

Comments	MD (ft)	Incl (°)	Azim Grid (°)	TVD (ft)	VSEC (ft)	NS (ft)	EW (ft)	DLS (°/100ft)	Northing (RUS)	Easting (RUS)	Latitude (N/S ° ' ")	Longitude (E/W ° ' ")
SHL [330' FNL, 410' FWL]	0.00	0.00	90.00	0.00	0.00	0.00	0.00	N/A	398489.40	767959.85	N 32 5 36.29 W 103 36 5.51	
	100.00	0.00	90.00	100.00	0.00	0.00	0.00	0.00	398489.40	767959.85	N 32 5 36.29 W 103 36 5.51	
	200.00	0.00	90.00	200.00	0.00	0.00	0.00	0.00	398489.40	767959.85	N 32 5 36.29 W 103 36 5.51	
	300.00	0.00	90.00	300.00	0.00	0.00	0.00	0.00	398489.40	767959.85	N 32 5 36.29 W 103 36 5.51	
	400.00	0.00	90.00	400.00	0.00	0.00	0.00	0.00	398489.40	767959.85	N 32 5 36.29 W 103 36 5.51	
	500.00	0.00	90.00	500.00	0.00	0.00	0.00	0.00	398489.40	767959.85	N 32 5 36.29 W 103 36 5.51	
	600.00	0.00	90.00	600.00	0.00	0.00	0.00	0.00	398489.40	767959.85	N 32 5 36.29 W 103 36 5.51	
	700.00	0.00	90.00	700.00	0.00	0.00	0.00	0.00	398489.40	767959.85	N 32 5 36.29 W 103 36 5.51	
	800.00	0.00	90.00	800.00	0.00	0.00	0.00	0.00	398489.40	767959.85	N 32 5 36.29 W 103 36 5.51	
	900.00	0.00	90.00	900.00	0.00	0.00	0.00	0.00	398489.40	767959.85	N 32 5 36.29 W 103 36 5.51	
Rustler	1000.00	0.00	90.00	1000.00	0.00	0.00	0.00	0.00	398489.40	767959.85	N 32 5 36.29 W 103 36 5.51	
	1100.00	0.00	90.00	1100.00	0.00	0.00	0.00	0.00	398489.40	767959.85	N 32 5 36.29 W 103 36 5.51	
	1200.00	0.00	90.00	1200.00	0.00	0.00	0.00	0.00	398489.40	767959.85	N 32 5 36.29 W 103 36 5.51	
	1300.00	0.00	90.00	1300.00	0.00	0.00	0.00	0.00	398489.40	767959.85	N 32 5 36.29 W 103 36 5.51	
Top of Salt	1340.00	0.00	90.00	1340.00	0.00	0.00	0.00	0.00	398489.40	767959.85	N 32 5 36.29 W 103 36 5.51	
	1400.00	0.00	90.00	1400.00	0.00	0.00	0.00	0.00	398489.40	767959.85	N 32 5 36.29 W 103 36 5.51	
	1500.00	0.00	90.00	1500.00	0.00	0.00	0.00	0.00	398489.40	767959.85	N 32 5 36.29 W 103 36 5.51	
	1600.00	0.00	90.00	1600.00	0.00	0.00	0.00	0.00	398489.40	767959.85	N 32 5 36.29 W 103 36 5.51	
	1700.00	0.00	90.00	1700.00	0.00	0.00	0.00	0.00	398489.40	767959.85	N 32 5 36.29 W 103 36 5.51	
	1800.00	0.00	90.00	1800.00	0.00	0.00	0.00	0.00	398489.40	767959.85	N 32 5 36.29 W 103 36 5.51	
	1900.00	0.00	90.00	1900.00	0.00	0.00	0.00	0.00	398489.40	767959.85	N 32 5 36.29 W 103 36 5.51	
	2000.00	0.00	90.00	2000.00	0.00	0.00	0.00	0.00	398489.40	767959.85	N 32 5 36.29 W 103 36 5.51	
	2100.00	0.00	90.00	2100.00	0.00	0.00	0.00	0.00	398489.40	767959.85	N 32 5 36.29 W 103 36 5.51	
	2200.00	0.00	90.00	2200.00	0.00	0.00	0.00	0.00	398489.40	767959.85	N 32 5 36.29 W 103 36 5.51	
	2300.00	0.00	90.00	2300.00	0.00	0.00	0.00	0.00	398489.40	767959.85	N 32 5 36.29 W 103 36 5.51	
	2400.00	0.00	90.00	2400.00	0.00	0.00	0.00	0.00	398489.40	767959.85	N 32 5 36.29 W 103 36 5.51	
Nudge 2"/100' DLS	2500.00	0.00	90.00	2500.00	0.00	0.00	0.00	0.00	398489.40	767959.85	N 32 5 36.29 W 103 36 5.51	

Comments	MD (ft)	Incl (°)	Azlm Grd (°)	TVD (ft)	VSEC (ft)	NS (ft)	EW (ft)	DLS (°/100ft)	Northng (ftUS)	Eastng (ftUS)	Latitude (N/S...°)	Longitude (E/W...°)
	2800.00	2.00	90.00	2599.99	0.01	0.00	1.75	2.00	399489.40	767961.60	N 32 5 36.29 W 103 36 5.49	
	2700.00	4.00	90.00	2699.84	0.05	0.00	6.98	2.00	399489.40	767966.83	N 32 5 36.29 W 103 36 5.43	
	2789.80	5.80	90.00	2789.41	0.10	0.00	14.66	2.00	399489.40	767974.51	N 32 5 36.29 W 103 36 5.34	
Hold Nudge	2800.00	5.80	90.00	2789.45	0.10	0.00	15.68	0.00	399489.40	767975.53	N 32 5 36.29 W 103 36 5.33	
	2900.00	5.80	90.00	2898.94	0.17	0.00	25.78	0.00	399489.40	767985.63	N 32 5 36.29 W 103 36 5.21	
	3000.00	5.80	90.00	2998.43	0.23	0.00	35.88	0.00	399489.40	767995.73	N 32 5 36.28 W 103 36 5.10	
	3100.00	5.80	90.00	3097.92	0.30	0.00	45.98	0.00	399489.40	768005.83	N 32 5 36.28 W 103 36 4.98	
	3200.00	5.80	90.00	3197.41	0.37	0.00	56.08	0.00	399489.40	768015.93	N 32 5 36.28 W 103 36 4.86	
	3300.00	5.80	90.00	3296.90	0.43	0.00	66.19	0.00	399489.40	768026.03	N 32 5 36.28 W 103 36 4.74	
	3400.00	5.80	90.00	3396.39	0.50	0.00	76.29	0.00	399489.40	768036.14	N 32 5 36.28 W 103 36 4.61	
	3500.00	5.80	90.00	3495.87	0.56	0.00	86.39	0.00	399489.40	768046.24	N 32 5 36.28 W 103 36 4.51	
	3600.00	5.80	90.00	3595.36	0.63	0.00	96.48	0.00	399489.40	768056.34	N 32 5 36.28 W 103 36 4.39	
	3700.00	5.80	90.00	3694.85	0.69	0.00	106.58	0.00	399489.40	768066.44	N 32 5 36.28 W 103 36 4.27	
	3800.00	5.80	90.00	3794.34	0.76	0.00	116.70	0.00	399489.40	768076.54	N 32 5 36.28 W 103 36 4.16	
	3900.00	5.80	90.00	3893.83	0.83	0.00	126.80	0.00	399489.40	768086.65	N 32 5 36.28 W 103 36 4.04	
	4000.00	5.80	90.00	3993.31	0.89	0.00	136.90	0.00	399489.40	768096.75	N 32 5 36.28 W 103 36 3.92	
	4100.00	5.80	90.00	4092.80	0.96	0.00	147.00	0.00	399489.40	768106.85	N 32 5 36.28 W 103 36 3.80	
	4200.00	5.80	90.00	4192.29	1.02	0.00	157.11	0.00	399489.40	768116.95	N 32 5 36.28 W 103 36 3.69	
	4300.00	5.80	90.00	4291.78	1.02	0.00	167.21	0.00	399489.40	768127.05	N 32 5 36.28 W 103 36 3.57	
	4400.00	5.80	90.00	4391.27	1.15	0.00	177.31	0.00	399489.40	768137.15	N 32 5 36.27 W 103 36 3.45	
	4500.00	5.80	90.00	4490.76	1.22	0.00	187.41	0.00	399489.40	768147.26	N 32 5 36.27 W 103 36 3.33	
	4600.00	5.80	90.00	4590.25	1.29	0.00	197.51	0.00	399489.40	768157.36	N 32 5 36.27 W 103 36 3.22	
	4699.80	5.80	90.00	4689.74	1.31	0.00	207.61	0.00	399489.40	768167.46	N 32 5 36.27 W 103 36 3.10	
Base of Sail	4700.00	5.80	90.00	4789.22	1.35	0.00	217.72	0.00	399489.40	768177.56	N 32 5 36.27 W 103 36 2.98	
	4800.00	5.80	90.00	4888.71	1.48	0.00	227.82	0.00	399489.40	768187.66	N 32 5 36.27 W 103 36 2.86	
	4900.00	5.80	90.00	4988.20	1.49	0.00	237.92	0.00	399489.40	768197.77	N 32 5 36.27 W 103 36 2.75	
Delaware Sands	5000.00	5.80	90.00	5087.69	1.55	0.00	248.02	0.00	399489.40	768207.87	N 32 5 36.27 W 103 36 2.63	
Drop to Vertical 2°/100' DLS	5011.86	5.80	90.00	5000.00	1.56	0.00	238.12	0.00	399489.40	768198.98	N 32 5 36.27 W 103 36 2.73	
	5100.00	4.04	90.00	5087.81	1.61	0.00	246.66	2.00	399489.40	768208.52	N 32 5 36.27 W 103 36 2.54	
	5200.00	2.04	90.00	5187.67	1.64	0.00	251.97	2.00	399489.40	768211.91	N 32 5 36.27 W 103 36 2.58	
	5300.00	0.04	90.00	5287.64	1.65	0.00	253.78	2.00	399489.40	768213.62	N 32 5 36.27 W 103 36 2.56	
Hold Vertical	5301.76	0.00	90.00	5289.41	1.65	0.00	253.78	2.00	399489.40	768213.62	N 32 5 36.27 W 103 36 2.56	
	5400.00	0.00	90.00	5389.38	1.65	0.00	253.78	0.00	399489.40	768213.62	N 32 5 36.27 W 103 36 2.56	
	5500.00	0.00	90.00	5489.35	1.65	0.00	253.78	0.00	399489.40	768213.62	N 32 5 36.27 W 103 36 2.56	
	5600.00	0.00	90.00	5589.32	1.65	0.00	253.78	0.00	399489.40	768213.62	N 32 5 36.27 W 103 36 2.56	
	5700.00	0.00	90.00	5689.29	1.65	0.00	253.78	0.00	399489.40	768213.62	N 32 5 36.27 W 103 36 2.56	
	5800.00	0.00	90.00	5789.26	1.65	0.00	253.78	0.00	399489.40	768213.62	N 32 5 36.27 W 103 36 2.56	
	5900.00	0.00	90.00	5889.23	1.65	0.00	253.78	0.00	399489.40	768213.62	N 32 5 36.27 W 103 36 2.56	
	6000.00	0.00	90.00	5989.20	1.65	0.00	253.78	0.00	399489.40	768213.62	N 32 5 36.27 W 103 36 2.56	
	6100.00	0.00	90.00	6089.17	1.65	0.00	253.78	0.00	399489.40	768213.62	N 32 5 36.27 W 103 36 2.56	
	6200.00	0.00	90.00	6189.14	1.65	0.00	253.78	0.00	399489.40	768213.62	N 32 5 36.27 W 103 36 2.56	
	6300.00	0.00	90.00	6289.11	1.65	0.00	253.78	0.00	399489.40	768213.62	N 32 5 36.27 W 103 36 2.56	
	6400.00	0.00	90.00	6389.08	1.65	0.00	253.78	0.00	399489.40	768213.62	N 32 5 36.27 W 103 36 2.56	
	6500.00	0.00	90.00	6489.05	1.65	0.00	253.78	0.00	399489.40	768213.62	N 32 5 36.27 W 103 36 2.56	
	6600.00	0.00	90.00	6589.02	1.65	0.00	253.78	0.00	399489.40	768213.62	N 32 5 36.27 W 103 36 2.56	
	6700.00	0.00	90.00	6688.99	1.65	0.00	253.78	0.00	399489.40	768213.62	N 32 5 36.27 W 103 36 2.56	
	6800.00	0.00	90.00	6788.96	1.65	0.00	253.78	0.00	399489.40	768213.62	N 32 5 36.27 W 103 36 2.56	
	6900.00	0.00	90.00	6888.93	1.65	0.00	253.78	0.00	399489.40	768213.62	N 32 5 36.27 W 103 36 2.56	
	7000.00	0.00	90.00	6988.90	1.65	0.00	253.78	0.00	399489.40	768213.62	N 32 5 36.27 W 103 36 2.56	
	7100.00	0.00	90.00	7088.87	1.65	0.00	253.78	0.00	399489.40	768213.62	N 32 5 36.27 W 103 36 2.56	
	7200.00	0.00	90.00	7188.84	1.65	0.00	253.78	0.00	399489.40	768213.62	N 32 5 36.27 W 103 36 2.56	
	7300.00	0.00	90.00	7288.81	1.65	0.00	253.78	0.00	399489.40	768213.62	N 32 5 36.27 W 103 36 2.56	
	7400.00	0.00	90.00	7388.78	1.65	0.00	253.78	0.00	399489.40	768213.62	N 32 5 36.27 W 103 36 2.56	
	7500.00	0.00	90.00	7488.75	1.65	0.00	253.78	0.00	399489.40	768213.62	N 32 5 36.27 W 103 36 2.56	
	7600.00	0.00	90.00	7588.72	1.65	0.00	253.78	0.00	399489.40	768213.62	N 32 5 36.27 W 103 36 2.56	
	7700.00	0.00	90.00	7688.69	1.65	0.00	253.78	0.00	399489.40	768213.62	N 32 5 36.27 W 103 36 2.56	

Comments	MD	Incl	Adm GHD	TVD	VSEC	NS	EW	DLS	Northing	Easting	Latitude	Longitude
	(ft)	(°)	(ft)	(ft)	(ft)	(ft)	(ft)	(ft/100ft)	(ftUS)	(ftUS)	(N/S ° ' ")	(E/W ° ' ")
Bone Spring	7600.00	0.00	90.00	7787.64	1.65	0.00	253.78	0.00	398489.40	768213.62	N 32 5.3627 W 103.36 2.56	
	8000.00	0.00	90.00	7987.64	1.65	0.00	253.78	0.00	398489.40	768213.62	N 32 5.3627 W 103.36 2.56	
	8100.00	0.00	90.00	7987.64	1.65	0.00	253.78	0.00	398489.40	768213.62	N 32 5.3627 W 103.36 2.56	
	8200.00	0.00	90.00	8087.64	1.65	0.00	253.78	0.00	398489.40	768213.62	N 32 5.3627 W 103.36 2.56	
	8300.00	0.00	90.00	8187.64	1.65	0.00	253.78	0.00	398489.40	768213.62	N 32 5.3627 W 103.36 2.56	
	8400.00	0.00	90.00	8287.64	1.65	0.00	253.78	0.00	398489.40	768213.62	N 32 5.3627 W 103.36 2.56	
	8500.00	0.00	90.00	8387.64	1.65	0.00	253.78	0.00	398489.40	768213.62	N 32 5.3627 W 103.36 2.56	
	8600.00	0.00	90.00	8487.64	1.65	0.00	253.78	0.00	398489.40	768213.62	N 32 5.3627 W 103.36 2.56	
	8700.00	0.00	90.00	8587.64	1.65	0.00	253.78	0.00	398489.40	768213.62	N 32 5.3627 W 103.36 2.56	
	8800.00	0.00	90.00	8687.64	1.65	0.00	253.78	0.00	398489.40	768213.62	N 32 5.3627 W 103.36 2.56	
1st Bone Spring Sand	8900.00	0.00	90.00	8787.64	1.65	0.00	253.78	0.00	398489.40	768213.62	N 32 5.3627 W 103.36 2.56	
	9000.00	0.00	90.00	8887.64	1.65	0.00	253.78	0.00	398489.40	768213.62	N 32 5.3627 W 103.36 2.56	
	9027.36	0.00	90.00	8987.64	1.65	0.00	253.78	0.00	398489.40	768213.62	N 32 5.3627 W 103.36 2.56	
	9100.00	0.00	90.00	9025.00	1.65	0.00	253.78	0.00	398489.40	768213.62	N 32 5.3627 W 103.36 2.56	
	9200.00	0.00	90.00	9025.00	1.65	0.00	253.78	0.00	398489.40	768213.62	N 32 5.3627 W 103.36 2.56	
	9300.00	0.00	90.00	9187.64	1.65	0.00	253.78	0.00	398489.40	768213.62	N 32 5.3627 W 103.36 2.56	
	9400.00	0.00	90.00	9287.64	1.65	0.00	253.78	0.00	398489.40	768213.62	N 32 5.3627 W 103.36 2.56	
	9500.00	0.00	90.00	9387.64	1.65	0.00	253.78	0.00	398489.40	768213.62	N 32 5.3627 W 103.36 2.56	
	9600.00	0.00	90.00	9487.64	1.65	0.00	253.78	0.00	398489.40	768213.62	N 32 5.3627 W 103.36 2.56	
	9700.00	0.00	90.00	9587.64	1.65	0.00	253.78	0.00	398489.40	768213.62	N 32 5.3627 W 103.36 2.56	
2nd Bone Spring Carb	9800.00	0.00	90.00	9687.64	1.65	0.00	253.78	0.00	398489.40	768213.62	N 32 5.3627 W 103.36 2.56	
	9800.00	0.00	90.00	9787.64	1.65	0.00	253.78	0.00	398489.40	768213.62	N 32 5.3627 W 103.36 2.56	
	9800.00	0.00	90.00	9887.64	1.65	0.00	253.78	0.00	398489.40	768213.62	N 32 5.3627 W 103.36 2.56	
	10000.00	0.00	90.00	9987.64	1.65	0.00	253.78	0.00	398489.40	768213.62	N 32 5.3627 W 103.36 2.56	
	10022.36	0.00	90.00	10010.00	1.65	0.00	253.78	0.00	398489.40	768213.62	N 32 5.3627 W 103.36 2.56	
	10100.00	0.00	90.00	10087.64	1.65	0.00	253.78	0.00	398489.40	768213.62	N 32 5.3627 W 103.36 2.56	
	10200.00	0.00	90.00	10187.64	1.65	0.00	253.78	0.00	398489.40	768213.62	N 32 5.3627 W 103.36 2.56	
	10222.36	0.00	90.00	10210.00	1.65	0.00	253.78	0.00	398489.40	768213.62	N 32 5.3627 W 103.36 2.56	
	10300.00	0.00	90.00	10287.64	1.65	0.00	253.78	0.00	398489.40	768213.62	N 32 5.3627 W 103.36 2.56	
	10400.00	0.00	90.00	10387.64	1.65	0.00	253.78	0.00	398489.40	768213.62	N 32 5.3627 W 103.36 2.56	
3rd Bone Spring Carb	10500.00	0.00	90.00	10487.64	1.65	0.00	253.78	0.00	398489.40	768213.62	N 32 5.3627 W 103.36 2.56	
	10577.36	0.00	90.00	10565.00	1.65	0.00	253.78	0.00	398489.40	768213.62	N 32 5.3627 W 103.36 2.56	
	10600.00	0.00	90.00	10657.64	1.65	0.00	253.78	0.00	398489.40	768213.62	N 32 5.3627 W 103.36 2.56	
	10700.00	0.00	90.00	10687.64	1.65	0.00	253.78	0.00	398489.40	768213.62	N 32 5.3627 W 103.36 2.56	
	10800.00	0.00	90.00	10787.64	1.65	0.00	253.78	0.00	398489.40	768213.62	N 32 5.3627 W 103.36 2.56	
	10900.00	0.00	90.00	10887.64	1.65	0.00	253.78	0.00	398489.40	768213.62	N 32 5.3627 W 103.36 2.56	
	11000.00	0.00	90.00	10987.64	1.65	0.00	253.78	0.00	398489.40	768213.62	N 32 5.3627 W 103.36 2.56	
	11000.00	0.00	90.00	11035.00	1.65	0.00	253.78	0.00	398489.40	768213.62	N 32 5.3627 W 103.36 2.56	
	11100.00	0.00	90.00	11087.64	1.65	0.00	253.78	0.00	398489.40	768213.62	N 32 5.3627 W 103.36 2.56	
	11200.00	0.00	90.00	11187.64	1.65	0.00	253.78	0.00	398489.40	768213.62	N 32 5.3627 W 103.36 2.56	
KOP - Build 127/100' DLS	11300.00	0.00	90.00	11287.64	1.65	0.00	253.78	0.00	398489.40	768213.62	N 32 5.3627 W 103.36 2.56	
	11400.00	0.00	90.00	11387.64	1.65	0.00	253.78	0.00	398489.40	768213.62	N 32 5.3627 W 103.36 2.56	
	11500.00	0.00	90.00	11487.64	1.65	0.00	253.78	0.00	398489.40	768213.62	N 32 5.3627 W 103.36 2.56	
	11574.89	0.00	90.00	11562.64	1.65	0.00	253.78	0.00	398489.40	768213.62	N 32 5.3627 W 103.36 2.56	
	11600.00	3.01	179.63	11587.63	2.31	-0.66	253.78	12.00	398488.74	768213.62	N 32 5.3626 W 103.36 2.56	
	11700.00	15.01	179.63	11686.22	17.95	-16.30	253.88	12.00	398473.10	768213.72	N 32 5.3611 W 103.36 2.56	
	11703.92	15.48	179.63	11690.00	18.88	-17.33	253.89	12.00	398472.07	768213.73	N 32 5.3610 W 103.36 2.56	
	11800.00	27.01	179.63	11779.40	53.74	-52.09	254.12	12.00	398437.31	768213.96	N 32 5.3575 W 103.36 2.56	
	11800.00	39.01	179.63	11863.10	108.13	-106.47	254.47	12.00	398382.93	768214.31	N 32 5.3522 W 103.36 2.56	
	12000.00	51.01	179.63	11933.68	178.72	-177.07	254.93	12.00	398312.34	768214.77	N 32 5.3452 W 103.36 2.56	
12100.00	63.01	179.63	11988.01	262.45	-260.79	255.47	12.00	398228.62	768215.32	N 32 5.3389 W 103.36 2.56		
12200.00	75.01	179.63	12023.76	355.64	-353.99	256.08	12.00	398135.43	768215.92	N 32 5.3277 W 103.36 2.56		
12300.00	87.01	179.63	12039.35	454.24	-452.58	256.72	12.00	398036.84	768216.56	N 32 5.3179 W 103.36 2.56		

Drilling Office 2.10.7150

...Cinmarex Red Hills Unit #131H(Original Bonehole)Cinmarex Red Hills Unit #131H Rev0 RM 10May18

5/23/2018 2:17 PM Page 3 of 5

Comments	MD	Incl	Azim Ghd	TVD	VSEC	NS	EW	DLS	Northng	Eastng	Latitude	Longitude
	(ft)	(°)	(°)	(ft)	(ft)	(ft)	(ft)	(ft)	(ft)	(ft)	(N...E)	(W...S)
	12324.88	90.00	179.63	479.12	-477.45	256.89	256.37	12.00	398011.96	768216.73	31.55	103.36
	12400.00	90.00	179.63	554.23	-552.56	257.37	257.37	0.00	397936.86	768217.22	30.80	103.36
	12500.00	90.00	179.63	654.23	-652.56	258.03	258.03	0.00	397936.86	768217.87	29.81	103.36
	12600.00	90.00	179.63	754.23	-752.56	258.68	258.68	0.00	397936.86	768218.52	28.82	103.36
	12700.00	90.00	179.63	854.23	-852.56	259.33	259.33	0.00	397936.86	768219.17	27.83	103.36
	12800.00	90.00	179.63	954.23	-952.56	259.98	259.98	0.00	397936.86	768219.82	26.84	103.36
	12900.00	90.00	179.63	1054.23	-1052.55	260.63	260.63	0.00	397436.88	768220.47	25.85	103.36
	13000.00	90.00	179.63	1154.23	-1152.55	261.28	261.28	0.00	397336.89	768221.12	24.86	103.36
	13100.00	90.00	179.63	1254.23	-1252.55	261.93	261.93	0.00	397236.90	768221.77	23.88	103.36
	13200.00	90.00	179.63	1354.23	-1352.54	262.58	262.58	0.00	397136.90	768222.42	22.89	103.36
	13300.00	90.00	179.63	1454.23	-1452.54	263.23	263.23	0.00	397036.91	768223.07	21.90	103.36
	13400.00	90.00	179.63	1554.23	-1552.54	263.88	263.88	0.00	396936.91	768223.72	20.91	103.36
	13500.00	90.00	179.63	1654.23	-1652.54	264.53	264.53	0.00	396836.92	768224.38	19.92	103.36
	13600.00	90.00	179.63	1754.23	-1752.54	265.18	265.18	0.00	396736.92	768225.03	18.93	103.36
	13700.00	90.00	179.63	1854.23	-1852.53	265.84	265.84	0.00	396636.93	768225.68	17.94	103.36
	13800.00	90.00	179.63	1954.23	-1952.53	266.49	266.49	0.00	396536.93	768226.33	16.95	103.36
	13900.00	90.00	179.63	2054.23	-2052.53	267.14	267.14	0.00	396436.94	768226.98	15.96	103.36
	14000.00	90.00	179.63	2154.23	-2152.53	267.79	267.79	0.00	396336.95	768227.63	14.97	103.36
	14100.00	90.00	179.63	2254.23	-2252.53	268.44	268.44	0.00	396236.95	768228.28	13.98	103.36
	14200.00	90.00	179.63	2354.23	-2352.52	269.09	269.09	0.00	396136.96	768228.93	12.99	103.36
	14300.00	90.00	179.63	2454.23	-2452.52	269.74	269.74	0.00	396036.96	768229.58	12.00	103.36
	14400.00	90.00	179.63	2554.23	-2552.52	270.39	270.39	0.00	395936.97	768230.23	11.01	103.36
	14500.00	90.00	179.63	2654.23	-2652.52	271.04	271.04	0.00	395836.97	768230.88	10.02	103.36
	14600.00	90.00	179.63	2754.23	-2752.52	271.69	271.69	0.00	395736.98	768231.54	9.03	103.36
	14700.00	90.00	179.63	2854.23	-2852.51	272.35	272.35	0.00	395636.98	768232.19	8.04	103.36
	14800.00	90.00	179.63	2954.23	-2952.51	273.00	273.00	0.00	395536.99	768232.84	7.05	103.36
	14900.00	90.00	179.63	3054.23	-3052.51	273.65	273.65	0.00	395437.00	768233.49	6.06	103.36
	15000.00	90.00	179.63	3154.23	-3152.51	274.30	274.30	0.00	395337.00	768234.14	5.07	103.36
	15100.00	90.00	179.63	3254.23	-3252.50	274.95	274.95	0.00	395237.01	768234.79	4.08	103.36
	15200.00	90.00	179.63	3354.23	-3352.50	275.60	275.60	0.00	395137.01	768235.44	3.09	103.36
	15300.00	90.00	179.63	3454.23	-3452.50	276.25	276.25	0.00	395037.02	768236.09	2.11	103.36
	15400.00	90.00	179.63	3554.23	-3552.50	276.90	276.90	0.00	394937.02	768236.74	1.12	103.36
	15500.00	90.00	179.63	3654.23	-3652.50	277.55	277.55	0.00	394837.03	768237.39	0.13	103.36
	15600.00	90.00	179.63	3754.23	-3752.49	278.20	278.20	0.00	394737.03	768238.04	0.88	103.36
	15700.00	90.00	179.63	3854.23	-3852.49	278.86	278.86	0.00	394637.04	768238.69	1.63	103.36
	15800.00	90.00	179.63	3954.23	-3952.49	279.51	279.51	0.00	394537.04	768239.34	2.38	103.36
	15900.00	90.00	179.63	4054.23	-4052.49	280.16	280.16	0.00	394437.05	768240.00	3.13	103.36
	16000.00	90.00	179.63	4154.23	-4152.49	280.81	280.81	0.00	394337.06	768240.65	3.88	103.36
	16100.00	90.00	179.63	4254.23	-4252.49	281.46	281.46	0.00	394237.06	768241.30	4.63	103.36
	16200.00	90.00	179.63	4354.23	-4352.49	282.11	282.11	0.00	394137.07	768241.95	5.38	103.36
	16300.00	90.00	179.63	4454.23	-4452.49	282.76	282.76	0.00	394037.07	768242.60	6.13	103.36
	16400.00	90.00	179.63	4554.23	-4552.49	283.41	283.41	0.00	393937.08	768243.25	6.88	103.36
	16500.00	90.00	179.63	4654.23	-4652.49	284.06	284.06	0.00	393837.08	768243.90	7.63	103.36
	16600.00	90.00	179.63	4754.23	-4752.49	284.71	284.71	0.00	393737.09	768244.55	8.38	103.36
	16700.00	90.00	179.63	4854.23	-4852.49	285.36	285.36	0.00	393637.09	768245.20	9.13	103.36
	16800.00	90.00	179.63	4954.23	-4952.49	286.02	286.02	0.00	393537.10	768245.85	9.88	103.36
	16900.00	90.00	179.63	5054.23	-5052.49	286.67	286.67	0.00	393437.11	768246.50	10.63	103.36
	17000.00	90.00	179.63	5154.23	-5152.49	287.32	287.32	0.00	393337.11	768247.15	11.38	103.36
	17100.00	90.00	179.63	5254.23	-5252.49	287.97	287.97	0.00	393237.12	768247.80	12.13	103.36
	17200.00	90.00	179.63	5354.23	-5352.49	288.62	288.62	0.00	393137.12	768248.45	12.88	103.36
	17300.00	90.00	179.63	5454.23	-5452.49	289.27	289.27	0.00	393037.13	768249.10	13.63	103.36
	17400.00	90.00	179.63	5554.23	-5552.49	289.92	289.92	0.00	392937.13	768249.75	14.38	103.36
	17500.00	90.00	179.63	5654.23	-5652.49	290.57	290.57	0.00	392837.14	768250.40	15.13	103.36
	17600.00	90.00	179.63	5754.23	-5752.49	291.22	291.22	0.00	392737.14	768251.05	15.88	103.36
	17700.00	90.00	179.63	5854.23	-5852.49	291.87	291.87	0.00	392637.15	768251.70	16.63	103.36
	17800.00	90.00	179.63	5954.23	-5952.49	292.52	292.52	0.00	392537.16	768252.35	17.38	103.36
	17900.00	90.00	179.63	6054.23	-6052.49	293.18	293.18	0.00	392437.16	768253.00	18.13	103.36
	18000.00	90.00	179.63	6154.23	-6152.49	293.83	293.83	0.00	392337.17	768253.65	18.88	103.36
	18100.00	90.00	179.63	6254.23	-6252.49	294.48	294.48	0.00	392237.17	768254.30	19.63	103.36

Comments	MD	Incl	Azim Ghd	TVD	VSEC	EW	DLS	Nothing	Eastng	Latitude	Longitude
	(ft)	(°)	(°)	(ft)	(ft)	(ft)	(ft/100ft)	(ft)	(ft)	(N/S...°)	(E/W...°)
	18200.00	179.63	12040.00	6354.23	-8352.44	285.78	0.00	392137.18	768254.97	N 32	4 33.41 W 103 36 2.58
	18100.00	179.63	12040.00	7154.23	-752.42	300.34	0.00	391437.22	768260.18	N 32	4 25.49 W 103 36 2.58
	18000.00	179.63	12040.00	7054.23	-7052.42	299.89	0.00	391437.22	768258.52	N 32	4 26.48 W 103 36 2.58
	18000.00	179.63	12040.00	6964.23	-6952.43	299.03	0.00	391537.21	768258.87	N 32	4 27.47 W 103 36 2.58
	18000.00	179.63	12040.00	6854.23	-6852.43	298.38	0.00	391637.21	768258.22	N 32	4 28.46 W 103 36 2.58
	18000.00	179.63	12040.00	6754.23	-6752.43	297.73	0.00	391737.20	768257.57	N 32	4 29.45 W 103 36 2.58
	18000.00	179.63	12040.00	6654.23	-6652.43	297.08	0.00	391837.19	768256.92	N 32	4 30.44 W 103 36 2.58
	18000.00	179.63	12040.00	6554.23	-6552.43	296.43	0.00	391937.19	768256.27	N 32	4 31.43 W 103 36 2.58
	18000.00	179.63	12040.00	6454.23	-6452.44	295.78	0.00	392037.18	768255.62	N 32	4 32.42 W 103 36 2.58
	18200.00	179.63	12040.00	6354.23	-8352.44	285.78	0.00	392137.18	768254.97	N 32	4 33.41 W 103 36 2.58
	18100.00	179.63	12040.00	7254.23	-752.42	300.99	0.00	391237.23	768260.83	N 32	4 24.50 W 103 36 2.58
	19300.00	179.63	12040.00	7354.23	-752.42	301.64	0.00	391137.23	768261.48	N 32	4 23.51 W 103 36 2.58
	19300.00	179.63	12040.00	7454.23	-7452.42	302.29	0.00	391037.24	768262.13	N 32	4 22.52 W 103 36 2.58
	19400.00	179.63	12040.00	7554.23	-752.41	302.94	0.00	390937.24	768262.78	N 32	4 21.53 W 103 36 2.58
	19500.00	179.63	12040.00	7654.23	-752.41	303.59	0.00	390837.25	768263.43	N 32	4 20.54 W 103 36 2.58
	19600.00	179.63	12040.00	7754.23	-752.41	304.24	0.00	390737.25	768264.08	N 32	4 19.56 W 103 36 2.58
	19700.00	179.63	12040.00	7854.23	-752.41	304.89	0.00	390637.26	768264.73	N 32	4 18.57 W 103 36 2.58
	19800.00	179.63	12040.00	7954.23	-752.41	305.54	0.00	390537.27	768265.38	N 32	4 17.58 W 103 36 2.58
	19800.00	179.63	12040.00	8054.23	-8052.40	306.19	0.00	390437.27	768266.03	N 32	4 16.59 W 103 36 2.58
	20000.00	179.63	12040.00	8154.23	-8152.40	306.85	0.00	390337.28	768266.68	N 32	4 15.60 W 103 36 2.58
	20100.00	179.63	12040.00	8254.23	-8252.40	307.50	0.00	390237.28	768267.34	N 32	4 14.61 W 103 36 2.58
	20200.00	179.63	12040.00	8354.23	-8352.40	308.15	0.00	390137.29	768267.99	N 32	4 13.62 W 103 36 2.58
	20300.00	179.63	12040.00	8454.23	-8452.39	308.80	0.00	390037.29	768268.64	N 32	4 12.63 W 103 36 2.58
	20500.00	179.63	12040.00	8554.23	-8552.39	309.45	0.00	389937.30	768269.29	N 32	4 11.64 W 103 36 2.58
	20600.00	179.63	12040.00	8654.23	-8652.39	310.10	0.00	389837.30	768269.94	N 32	4 10.65 W 103 36 2.58
	20700.00	179.63	12040.00	8754.23	-8752.39	310.75	0.00	389737.31	768270.59	N 32	4 9.66 W 103 36 2.58
	20700.00	179.63	12040.00	8854.23	-8852.39	311.40	0.00	389637.32	768271.24	N 32	4 8.67 W 103 36 2.58
	20800.00	179.63	12040.00	8954.23	-8952.38	312.05	0.00	389537.32	768271.89	N 32	4 7.68 W 103 36 2.58
	20900.00	179.63	12040.00	9054.23	-9052.38	312.70	0.00	389437.33	768272.54	N 32	4 6.69 W 103 36 2.58
	21000.00	179.63	12040.00	9154.23	-9152.38	313.35	0.00	389337.33	768273.19	N 32	4 5.70 W 103 36 2.58
	21200.00	179.63	12040.00	9254.23	-9252.38	314.01	0.00	389237.34	768273.84	N 32	4 4.71 W 103 36 2.58
	21300.00	179.63	12040.00	9354.23	-9352.38	314.66	0.00	389137.34	768274.50	N 32	4 3.72 W 103 36 2.58
	21400.00	179.63	12040.00	9454.23	-9452.37	315.31	0.00	389037.35	768275.15	N 32	4 2.73 W 103 36 2.58
	21500.00	179.63	12040.00	9554.23	-9552.37	315.96	0.00	388937.35	768275.80	N 32	4 1.74 W 103 36 2.58
	21600.00	179.63	12040.00	9654.23	-9652.37	316.61	0.00	388837.36	768276.45	N 32	4 0.75 W 103 36 2.58
	21700.00	179.63	12040.00	9754.23	-9752.37	317.26	0.00	388737.37	768277.10	N 32	3 58.77 W 103 36 2.58
	21700.00	179.63	12040.00	9854.23	-9852.36	317.91	0.00	388637.37	768277.75	N 32	3 58.77 W 103 36 2.58
	21744.48	179.63	12040.00	9898.71	-9898.85	318.20	0.00	38852.89	768279.04	N 32	3 58.33 W 103 36 2.58


Cimarex Red Hills Unit #131H - PHL [330] FSL, 660' FWL]

Survey Type: Non-Def Plan


Survey Error Model: ISWASA Rev 0 ... 3-D 95.000% Confidence 2.7955 sigma

Description	Part	MD From (ft)	MD To (ft)	EOU Freq (ft)	Hole Size (in)	Casing Diameter (in)	Expected Max Inclination (deg)	Survey Tool Type	Borehole / Survey
Original Borehole / Cimarex Red Hills Unit #131H Rev0 RM	1	0.000	26.000	1/100.000	30.000	30.000	30.000	NAL_MWD_FR1+MS-Depth Only	Original Borehole / Cimarex Red Hills Unit #131H Rev0 RM
Original Borehole / Cimarex Red Hills Unit #131H Rev0 RM	1	26.000	21744.483	1/100.000	30.000	30.000	30.000	NAL_MWD_FR1+MS	Original Borehole / Cimarex Red Hills Unit #131H Rev0 RM

Co-Flex Hose  
Red Hills Unit 131H  
Cimarex Energy Co.  
32-25S-33E  
Lea Co., NM



Co-Flex Hose Hydrostatic Test  
 Red Hills Unit 131H  
 Cimarex Energy Co.  
 32-25S-33E  
 Lea Co., NM



## Midwest Hose & Specialty, Inc.

INTERNAL HYDROSTATIC TEST REPORT		
Customer: Oderco Inc.		P.O. Number: odyd-271
<b>HOSE SPECIFICATIONS</b>		
Type: Stainless Steel Armor Choke & Kill Hose		Hose Length: 45'ft.
I.D. 4 INCHES	O.D. 9 INCHES	
WORKING PRESSURE 10,000 PSI	TEST PRESSURE 15,000 PSI	BURST PRESSURE 0 PSI
<b>COUPLINGS</b>		
Stem Part No. OKC OKC		Ferrule No. OKC OKC
Type of Coupling: Swage-It		
<b>PROCEDURE</b>		
<i>Hose assembly pressure tested with water at ambient temperature.</i>		
TIME HELD AT TEST PRESSURE 15 MIN.		ACTUAL BURST PRESSURE: 0 PSI
Hose Assembly Serial Number: 79793		Hose Serial Number: OKC
Comments:		
Date: 3/8/2011	Tested: <i>A. James Jones</i>	Approved: <i>Kevin [Signature]</i>

March 3, 2011

# Internal Hydrostatic Test Graph



Midwest Hose & Specialty, Inc.

Customer: Houston


Pick Ticket #: 94260

### Hose Specifications

Hose Type: C & K  
 ID: 4"  
 Working Pressure: 10000 PSI  
 Length: 45'  
 O.D.: 6.09"  
 Burst Pressure: Standard Safety Multiplier Applies

### Verification

Type of Fittings: 41/16 10K  
 Coupling Method: Swage  
 Final O.D.: 6.25"  
 Hose Serial #: 5544  
 Hose Assembly Serial #: 79793



Test Pressure: 15000 PSI  
 Time Held at Test Pressure: 11 Minutes  
 Actual Burst Pressure: 15483 PSI  
 Peak Pressure: 15483 PSI

Comments: Hose assembly pressure tested with water at ambient temperature.

Tested By: Zac McConnell

Approved By: Kim Thomas

Co-Flex Hose  
Red Hills Unit 131H  
Cimarex Energy Co.  
32-25S-33E  
Lea Co., NM



## Midwest Hose & Specialty, Inc.

### Certificate of Conformity

<b>Customer:</b>		<b>PO</b>
DEM		ODYD-271
<b>SPECIFICATIONS</b>		
<b>Sales Order</b>	<b>Dated:</b>	
79793	3/8/2011	
<p>We hereby certify that the material supplied for the referenced purchase order to be true according to the requirements of the purchase order and current industry standards</p> <p>Supplier: Midwest Hose &amp; Specialty, Inc. 10640 Tanner Road Houston, Texas 77041</p>		
<b>Comments:</b>		
<b>Approved:</b>		<b>Date:</b>
<i>Joel Garcia</i>		3/8/2011



Midwest Hose  
& Specialty, Inc.


Co-Flex Hose  
Red Hills Unit 131H  
Cimarex Energy Co.  
32-25S-33E  
Lea Co., NM

## Specification Sheet Choke & Kill Hose

The Midwest Hose & Specialty Choke & Kill hose is manufactured with only premium components. The reinforcement cables, inner liner and cover are made of the highest quality material to handle the tough drilling applications of today's industry. The end connections are available with API flanges, API male threads, hubs, hammer unions or other special fittings upon request. Hose assembly is manufactured to API 7K. This assembly is wrapped with fire resistant vermiculite coated fiberglass insulation, rated at 2000 degrees with stainless steel armor cover.

<b>Working Pressure:</b>	5,000 or 10,000 psi working pressure
<b>Test Pressure:</b>	10,000 or 15,000 psi test pressure
<b>Reinforcement:</b>	Multiple steel cables
<b>Cover:</b>	Stainless Steel Armor
<b>Inner Tube:</b>	Petroleum resistant, Abrasion resistant
<b>End Fitting:</b>	API flanges, API male threads, threaded or butt weld hammer unions, unbolt and other special connections
<b>Maximum Length:</b>	110 Feet
<b>ID:</b>	2-1/2", 3", 3-1/2", 4"
<b>Operating Temperature:</b>	-22 deg F to +180 deg F (-30 deg C to +82 deg C)

# Multi-bowl Wellhead Diagram



Multi-bowl Wellhead Diagram  
**Red Hills Unit 131H**  
 Cimarex Energy Co.  
 32-25S-33E  
 Lea Co., NM

**1. Geological Formations**

TVD of target 12,040  
MD at TD 21,744

Pilot Hole TD N/A  
Deepest expected fresh water

Formation	Depth (TVD) from KB	Water/Mineral Bearing/Target Zone	Hazards
Rustler	1000	N/A	
Top of Salt	1340	N/A	
Base of Salt	4630	N/A	
Delaware Sands	4895	N/A	
Bone Spring	9025	Hydrocarbons	
1st Bone Spring Sand	10010	Hydrocarbons	
2nd Bone Spring Sand	10565	Hydrocarbons	
3rd Bone Spring Sand	11689	Hydrocarbons	
3rd Bone Spring Target	12040	Hydrocarbons	
Wolfcamp	12145	Hydrocarbons	

**2. Casing Program**

Hole Size	Casing Depth From	Casing Depth To	Casing Size	Weight (lb/ft)	Grade	Conn.	SF Collapse	SF Burst	SF Tension
17 1/2	0	1050	13-3/8"	48.00	H-40/J-55 Hybrid	ST&C	1.54	3.60	6.39
12 1/4	0	4875	9-5/8"	40.00	J-55	LT&C	1.21	1.53	2.67
8 3/4	0	11575	5-1/2"	20.00	L-80	LT&C	1.63	1.70	1.73
8 3/4	11575	21744	5-1/2"	20.00	L-80	BT&C	1.57	1.60	50.11
BLM Minimum Safety Factor							1.125	1	1.6 Dry 1.8 Wet

TVD was used on all calculations.

All casing strings will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.h

Cimarex Energy Co., Red Hills Unit 131H

	Y or N
Is casing new? If used, attach certification as required in Onshore Order #1	Y
Does casing meet API specifications? If no, attach casing specification sheet.	Y
Is premium or uncommon casing planned? If yes attach casing specification sheet.	N
Does the above casing design meet or exceed BLM's minimum standards? If not provide justification (loading assumptions, casing design criteria).	Y
Will the intermediate pipe be kept at a minimum 1/3 fluid filled to avoid approaching the collapse pressure rating of the casing?	Y
Is well located within Capitan Reef?	N
If yes, does production casing cement tie back a minimum of 50' above the Reef?	N
Is well within the designated 4 string boundary.	N
Is well located in SOPA but not in R-111-P?	N
If yes, are the first 2 strings cemented to surface and 3rd string cement tied back 500' into previous casing?	N
Is well located in R-111-P and SOPA?	N
If yes, are the first three strings cemented to surface?	N
Is 2nd string set 100' to 600' below the base of salt?	N
Is well located in high Cave/Karst?	N
If yes, are there two strings cemented to surface?	N
(For 2 string wells) If yes, is there a contingency casing if lost circulation occurs?	N
Is well located in critical Cave/Karst?	N
If yes, are there three strings cemented to surface?	N

**3. Cementing Program**

Casing	# Sks	Wt. lb/gal	Yld ft <sup>3</sup> /sack	H <sub>2</sub> O gal/sk	500# Comp. Strength (hours)	Slurry Description
Surface	509	13.50	1.72	9.15	15.5	Lead: Class C + Bentonite
	136	14.80	1.34	6.32	9.5	Tail: Class C + LCM
Intermediate	923	12.90	1.88	9.65	12	Lead: 35:65 (Poz:C) + Salt + Bentonite
	285	14.80	1.34	6.32	9.5	Tail: Class C + LCM
Production	596	10.30	3.64	22.18		Lead: Tuned Light + LCM
	2174	14.20	1.30	5.86	14:30	Tail: 50:50 (Poz:H) + Salt + Bentonite + Fluid Loss + Dispersant + SMS

Casing String	TOC	% Excess
Surface		45
Intermediate		50
Production	4675	16

**4. Pressure Control Equipment**

	A variance is requested for the use of a diverter on the surface casing. See attached for schematic.
--	--

BOP installed and tested before drilling which hole?	Size	Min Required WP	Type		Tested To
12 1/4	13 5/8	2M	Annular	X	50% of working pressure
			Blind Ram		2M
			Pipe Ram		
			Double Ram	X	
			Other		
8 3/4	13 5/8	3M	Annular	X	50% of working pressure
			Blind Ram		3M
			Pipe Ram		
			Double Ram	X	
			Other		

BOP/BOPE will be tested by an independent service company to 250 psi low and the high pressure indicated above per Onshore Order 2 requirements. The System may be upgraded to a higher pressure but still tested to the working pressure listed in the table above. If the system is upgraded all the components installed will be functional and tested.

Pipe rams will be operationally checked each 24 hour period. Blind rams will be operationally checked on each trip out of the hole. These checks will be noted on the daily tour sheets. Other accessories to the BOP equipment will include a Kelly cock and floor safety valve (inside BOP) and choke lines and choke manifold. See attached schematics.

	Formation integrity test will be performed per Onshore Order #2. On Exploratory wells or on that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.i.
X	A variance is requested for the use of a flexible choke line from the BOP to Choke Manifold. See attached for specs and hydrostatic test chart.
N	Are anchors required by manufacturer?

**5. Mud Program**

Depth	Type	Weight (ppg)	Viscosity	Water Loss
0' to 1050'	FW Spud Mud	8.30 - 8.80	30-32	N/C
1050' to 4875'	Brine Water	9.70 - 10.20	30-32	N/C
4875' to 21744'	FW/Cut Brine	8.50 - 9.00	30-32	N/C

Sufficient mud materials to maintain mud properties and meet minimum lost circulation and weight increase requirements will be kept on location at all times.

What will be used to monitor the loss or gain of fluid?	PVT/Pason/Visual Monitoring
---	-----------------------------

**6. Logging and Testing Procedures**

Logging, Coring and Testing	
X	Will run GR/CNL from TD to surface (horizontal well – vertical portion of hole). Stated logs run will be in the Completion Report and submitted to the BLM.
	No logs are planned based on well control or offset log information.
	Drill stem test?
	Coring?

Additional Logs Planned	Interval

**7. Drilling Conditions**

Condition	
BH Pressure at deepest TVD	5634 psi
Abnormal Temperature	No

Hydrogen Sulfide (H2S) monitors will be installed prior to drilling out the surface shoe. If H2S is detected in concentrations greater than 100 ppm, the operator will comply with the provisions of Onshore Oil and Gas Order #6. If Hydrogen Sulfide is encountered, measured values and formations will be provided to the BLM.	
X	H2S is present
X	H2S plan is attached

**8. Other Facets of Operation**

**9. Wellhead**

A multi-bowl wellhead system will be utilized.

After running the 13-3/8" surface casing, a 13 5/8" BOP/BOPE system with a minimum working pressure of 3000 psi will be installed on the wellhead system and will be pressure tested to 250 psi low followed by a 3000 psi test. Annular will be tested to 50% of working pressure. The pressure test will be repeated at least every 30 days, as per Onshore Order No. 2.

The multi-bowl wellhead will be installed by vendor's representative. A copy of the installation instructions has been sent to the BLM field office.

The wellhead will be installed by a third-party welder while being monitored by the wellhead vendor representative.

All BOP equipment will be tested utilizing a conventional test plug. Not a cup or J-packer type.

A solid steel body pack-off will be utilized after running and cementing the intermediate casing. After installation the pack-off and lower flange will be pressure tested to 3000 psi.

The surface casing string will be tested as per Onshore Order No. 2 to at least 0.22 psi/ft or 1500 psi, whichever is greater.

The casing string utilizing steel body pack-off will be tested to 70% of casing burst.

If well conditions dictate conventional slips will be set and BOPE will be tested to appropriate pressures based on permitted pressure requirements.



APD ID: 10400030762

Submission Date: 05/31/2018

Operator Name: CIMAREX ENERGY COMPANY

Well Name: RED HILLS UNIT

Well Number: 131H

Well Type: CONVENTIONAL GAS WELL

Well Work Type: Drill



Show Final Text

### Section 1 - Existing Roads

Will existing roads be used? NO

### Section 2 - New or Reconstructed Access Roads

Will new roads be needed? YES

New Road Map:

Red\_Hills\_Unit\_32\_5\_Road\_Route\_20180531153233.pdf

Navigation type: COLLECTOR	Length (feet)	Width (feet)
15' Above (ft) AD		10' Inside (ft) IS
Allowance of Emissions (ACOE) permit required? NO		

ACOE Permit Number(s):

New road access location: This will be a new road access location. The site address of any drainage channels or swales that are crossed will be recorded in a digital photo on the map and marked as necessary to avoid erosion. Where the project cannot be avoided, water bars or silt fences will be constructed, mulch mat applied, or other measures employed as necessary to control erosion. Flow bars, check walls or silt fences may also be installed to control erosion as needed. All disturbances will be seeded with a mix appropriate for the area unless specified otherwise by the landowner.

New road access plan attachment? YES

New road access plan attachment:

Access road engineering design? NO

Access road engineering design attachment:

Access surfacing type: GRAVEL

Access location: ONSITE

Operator Name: CIMAREX ENERGY COMPANY

Well Name: RED HILLS UNIT

Well Number: 131H

Access surfacing type description:

Access finish topsoil source depth: 0

Offsite topsoil source description:

Offsite topsoil removal process: Push off and stockpile alongside the location.

Access other construction information:

Access miscellaneous information:

Number of access turnouts:

Access turnout map:

### Drainage Control

New road drainage crossing: CULVERT, LOW WATER, OTHER

Drainage Control components: To control and prevent potentially contaminated precipitation from leaving the pad site, a perimeter berm and sediment pond will be installed. Contaminated water will be collected from pond, directed to waste tanks, and disposed of at a state approved facility. Standing water or puddles will not be allowed. Drainage ditches would be established and maintained on the pad and along access roads to divert water away from operations. Natural drainage areas disturbed during construction would be re-adjointed to near original condition prior to construction. Erosion Control Best Management Practices would be used where necessary and consist of seeding, fibermella, water bars, culchages, and temporary diversion dikes. Areas disturbed during construction that are no longer needed for operations would be rehabilitated, re-contoured to near original condition prior to construction. Erosion Control Best Management Practices would be used where necessary and consist of seeding, fibermella, water bars, culchages, and temporary diversion dikes. Areas disturbed during construction that are no longer needed for operations would be rehabilitated, re-contoured, and reclaimed to near original condition to re-establish natural drainage.

Road Drainage Control Structures (DCS) description: N/A

Road Drainage Control Structures (DCS) attachment:

### Access Additional Attachments

Additional Attachment(s):

### Section 2 - New or Reconstructed Access Roads

Will new roads be needed? YES

New Road Map:

Red\_Hills\_Unit\_32\_5\_Road\_Route\_20180531153233.pdf

New road type:

Length:

Width (ft):

Width (ft):

Max grade (%):

Army Corp of Engineers (ACOE) permit required?

ACOE Permit Number(s):

New road travel width:

New road status: erosion control:

Operator Name: CIMAREX ENERGY COMPANY

Well Name: RED HILLS UNIT

Well Number: 131H

New road access plan or profile prepared?

New road access plan attachment:

Access road engineering design?

Access road engineering design attachment:

Access surfacing type?

Access topsoil source?

Access surfacing type description:

Access onsite topsoil source description:

Offsite topsoil source description:

Onsite topsoil removal process?

Access other construction information:

Access miscellaneous information:

Number of access turnouts:

Access turnout map:

### Drainage Control

New road drainage control?

Drainage Control comment:

Road Drainage Control Structures (DCS) description:

Road Drainage Control Structures (DCS) attachment:

### Access Additional Attachments

Additional Attachment(s):

## Section 2 - New or Reconstructed Access Roads

Will new roads be needed? YES

New Road Map:

Red\_Hills\_Unit\_32\_5\_Road\_Route\_20180531153233.pdf

New road type?

Length

Width (ft)

Max Slope (%)

Max Grade (%)

Army Corp of Engineers (ACE) permit required?

ACOE Permit Number(s):

New road gravel width?

New road erosion control?

**Operator Name:** CIMAREX ENERGY COMPANY

**Well Name:** RED HILLS UNIT

**Well Number:** 131H

**New road access plan or profile prepared?**

**New road access plan attachment:**

**Access road engineering design?**

**Access road engineering design attachment:**

**Access surfacing type?**

**Access topsoil source?**

**Access surfacing type description:**

**Access on the topsoil source description:**

**Offsite topsoil source description:**

**Onsite topsoil removal process?**

**Access other construction information:**

**Access miscellaneous information:**

**Number of access turnouts:**

**Access turnout map:**

**Drainage Control**

**New road drainage engineering?**

**Drainage Control comments?**

**Road Drainage Control Structures (DCS) description?**

**Road Drainage Control Structures (DCS) attachment:**

**Access Additional Attachments**

**Additional Attachment(s):**

**Section 3 - Location of Existing Wells**

**Existing Wells Map? YES**

**Attach Well map:**

Red\_Hills\_Unit\_32\_5\_W2W2\_Pad\_1\_Mile\_Radius\_Existing\_Wells\_20180531153304.pdf

**Existing Wells description:**

**Section 4 - Location of Existing and/or Proposed Production Facilities**

**Submit or defer a Proposed Production Facilities plan? SUBMIT**

**Production Facilities description:**

**Production Facilities map:**

**Operator Name:** CIMAREX ENERGY COMPANY

**Well Name:** RED HILLS UNIT

**Well Number:** 131H

Red\_Hills\_Unit\_32\_East\_BS\_\_3\_CTB\_Battery\_Layout\_20180531153320.pdf

Red\_Hills\_Unit\_32\_East\_WC\_\_4\_CTB\_Battery\_Layout\_20180531153323.pdf

Red\_Hills\_Unit\_32\_West\_BS\_\_1\_CTB\_Battery\_Layout\_20180531153325.pdf

Red\_Hills\_Unit\_32\_West\_WC\_\_2\_CTB\_Battery\_Layout\_20180531153329.pdf

## Section 5 - Location and Types of Water Supply

### Water Source Table

**Water source use type:** INTERMEDIATE/PRODUCTION CASING,  
SURFACE CASING

**Water source type:** MUNICIPAL

**Describe type:**

**Source latitude:**

**Source longitude:**

**Source datum:**

**Water source permit type:** WATER RIGHT,WATER RIGHT

**Permit Number:**

**Source land ownership:** STATE

**Water source transport method:**

PIPELINE,PIPELINE,TRUCKING,TRUCKING

**Source transportation land ownership:** STATE

**Water source volume (barrels):** 5000

**Source volume (acre-feet):** 0.6444655

**Source volume (gal):** 210000

**Water source and transportation map:**

Red\_Hills\_Unit\_32\_5\_Drilling\_Water\_Routes\_20180531153408.pdf

**Water source comments:**

**New water well?** NO

### New Water Well Info

**Well latitude:**

**Well Longitude:**

**Well datum:**

**Well target aquifer:**

**Est. depth to top of aquifer(ft):**

**Est thickness of aquifer:**

**Aquifer comments:**

**Aquifer documentation:**

**Well depth (ft):**

**Well casing type:**

**Well casing outside diameter (in.):**

**Well casing inside diameter (in.):**

**New water well casing?**

**Used casing source:**

**Drilling method:**

**Drill material:**

**Grout material:**

**Grout depth:**

**Operator Name:** CIMAREX ENERGY COMPANY

**Well Name:** RED HILLS UNIT

**Well Number:** 131H

**Casing length (ft.):**

**Casing top depth (ft.):**

**Well Production type:**

**Completion Method:**

**Water well additional information:**

**State appropriation permit:**

**Additional information attachment:**

### Section 6 - Construction Materials

**Construction Materials description:** The drilling and testing operations will be conducted on a watered and compacted native soil grade. Soft spots will be covered with scoria, free of large rocks (3" diameter). Upon completion as a commercial producer the location will be covered with scoria, free of large rocks (3" dia.) from an existing privately owned gravel pit.

**Construction Materials source location attachment:**

### Section 7 - Methods for Handling Waste

**Waste type:** DRILLING

**Waste content description:** Drilling Fluids, drill cuttings, water and other waste produced from the well during drilling operations.

**Amount of waste:** 15000 barrels

**Waste disposal frequency :** Weekly

**Safe containment description:** n/a

**Safe containmant attachment:**

**Waste disposal type:** HAUL TO COMMERCIAL FACILITY **Disposal location ownership:** COMMERCIAL

**Disposal type description:**

**Disposal location description:** Haul to R360 commercial Disposal

**Waste type:** GARBAGE

**Waste content description:** Garbage and trash produced during drilling and completion operations

**Amount of waste:** 32500 pounds

**Waste disposal frequency :** Weekly

**Safe containment description:** n/a

**Safe containmant attachment:**

**Waste disposal type:** HAUL TO COMMERCIAL FACILITY **Disposal location ownership:** COMMERCIAL

**Disposal type description:**

**Disposal location description:** Windmill Spraying Service hauls trash to Lea County Landfill

### Reserve Pit

**Reserve Pit being used?** NO

**Operator Name:** CIMAREX ENERGY COMPANY

**Well Name:** RED HILLS UNIT

**Well Number:** 131H

**Temporary disposal of produced water into reserve pit?**

**Reserve pit length (ft.)**                      **Reserve pit width (ft.)**

**Reserve pit depth (ft.)**    **Reserve pit volume (cu. yd.)**

**Is at least 50% of the reserve pit in cut?**

**Reserve pit liner**

**Reserve pit liner specifications and installation description**

### **Cuttings Area**

**Cuttings Area being used?** NO

**Are you storing cuttings on location?** NO

**Description of cuttings location**

**Cuttings area length (ft.)**    **Cuttings area width (ft.)**

**Cuttings area depth (ft.)**    **Cuttings area volume (cu. yd.)**

**Is at least 50% of the cuttings area in cut?**

**WCuttings area liner**

**Cuttings area liner specifications and installation description**

### **Section 8 - Ancillary Facilities**

**Are you requesting any Ancillary Facilities?:** NO

**Ancillary Facilities attachment:**

**Comments:**

### **Section 9 - Well Site Layout**

**Well Site Layout Diagram:**

Red\_Hills\_Unit\_131H\_Wellsite\_layout\_20180531153431.pdf

**Comments:**

**Operator Name:** CIMAREX ENERGY COMPANY

**Well Name:** RED HILLS UNIT

**Well Number:** 131H

**Section 10 - Plans for Surface Reclamation**

**Type of disturbance:** New Surface Disturbance

**Multiple Well Pad Name:** RED HILLS UNIT 32-5 W2W2

**Multiple Well Pad Number:** PAD 1

**Recontouring attachment:**

Red\_Hills\_Unit\_32\_5\_W2W2\_Pad\_1\_Interim\_Reclaim\_20180531153445.pdf

**Drainage/Erosion control construction:** To control and prevent potentially contaminated precipitation from leaving the pad site, a perimeter berm and settlement pond will be installed. Contaminated water will be removed from pond, stored in waste tanks, and disposed of at a state approved facility. Standing water or puddles will not be allowed. Drainage ditches would be established and maintained on the pad and along access roads to divert water away from operations. Natural drainage areas disturbed during construction would be re-contoured to near original condition prior to construction. Erosion Control Best Management Practices would be used where necessary and consist of seeding, fiber rolls, water bars, silt fences, and temporary diversion dikes. Areas disturbed during construction that are no longer needed for operations would be obliterated, re-contoured to near original condition prior to construction. Erosion Control Best Management Practices would be used where necessary and consist of seeding, fiber rolls, water bars, silt fences, and temporary diversion dikes. Areas disturbed during construction that are no longer needed for operations would be obliterated, re-contoured, and reclaimed to near original condition to re-establish natural drainage.

**Drainage/Erosion control reclamation:** All disturbed and re-contoured areas would be reseeded according to specifications. Approved seed mixtures would be certified weed free and consist of grasses, forbs, or shrubs similar to the surrounding area. Compacted soil areas may need to be obliterated and reclaimed to near natural conditions by re-contouring all slopes to facilitate and re-establish natural drainage.

<b>Well pad proposed disturbance (acres):</b> 6.907	<b>Well pad interim reclamation (acres):</b> 3.551	<b>Well pad long term disturbance (acres):</b> 3.356
<b>Road proposed disturbance (acres):</b> 6.227	<b>Road interim reclamation (acres):</b> 0	<b>Road long term disturbance (acres):</b> 6.227
<b>Powerline proposed disturbance (acres):</b> 8.233	<b>Powerline interim reclamation (acres):</b> 0	<b>Powerline long term disturbance (acres):</b> 8.233
<b>Pipeline proposed disturbance (acres):</b> 30.138	<b>Pipeline interim reclamation (acres):</b> 0	<b>Pipeline long term disturbance (acres):</b> 30.138
<b>Other proposed disturbance (acres):</b> 10.181	<b>Other interim reclamation (acres):</b> 0	<b>Other long term disturbance (acres):</b> 10.181
<b>Total proposed disturbance:</b> 61.686	<b>Total interim reclamation:</b> 3.551	<b>Total long term disturbance:</b> 58.135

**Disturbance Comments:** Flowline: 6009', Gas lift: 6009', Power: 11952', SWD: 11421', Sales: 7555', Oil: 8997', Road: 9041' Temp fresh water line: 9641'

**Reconstruction method:** After well plugging, all disturbed areas would be returned to the original contour or a contour that blends with the surrounding landform including roads unless the surface owner requests that they be left intact. In consultation with the surface owners it will be determined if any gravel or similar materials used to reinforce an area are to be removed, buried, or left in place during final reclamation. Salvaged topsoil, if any, would be re-spread evenly over the surfaces to be re-vegetated. As necessary, the soil surface would be prepared to provide a seedbed for re-establishment of desirable vegetation. Site preparation may include gouging, scarifying, dozer track-walking, mulching, or fertilizing. Reclamation, Re-vegetation, and Drainage: All disturbed and re-contoured areas would be reseeded using techniques outlined under Phase I and II of this plan or as specified by the land owner. Approved seed mixtures would be certified weed free and consist of grasses, forbs, or shrubs similar to the surrounding area. Compacted soil areas may need to be obliterated and reclaimed to near natural conditions by re-contouring all slopes to facilitate and re-establish natural drainage. **Topsoil redistribution:** Salvaged topsoil, if any, would be re-spread evenly over the surfaces to be re-vegetated.

**Soil treatment:** As necessary, the soil surface would be prepared to provide a seedbed for re-establishment of desirable vegetation. Site preparation may include gouging, scarifying, dozer track-walking, mulching or fertilizing.

**Existing Vegetation at the well pad:**

**Operator Name:** CIMAREX ENERGY COMPANY

**Well Name:** RED HILLS UNIT

**Well Number:** 131H

**Existing Vegetation at the well pad attachment:**

**Existing Vegetation Community at the road:**

**Existing Vegetation Community at the road attachment:**

**Existing Vegetation Community at the pipeline:**

**Existing Vegetation Community at the pipeline attachment:**

**Existing Vegetation Community at other disturbances:**

**Existing Vegetation Community at other disturbances attachment:**

**Non native seed used?**

**Non native seed description:**

**Seedling transplant description:**

**Will seedlings be transplanted for this project?**

**Seedling transplant description attachment:**

**Will seed be harvested for use in site reclamation?**

**Seed harvest description:**

**Seed harvest description attachment:**

**Seed Management**

**Seed Table**

**Seed type:**

**Seed source:**

**Seed name:**

**Source name:**

**Source address:**

**Source phone:**

**Seed cultivar:**

**Seed use location:**

**PLS pounds per acre:**

**Proposed seeding season:**

<b>Seed Summary</b>	
<b>Seed Type</b>	<b>Pounds/Acre</b>

**Total pounds/Acre:**

**Operator Name:** CIMAREX ENERGY COMPANY

**Well Name:** RED HILLS UNIT

**Well Number:** 131H

**Seed reclamation attachment:**

**Operator Contact/Responsible Official Contact Info**

**First Name:**

**Last Name:**

**Phone:**

**Email:**

**Seedbed prep:**

**Seed BMP:**

**Seed method:**

**Existing invasive species?** NO

**Existing invasive species treatment description:**

**Existing invasive species treatment attachment:**

**Weed treatment plan description:** N/A

**Weed treatment plan attachment:**

**Monitoring plan description:** N/A

**Monitoring plan attachment:**

**Success standards:** N/A

**Pit closure description:** N/A

**Pit closure attachment:**

**Section 11 - Surface Ownership**

**Disturbance type:** WELL PAD

**Describe:**

**Surface Owner:** PRIVATE OWNERSHIP

**Other surface owner description:**

**BIA Local Office:**

**BOR Local Office:**

**COE Local Office:**

**DOD Local Office:**

**NPS Local Office:**

**State Local Office:**

**Military Local Office:**

**USFWS Local Office:**

**Operator Name:** CIMAREX ENERGY COMPANY

**Well Name:** RED HILLS UNIT

**Well Number:** 131H

**Other Local Office:**

**USFS Region:**

**USFS Forest/Grassland:**

**USFS Ranger District:**

**Fee Owner:** Tommy Dinwiddle (Dinwiddie Cattle Co) **Fee Owner Address:** PO Box 963 Capitan, NM 88316

**Phone:** (575)355-7610

**Email:**

**Surface use plan certification:** YES

**Surface use plan certification document:**

Red\_Hills\_Unit\_131H\_Operator\_Land\_Owner\_Agreement\_20180531153607.pdf

**Surface access agreement or bond:** Agreement

**Surface Access Agreement Need description:** See Attached Operator\_Land Owner Agreement

**Surface Access Bond BLM or Forest Service:**

**BLM Surface Access Bond number:**

**USFS Surface access bond number:**

## Section 12 - Other Information

**Right of Way needed?** YES

**Use APD as ROW?** YES

**ROW Type(s):** 281001 ROW - ROADS,285003 ROW – POWER TRANS,288100 ROW – O&G Pipeline,288101 ROW – O&G Facility Sites,288103 ROW – Salt Water Disposal Pipeline/Facility,288104 ROW – Salt Water Disposal ApIn/Fac-FLPMA,289001 ROW- O&G Well Pad,FLPMA (Powerline),Other

## ROW Applications

**SUPO Additional Information:** The surface disturbance for the SWD, Road, Sales, Oil & Power routes are the same for Red Hills Unit Wells in Sec 32-25S-33R.

**Use a previously conducted onsite?** YES

**Previous Onsite information:** Onsite April 17, 2018 with BLM (Jeff Robertson) and Cimarex (Barry Hunt)

## Other SUPO Attachment

Red\_Hills\_Unit\_32\_5\_W2W2\_Pad\_1\_Public\_Access\_20180531153647.pdf

Red\_Hills\_Unit\_32\_5\_W2W2\_Pad\_1\_Road\_Description\_20180531153649.pdf

Red\_Hills\_Unit\_32\_5\_Flow\_Gas\_lift\_Route\_20180531153651.pdf

Red\_Hills\_Unit\_32\_5\_Oil\_Pipeline\_Route\_20180531153654.pdf

**Operator Name:** CIMAREX ENERGY COMPANY

**Well Name:** RED HILLS UNIT

**Well Number:** 131H


Red\_Hills\_Unit\_32\_5\_Power\_Route\_20180531153658.pdf


Red\_Hills\_Unit\_32\_5\_Sales\_Route\_20180531153659.pdf

Red\_Hills\_Unit\_32\_5\_SWD\_Route\_20180531153702.pdf

Red\_Hills\_Unit\_131H\_SUPO\_20180531153704.pdf

Red\_Hills\_Unit\_32\_5\_Temp\_Water\_Route\_20180531153703.pdf






A 30' WIDE RIGHT-OF-WAY 15' ON EACH SIDE OF THE FOLLOWING DESCRIBED CENTERLINE.

BEGINNING AT A POINT IN THE SW 1/4 SW 1/4 OF SECTION 28, T25S, R33E, N.M.P.M., WHICH BEARS N88°23'10"E 663.86' FROM THE SOUTHWEST CORNER OF SAID SECTION 28, THENCE S89°59'33"W 663.64' TO A POINT ON THE WEST LINE OF THE SW 1/4 SW 1/4 OF SAID SECTION 28, WHICH BEARS N00°07'52"W 18.61' FROM THE SOUTHWEST CORNER OF SAID SECTION 28. THE SIDE LINES OF SAID DESCRIBED RIGHT-OF-WAY BEING SHORTENED OR ELONGATED TO MEET THE GRANTOR'S PROPERTY LINES. BASIS OF BEARINGS IS A TRANSVERSE MERCATOR PROJECTION WITH A CENTRAL MERIDIAN OF W103°53'00". CONTAINS 0.457 ACRES MORE OR LESS.

END OF PROPOSED ROAD "A" RIGHT-OF-WAY ON BLM LANDS IN SECTION 28 (At Section Line)

BEGINNING OF ROAD BEARS N88°23'10"E 663.86' FROM THE SOUTHWEST CORNER OF SECTION 28, T25S, R33E, N.M.P.M.

END OF ROAD ON BLM LANDS IN SECTION 28 BEARS N00°07'52"W 18.61' FROM THE SOUTHWEST CORNER OF SECTION 28, T25S, R33E, N.M.P.M.




LINE TABLE		
LINE	DIRECTION	LENGTH
L1	S89°59'33"W	663.64'



ACREAGE / LENGTH TABLE				
	OWNERSHIP	FEET	RODS	ACRES
SEC. 28 (SW 1/4)	BLM	663.64	40.22	0.457

▲ = SECTION CORNERS LOCATED.

**CERTIFICATE**  
THIS IS TO CERTIFY THAT THIS EASEMENT PLAT AND THE ACTUAL SURVEY OF THE GROUND UPON WHICH IT IS BASED WERE PERFORMED BY ME OR UNDER MY DIRECT SUPERVISION, THAT I AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY MEETS THE MINIMUM STANDARDS FOR SURVEYING IN NEW MEXICO, AND THAT IT IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.



FILE: 63857-A1

Sheet 1 of 8

**NOTES:**

- The maximum grade of existing ground for the proposed access road is ± 3.08%.
- Basis of Bearings is a Transverse Mercator Projection with a Central Meridian of W103°53'00"





**UELS, LLC**  
Corporate Office \* 85 South 200 East  
Vernal, UT 84078 \* (435) 789-1017



**CIMAREX ENERGY CO.**  
**RED HILLS UNIT 32-5 ACCESS ROAD NETWORK  
ON BLM LANDS  
SECTION 28, T25S, R33E, N.M.P.M.  
LEA COUNTY, NEW MEXICO**

SURVEYED BY	J.J., C.H.	04-20-18	SCALE
DRAWN BY	J.P.P.	05-17-18	1" = 1000'
<b>ACCESS ROAD R-O-W</b>		<b>EXHIBIT D</b>	



LINE TABLE		
LINE	DIRECTION	LENGTH
L2	S89°59'33"W	9.70'
L3	S45°01'08"W	26.39'


**ROAD "A" RIGHT-OF-WAY DESCRIPTION ON BLM LANDS IN SECTION 29**

A 30' WIDE RIGHT-OF-WAY 15' ON EACH SIDE OF THE FOLLOWING DESCRIBED CENTERLINE.

BEGINNING AT A POINT ON THE EAST LINE OF THE SE 1/4 SE 1/4 OF SECTION 29, T25S, R33E, N.M.P.M., WHICH BEARS N00°07'52"W 18.61' FROM THE SOUTHEAST CORNER OF SAID SECTION 29, THENCE S89°59'33"W 9.70'; THENCE S45°01'08"W 26.39' TO A POINT ON THE SOUTH LINE OF THE SE 1/4 SE 1/4 OF SAID SECTION 29, WHICH BEARS S89°54'44"W 28.41' FROM THE SOUTHEAST CORNER OF SAID SECTION 29. THE SIDE LINES OF SAID DESCRIBED RIGHT-OF-WAY BEING SHORTENED OR ELONGATED TO MEET THE GRANTOR'S PROPERTY LINES. BASIS OF BEARINGS IS A TRANSVERSE MERCATOR PROJECTION WITH A CENTRAL MERIDIAN OF W103°53'00". CONTAINS 0.025 ACRES MORE OR LESS.

**Detail "A"**  
No Scale



END OF PROPOSED ROAD "A" RIGHT-OF-WAY ON BLM LANDS IN SECTION 29 (At Section Line)



BEGINNING OF ROAD ON BLM LANDS IN SECTION 29 BEARS N00°07'52"W 18.61' FROM THE SOUTHEAST CORNER OF SECTION 29, T25S, R33E, N.M.P.M.

END OF ROAD ON BLM LANDS IN SECTION 29 BEARS S89°54'44"W 28.41' FROM THE SOUTHEAST CORNER OF SECTION 29, T25S, R33E, N.M.P.M.

**CERTIFICATE**  
THIS IS TO CERTIFY THAT THIS EASEMENT PLAT AND THE ACTUAL SURVEY ON THE GROUND UPON WHICH IT IS BASED WERE PERFORMED BY ME OR UNDER MY DIRECT SUPERVISION, THAT I AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY MEETS THE MINIMUM STANDARDS FOR SURVEYING IN NEW MEXICO, AND THAT IT IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.



ACREAGE / LENGTH TABLE				
	OWNERSHIP	FEET	RODS	ACRES
SEC. 29 (SE 1/4)	BLM	36.09	2.19	0.025

▲ = SECTION CORNERS LOCATED.

FILE: 63857-B1

Sheet 3 of 8

**NOTES:**

- The maximum grade of existing ground for the proposed access road is ± 3.08%.
- Basis of Bearings is a Transverse Mercator Projection with a Central Meridian of W103°53'00"



**UELS, LLC**  
Corporate Office \* 85 South 200 East  
Vernal, UT 84078 \* (435) 789-1017



**CIMAREX ENERGY CO.**  
**RED HILLS UNIT 32-5 ACCESS ROAD NETWORK**  
**ON BLM LANDS**  
**SECTION 29, T25S, R33E, N.M.P.M.**  
**LEA COUNTY, NEW MEXICO**

SURVEYED BY	J.J., C.H.	04-20-18	SCALE
DRAWN BY	J.P.P.	05-17-18	1" = 1000'


**ACCESS ROAD R-O-W EXHIBIT D**



END OF PROPOSED ROAD "B" RIGHT-OF-WAY (At Edge of Proposed Red Hills Unit 32-5 E2E2 Pad #6)


BEGINNING OF PROPOSED ROAD "A" RIGHT-OF-WAY ON STATE OF NEW MEXICO LANDS IN SECTION 32 (At Section Line)

BEGINNING OF PROPOSED ROAD "C" RIGHT-OF-WAY (At the Centerline of the Proposed Red Hill Unit 32-5 Access Road "A")



BEGINNING OF PROPOSED ROAD "B" RIGHT-OF-WAY (At the Centerline of the Proposed Red Hill Unit 32-5 Access Road "A")

END OF PROPOSED ROAD "C" RIGHT-OF-WAY (At Edge of Proposed Red Hills Unit 32-5 W2W2 Pad #1)



END OF PROPOSED ROAD "A" RIGHT-OF-WAY (At Edge of Proposed Red Hills Unit 32 West BS #1 CTB)

BEGINNING OF PROPOSED ROAD "D" RIGHT-OF-WAY (At the Centerline of the Proposed Red Hill Unit 32-5 Access Road "A")

ACREAGE / LENGTH TABLE "A"				
	OWNERSHIP	FEET	RODS	ACRES
SEC. 32 (NE 1/4 NE 1/4)	STATE OF NEW MEXICO	1302.73	78.95	0.897
SEC. 32 (NW 1/4 NE 1/4)	STATE OF NEW MEXICO	1322.85	80.17	0.911
SEC. 32 (NE 1/4 NW 1/4)	STATE OF NEW MEXICO	1321.89	80.11	0.910
SEC. 32 (NW 1/4 NW 1/4)	STATE OF NEW MEXICO	1866.13	113.10	1.285
SEC. 32 (SW 1/4 NW 1/4)	STATE OF NEW MEXICO	369.06	22.37	0.254
TOTAL		6182.66	374.71	4.258


ACREAGE / LENGTH TABLE "B"				
	OWNERSHIP	FEET	RODS	ACRES
SEC. 32 (NE 1/4 NE 1/4)	STATE OF NEW MEXICO	108.92	6.60	0.075

ACREAGE / LENGTH TABLE "C"				
	OWNERSHIP	FEET	RODS	ACRES
SEC. 32 (NW 1/4 NW 1/4)	STATE OF NEW MEXICO	66.63	4.04	0.046

ACREAGE / LENGTH TABLE "D"				
	OWNERSHIP	FEET	RODS	ACRES
SEC. 32 (NW 1/4 NW 1/4)	STATE OF NEW MEXICO	574.47	34.82	0.396
SEC. 32 (NE 1/4 NW 1/4)	STATE OF NEW MEXICO	1321.89	80.11	0.910
SEC. 32 (NW 1/4 NE 1/4)	STATE OF NEW MEXICO	86.62	5.25	0.060
TOTAL		1982.98	120.18	1.366

CERTIFICATE

THIS IS TO CERTIFY THAT THIS EASEMENT PLAT AND THE ACTUAL SURVEY ON THE GROUND UPON WHICH IT IS BASED WERE PERFORMED BY ME OR UNDER MY DIRECT SUPERVISION, THAT I AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY MEETS THE MINIMUM STANDARDS FOR SURVEYING IN NEW MEXICO, AND THAT IT IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.



FILE: 63857-C2

Sheet 6 of 8

CIMAREX ENERGY CO.


RED HILLS UNIT 32-5 ROAD ACCESS NETWORK ON STATE OF NEW MEXICO LANDS SECTION 32, T25S, R33E, N.M.P.M. LEA COUNTY, NEW MEXICO

SURVEYED BY	J.J., C.H.	04-20-18	SCALE
DRAWN BY	J.P.P.	05-17-18	N/A

ACCESS ROAD R-O-W EXHIBIT D



UELS, LLC  
Corporate Office \* 85 South 200 East  
Vernal, UT 84078 \* (435) 789-1017



**LEGEND:**

- EXISTING WELLS




**UELS, LLC**  
Corporate Office \* 85 South 200 East  
Vernal, UT 84078 \* (435) 789-1017





**CIMAREX ENERGY CO.**

**RED HILLS UNIT 32-5 W2W2 PAD #1**  
NE 1/4 NW 1/4, SECTION 32, T25S, R33E, N.M.P.M.  
LEA COUNTY, NEW MEXICO

<b>SURVEYED BY</b>	A.H., F.R.	05-01-18	<b>SCALE</b>
<b>DRAWN BY</b>	V.L.D.	05-07-18	1 : 36,000
<b>ONE MILE RADIUS PLAT</b>			<b>EXHIBIT A</b>



**CERTIFICATE**  
 THIS MAP HAS BEEN PRODUCED ACCORDING TO PROCEDURES THAT HAVE BEEN DEMONSTRATED TO PRODUCE DATA THAT MEETS OR EXCEEDS THE MINIMUM STANDARDS FOR A TOPOGRAPHIC MAP COMPILED AT A SCALE OF 1" = 100' WITH A CONTOUR INTERVAL OF 2'



**FINISHED GRADE ELEVATION = 3409.2'**

- NOTES:**
- Contours shown at 2' intervals.
  - Cut/Fill slopes 1 1/2:1 (Typ. except where noted)
  - Basis of Bearings is a Transverse Mercator Projection with a Central Meridian of W103°53'00"




**UELS, LLC**  
 Corporate Office \* 85 South 200 East  
 Vernal, UT 84078 \* (435) 789-1017

**CIMAREX ENERGY CO.**  
**RED HILLS UNIT 32 EAST BS #3 CTB**  
**1005' FNL 2276' FWL (APPROX. CENTER OF PAD)**  
**NE 1/4 NW 1/4, SECTION 32, T25S, R33E, N.M.P.M.**  
**LEA COUNTY, NEW MEXICO**

<b>SURVEYED BY</b>	J.J., C.H.	05-01-18	<b>SCALE</b>
<b>DRAWN BY</b>	J.N.	05-07-18	1" = 100'

**LOCATION LAYOUT EXHIBIT F**

1" = 40'  
 X-Section  
 Scale  
 1" = 100'



APPROXIMATE EARTHWORK QUANTITIES	
(4") TOPSOIL STRIPPING	3,110 Cu. Yds.
REMAINING LOCATION	4,770 Cu. Yds.
<b>TOTAL CUT</b>	<b>7,880 Cu. Yds.</b>
<b>FILL</b>	<b>4,770 Cu. Yds.</b>
EXCESS MATERIAL	3,110 Cu. Yds.
TOPSOIL & PIT BACKFILL	3,110 Cu. Yds.
<b>EXCESS UNBALANCE</b> (After Interim Rehabilitation)	<b>0 Cu. Yds.</b>

APPROXIMATE SURFACE DISTURBANCE AREAS		
	DISTANCE	ACRES
WELL SITE DISTURBANCE	NA	±6.055
PROPOSED FLOW LINE CONNECTION AREA	NA	±0.230
<b>TOTAL SURFACE USE AREA</b>		<b>±6.285</b>

**NOTES:**

- Fill quantity includes 5% for compaction.
- Cut/Fill slopes 1 1/2:1 (Typ. except where noted)

**CIMAREX ENERGY CO.**


**RED HILLS UNIT 32 EAST BS #3 CTB**  
**1005' FNL 2276' FWL (APPROX. CENTER OF PAD)**  
**NE 1/4 NW 1/4, SECTION 32, T25S, R33E, N.M.P.M.**  
**LEA COUNTY, NEW MEXICO**



**UELS, LLC**  
 Corporate Office \* 85 South 200 East  
 Vernal, UT 84078 \* (435) 789-1017

SURVEYED BY	J.J., C.H.	05-01-18	SCALE
DRAWN BY	J.N.	05-07-18	AS SHOWN

**TYPICAL CROSS SECTIONS EXHIBIT F**



650' X 750' Archaeological Survey Boundary

Proposed Flow Line  
Connection Area

Topsail Stockpile

Proposed Red Hills  
Unit 32-5  
Access Road "D"

Proposed Red Hills  
Unit 32-5  
Access Road "D"  
(Alternate Egress)

**NOTES:**

**CIMAREX ENERGY CO.**

**RED HILLS UNIT 32 EAST BS #3 CTB  
1005' FNL 2276' FWL (APPROX. CENTER OF PAD)  
NE 1/4 NW 1/4, SECTION 32, T25S, R33E, N.M.P.M.  
LEA COUNTY, NEW MEXICO**

<b>SURVEYED BY</b>	J.J., C.H.	05-01-18	<b>SCALE</b>
<b>DRAWN BY</b>	J.N.	05-07-18	1" = 100'
<b>ARCHAEOLOGICAL SURVEY BOUNDARY</b>			<b>EXHIBIT F</b>



**UELS, LLC**  
Corporate Office \* 85 South 200 East  
Vernal, UT 84078 \* (435) 789-1017

BEGINNING AT THE INTERSECTION J-1/ORLA ROAD AND AN EXISTING ROAD TO THE EAST (LOCATED AT NAD 83 LATITUDE N32.0650° AND LONGITUDE W103.6743°) PROCEED IN AN EASTERLY DIRECTION APPROXIMATELY 5.0 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE NORTHWEST; TURN LEFT AND PROCEED IN A NORTHWESTERLY, THEN NORTHEASTERLY DIRECTION APPROXIMATELY 2.4 MILES TO THE BEGINNING OF THE PROPOSED RED HILLS UNIT 32-5 ACCESS ROAD "A" TO THE WEST; FOLLOW ROAD FLAGS IN A WESTERLY, THEN SOUTHERLY DIRECTION APPROXIMATELY 6,409' TO THE BEGINNING OF THE PROPOSED RED HILLS UNIT 32-5 ACCESS ROAD "D" TO THE EAST; TURN LEFT AND PROCEED IN AN EASTERLY DIRECTION APPROXIMATELY 1,253' TO THE PROPOSED LOCATION.

TOTAL DISTANCE FROM THE INTERSECTION OF J-1/ORLA ROAD AND AN EXISTING ROAD TO THE EAST (LOCATED AT NAD 83 LATITUDE N32.0650° AND LONGITUDE W103.6743°) TO THE PROPOSED WELL LOCATION IS APPROXIMATELY 8.9 MILES.


**CIMAREX ENERGY CO.**

**RED HILLS UNIT 32 EAST BS #3 CTB  
1005' FNL 2276' FWL (APPROX. CENTER OF PAD)  
NE 1/4 NW 1/4, SECTION 32, T25S, R33E, N.M.P.M.  
LEA COUNTY, NEW MEXICO**

<b>SURVEYED BY</b>	J.J. C.H.	05-01-18	
<b>DRAWN BY</b>	V.L.D.	05-15-18	
<b>ROAD DESCRIPTION</b>			<b>EXHIBIT F</b>



**UELS, LLC**  
Corporate Office \* 85 South 200 East  
Vernal, UT 84078 \* (435) 789-1017



JAL, NEW MEXICO IS 23.6 +/- MILES EASTERLY

**LEGEND:**

● PROPOSED LOCATION




**UELS, LLC**  
 Corporate Office \* 85 South 200 East  
 Vernal, UT 84078 \* (435) 789-1017



**CIMAREX ENERGY CO.**


**RED HILLS UNIT 32 EAST BS #3 CTB**  
 1005' FNL 2276' FWL (APPROX. CENTER OF PAD)  
 NE 1/4 NW 1/4, SECTION 32, T25S, R33E, N.M.P.M.  
 LEA COUNTY, NEW MEXICO

SURVEYED BY	J.J., C.H.	05-01-18	SCALE
DRAWN BY	V.L.D.	05-15-18	1 : 100,000
<b>PUBLIC ACCESS ROAD MAP EXHIBIT F</b>			




**FLOW LINE CONNECTION SURFACE USE AREA DESCRIPTION**

BEGINNING AT A POINT IN THE NE 1/4 NW 1/4 OF SECTION 32, T25S, R33E, N.M.P.M., WHICH BEARS S31°05'07\"/>



**CERTIFICATE**  
 THIS IS TO CERTIFY THAT THIS SURFACE USE AREA PLAT AND THE ACTING SURVEY ON THE GROUND UPON WHICH IT IS BASED WERE PERFORMED BY ME OR UNDER MY DIRECT SUPERVISION THAT I AM RESPONSIBLE FOR THIS SURVEY. THAT THIS SURVEY MEETS THE MINIMUM STANDARDS FOR SURVEYING IN NEW MEXICO AND THAT THIS IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.



▲ = SECTION CORNERS LOCATED.

FILE: 63867-A1

Sheet 1 of 2

**NOTES:**

• Basis of Bearings is a Transverse Mercator Projection with a Central Meridian of W103°53'00\"/>



**UELS, LLC**  
 Corporate Office \* 85 South 200 East  
 Vernal, UT 84078 \* (435) 789-1017




**CIMAREX ENERGY CO.**



**RED HILLS UNIT 32 EAST BS #3 CTB  
 ON STATE OF NEW MEXICO LANDS IN  
 SECTION 32, T25S, R33E, N.M.P.M.  
 LEA COUNTY, NEW MEXICO**

SURVEYED BY	J.J., C.H.	05-01-18	SCALE
DRAWN BY	R.J.	05-16-18	1" = 1000'

**FLOW LINE CONNECTION SUA EXHIBIT F**



**CERTIFICATE**  
 THIS MAP HAS BEEN PRODUCED ACCORDING TO PROCEDURES THAT HAVE BEEN DEMONSTRATED TO PRODUCE DATA THAT MEETS OR EXCEEDS THE MINIMUM STANDARDS FOR A TOPOGRAPHIC MAP COMPILED AT A SCALE OF 1"=200' WITH A CONTOUR INTERVAL OF 2'



**FINISHED GRADE ELEVATION = 3409.5'**

- NOTES:**
- Contours shown at 2' intervals.
  - Cut/Fill slopes 1 1/2:1 (Typ. except where noted)
  - Topsoil stockpile to be seeded in place prior to reclamation.

**CIMAREX ENERGY CO.**

**RED HILLS UNIT 32 EAST WC #4 CTB**  
**1005' FNL 2284' FEL (APPROX. CENTER OF PAD)**  
**NW 1/4 NE 1/4, SECTION 32, T25S, R33E, N.M.P.M.**  
**LEA COUNTY, NEW MEXICO**


SURVEYED BY	J.J. C.H.	05-01-18	SCALE
DRAWN BY	R.J.	05-06-18	1" = 80'

**LOCATION LAYOUT EXHIBIT F**



**UELS, LLC**  
 Corporate Office \* 85 South 200 East  
 Vernal, UT 84078 \* (435) 789-1017

1" = 40'  
 X-Section  
 Scale  
 1" = 100'



APPROXIMATE EARTHWORK QUANTITIES	
(4") TOPSOIL STRIPPING	3,100 Cu. Yds.
REMAINING LOCATION	4,800 Cu. Yds.
<b>TOTAL CUT</b>	<b>7,900 Cu. Yds.</b>
<b>FILL</b>	<b>4,800 Cu. Yds.</b>
EXCESS MATERIAL	3,100 Cu. Yds.
TOPSOIL	3,100 Cu. Yds.
<b>EXCESS UNBALANCE</b> (After Interim Rehabilitation)	<b>0 Cu. Yds.</b>

APPROXIMATE SURFACE DISTURBANCE AREAS		
	DISTANCE	ACRES
WELL SITE DISTURBANCE	NA	±6.033
PROPOSED FLOW LINE CONNECTION AREA	NA	±0.230
<b>TOTAL SURFACE USE AREA</b>		<b>±6.263</b>

**NOTES:**

- Fill quantity includes 5% for compaction.
- Cut/Fill slopes 1 1/2:1 (Typ. except where noted)


**CIMAREX ENERGY CO.**

**RED HILLS UNIT 32 EAST WC #4 CTB  
 1005' FNL 2284' FEL (APPROX. CENTER OF PAD)  
 NW 1/4 NE 1/4, SECTION 32, T25S, R33E, N.M.P.M.  
 LEA COUNTY, NEW MEXICO**

SURVEYED BY	J.J., C.H.	05-01-18	SCALE
DRAWN BY	R.J.	05-06-18	AS SHOWN
<b>TYPICAL CROSS SECTIONS</b>			<b>EXHIBIT F</b>



**UELS, LLC**  
 Corporate Office \* 85 South 200 East  
 Vernal, UT 84078 \* (435) 789-1017



750' X 650'  
Archaeological Survey Boundary

Proposed Flow Line  
Connection Area

Topsail Stockpile

Proposed Red Hills  
Unit 32-5  
Access Road "D"

**NOTES:**

**CIMAREX ENERGY CO.**

**RED HILLS UNIT 32 EAST WC #4 CTB  
1005' FNL 2284' FEL (APPROX. CENTER OF PAD)  
NW 1/4 NE 1/4, SECTION 32, T25S, R33E, N.M.P.M.  
LEA COUNTY, NEW MEXICO**

<b>SURVEYED BY</b>	J.J., C.H.	05-01-18	<b>SCALE</b>
<b>DRAWN BY</b>	R.J.	05-06-18	1" = 100'
<b>ARCHAEOLOGICAL SURVEY BOUNDARY</b>			<b>EXHIBIT F</b>



**UELS, LLC**  
Corporate Office \* 85 South 200 East  
Vernal, UT 84078 \* (435) 789-1017

BEGINNING AT THE INTERSECTION J-1/ORLA ROAD AND AN EXISTING ROAD TO THE EAST (LOCATED AT NAD 83 LATITUDE N32.0650° AND LONGITUDE W103.6743°) PROCEED IN AN EASTERLY DIRECTION APPROXIMATELY 5.0 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE NORTHWEST; TURN LEFT AND PROCEED IN A NORTHWESTERLY, THEN NORTHEASTERLY DIRECTION APPROXIMATELY 2.4 MILES TO THE BEGINNING OF THE PROPOSED RED HILLS UNIT 32-5 ACCESS ROAD "A" TO THE WEST; FOLLOW ROAD FLAGS IN A WESTERLY, THEN SOUTHERLY DIRECTION APPROXIMATELY 6,409' TO THE BEGINNING OF THE PROPOSED RED HILLS UNIT 32-5 ACCESS ROAD "D" TO THE EAST; TURN LEFT AND PROCEED IN AN EASTERLY DIRECTION APPROXIMATELY 1,983' TO THE PROPOSED LOCATION.

TOTAL DISTANCE FROM THE INTERSECTION OF J-1/ORLA ROAD AND AN EXISTING ROAD TO THE EAST (LOCATED AT NAD 83 LATITUDE N32.0650° AND LONGITUDE W103.6743°) TO THE PROPOSED WELL LOCATION IS APPROXIMATELY 9.0 MILES.


**CIMAREX ENERGY CO.**

**RED HILLS UNIT 32 EAST WC #4 CTB  
1005' FNL 2284' FEL (APPROX. CENTER OF PAD)  
NW 1/4 NE 1/4, SECTION 32, T25S, R33E, N.M.P.M.  
LEA COUNTY, NEW MEXICO**

<b>SURVEYED BY</b>	J.J., C.H.	05-01-18	
<b>DRAWN BY</b>	V.L.D.	05-15-18	
<b>ROAD DESCRIPTION</b>			<b>EXHIBIT F</b>



**UELS, LLC**  
Corporate Office \* 85 South 200 East  
Vernal, UT 84078 \* (435) 789-1017



JAL, NEW MEXICO IS 23.5 +/- MILES EASTERLY

**LEGEND:**

**PROPOSED LOCATION**




**UELS, LLC**  
 Corporate Office \* 85 South 200 East  
 Vernal, UT 84078 \* (435) 789-1017



**CIMAREX ENERGY CO.**


**RED HILLS UNIT 32 EAST WC #4 CTB**  
 1005' FNL 2284' FEL (APPROX. CENTER OF PAD)  
 NW 1/4 NE 1/4, SECTION 32, T25S, R33E, N.M.P.M.  
 LEA COUNTY, NEW MEXICO

<b>SURVEYED BY</b>	J.J., C.H.	05-01-18	<b>SCALE</b>
<b>DRAWN BY</b>	V.L.D.	05-15-18	1 : 100,000
<b>PUBLIC ACCESS ROAD MAP EXHIBIT F</b>			





**FLOW LINE CONNECTION SURFACE USE AREA DESCRIPTION**

BEGINNING AT A POINT IN THE NW 1/4 NE 1/4 OF SECTION 32, T25S, R33E, N.M.P.M., WHICH BEARS S06°56'48"E 735.73' FROM THE NORTH 1/4 CORNER OF SAID SECTION 32, THENCE N89°53'56"E 200.00'; THENCE S00°06'04"E 50.00'; THENCE S89°53'56"W 200.00'; THENCE N00°06'04"W 50.00' TO THE POINT OF BEGINNING. BASIS OF BEARING IS A TRANSVERSE MERCATOR PROJECTION WITH A CENTRAL MERIDIAN OF W103°53'00". CONTAINS 0.230 ACRES MORE OR LESS.



**PROPOSED FLOW LINE CONNECTION SURFACE USE AREA**  
Acres = 0.230 ±

**CERTIFICATE**  
THIS IS TO CERTIFY THAT THIS SURFACE USE AREA PLAT AND THE ACTUAL SURVEY ON THE GROUND UPON WHICH IT IS BASED WERE PERFORMED BY ME OR UNDER MY DIRECT SUPERVISION THAT I AM RESPONSIBLE FOR THIS SURVEY. THAT THIS SURVEY MEETS THE MINIMUM STANDARDS FOR SURVEYING IN NEW MEXICO AND THAT THIS IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.



▲ = SECTION CORNERS LOCATED.

FILE: 63863-A1

Sheet 1 of 2

**NOTES:**

\* Basis of Bearings is a Transverse Mercator Projection with a Central Meridian of W103°53'00"

**CIMAREX ENERGY CO.**

**RED HILLS UNIT 32 EAST WC #4 CTB  
ON STATE OF NEW MEXICO LANDS IN  
SECTION 32, T25S, R33E, N.M.P.M.  
LEA COUNTY, NEW MEXICO**

SURVEYED BY	J.J. C.H.	05-01-18	SCALE
DRAWN BY	R.J.	05-16-18	1" = 1000'


**FLOW LINE CONNECTION SURFACE USE AREA EXHIBIT F**



**UELS, LLC**  
Corporate Office \* 85 South 200 East  
Vernal, UT 84078 \* (435) 789-1017








1" = 40'  
 X-Section Scale  
 1" = 100'

Slope = 1 1/2:1  
 (Typ.)



APPROXIMATE EARTHWORK QUANTITIES	
(4") TOPSOIL STRIPPING	3,110 Cu. Yds.
REMAINING LOCATION	4,870 Cu. Yds.
<b>TOTAL CUT</b>	<b>7,980 Cu. Yds.</b>
<b>FILL</b>	<b>4,870 Cu. Yds.</b>
EXCESS MATERIAL	3,110 Cu. Yds.
TOPSOIL	3,110 Cu. Yds.
<b>EXCESS UNBALANCE</b> (After Interim Rehabilitation)	<b>0 Cu. Yds.</b>

APPROXIMATE SURFACE DISTURBANCE AREAS		
	DISTANCE	ACRES
WELL SITE DISTURBANCE	NA	±6.074
PROPOSED FLOW LINE CONNECTION AREA	NA	±0.230
<b>TOTAL SURFACE USE AREA</b>		<b>±6.304</b>

**NOTES:**

- Fill quantity includes 5% for compaction.
- Cut/Fill slopes 1 1/2:1 (Typ. except where noted)

**CIMAREX ENERGY CO.**


**RED HILLS UNIT 32 WEST BS #1 CTB**  
**1414' FNL 405' FWL (APPROX. CENTER OF PAD)**  
**W 1/2 NW 1/4, SECTION 32, T25S, R33E, N.M.P.M.**  
**LEA COUNTY, NEW MEXICO**

SURVEYED BY	J.J., C.H.	05-01-18	SCALE
DRAWN BY	R.J.	05-06-18	AS SHOWN

**TYPICAL CROSS SECTIONS EXHIBIT F**



**UELS, LLC**  
 Corporate Office \* 85 South 200 East  
 Vernal, UT 84078 \* (435) 789-1017



Existing Pipeline Gas  
(Southern Union Gas)

750' X 650'  
Archaeological Survey Boundary

Proposed Flow Line  
Connection Area

Topsail Stockpile

LINE TABLE		
LINE	DIRECTION	LENGTH
L1	N38°E	100'

Proposed Red Hills Unit 32-5 Access Road "A"

**NOTES:**

- Basis of Bearings is a Transverse Mercator Projection with a Central Meridian of W103°53'00"

**CIMAREX ENERGY CO.**

**RED HILLS UNIT 32 WEST BS #1 CTB**  
**1414' FNL 405' FWL (APPROX. CENTER OF PAD)**  
**W 1/2 NW 1/4, SECTION 32, T25S, R33E, N.M.P.M.**  
**LEA COUNTY, NEW MEXICO**

SURVEYED BY	J.J., C.H.	05-01-18	SCALE
DRAWN BY	R.J.	05-06-18	1" = 100'



**UELS, LLC**  
 Corporate Office \* 85 South 200 East  
 Vernal, UT 84078 \* (435) 789-1017

ARCHAEOLOGICAL SURVEY BOUNDARY **EXHIBIT F**

BEGINNING AT THE INTERSECTION J-1/ORLA ROAD AND AN EXISTING ROAD TO THE EAST (LOCATED AT NAD 83 LATITUDE N32.0650° AND LONGITUDE W103.6743°) PROCEED IN AN EASTERLY DIRECTION APPROXIMATELY 5.0 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE NORTHWEST; TURN LEFT AND PROCEED IN A NORTHWESTERLY, THEN NORTHEASTERLY DIRECTION APPROXIMATELY 2.4 MILES TO THE BEGINNING OF THE PROPOSED RED HILLS UNIT 32-5 ACCESS ROAD "A" TO THE WEST; FOLLOW ROAD FLAGS IN A WESTERLY, THEN SOUTHERLY, THEN WESTERLY DIRECTION APPROXIMATELY 6,882' TO THE PROPOSED LOCATION.

TOTAL DISTANCE FROM THE INTERSECTION OF J-1/ORLA ROAD AND AN EXISTING ROAD TO THE EAST (LOCATED AT NAD 83 LATITUDE N32.0650° AND LONGITUDE W103.6743°) TO THE PROPOSED WELL LOCATION IS APPROXIMATELY 8.7 MILES.


**CIMAREX ENERGY CO.**

**RED HILLS UNIT 32 WEST BS #1 CTB  
1414' FNL 405' FWL (APPROX. CENTER OF PAD)  
W 1/2 NW 1/4, SECTION 32, T25S, R33E, N.M.P.M.  
LEA COUNTY, NEW MEXICO**

<b>SURVEYED BY</b>	J.J., C.H.	05-01-18	
<b>DRAWN BY</b>	V.L.D.	05-14-18	
<b>ROAD DESCRIPTION</b>			<b>EXHIBIT F</b>



**UELS, LLC**  
Corporate Office \* 85 South 200 East  
Vernal, UT 84078 \* (435) 789-1017



JAL, NEW MEXICO IS 24.0 +/- MILES EASTERLY

**LEGEND:**



**PROPOSED LOCATION**




**UELS, LLC**  
 Corporate Office \* 85 South 200 East  
 Vernal, UT 84078 \* (435) 789-1017



**CIMAREX ENERGY CO.**


**RED HILLS UNIT 32 WEST BS #1 CTB**  
 1414' FNL 405' FWL (APPROX. CENTER OF PAD)  
 W 1/2 NW 1/4, SECTION 32, T25S, R33E, N.M.P.M.  
 LEA COUNTY, NEW MEXICO

SURVEYED BY	J.J., C.H.	05-01-18	SCALE
DRAWN BY	V.L.D.	05-14-18	1: 100,000
<b>PUBLIC ACCESS ROAD MAP EXHIBIT F</b>			





**FLOW LINE CONNECTION SURFACE USE AREA DESCRIPTION**

BEGINNING AT A POINT IN THE NW 1/4 NW 1/4 OF SECTION 32, T25S, R33E, N.M.P.M., WHICH BEARS S06°40'06"E 1146.13' FROM THE NORTHWEST CORNER OF SAID SECTION 32, THENCE N89°52'08"E 200.00'; THENCE S00°07'52"E 50.00'; THENCE S89°52'08"W 200.00'; THENCE N00°07'52"W 50.00' TO THE POINT OF BEGINNING. BASIS OF BEARING IS A TRANSVERSE MERCATOR PROJECTION WITH A CENTRAL MERIDIAN OF W103°53'00". CONTAINS 0.230 ACRES MORE OR LESS.



**CERTIFICATE**  
 THIS IS TO CERTIFY THAT THIS SURFACE USE AREA PLAT AND THE ACTUAL SURVEY ON THE GROUND UPON WHICH IT IS BASED WERE PERFORMED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM RESPONSIBLE FOR THIS SURVEY. THAT THIS SURVEY MEETS THE MINIMUM STANDARDS FOR SURVEYING IN NEW MEXICO AND THAT IT IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.



▲ = SECTION CORNERS LOCATED.

FILE: 63868-A1

Sheet 1 of 2

**NOTES:**  
 • Basis of Bearings is a Transverse Mercator Projection with a Central Meridian of W103°53'00"



**CIMAREX ENERGY CO.**


**RED HILLS UNIT 32 WEST BS #1 CTB  
 ON STATE OF NEW MEXICO LANDS IN  
 SECTION 32, T25S, R33E, N.M.P.M.  
 LEA COUNTY, NEW MEXICO**

SURVEYED BY	J.J. C.H.	05-01-18	SCALE
DRAWN BY	R.J.	05-16-18	1" = 1000'



**FLOW LINE CONNECTION SUA EXHIBIT F**



**UELS, LLC**  
 Corporate Office \* 85 South 200 East  
 Vernal, UT 84078 \* (435) 789-1017



**CERTIFICATE**  
 THIS MAP HAS BEEN PRODUCED ACCORDING TO PROCEDURES THAT HAVE BEEN DEMONSTRATED TO PRODUCE DATA THAT MEETS OR EXCEEDS THE MINIMUM STANDARDS FOR A TOPOGRAPHIC MAP COMPILED AT A SCALE OF 1" = 80' WITH A CONTOUR INTERVAL OF 2'



**FINISHED GRADE ELEVATION = 3405.1'**

- NOTES:**
- Contours shown at 2' intervals.
  - Cut/Fill slopes 1 1/2:1 (Typ. except where noted)
  - Topsoil stockpile to be seeded in place prior to reclamation.

**CIMAREX ENERGY CO.**

**RED HILLS UNIT 32 WEST WC #2 CTB**  
**1005' FNL 1357' FWL (APPROX. CENTER OF PAD)**  
**N 1/2 NW 1/4, SECTION 32, T25S, R33E, N.M.P.M.**  
**LEA COUNTY, NEW MEXICO**

<b>SURVEYED BY</b>	J.J., C.H.	05-01-18	<b>SCALE</b>
<b>DRAWN BY</b>	R.J.	05-06-18	1" = 80'



**LOCATION LAYOUT**

**EXHIBIT F**



**UELS, LLC**  
 Corporate Office \* 85 South 200 East  
 Vernal, UT 84078 \* (435) 789-1017

1" = 40'  
 X-Section Scale  
 1" = 100'



APPROXIMATE EARTHWORK QUANTITIES	
(4") TOPSOIL STRIPPING	3,110 Cu. Yds.
REMAINING LOCATION	4,520 Cu. Yds.
<b>TOTAL CUT</b>	<b>7,630 Cu. Yds.</b>
<b>FILL</b>	<b>4,520 Cu. Yds.</b>
EXCESS MATERIAL	3,110 Cu. Yds.
TOPSOIL	3,110 Cu. Yds.
<b>EXCESS UNBALANCE</b> (After Interim Rehabilitation)	<b>0 Cu. Yds.</b>

APPROXIMATE SURFACE DISTURBANCE AREAS		
	DISTANCE	ACRES
WELL SITE DISTURBANCE	NA	±6.061
PROPOSED FLOW LINE CONNECTION AREA	NA	±0.230
<b>TOTAL SURFACE USE AREA</b>		<b>±6.291</b>

- NOTES:**
- Fill quantity includes 5% for compaction.
  - Cut/Fill slopes 1 1/2:1 (Typ. except where noted)

**CIMAREX ENERGY CO.**


**RED HILLS UNIT 32 WEST WC #2 CTB**  
**1005' FNL 1357' FWL (APPROX. CENTER OF PAD)**  
**N 1/2 NW 1/4, SECTION 32, T25S, R33E, N.M.P.M.**  
**LEA COUNTY, NEW MEXICO**

SURVEYED BY	J.J., C.H.	05-01-18	SCALE
DRAWN BY	R.J.	05-06-18	AS SHOWN

**TYPICAL CROSS SECTIONS EXHIBIT F**



**UELS, LLC**  
 Corporate Office \* 85 South 200 East  
 Vernal, UT 84078 \* (435) 789-1017



750' X 650'  
Archaeological Survey Boundary

Proposed Flow Line  
Connection Area

Topsail Stockpile

Proposed Red Hills  
Unit 32-5 Access  
Road "D"

Proposed Red Hills  
Unit 32-5 Access  
Road "D"  
(Alternate Egress)

**NOTES:**

**CIMAREX ENERGY CO.**

**RED HILLS UNIT 32 WEST WC #2 CTB  
1005' FNL 1357' FWL (APPROX. CENTER OF PAD)  
N 1/2 NW 1/4, SECTION 32, T25S, R33E, N.M.P.M.  
LEA COUNTY, NEW MEXICO**

<b>SURVEYED BY</b>	J.J., C.H.	05-01-18	<b>SCALE</b>
<b>DRAWN BY</b>	R.J.	05-06-18	1" = 100'
<b>ARCHAEOLOGICAL SURVEY BOUNDARY</b>			<b>EXHIBIT F</b>



**UELS, LLC**  
Corporate Office \* 85 South 200 East  
Vernal, UT 84078 \* (435) 789-1017

BEGINNING AT THE INTERSECTION J-1/ORLA ROAD AND AN EXISTING ROAD TO THE EAST (LOCATED AT NAD 83 LATITUDE N32.0650° AND LONGITUDE W103.6743°) PROCEED IN AN EASTERLY DIRECTION APPROXIMATELY 5.0 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE NORTHWEST; TURN LEFT AND PROCEED IN A NORTHWESTERLY, THEN NORTHEASTERLY DIRECTION APPROXIMATELY 2.4 MILES TO THE BEGINNING OF THE PROPOSED RED HILLS UNIT 32-5 ACCESS ROAD "A" TO THE WEST; FOLLOW ROAD FLAGS IN A WESTERLY, THEN SOUTHERLY DIRECTION APPROXIMATELY 6,409' TO THE BEGINNING OF THE PROPOSED RED HILLS UNIT 32-5 ACCESS ROAD "D" TO THE EAST; TURN LEFT AND PROCEED 334' TO THE PROPOSED LOCATION.

TOTAL DISTANCE FROM THE INTERSECTION OF J-1/ORLA ROAD AND AN EXISTING ROAD TO THE EAST (LOCATED AT NAD 83 LATITUDE N32.0650° AND LONGITUDE W103.6743°) TO THE PROPOSED WELL LOCATION IS APPROXIMATELY 8.7 MILES.


**CIMAREX ENERGY CO.**

**RED HILLS UNIT 32 WEST WC #2 CTB  
1005' FNL 1357' FWL (APPROX. CENTER OF PAD)  
N 1/2 NW 1/4, SECTION 32, T25S, R33E, N.M.P.M.  
LEA COUNTY, NEW MEXICO**

<b>SURVEYED BY</b>	J.J., C.H.	05-01-18	
<b>DRAWN BY</b>	V.L.D.	05-14-18	
<b>ROAD DESCRIPTION</b>		<b>EXHIBIT F</b>	



**UELS, LLC**  
Corporate Office \* 85 South 200 East  
Vernal, UT 84078 \* (435) 789-1017



JAL, NEW MEXICO IS 23.8 +/- MILES EASTERLY

**LEGEND:**

**PROPOSED LOCATION**



**UELS, LLC**  
 Corporate Office \* 85 South 200 East  
 Vernal, UT 84078 \* (435) 789-1017




**CIMAREX ENERGY CO.**

**RED HILLS UNIT 32 WEST WC #2 CTB**  
 1005' FNL 1357' FWL (APPROX. CENTER OF PAD)  
 N 1/2 NW 1/4, SECTION 32, T25S, R33E, N.M.P.M.  
 LEA COUNTY, NEW MEXICO


<b>SURVEYED BY</b>	J.J., C.H.	05-01-18	<b>SCALE</b>
<b>DRAWN BY</b>	V.L.D.	05-14-18	1 : 100,000

**PUBLIC ACCESS ROAD MAP EXHIBIT F**





**FLOW LINE CONNECTION SURFACE USE AREA DESCRIPTION**

BEGINNING AT A POINT IN THE NW 1/4 NW 1/4 OF SECTION 32, T25S, R33E, N.M.P.M., WHICH BEARS S56°07'07"E 1305.97' FROM THE NORTHWEST CORNER OF SAID SECTION 32, THENCE N89°53'56"E 200.00'; THENCE S00°06'04"E 50.00'; THENCE S89°53'56"W 200.00'; THENCE N00°06'04"W 50.00' TO THE POINT OF BEGINNING. BASIS OF BEARING IS A TRANSVERSE MERCATOR PROJECTION WITH A CENTRAL MERIDIAN OF W103°53'00". CONTAINS 0.230 ACRES MORE OR LESS.



**CERTIFICATE**  
 THIS IS TO CERTIFY THAT THIS SURFACE USE AREA PLAT AND THE ACTING SURVEY ON THE GROUND UPON WHICH IT IS BASED WERE PERFORMED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM RESPONSIBLE FOR THIS SURVEY. THAT THIS SURVEY MEETS THE MINIMUM STANDARDS FOR SURVEYING IN NEW MEXICO AND THAT THIS IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.



▲ = SECTION CORNERS LOCATED.

FILE: 63864-A1

Sheet 1 of 2

**NOTES:**

\* Basis of Bearings is a Transverse Mercator Projection with a Central Meridian of W103°53'00"



**CIMAREX ENERGY CO.**


**RED HILLS UNIT 32 WEST WC #2 CTB  
 ON STATE OF NEW MEXICO LANDS IN  
 SECTION 32, T25S, R33E, N.M.P.M.  
 LEA COUNTY, NEW MEXICO**

SURVEYED BY	J.J. C.H.	05-01-18	SCALE
DRAWN BY	R.J.	05-16-18	1" = 1000'

**FLOW LINE CONNECTION SURFACE USE AREA EXHIBIT F**



**UELS, LLC**  
 Corporate Office \* 85 South 200 East  
 Vernal, UT 84078 \* (435) 789-1017



**Legend**

- Double M Water Sales - 28/24S/33E
- Red Hills Unit

Drilling Route #1  
Red Hills Unit  
Citarex Energy Co.  
Sec. 32-25S-83E  
Lea, NM

Turn right onto NM-128 E  
Turn right onto Diamond Rd/J-2  
Turn right onto J-1/Ora Rd  
Sign left  
Head northwest on County Rd 1-B

Red Hills Unit

Google Earth

©2018 Google

7 mi





**Legend**

-  Lindsey FW Station 10 Blk 55 T1 T&P RR Co
-  Red Hills Unit

Turn left onto J-1/Ora Rd

Slight Left

Red Hills Unit  
Head northwest on County Rd 1-B

Drilling Route #2  
Red Hills Unit  
Cimarex Energy Co.  
Sec. 32-25S-33E  
Lea, NM

Continue onto RM 652 W


Lindsey FW Station 10 Blk 55 T1 T&P RR Co

Google Earth

© 2018 Google

8 mi





**CERTIFICATE**  
 THIS MAP HAS BEEN PRODUCED ACCORDING TO PROCEDURES THAT HAVE BEEN DEMONSTRATED TO PRODUCE DATA THAT MEETS OR EXCEEDS THE MINIMUM STANDARDS FOR A TOPOGRAPHIC MAP COMPILED AT A SCALE OF 1" = 80' WITH A CONTOUR INTERVAL OF 2'



**NOTE:** Earthwork Calculations Require a Fill @ some Location Stakes For Balance. All Fill is to be Compacted to a Minimum of 95% of the Maximum Dry Density Obtained by AASHTO Method t-99.

**FINISHED GRADE ELEVATION = 3396.8'**

- NOTES:**
- Flare pit is to be located a min. of 100' from the wellhead.
  - Contours shown at 2' intervals.
  - Cut/Fill slopes 1 1/2:1 (Typ. except where noted)
  - Basis of Bearings is a Transverse Mercator Projection with a Central Meridian of W103°53'00"

**CIMAREX ENERGY CO.**


**RED HILLS UNIT 32-5 W2W2 PAD #1**  
 NW 1/4 NW 1/4, SECTION 32, T25S, R33E, N.M.P.M.  
 LEA COUNTY, NEW MEXICO




**UELS, LLC**  
 Corporate Office \* 85 South 200 East  
 Vernal, UT 84078 \* (435) 789-1017

<b>SURVEYED BY</b>	J.J., C.H.	05-01-18	<b>SCALE</b>
<b>DRAWN BY</b>	R.J.	05-09-18	1" = 80'
<b>LOCATION LAYOUT</b>		<b>EXHIBIT J</b>	

1" = 40'  
X-Section Scale  
1" = 100'




STA. 5+60




STA. 3+70

Slope = 1 1/2:1 (Typ.)



STA. 3+10



STA. 1+90



STA. 0+00

APPROXIMATE EARTHWORK QUANTITIES	
(4") TOPSOIL STRIPPING	3,520 Cu. Yds.
REMAINING LOCATION	5,180 Cu. Yds.
<b>TOTAL CUT</b>	<b>8,700 Cu. Yds.</b>
<b>FILL</b>	<b>5,180 Cu. Yds.</b>
EXCESS MATERIAL	3,520 Cu. Yds.
TOPSOIL	3,520 Cu. Yds.
<b>EXCESS UNBALANCE</b> (After Interim Rehabilitation)	<b>0 Cu. Yds.</b>

APPROXIMATE SURFACE DISTURBANCE AREAS		
	DISTANCE	ACRES
WELL SITE DISTURBANCE	NA	±6.907

**NOTES:**

- Fill quantity includes 5% for compaction.
- Cut/Fill slopes 1 1/2:1 (Typ. except where noted)

**CIMAREX ENERGY CO.**


**RED HILLS UNIT 32-5 W2W2 PAD #1**  
NW 1/4 NW 1/4, SECTION 32, T25S, R33E, N.M.P.M.  
LEA COUNTY, NEW MEXICO




**UELS, LLC**  
Corporate Office \* 85 South 200 East  
Vernal, UT 84078 \* (435) 789-1017

SURVEYED BY	J.J. C.H.	05-01-18	SCALE
DRAWN BY	R.J.	05-09-18	AS SHOWN

**TYPICAL CROSS SECTIONS EXHIBIT J**



**CERTIFICATE**  
 THIS MAP HAS BEEN PRODUCED ACCORDING TO PROCEDURES THAT HAVE BEEN DEMONSTRATED TO PRODUCE DATA THAT MEETS OR EXCEEDS THE MINIMUM STANDARDS FOR A TOPOGRAPHIC MAP COMPILED AT A SCALE OF 1" = 80' WITH A CONTOUR INTERVAL OF 2'



**NOTES:**  
 • Contours shown at 2' intervals.

**CIMAREX ENERGY CO.**

**RED HILLS UNIT 131H**  
**330' FNL 410' FWL**  
 NW 1/4 NW 1/4, SECTION 32, T25S, R33E, N.M.P.M.  
 LEA COUNTY, NEW MEXICO

SURVEYED BY	J.J., C.H.	05-01-18	SCALE
DRAWN BY	R.J.	05-09-18	1" = 80'

**TYPICAL RIG LAYOUT EXHIBIT K**



**UELS, LLC**  
 Corporate Office \* 85 South 200 East  
 Vernal, UT 84078 \* (435) 789-1017


700' X 760'  
Archaeological Survey Boundary

Proposed Red Hills  
Unit 32-5 Access  
Road "C"

Section 29

Section Line

Section 32



Topsoil Stockpile

140H  
139H  
138H  
137H

133H  
132H  
131H  
130H

136H  
135H  
134H

129H  
128H  
127H

LINE TABLE		
LINE	DIRECTION	LENGTH
L1	S39°W	371'

Proposed Red Hills 32-5 Access Road "A"

Existing Buried Pipeline  
(Southern Union)

**NOTES:**

• Basis of Bearings is a Transverse Mercator Projection with a Central Meridian of W103°53'00"


**CIMAREX ENERGY CO.**

**RED HILLS UNIT 32-5 W2W2 PAD #1  
NW 1/4 NW 1/4, SECTION 32, T25S, R33E, N.M.P.M.  
LEA COUNTY, NEW MEXICO**

SURVEYED BY	J.J., C.H.	05-01-18	SCALE
DRAWN BY	R.J.	05-09-18	1" = 100'
ARCHAEOLOGICAL SURVEY BOUNDARY			<b>EXHIBIT L</b>




**UELS, LLC**  
Corporate Office \* 85 South 200 East  
Vernal, UT 84078 \* (435) 789-1017



Access Road

Pad will be reclaimed after cessation of drilling operations.  
Please see Surface Use Plan for pad reclamation plans.



**Exhibit P**  
**Interim Reclamation Diagram**  
 Red Hills Unit 32-5 W2W2 Pad  
 Cimarex Energy Co.  
 Sec 32-25S-33E  
 Lea Cty, NM

## Operator - Land Owner Agreement

Company: Cimarex Energy Co.

Proposed Well: Red Hills Unit 131H

Federal Lease Number: NMNM0106040A


Please be advised that Cimarex Energy Co. has an agreement with the surface owner, listed below, concerning entry and surface restoration after completion of drilling operations at the above described well.


**Tommy Dinwiddie (Dinwiddie Cattle Co)**  
**PO Box 963**  
**Capitan, NM 88316**  
**(575) 355-7610**

After abandonment of the well, all pits will be filled and levelled and all equipment and trash will be removed from the well site. No other requirements were made concerning restoration of the well site.

5/23/2018

Date

  
Signature Aricka Easterling



JAL, NEW MEXICO IS 24.0 +/- MILES EASTERLY

**LEGEND:**

 PROPOSED LOCATION



**UELS, LLC**  
 Corporate Office \* 85 South 200 East  
 Vernal, UT 84078 \* (435) 789-1017



**CIMAREX ENERGY CO.**

**RED HILLS UNIT 32-5 W2W2 PAD #1**  
 NW 1/4 NW 1/4, SECTION 32, T25S, R33E, N.M.P.M.  
 LEA COUNTY, NEW MEXICO

<b>SURVEYED BY</b>	A.H., F.R.	05-01-18	<b>SCALE</b>
<b>DRAWN BY</b>	V.L.D.	05-07-18	1 : 100,000
<b>PUBLIC ACCESS ROAD MAP EXHIBIT B</b>			

BEGINNING AT THE INTERSECTION J-1/ORLA ROAD AND AN EXISTING ROAD TO THE EAST (LOCATED AT NAD 83 LATITUDE N32.0650° AND LONGITUDE W103.6743°) PROCEED IN AN EASTERLY DIRECTION APPROXIMATELY 5.0 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE NORTHWEST; TURN LEFT AND PROCEED IN A NORTHWESTERLY, THEN NORTHEASTERLY DIRECTION APPROXIMATELY 2.4 MILES TO THE BEGINNING OF THE PROPOSED RED HILLS UNIT 32-5 ACCESS ROAD "A" TO THE WEST; FOLLOW ROAD FLAGS IN A WESTERLY DIRECTION APPROXIMATELY 5,214' TO THE BEGINNING OF THE PROPOSED RED HILLS UNIT 32-5 ACCESS ROAD "C" TO THE SOUTHWEST; FOLLOW ROAD FLAGS IN A SOUTHWESTERLY DIRECTION APPROXIMATELY 67' TO THE PROPOSED LOCATION.

TOTAL DISTANCE FROM THE INTERSECTION OF J-1/ORLA ROAD AND AN EXISTING ROAD TO THE EAST (LOCATED AT NAD 83 LATITUDE N32.0650° AND LONGITUDE W103.6743°) TO THE PROPOSED WELL LOCATION IS APPROXIMATELY 8.4 MILES.


**CIMAREX ENERGY CO.**

**RED HILLS UNIT 32-5 W2W2 PAD #1  
NW 1/4 NW 1/4, SECTION 32, T25S, R33E, N.M.P.M.  
LEA COUNTY, NEW MEXICO**

<b>SURVEYED BY</b>	<b>A.H., F.R.</b>	<b>05-01-18</b>	
<b>DRAWN BY</b>	<b>V.L.D.</b>	<b>05-07-18</b>	
<b>ROAD DESCRIPTION</b>		<b>EXHIBIT A</b>	



**UELS, LLC**  
Corporate Office \* 85 South 200 East  
Vernal, UT 84078 \* (435) 789-1017



BEGINNING OF FLOW LINE BEARS S55°13'29"W 838.69' FROM THE NORTHEAST CORNER OF SECTION 32, T25S, R33E, N.M.P.M.

END OF FLOW LINE BEARS S11°34'27"E 1161.77' FROM THE NORTHWEST CORNER OF SECTION 32, T25S, R33E, N.M.P.M.

BEGINNING OF FLOW LINE LATERAL "A" BEARS S72°10'04"E 1300.02' FROM THE NORTH 1/4 CORNER OF SECTION 32, T25S, R33E, N.M.P.M.

END OF FLOW LINE LATERAL "A" BEARS S69°28'16"E 1136.01' FROM THE NORTH 1/4 CORNER OF SECTION 32, T25S, R33E, N.M.P.M.

BEGINNING OF FLOW LINE LATERAL "B" BEARS S33°23'25"E 693.96' FROM THE NORTH 1/4 CORNER OF SECTION 32, T25S, R33E, N.M.P.M.

END OF FLOW LINE LATERAL "B" BEARS S31°39'27"E 727.81' FROM THE NORTH 1/4 CORNER OF SECTION 32, T25S, R33E, N.M.P.M.

BEGINNING OF FLOW LINE LATERAL "C" BEARS S16°56'46"E 648.02' FROM THE NORTH 1/4 CORNER OF SECTION 32, T25S, R33E, N.M.P.M.

END OF FLOW LINE LATERAL "C" BEARS S14°30'59"E 754.32' FROM THE NORTH 1/4 CORNER OF SECTION 32, T25S, R33E, N.M.P.M.

BEGINNING OF FLOW LINE LATERAL "D" BEARS S25°32'02"W 643.40' FROM THE NORTH 1/4 CORNER OF SECTION 32, T25S, R33E, N.M.P.M.

END OF FLOW LINE LATERAL "D" BEARS S24°04'02"W 679.88' FROM THE NORTH 1/4 CORNER OF SECTION 32, T25S, R33E, N.M.P.M.

BEGINNING OF FLOW LINE LATERAL "E" BEARS S41°03'16"W 823.90' FROM THE NORTH 1/4 CORNER OF SECTION 32, T25S, R33E, N.M.P.M.

END OF FLOW LINE LATERAL "E" BEARS S36°28'51"W 909.80' FROM THE NORTH 1/4 CORNER OF SECTION 32, T25S, R33E, N.M.P.M.

BEGINNING OF FLOW LINE LATERAL "F" BEARS S63°56'42"E 1315.12' FROM THE NORTHWEST CORNER OF SECTION 32, T25S, R33E, N.M.P.M.

END OF FLOW LINE LATERAL "F" ALSO BEGINNING OF FLOW LINE LATERAL "G" BEARS S62°23'47"E 1333.30' FROM THE NORTHWEST CORNER OF SECTION 32, T25S, R33E, N.M.P.M.

END OF FLOW LINE LATERAL "G" BEARS S58°22'10"E 1387.91' FROM THE NORTHWEST CORNER OF SECTION 32, T25S, R33E, N.M.P.M.

BEGINNING OF FLOW LINE LATERAL "H" BEARS S40°19'24"E 759.47' FROM THE NORTHWEST CORNER OF SECTION 32, T25S, R33E, N.M.P.M.

END OF FLOW LINE LATERAL "H" BEARS S38°26'51"E 790.52' FROM THE NORTHWEST CORNER OF SECTION 32, T25S, R33E, N.M.P.M.

**CERTIFICATE**  
 THIS IS TO CERTIFY THAT THIS EASEMENT PLAT AND THE ACTUAL SURVEYED GROUND UPON WHICH IT IS BASED WERE PERFORMED BY ME OR UNDER MY DIRECT SUPERVISION, THAT I AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY MEETS THE MINIMUM STANDARDS FOR SURVEYING IN NEW MEXICO, AND THAT IT IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.



▲ = SECTION CORNERS LOCATED.

FILE: 63848-A1

Sheet 1 of 8

**NOTES:**  
 \* Basis of Bearings is a Transverse Mercator Projection with a Central Meridian of W103°53'00"

**CIMAREX ENERGY CO.**


**RED HILLS UNIT 32-5 FLOW LINE NETWORK  
 ON STATE OF NEW MEXICO LANDS  
 SECTION 32, T25S, R33E, N.M.P.M.  
 LEA COUNTY, NEW MEXICO**

SURVEYED BY	A.H. F.R.	05-01-18	SCALE
DRAWN BY	J.P.P.	05-17-18	1" = 1000'

**FLOW LINE & GAS LIFT ROW EXHIBIT M&N**



**UELS, LLC**  
 Corporate Office \* 85 South 200 East  
 Vernal, UT 84078 \* (435) 789-1017



FILE: 63848-A2

Sheet 2 of 8

**CIMAREX ENERGY CO.**

**RED HILLS UNIT 32-5 FLOW LINE NETWORK  
ON STATE OF NEW MEXICO LANDS  
SECTION 32, T25S, R33E, N.M.P.M.  
LEA COUNTY, NEW MEXICO**


SURVEYED BY	A.H., F.R.	05-01-18	SCALE
DRAWN BY	J.P.P.	05-17-18	N/A

**FLOW LINE & GAS LIFT ROW EXHIBIT M&N**



**UELS, LLC**  
Corporate Office \* 85 South 200 East  
Vernal, UT 84078 \* (435) 789-1017


BEGINNING OF PROPOSED  
FLOW LINE LATERAL "F"  
RIGHT-OF-WAY  
(At Edge Of Proposed Red  
Hills Unit 32-5 W2W2 Pad #2)



END OF PROPOSED FLOW  
LINE LATERAL "F"  
RIGHT-OF-WAY ALSO  
BEGINNING OF PROPOSED  
FLOW LINE LATERAL "G"  
RIGHT-OF-WAY  
(At Proposed Red Hills  
Unit 32-5 Flow Line)

END OF PROPOSED FLOW  
LINE LATERAL "G"  
RIGHT-OF-WAY  
(At Edge Of Proposed Red  
Hills Unit 32 West WC #2 CTB  
Flow Line Connection Area)

Detail "F"  
No Scale



BEGINNING OF PROPOSED  
FLOW LINE LATERAL "H"  
RIGHT-OF-WAY  
(At Edge of Proposed Red Hills  
Unit 32-5 W2W2 Pad #1)


END OF PROPOSED FLOW  
LINE LATERAL "G"  
RIGHT-OF-WAY  
(At Proposed Red Hills  
Unit 32-5 Flow Line)

Detail "F"  
No Scale

LINE TABLE		
LINE	DIRECTION	LENGTH
L1	S89°54'44"W	40.00'
L2	S00°05'16"E	130.59'
L3	S89°54'44"W	669.25'
L4	N47°42'53"W	248.47'
L5	N00°05'16"W	40.44'
L6	S89°54'44"W	442.18'
L7	S00°06'04"E	220.00'
L8	S89°53'23"W	240.08'
L9	S89°53'23"W	193.10'
L10	S89°53'23"W	466.14'
L11	S89°53'23"W	263.86'
L12	S89°53'23"W	921.11'

LINE TABLE		
LINE	DIRECTION	LENGTH
L13	S89°53'23"W	690.00'
L14	S89°53'23"W	259.64'
L15	S00°07'52"E	518.53'
L16	S89°54'44"W	173.70'
L17	S00°06'04"E	40.10'
L18	S00°06'04"E	110.36'
L19	S00°06'04"E	40.23'
L20	S00°06'04"E	110.24'
L21	S00°06'04"E	40.14'
L22	S00°06'04"E	110.09'
L23	S00°07'52"E	40.09'

CERTIFICATE  
THIS IS TO CERTIFY THAT THIS EASEMENT PLAT AND  
THE ACTUAL SURVEY ON THE GROUND UPON WHICH IT  
IS BASED WERE PERFORMED BY ME OR UNDER MY  
DIRECT SUPERVISION, THAT I AM RESPONSIBLE FOR  
THIS SURVEY, THAT THIS SURVEY MEETS THE  
MINIMUM STANDARDS FOR SURVEYING IN NEW  
MEXICO, AND THAT IT IS TRUE AND CORRECT TO THE  
BEST OF MY KNOWLEDGE AND BELIEF.



FILE: 63848-A3

Sheet 3 of 8

NOTES:  
\* Basis of Bearings is a Transverse Mercator Projection with a Central Meridian of W103°53'00"

**CIMAREX ENERGY CO.**  
RED HILLS UNIT 32-5 FLOW LINE NETWORK  
ON STATE OF NEW MEXICO LANDS  
SECTION 32, T25S, R33E, N.M.P.M.  
LEA COUNTY, NEW MEXICO

SURVEYED BY	A.H., F.R.	05-01-18	SCALE
DRAWN BY	J.P.P.	05-17-18	N/A
FLOW LINE & GAS LIFT ROW EXHIBIT M&N			



**UELS, LLC**  
Corporate Office \* 85 South 200 East  
Vernal, UT 84078 \* (435) 789-1017

<b>ACREAGE / LENGTH TABLE</b>				
	OWNERSHIP	FEET	RODS	ACRES
SEC. 32 (NE 1/4 NE 1/4)	STATE OF NEW MEXICO	763.16	46.25	1.051
SEC. 32 (NW 1/4 NE 1/4)	STATE OF NEW MEXICO	1648.15	99.89	2.270
SEC. 32 (NE 1/4 NW 1/4)	STATE OF NEW MEXICO	1321.89	80.11	1.821
SEC. 32 (NW 1/4 NW 1/4)	STATE OF NEW MEXICO	1610.20	97.59	2.218
TOTAL		5343.40	323.84	7.360

<b>ACREAGE / LENGTH TABLE LATERAL "A"</b>				
	OWNERSHIP	FEET	RODS	ACRES
SEC. 32 (NW 1/4 NE 1/4)	STATE OF NEW MEXICO	173.70	10.53	0.239

<b>ACREAGE / LENGTH TABLE LATERAL "B"</b>				
	OWNERSHIP	FEET	RODS	ACRES
SEC. 32 (NW 1/4 NE 1/4)	STATE OF NEW MEXICO	40.10	2.43	0.055

<b>ACREAGE / LENGTH TABLE LATERAL "C"</b>				
	OWNERSHIP	FEET	RODS	ACRES
SEC. 32 (NW 1/4 NE 1/4)	STATE OF NEW MEXICO	110.36	6.69	0.152

<b>ACREAGE / LENGTH TABLE LATERAL "D"</b>				
	OWNERSHIP	FEET	RODS	ACRES
SEC. 32 (NE 1/4 NW 1/4)	STATE OF NEW MEXICO	40.23	2.44	0.055


<b>ACREAGE / LENGTH TABLE LATERAL "E"</b>				
	OWNERSHIP	FEET	RODS	ACRES
SEC. 32 (NE 1/4 NW 1/4)	STATE OF NEW MEXICO	110.24	6.68	0.152

<b>ACREAGE / LENGTH TABLE LATERAL "F"</b>				
	OWNERSHIP	FEET	RODS	ACRES
SEC. 32 (NW 1/4 NW 1/4)	STATE OF NEW MEXICO	40.14	2.43	0.055

<b>ACREAGE / LENGTH TABLE LATERAL "G"</b>				
	OWNERSHIP	FEET	RODS	ACRES
SEC. 32 (NW 1/4 NW 1/4)	STATE OF NEW MEXICO	110.09	6.67	0.152

<b>ACREAGE / LENGTH TABLE LATERAL "H"</b>				
	OWNERSHIP	FEET	RODS	ACRES
SEC. 32 (NW 1/4 NW 1/4)	STATE OF NEW MEXICO	40.09	2.43	0.055

**CERTIFICATE**  
 THIS IS TO CERTIFY THAT THIS EASEMENT PLAT AND THE ACTUAL SURVEY ON THE GROUND UPON WHICH IT IS BASED WERE PERFORMED BY ME OR UNDER MY DIRECT SUPERVISION THAT I AM RESPONSIBLE FOR THIS SURVEY. THAT THIS SURVEY MEETS THE MINIMUM STANDARDS FOR SURVEYING IN NEW MEXICO AND THAT IT IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.



FILE: 63848-A4

Sheet 4 of 8

**NOTES:**

\* Basis of Bearings is a Transverse Mercator Projection with a Central Meridian of W103°53'00"

**CIMAREX ENERGY CO.**


**RED HILLS UNIT 32-5 FLOW LINE NETWORK  
 ON STATE OF NEW MEXICO LANDS  
 SECTION 32, T25S, R33E, N.M.P.M.  
 LEA COUNTY, NEW MEXICO**


SURVEYED BY	A.H., F.R.	05-01-18	SCALE
DRAWN BY	J.P.P.	05-17-18	N/A

**FLOW LINE & GAS LIFT ROW - EXHIBIT M&N**



**UELS, LLC**  
 Corporate Office \* 85 South 200 East  
 Vernal, UT 84078 \* (435) 789-1017





BEGINNING OF OIL PIPELINE BEARS N31°06'36"E 1309.85' FROM THE WEST 1/4 CORNER OF SECTION 32, T25S, R33E, N.M.P.M.

END OF OIL PIPELINE ON STATE OF NEW MEXICO LANDS BEARS N00°08'32"W 70.92' FROM THE EAST 1/4 CORNER OF SECTION 32, T25S, R33E, N.M.P.M.

BEGINNING OF OIL PIPELINE LATERAL "A" BEARS S29°58'30"E 1280.45' FROM THE NORTH 1/4 CORNER OF SECTION 32, T25S, R33E, N.M.P.M.

END OF OIL PIPELINE LATERAL "A" BEARS N42°15'32"E 1763.29' FROM THE WEST 1/4 CORNER OF SECTION 32, T25S, R33E, N.M.P.M.

BEGINNING OF OIL PIPELINE LATERAL "B" BEARS S04°38'48"W 1114.13' FROM THE NORTH 1/4 CORNER OF SECTION 32, T25S, R33E, N.M.P.M.


END OF OIL PIPELINE LATERAL "B" BEARS S03°01'02"W 1327.54' FROM THE NORTH 1/4 CORNER OF SECTION 32, T25S, R33E, N.M.P.M.

BEGINNING OF OIL PIPELINE LATERAL "C" BEARS S42°12'52"W 1501.54' FROM THE NORTH 1/4 CORNER OF SECTION 32, T25S, R33E, N.M.P.M.

END OF OIL PIPELINE LATERAL "C" BEARS S36°40'36"W 1654.97' FROM THE NORTH 1/4 CORNER OF SECTION 32, T25S, R33E, N.M.P.M.

LINE TABLE		
LINE	DIRECTION	LENGTH
L1	N89°52'08"E	362.39'
L2	N38°44'28"E	234.28'
L3	S51°15'24"E	3787.56'
L4	N38°45'21"E	269.01'
L5	S51°12'37"E	179.78'
L6	N38°44'59"E	1286.87'
L7	N39°14'36"E	54.94'
L8	N89°53'58"E	20.00'
L10	S00°06'04"E	215.26'
L11	S89°53'56"W	730.00'
L12	S89°53'56"W	918.64'
L13	S89°53'56"W	453.91'
L14	S38°44'28"W	13.39'
L15	N89°53'56"E	20.00'
L16	S00°06'04"E	215.26'
L17	N89°53'58"E	20.00'
L18	S00°06'04"E	215.26'

CERTIFICATE  
 THIS IS TO CERTIFY THAT THIS EASEMENT PLAT AND THE ACTUAL SURVEY ON THE GROUND UPON WHICH IT IS BASED WERE PERFORMED BY ME OR UNDER MY DIRECT SUPERVISION, THAT I AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY MEETS THE MINIMUM STANDARDS FOR SURVEYING IN NEW MEXICO, AND THAT IT IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.



▲ = SECTION CORNERS LOCATED.

FILE: 63852-A1

Sheet 1 of 4

NOTES:  
 • Basis of Bearings is a Transverse Mercator Projection with a Central Meridian of W103°53'00"




UELS, LLC  
 Corporate Office \* 85 South 200 East  
 Vernal, UT 84078 \* (435) 789-1017



CIMAREX ENERGY CO.  
 RED HILLS UNIT 32-5 OIL PIPELINE NETWORK  
 ON STATE OF NEW MEXICO LANDS  
 SECTION 32, T25S, R33E, N.M.P.M.  
 LEA COUNTY, NEW MEXICO


SURVEYED BY	A.H., F.R.	05-01-18	SCALE
DRAWN BY	J.P.P.	05-17-18	1" = 1000'

OIL PIPELINE R-O-W EXHIBIT Q




**Detail "A"**  
No Scale

**BEGINNING OF PROPOSED OIL PIPELINE LATERAL "A" RIGHT-OF-WAY**  
(At Edge of Proposed Red Hills Unit 32 West WC #4 CTB)



**Detail "B"**  
No Scale


**BEGINNING OF PROPOSED OIL PIPELINE LATERAL "B" RIGHT-OF-WAY**  
(At Edge of Proposed Red Hills Unit 32 East BS #3 CTB)



**Detail "C"**  
No Scale


**BEGINNING OF PROPOSED OIL PIPELINE LATERAL "C" RIGHT-OF-WAY**  
(At Edge of Proposed Red Hills Unit 32 West WC #2 CTB)

**END OF PROPOSED OIL PIPELINE LATERAL "B" RIGHT-OF-WAY**  
(At Proposed Red Hills Unit 32-5 Oil Pipeline Lateral "A")




**Detail "D"**  
No Scale

**END OF PROPOSED OIL PIPELINE LATERAL "C" RIGHT-OF-WAY**  
(At Proposed Red Hills Unit 32-5 Oil Pipeline Lateral "A")



**Detail "E"**  
No Scale



**Detail "F"**  
No Scale

**CERTIFICATE**  
THIS IS TO CERTIFY THAT THIS EASEMENT PLAT AND THE ACTUAL SURVEY ON THE GROUND UPON WHICH IT IS BASED WERE PERFORMED BY ME OR UNDER MY DIRECT SUPERVISION, THAT I AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY MEETS THE MINIMUM STANDARDS FOR SURVEYING IN NEW MEXICO, AND THAT IT IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.



FILE: 63852-A2

Sheet 2 of 4

**CIMAREX ENERGY CO.**

**RED HILLS UNIT 32-5 OIL PIPELINE NETWORK ON STATE OF NEW MEXICO LANDS SECTION 32, T25S, R33E, N.M.P.M. LEA COUNTY, NEW MEXICO**

SURVEYED BY	A.H., F.R.	05-01-18	SCALE
DRAWN BY	J.P.P.	05-17-18	N/A
<b>OIL PIPELINE R-O-W</b>			<b>EXHIBIT Q</b>



**UELS, LLC**  
Corporate Office \* 85 South 200 East  
Vernal, UT 84078 \* (435) 789-1017

**OIL PIPELINE RIGHT-OF-WAY DESCRIPTION ON STATE OF NEW MEXICO LANDS**

A 30' WIDE RIGHT-OF-WAY 15' ON EACH SIDE OF THE FOLLOWING DESCRIBED CENTERLINE.

BEGINNING AT A POINT IN THE SW 1/4 NW 1/4 OF SECTION 32, T25S, R33E, N.M.P.M., WHICH BEARS N31°06'36"E 1309.85' FROM THE WEST 1/4 CORNER OF SAID SECTION 32, THENCE N89°52'08"E 362.39'; THENCE N38°44'28"E 234.28'; THENCE S51°15'24"E 3787.56'; THENCE N38°45'21"E 269.01'; THENCE S51°12'37"E 179.76'; THENCE N38°44'59"E 1286.87'; THENCE N39°14'36"E 54.94' TO A POINT ON THE EAST LINE OF THE SE 1/4 NE 1/4 OF SAID SECTION 32, WHICH BEARS N00°08'32"W 70.92' FROM THE EAST 1/4 CORNER OF SAID SECTION 32. THE SIDE LINES OF SAID DESCRIBED RIGHT-OF-WAY BEING SHORTENED OR ELONGATED TO MEET THE GRANTOR'S PROPERTY LINES. BASIS OF BEARINGS IS A TRANSVERSE MERCATOR PROJECTION WITH A CENTRAL MERIDIAN OF W103°53'00". CONTAINS 4.253 ACRES MORE OR LESS.

**OIL PIPELINE LATERAL "A" RIGHT-OF-WAY DESCRIPTION**

A 30' WIDE RIGHT-OF-WAY 15' ON EACH SIDE OF THE FOLLOWING DESCRIBED CENTERLINE.

BEGINNING AT A POINT IN THE NW 1/4 NE 1/4 OF SECTION 32, T25S, R33E, N.M.P.M., WHICH BEARS S29°58'30"E 1280.45' FROM THE NORTH 1/4 CORNER OF SAID SECTION 32, THENCE N89°53'56"E 20.00'; THENCE S00°06'04"E 215.26'; THENCE S89°53'56"W 730.00'; THENCE CONTINUING S89°53'56"W 918.64'; THENCE CONTINUING S89°53'56"W 453.91'; THENCE S38°44'28"W 13.39' TO A POINT IN THE SW 1/4 NW 1/4 OF SAID SECTION 32, WHICH BEARS N42°15'32"E 1763.29' FROM THE WEST 1/4 CORNER OF SAID SECTION 32. THE SIDE LINES OF SAID DESCRIBED RIGHT-OF-WAY BEING SHORTENED OR ELONGATED TO MEET THE GRANTOR'S PROPERTY LINES. BASIS OF BEARINGS IS A TRANSVERSE MERCATOR PROJECTION WITH A CENTRAL MERIDIAN OF W103°53'00". CONTAINS 1.619 ACRES MORE OR LESS.

**OIL PIPELINE LATERAL "B" RIGHT-OF-WAY DESCRIPTION**

A 30' WIDE RIGHT-OF-WAY 15' ON EACH SIDE OF THE FOLLOWING DESCRIBED CENTERLINE.

BEGINNING AT A POINT IN THE NE 1/4 NW 1/4 OF SECTION 32, T25S, R33E, N.M.P.M., WHICH BEARS S04°38'48"W 1114.13' FROM THE NORTH 1/4 CORNER OF SAID SECTION 32, THENCE N89°53'56"E 20.00'; THENCE S00°06'04"E 215.26' TO A POINT IN THE SE 1/4 NW 1/4 OF SAID SECTION 32, WHICH BEARS S03°01'02"W 1327.54' FROM THE NORTH 1/4 CORNER OF SAID SECTION 32. THE SIDE LINES OF SAID DESCRIBED RIGHT-OF-WAY BEING SHORTENED OR ELONGATED TO MEET THE GRANTOR'S PROPERTY LINES. BASIS OF BEARINGS IS A TRANSVERSE MERCATOR PROJECTION WITH A CENTRAL MERIDIAN OF W103°53'00". CONTAINS 0.162 ACRES MORE OR LESS.

**OIL PIPELINE LATERAL "C" RIGHT-OF-WAY DESCRIPTION**

A 30' WIDE RIGHT-OF-WAY 15' ON EACH SIDE OF THE FOLLOWING DESCRIBED CENTERLINE.

BEGINNING AT A POINT IN THE NE 1/4 NW 1/4 OF SECTION 32, T25S, R33E, N.M.P.M., WHICH BEARS S42°12'52"W 1501.54' FROM THE NORTH 1/4 CORNER OF SAID SECTION 32, THENCE N89°53'56"E 20.00'; THENCE S00°06'04"E 215.26' TO A POINT IN THE SE 1/4 NW 1/4 OF SAID SECTION 32, WHICH BEARS S36°40'36"W 1654.97' FROM THE NORTH 1/4 CORNER OF SAID SECTION 32. THE SIDE LINES OF SAID DESCRIBED RIGHT-OF-WAY BEING SHORTENED OR ELONGATED TO MEET THE GRANTOR'S PROPERTY LINES. BASIS OF BEARINGS IS A TRANSVERSE MERCATOR PROJECTION WITH A CENTRAL MERIDIAN OF W103°53'00". CONTAINS 0.162 ACRES MORE OR LESS.


<b>ACREAGE / LENGTH TABLE</b>				
	OWNERSHIP	FEET	RODS	ACRES
SEC. 32 (SW 1/4 NW 1/4)	STATE OF NEW MEXICO	767.00	46.48	0.528
SEC. 32 (SE 1/4 NW 1/4)	STATE OF NEW MEXICO	1698.54	102.94	1.170
SEC. 32 (SW 1/4 NE 1/4)	STATE OF NEW MEXICO	210.42	12.75	0.145
SEC. 32 (NW 1/4 SE 1/4)	STATE OF NEW MEXICO	1488.74	90.23	1.025
SEC. 32 (NE 1/4 SE 1/4)	STATE OF NEW MEXICO	1918.69	116.28	1.321
SEC. 32 (SE 1/4 NE 1/4)	STATE OF NEW MEXICO	91.41	5.54	0.063
TOTAL		6174.80	374.23	4.253

<b>ACREAGE / LENGTH TABLE LATERAL "A"</b>				
	OWNERSHIP	FEET	RODS	ACRES
SEC. 32 (NW 1/4 NE 1/4)	STATE OF NEW MEXICO	229.95	13.94	0.158
SEC. 32 (SW 1/4 NE 1/4)	STATE OF NEW MEXICO	661.83	40.11	0.456
SEC. 32 (SE 1/4 NW 1/4)	STATE OF NEW MEXICO	1321.89	80.11	0.910
SEC.32 (SW 1/4 NW 1/4)	STATE OF NEW MEXICO	137.54	8.34	0.095
TOTAL		2351.21	142.50	1.619

<b>ACREAGE / LENGTH TABLE LATERAL "B"</b>				
	OWNERSHIP	FEET	RODS	ACRES
SEC. 32 (NE 1/4 NW 1/4)	STATE OF NEW MEXICO	229.72	13.92	0.158
SEC. 32 (SE 1/4 NW 1/4)	STATE OF NEW MEXICO	5.54	0.34	0.004
TOTAL		235.26	14.26	0.162

<b>ACREAGE / LENGTH TABLE LATERAL "C"</b>				
	OWNERSHIP	FEET	RODS	ACRES
SEC. 32 (NE 1/4 NW 1/4)	STATE OF NEW MEXICO	229.63	13.92	0.158
SEC. 32 (SE 1/4 NW 1/4)	STATE OF NEW MEXICO	5.63	0.34	0.004
TOTAL		235.26	14.26	0.162

**CERTIFICATE**  
 THIS IS TO CERTIFY THAT THIS EASEMENT PLAT AND THE ACTUAL SURVEY ON THE GROUND UPON WHICH IT IS BASED WERE PERFORMED BY ME OR UNDER MY DIRECT SUPERVISION, THAT I AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY MEETS THE MINIMUM STANDARDS FOR SURVEYING IN NEW MEXICO, AND THAT IT IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.



FILE: 63852-A3

Sheet 3 of 4

**CIMAREX ENERGY CO.**


**RED HILLS UNIT 32-5 OIL PIPELINE NETWORK  
 ON STATE OF NEW MEXICO LANDS  
 SECTION 32, T25S, R33E, N.M.P.M.  
 LEA COUNTY, NEW MEXICO**

SURVEYED BY	A.H., F.R.	05-01-18	SCALE
DRAWN BY	J.P.P.	05-17-18	N/A

**OIL PIPELINE R-O-W EXHIBIT Q**



**UELS, LLC**  
 Corporate Office \* 85 South 200 East  
 Vernal, UT 84078 \* (435) 789-1017



T25S  
T26S


**LEGEND:**  
 ——— PROPOSED CENTERLINE  
 ——— SECTION LINE  
 - - - 1/4 SECTION LINE  
 - - - 1/16 SECTION LINE  
 - - - PROPERTY LINE



**CIMAREX ENERGY CO.**  
 RED HILLS UNIT 32-5 POWER LINE NETWORK  
 SECTIONS 32 & 33, T25S, R33E, N.M.P.M.  
 LEA COUNTY, NEW MEXICO

SURVEYED BY	A.L.F.R.	05-01-18	SCALE
DRAWN BY	J.P.P.	05-17-18	N/A

**OVERALL POWER LINE**




See Detail "D"  
On Sheet 4 of 7

See Detail "B"

See Detail "C"  
On Sheet 3 of 7

See Detail "A"  
On Sheet 3 of 7



END OF PROPOSED POWER LINE "B" RIGHT-OF-WAY  
(At Edge of Proposed Red Hills Unit 32-5 W2W2 Pad #1)

END OF PROPOSED POWER LINE "C" RIGHT-OF-WAY  
(At Edge Of Proposed Red Hills Unit 32-5 W2W2 Pad #2)

END OF PROPOSED POWER LINE "E" RIGHT-OF-WAY  
(At Edge Of Proposed Red Hills Unit 32 West WC #2 CTB)

BEGINNING OF PROPOSED POWER LINE "C" RIGHT-OF-WAY  
(At the Centerline of the Proposed Red Hills Unit 32-5 Power Line "B")


BEGINNING OF PROPOSED POWER LINE "E" RIGHT-OF-WAY  
(At the Centerline of the Proposed Red Hills Unit 32-5 Power Line "D")

END OF PROPOSED POWER LINE "A" RIGHT-OF-WAY  
(At Edge Of Proposed Red Hills Unit 32 West BS #1 CTB)

BEGINNING OF PROPOSED POWER LINE "D" RIGHT-OF-WAY  
(At the Centerline of the Proposed Red Hills Unit 32-5 Power Line "A")

BEGINNING OF PROPOSED POWER LINE "B" RIGHT-OF-WAY  
(At the Centerline of the Proposed Red Hills Unit 32-5 Power Line "A")

CERTIFICATE  
THIS IS TO CERTIFY THAT THIS EASEMENT PLAT AND THE ACTUAL SURVEY ON THE GROUND UPON WHICH IT IS BASED WERE PERFORMED BY ME OR UNDER MY DIRECT SUPERVISION, THAT I AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY MEETS THE MINIMUM STANDARDS FOR SURVEYING IN NEW MEXICO, AND THAT I AM NOT AWARE OF ANY FACTS WHICH WOULD CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.



▲ = SECTION CORNERS LOCATED.

Detail "B"  
No Scale

FILE: 63849-A1

Sheet 1 of 7

NOTES:  
• Basis of Bearings is a Transverse Mercator Projection with a Central Meridian of W103°53'00"



CIMAREX ENERGY CO.

RED HILLS UNIT 32-5 POWER LINE NETWORK  
ON STATE OF NEW MEXICO LANDS  
SECTION 32, T25S, R33E, N.M.P.M.  
LEA COUNTY, NEW MEXICO

SURVEYED BY	A.H. F.R.	05-01-18	SCALE
DRAWN BY	J.P.P.	05-17-18	1" = 1000'

POWER LINE R-O-W

EXHIBIT I



UELS, LLC  
Corporate Office \* 85 South 200 East  
Vernal, UT 84078 \* (435) 789-1017

BEGINNING OF POWER LINE "A" BEARS S41°44'39"W 1712.65' FROM THE EAST 1/4 CORNER OF SECTION 32, T25S, R33E, N.M.P.M.

END OF POWER LINE "A" BEARS N21°53'29"E 1078.33' FROM THE WEST 1/4 CORNER OF SECTION 32, T25S, R33E, N.M.P.M.

BEGINNING OF POWER "B" LINE BEARS N38°29'58"E 1239.78' FROM THE WEST 1/4 CORNER OF SECTION 32, T25S, R33E, N.M.P.M.

END OF POWER LINE "B" BEARS S50°48'50"E 892.03' FROM THE NORTHWEST CORNER OF SECTION 32, T25S, R33E, N.M.P.M.

BEGINNING OF POWER LINE "C" BEARS S54°16'05"E 964.80' FROM THE NORTHWEST CORNER OF SECTION 32, T25S, R33E, N.M.P.M.

END OF POWER LINE "C" BEARS S57°25'14"E 1046.00' FROM THE NORTHWEST CORNER OF SECTION 32, T25S, R33E, N.M.P.M.

BEGINNING OF POWER LINE "D" BEARS N54°19'52"E 1666.27' FROM THE WEST 1/4 CORNER OF SECTION 32, T25S, R33E, N.M.P.M.

END OF POWER LINE "D" BEARS S16°31'38"E 1282.94' FROM THE NORTH 1/4 CORNER OF SECTION 32, T25S, R33E, N.M.P.M.

BEGINNING OF POWER LINE "E" BEARS S42°58'06"W 1882.98' FROM THE NORTH 1/4 CORNER OF SECTION 32, T25S, R33E, N.M.P.M.

END OF POWER LINE "E" BEARS S46°09'27"W 1779.81' FROM THE NORTH 1/4 CORNER OF SECTION 32, T25S, R33E, N.M.P.M.

BEGINNING OF POWER LINE "F" BEARS S14°50'44"W 1423.74' FROM THE NORTH 1/4 CORNER OF SECTION 32, T25S, R33E, N.M.P.M.

END OF POWER LINE "F" BEARS S16°30'52"W 1284.19' FROM THE NORTH 1/4 CORNER OF SECTION 32, T25S, R33E, N.M.P.M.

BEGINNING OF POWER LINE "G" BEARS S01°35'26"E 1376.04' FROM THE NORTH 1/4 CORNER OF SECTION 32, T25S, R33E, N.M.P.M.

END OF POWER LINE "G" BEARS S07°47'40"W 570.43' FROM THE NORTH 1/4 CORNER OF SECTION 32, T25S, R33E, N.M.P.M.

BEGINNING OF POWER LINE "H" BEARS S03°43'24"E 566.15' FROM THE NORTH 1/4 CORNER OF SECTION 32, T25S, R33E, N.M.P.M.

END OF POWER LINE "H" BEARS S08°15'10"E 570.79' FROM THE NORTH 1/4 CORNER OF SECTION 32, T25S, R33E, N.M.P.M.

BEGINNING OF POWER LINE "I" ON STATE OF NEW MEXICO LANDS BEARS S00°08'32"E 687.30' FROM THE NORTHEAST CORNER OF SECTION 32, T25S, R33E, N.M.P.M.

END OF POWER LINE "I" BEARS S57°47'19"W 1090.74' FROM THE NORTHEAST CORNER OF SECTION 32, T25S, R33E, N.M.P.M.

BEGINNING OF POWER LINE "J" BEARS S16°29'31"W 717.12' FROM THE NORTHEAST CORNER OF SECTION 32, T25S, R33E, N.M.P.M.

END OF POWER LINE "J" BEARS S17°12'16"W 688.42' FROM THE NORTHEAST CORNER OF SECTION 32, T25S, R33E, N.M.P.M.

ACREAGE / LENGTH TABLE "A"				
	OWNERSHIP	FEET	RODS	ACRES
SEC. 32 (NE 1/4 SE 1/4)	STATE OF NEW MEXICO	229.94	13.94	0.158
SEC. 32 (NW 1/4 SE 1/4)	STATE OF NEW MEXICO	1699.06	102.97	1.170
SEC. 32 (NE 1/4 SW 1/4)	STATE OF NEW MEXICO	107.13	6.49	0.074
SEC. 32 (SE 1/4 NW 1/4)	STATE OF NEW MEXICO	1581.54	95.85	1.089
SEC. 32 (SW 1/4 NW 1/4)	STATE OF NEW MEXICO	948.27	57.47	0.653
TOTAL		4565.94	276.72	3.145

ACREAGE / LENGTH TABLE "B"				
	OWNERSHIP	FEET	RODS	ACRES
SEC. 32 (SW 1/4 NW 1/4)	STATE OF NEW MEXICO	350.19	21.22	0.241
SEC. 32 (NW 1/4 NW 1/4)	STATE OF NEW MEXICO	846.21	51.29	0.583
TOTAL		1196.40	72.51	0.824

ACREAGE / LENGTH TABLE "C"				
	OWNERSHIP	FEET	RODS	ACRES
SEC.32 (NW 1/4 NW 1/4)	STATE OF NEW MEXICO	98.23	5.95	0.068

ACREAGE / LENGTH TABLE "D"				
	OWNERSHIP	FEET	RODS	ACRES
SEC. 32 (SE 1/4 NW 1/4)	STATE OF NEW MEXICO	1581.33	95.84	1.089
SEC. 32 (SW 1/4 NE 1/4)	STATE OF NEW MEXICO	416.88	25.27	0.287
SEC. 32 (NW 1/4 NE 1/4)	STATE OF NEW MEXICO	89.59	5.43	0.062
TOTAL		2087.80	126.53	1.438

ACREAGE / LENGTH TABLE "E"				
	OWNERSHIP	FEET	RODS	ACRES
SEC. 32 (SE 1/4 NW 1/4)	STATE OF NEW MEXICO	55.66	3.37	0.038
SEC. 32 (NE 1/4 NW 1/4)	STATE OF NEW MEXICO	89.34	5.41	0.062
TOTAL		145.00	8.79	0.100

LINE TABLE		
LINE	DIRECTION	LENGTH
L1	N51°15'32"W	3583.24'
L2	S89°52'08"W	581.91'
L3	S89°52'08"W	368.65'
L4	N00°07'54"W	31.15'
L5	N00°13'10"E	1104.82'
L6	S89°53'08"W	91.77'
L7	N89°53'08"E	98.23'
L8	N00°06'04"W	294.16'
L9	N89°53'56"E	918.64'
L10	N89°53'56"E	402.98'
L11	N89°53'56"E	327.02'
L12	N00°06'04"W	145.00'
L13	N00°06'04"W	145.00'
L14	N00°06'04"W	145.00'
L15	N00°06'04"W	810.55'
L16	S89°53'57"W	114.13'
L17	N89°53'57"E	45.17'
L20	S89°54'45"W	205.28'
L21	S89°54'45"W	719.20'
L22	N00°02'43"W	107.30'
L23	N00°05'16"W	30.00'

CERTIFICATE  
THIS IS TO CERTIFY THAT THIS EASEMENT PLAT AND THE ACTUAL SURVEY ON THE GROUND UPON WHICH IT IS BASED WERE PERFORMED BY ME OR UNDER MY DIRECT SUPERVISION. THAT I AM RESPONSIBLE FOR THIS SURVEY. THAT THIS SURVEY MEETS THE MINIMUM STANDARDS FOR THE STATE OF NEW MEXICO AND THAT I HAVE NO OTHER INTEREST IN THE SUBJECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.



FILE: 63849-A2

Sheet 2 of 7

NOTES:

Basis of Bearings is a Transverse Mercator Projection with a Central Meridian of W103°53'00"


CIMAREX ENERGY CO.

RED HILLS UNIT 32-5 POWER LINE NETWORK  
ON STATE OF NEW MEXICO LANDS  
SECTION 32, T25S, R33E, N.M.P.M.  
LEA COUNTY, NEW MEXICO

SURVEYED BY	A.H., F.R.	05-01-18	SCALE
DRAWN BY	J.P.P.	05-17-18	N/A
POWER LINE R-O-W		EXHIBIT I	



UELS, LLC  
Corporate Office \* 85 South 200 East  
Vernal, UT 84078 \* (435) 789-1017



**ACREAGE / LENGTH TABLE "F"**

	OWNERSHIP	FEET	RODS	ACRES
SEC. 32 (SE 1/4 NW 1/4)	STATE OF NEW MEXICO	55.57	3.37	0.038
SEC. 32 (NE 1/4 NW 1/4)	STATE OF NEW MEXICO	89.43	5.42	0.062
<b>TOTAL</b>		<b>145.00</b>	<b>8.79</b>	<b>0.100</b>

**ACREAGE / LENGTH TABLE "G"**

	OWNERSHIP	FEET	RODS	ACRES
SEC. 32 (SW 1/4 NE 1/4)	STATE OF NEW MEXICO	55.52	3.36	0.038
SEC. 32 (NW 1/4 NE 1/4)	STATE OF NEW MEXICO	790.26	47.89	0.544
SEC. 32 (NE 1/4 NW 1/4)	STATE OF NEW MEXICO	78.90	4.78	0.054
<b>TOTAL</b>		<b>924.68</b>	<b>56.04</b>	<b>0.637</b>

**ACREAGE / LENGTH TABLE "H"**


	OWNERSHIP	FEET	RODS	ACRES
SEC.32 (NW 1/4 NE 1/4)	STATE OF NEW MEXICO	45.17	2.74	0.031

**ACREAGE / LENGTH TABLE "I"**

	OWNERSHIP	FEET	RODS	ACRES
SEC.32 (NE 1/4 NE 1/4)	STATE OF NEW MEXICO	1031.78	62.53	0.711


**ACREAGE / LENGTH TABLE "J"**

	OWNERSHIP	FEET	RODS	ACRES
SEC.32 (NE 1/4 NE 1/4)	STATE OF NEW MEXICO	30.00	1.82	0.021



**BEGINNING OF PROPOSED POWER LINE "A" RIGHT-OF-WAY**  
(At Existing Power Line)

**CERTIFICATE**  
THIS IS TO CERTIFY THAT THIS EASEMENT PLAT AND THE ACTUAL SURVEY ON THE GROUND UPON WHICH IT IS BASED WERE PERFORMED BY ME OR UNDER MY DIRECT SUPERVISION, THAT I AM RESPONSIBLE FOR THIS SURVEY, THAT THE SURVEY MEETS THE MINIMUM STANDARDS FOR SURVEYING IN NEW MEXICO, AND THAT IT IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.



FILE: 63849-A3

Sheet 3 of 7


**NOTES:**  
• Basis of Bearings is a Transverse Mercator Projection with a Central Meridian of W103°53'00"

**CIMAREX ENERGY CO.**  
**RED HILLS UNIT 32-5 POWER LINE NETWORK**  
**ON STATE OF NEW MEXICO LANDS**  
**SECTION 32, T25S, R33E, N.M.P.M.**  
**LEA COUNTY, NEW MEXICO**

<b>SURVEYED BY</b>	A.H. F.R.	05-01-18	<b>SCALE</b>
<b>DRAWN BY</b>	J.P.P.	05-17-18	N/A
<b>POWER LINE R-O-W</b>		<b>EXHIBIT I</b>	




**UELS, LLC**  
Corporate Office \* 85 South 200 East  
Vernal, UT 84078 \* (435) 789-1017



**Detail "D"**  
No Scale

**CERTIFICATE**  
THIS IS TO CERTIFY THAT THIS EASEMENT PLAT AND THE ACTUAL SURVEY ON THE GROUND UPON WHICH IT IS BASED WERE PERFORMED BY ME OR UNDER MY DIRECT SUPERVISION; THAT I AM RESPONSIBLE FOR THIS SURVEY; THAT THIS SURVEY MEETS THE MINIMUM STANDARDS FOR SURVEYING IN NEW MEXICO; AND THAT IT IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.



FILE: 63849-A4

Sheet 4 of 7

**NOTES:**

• Basis of Bearings is a Transverse Mercator Projection with a Central Meridian of W103°53'00"

**CIMAREX ENERGY CO.**

**RED HILLS UNIT 32-5 POWER LINE NETWORK  
ON STATE OF NEW MEXICO LANDS  
SECTION 32, T25S, R33E, N.M.P.M.  
LEA COUNTY, NEW MEXICO**


SURVEYED BY	A.H., F.R.	05-01-18	SCALE
DRAWN BY	J.P.P.	05-17-18	N/A

**POWER LINE R-O-W**

**EXHIBIT I**



**UELS, LLC**  
Corporate Office \* 85 South 200 East  
Vernal, UT 84078 \* (435) 789-1017




LINE TABLE		
LINE	DIRECTION	LENGTH
L18	N00°03'55"W	1656.97'
L19	S89°54'45"W	24.27'


BEGINNING OF POWER LINE "1" BEARS N04°06'50"E 297.12' FROM THE WEST 1/4 CORNER OF SECTION 33, T25S, R33E, N.M.P.M.

END OF POWER LINE "1" ON BLM LANDS BEARS S00°08'32"E 687.30' FROM THE NORTHEAST CORNER OF SECTION 33, T25S, R33E, N.M.P.M.


END OF PROPOSED POWER LINE "1" RIGHT-OF-WAY ON BLM LANDS (At Section Line)



Detail "A"  
No Scale



TYPICAL RIGHT-OF-WAY DETAIL  
NO SCALE



ACREAGE / LENGTH TABLE				
	OWNERSHIP	FEET	RODS	ACRES
SEC. 33 (NW 1/4)	BLM	1681.24	101.89	1.158


▲ = SECTION CORNERS LOCATED.

NOTES:

\* Basis of Bearings is a Transverse Mercator Projection with a Central Meridian of W103°53'00"

CERTIFICATE

THIS IS TO CERTIFY THAT THIS EASEMENT PLAT AND THE ACTUAL SURVEY ON THE GROUND UPON WHICH IT IS BASED WERE PERFORMED BY ME OR UNDER MY DIRECT SUPERVISION; THAT I AM RESPONSIBLE FOR THIS SURVEY; THAT THIS SURVEY MEETS THE MINIMUM STANDARDS FOR SURVEYING IN NEW MEXICO; AND THAT IT IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.



FILE: 63849-BI

Sheet 1 of 2




UELS, LLC  
Corporate Office \* 85 South 200 East  
Vernal, UT 84078 \* (435) 789-1017



**CIMAREX ENERGY CO.**  
RED HILLS UNIT 32-5 POWER LINE NETWORK  
ON BLM LANDS  
SECTION 33, T25S, R33E, N.M.P.M.  
LEA COUNTY, NEW MEXICO

SURVEYED BY	A.H., F.R.	05-01-18	SCALE
DRAWN BY	J.P.P.	05-17-18	1" = 1000'

**POWER LINE R-O-W EXHIBIT I**



BEGINNING OF SALES PIPELINE BEARS  
 N30°26'33"E 1335.59' FROM THE WEST 1/4  
 CORNER OF SECTION 32, T25S, R33E, N.M.P.M.

END OF SALES PIPELINE BEARS S40°20'17"W  
 1628.45' FROM THE EAST 1/4 CORNER OF  
 SECTION 32, T25S, R33E, N.M.P.M.

BEGINNING OF SALES PIPELINE LATERAL "A" BEARS  
 S30°39'27"E 1254.53' FROM THE NORTH 1/4  
 CORNER OF SECTION 32, T25S, R33E, N.M.P.M.

END OF SALES PIPELINE LATERAL "A" BEARS  
 N41°08'24"E 1688.94' FROM THE WEST 1/4 CORNER  
 OF SECTION 32, T25S, R33E, N.M.P.M.

BEGINNING OF SALES PIPELINE LATERAL "B"  
 BEARS S04°46'40"W 1084.24' FROM THE NORTH  
 1/4 CORNER OF SECTION 32, T25S, R33E,  
 N.M.P.M.


END OF SALES PIPELINE LATERAL "B" BEARS  
 S01°26'34"W 1288.54' FROM THE NORTH 1/4  
 CORNER OF SECTION 32, T25S, R33E, N.M.P.M.

BEGINNING OF SALES PIPELINE LATERAL "C"  
 BEARS S42°59'48"W 1479.49' FROM THE NORTH  
 1/4 CORNER OF SECTION 32, T25S, R33E,  
 N.M.P.M.

END OF SALES PIPELINE LATERAL "C" BEARS  
 S36°24'20"W 1602.50' FROM THE NORTH 1/4  
 CORNER OF SECTION 32, T25S, R33E, N.M.P.M.

LINE TABLE		
LINE	DIRECTION	LENGTH
L1	N89°52'08"E	338.41'
L2	N38°44'28"E	153.48'
L3	S51°15'32"E	4004.70'
L4	N89°53'56"E	57.50'
L5	S00°06'04"E	207.76'
L6	S89°53'56"W	730.00'
L7	S89°53'56"W	918.64'
L8	S89°53'56"W	509.36'
L9	S38°44'28"W	103.84'
L10	N89°53'56"E	57.50'
L11	S00°06'04"E	207.76'
L12	N89°53'56"E	57.50'
L13	S00°06'04"E	207.76'

**CERTIFICATE**  
 THIS IS TO CERTIFY THAT THIS EASEMENT PLAT AND  
 THE ACTUAL SURVEY ON THE GROUND UPON WHICH IT  
 IS BASED WERE PERFORMED BY ME OR UNDER MY  
 DIRECT SUPERVISION, THAT I AM RESPONSIBLE FOR  
 THIS SURVEY, THAT THIS SURVEY MEETS THE  
 MINIMUM STANDARDS FOR SURVEYING IN NEW  
 MEXICO, AND THAT IT IS TRUE AND CORRECT TO THE  
 BEST OF MY KNOWLEDGE AND BELIEF.



▲ = SECTION CORNERS LOCATED.

**NOTES:**

\* Basis of Bearings is a Transverse Mercator Projection with a Central Meridian of W103°53'00"

FILE: 63859-A1

Sheet 1 of 4



**CIMAREX ENERGY CO.**


**RED HILLS UNIT 32-5 SALES PIPELINE NETWORK  
 ON STATE OF NEW MEXICO LANDS  
 SECTION 32, T25S, R33E, N.M.P.M.  
 LEA COUNTY, NEW MEXICO**

SURVEYED BY	A.H. F.R.	05-01-18	SCALE
DRAWN BY	J.P.P.	05-17-18	1" = 1000'
<b>SALES PIPELINE R-O-W</b>			<b>EXHIBIT G</b>




**UELS, LLC**  
 Corporate Office \* 85 South 200 East  
 Vernal, UT 84078 \* (435) 789-1017

**BEGINNING OF PROPOSED SALES PIPELINE LATERAL "B" RIGHT-OF-WAY**  
(At Edge of Proposed Red Hills Unit 32 East BS #3 CTB)



**Detail "A"**  
No Scale


**BEGINNING OF PROPOSED SALES PIPELINE LATERAL "C" RIGHT-OF-WAY**  
(At Edge of Proposed Red Hills Unit 32 West WC #2 CTB)



**Detail "B"**  
No Scale

**END OF PROPOSED SALES PIPELINE LATERAL "C" RIGHT-OF-WAY**  
(At Proposed Red Hills Unit 32-5 SWD Pipeline Lateral "A")

**END OF PROPOSED SALES PIPELINE LATERAL "B" RIGHT-OF-WAY**  
(At Proposed Red Hills Unit 32-5 SWD Pipeline Lateral "A")



**Detail "C"**  
No Scale

**END OF PROPOSED SALES PIPELINE RIGHT-OF-WAY**  
(At Edge Of Proposed Enlink 4.99 Acre Tract)


<b>ACREAGE / LENGTH TABLE</b>				
	OWNERSHIP	FEET	RODS	ACRES
SEC. 32 (SW 1/4 NW 1/4)	STATE OF NEW MEXICO	758.20	45.95	0.783
SEC. 32 (SE 1/4 NW 1/4)	STATE OF NEW MEXICO	1698.49	102.94	1.755
SEC. 32 (SW 1/4 NE 1/4)	STATE OF NEW MEXICO	61.96	3.76	0.064
SEC. 32 (NW 1/4 SE 1/4)	STATE OF NEW MEXICO	1637.12	99.22	1.691
SEC. 32 (NE 1/4 SE 1/4)	STATE OF NEW MEXICO	340.81	20.66	0.352
<b>TOTAL</b>		<b>4496.58</b>	<b>272.52</b>	<b>4.645</b>

<b>ACREAGE / LENGTH TABLE LATERAL "A"</b>				
	OWNERSHIP	FEET	RODS	ACRES
SEC. 32 (NW 1/4 NE 1/4)	STATE OF NEW MEXICO	959.31	58.14	0.991
SEC. 32 (NE 1/4 NW 1/4)	STATE OF NEW MEXICO	1321.89	80.11	1.366
SEC. 32 (NW 1/4 NW 1/4)	STATE OF NEW MEXICO	182.91	11.09	0.189
SEC. 32 (SW 1/4 NW 1/4)	STATE OF NEW MEXICO	62.99	3.82	0.065
<b>TOTAL</b>		<b>2527.11</b>	<b>153.16</b>	<b>2.611</b>

<b>ACREAGE / LENGTH TABLE LATERAL "B"</b>				
	OWNERSHIP	FEET	RODS	ACRES
SEC. 32 (NE 1/4 NW 1/4)	STATE OF NEW MEXICO	265.26	16.08	0.274

<b>ACREAGE / LENGTH TABLE LATERAL "C"</b>				
	OWNERSHIP	FEET	RODS	ACRES
SEC. 32 (NE 1/4 NW 1/4)	STATE OF NEW MEXICO	265.26	16.08	0.274

**CERTIFICATE**  
THIS IS TO CERTIFY THAT THIS EASEMENT PLAT AND THE ACTUAL SURVEY ON THE GROUND UPON WHICH IT IS BASED WERE PERFORMED BY ME OR UNDER MY DIRECT SUPERVISION, THAT I AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY MEETS THE MINIMUM STANDARDS FOR SURVEYING IN NEW MEXICO, AND THAT IT IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.



FILE: 63859-A2

Sheet 2 of 4

**NOTES:**

\* Basis of Bearings is a Transverse Mercator Projection with a Central Meridian of W103°53'00"

**CIMAREX ENERGY CO.**


**RED HILLS UNIT 32-5 SALES PIPELINE NETWORK  
ON STATE OF NEW MEXICO LANDS  
SECTION 32, T25S, R33E, N.M.P.M.  
LEA COUNTY, NEW MEXICO**

<b>SURVEYED BY</b>	A.H., F.R.	05-01-18	<b>SCALE</b>
<b>DRAWN BY</b>	J.P.P.	05-17-18	N/A

**SALES PIPELINE R-O-W EXHIBIT G**





**UELS, LLC**  
Corporate Office \* 85 South 200 East  
Vernal, UT 84078 \* (435) 789-1017



- LEGEND:**
- PROPOSED CENTERLINE
  - SECTION LINE
  - 1/4 SECTION LINE
  - 1/16 SECTION LINE
  - PROPERTY LINE



<b>CIMAREX ENERGY CO.</b>			
<b>RED HILLS UNIT 32-5 SWD PIPELINE NETWORK</b>			
<b>SECTIONS 32 &amp; 33 T25S, R33E, N.M.P.M.</b>			
<b>LEA COUNTY, NEW MEXICO</b>			
SURVEYED BY	A.H.F.R.	05-01-18	SCALE
DRAWN BY	J.P.P.	05-17-18	N/A
<b>OVERALL SWD PIPELINE</b>			



BEGINNING OF SWD PIPELINE BEARS N30°00'42"E 1352.85' FROM THE WEST 1/4 CORNER OF SECTION 32, T25S, R33E, N.M.P.M.

END OF SWD PIPELINE ON STATE OF NEW MEXICO LANDS BEARS N00°08'33"W 23.64' FROM THE EAST 1/4 CORNER OF SECTION 32, T25S, R33E, N.M.P.M.

BEGINNING OF SWD PIPELINE LATERAL "A" BEARS S31°07'42"E 1237.35' FROM THE NORTH 1/4 CORNER OF SECTION 32, T25S, R33E, N.M.P.M.


END OF SWD PIPELINE LATERAL "A" BEARS S40°25'32"E 1720.53' FROM THE NORTHWEST CORNER OF SECTION 32, T25S, R33E, N.M.P.M.

BEGINNING OF SWD PIPELINE LATERAL "B" BEARS S04°52'10"W 1064.31' FROM THE NORTH 1/4 CORNER OF SECTION 32, T25S, R33E, N.M.P.M.

END OF SWD PIPELINE LATERAL "B" BEARS S00°13'43"E 1250.58' FROM THE NORTH 1/4 CORNER OF SECTION 32, T25S, R33E, N.M.P.M.

BEGINNING OF SWD PIPELINE LATERAL "C" BEARS S43°31'52"W 1464.95' FROM THE NORTH 1/4 CORNER OF SECTION 32, T25S, R33E, N.M.P.M.


END OF SWD PIPELINE LATERAL "C" BEARS S36°06'58"W 1550.07' FROM THE NORTH 1/4 CORNER OF SECTION 32, T25S, R33E, N.M.P.M.



▲ = SECTION CORNERS LOCATED.

LINE	DIRECTION	LENGTH
L1	N89°52'08"E	306.36'
L2	N38°44'28"E	200.52'
L3	S51°15'27"E	3893.79'
L4	N38°44'30"E	289.13'
L5	S51°11'33"E	178.59'
L6	N38°44'59"E	1316.61'
L7	N39°14'36"E	18.27'
L18	N89°53'56"E	95.00'
L19	S00°08'04"E	190.26'
L20	S89°53'56"W	730.00'
L21	S89°53'56"W	918.64'
L22	S89°53'56"W	564.81'
L23	S38°44'28"W	79.29'
L24	N89°53'56"E	95.00'
L25	S00°08'04"E	190.26'
L26	N89°53'56"E	95.00'
L27	S00°08'04"E	190.26'

CERTIFICATE  
THIS IS TO CERTIFY THAT THIS EASEMENT PLAT AND THE ACTUAL SURVEY ON THE GROUND UPON WHICH IT IS BASED WERE PERFORMED BY ME OR UNDER MY DIRECT SUPERVISION, THAT I AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY MEETS THE MINIMUM STANDARDS FOR SURVEYING IN NEW MEXICO, AND THAT IT IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.



FILE: 63851-A1

Sheet 1 of 4

NOTES:  
• Basis of Bearings is a Transverse Mercator Projection with a Central Meridian of W103°53'00"

**CIMAREX ENERGY CO.**  
**RED HILLS UNIT 32-5 SWD PIPELINE NETWORK**  
**ON STATE OF NEW MEXICO LANDS**  
**SECTION 32, T25S, R33E, N.M.P.M.**  
**LEA COUNTY, NEW MEXICO**


SURVEYED BY	A.H., F.R.	05-01-18	SCALE
DRAWN BY	J.P.P.	05-17-18	1" = 1000'

**SWD PIPELINE R-O-W EXHIBIT II**




**UELS, LLC**  
 Corporate Office \* 85 South 200 East  
 Vernal, UT 84078 \* (435) 789-1017

END OF PROPOSED SWD PIPELINE RIGHT-OF-WAY ON STATE OF NEW MEXICO LANDS



Detail "A"  
No Scale


BEGINNING OF PROPOSED SWD PIPELINE LATERAL "C" RIGHT-OF-WAY  
(At Edge of Proposed Red Hills Unit 32 East BS #3 CTB)



Detail "B"  
No Scale


END OF PROPOSED SWD PIPELINE LATERAL "B" RIGHT-OF-WAY  
(At Proposed Red Hills Unit 32-5 SWD Pipeline Lateral "A")

BEGINNING OF PROPOSED SWD PIPELINE LATERAL "C" RIGHT-OF-WAY  
(At Edge of Proposed Red Hills Unit 32 West WC #2 CTB)




Detail "C"  
No Scale

END OF PROPOSED SWD PIPELINE LATERAL "C" RIGHT-OF-WAY  
(At Proposed Red Hills Unit 32-5 SWD Pipeline Lateral "A")



Detail "D"  
No Scale

CERTIFICATE  
THIS IS TO CERTIFY THAT THIS EASEMENT PLAT AND THE ACTUAL SURVEY ON THE GROUND UPON WHICH IT IS BASED WERE PERFORMED BY ME OR UNDER MY DIRECT SUPERVISION, THAT I AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY MEETS THE MINIMUM STANDARDS FOR SURVEYING IN NEW MEXICO, AND THAT IT IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.



FILE: 63851-A2

Sheet 2 of 4

NOTES:  
• Basis of Bearings is a Transverse Mercator Projection with a Central Meridian of W103°53'00"

**CIMAREX ENERGY CO.**

**RED HILLS UNIT 32-5 SWD PIPELINE NETWORK ON STATE OF NEW MEXICO LANDS SECTION 32, T25S, R33E, N.M.P.M. LEA COUNTY, NEW MEXICO**



**UELS, LLC**  
Corporate Office \* 85 South 200 East  
Vernal, UT 84078 \* (435) 789-1017

SURVEYED BY	A.H. F.R.	05-01-18	SCALE
DRAWN BY	J.P.P.	05-17-18	N/A
<b>SWD PIPELINE R-O-W</b>			<b>EXHIBIT II</b>

**PIPELINE RIGHT-OF-WAY DESCRIP  
ON STATE OF NEW MEXICO LANDS**

A 30' WIDE RIGHT-OF-WAY 15' ON EACH SIDE OF THE FOLLOWING DESCRIBED CENTERLINE.

BEGINNING AT A POINT IN THE SW 1/4 NW 1/4 OF SECTION 32, T25S, R33E, N.M.P.M., WHICH BEARS N30°00'42"E 1352.85' FROM THE WEST 1/4 CORNER OF SAID SECTION 32, THENCE N89°52'08"E 306.36'; THENCE N38°44'28"E 200.52'; THENCE S51°15'27"E 3893.79'; THENCE N38°44'30"E 269.13'; THENCE S51°11'33"E 178.59'; THENCE N38°44'59"E 1316.61'; THENCE N39°14'36"E 18.27' TO A POINT ON THE EAST LINE OF THE SE 1/4 NE 1/4 OF SAID SECTION 32, WHICH BEARS N00°08'33"W 23.64' FROM THE EAST 1/4 CORNER OF SAID SECTION 32. THE SIDE LINES OF SAID DESCRIBED RIGHT-OF-WAY BEING SHORTENED OR ELONGATED TO MEET THE GRANTOR'S PROPERTY LINES. BASIS OF BEARINGS IS A TRANSVERSE MERCATOR PROJECTION WITH A CENTRAL MERIDIAN OF W103°53'00". CONTAINS 4.258 ACRES MORE OR LESS.

**SWD PIPELINE RIGHT-OF-WAY DESCRIPTION LATERAL "A"**

A 30' WIDE RIGHT-OF-WAY 15' ON EACH SIDE OF THE FOLLOWING DESCRIBED CENTERLINE.

BEGINNING AT A POINT IN THE NW 1/4 NE 1/4 OF SECTION 32, T25S, R33E, N.M.P.M., WHICH BEARS S31°07'42"E 1237.35' FROM THE NORTH 1/4 CORNER OF SAID SECTION 32, THENCE N89°53'56"E 95.00'; THENCE S00°06'04"E 190.26'; THENCE S89°53'56"W 730.00'; THENCE S89°53'56"W 918.64'; THENCE S89°53'56"W 564.81'; THENCE S38°44'28"W 79.29' TO A POINT IN THE NW 1/4 NW 1/4 OF SAID SECTION 32, WHICH BEARS S40°25'32"E 1720.53' FROM THE NORTHWEST CORNER OF SAID SECTION 32. THE SIDE LINES OF SAID DESCRIBED RIGHT-OF-WAY BEING SHORTENED OR ELONGATED TO MEET THE GRANTOR'S PROPERTY LINES. BASIS OF BEARINGS IS A TRANSVERSE MERCATOR PROJECTION WITH A CENTRAL MERIDIAN OF W103°53'00". CONTAINS 1.775 ACRES MORE OR LESS.

**SWD PIPELINE RIGHT-OF-WAY DESCRIPTION LATERAL "B"**

A 30' WIDE RIGHT-OF-WAY 15' ON EACH SIDE OF THE FOLLOWING DESCRIBED CENTERLINE.

BEGINNING AT A POINT IN THE NE 1/4 NW 1/4 OF SECTION 32, T25S, R33E, N.M.P.M., WHICH BEARS S04°52'10"W 1064.31' FROM THE NORTH 1/4 CORNER OF SAID SECTION 32, THENCE N89°53'56"E 95.00'; THENCE S00°06'04"E 190.26' TO A POINT IN THE NW 1/4 NE 1/4 OF SAID SECTION 32, WHICH BEARS S00°13'43"E 1250.58' FROM THE NORTH 1/4 CORNER OF SAID SECTION 32. THE SIDE LINES OF SAID DESCRIBED RIGHT-OF-WAY BEING SHORTENED OR ELONGATED TO MEET THE GRANTOR'S PROPERTY LINES. BASIS OF BEARINGS IS A TRANSVERSE MERCATOR PROJECTION WITH A CENTRAL MERIDIAN OF W103°53'00". CONTAINS 0.196 ACRES MORE OR LESS.

**SWD PIPELINE RIGHT-OF-WAY DESCRIPTION LATERAL "C"**

A 30' WIDE RIGHT-OF-WAY 15' ON EACH SIDE OF THE FOLLOWING DESCRIBED CENTERLINE.

BEGINNING AT A POINT IN THE NE 1/4 NW 1/4 OF SECTION 32, T25S, R33E, N.M.P.M., WHICH BEARS S43°31'52"W 1464.95' FROM THE NORTH 1/4 CORNER OF SAID SECTION 32, THENCE N89°53'56"E 95.00'; THENCE S00°06'04"E 190.26' TO A POINT IN THE NE 1/4 NW 1/4 OF SAID SECTION 32, WHICH BEARS S36°06'58"W 1550.07' FROM THE NORTH 1/4 CORNER OF SAID SECTION 32. THE SIDE LINES OF SAID DESCRIBED RIGHT-OF-WAY BEING SHORTENED OR ELONGATED TO MEET THE GRANTOR'S PROPERTY LINES. BASIS OF BEARINGS IS A TRANSVERSE MERCATOR PROJECTION WITH A CENTRAL MERIDIAN OF W103°53'00". CONTAINS 0.196 ACRES MORE OR LESS.

**ACREAGE / LENGTH TABLE**

	OWNERSHIP	FEET	RODS	ACRES
SEC. 32 (SW 1/4 NW 1/4)	STATE OF NEW MEXICO	754.66	45.74	0.520
SEC. 32 (NW 1/4 NW 1/4)	STATE OF NEW MEXICO	21.75	1.32	0.015
SEC. 32 (SE 1/4 NW 1/4)	STATE OF NEW MEXICO	1698.52	102.94	1.170
SEC. 32 (SW 1/4 NE 1/4)	STATE OF NEW MEXICO	148.99	9.03	0.103
SEC. 32 (NW 1/4 SE 1/4)	STATE OF NEW MEXICO	1550.14	93.95	1.068
SEC. 32 (NE 1/4 SE 1/4)	STATE OF NEW MEXICO	1978.74	119.92	1.363
SEC. 32 (SE 1/4 NE 1/4)	STATE OF NEW MEXICO	30.47	1.85	0.021
TOTAL		6183.27	374.74	4.258

**ACREAGE / LENGTH TABLE LATERAL "A"**

	OWNERSHIP	FEET	RODS	ACRES
SEC. 32 (NW 1/4 NE 1/4)	STATE OF NEW MEXICO	1016.85	61.63	0.700
SEC. 32 (NE 1/4 NW 1/4)	STATE OF NEW MEXICO	1321.89	80.11	0.910
SEC. 32 (NW 1/4 NW 1/4)	STATE OF NEW MEXICO	239.27	14.50	0.165
TOTAL		2578.01	156.24	1.775


**ACREAGE / LENGTH TABLE LATERAL "B"**

	OWNERSHIP	FEET	RODS	ACRES
SEC. 32 (NE 1/4 NW 1/4)	STATE OF NEW MEXICO	93.23	5.65	0.064
SEC. 32 (NW 1/4 NE 1/4)	STATE OF NEW MEXICO	192.03	11.64	0.132
TOTAL		285.26	17.29	0.196

**ACREAGE / LENGTH TABLE LATERAL "C"**

	OWNERSHIP	FEET	RODS	ACRES
SEC. 32 (NE 1/4 NW 1/4)	STATE OF NEW MEXICO	285.26	17.29	0.196

**CERTIFICATE**  
THIS IS TO CERTIFY THAT THIS EASEMENT PLAT AND THE ACTUAL SURVEY ON THE GROUND UPON WHICH IT IS BASED WERE PERFORMED BY ME OR UNDER MY DIRECT SUPERVISION, THAT I AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY MEETS THE MINIMUM STANDARDS FOR SURVEYING IN NEW MEXICO, AND THAT THE PLAT IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.



FILE: 63851-A3

Sheet 3 of 4

**NOTES:**

\* Basis of Bearings is a Transverse Mercator Projection with a Central Meridian of W103°53'00"

**CIMAREX ENERGY CO.**



**RED HILLS UNIT 32-5 SWD PIPELINE NETWORK  
ON STATE OF NEW MEXICO LANDS  
SECTION 32, T25S, R33E, N.M.P.M.  
LEA COUNTY, NEW MEXICO**

SURVEYED BY	A.H., F.R.	05-01-18	SCALE
DRAWN BY	J.P.P.	05-17-18	N/A

**SWD PIPELINE R-O-W EXHIBIT II**



**UELS, LLC**  
Corporate Office \* 85 South 200 East  
Vernal, UT 84078 \* (435) 789-1017



LINE TABLE		
LINE	DIRECTION	LENGTH
L8	N39°14'36"E	184.08'
L9	N00°06'42"E	400.96'
L10	N36°33'59"E	337.08'
L11	N29°36'18"E	158.21'
L12	N37°51'19"E	374.43'
L13	N23°19'07"E	54.90'
L14	N14°29'48"E	83.83'
L15	N08°22'53"E	114.16'
L16	N06°04'42"E	267.92'
L17	S85°18'51"E	132.79'

BEGINNING OF SWD PIPELINE ON BLM LANDS BEARS N00°08'33"W 23.64' FROM THE WEST 1/4 CORNER OF SECTION 33, T25S, R33E, N.M.P.M.


END OF SWD PIPELINE BEARS S43°30'15"E 1220.05' FROM THE NORTHWEST CORNER OF SECTION 33, T25S, R33E, N.M.P.M.



ACREAGE / LENGTH TABLE			
SECTION	OWNERSHIP	FEET	RODS ACRES
SEC. 33 (NW 1/4)	BLM	2088.34	126.57 1.438

▲ = SECTION CORNERS LOCATED.

**CERTIFICATE**  
THIS IS TO CERTIFY THAT THIS EASEMENT PLAT AND THE ACTUAL SURVEY ON THE GROUND UPON WHICH IT IS BASED WERE PERFORMED BY ME OR UNDER MY DIRECT SUPERVISION. THAT I AM RESPONSIBLE FOR THIS SURVEY. THAT THIS SURVEY MEETS THE MINIMUM STANDARDS FOR SURVEYING IN NEW MEXICO AND THAT THE SAME IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.



FILE: 63851-B1 Sheet 1 of 2

**NOTES:**  
\* Basis of Bearings is a Transverse Mercator Projection with a Central Meridian of W103°53'00"



**UELS, LLC**  
Corporate Office \* 85 South 200 East  
Vernal, UT 84078 \* (435) 789-1017

**CIMAREX ENERGY CO.**  
**RED HILLS UNIT 32-5 SWD PIPELINE NETWORK**  
**ON BLM LANDS**  
**SECTION 33, T25S, R33E, N.M.P.M.**  
**LEA COUNTY, NEW MEXICO**

SURVEYED BY	A.H., F.R.	05-01-18	SCALE
DRAWN BY	J.P.P.	05-17-18	1" = 1000'

**SWD PIPELINE R-O-W EXHIBIT II**

## **Cimarex Red Hills Unit 131H Surface Use Plan**

Upon approval of the Application for Permit to Drill (APD) the following surface use plan of operations will be followed and carried out. The surface use plan outlines the proposed surface disturbance. If any other disturbance is needed after the APD is approved, a BLM sundry notice or right of way application will be submitted for approval prior to any additional surface disturbance.

### **Existing Roads**

- Directions to location - Exhibit A.
- Public access route - Exhibit B.
- Existing access road for the proposed project. Please see Exhibit B and C.
- Cimarex Energy will:
  - Improve and/or maintain existing road(s) condition the same as or better than before the operations began.
  - Provide plans for improvement and /or maintenance of existing roads if requested.
  - Repair or replace damaged or deteriorated structures as needed. Including cattle guards and culverts.
  - Prevent and abate fugitive dust as needed, whether created by vehicular traffic, equipment operations, or other events.
  - Obtain written BLM approval prior to the application of surfactants, binding agents, or other dust suppression chemicals on the roadways.
- The maximum width of the driving surface will be 18'. The road will be crowned and ditched with a 2% slope from the tip of the crown to the edge of the driving surface. The ditches will be 1' deep with 3:1 slopes. The driving surface will be made of 6" rolled and compacted caliche.

### **New or Reconstructed Access Roads**

Cimarex Energy plans to construct a new off-lease access road

- Length: 9041'
- Width: 30'
- Road Plat - Exhibit D.
- A ROW will be submitted to the BLM for approval.
- Cimarex Energy will complete improvements to the driving surface as needed.
- The maximum width of the driving surface for all roads above will be 18'.
- The road will be crowned and ditched with a 2% slope from the tip of the crown to the edge of the driving surface.
- The ditches will be 1' deep with 3:1 slopes.
- The driving surface will be made of 6" rolled and compacted caliche.
- Cimarex Energy will prevent and abate fugitive dust as needed, whether created by vehicular traffic, equipment operations, or other events.

### **Well Radius Map**

Please see Exhibit E for wells within one mile or proposed well SHL and BHL.

### **Proposed or Existing Production Facility**

A new facility will be constructed for this project if the well is productive.

- Red Hills Unit 32 West BS#1, Red Hills Unit 32 West WC#2, Red Hills Unit 32 East BS#3, and Red Hills Unit 32 East WC#4 CTB - Exhibit F
  - Direction to facility
  - Facility pad location layout and cut and fill
  - Facility pad archeological boundary
  - Facility pad flowline corridor
  - Facility pad access road

### **Gas Pipeline Specifications**

- Cimarex plans to construct an on-lease gas pipeline to service this battery location.
- Please see Exhibit G for proposed pipeline route.
- Three pipelines: 12" LP Steel, 8" HP Steel, 4" HP Steel.
- Pipeline Length: 7,555'. Pipeline Width: 45'.
- Pipeline will be buried and will require a construction width of 75'.
- MAOP: 1,440psi.
- Anticipated working pressure: 12": 300psi; 8" & 4": 1100 psi.

# Cimarex Red Hills Unit 131H

## Surface Use Plan

### Gas Pipeline Specifications

- Cimarex plans to construct an on-lease oil pipeline to service this battery location.
- Please see Exhibit Q for proposed pipeline route.
- Three pipelines: 12" LP Steel, 8" HP Steel, 4" HP Steel.
- Pipeline Length: 8997. Pipeline will be buried
- MAOP: 1,440psi.
- Anticipated working pressure: 12": 300psi; 8" & 4": 1100 psi

### Salt Water Disposal Specifications

- Cimarex plans to construct an on-lease SWD pipeline to service this battery location.
- Please see Exhibit H for proposed pipeline route.
- Two pipelines: 4" Surface poly & 12" Buried poly. Both pipelines follow the same route.
- Length: 11,421'.
- MAOP: 4" line: 120psi; 12" line: 150psi.
- Anticipated working pressure: 4" line: 110psi; 12": 225 psi.

### Power Lines

- Cimarex plans to construct an on-lease power line to service the Red Hills Unit 32-5 Well pads & Batteries.
- Overhead power line from an existing power source located in the SE/4 of Sec 32-25S-33E And NW/4 of Sec 33-25S-33E.
- Length: 11,952'.
- Poles: 43
- Specifications: 480 volt, 4 wire, 3 phase.
- Please see Exhibit I for proposed route.

### Well Site Location

- Proposed well pad/location layout - Exhibit J.
- Proposed Rig layout - Exhibit K
  - The rig layout, including V-door and flare line may change depending on rig availability. The pad dimensions and orientation will remain the same. No additional disturbance is anticipated if a rig layout change is necessary to accommodate the drilling rig. If additional disturbance is required a sundry notice will be submitted to the BLM for approval.
  - Mud pits in the closed circulation system will be steel pits and the cuttings will be stored in the steel containment pits.
  - Cuttings will be stored in steel pits until they are hauled to a state-approved disposal facility.
- Archeological boundary - Exhibit L
- Multi well pad: Red Hills Unit 127H through 140H
- Pad Size: 500X560
- Construction Material
  - If possible, native caliche will be obtained from the excavation of drill site. The primary way of obtaining caliche will be by "turning over" the location. This means caliche will be obtained from the actual well site. A caliche permit will be obtained from BLM prior to pushing up any caliche. 2,400 cu yds is the max amount of caliche needed for pad and roads. Amount will vary for each pad. The procedure below has been approved by BLM personnel:
    - The top 6 inches of topsoil is pushed off and stockpiled along the side of the location.
    - An approximate 120' x 120' area is used within the proposed well site to remove caliche.
    - Subsoil is removed and piled alongside the 120' x 120' area within the pad site.
    - When caliche is found, material will be stockpiled within the pad site to build the location and road.
    - Then subsoil is pushed back in the hole and caliche is spread accordingly across entire location and road.
    - Once well is drilled, the stockpiled top soil will be used for interim reclamation and spread along areas where caliche is picked up and the location size is reduced. Neither caliche nor subsoil will be stockpiled outside of the well pad. Topsoil will be stockpiled along the edge of the pad as depicted in Exhibit J - Layout Diagram.
    - Per the Surface Use Agreement Cimarex will be required to use caliche from a BLM Approved pit in Sec. 20-25S-33E.
  - Mud pits in the closed circulation system will be steel pits and the cuttings will be stored in steel containment pits.
- Cuttings will be stored in steel pits until they are hauled to a state-approved disposal facility.
- If the well is a producer, those areas of the location not essential to production facilities will be reclaimed and seeded per BLM requirements. Exhibit P: Interim Reclamation Diagram.
- There are no known dwellings within 1.5 miles of this location.

# Cimarex Red Hills Unit 131H

## Surface Use Plan

### Flowlines and Gas Lift Pipelines

All proposed pipelines will be constructed in a 60' ROW corridor.

- Flowlines
  - Cimarex Energy plans to construct on-lease flowlines to service the well.
  - 6" HP steel for oil, gas, and water production.
  - Length: 6,009'.
  - MAOP: 1,500 psi; Anticipated working pressure: 200-300 psi.
  - Please see Exhibit M for proposed on lease route.
- Gas Lift Pipeline
  - Cimarex Energy plans to construct on-lease gas lift pipelines to service the well.
  - 6" HP steel for gas lift.
  - Length: 6,009'.
  - MAOP: 1,500 psi; Anticipated working pressure: 200-300 psi.
  - Please see Exhibit N for proposed on lease route.

### Water Resources

- A temporary surface fresh water pipeline(s) will be utilized for this project.
- Cimarex plans to lay the fresh water surface pipeline(s) prior to commencement of the stimulation job.
- 10" lay-flat surface pipeline.
- The surface pipeline(s) will follow the road from a frac pit to the well.
- Length: 9,641'.
- Operating pressure: <140 psi.
- Fresh water will be purchased from a 3rd party.
- Please see Exhibit O for proposed route.

### Methods of Handling Waste

- Drilling fluids, produced oil, and water from the well during drilling and completion operations will be stored safely and disposed of properly in a NMOCD approved disposal facility.
- Garbage and trash produced during drilling and completion operations will be collected in a trash container and disposed of properly at a state approved disposal facility. All trash on and around well site will be collected for disposal.
- Human waste and grey water will be contained and disposed of properly at a state approved disposal site.
- After drilling and completion operations, trash, chemicals, salts, frac sand and other waste will be removed and disposed of properly at a state approved disposal site.
- The well will be drilled utilizing a closed loop system. Drill cuttings will be properly disposed of into steel tanks and taken to an NMOCD approved disposal facility.

### Waste Minimization Plan

See Gas Capture Plan.

### Ancillary Facilities

No camps or airstrips to be constructed.

### Interim and Final Reclamation

- Rehabilitation of the location will start in a timely manner after all proposed drilling wells have been drilled from the pad or if drilling operations have ceased as outlined below:
  - No approved or pending drill permits for wells located on the drill pad
  - No drilling activity for 5 years from the drill pad
- Surfacing materials will be removed and returned to a mineral pit or recycled to repair or build roads and well pads.
- Drainage systems, if any, will be reshaped to the original configuration with provisions made to alleviate erosion. These may need to be modified in certain circumstances to prevent inundation of the location's pad and surface facilities. After the area has been shaped and contoured, topsoil from the spoil pile will be placed over the disturbed area to the extent possible. Revegetation procedures will comply with BLM standards.
- Exhibit P illustrates the proposed Surface Reclamation plans after cessation of drilling operations as outlined above.
  - The areas of the location not essential to production facilities and operations will be reclaimed and seeded per BLM requirements.
- Operator will amend the surface reclamation plan if well is a dry hole and/or a single well pad.

### Surface Ownership

- The wellsite is on surface owned by Dinwiddle Cattle Co, PO Box 963, Capitan, NM 88316.
- A copy of Surface Use Agreement has been given to the surface owner.
- The land is used mainly for farming, cattle ranching, recreational use, and oil and gas production.

## **Cimarex Red Hills Unit 131H Surface Use Plan**

### **Cultural Resource Survey - Archeology**

- Cultural Resources Survey will be conducted for the entire project as proposed in the APD and submitted to the BLM for review and approval.

### **On Site Notes and Information**

Onsite Date: 4/17/2018


BLM Personnel on site: Jeff Robertson

Cimarex Energy personnel on site: Barry Hunt

Pertinent information from onsite:

Proposed Frac Water Route, Red Hills Unit Pad (Sec. 32-25S-33E), water from Cimarex Cascade Frac Pit (Sec. 29-25S-33E)  
Lea County, NM

# EXHIBIT O



— 1 10" Freshwater Line



**Section 1 - General**

Would you like to address long-term produced water disposal? NO

**Section 2 - Lined Pits**

Would you like to utilize Lined Pit PWD options? NO

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Lined pit PWD on or off channel:

Lined pit PWD discharge volume (bbl/day):

Lined pit specifications:

Pit liner description:

Pit liner manufacturers information:

Precipitated solids disposal:

Describe precipitated solids disposal:

Precipitated solids disposal permit:

Lined pit precipitated solids disposal schedule:

Lined pit precipitated solids disposal schedule attachment:

Lined pit reclamation description:

Lined pit reclamation attachment:

Leak detection system description:

Leak detection system attachment:

Lined pit Monitor description:

Lined pit Monitor attachment:

Lined pit: do you have a reclamation bond for the pit?

Is the reclamation bond a rider under the BLM bond?

Lined pit bond number:

Lined pit bond amount:

Additional bond information attachment:

### **Section 3 - Unlined Pits**

Would you like to utilize Unlined Pit PWD options? NO

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Unlined pit PWD on or off channel:

Unlined pit PWD discharge volume (bbl/day):

Unlined pit specifications:

Precipitated solids disposal:

Describe precipitated solids disposal:

Precipitated solids disposal permit:

Unlined pit precipitated solids disposal schedule:

Unlined pit precipitated solids disposal schedule attachment:

Unlined pit reclamation description:

Unlined pit reclamation attachment:

Unlined pit Monitor description:

Unlined pit Monitor attachment:

Do you propose to put the produced water to beneficial use?

Beneficial use user confirmation:

Estimated depth of the shallowest aquifer (feet):

Does the produced water have an annual average Total Dissolved Solids (TDS) concentration equal to or less than that of the existing water to be protected?

TDS lab results:

Geologic and hydrologic evidence:

State authorization:

Unlined Produced Water Pit Estimated percolation:

Unlined pit: do you have a reclamation bond for the pit?

Is the reclamation bond a rider under the BLM bond?

Unlined pit bond number:

Unlined pit bond amount:

Additional bond information attachment:

### **Section 4 - Injection**

Would you like to utilize Injection PWD options? NO

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Injection PWD discharge volume (bbl/day):

Injection well mineral owner:

**Injection well type:**

**Injection well number:**

**Assigned injection well API number?**

**Injection well new surface disturbance (acres):**

**Minerals protection information:**

**Mineral protection attachment:**

**Underground Injection Control (UIC) Permit?**

**UIC Permit attachment:**

**Injection well name:**

**Injection well API number:**

### **Section 5 - Surface Discharge**

**Would you like to utilize Surface Discharge PWD options? NO**

**Produced Water Disposal (PWD) Location:**

**PWD surface owner:**

**PWD disturbance (acres):**

**Surface discharge PWD discharge volume (bbl/day):**

**Surface Discharge NPDES Permit?**

**Surface Discharge NPDES Permit attachment:**

**Surface Discharge site facilities information:**

**Surface discharge site facilities map:**

### **Section 6 - Other**

**Would you like to utilize Other PWD options? NO**

**Produced Water Disposal (PWD) Location:**

**PWD surface owner:**

**PWD disturbance (acres):**

**Other PWD discharge volume (bbl/day):**

**Other PWD type description:**

**Other PWD type attachment:**

**Have other regulatory requirements been met?**

**Other regulatory requirements attachment:**



**U.S. Department of the Interior  
BUREAU OF LAND MANAGEMENT**

**Bond Information**

**Federal/Indian APD: FED**

**BLM Bond number: NMB001188**

**BIA Bond number:**

**Do you have a reclamation bond? NO**

**Is the reclamation bond a rider under the BLM bond?**

**Is the reclamation bond BLM or Forest Service?**

**BLM reclamation bond number:**

**Forest Service reclamation bond number:**

**Forest Service reclamation bond attachment:**

**Reclamation bond number:**

**Reclamation bond amount:**

**Reclamation bond rider amount:**

**Additional reclamation bond information attachment:**