

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENTFORM APPROVED
OMB NO. 1004-0137
Expires: January 31, 2018**SUNDRY NOTICES AND REPORTS ON WELLS**
*Do not use this form for proposals to drill or to re-enter an abandoned well. Use form 3160-3 (APD) for such proposals.*5. Lease Serial No.
NMNM01917

6. If Indian, Allottee or Tribe Name

7. If Unit or CA/Agreement, Name and/or No.

8. Well Name and No.
DOS EQUIS 11-14 FEDERAL COM 4H9. API Well No.
30-025-4541310. Field and Pool or Exploratory Area
TRISTE DRAW BONE SPRING11. County or Parish, State
LEA COUNTY, NM

SUBMIT IN TRIPLICATE - Other instructions on page 2

HOBBS OGD

JAN 16 2019

RECEIVED

Sundance Field Office

12. CHECK THE APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
☒ Notice of Intent	☐ Acidize	☐ Deepen	☐ Production (Start/Resume)	☐ Water Shut-Off
☐ Subsequent Report	☐ Alter Casing	☐ Hydraulic Fracturing	☐ Reclamation	☐ Well Integrity
☐ Final Abandonment Notice	☐ Casing Repair	☐ New Construction	☐ Recomplete	☒ Other
	☐ Change Plans	☐ Plug and Abandon	☐ Temporarily Abandon	Change to Original A
	☐ Convert to Injection	☐ Plug Back	☐ Water Disposal	PD

13. Describe Proposed or Completed Operation: Clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports must be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 must be filed once testing has been completed. Final Abandonment Notices must be filed only after all requirements, including reclamation, have been completed and the operator has determined that the site is ready for final inspection.

Cimarex respectfully requests approval to change the SHL and BHL of the Dos Equis 11-14 Federal Com 4H well. Cimarex also requests approval to change the completion formation to Wolfcamp. The additional surface disturbance was approved by Cody Layton.

Approved:
SHL: 470 FNL & 370 FEL
BHL: 330 FSL & 360 FWL
Proposed:
SHL: 530 FNL & 370 FWL
BHL: 100 FSL & 330 FWL

SEE ATTACHED FOR
CONDITIONS OF APPROVAL

Please see attached plat, directional plan, and drilling plan for changes.

Engineering is Good. 2S 11/8/19 Surface good SR 1-9-2019

14. I hereby certify that the foregoing is true and correct.

Electronic Submission #449305 verified by the BLM Well Information System
For CIMAREX ENERGY CO, sent to the Hobbs
Committed to AFMSS for processing by ZOTA STEVENS on 01/08/2019 ()

Name (Printed/Typed) ARICKA EASTERLING

Title REGULATORY ANALYST

Signature (Electronic Submission)

Date 01/07/2019

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved By

Title

Date

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on page 2)

** OPERATOR-SUBMITTED ** OPERATOR-SUBMITTED ** OPERATOR-SUBMITTED **

KZ

1. Geological Formations

TVD of target 12,270
MD at TD 22,017

Pilot Hole TD 13,067
Deepest expected fresh water

Formation	Depth (TVD) from KB	Water/Mineral Bearing/Target Zone	Hazards
Rustler	1051	N/A	
Top of Salt	1372	N/A	
Base of Salt	4678	N/A	
Lamar	4910	N/A	
Bell Canyon	4948	N/A	
Cherry Canyon	5855	N/A	
Brushy Canyon	7327	Hydrocarbons	
Bone Spring	8818	Hydrocarbons	
1st Bone Spring	9907	Hydrocarbons	
2nd Bone Spring	10503	Hydrocarbons	
3rd Bone Spring	11830	Hydrocarbons	
Wolfcamp	12119	Hydrocarbons	
Wolfcamp Y Target	12310	Hydrocarbons	

2. Casing Program

Hole Size	Casing Depth From	Casing Depth To	Setting Depth TVD	Casing Size	Weight (lb/ft)	Grade	Conn.	SF Collapse	SF Burst	SF Tension
14 3/4	0	1235	1235	10-3/4"	40.50	J-55	BT&C	2.80	5.54	12.58
9 7/8	0	11793	11793	7-5/8"	29.70	L-80	BT&C	2.35	1.20	1.82
8 3/4	11793	12429	12261	7-5/8"	29.70	L-80 HC	Ultra FJ	2.88	1.20	28.6
6 3/4	0	11743	11743	5-1/2"	23.00	P-110	LT&C	1.90	1.78	2.91
6 3/4	10265	22017	12270	5"	18.00	P-110	BT&C	1.69	1.71	61.14
BLM Minimum Safety Factor								1.125	1	1.6 Dry 1.8 Wet

TVD was used on all calculations.

All casing strings will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.h

Request Variance for 5-1/2" x 7-5/8" annular clearance. The portion that does not meet clearance will not be cemented

	Y or N
Is casing new? If used, attach certification as required in Onshore Order #1	Y
Does casing meet API specifications? If no, attach casing specification sheet.	Y
Is premium or uncommon casing planned? If yes attach casing specification sheet.	Y
Does the above casing design meet or exceed BLM's minimum standards? If not provide justification (loading assumptions, casing design criteria).	Y
Will the intermediate pipe be kept at a minimum 1/3 fluid filled to avoid approaching the collapse pressure rating of the casing?	Y
Is well located within Capitan Reef?	N
If yes, does production casing cement tie back a minimum of 50' above the Reef?	N
Is well within the designated 4 string boundary.	N
Is well located in SOPA but not in R-111-P?	N
If yes, are the first 2 strings cemented to surface and 3rd string cement tied back 500' into previous casing?	N
Is well located in R-111-P and SOPA?	N
If yes, are the first three strings cemented to surface?	N
Is 2nd string set 100' to 600' below the base of salt?	N

Is well located in high Cave/Karst?	N
If yes, are there two strings cemented to surface?	N
(For 2 string wells) If yes, is there a contingency casing if lost circulation occurs?	N
Is well located in critical Cave/Karst?	N
If yes, are there three strings cemented to surface?	N
Is AC Report included?	N

3. Cementing Program

Casing	# Sk	Wt. lb/gal	Yld ft ³ /sack	H ₂ O gal/sk	500# Comp. Strength (hours)	Slurry Description
Surface	480	13.50	1.72	9.15	15.5	Lead: Class C + Bentonite
	128	14.80	1.34	6.32	9.5	Tail: Class C + LCM
Intermediate Stage 1	585	10.30	3.64	22.18		Lead: Tuned Light + LCM
	207	14.20	1.30	5.86	14:30	Tail: 50:50 (Poz:H) + Salt + Bentonite + Fluid Loss + Dispersant + SMS
Intermediate Stage 2	771	12.90	1.88	9.65	12	Lead: 35:65 (Poz:C) + Salt + Bentonite
Production	723	14.20	1.30	5.86	14:30	Tail: 50:50 (Poz:H) + Salt + Bentonite + Fluid Loss + Dispersant + SMS

DV tool with possible annular casing packer as needed is proposed at a depth of +/- 4,830'.

Casing String	TOC	% Excess
Surface	0	45
Intermediate Stage 1	4830	47
Intermediate Stage 2	0	37
Production	11743	9

Pilot Hole Cementing Specs
Pilot Hole Depth: 13067
KOP: 11794
EOC: 12,810'

Pipe Size	Pipe Depth	TOC	% Excess	Whipstock Depth	Wt. lb/gal	Weight	Yld ft ³ /sack	OH Size	No. Sacks	Blend
2-7/8"	12970	11793	20	11793	5.240	15.600	1.190	9 7/8	617	Class H Neat

4. Pressure Control Equipment

	A variance is requested for the use of a diverter on the surface casing. See attached for schematic.
--	--

BOP Installed and tested before drilling which hole?	Size	Min Required WP	Type		Tested To
9 7/8	13 5/8	5M	Annular	X	50% of working pressure
			Blind Ram		5M
			Pipe Ram	X	
			Double Ram	X	
			Other		
6 3/4	13 5/8	10M	Annular	X	50% of working pressure
			Blind Ram		10M
			Pipe Ram	X	
			Double Ram	X	
			Other		

BOP/BOPE will be tested by an independent service company to 250 psi low and the high pressure indicated above per Onshore Order 2 requirements. The System may be upgraded to a higher pressure but still tested to the working pressure listed in the table above. If the system is upgraded all the components installed will be functional and tested.

Pipe rams will be operationally checked each 24 hour period. Blind rams will be operationally checked on each trip out of the hole. These checks will be noted on the daily tour sheets. Other accessories to the BOP equipment will include a Kelly cock and floor safety valve (inside BOP) and choke lines and choke manifold. See attached schematics.

X	Formation integrity test will be performed per Onshore Order #2. On Exploratory wells or on that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.i.
---	---

X	A variance is requested for the use of a flexible choke line from the BOP to Choke Manifold. See attached for specs and hydrostatic test chart.
---	---

N	Are anchors required by manufacturer?
---	---------------------------------------

5. Mud Program

Depth	Type	Weight (ppg)	Viscosity	Water Loss
0' to 1235'	FW Spud Mud	8.30 - 8.80	30-32	N/C
1235' to 12429'	Brine Diesel Emulsion	8.50 - 9.00	30-35	N/C
12429' to 22017'	Oil Based Mud	12.00 - 12.50	50-70	N/C

Sufficient mud materials to maintain mud properties and meet minimum lost circulation and weight increase requirements will be kept on location at all times.

The Brine Emulsion is completely saturated brine fluid that ties diesel into itself to lower the weight of the fluid. The drilling fluid is completely salt saturated.

What will be used to monitor the loss or gain of fluid?	PVT/Pason/Visual Monitoring
---	-----------------------------

6. Logging and Testing Procedures**Logging, Coring and Testing**

☒	Will run GR/CNL from TD to surface (horizontal well – vertical portion of hole). Stated logs run will be in the Completion Report and submitted to the BLM.
-------------------------------------	---

☐	No logs are planned based on well control or offset log information.
--------------------------	--

☐	Drill stem test?
--------------------------	------------------

☐	Coring?
--------------------------	---------

Additional Logs Planned	Interval
-------------------------	----------

7. Drilling Conditions

Condition	
-----------	--

BH Pressure at deepest TVD	7975 psi
----------------------------	----------

Abnormal Temperature	No
----------------------	----

Hydrogen Sulfide (H₂S) monitors will be installed prior to drilling out the surface shoe. If H₂S is detected in concentrations greater than 100 ppm, the operator will comply with the provisions of Onshore Oil and Gas Order #6. If Hydrogen Sulfide is encountered, measured values and formations will be provided to the BLM.

☒	H ₂ S is present
-------------------------------------	-----------------------------

☒	H ₂ S plan is attached
-------------------------------------	-----------------------------------

8. Other Facets of Operation**9. Wellhead**

A multi-bowl wellhead system will be utilized.

After running the 10-3/4" surface casing, a 13 5/8" BOP/BOPE system with a minimum working pressure of 10000 psi will be installed on the wellhead system and will be pressure tested to 250 psi low followed by a 10000 psi test. Annular will be tested to 50% of working pressure. The pressure test will be repeated at least every 30 days, as per Onshore Order No. 2.

The multi-bowl wellhead will be installed by vendor's representative. A copy of the installation instructions has been sent to the BLM field office.

The wellhead will be installed by a third-party welder while being monitored by the wellhead vendor representative.

All BOP equipment will be tested utilizing a conventional test plug. Not a cup or J-packer type.

A solid steel body pack-off will be utilized after running and cementing the intermediate casing. After installation the pack-off and lower flange will be pressure tested to 10000 psi.


The surface casing string will be tested as per Onshore Order No. 2 to at least 0.22 psi/ft or 1500 psi, whichever is greater.

The casing string utilizing steel body pack-off will be tested to 70% of casing burst.

If well conditions dictate conventional slips will be set and BOPE will be tested to appropriate pressures based on permitted pressure requirements.

Borehole:	Well:	Field:	Structure:
ST01	Cimarex Dos Equis 11-14 Federal Com 4H	NM Lea County (NAD 83)	Cimarex Dos Equis 11-14 Federal Com 4H

Gravity & Magnetic Parameters	Surface Location	Miscellaneous
Model: HDGM 2018 Dip: 66.927° Date: 19-Dec-2018	NAD83 New Mexico State Plane, Eastern Zone, US Feet	Cimarex Dos Equis 11-14
MagDec: 6.746° FS: 47967.491nT Gravity FS: 958.434mgal (0.80665 Based)	Lat: N 32 14 16.80 Northing: 450964.248US Grid Conv: 0.3631°	Slot: Equis 11-14 TVD Ref: RKB(3687.6ft above MSL)
	Lon: W 103 39 9.83 Easting: 751763.048US Scale Fact: 0.9999998	Plan: Cimarex Dos Equis 11-14 Federal Com 4H ST01 Rev0 RM 19Dec18



Vertical Section (ft) Azim = 179.65° Scale = 1:2417.62(ft) Origin = ON/-S, OE/-W

Critical Point	MD	INCL	AZIM	TVD	VSEC	N(+)/S(-)	E(+)/W(-)	DLS
SHL (530' FNL, 370' FWL)	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Rustler	1051.00	0.00	192.46	1051.00	0.00	0.00	0.00	0.00
Salado (Top Salt)	1372.00	0.00	192.46	1372.00	0.00	0.00	0.00	0.00
Base of Salt	4678.00	0.00	192.46	4678.00	0.00	0.00	0.00	0.00
Lamar	4910.00	0.00	192.46	4910.00	0.00	0.00	0.00	0.00
Bell Canyon	4948.00	0.00	192.46	4948.00	0.00	0.00	0.00	0.00
Cherry Canyon	5855.00	0.00	192.46	5855.00	0.00	0.00	0.00	0.00
Brushy Canyon	7327.00	0.00	192.46	7327.00	0.00	0.00	0.00	0.00
Bone Spring	8818.00	0.00	192.46	8818.00	0.00	0.00	0.00	0.00
Leonard Shale	8971.00	0.00	192.46	8971.00	0.00	0.00	0.00	0.00
Avalon Shale	9297.00	0.00	192.46	9297.00	0.00	0.00	0.00	0.00
1st Bone Spring Sand	9907.00	0.00	192.46	9907.00	0.00	0.00	0.00	0.00
2nd Bone Spring Carb	10182.00	0.00	192.46	10182.00	0.00	0.00	0.00	0.00
2nd Bone Spring Sand	10503.00	0.00	192.46	10503.00	0.00	0.00	0.00	0.00
3rd Bone Spring Carb	11031.00	0.00	192.46	11031.00	0.00	0.00	0.00	0.00
KOP - Build 12°/100' DLS	11793.81	0.00	192.46	11793.81	0.00	0.00	0.00	0.00
3rd Bone Spring Sand	11830.03	4.35	192.46	11830.03	1.34	-1.34	-0.30	12.00
Build & Turn 12°/100' DLS	12085.48	35.00	192.46	12067.67	84.20	-84.32	-18.62	12.00
Wolfcamp	12151.35	42.54	188.66	12119.00	124.68	-124.84	-26.06	12.00
Build 4°/100' DLS	12428.93	75.00	179.65	12261.21	358.03	-358.28	-39.78	12.00
Wolfcamp Y SS	12552.48	79.94	179.65	12288.00	478.60	-478.85	-39.01	4.00
Wolfcamp Y SS Target	12797.70	89.75	179.65	12310.00	722.53	-722.78	-37.50	4.00
Landing Point	12810.15	90.25	179.65	12310.00	734.98	-735.23	-37.42	4.00
Wolfcamp Y SS Target	12810.15	90.25	179.65	12310.00	734.99	-735.23	-37.42	4.00
Wolfcamp Y SS	12810.15	90.25	179.65	12288.00	5798.72	-5798.87	-6.05	0.00
Cimarex Dos Equis 11-14 Federal Com 4H - PBHL (100' FSL, 330' FWL)	22017.04	90.25	179.65	12270.00	9941.78	-9941.85	19.62	0.00
Wolfcamp A1	NaN			12357.00				
Wolfcamp A2	NaN			12967.00				

Cimarex Dos Equis 11-14 Federal Com 4H ST01 Rev0 RM 19Dec18
Proposal Geodetic Report
(Non-Def Plan)



Report Date:	December 19, 2018 - 12:04 PM	Survey / DLS Computation:	Minimum Curvature / Lubinski
Client:	Cimarex	Vertical Section Azimuth:	179.645 ° (Grid North)
Field:	NM Lea County (NAD 83)	Vertical Section Origin:	0.000 ft, 0.000 ft
Structure / Slot:	Cimarex Dos Equis 11-14 Federal Com 4H / Cimarex Dos Equis 11-14 Federal Com 4H	TVD Reference Datum:	RKB
Well:	Cimarex Dos Equis 11-14 Federal Com 4H	TVD Reference Elevation:	3657.600 ft above MSL
Borehole:	ST01	Seabed / Ground Elevation:	3631.600 ft above MSL
UWI / API#:	Unknown / Unknown	Magnetic Declination:	6.746 °
Survey Name:	Cimarex Dos Equis 11-14 Federal Com 4H ST01 Rev0 RM 19Dec18	Total Gravity Field Strength:	998.4343mgm (9.80665 Based)
Survey Date:	December 19, 2018	Gravity Model:	GARM
Tort / AHD / DDI / ERD Ratio:	91.463 ° / 9945.375 ft / 6.211 / 0.808	Total Magnetic Field Strength:	47967.401 nT
Coordinate Reference System:	NAD83 New Mexico State Plane, Eastern Zone, US Feet	Magnetic Dip Angle:	59.927 °
Location Lat / Long:	N 32° 14' 16.59813", W 103° 39' 9.93101"	Declination Date:	December 19, 2018
Location Grid N/E Y/X:	N 450964.240 ftUS, E 751763.040 ftUS	Magnetic Declination Model:	HDGM 2019
CRS Grid Convergence Angle:	0.3631 °	North Reference:	Grid North
Grid Scale Factor:	0.9999598	Grid Convergence Used:	0.3631 °
Version / Patch:	2.10.753.0	Total Corr Mag North->Grid North:	6.3826 °
		Local Coord Referenced To:	Structure Reference Point

Comments	MD (ft)	Incl (°)	Azim Grid (°)	TVD (ft)	VSEC (ft)	NS (ft)	EW (ft)	DLS (°/100ft)	Northing (ftUS)	Easting (ftUS)	Latitude (N/S ° ' ")	Longitude (E/W ° ' ")
SHL [530' FNL, 370' FWL]	0.00	0.00	0.00	0.00	0.00	0.00	0.00	N/A	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	100.00	0.00	192.46	100.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	200.00	0.00	192.46	200.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	300.00	0.00	192.46	300.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	400.00	0.00	192.46	400.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	500.00	0.00	192.46	500.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	600.00	0.00	192.46	600.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	700.00	0.00	192.46	700.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	800.00	0.00	192.46	800.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	900.00	0.00	192.46	900.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	1000.00	0.00	192.46	1000.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
Rustler	1051.00	0.00	192.46	1051.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	1100.00	0.00	192.46	1100.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	1200.00	0.00	192.46	1200.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	1300.00	0.00	192.46	1300.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
Salado (Top Salt)	1372.00	0.00	192.46	1372.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	1400.00	0.00	192.46	1400.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	1500.00	0.00	192.46	1500.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	1600.00	0.00	192.46	1600.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	1700.00	0.00	192.46	1700.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	1800.00	0.00	192.46	1800.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	1900.00	0.00	192.46	1900.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	2000.00	0.00	192.46	2000.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	2100.00	0.00	192.46	2100.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93

Comments	MD (ft)	Incl (°)	Azim Grid (°)	TVD (ft)	VSEC (ft)	NS (ft)	EW (ft)	DLS (°/100ft)	Northing (ftUS)	Easting (ftUS)	Latitude (N/S ° ° °)	Longitude (E/W ° ° °)
	2200.00	0.00	192.46	2200.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	2300.00	0.00	192.46	2300.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	2400.00	0.00	192.46	2400.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	2500.00	0.00	192.46	2500.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	2600.00	0.00	192.46	2600.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	2700.00	0.00	192.46	2700.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	2800.00	0.00	192.46	2800.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	2900.00	0.00	192.46	2900.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	3000.00	0.00	192.46	3000.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	3100.00	0.00	192.46	3100.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	3200.00	0.00	192.46	3200.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	3300.00	0.00	192.46	3300.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	3400.00	0.00	192.46	3400.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	3500.00	0.00	192.46	3500.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	3600.00	0.00	192.46	3600.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	3700.00	0.00	192.46	3700.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	3800.00	0.00	192.46	3800.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	3900.00	0.00	192.46	3900.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	4000.00	0.00	192.46	4000.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	4100.00	0.00	192.46	4100.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	4200.00	0.00	192.46	4200.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	4300.00	0.00	192.46	4300.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	4400.00	0.00	192.46	4400.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	4500.00	0.00	192.46	4500.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	4600.00	0.00	192.46	4600.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
Base of Salt	4678.00	0.00	192.46	4678.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	4700.00	0.00	192.46	4700.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	4800.00	0.00	192.46	4800.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	4900.00	0.00	192.46	4900.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
Lamar	4910.00	0.00	192.46	4910.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
Bell Canyon	4948.00	0.00	192.46	4948.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	5000.00	0.00	192.46	5000.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	5100.00	0.00	192.46	5100.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	5200.00	0.00	192.46	5200.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	5300.00	0.00	192.46	5300.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	5400.00	0.00	192.46	5400.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	5500.00	0.00	192.46	5500.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	5600.00	0.00	192.46	5600.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	5700.00	0.00	192.46	5700.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	5800.00	0.00	192.46	5800.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
Cherry Canyon	5855.00	0.00	192.46	5855.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	5900.00	0.00	192.46	5900.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	6000.00	0.00	192.46	6000.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	6100.00	0.00	192.46	6100.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	6200.00	0.00	192.46	6200.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	6300.00	0.00	192.46	6300.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	6400.00	0.00	192.46	6400.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	6500.00	0.00	192.46	6500.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	6600.00	0.00	192.46	6600.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	6700.00	0.00	192.46	6700.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	6800.00	0.00	192.46	6800.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	6900.00	0.00	192.46	6900.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	7000.00	0.00	192.46	7000.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	7100.00	0.00	192.46	7100.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	7200.00	0.00	192.46	7200.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	7300.00	0.00	192.46	7300.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
Brushy Canyon	7327.00	0.00	192.46	7327.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	7400.00	0.00	192.46	7400.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	7500.00	0.00	192.46	7500.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93

Comments	MD (ft)	Incl (°)	Azim Grid (°)	TVD (ft)	VSEC (ft)	NS (ft)	EW (ft)	DLS (°/100ft)	Northing (ftUS)	Easting (ftUS)	Latitude (N/S ° ' ")	Longitude (E/W ° ' ")
	7600.00	0.00	192.46	7600.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	7700.00	0.00	192.46	7700.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	7800.00	0.00	192.46	7800.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	7900.00	0.00	192.46	7900.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	8000.00	0.00	192.46	8000.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	8100.00	0.00	192.46	8100.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	8200.00	0.00	192.46	8200.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	8300.00	0.00	192.46	8300.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	8400.00	0.00	192.46	8400.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	8500.00	0.00	192.46	8500.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	8600.00	0.00	192.46	8600.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	8700.00	0.00	192.46	8700.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	8800.00	0.00	192.46	8800.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
Bone Spring	8818.00	0.00	192.46	8818.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	8900.00	0.00	192.46	8900.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
Leonard Shale	8971.00	0.00	192.46	8971.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	9000.00	0.00	192.46	9000.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	9100.00	0.00	192.46	9100.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	9200.00	0.00	192.46	9200.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
Avalon Shale	9297.00	0.00	192.46	9297.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	9300.00	0.00	192.46	9300.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	9400.00	0.00	192.46	9400.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	9500.00	0.00	192.46	9500.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	9600.00	0.00	192.46	9600.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	9700.00	0.00	192.46	9700.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	9800.00	0.00	192.46	9800.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	9900.00	0.00	192.46	9900.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
1st Bone Spring Sand	9907.00	0.00	192.46	9907.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	10000.00	0.00	192.46	10000.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	10100.00	0.00	192.46	10100.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
2nd Bone Spring Carb	10182.00	0.00	192.46	10182.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	10200.00	0.00	192.46	10200.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	10300.00	0.00	192.46	10300.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	10400.00	0.00	192.46	10400.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	10500.00	0.00	192.46	10500.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
2nd Bone Spring Sand	10503.00	0.00	192.46	10503.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	10600.00	0.00	192.46	10600.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	10700.00	0.00	192.46	10700.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	10800.00	0.00	192.46	10800.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	10900.00	0.00	192.46	10900.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	11000.00	0.00	192.46	11000.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
3rd Bone Spring Carb	11031.00	0.00	192.46	11031.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	11100.00	0.00	192.46	11100.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	11200.00	0.00	192.46	11200.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	11300.00	0.00	192.46	11300.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	11400.00	0.00	192.46	11400.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	11500.00	0.00	192.46	11500.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	11600.00	0.00	192.46	11600.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	11700.00	0.00	192.46	11700.00	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
KOP - Build 12"/100' DLS	11793.81	0.00	192.46	11793.81	0.00	0.00	0.00	0.00	450964.24	751763.04	N 32 14 16.60 W 103 39	9.93
	11800.00	0.74	192.46	11800.00	0.04	-0.04	-0.01	12.00	450964.20	751763.03	N 32 14 16.60 W 103 39	9.93
3rd Bone Spring Sand	11830.03	4.35	192.46	11830.00	1.34	-1.34	-0.30	12.00	450962.90	751762.74	N 32 14 16.58 W 103 39	9.93
	11900.00	12.74	192.46	11899.13	11.47	-11.48	-2.54	12.00	450952.76	751760.50	N 32 14 16.48 W 103 39	9.96

Comments	MD (ft)	Incl (°)	Azim Grid (°)	TVD (ft)	VSEC (ft)	NS (ft)	EW (ft)	DLS (°/100ft)	Northing (ftUS)	Easting (ftUS)	Latitude (N/S ° ' ")	Longitude (E/W ° ' ")
	12000.00	24.74	192.46	11993.65	42.74	-42.80	-9.45	12.00	450921.44	751753.59	N 32 14 16.18	W 103 39 10.04
Build & Turn 12"/100' DLS	12085.48	35.00	192.46	12067.67	84.20	-84.32	-18.62	12.00	450879.93	751744.42	N 32 14 15.76	W 103 39 10.15
	12100.00	36.65	191.51	12079.45	92.50	-92.63	-20.39	12.00	450871.61	751742.65	N 32 14 15.68	W 103 39 10.18
Wolfcamp	12151.35	42.54	188.66	12119.00	124.68	-124.84	-26.06	12.00	450839.40	751736.98	N 32 14 15.36	W 103 39 10.24
	12200.00	48.18	186.51	12153.17	158.95	-159.14	-30.60	12.00	450805.10	751732.44	N 32 14 15.03	W 103 39 10.30
	12300.00	59.85	183.06	12211.84	239.40	-239.63	-37.15	12.00	450724.62	751725.89	N 32 14 14.23	W 103 39 10.38
	12400.00	71.60	180.35	12252.89	330.33	-330.58	-39.76	12.00	450633.68	751723.28	N 32 14 13.33	W 103 39 10.42
Build 4"/100' DLS	12428.93	75.00	179.65	12261.21	358.03	-358.28	-39.76	12.00	450605.97	751723.28	N 32 14 13.06	W 103 39 10.42
	12500.00	77.84	179.65	12277.89	427.11	-427.36	-39.33	4.00	450536.90	751723.71	N 32 14 12.37	W 103 39 10.42
Wolfcamp Y SS	12552.48	79.94	179.65	12288.00	478.60	-478.85	-39.01	4.00	450485.41	751724.03	N 32 14 11.86	W 103 39 10.42
	12600.00	81.84	179.65	12295.52	525.52	-525.77	-38.72	4.00	450438.49	751724.32	N 32 14 11.40	W 103 39 10.42
	12700.00	85.84	179.65	12306.24	624.92	-625.17	-38.10	4.00	450339.10	751724.94	N 32 14 10.41	W 103 39 10.42
Wolfcamp Y SS Target	12797.70	89.75	179.65	12310.00	722.53	-722.78	-37.50	4.00	450241.49	751725.54	N 32 14 9.45	W 103 39 10.42
Wolfcamp Y SS Target	12800.00	89.84	179.65	12310.01	724.83	-725.08	-37.49	4.00	450239.19	751725.56	N 32 14 9.43	W 103 39 10.42
Wolfcamp Y SS Target Landing Point	12810.15	90.25	179.65	12310.00	734.98	-735.23	-37.42	4.00	450229.04	751725.62	N 32 14 9.33	W 103 39 10.42
	12900.00	90.25	179.65	12309.61	824.83	-825.08	-36.87	0.00	450139.20	751726.18	N 32 14 8.44	W 103 39 10.42
	13000.00	90.25	179.65	12309.18	924.83	-925.07	-36.25	0.00	450039.21	751726.80	N 32 14 7.45	W 103 39 10.42
	13100.00	90.25	179.65	12308.74	1024.83	-1025.07	-35.63	0.00	449939.21	751727.42	N 32 14 6.46	W 103 39 10.42
	13200.00	90.25	179.65	12308.31	1124.83	-1125.07	-35.01	0.00	449839.22	751728.03	N 32 14 5.47	W 103 39 10.42
	13300.00	90.25	179.65	12307.87	1224.83	-1225.06	-34.39	0.00	449739.23	751728.65	N 32 14 4.48	W 103 39 10.42
	13400.00	90.25	179.65	12307.44	1324.83	-1325.06	-33.77	0.00	449639.23	751729.27	N 32 14 3.49	W 103 39 10.42
	13500.00	90.25	179.65	12307.00	1424.83	-1425.06	-33.15	0.00	449539.24	751729.89	N 32 14 2.50	W 103 39 10.42
	13600.00	90.25	179.65	12306.57	1524.82	-1525.06	-32.53	0.00	449439.25	751730.51	N 32 14 1.51	W 103 39 10.42
	13700.00	90.25	179.65	12306.13	1624.82	-1625.05	-31.91	0.00	449339.26	751731.13	N 32 14 0.52	W 103 39 10.42
	13800.00	90.25	179.65	12305.70	1724.82	-1725.05	-31.29	0.00	449239.26	751731.75	N 32 13 59.53	W 103 39 10.42
	13900.00	90.25	179.65	12305.27	1824.82	-1825.05	-30.67	0.00	449139.27	751732.37	N 32 13 58.54	W 103 39 10.42
	14000.00	90.25	179.65	12304.83	1924.82	-1925.04	-30.05	0.00	449039.28	751732.99	N 32 13 57.55	W 103 39 10.42
	14100.00	90.25	179.65	12304.40	2024.82	-2025.04	-29.43	0.00	448939.28	751733.61	N 32 13 56.56	W 103 39 10.42
	14200.00	90.25	179.65	12303.96	2124.82	-2125.04	-28.81	0.00	448839.29	751734.23	N 32 13 55.57	W 103 39 10.42
	14300.00	90.25	179.65	12303.53	2224.82	-2225.04	-28.19	0.00	448739.30	751734.85	N 32 13 54.58	W 103 39 10.42
	14400.00	90.25	179.65	12303.09	2324.82	-2325.03	-27.57	0.00	448639.31	751735.47	N 32 13 53.59	W 103 39 10.42
	14500.00	90.25	179.65	12302.66	2424.82	-2425.03	-26.95	0.00	448539.31	751736.09	N 32 13 52.60	W 103 39 10.42
	14600.00	90.25	179.65	12302.22	2524.82	-2525.03	-26.33	0.00	448439.32	751736.71	N 32 13 51.61	W 103 39 10.42
	14700.00	90.25	179.65	12301.79	2624.81	-2625.02	-25.71	0.00	448339.33	751737.33	N 32 13 50.63	W 103 39 10.42
	14800.00	90.25	179.65	12301.35	2724.81	-2725.02	-25.09	0.00	448239.33	751737.95	N 32 13 49.64	W 103 39 10.42
	14900.00	90.25	179.65	12300.92	2824.81	-2825.02	-24.47	0.00	448139.34	751738.57	N 32 13 48.65	W 103 39 10.42
	15000.00	90.25	179.65	12300.49	2924.81	-2925.02	-23.85	0.00	448039.35	751739.19	N 32 13 47.66	W 103 39 10.42
	15100.00	90.25	179.65	12300.05	3024.81	-3025.01	-23.23	0.00	447939.36	751739.81	N 32 13 46.67	W 103 39 10.42
	15200.00	90.25	179.65	12299.62	3124.81	-3125.01	-22.62	0.00	447839.36	751740.43	N 32 13 45.68	W 103 39 10.42
	15300.00	90.25	179.65	12299.18	3224.81	-3225.01	-22.00	0.00	447739.37	751741.05	N 32 13 44.69	W 103 39 10.42
	15400.00	90.25	179.65	12298.75	3324.81	-3325.00	-21.38	0.00	447639.38	751741.66	N 32 13 43.70	W 103 39 10.43
	15500.00	90.25	179.65	12298.31	3424.81	-3425.00	-20.76	0.00	447539.38	751742.28	N 32 13 42.71	W 103 39 10.43
	15600.00	90.25	179.65	12297.88	3524.81	-3525.00	-20.14	0.00	447439.39	751742.90	N 32 13 41.72	W 103 39 10.43
	15700.00	90.25	179.65	12297.44	3624.80	-3625.00	-19.52	0.00	447339.40	751743.52	N 32 13 40.73	W 103 39 10.43
	15800.00	90.25	179.65	12297.01	3724.80	-3724.99	-18.90	0.00	447239.40	751744.14	N 32 13 39.74	W 103 39 10.43
	15900.00	90.25	179.65	12296.58	3824.80	-3824.99	-18.28	0.00	447139.41	751744.76	N 32 13 38.75	W 103 39 10.43
	16000.00	90.25	179.65	12296.14	3924.80	-3924.99	-17.66	0.00	447039.42	751745.38	N 32 13 37.76	W 103 39 10.43
	16100.00	90.25	179.65	12295.71	4024.80	-4024.98	-17.04	0.00	446939.43	751746.00	N 32 13 36.77	W 103 39 10.43
	16200.00	90.25	179.65	12295.27	4124.80	-4124.98	-16.42	0.00	446839.43	751746.62	N 32 13 35.78	W 103 39 10.43
	16300.00	90.25	179.65	12294.84	4224.80	-4224.98	-15.80	0.00	446739.44	751747.24	N 32 13 34.79	W 103 39 10.43
	16400.00	90.25	179.65	12294.40	4324.80	-4324.98	-15.18	0.00	446639.45	751747.86	N 32 13 33.80	W 103 39 10.43
	16500.00	90.25	179.65	12293.97	4424.80	-4424.97	-14.56	0.00	446539.45	751748.48	N 32 13 32.81	W 103 39 10.43
	16600.00	90.25	179.65	12293.53	4524.80	-4524.97	-13.94	0.00	446439.46	751749.10	N 32 13 31.82	W 103 39 10.43

Comments	MD (ft)	Incl (°)	Azim Grid (°)	TVD (ft)	VSEC (ft)	NS (ft)	EW (ft)	DLS (°/100ft)	Northing (ftUS)	Easting (ftUS)	Latitude (N/S ° ' ")	Longitude (E/W ° ' ")
	16700.00	90.25	179.65	12293.10	4624.80	-4624.97	-13.32	0.00	446339.47	751749.72	N 32 13 30.84 W	103 39 10.43
	16800.00	90.25	179.65	12292.67	4724.79	-4724.96	-12.70	0.00	446239.48	751750.34	N 32 13 29.85 W	103 39 10.43
	16900.00	90.25	179.65	12292.23	4824.79	-4824.96	-12.08	0.00	446139.48	751750.96	N 32 13 28.86 W	103 39 10.43
	17000.00	90.25	179.65	12291.80	4924.79	-4924.96	-11.46	0.00	446039.49	751751.58	N 32 13 27.87 W	103 39 10.43
	17100.00	90.25	179.65	12291.36	5024.79	-5024.96	-10.84	0.00	445939.50	751752.20	N 32 13 26.88 W	103 39 10.43
	17200.00	90.25	179.65	12290.93	5124.79	-5124.95	-10.22	0.00	445839.50	751752.82	N 32 13 25.89 W	103 39 10.43
	17300.00	90.25	179.65	12290.49	5224.79	-5224.95	-9.60	0.00	445739.51	751753.44	N 32 13 24.90 W	103 39 10.43
	17400.00	90.25	179.65	12290.06	5324.79	-5324.95	-8.98	0.00	445639.52	751754.06	N 32 13 23.91 W	103 39 10.43
	17500.00	90.25	179.65	12289.62	5424.79	-5424.94	-8.37	0.00	445539.53	751754.68	N 32 13 22.92 W	103 39 10.43
	17600.00	90.25	179.65	12289.19	5524.79	-5524.94	-7.75	0.00	445439.53	751755.29	N 32 13 21.93 W	103 39 10.43
	17700.00	90.25	179.65	12288.76	5624.79	-5624.94	-7.13	0.00	445339.54	751755.91	N 32 13 20.94 W	103 39 10.43
	17800.00	90.25	179.65	12288.32	5724.78	-5724.94	-6.51	0.00	445239.55	751756.53	N 32 13 19.95 W	103 39 10.43
Wolfcamp Y SS	17873.94	90.25	179.65	12288.00	5798.72	-5798.87	-6.05	0.00	445165.61	751756.99	N 32 13 19.22 W	103 39 10.43
	17900.00	90.25	179.65	12287.89	5824.78	-5824.93	-5.89	0.00	445139.55	751757.15	N 32 13 18.96 W	103 39 10.43
	18000.00	90.25	179.65	12287.45	5924.78	-5924.93	-5.27	0.00	445039.56	751757.77	N 32 13 17.97 W	103 39 10.43
	18100.00	90.25	179.65	12287.02	6024.78	-6024.93	-4.65	0.00	444939.57	751758.39	N 32 13 16.98 W	103 39 10.43
	18200.00	90.25	179.65	12286.58	6124.78	-6124.92	-4.03	0.00	444839.57	751759.01	N 32 13 15.99 W	103 39 10.43
	18300.00	90.25	179.65	12286.15	6224.78	-6224.92	-3.41	0.00	444739.58	751759.63	N 32 13 15.00 W	103 39 10.43
	18400.00	90.25	179.65	12285.71	6324.78	-6324.92	-2.79	0.00	444639.59	751760.25	N 32 13 14.01 W	103 39 10.43
	18500.00	90.25	179.65	12285.28	6424.78	-6424.92	-2.17	0.00	444539.60	751760.87	N 32 13 13.02 W	103 39 10.43
	18600.00	90.25	179.65	12284.85	6524.78	-6524.91	-1.55	0.00	444439.60	751761.49	N 32 13 12.03 W	103 39 10.43
	18700.00	90.25	179.65	12284.41	6624.78	-6624.91	-0.93	0.00	444339.61	751762.11	N 32 13 11.05 W	103 39 10.43
	18800.00	90.25	179.65	12283.98	6724.78	-6724.91	-0.31	0.00	444239.62	751762.73	N 32 13 10.06 W	103 39 10.43
	18900.00	90.25	179.65	12283.54	6824.77	-6824.90	0.31	0.00	444139.62	751763.35	N 32 13 9.07 W	103 39 10.43
	19000.00	90.25	179.65	12283.11	6924.77	-6924.90	0.93	0.00	444039.63	751763.97	N 32 13 8.08 W	103 39 10.43
	19100.00	90.25	179.65	12282.67	7024.77	-7024.90	1.55	0.00	443939.64	751764.59	N 32 13 7.09 W	103 39 10.43
	19200.00	90.25	179.65	12282.24	7124.77	-7124.89	2.17	0.00	443839.65	751765.21	N 32 13 6.10 W	103 39 10.43
	19300.00	90.25	179.65	12281.80	7224.77	-7224.89	2.79	0.00	443739.65	751765.83	N 32 13 5.11 W	103 39 10.43
	19400.00	90.25	179.65	12281.37	7324.77	-7324.89	3.41	0.00	443639.66	751766.45	N 32 13 4.12 W	103 39 10.43
	19500.00	90.25	179.65	12280.94	7424.77	-7424.89	4.03	0.00	443539.67	751767.07	N 32 13 3.13 W	103 39 10.43
	19600.00	90.25	179.65	12280.50	7524.77	-7524.88	4.65	0.00	443439.67	751767.69	N 32 13 2.14 W	103 39 10.43
	19700.00	90.25	179.65	12280.07	7624.77	-7624.88	5.27	0.00	443339.68	751768.30	N 32 13 1.15 W	103 39 10.43
	19800.00	90.25	179.65	12279.63	7724.77	-7724.88	5.88	0.00	443239.69	751768.92	N 32 13 0.16 W	103 39 10.43
	19900.00	90.25	179.65	12279.20	7824.77	-7824.87	6.50	0.00	443139.70	751769.54	N 32 12 59.17 W	103 39 10.43
	20000.00	90.25	179.65	12278.76	7924.76	-7924.87	7.12	0.00	443039.70	751770.16	N 32 12 58.18 W	103 39 10.43
	20100.00	90.25	179.65	12278.33	8024.76	-8024.87	7.74	0.00	442939.71	751770.78	N 32 12 57.19 W	103 39 10.43
	20200.00	90.25	179.65	12277.89	8124.76	-8124.87	8.36	0.00	442839.72	751771.40	N 32 12 56.20 W	103 39 10.43
	20300.00	90.25	179.65	12277.46	8224.76	-8224.86	8.98	0.00	442739.72	751772.02	N 32 12 55.21 W	103 39 10.43
	20400.00	90.25	179.65	12277.03	8324.76	-8324.86	9.60	0.00	442639.73	751772.64	N 32 12 54.22 W	103 39 10.43
	20500.00	90.25	179.65	12276.59	8424.76	-8424.86	10.22	0.00	442539.74	751773.26	N 32 12 53.23 W	103 39 10.43
	20600.00	90.25	179.65	12276.16	8524.76	-8524.85	10.84	0.00	442439.74	751773.88	N 32 12 52.24 W	103 39 10.43
	20700.00	90.25	179.65	12275.72	8624.76	-8624.85	11.46	0.00	442339.75	751774.50	N 32 12 51.25 W	103 39 10.43
	20800.00	90.25	179.65	12275.29	8724.76	-8724.85	12.08	0.00	442239.76	751775.12	N 32 12 50.27 W	103 39 10.43
	20900.00	90.25	179.65	12274.85	8824.76	-8824.85	12.70	0.00	442139.77	751775.74	N 32 12 49.28 W	103 39 10.43
	21000.00	90.25	179.65	12274.42	8924.75	-8924.84	13.32	0.00	442039.77	751776.36	N 32 12 48.29 W	103 39 10.43
	21100.00	90.25	179.65	12273.98	9024.75	-9024.84	13.94	0.00	441939.78	751776.98	N 32 12 47.30 W	103 39 10.43
	21200.00	90.25	179.65	12273.55	9124.75	-9124.84	14.56	0.00	441839.79	751777.60	N 32 12 46.31 W	103 39 10.43
	21300.00	90.25	179.65	12273.12	9224.75	-9224.83	15.18	0.00	441739.79	751778.22	N 32 12 45.32 W	103 39 10.43
	21400.00	90.25	179.65	12272.68	9324.75	-9324.83	15.80	0.00	441639.80	751778.84	N 32 12 44.33 W	103 39 10.43
	21500.00	90.25	179.65	12272.25	9424.75	-9424.83	16.42	0.00	441539.81	751779.46	N 32 12 43.34 W	103 39 10.43
	21600.00	90.25	179.65	12271.81	9524.75	-9524.83	17.04	0.00	441439.82	751780.08	N 32 12 42.35 W	103 39 10.43
	21700.00	90.25	179.65	12271.38	9624.75	-9624.82	17.66	0.00	441339.82	751780.70	N 32 12 41.36 W	103 39 10.44
	21800.00	90.25	179.65	12270.94	9724.75	-9724.82	18.28	0.00	441239.83	751781.32	N 32 12 40.37 W	103 39 10.44
	21900.00	90.25	179.65	12270.51	9824.75	-9824.82	18.90	0.00	441139.84	751781.93	N 32 12 39.38 W	103 39 10.44
	22000.00	90.25	179.65	12270.07	9924.75	-9924.81	19.52	0.00	441039.84	751782.55	N 32 12 38.39 W	103 39 10.44

Comments	MD (ft)	Incl (°)	Azim Grid (°)	TVD (ft)	VSEC (ft)	NS (ft)	EW (ft)	DLS (°/100ft)	Northing (ftUS)	Easting (ftUS)	Latitude (N/S ° ' ")	Longitude (E/W ° ' ")
Cimarex Dos Equis 11-14 Federal Com 4H - PBHL [100' FSL, 330' FWL]	22017.04	90.25	179.65	12270.00	9941.78	-9941.85	19.62	0.00	441022.81	751782.66	N 32 12 38.22 W	103 39 10.44

Survey Type: Non-Def Plan

Survey Error Model: ISCWSA Rev 0 *** 3-D 95.000% Confidence 2.7955 sigma

Survey Program:

Description	Part	MD From (ft)	MD To (ft)	EOU Freq (ft)	Hole Size (in)	Casing Diameter (in)	Expected Max Inclination (deg)	Survey Tool Type	Borehole / Survey
	1	0.000	26.000	1/100.000	30.000	30.000		NAL_MWD_IFR1+MS-Depth Only	ST01 / Cimarex Dos Equis 11-14 Federal Com 4H ST01 Rev0 RM 19Dec18
	1	26.000	22017.035	1/100.000	30.000	30.000		NAL_MWD_IFR1+MS	ST01 / Cimarex Dos Equis 11-14 Federal Com 4H ST01 Rev0 RM



Cimarex 10M Well Control Plan

Version 1.0

BOPE Preventer Utilization

The table below displays all BHA components, drill pipe, casing, or open hole that could be present during a required shut in and the associated preventer component that would provide a barrier to flow. It is specific to the hole section that requires a 10M system. The mud system being utilized in the hole will always assumed to be the first barrier to flow. The below table, combined with the mud program, documents that two barriers to flow can be maintained at all times, independent of the rating of the annular preventer.

Drill String Element	OD	Preventer	RWP
4" Drillpipe	4"	Lower Ram 3 1/2" - 5 1/2" VBR* Upper Ram 3 1/2" - 5 1/2" VBR*	10M
4.5" Drillpipe	4.5"	Lower Ram 3 1/2" - 5 1/2" VBR* Upper Ram 3 1/2" - 5 1/2" VBR*	10M
4" HWDP Drillpipe	4"	Lower Ram 3 1/2" - 5 1/2" VBR* Upper Ram 3 1/2" - 5 1/2" VBR*	10M
4.5" HWDP Drillpipe	4.5"	Lower Ram 3 1/2" - 5 1/2" VBR* Upper Ram 3 1/2" - 5 1/2" VBR*	10M
Drill Collars (including non-magnetic)	4.75- 5.25"	Lower Ram 3 1/2" - 5 1/2" VBR* Upper Ram 3 1/2" - 5 1/2" VBR*	10M
Production Casing	5.5"	Lower Ram 3 1/2" - 5 1/2" VBR* Upper Ram 3 1/2" - 5 1/2" VBR*	10M
Production Casing	5"	Lower Ram 3 1/2" - 5 1/2" VBR* Upper Ram 3 1/2" - 5 1/2" VBR*	10M
Production Casing	4.5"	Lower Ram 3 1/2" - 5 1/2" VBR* Upper Ram 3 1/2" - 5 1/2" VBR*	10M
ALL	0-13 5/8"	Annular	5M
Open Hole		Blind Rams	10M

*VBR – Variable Bore Ram

Well Control Procedures

Proper well control response is highly specific to current well conditions and must be adapted based on environment as needed. The procedures below are given in "common" operating conditions to cover the basic and most necessary operations required during the wellbore construction. These include drilling ahead, tripping pipe, tripping BHA, running casing, and pipe out of the hole/open hole. In some of the procedures below, there will be a switch of control from the lesser RWP annular to the appropriate 10M RWP ram. The pressure at which this is done is variable based on overall well conditions that must be evaluated situationally. The pressure that control is switched may be equal to or less than the RWP but at no time will the pressure on the annular preventer exceed the RWP of the annular. The annular will be tested to 5,000 psi. This will be the RWP of the annular preventer.

Shutting In While Drilling

1. Sound alarm to alert crew
2. Space out drill string
3. Shut down pumps
4. Shut in uppermost BOPE preventer (typically the annular preventer) and open HCR.
5. Verify well is shut-in and flow has stopped
6. Notify supervisory personnel
7. Record data (SIDP, SICP, Pit Gain, and Time)
8. Hold pre-job safety meeting and discuss kill procedure

9. If pressure is anticipated to climb to the RWP of the annular preventer during kill procedure, swap control of the well to the upper pipe ram

Shutting In While Tripping

1. Sound alarm and alert crew
2. Install open, full open safety valve and close valve
3. Shut in uppermost BOPE preventer (typically the annular preventer) and open HCR.
4. Verify well is shut-in and flow has stopped
5. Notify supervisory personnel
6. Record data (SIDP, SICP, Pit Gain, and Time)
7. Hold pre-job safety meeting and discuss kill procedure
8. If pressure is anticipated to climb to the RWP of the annular preventer during kill procedure, swap control of the well to the upper pipe ram

Shutting In While Running Casing

1. Sound alarm and alert crew
2. Install circulating swedge. Close high pressure, low torque valves.
3. Shut in uppermost BOPE preventer (typically the annular preventer) and open HCR.
4. Verify well is shut-in and flow has stopped
5. Notify supervisory personnel
6. Record data (SIDP, SICP, Pit Gain, and Time)
7. Hold Pre-job safety meeting and discuss kill procedure
8. If pressure is anticipated to climb to the RWP of the annular preventer during kill procedure, swap control of the well to the upper pipe ram

Shutting in while out of hole

1. Sound alarm
2. Shut-in well: close blind rams
3. Verify well is shut-in and monitor pressures
4. Notify supervisory personnel
5. Record data (SIDP, SICP, Pit Gain, and Time)
6. Hold Pre-job safety meeting and discuss kill procedure

Shutting in prior to pulling BHA through stack

1. Prior to pulling last joint of drill pipe thru the stack space out and check flow. If flowing see steps below.
2. Sound alarm and alert crew
3. Install open, full open safety valve and close valve
4. Shut in upper pipe ram and open HCR.

5. Verify well is shut-in and flow has stopped
6. Notify supervisory personnel
7. Record data (SIDP, SICP, Pit Gain, and Time)
8. Hold pre-job safety meeting and discuss kill procedure

Shutting in while BHA is in the stack and ram preventer and combo immediately available

1. Sound alarm and alert crew
2. Stab Crossover and install open, full open safety valve and close valve
3. Space out drill string with upset just beneath the compatible pipe ram.
4. Shut in upper compatible pipe ram and open HCR.
5. Verify well is shut-in and flow has stopped
6. Notify supervisory personnel
7. Record data (SIDP, SICP, Pit Gain, and Time)
8. Hold pre-job safety meeting and discuss kill procedure

Shutting in while BHA is in the stack and no ram preventer or combo immediately available

1. Sound alarm and alert crew
2. If possible pick up high enough, to pull string clear and follow "Open Hole" scenario
3. If not possible to pick up high enough:
 1. Stab Crossover, make up one joint/stand of drill pipe, and install open, full open safety valve and close valve
4. Space out drill string with upset just beneath the compatible pipe ram.
5. Shut in upper compatible pipe ram and open HCR.
6. Verify well is shut-in and flow has stopped
7. Notify supervisory personnel
8. Record data (SIDP, SICP, Pit Gain, and Time)
9. Hold pre-job safety meeting and discuss kill procedure

PECOS DISTRICT

DRILLING CONDITIONS OF APPROVAL

OPERATOR'S NAME:	CIMAREX ENERGY COMPANY
LEASE NO.:	NMNM0001917
WELL NAME & NO.:	4H- DOS EQUIS 11-14 FEDERAL COM
SURFACE HOLE FOOTAGE:	530'/N & 370'/W
BOTTOM HOLE FOOTAGE:	100'/S & 330'/W
LOCATION:	Section.11.,T24S., R.32E., NMP
COUNTY:	LEA County, New Mexico

COA

All previous COAs still apply expect the following:

H2S	☐ Yes	☒ No	
Potash	☒ None	☐ Secretary	☐ R-111-P
Cave/Karst Potential	☒ Low	☐ Medium	☐ High
Variance	☐ None	☒ Flex Hose	☐ Other
Wellhead	☐ Conventional	☒ Multibowl	☐ Both
Other	☐ 4 String Area	☐ Capitan Reef	☐ WIPP

A. Hydrogen Sulfide

Hydrogen Sulfide (H2S) monitors shall be installed prior to drilling out the surface shoe. If H2S is detected in concentrations greater than 100 ppm, the Hydrogen Sulfide area shall meet Onshore Order 6 requirements, which includes equipment and personnel/public protection items. If Hydrogen Sulfide is encountered, provide measured values and formations to the BLM.

B. CASING

1. The **10-3/4** inch surface casing shall be set at approximately **1235** feet (a minimum of 25 feet into the Rustler Anhydrite and above the salt) and cemented to the surface.
 - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.
 - b. Wait on cement (WOC) time for a primary cement job will be a minimum of **8 hours** or 500 pounds compressive strength, whichever is greater. (This is to include the lead cement)

- c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.
- d. If cement falls back, remedial cementing will be done prior to drilling out that string.

Operator shall filled 1/3rd casing with fluid while running intermediate casing to maintain collapse safety factor.

2. The minimum required fill of cement behind the 7-5/8 inch intermediate casing is:

- Cement to surface. If cement does not circulate see B.1.a, c-d above.

Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to cave/karst or potash.

The pilot hole plugging procedure is approved as written. Note plug tops on subsequent drilling report.

Pilot hole is required to have a plug at the bottom of the hole. If two plugs are set, the BLM is to be contacted (575-361-2822) prior to tag of bottom plug, which must be a minimum of 200' in length. Operator can set one plug from bottom of pilot hole to kick-off point and save the WOC time for tagging the first plug. Note plug tops on subsequent drilling report.

During drilling of intermediate hole from 250-1900 feet fresh water will be used unless lost circulation is encountered then air may be used concurrently to lighten the hydrostatic pressure.

Varaince is approved for annual spacing between 7 5/8" x 5 1/2" casing.

3. The minimum required fill of cement behind the 5-1/2 inch production casing is:

- Cement should tie-back at least 200 feet into previous casing string. Operator shall provide method of verification. **Additional cement maybe required. Excess calculates to 14%.**

C. PRESSURE CONTROL

1. Variance approved to use flex line from BOP to choke manifold. Manufacturer's specification to be readily available. No external damage to flex line. Flex line to be installed as straight as possible (no hard bends).
2. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be **5000 (5M) psi.**
3. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the intermediate casing shoe shall be **10,000 (10M) psi**

Variance approved to use a 5M annular. The annular must be tested to full working pressure (5000 psi.)

GENERAL REQUIREMENTS

The BLM is to be notified in advance for a representative to witness:

- a. Spudding well (minimum of 24 hours)
- b. Setting and/or Cementing of all casing strings (minimum of 4 hours)
- c. BOPE tests (minimum of 4 hours)

☒ Chaves and Roosevelt Counties

Call the Roswell Field Office, 2909 West Second St., Roswell NM 88201.

During office hours call (575) 627-0272.

After office hours call (575)

☒ Eddy County

Call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220,
(575) 361-2822

☒ Lea County

Call the Hobbs Field Station, 414 West Taylor, Hobbs NM 88240, (575)
393-3612

1. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval.
 - a. In the event the operator has proposed to drill multiple wells utilizing a skid/walking rig. Operator shall secure the wellbore on the current well, after installing and testing the wellhead, by installing a blind flange of like pressure rating to the wellhead and a pressure gauge that can be monitored while drilling is performed on the other well(s).
 - b. When the operator proposes to set surface casing with Spudder Rig
 - Notify the BLM when moving in and removing the Spudder Rig.
 - Notify the BLM when moving in the 2nd Rig. Rig to be moved in within 90 days of notification that Spudder Rig has left the location.
 - BOP/BOPE test to be conducted per Onshore Oil and Gas Order No. 2 as soon as 2nd Rig is rigged up on well.
2. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works are located, this does not include the dog house or stairway area.
3. The record of the drilling rate along with the GR/N well log (one log per well pad is acceptable) run from TD to surface (horizontal well – vertical portion of hole) shall be submitted to the BLM office as well as all other logs run on the borehole 30 days

from completion. If available, a digital copy of the logs is to be submitted in addition to the paper copies. The Rustler top and top and bottom of Salt are to be recorded on the Completion Report.

A. CASING

1. Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size or are Non-API. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.). The initial wellhead installed on the well will remain on the well with spools used as needed.
2. Wait on cement (WOC) for Potash Areas: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi for all cement blends, 2) until cement has been in place at least 24 hours. WOC time will be recorded in the driller's log. The casing integrity test can be done (prior to the cement setting up) immediately after bumping the plug.
3. Wait on cement (WOC) for Water Basin: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi at the shoe, 2) until cement has been in place at least 8 hours. WOC time will be recorded in the driller's log. See individual casing strings for details regarding lead cement slurry requirements. The casing integrity test can be done (prior to the cement setting up) immediately after bumping the plug.
4. Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. Have well specific cement details onsite prior to pumping the cement for each casing string.
5. No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.
6. On that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Formation at the shoe shall be tested to a minimum of the mud weight equivalent anticipated to control the formation pressure to the next casing depth or at total depth of the well. This test shall be performed before drilling more than 20 feet of new hole.
7. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a

larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.

8. Whenever a casing string is cemented in the R-111-P potash area, the NMOCD requirements shall be followed.

B. PRESSURE CONTROL

1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in Onshore Oil and Gas Order No. 2 and API RP 53 Sec. 17.
2. If a variance is approved for a flexible hose to be installed from the BOP to the choke manifold, the following requirements apply: The flex line must meet the requirements of API 16C. Check condition of flexible line from BOP to choke manifold, replace if exterior is damaged or if line fails test. Line to be as straight as possible with no hard bends and is to be anchored according to Manufacturer's requirements. The flexible hose can be exchanged with a hose of equal size and equal or greater pressure rating. Anchor requirements, specification sheet and hydrostatic pressure test certification matching the hose in service, to be onsite for review. These documents shall be posted in the company man's trailer and on the rig floor.
3. 5M or higher system requires an HCR valve, remote kill line and annular to match. The remote kill line is to be installed prior to testing the system and tested to stack pressure.
4. If the operator has proposed a multi-bowl wellhead assembly in the APD. The following requirements must be met:
 - a. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
 - b. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
 - c. Manufacturer representative shall install the test plug for the initial BOP test.
 - d. If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
 - e. Whenever any seal subject to test pressure is broken, all the tests in OOGO2.III.A.2.i must be followed.
5. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.

- a. In a water basin, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. The casing cut-off and BOP installation can be initiated four hours after installing the slips, which will be approximately six hours after bumping the plug. For those casing strings not using slips, the minimum wait time before cut-off is eight hours after bumping the plug. BOP/BOPE testing can begin after cut-off or once cement reaches 500 psi compressive strength (including lead when specified), whichever is greater. However, if the float does not hold, cut-off cannot be initiated until cement reaches 500 psi compressive strength (including lead when specified).
- b. In potash areas, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. For all casing strings, casing cut-off and BOP installation can be initiated at twelve hours after bumping the plug. However, **no tests** shall commence until the cement has had a minimum of 24 hours setup time, except the casing pressure test can be initiated immediately after bumping the plug (only applies to single stage cement jobs).
- c. The tests shall be done by an independent service company utilizing a test plug. The results of the test shall be reported to the appropriate BLM office.
- d. The test shall be run on a 5000 psi chart for a 2-3M BOP/BOP, on a 10000 psi chart for a 5M BOP/BOPE and on a 15000 psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one hour chart. A circular chart shall have a maximum 2 hour clock. If a twelve hour or twenty-four hour chart is used, tester shall make a notation that it is run with a two hour clock.
- e. All tests are required to be recorded on a calibrated test chart. A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.
- f. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes. This test shall be performed prior to the test at full stack pressure.
- g. BOP/BOPE must be tested by an independent service company within 500 feet of the top of the Wolfcamp formation if the time between the setting of the intermediate casing and reaching this depth exceeds 20 days. This test does not exclude the test prior to drilling out the casing shoe as per Onshore Order No. 2.

C. DRILLING MUD

Mud system monitoring equipment, with derrick floor indicators and visual and audio alarms, shall be operating before drilling into the Wolfcamp formation, and shall be used until production casing is run and cemented.

D. WASTE MATERIAL AND FLUIDS

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area.

Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.

Waste Minimization Plan (WMP)

In the interest of resource development, submission of additional well gas capture development plan information is deferred but may be required by the BLM Authorized Officer at a later date.

ZS 010818