

R/P
[H]

HOBBS OCD

FORM APPROVED
OMB No. 1004-0137
Expires: January 31, 2018

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

APR 16 2019

**APPLICATION FOR PERMIT TO DRILL OR REENTER
RECEIVED**

1a. Type of work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER		7. If Unit or CA Agreement, Name and No.	
1b. Type of Well: <input checked="" type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Other		8. Lease Name and Well No. JUNIPER FED.COM 25 36 34 091H (725776)	
1c. Type of Completion: <input type="checkbox"/> Hydraulic Fracturing <input checked="" type="checkbox"/> Single Zone <input type="checkbox"/> Multiple Zone		9. API Well No. 70-025-4587	
2. Name of Operator AMEREDEV OPERATING LLC (772224)		10. Field and Pool, or Exploratory JAL / WOLFGAMP WEST B5 (98150)	
3a. Address 5707 Southwest Parkway, Building 1, Suite 275 Austin TX		3b. Phone No. (include area code) (737)300-4700	
4. Location of Well (Report location clearly and in accordance with any State requirements. *) At surface LOT D / 230 FNL / 270 FWL / LAT 32.07894 / LONG -103.26068 At proposed prod. zone LOT D / 50 FNL / 200 FWL / LAT 32.10845 / LONG -103.26091		11. Sec., T. R. M. or Blk. and Survey or Area SEC 3 / T26S / R36E / NMP	
14. Distance in miles and direction from nearest town or post office* 5 miles		12. County or Parish LEA	13. State NM
15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) 230 feet	16. No of acres in lease 1280	17. Spacing Unit dedicated to this well 640	
18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft. 8570 feet	19. Proposed Depth 11280 feet / 22233 feet	20. BLM/BIA Bond No. in file FED: NMB001478	
21. Elevations (Show whether DF, KDB, RT, GL, etc.) 2992 feet	22. Approximate date work will start* 03/01/2019	23. Estimated duration 90 days	

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, and the Hydraulic Fracturing rule per 43 CFR 3162.3-3 (as applicable)

- | | |
|--|---|
| 1. Well plat certified by a registered surveyor. | 4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above). |
| 2. A Drilling Plan. | 5. Operator certification. |
| 3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO must be filed with the appropriate Forest Service Office). | 6. Such other site specific information and/or plans as may be requested by the BLM. |

25. Signature (Electronic Submission)	Name (Printed/Typed) Christie Hanna / Ph: (737)300-4723	Date 08/02/2018
Title Senior Engineering Technician		
Approved by (Signature) (Electronic Submission)	Name (Printed/Typed) Cody Layton / Ph: (575)234-5959	Date 03/22/2019
Title Assistant Field Manager Lands & Minerals		

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

GCP Rec 04/16/19

KZ
04/16/19

APPROVED WITH CONDITIONS

INSTRUCTIONS

GENERAL: This form is designed for submitting proposals to perform certain well operations, as indicated on Federal and Indian lands and leases for action by appropriate Federal agencies, pursuant to applicable Federal laws and regulations. Any necessary special instructions concerning the use of this form and the number of copies to be submitted, particularly with regard to local, area, or regional procedures and practices, either are shown below or will be issued by, or may be obtained from local Federal offices.

ITEM I: If the proposal is to redrill to the same reservoir at a different subsurface location or to a new reservoir, use this form with appropriate notations. Consult applicable Federal regulations concerning subsequent work proposals or reports on the well.

ITEM 4: Locations on Federal or Indian land should be described in accordance with Federal requirements. Consult local Federal offices for specific instructions.

ITEM 14: Needed only when location of well cannot readily be found by road from the land or lease description. A plat, or plats, separate or on the reverse side, showing the roads to, and the surveyed location of, the well, and any other required information, should be furnished when required by Federal agency offices.

ITEMS 15 AND 18: If well is to be, or has been directionally drilled, give distances for subsurface location of hole in any present or objective productive zone.

ITEM 22: Consult applicable Federal regulations, or appropriate officials, concerning approval of the proposal before operations are started.

ITEM 24: If the proposal will involve hydraulic fracturing operations, you must comply with 43 CFR 3162.3-3, including providing information about the protection of usable water. Operators should provide the best available information about all formations containing water and their depths. This information could include data and interpretation of resistivity logs run on nearby wells. Information may also be obtained from state or tribal regulatory agencies and from local BLM offices.

NOTICES

The Privacy Act of 1974 and regulation in 43 CFR 2.48(d) provide that you be furnished the following information in connection with information required by this application.

AUTHORITY: 30 U.S.C. 181 et seq., 25 U.S.C. 396; 43 CFR 3160

PRINCIPAL PURPOSES: The information will be used to: (1) process and evaluate your application for a permit to drill a new oil, gas, or service well or to reenter a plugged and abandoned well; and (2) document, for administrative use, information for the management, disposal and use of National Resource Lands and resources including (a) analyzing your proposal to discover and extract the Federal or Indian resources encountered; (b) reviewing procedures and equipment and the projected impact on the land involved; and (c) evaluating the effects of the proposed operation on the surface and subsurface water and other environmental impacts.

ROUTINE USE: Information from the record and/or the record will be transferred to appropriate Federal, State, and local or foreign agencies, when relevant to civil, criminal or regulatory investigations or prosecution, in connection with congressional inquiries and for regulatory responsibilities.

EFFECT OF NOT PROVIDING INFORMATION: Filing of this application and disclosure of the information is mandatory only if you elect to initiate a drilling or reentry operation on an oil and gas lease.

The Paperwork Reduction Act of 1995 requires us to inform you that:

The BLM collects this information to allow evaluation of the technical, safety, and environmental factors involved with drilling for oil and/or gas on Federal and Indian oil and gas leases. This information will be used to analyze and approve applications. Response to this request is mandatory only if the operator elects to initiate drilling or reentry operations on an oil and gas lease. The BLM would like you to know that you do not have to respond to this or any other Federal agency-sponsored information collection unless it displays a currently valid OMB control number.

BURDEN HOURS STATEMENT: Public reporting burden for this form is estimated to average 8 hours per response, including the time for reviewing instructions, gathering and maintaining data, and completing and reviewing the form. Direct comments regarding the burden estimate or any other aspect of this form to U.S. Department of the Interior, Bureau of Land Management (1004-0137), Bureau Information Connection Clearance Officer (WO-630), 1849 C Street, N.W., Mail Stop 401 LS, Washington, D.C. 20240.

Additional Operator Remarks

Location of Well

1. SHL: LOT D / 230 FNL / 270 FWL / TWSP: 26S / RANGE: 36E / SECTION: 3 / LAT: 32.07894 / LONG: -103.26068 (TVD: 0 feet, MD: 0 feet)
PPP: SWSW / 0 FSL / 145 FWL / TWSP: 25S / RANGE: 36E / SECTION: 27 / LAT: 32.09408 / LONG: -103.26091 (TVD: 11280 feet, MD: 17005 feet)
PPP: SWSW / 0 FSL / 201 FWL / TWSP: 25S / RANGE: 36E / SECTION: 34 / LAT: 32.07967 / LONG: -103.2609 (TVD: 11277 feet, MD: 11760 feet)
BHL: LOT D / 50 FNL / 200 FWL / TWSP: 25S / RANGE: 36E / SECTION: 27 / LAT: 32.10845 / LONG: -103.26091 (TVD: 11280 feet, MD: 22233 feet)

BLM Point of Contact

Name: Tenille Ortiz

Title: Legal Instruments Examiner

Phone: 5752342224

Email: tortiz@blm.gov

Review and Appeal Rights

A person contesting a decision shall request a State Director review. This request must be filed within 20 working days of receipt of the Notice with the appropriate State Director (see 43 CFR 3165.3). The State Director review decision may be appealed to the Interior Board of Land Appeals, 801 North Quincy Street, Suite 300, Arlington, VA 22203 (see 43 CFR 3165.4). Contact the above listed Bureau of Land Management office for further information.

PECOS DISTRICT DRILLING CONDITIONS OF APPROVAL

OPERATOR'S NAME:	Ameredev Operating, LLC
LEASE NO.:	NMNM-136233
WELL NAME & NO.:	Juniper Fed Com 25 36 34 91H
SURFACE HOLE FOOTAGE:	0230' FNL & 0270' FWL
BOTTOM HOLE FOOTAGE	0050' FNL & 0200' FWL Sec. 27, T. 25 S., R 36 E.
LOCATION:	Section 03, T. 26 S., R 36 E., NMPM
COUNTY:	County, New Mexico

Operator to submit sundry for 4 string contingency casing design option after receiving approved permit.

Communitization Agreement

The operator will submit a Communitization Agreement to the Carlsbad Field Office, 620 E Greene St. Carlsbad, New Mexico 88220, at least 90 days before the anticipated date of first production from a well subject to a spacing order issued by the New Mexico Oil Conservation Division. The Communitization Agreement will include the signatures of all working interest owners in all Federal and Indian leases subject to the Communitization Agreement (i.e., operating rights owners and lessees of record), or certification that the operator has obtained the written signatures of all such owners and will make those signatures available to the BLM immediately upon request.

If the operator does not comply with this condition of approval, the BLM may take enforcement actions that include, but are not limited to, those specified in 43 CFR 3163.1.

In addition, the well sign shall include the surface and bottom hole lease numbers. When the Communitization Agreement number is known, it shall also be on the sign.

A. DRILLING OPERATIONS REQUIREMENTS

The BLM is to be notified in advance for a representative to witness:

- a. Spudding well (minimum of 24 hours)
- b. Setting and/or Cementing of all casing strings (minimum of 4 hours)
- c. BOPE tests (minimum of 4 hours)

Lea County

Call the Hobbs Field Station, 414 West Taylor, Hobbs NM 88240,

(575) 3933612

1. **Hydrogen Sulfide (H₂S) monitors shall be installed prior to drilling out the surface shoe. If H₂S is detected in concentrations greater than 100 ppm, the Hydrogen Sulfide area shall meet Onshore Order 6 requirements, which includes equipment and personnel/public protection items. If Hydrogen Sulfide is encountered, provide measured values and formations to the BLM.**
2. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval. **If the drilling rig is removed without approval – an Incident of Non-Compliance will be written and will be a “Major” violation.**
3. **Alternative when using skid/walking rig**
The operator has proposed to drill multiple wells utilizing a skid/walking rig. Operator shall secure the wellbore on the current well, after installing and testing the wellhead, by installing a blind flange of like pressure rating to the wellhead and a pressure gauge that can be monitored while drilling is performed on the other wells.
4. Option – Setting surface casing with Surface Rig
 - a. Notify the BLM when removing the Surface Services Rig.
 - b. Notify the BLM when moving in the H&P Flex Rig. Rig to be moved in within 60 days of notification that Surface Rig has left the location. Failure to notify or have rig on location within 60 days will result in an Incident of Non-Compliance.
 - c. Once the H&P Flex Rig is on location, it shall not be removed from over the hole without prior approval unless the production casing has been run and cemented or the well has been properly plugged. **If the drilling rig is removed without approval – an Incident of Non-Compliance will be written and will be a “Major” violation.**
 - d. BOP/BOPE test to be conducted per Onshore Oil and Gas Order No. 2 as soon as H&P Flex Rig is rigged up on well. CIT for the surface casing shall be performed and results recorded on subsequent sundry – pressure to be 1200 psi.
5. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works is located, this does not include the dog house or stairway area.

6. **The record of the drilling rate along with the GR/N well log run from TD to surface (horizontal well – vertical portion of hole) shall be submitted to the BLM office as well as all other logs run on the borehole 30 days from completion. If available, a digital copy of the logs is to be submitted in addition to the paper copies. The Rustler top and top and bottom of Salt are to be recorded on the Completion Report.**

B. CASING

Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size or are Non-API. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.). The initial wellhead installed on the well will remain on the well with spools used as needed.

Centralizers required on surface casing per Onshore Order 2.III.B.1.f.

Wait on cement (WOC) for Water Basin:

After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi at the shoe, 2) until cement has been in place at least 8 hours. WOC time will be recorded in the driller's log. See individual casing strings for details regarding lead cement slurry requirements.

Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. Have well specific cement details onsite prior to pumping the cement for each casing string.

No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.

Capitan Reef

Possible water flows in the Castile, Salado, and Capitan Reef.

Possible lost circulation in the Rustler, Red Beds, and Delaware.

Abnormal pressures may be encountered within the 3rd Bone Spring and Wolfcamp Formations.

1. The 13-3/8 inch surface casing shall be set at approximately 1888 feet (a minimum of 25 feet into the Rustler Anhydrite and above the salt) and cemented to the surface. **If salt is encountered, set casing at least 25 feet above the salt.**
 - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.
 - b. **Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry.**
 - c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.
 - d. If cement falls back, remedial cementing will be done prior to drilling out that string.

Formation below the 13-3/8" shoe to be tested according to Onshore Order 2.III.B.1.i. Test to be done as a mud equivalency test using the mud weight necessary for the pore pressure of the formation below the shoe and the mud weight for the bottom of the hole. Report results to BLM office.

Special Capitan Reef requirements:

If lost circulation (50% or greater) occurs below the Base of the Salt, the operator shall do the following in addition to switching to their four string contingency design:

- **Switch to fresh water mud to protect the Capitan Reef and use fresh water mud until setting the intermediate casing. The appropriate BLM office is to be notified for a PET to witness the switch to fresh water.**
- **Daily drilling reports from the Base of the Salt to the setting of the intermediate casing are to be submitted to the BLM CFO engineering staff via e-mail by 0800 hours each morning. Any lost circulation encountered is to be recorded on these drilling reports. The daily drilling report should show mud volume per shift/tour. Failure to submit these reports will result in an Incidence of Non-Compliance being issued for failure to comply with the Conditions of Approval. If not already planned, the operator shall run a caliper survey for the intermediate well bore and submit to the appropriate BLM office.**

9-5/8" Intermediate casing shall be kept fluid filled while running into hole to meet BLM minimum collapse requirements.

2. The minimum required fill of cement behind the 9-5/8 inch intermediate casing is:

Operator has proposed DV tool at depth of 5013', but will adjust cement proportionately if moved. DV tool shall be set a minimum of 50' below previous shoe and a minimum of 200' above current shoe. Operator shall submit sundry if DV tool depth cannot be set in this range. If an ECP is used, it is to be set a minimum of 50' below the shoe to provide cement across the shoe. If it cannot be set below the shoe, a CBL shall be run to verify cement coverage.

a. First stage to DV tool:___

- Cement to circulate. If cement does not circulate, contact the appropriate BLM office before proceeding with second stage cement job. Operator should have plans as to how they will achieve circulation on the next stage.**

b. Second stage above DV tool:

- Cement to surface. If cement does not circulate, contact the appropriate BLM office. Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to Capitan Reef. Excess calculates to 7% - Additional cement may be required.**

Formation below the 9-5/8" shoe to be tested according to Onshore Order 2.III.B.1.i. Test to be done as a mud equivalency test using the mud weight necessary for the

pore pressure of the formation below the shoe (not the mud weight required to prevent dissolving the salt formation) and the mud weight for the bottom of the hole. Report results to BLM office.

Centralizers required through the curve and a minimum of one every other joint.

3. The minimum required fill of cement behind the 5-1/2 inch production casing is:
 - Cement should tie-back at least **50 feet above the Capitan Reef** (Top of Capitan Reef estimated at 3734'). Operator shall provide method of verification.
4. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.

C. PRESSURE CONTROL

1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in Onshore Oil and Gas Order No. 2 and API 53.
2. Variance approved to use flex line from BOP to choke manifold. Check condition of flexible line from BOP to choke manifold, replace if exterior is damaged or if line fails test. Line to be as straight as possible with no hard bends and is to be anchored according to Manufacturer's requirements. The flexible hose can be exchanged with a hose of equal size and equal or greater pressure rating. **Anchor requirements, specification sheet and hydrostatic pressure test certification matching the hose in service, to be onsite for review. These documents shall be posted in the company man's trailer and on the rig floor.** If the BLM inspector questions the straightness of the hose, a BLM engineer will be contacted and will review in the field or via picture supplied by inspector to determine if changes are required (operator shall expect delays if this occurs).
3. **Operator has proposed a multi-bowl wellhead assembly. This assembly will only be tested when installed on the surface casing. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be psi.**
 - a. **Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.**

- b. **If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.**
- c. **Manufacturer representative shall install the test plug for the initial BOP test.**
- d. **Operator shall perform the intermediate casing integrity test to 70% of the casing burst. This will test the multi-bowl seals.**
- e. **Operator shall perform the 9-5/8" and 7-5/8" casing integrity tests to 70% of the casing burst. This will test the multi-bowl seals.**
- f. **If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.**

Variance approved to use a 5M annular. The annular must be tested to full working pressure (5000 psi.)

10M system requires an HCR valve, remote kill line and annular to match. The remote kill line is to be installed prior to testing the system and tested to stack pressure.

- 4. The appropriate BLM office shall be notified a minimum of hours in advance for a representative to witness the tests.
 - a. In a water basin, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. The casing cut-off and BOP installation can be initiated four hours after installing the slips, which will be approximately six hours after bumping the plug. For those casing strings not using slips, the minimum wait time before cut-off is eight hours after bumping the plug. BOP/BOPE testing can begin after cut-off or once cement reaches 500 psi compressive strength (including lead when specified), whichever is greater. However, if the float does not hold, cut-off cannot be initiated until cement reaches 500 psi compressive strength (including lead when specified).
 - a. The tests shall be done by an independent service company utilizing a test plug not a cup or J-packer.
 - b. The test shall be run on a 5000 psi chart for a 2-3M BOP/BOP, on a 10000 psi chart for a 5M BOP/BOPE and on a 15000 psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one hour chart. A circular chart shall

have a maximum 2 hour clock. If a twelve hour or twenty-four hour chart is used, tester shall make a notation that it is run with a two hour clock.

- c. The results of the test shall be reported to the appropriate BLM office.
- d. All tests are required to be recorded on a calibrated test chart. **A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.**
- e. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug. This test shall be performed prior to the test at full stack pressure.

D. DRILL STEM TEST

If drill stem tests are performed, Onshore Order 2.III.D shall be followed.

E. WASTE MATERIAL AND FLUIDS

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area.

Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.

JAM 031519

**PECOS DISTRICT
SURFACE USE
CONDITIONS OF APPROVAL**

OPERATOR'S NAME:	AMEREDEV OPERATING LLC
LEASE NO.:	NMNM 137804
WELL NAME & NO.:	JUNIPER FED 25 36 34 091H
SURFACE HOLE FOOTAGE:	230'/N & 330'/W
BOTTOM HOLE FOOTAGE:	200'/N & 660'/W
LOCATION:	SECTION 03, T26S, R36E, NMPM
COUNTY:	LEA

TABLE OF CONTENTS

Standard Conditions of Approval (COA) apply to this APD. If any deviations to these standards exist or special COAs are required, the section with the deviation or requirement will be checked below.

- General Provisions**
- Permit Expiration**
- Archaeology, Paleontology, and Historical Sites**
- Noxious Weeds**
- Special Requirements**
 - Hydrology
- Construction**
 - Notification
 - Topsoil
 - Closed Loop System
 - Federal Mineral Material Pits
 - Well Pads
 - Roads
- Road Section Diagram**
- Production (Post Drilling)**
 - Well Structures & Facilities
 - Pipelines
 - Electric Lines
- Interim Reclamation**
- Final Abandonment & Reclamation**

I. GENERAL PROVISIONS

The approval of the Application For Permit To Drill (APD) is in compliance with all applicable laws and regulations: 43 Code of Federal Regulations 3160, the lease terms, Onshore Oil and Gas Orders, Notices To Lessees, New Mexico Oil Conservation Division (NMOCD) Rules, National Historical Preservation Act As Amended, and instructions and orders of the Authorized Officer. Any request for a variance shall be submitted to the Authorized Officer on Form 3160-5, Sundry Notices and Report on Wells.

II. PERMIT EXPIRATION

If the permit terminates prior to drilling and drilling cannot be commenced within 60 days after expiration, an operator is required to submit Form 3160-5, Sundry Notices and Reports on Wells, requesting surface reclamation requirements for any surface disturbance. However, if the operator will be able to initiate drilling within 60 days after the expiration of the permit, the operator must have set the conductor pipe in order to allow for an extension of 60 days beyond the expiration date of the APD. (Filing of a Sundry Notice is required for this 60 day extension.)

III. ARCHAEOLOGICAL, PALEONTOLOGY & HISTORICAL SITES

Any cultural and/or paleontological resource discovered by the operator or by any person working on the operator's behalf shall immediately report such findings to the Authorized Officer. The operator is fully accountable for the actions of their contractors and subcontractors. The operator shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery shall be made by the Authorized Officer to determine the appropriate actions that shall be required to prevent the loss of significant cultural or scientific values of the discovery. The operator shall be held responsible for the cost of the proper mitigation measures that the Authorized Officer assesses after consultation with the operator on the evaluation and decisions of the discovery. Any unauthorized collection or disturbance of cultural or paleontological resources may result in a shutdown order by the Authorized Officer.

IV. NOXIOUS WEEDS

The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes the roads, pads, associated pipeline corridor, and adjacent land affected by the establishment of weeds due to this action. The operator shall consult

with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

Approval Date: 03/22/2019

v. SPECIAL REQUIREMENT(S)

Hydrology:

Tank battery locations will be lined and bermed. A 20 mil permanent liner will be installed with a 4 oz. felt backing to prevent tears or punctures. Tank battery berms must be large enough to contain 1 ½ times the content of the largest tank or 24 hour production, whichever is greater. Automatic shut off, check valves, or similar systems will be installed for tanks to minimize the effects of catastrophic line failures used in production or drilling.

A leak detection plan will be submitted to the BLM Carlsbad Field Office for approval prior to pipeline installation. The method could incorporate gauges to detect pressure drops, situating valves and lines so they can be visually inspected periodically or installing electronic sensors to alarm when a leak is present. The leak detection plan will incorporate an automatic shut off system that will be installed for proposed pipelines to minimize the effects of an undesirable event.

Electric Lines: Any water erosion that may occur due to the construction of overhead electric line and during the life of the power line will be quickly corrected and proper measures will be taken to prevent future erosion.

VI. CONSTRUCTION

A. NOTIFICATION

The BLM shall administer compliance and monitor construction of the access road and well pad. Notify the at least 3 working days prior to commencing construction of the access road and/or well pad.

When construction operations are being conducted on this well, the operator shall have the approved APD and Conditions of Approval (COA) on the well site and they shall be made available upon request by the Authorized Officer.

B. TOPSOIL

The operator shall strip the top portion of the soil (root zone) from the entire well pad area and stockpile the topsoil along the edge of the well pad as depicted in the APD. The root zone is typically six (6) inches in depth. All the stockpiled topsoil will be redistributed over the interim reclamation areas. Topsoil shall not be used for berming the pad or facilities. For final reclamation, the topsoil shall be spread over the entire pad area for seeding preparation.

Other subsoil (below six inches) stockpiles must be completely segregated from the topsoil stockpile. Large rocks or subsoil clods (not evident in the surrounding terrain) must be buried within the approved area for interim and final reclamation.

C. CLOSED LOOP SYSTEM

Tanks are required for drilling operations: No Pits.

The operator shall properly dispose of drilling contents at an authorized disposal site.

D. FEDERAL MINERAL MATERIALS PIT

Payment shall be made to the BLM prior to removal of any federal mineral materials. Call the .

E. WELL PAD SURFACING

Surfacing of the well pad is not required.

If the operator elects to surface the well pad, the surfacing material may be required to be removed at the time of reclamation. The well pad shall be constructed in a manner which

creates the smallest possible surface disturbance, consistent with safety and operational needs.

F. EXCLOSURE FENCING (CELLARS & PITS)

Exclosure Fencing

The operator will install and maintain exclosure fencing for all open well cellars to prevent access to public, livestock, and large forms of wildlife before and after drilling operations until the pit is free of fluids and the operator initiates backfilling. (For examples of exclosure fencing design, refer to BLM's Oil and Gas Gold Book, Exclosure Fence Illustrations, Figure 1, Page 18.)

G. ON LEASE ACCESS ROADS

Road Width

The access road shall have a driving surface that creates the smallest possible surface disturbance and does not exceed fourteen (14) feet in width. The maximum width of surface disturbance, when constructing the access road, shall not exceed twenty-five (25) feet.

Surfacing

Surfacing material is not required on the new access road driving surface. If the operator elects to surface the new access road or pad, the surfacing material may be required to be removed at the time of reclamation.

Where possible, no improvements should be made on the unsurfaced access road other than to remove vegetation as necessary, road irregularities, safety issues, or to fill low areas that may sustain standing water.

The Authorized Officer reserves the right to require surfacing of any portion of the access road at any time deemed necessary. Surfacing may be required in the event the road deteriorates, erodes, road traffic increases, or it is determined to be beneficial for future field development. The surfacing depth and type of material will be determined at the time of notification.

Crowning

Crowning shall be done on the access road driving surface. The road crown shall have a grade of approximately 2% (i.e., a 1" crown on a 14' wide road). The road shall conform to Figure 1; cross section and plans for typical road construction.

Ditching

Ditching shall be required on both sides of the road.


Turnouts

Vehicle turnouts shall be constructed on the road. Turnouts shall be intervisible with interval spacing distance less than 1000 feet. Turnouts shall conform to Figure 1; cross section and plans for typical road construction.

Drainage

Drainage control systems shall be constructed on the entire length of road (e.g. ditches, sidehill outsloping and insloping, leadoff ditches, culvert installation, and low water crossings).

A typical lead-off ditch has a minimum depth of 1 foot below and a berm of 6 inches above natural ground level. The berm shall be on the down-slope side of the lead-off ditch.



All lead-off ditches shall be graded to drain water with a 1 percent minimum to 3 percent maximum ditch slope. The spacing interval are variable for lead-off ditches and shall be determined according to the formula for spacing intervals of lead-off ditches, but may be amended depending upon existing soil types and centerline road slope (in %);

Cattle guards

An appropriately sized cattle guard sufficient to carry out the project shall be installed and maintained at fence/road crossings. Any existing cattle guards on the access road route shall be repaired or replaced if they are damaged or have deteriorated beyond practical use. The operator shall be responsible for the condition of the existing cattle guards that are in place and are utilized during lease operations.

Fence Requirement

Where entry is granted across a fence line, the fence shall be braced and tied off on both sides of the passageway prior to cutting. The operator shall notify the private surface landowner or the grazing allotment holder prior to crossing any fences.

Public Access

Public access on this road shall not be restricted by the operator without specific written approval granted by the Authorized Officer.

Approval Date: 03/22/2019

Construction Steps

1. Salvage topsoil
2. Construct road

3. Redistribute topsoil
4. Revegetate slopes




Figure 1. Cross-sections and plans for typical road sections representative of BLM resource or FS local and higher-class roads.

VII. PRODUCTION (POST DRILLING)

A. WELL STRUCTURES & FACILITIES

Placement of Production Facilities

Production facilities should be placed on the well pad to allow for maximum interim recontouring and revegetation of the well location.

Exclosure Netting (Open-top Tanks)

Immediately following active drilling or completion operations, the operator will take actions necessary to prevent wildlife and livestock access, including avian wildlife, to all open-topped tanks that contain or have the potential to contain salinity sufficient to cause harm to wildlife or livestock, hydrocarbons, or Resource Conservation and Recovery Act of 1976-exempt hazardous substances. At a minimum, the operator will net, screen, or cover open-topped tanks to exclude wildlife and livestock and prevent mortality. If the operator uses netting, the operator will cover and secure the open portion of the tank to prevent wildlife entry. The operator will net, screen, or cover the tanks until the operator removes the tanks from the location or the tanks no longer contain substances that could be harmful to wildlife or livestock. Use a maximum netting mesh size of 1 ½ inches. The netting must not be in contact with fluids and must not have holes or gaps.

Chemical and Fuel Secondary Containment and Exclosure Screening

The operator will prevent all hazardous, poisonous, flammable, and toxic substances from coming into contact with soil and water. At a minimum, the operator will install and maintain an impervious secondary containment system for any tank or barrel containing hazardous, poisonous, flammable, or toxic substances sufficient to contain the contents of the tank or barrel and any drips, leaks, and anticipated precipitation. The operator will dispose of fluids within the containment system that do not meet applicable state or U. S. Environmental Protection Agency livestock water standards in accordance with state law; the operator must not drain the fluids to the soil or ground. The operator will design, construct, and maintain all secondary containment systems to prevent wildlife and livestock exposure to harmful substances. At a minimum, the operator will install effective wildlife and livestock exclosure systems such as fencing, netting, expanded metal mesh, lids, and grate covers. Use a maximum netting mesh size of 1 ½ inches.

Open-Vent Exhaust Stack Exclosures

The operator will construct, modify, equip, and maintain all open-vent exhaust stacks on production equipment to prevent birds and bats from entering, and to discourage perching, roosting, and nesting. (*Recommended exclosure structures on open-vent exhaust stacks are in the shape of a cone.*) Production equipment includes, but may not be limited to, tanks, heater-treaters, separators, dehydrators, flare stacks, in-line units, and compressor mufflers.

Containment Structures

Proposed production facilities such as storage tanks and other vessels will have a secondary containment structure that is constructed to hold the capacity of 1.5 times the largest tank, plus freeboard to account for precipitation, unless more stringent protective requirements are deemed necessary.

Painting Requirement

All above-ground structures including meter housing that are not subject to safety requirements shall be painted a flat non-reflective paint color, **Shale Green** from the BLM Standard Environmental Color Chart (CC-001: June 2008).

B. PIPELINES

BURIED PIPELINE STIPULATIONS

A copy of the application (Grant, APD, or Sundry Notice) and attachments, including conditions of approval, survey plat and/or map, will be on location during construction. BLM personnel may request to you a copy of your permit during construction to ensure compliance with all stipulations.

Holder agrees to comply with the following stipulations to the satisfaction of the Authorized Officer:

1. The Holder shall indemnify the United States against any liability for damage to life or property arising from the occupancy or use of public lands under this grant.
2. The Holder shall comply with all applicable Federal laws and regulations existing or hereafter enacted or promulgated. In any event, the holder shall comply with the Toxic Substances Control Act of 1976 as amended, 15 USC 2601 et seq. (1982) with regards to any toxic substances that are used, generated by or stored on the right-of-way or on facilities authorized under this right-of-way grant. (See 40 CFR Part 702-799 and especially, provisions on polychlorinated biphenyls, 40 CFR 761.1-761.193.) Additionally, any release of toxic substances (leaks, spills, etc.) in excess of the reportable quantity established by 40 CFR Part 117 shall be reported as required by the Comprehensive Environmental Response, Compensation, and Liability Act, section 102b. A copy of any report required or requested by any Federal agency or State government as a result of a reportable release or spill of any toxic substances shall be furnished to the authorized officer concurrent with the filing of the reports to the involved Federal agency or State government.
3. The holder agrees to indemnify the United States against any liability arising from the release of any hazardous substance or hazardous waste (as these terms are defined in the Comprehensive Environmental Response, Compensation and Liability Act of 1980, 42 U.S.C. 9601, et seq. or the Resource Conservation and Recovery Act, 42 U.S.C.6901, et seq.) on the Right-of-Way (unless the release or threatened release is wholly unrelated to the Right-of-Way holder's activity on the Right-of-Way), or resulting from the activity of the Right-of-Way holder on the Right-of-Way.

This agreement applies without regard to whether a release is caused by the holder, its agent, or unrelated third parties.

4. If, during any phase of the construction, operation, maintenance, or termination of the pipeline, any oil or other pollutant should be discharged from the pipeline system, impacting Federal lands, the control and total removal, disposal, and cleaning up of such oil or other pollutant, wherever found, shall be the responsibility of holder, regardless of fault. Upon failure of holder to control, dispose of, or clean up such discharge on or affecting Federal lands, or to repair all damages resulting therefrom, on the Federal lands, the Authorized Officer may take such measures as he deems necessary to control and clean up the discharge and restore the area, including where appropriate, the aquatic environment and fish and wildlife habitats, at the full expense of the holder. Such action by the Authorized Officer shall not relieve holder of any responsibility as provided herein.

5. All construction and maintenance activity will be confined to the authorized right-of-way.

6. The pipeline will be buried with a minimum cover of 36 inches between the top of the pipe and ground level.

7. The maximum allowable disturbance for construction in this right-of-way will be 30 feet:

- Blading of vegetation within the right-of-way will be allowed: maximum width of blading operations will not exceed 20 feet. The trench is included in this area. (*Blading is defined as the complete removal of brush and ground vegetation.*)
- Clearing of brush species within the right-of-way will be allowed: maximum width of clearing operations will not exceed 30 feet. The trench and bladed area are included in this area. (*Clearing is defined as the removal of brush while leaving ground vegetation (grasses, weeds, etc.) intact. Clearing is best accomplished by holding the blade 4 to 6 inches above the ground surface.*)
- The remaining area of the right-of-way (if any) shall only be disturbed by compressing the vegetation. (*Compressing can be caused by vehicle tires, placement of equipment, etc.*)

8. The holder shall stockpile an adequate amount of topsoil where blading is allowed. The topsoil to be stripped is approximately 6 inches in depth. The topsoil will be segregated from other spoil piles from trench construction. The topsoil will be evenly distributed over the bladed area for the preparation of seeding.

9. The holder shall minimize disturbance to existing fences and other improvements on public lands. The holder is required to promptly repair improvements to at least their former state. Functional use of these improvements will be maintained at all times. The holder will contact the owner of any improvements prior to disturbing them. When necessary to pass through a fence line, the fence shall be braced on both sides of the passageway prior to cutting of the fence. No permanent gates will be allowed unless approved by the Authorized Officer.

10. Vegetation, soil, and rocks left as a result of construction or maintenance activity will be randomly scattered on this right-of-way and will not be left in rows, piles, or berms, unless otherwise approved by the Authorized Officer. The entire right-of-way shall be recontoured to match the surrounding landscape. The backfilled soil shall be compacted and a 6 inch berm will be left over the ditch line to allow for settling back to grade.

11. In those areas where erosion control structures are required to stabilize soil conditions, the holder will install such structures as are suitable for the specific soil conditions being encountered and which are in accordance with sound resource management practices.

12. The holder will reseed all disturbed areas. Seeding will be done according to the attached seeding requirements, using the following seed mix.

- | | |
|--|--|
| <input type="checkbox"/> seed mixture 1 | <input type="checkbox"/> seed mixture 3 |
| <input checked="" type="checkbox"/> seed mixture 2 | <input type="checkbox"/> seed mixture 4 |
| <input type="checkbox"/> seed mixture 2/LPC | <input type="checkbox"/> Aplomado Falcon Mixture |

13. All above-ground structures not subject to safety requirements shall be painted by the holder to blend with the natural color of the landscape. The paint used shall be color which simulates "Standard Environmental Colors" – **Shale Green**, Munsell Soil Color No. 5Y 4/2.

14. The pipeline will be identified by signs at the point of origin and completion of the right-of-way and at all road crossings. At a minimum, signs will state the holder's name, BLM serial number, and the product being transported. All signs and information thereon will be posted in a permanent, conspicuous manner, and will be maintained in a legible condition for the life of the pipeline.

15. The holder shall not use the pipeline route as a road for purposes other than routine maintenance as determined necessary by the Authorized Officer in consultation with the holder before maintenance begins. The holder will take whatever steps are necessary to ensure that the pipeline route is not used as a roadway. As determined necessary during the life of the pipeline, the Authorized Officer may ask the holder to construct temporary deterrence structures.

16. Any cultural and/or paleontological resources (historic or prehistoric site or object) discovered by the holder, or any person working on his behalf, on public or Federal land shall be immediately reported to the Authorized Officer. Holder shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery will be made by the Authorized Officer to determine appropriate actions to prevent the loss of significant cultural or scientific values. The holder will be responsible for the cost of evaluation and any decision as to proper mitigation measures will be made by the Authorized Officer after consulting with the holder.

17. The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes associated roads, pipeline corridor and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

18. Escape Ramps - The operator will construct and maintain pipeline/utility trenches [that are not otherwise fenced, screened, or netted] to prevent livestock, wildlife, and humans from becoming entrapped. At a minimum, the operator will construct and maintain escape ramps, ladders, or other methods of avian and terrestrial wildlife escape in the trenches according to the following criteria:

- a. Any trench left open for eight (8) hours or less is not required to have escape ramps; however, before the trench is backfilled, the contractor/operator shall inspect the trench for wildlife, remove all trapped wildlife, and release them at least 100 yards from the trench.
- b. For trenches left open for eight (8) hours or more, earthen escape ramps (built at no more than a 30 degree slope and spaced no more than 500 feet apart) shall be placed in the trench.

C. ELECTRIC LINES

STANDARD STIPULATIONS FOR OVERHEAD ELECTRIC DISTRIBUTION LINES

A copy of the grant and attachments, including stipulations, survey plat and/or map, will be on location during construction. BLM personnel may request to you a copy of your permit during construction to ensure compliance with all stipulations.

Holder agrees to comply with the following stipulations to the satisfaction of the Authorized Officer:

1. The holder shall indemnify the United States against any liability for damage to life or property arising from the occupancy or use of public lands under this grant.

2. The holder shall comply with all applicable Federal laws and regulations existing or hereafter enacted or promulgated. In any event, the holder shall comply with the Toxic Substances Control Act of 1976 as amended, 15 USC 2601 et seq. (1982) with regards to any toxic substances that are used, generated by or stored on the right-of-way or on facilities authorized under this right-of-way grant. (See 40 CFR, Part 702-799 and especially, provisions on polychlorinated biphenyls, 40 CFR 761.1-761.193.)

Additionally, any release of toxic substances (leaks, spills, etc.) in excess of the reportable quantity established by 40 CFR, Part 117 shall be reported as required by the Comprehensive Environmental Response, Compensation, and Liability Act, section 102b. A copy of any report required or requested by any Federal agency or State government as a result of a reportable release or spill of any toxic substances shall be furnished to the authorized officer concurrent with the filing of the reports to the involved Federal agency or State government.

3. The holder agrees to indemnify the United States against any liability arising from the release of any hazardous substance or hazardous waste (as these terms are defined in the Comprehensive Environmental Response, Compensation and Liability Act of 1980, 42 U.S.C. 9601, et seq. or the Resource Conservation and Recovery Act, 42 U.S.C. 6901, et seq.) on the Right-of-Way (unless the release or threatened release is wholly unrelated to the Right-of-Way holder's activity on the Right-of-Way), or resulting from the activity of the Right-of-Way holder on the Right-of-Way. This agreement applies without regard to whether a release is caused by the holder, its agent, or unrelated third parties.

4. There will be no clearing or blading of the right-of-way unless otherwise agreed to in writing by the Authorized Officer.

5. Power lines shall be constructed and designed in accordance to standards outlined in "Suggested Practices for Avian Protection on Power lines: The State of the Art in 2006" Edison Electric Institute, APLIC, and the California Energy Commission 2006 . The holder shall assume the burden and expense of proving that pole designs not shown in the above publication deter raptor perching, roosting, and nesting. Such proof shall be provided by a raptor expert approved by the Authorized Officer. The BLM reserves the right to require modification or additions to all powerline structures placed on this right-of-way, should they be necessary to ensure the safety of large perching birds. Such modifications and/or additions shall be made by the holder without liability or expense to the United States.

Raptor deterrence will consist of but not limited to the following: triangle perch discouragers shall be placed on each side of the cross arms and a nonconductive perching deterrence shall be placed on all vertical poles that extend past the cross arms.

6. The holder shall minimize disturbance to existing fences and other improvements on public lands. The holder is required to promptly repair improvements to at least their former state. Functional use of these improvements will be maintained at all times. The

holder will contact the owner of any improvements prior to disturbing them. When necessary to pass through a fence line, the fence shall be braced on both sides of the passageway prior to cutting the fence. No permanent gates will be allowed unless approved by the Authorized Officer.

7. The BLM serial number assigned to this authorization shall be posted in a permanent, conspicuous manner where the power line crosses roads and at all serviced facilities. Numbers will be at least two inches high and will be affixed to the pole nearest the road crossing and at the facilities served.

8. Upon cancellation, relinquishment, or expiration of this grant, the holder shall comply with those abandonment procedures as prescribed by the Authorized Officer.

9. All surface structures (poles, lines, transformers, etc.) shall be removed within 180 days of abandonment, relinquishment, or termination of use of the serviced facility or facilities or within 180 days of abandonment, relinquishment, cancellation, or expiration of this grant, whichever comes first. This will not apply where the power line extends service to an active, adjoining facility or facilities.

10. Any cultural and/or paleontological resource (historic or prehistoric site or object) discovered by the holder, or any person working on his behalf, on public or Federal land shall be immediately reported to the Authorized Officer. Holder shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery will be made by the Authorized Officer to determine appropriate actions to prevent the loss of significant cultural or scientific values. The holder will be responsible for the cost of evaluation and any decision as to proper mitigation measures will be made by the Authorized Officer after consulting with the holder.

11. Special Stipulations:

- For reclamation remove poles, lines, transformer, etc. and dispose of properly.
- Fill in any holes from the poles removed.

VIII. INTERIM RECLAMATION

During the life of the development, all disturbed areas not needed for active support of production operations should undergo interim reclamation in order to minimize the environmental impacts of development on other resources and uses.

Within six (6) months of well completion, operators should work with BLM surface management specialists (Jim Amos: 575-234-5909) to devise the best strategies to reduce the size of the location. Interim reclamation should allow for remedial well operations, as well as safe and efficient removal of oil and gas.

During reclamation, the removal of caliche is important to increasing the success of revegetating the site. Removed caliche that is free of contaminants may be used for road repairs, fire walls or for building other roads and locations. In order to operate the well or complete workover operations, it may be necessary to drive, park and operate on restored interim vegetation within the previously disturbed area. Disturbing revegetated areas for production or workover operations will be allowed. If there is significant disturbance and loss of vegetation, the area will need to be revegetated. Communicate with the appropriate BLM office for any exceptions/exemptions if needed.

All disturbed areas after they have been satisfactorily prepared need to be reseeded with the seed mixture provided below.

Upon completion of interim reclamation, the operator shall submit a Sundry Notices and Reports on Wells, Subsequent Report of Reclamation (Form 3160-5).

IX. FINAL ABANDONMENT & RECLAMATION

At final abandonment, well locations, production facilities, and access roads must undergo "final" reclamation so that the character and productivity of the land are restored.

Earthwork for final reclamation must be completed within six (6) months of well plugging. All pads, pits, facility locations and roads must be reclaimed to a satisfactory revegetated, safe, and stable condition, unless an agreement is made with the landowner or BLM to keep the road and/or pad intact.

After all disturbed areas have been satisfactorily prepared, these areas need to be revegetated with the seed mixture provided below. Seeding should be accomplished by drilling on the contour whenever practical or by other approved methods. Seeding may need to be repeated until revegetation is successful, as determined by the BLM.

Operators shall contact a BLM surface protection specialist prior to surface abandonment operations for site specific objectives (Jim Amos: 575-234-5909).

Seed Mixture 2, for Sandy Sites

The holder shall seed all disturbed areas with the seed mixture listed below. The seed mixture shall be planted in the amounts specified in pounds of pure live seed (PLS)* per acre. There shall be no primary or secondary noxious weeds in the seed mixture. Seed

will be tested and the viability testing of seed will be done in accordance with State law (s) and within nine (9) months prior to purchase. Commercial seed will be either certified or registered seed. The seed container will be tagged in accordance with State law(s) and available for inspection by the authorized officer.

Seed will be planted using a drill equipped with a depth regulator to ensure proper depth of planting where drilling is possible. The seed mixture will be evenly and uniformly planted over the disturbed area (smaller/heavier seeds have a tendency to drop the bottom of the drill and are planted first). The holder shall take appropriate measures to ensure this does not occur. Where drilling is not possible, seed will be broadcast and the area shall be raked or chained to cover the seed. When broadcasting the seed, the pounds per acre are to be doubled. The seeding will be repeated until a satisfactory stand is established as determined by the authorized officer. Evaluation of growth will not be made before completion of at least one full growing season after seeding.

Species to be planted in pounds of pure live seed* per acre:

<u>Species</u>	<u>lb/acre</u>
Sand dropseed (Sporobolus cryptandrus)	1.0
Sand love grass (Eragrostis trichodes)	1.0
Plains bristlegrass (Setaria macrostachya)	2.0

*Pounds of pure live seed:

Pounds of seed x percent purity x percent germination = pounds pure live seed



U.S. Department of the Interior
BUREAU OF LAND MANAGEMENT

Operator Certification Data Report

03/25/2019

Operator Certification

I hereby certify that I, or someone under my direct supervision, have inspected the drill site and access route proposed herein; that I am familiar with the conditions which currently exist; that I have full knowledge of state and Federal laws applicable to this operation; that the statements made in this APD package are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for the operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filing of false statements.

NAME: Christie Hanna

Signed on: 02/05/2019

Title: Senior Engineering Technician

Street Address: 5707 Southwest Parkway, Building 1, Suite 275

City: Austin

State: TX

Zip: 78735

Phone: (737)300-4723

Email address: channa@ameredev.com

Field Representative

Representative Name:

Street Address:

City:

State:

Zip:

Phone:

Email address:



APD ID: 10400031762

Submission Date: 08/02/2018

Operator Name: AMEREDEV OPERATING LLC

Well Name: JUNIPER FED COM 25 36 34

Well Number: 091H

Show Final Text

Well Type: OIL WELL

Well Work Type: Drill

Section 1 - General

APD ID: 10400031762

Tie to previous NOS? 10400024490

Submission Date: 08/02/2018

BLM Office: CARLSBAD

User: Christie Hanna

Title: Senior Engineering Technician

Federal/Indian APD: FED

Is the first lease penetrated for production Federal or Indian? FED

Lease number: NMNM136233

Lease Acres: 1280

Surface access agreement in place?

Allotted?

Reservation:

Agreement in place? NO

Federal or Indian agreement:

Agreement number:

Agreement name:

Keep application confidential? NO

Permitting Agent? NO

APD Operator: AMEREDEV OPERATING LLC

Operator letter of designation:

Operator Info

Operator Organization Name: AMEREDEV OPERATING LLC

Operator Address: 5707 Southwest Parkway, Building 1, Suite 275

Zip: 78735

Operator PO Box:

Operator City: Austin

State: TX

Operator Phone: (737)300-4700

Operator Internet Address:

Section 2 - Well Information

Well in Master Development Plan? NO

Master Development Plan name:

Well in Master SUPO? NO

Master SUPO name:

Well in Master Drilling Plan? NO

Master Drilling Plan name:

Well Name: JUNIPER FED COM 25 36 34

Well Number: 091H

Well API Number:

Field/Pool or Exploratory? Field and Pool

Field Name: JAL

Pool Name: WOLFCAMP
WEST

Is the proposed well in an area containing other mineral resources? USEABLE WATER,NATURAL GAS,CO2,OIL

Operator Name: AMEREDEV OPERATING LLC

Well Name: JUNIPER FED COM 25 36 34

Well Number: 091H

Describe other minerals:

Is the proposed well in a Helium production area? N Use Existing Well Pad? NO New surface disturbance?

Type of Well Pad: MULTIPLE WELL

Multiple Well Pad Name:

Number: 091H

Well Class: HORIZONTAL

JUNIPER

Number of Legs: 1

Well Work Type: Drill

Well Type: OIL WELL

Describe Well Type:

Well sub-Type: INFILL

Describe sub-type:

Distance to town: 5 Miles

Distance to nearest well: 8570 FT

Distance to lease line: 230 FT

Reservoir well spacing assigned acres Measurement: 640 Acres

Well plat: Juniper_Fed_Com_25_36_43_091H__GAS_CAPTURE_PLAN_20180629095644.pdf

JUNIPER_FED_COM_25_36_34_091H__BLM_LEASE_MAP_20190205114142.pdf

JUNIPER_FED_COM_25_36_34_091H__C_102_REV_SIG_20190205114143.pdf

JUNIPER_FED_COM_25_36_34_091H__EXH_2AB_20190205114144.pdf

JUNIPER_FED_COM_25_36_34_091H__VICINITY_MAP_20190205114144.pdf

Well work start Date: 03/01/2019

Duration: 90 DAYS

Section 3 - Well Location Table

Survey Type: RECTANGULAR

Describe Survey Type:

Datum: NAD83

Vertical Datum: NAVD88

Survey number: 18329

	NS-Foot	NS Indicator	EW-Foot	EW Indicator	Twsp	Range	Section	Aliquot/Lot/Tract	Latitude	Longitude	County	State	Meridian	Lease Type	Lease Number	Elevation	MD	TVD
SHL Leg #1	230	FNL	270	FWL	26S	36E	3	Lot D	32.07894	- 103.2606 8	LEA	NEW MEXI CO	NEW MEXI CO	F	NMNM 137804	299 2	0	0


Operator Name: AMEREDEV OPERATING LLC

Well Name: JUNIPER FED COM 25 36 34

Well Number: 091H

	NS-Foot	NS Indicator	EW-Foot	EW Indicator	Twsp	Range	Section	Aliquot/Lot/Tract	Latitude	Longitude	County	State	Meridian	Lease Type	Lease Number	Elevation	MD	TVD
KOP Leg #1	649	FNL	307	FWL	26S	36E	3	Aliquot NWN W	32.07779	- 103.2605 8	LEA	NEW MEXI CO	NEW MEXI CO	F	NMNM 137804	- 778 3	107 97	107 75
PPP Leg #1	0	FSL	201	FWL	25S	36E	34	Aliquot SWS W	32.07967	- 103.2609	LEA	NEW MEXI CO	NEW MEXI CO	F	NMNM 136233	- 828 5	117 60	112 77
PPP Leg #1	0	FSL	145	FWL	25S	36E	27	Aliquot SWS W	32.09408	- 103.2609 1	LEA	NEW MEXI CO	NEW MEXI CO	F	NMNM 136232	- 828 8	170 05	112 80
EXIT Leg #1	50	FNL	200	FWL	25S	36E	27	Aliquot SWS W	32.10845	- 103.2609 1	LEA	NEW MEXI CO	NEW MEXI CO	F	NMNM 136232	- 828 8	222 33	112 80
BHL Leg #1	50	FNL	200	FWL	25S	36E	27	Lot D	32.10845	- 103.2609 1	LEA	NEW MEXI CO	NEW MEXI CO	F	NMNM 136232	- 828 8	222 33	112 80

LOCATION & ELEVATION VERIFICATION MAP




AMEREDEV OPERATING, LLC

LEASE NAME & WELL NO.: JUNIPER FED COM 25 36 34 091H

SECTION 3 TWP 26-S RGE 36-E SURVEY N.M.P.M.
 COUNTY LEA STATE NM ELEVATION 2992'
 DESCRIPTION 230' FNL & 270' FWL

LATITUDE N 32.0789485 LONGITUDE W 103.2606876



THIS EASEMENT/SERVITUDE LOCATION SHOWN HEREON HAS BEEN SURVEYED ON THE GROUND UNDER MY SUPERVISION AND PREPARED ACCORDING TO THE EVIDENCE FOUND AT THE TIME OF SURVEY, AND DATA PROVIDED BY AMEREDEV OPERATING LLC. THIS CERTIFICATION IS MADE AND LIMITED TO THOSE PERSONS OR ENTITIES SHOWN ON THE FACE OF THIS PLAT AND IS NON-TRANSFERABLE. THIS SURVEY IS CERTIFIED FOR THIS TRANSACTION ONLY.

ALL BEARINGS, DISTANCES, AND COORDINATE VALUES CONTAINED HEREON ARE GRID BASED UPON THE NEW MEXICO STATE PLANE COORDINATE SYSTEM, EAST ZONE OF THE NORTH AMERICAN DATUM 1983, U.S. SURVEY FEET.




TOPOGRAPHIC
 LOYALTY INNOVATION LEGACY

1400 EVERMAN PARKWAY, Ste. 148 • FT. WORTH, TEXAS 76140
 TELEPHONE: (817) 744-7512 • FAX (817) 744-7554
 2803 NORTH BIG SPRING • MIDLAND, TEXAS 79705
 TELEPHONE: (432) 882-1653 OR (800) 767-1653 • FAX (432) 882-1743
 WWW.TOPOGRAPHIC.COM

AMEREDEV

AMEREDEV OPERATING, LLC EXHIBIT 2A

SECTION 3, TOWNSHIP 26-S, RANGE 36-E, N.M.P.M.
LEA COUNTY, NEW MEXICO



BOTTOM HOLE LOCATION
NEW MEXICO EAST
NAD 1983
X=873390
Y=404846
LAT.: N 32.1084590
LONG.: W 103.2609165

LAST TAKE POINT
NEW MEXICO EAST
NAD 1983
X=873391
Y=404796
LAT.: N 32.1083216
LONG.: W 103.2609166

FIRST TAKE POINT
NEW MEXICO EAST
NAD 1983
X=873495
Y=394440
LAT.: N 32.0798557
LONG.: W 103.2609139

SURFACE LOCATION
NEW MEXICO EAST
NAD 1983
X=873568
Y=394110
LAT.: N 32.0789485
LONG.: W 103.2606876

SCALE: 1" = 2000'
0' 1000' 2000'


LEASE NAME & WELL NO.: JUNIPER FED COM 25 36 34 091H

SECTION 3 TWP 26-S RGE 36-E SURVEY N.M.P.M.
COUNTY LEA STATE NM
DESCRIPTION 230' FNL & 270' FWL

DISTANCE & DIRECTION
FROM INT. OF 3RD ST./NM-205/FRYING PAN RD. & NM-128, HEAD SOUTH ON
3RD ST./NM-205/FRYING PAN RD. ±5.8 MILES, THENCE WEST (RIGHT) ON
ANTHONY RD ±3.4 MILES, THENCE NORTH (RIGHT) TO CONTINUE ON
ANTHONY RD ±0.3 MILES, THENCE EAST (RIGHT) ON PIPELINE RD. ±0.3
MILES, THENCE NORTH (LEFT) ON A LEASE RD. ±1.0 MILES, THENCE EAST
(RIGHT) ON A PROPOSED RD. ±1.1 MILES TO A POINT ±315 FEET NORTHWEST
OF THE LOCATION.

ALL BEARINGS, DISTANCES, AND COORDINATE VALUES CONTAINED HEREON ARE GRID
BASED UPON THE NEW MEXICO COORDINATE SYSTEM OF 1983, EAST ZONE, U.S. SURVEY
FEET


THIS EASEMENT/SERVITUDE LOCATION SHOWN HEREON HAS BEEN SURVEYED ON THE GROUND
UNDER MY SUPERVISION AND PREPARED ACCORDING TO THE EVIDENCE FOUND AT THE TIME OF
SURVEY, AND DATA PROVIDED BY AMEREDEV OPERATING LLC. THIS CERTIFICATION IS MADE AND
LIMITED TO THOSE PERSONS OR ENTITIES SHOWN ON THE FACE OF THIS PLAT AND IS
NON-TRANSFERABLE. THIS SURVEY IS CERTIFIED FOR THIS TRANSACTION ONLY.



PROPOSED ROAD - 5687

JUNIPER FED COM 25 36 34 121H
JUNIPER FED COM 25 36 34 081H
JUNIPER FED COM 25 36 34 111H
JUNIPER FED COM 25 36 34 091H
PIMENTO FED COM 26 36 03 111H
PIMENTO FED COM 26 36 03 121H

DETAIL VIEW
SCALE: 1" = 300'



Michael Blake Brown, P.S. No. 18329
NOVEMBER 30, 2018

TOPOGRAPHIC
LOYALTY INNOVATION LEGACY


1400 EVERMAN PARKWAY, Ste. 146 - FT. WORTH, TEXAS 76140
TELEPHONE: (817) 744-7512 - FAX: (817) 744-7534
2803 NORTH BIG SPRING - MIDLAND, TEXAS 79705
TELEPHONE: (432) 682-1653 OR (800) 767-1653 - FAX: (432) 682-1743
WWW.TOPOGRAPHIC.COM

EXHIBIT 2B




AMEREDEV OPERATING, LLC
 SECTION 3, TOWNSHIP 26-S, RANGE 36-E, N.M.P.M.
 LEA COUNTY, NEW MEXICO

DETAIL VIEW
 SCALE: 1" = 100'



LEASE NAME & WELL NO.: JUNIPER FED COM 25 36 34 091H
 091H LATITUDE N 32.0789485 091H LONGITUDE W 103.2606876

CENTER OF PAD IS 230' FNL 290' FWL




ALL BEARINGS, DISTANCES, AND COORDINATE VALUES CONTAINED HEREON ARE GRID BASED UPON THE NEW MEXICO STATE PLANE COORDINATE SYSTEM, EAST ZONE OF THE NORTH AMERICAN DATUM 1983, U.S. SURVEY FEET

THIS PROPOSED PAD SITE LOCATION SHOWN HEREON HAS BEEN SURVEYED ON THE GROUND UNDER MY SUPERVISION AND PREPARED ACCORDING TO THE EVIDENCE FOUND AT THE TIME OF SURVEY, AND DATA PROVIDED BY AMEREDEV OPERATING LLC. THIS CERTIFICATION IS MADE AND LIMITED TO THOSE PERSONS OR ENTITIES SHOWN ON THE FACE OF THIS PLAT AND IS NON-TRANSFERABLE. THIS SURVEY IS CERTIFIED FOR THIS TRANSACTION ONLY.



1400 EVERMAN PARKWAY, Ste. 197 - FT. WORTH, TEXAS 76140
 TELEPHONE: (817) 744-7512 - FAX (817) 744-7554
 2803 NORTH BIG SPRING - MIDLAND, TEXAS 79705
 TELEPHONE: (432) 682-1653 OR (800) 787-1653 - FAX (432) 682-1743
 WWW.TOPOGRAPHIC.COM

EXHIBIT 2
VICINITY MAP



AMEREDEV OPERATING, LLC


LEASE NAME & WELL NO.: JUNIPER FED COM 25 36 34 091H

SECTION 3 TWP 26-S RGE 36-E SURVEY N.M.P.M.
 COUNTY LEA STATE NM
 DESCRIPTION 230' FNL & 270' FVL

DISTANCE & DIRECTION
 FROM INT. OF 3RD ST./NM-205/FRYING PAN RD. & NM-128, HEAD SOUTH ON
 3RD ST./NM-205/FRYING PAN RD. ±5.6 MILES, THENCE WEST (RIGHT) ON
 ANTHONY RD ±3.4 MILES, THENCE NORTH (RIGHT) TO CONTINUE ON
 ANTHONY RD. ±0.3 MILES, THENCE EAST (RIGHT) ON PIPELINE RD. ±0.3
 MILES, THENCE NORTH (LEFT) ON A LEASE RD. ±1.0 MILES, THENCE EAST
 (RIGHT) ON A PROPOSED RD. ±1.1 MILES TO A POINT ±315 FEET NORTHWEST
 OF THE LOCATION.

THIS EASEMENT/SERVITUDE LOCATION SHOWN HEREON HAS BEEN SURVEYED ON THE GROUND UNDER MY SUPERVISION AND PREPARED ACCORDING TO THE EVIDENCE FOUND AT THE TIME OF SURVEY, AND DATA PROVIDED BY AMEREDEV OPERATING LLC. THIS CERTIFICATION IS MADE AND LIMITED TO THOSE PERSONS OR ENTITIES SHOWN ON THE FACE OF THIS PLAT AND IS NON-TRANSFERABLE. THIS SURVEY IS CERTIFIED FOR THIS TRANSACTION ONLY.

ALL BEARINGS, DISTANCES, AND COORDINATE VALUES CONTAINED HEREON ARE GRID BASED UPON THE NEW MEXICO COORDINATE SYSTEM OF 1983, EAST ZONE, U.S. SURVEY FEET.



1400 EVERMAN PARKWAY, Ste. 146 • FT. WORTH, TEXAS 76140
 TELEPHONE: (817) 744-7512 • FAX (817) 744-7554
 2903 NORTH BIG SPRING • MIDLAND, TEXAS 79705
 TELEPHONE: (432) 682-1653 OR (800) 767-1653 • FAX (432) 682-1743
 WWW.TOPOGRAPHIC.COM



APD ID: 10400031762

Submission Date: 08/02/2018

Operator Name: AMEREDEV OPERATING LLC

Well Name: JUNIPER FED COM 25 36 34

Well Number: 091H

Well Type: OIL WELL

Well Work Type: Drill

[Show Final Text](#)

Section 1 - Geologic Formations

Formation ID	Formation Name	Elevation	True Vertical Depth	Measured Depth	Lithologies	Mineral Resources	Producing Formation
1	RUSTLER	1254	1763	1763	ANHYDRITE	NONE	No
2	SALADO	-731	1985	1985	SALT	NONE	No
3	TANSILL	-2008	3262	3262	LIMESTONE	NONE	No
4	CAPITAN REEF	-2553	3807	3807	LIMESTONE	USEABLE WATER	No
5	LAMAR	-3709	4963	4963	LIMESTONE	NONE	No
6	BELL CANYON	-3905	5159	5159	SANDSTONE	NATURAL GAS,OIL	No
7	BRUSHY CANYON	-5450	6704	6704	SANDSTONE	NATURAL GAS,OIL	No
8	BONE SPRING LIME	-6434	7688	7688	LIMESTONE	NONE	No
9	BONE SPRING 1ST	-8046	9300	9300	SANDSTONE	NATURAL GAS,OIL	No
10	BONE SPRING 2ND	-8631	9885	9885	SANDSTONE	NATURAL GAS,OIL	No
11	BONE SPRING 3RD	-9291	10545	10545	LIMESTONE	NATURAL GAS,OIL	No
12	BONE SPRING 3RD	-9886	11140	11140	SANDSTONE	NATURAL GAS,OIL	Yes

Section 2 - Blowout Prevention

Pressure Rating (PSI): 10M

Rating Depth: 15000

Equipment: 10M BOPE SYSTEM WILL BE USED AFTER THE SURFACE CASING IS SET. A KELLY COCK WILL BE KEPT IN THE DRILL STRING AT ALL TIMES. A FULL OPENING DRILL PIPE STABBING VALVE WITH PROPER DRILL PIPE CONNECTIONS WILL BE ON THE RIG FLOOR AT ALL TIMES.

Requesting Variance? YES

Variance request: Co-Flex Choke Line, 5M Annular Preventer

Testing Procedure: See Attachment

Operator Name: AMEREDEV OPERATING LLC

Well Name: JUNIPER FED COM 25 36 34

Well Number: 091H

Choke Diagram Attachment:

10M_Choke_Manifold_REV_20190205115304.pdf

BOP Diagram Attachment:

5M_Annular_Preventer_Variance_and_Well_Control_Plan_20190205115321.pdf

5M_BOP_System_20190205115321.pdf

Pressure_Control_Plan_Single_Well_MB4_3String_Big_Hole_BLM_20190205115321.pdf

4_String_MB_Ameredev_Wellhead_Drawing_net_REV_20190205115333.pdf

Section 3 - Casing

Casing ID	String Type	Hole Size	Csg Size	Condition	Standard	Tapered String	Top Set MD	Bottom Set MD	Top Set TVD	Bottom Set TVD	Top Set MSL	Bottom Set MSL	Calculated casing length MD	Grade	Weight	Joint Type	Collapse SF	Burst SF	Joint SF Type	Joint SF	Body SF Type	Body SF
1	SURFACE	17.5	13.375	NEW	API	N	0	1888	0	1888	2992		1888	J-55	54.5	OTHER - BTC	4.86	0.52	DRY	8.89	DRY	8.29
2	INTERMEDIATE	12.25	9.625	NEW	API	N	0	10796	0	10796			10796	HCL-80	40	OTHER - BTC	1.27	1.15	DRY	2.17	DRY	2.18
3	PRODUCTION	8.5	5.5	NEW	API	N	0	22233	0	11280			22233	OTHER	20	OTHER - BTC	1.63	1.75	DRY	2.9	DRY	3.23

Casing Attachments

Casing ID: 1 String Type: SURFACE

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

13.375_54.50_J55_SEAH_20190205115700.pdf

JUNIPER_FED_COM_25_36_34_091H_WELLBORE_DIAGRAM_AND_CDA_20190207143723.pdf

Operator Name: AMEREDEV OPERATING LLC

Well Name: JUNIPER FED COM 25 36 34

Well Number: 091H

Casing Attachments

Casing ID: 2 String Type: INTERMEDIATE

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

9625_40_SeAH80HC_4100_Collapse_20190205115856.pdf

JUNIPER_FED_COM_25_36_34_091H_WELLBORE_DIAGRAM_AND_CDA_20190207143740.pdf

Casing ID: 3 String Type: PRODUCTION

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

JUNIPER_FED_COM_25_36_34_091H_WELLBORE_DIAGRAM_AND_CDA_20190207143750.pdf

5.50_20_USS_P110_HC_BTC_API_20190207143853.pdf

Section 4 - Cement

String Type	Lead/Tail	Stage Tool Depth	Top MD	Bottom MD	Quantity(sx)	Yield	Density	Cu Ft	Excess%	Cement type	Additives
SURFACE	Lead		0	1502	965	1.76	13.5	1697.63	50	Class C	Bentonite, Accelerator, Kolseal, Defoamer, Celloflake
SURFACE	Tail		1502	1888	200	1.34	14.8	268	100	Class C	Salt
INTERMEDIATE	Lead	5013	0	4163	686	2.47	11.9	1694.94	25	CLASS C	Salt, Bentonite, Kolseal, Defoamer, Celloflake, Anti-Settling Expansion

Operator Name: AMEREDEV OPERATING LLC

Well Name: JUNIPER FED COM 25 36 34

Well Number: 091H

String Type	Lead/Tail	Stage Tool Depth	Top MD	Bottom MD	Quantity(sx)	Yield	Density	Cu Ft	Excess%	Cement type	Additives
											Additive
INTERMEDIATE	Tail		4163	5013	200	1.33	14.8	266	25	CLASS C	Retarder
INTERMEDIATE	Lead	5013	5013	9540	1551	2.47	11.9	3830.08	25	Class H	Bentonite, Salt, Koseal, Defoamer, Celloflake, Retarder, Anti-Settling Expansion Additive
INTERMEDIATE	Tail		9540	10796	300	1.24	14.5	371.1	25	Class H	Salt, Bentonite, Retarder, Dispersant, Fluid Loss
PRODUCTION	Lead		0	22233	4747	1.34	14.2	6361.16	25	Class H	Salt, Bentonite, Fluid Loss, Dispersant, Retarder, Defoamer

Section 5 - Circulating Medium

Mud System Type: Closed

Will an air or gas system be Used? NO

Description of the equipment for the circulating system in accordance with Onshore Order #2:

Diagram of the equipment for the circulating system in accordance with Onshore Order #2:

Describe what will be on location to control well or mitigate other conditions: All necessary supplies (e.g. bentonite, cedar bark) for fluid control will be on site.

Describe the mud monitoring system utilized: An electronic pit volume totalizer (PVT) will be utilized on the circulating system to monitor pit volume, flow rate, pump pressure, and pump rate.

Circulating Medium Table

Top Depth	Bottom Depth	Mud Type	Min Weight (lbs/gal)	Max Weight (lbs/gal)	Density (lbs/cu ft)	Gel Strength (lbs/100 sqft)	PH	Viscosity (CP)	Salinity (ppm)	Filtration (cc)	Additional Characteristics
0	1888	WATER-BASED MUD	8.4	8.6							

Operator Name: AMEREDEV OPERATING LLC

Well Name: JUNIPER FED COM 25 36 34

Well Number: 091H

Top Depth	Bottom Depth	Mud Type	Min Weight (lbs/gal)	Max Weight (lbs/gal)	Density (lbs/cu ft)	Gel Strength (lbs/100 sqft)	PH	Viscosity (CP)	Salinity (ppm)	Filtration (cc)	Additional Characteristics
1888	1079 6	OTHER : Diesel Brine Emulsion	8.5	9.4							
1079	1128 6	OIL-BASED MUD	10.5	14							

Section 6 - Test, Logging, Coring

List of production tests including testing procedures, equipment and safety measures:

A directional survey, measurement while drilling and a mudlog/geologic lithology log will all be run from surface to TD.

List of open and cased hole logs run in the well:

DS,MWD,MUDLOG

Coring operation description for the well:

No coring will be done on this well.

Section 7 - Pressure

Anticipated Bottom Hole Pressure: 5000

Anticipated Surface Pressure: 2518.4

Anticipated Bottom Hole Temperature(F): 160

Anticipated abnormal pressures, temperatures, or potential geologic hazards? NO

Describe:

Contingency Plans geohazards description:

Contingency Plans geohazards attachment:

Hydrogen Sulfide drilling operations plan required? YES

Hydrogen sulfide drilling operations plan:

H2S_Plan_20180629084022.pdf

Operator Name: AMEREDEV OPERATING LLC

Well Name: JUNIPER FED COM 25 36 34

Well Number: 091H

Section 8 - Other Information

Proposed horizontal/directional/multi-lateral plan submission:

Jun091_DR_20190205121010.pdf

Jun091_LLRR_20190205121010.pdf

5M_Annular_Preventer_Variance_and_Well_Control_Plan_20190205121025.pdf

Pressure_Control_Plan_Single_Well_MB4_3String_Big_Hole_BLM_20190205121026.pdf

Other proposed operations facets description:

Other proposed operations facets attachment:


Other Variance attachment:

R616__CoC_for_hoses_12_18_17_20180629084119.pdf

Requested_Exceptions__3_String_Revised_01312019_20190205121039.pdf

13 5/8" 5M BOP
Configuration

CO-FLEX LINE TO
CHOKE MANIFOLD



4" 10M VALVES &

2" KILL LINE

10M Check Valve



5M Annular Preventer Variance Request and Well Control Procedures

Note: A copy of the Well Control Plan must be available at multiple locations on the rig for review by rig personnel, as well as review by the BLM PET/PE, and a copy must be maintained on the rig floor.

Dual Isolation Design for 5M Annular Exception

Ameredeve will utilize 13-5/8" 10M (5M Annular) BOPE System consisting of:

- 13-5/8" 5M Annular
- 13-5/8" 10M Upper Pipe Rams
 - 3-1/2" – 5-1/2" Variable Bore Ram
- 13-5/8" 10M Blind Rams
- 13-5/8" 10M Drilling Spool /w 2 - 4" 10M Outlets Double 10M Isolation Valves
- 13-5/8" 10M Lower Blind Rams
 - 3-1/2" – 5-1/2" Variable Bore Ram

All drilling components and casing associated to exposure > 5000 psi BHP requiring a 10M system will have a double isolation (secondary barrier) below the 5M Annular that would provide a barrier to flow. The mud system will always be primary barrier, it will be maintained by adjusting values based on tourly mud tests and monitoring a PVT System to maintain static wellbore conditions, displacement procedures will be followed and recorded on daily drilling reports during tripping operations. Surge and swab pressure values will be calculated and maintained and static flow check will be monitored at previous casing shoe and verified static well conditions prior to tripping out of hole and again prior to pulling last joint of drill pipe through BOPE. The below table, documents that two barriers to flow can be maintained at all times, independent of the rating of the annular preventer.

Drill Components	Size	Primary Barrier	Secondary Barrier	Third Barrier
Drillpipe	3-1/2"-5-1/2"	Drilling Fluid	Upper Pipe Rams	Lower Pipe Rams
HWDP Drillpipe	3-1/2"-5-1/2"	Drilling Fluid	Upper Pipe Rams	Lower Pipe Rams
Drill Collars	3-1/2"-5-1/2"	Drilling Fluid	Upper Pipe Rams	Lower Pipe Rams
Production Casing	3-1/2"-5-1/2"	Drilling Fluid	Upper Pipe Rams	Lower Pipe Rams
Open Hole	13-5/8	Drilling Fluid	Blind Rams	

All Drilling Components in 10M Environment will have OD that will allow full Operational RATED WORKING PRESSURE for system design. Kill line with minimum 2" ID will be available outside substructure with 10M Check Valve for OOH Kill Operations

Well Control Procedures

Proper well control procedures are dependent to differentiating well conditions, to cover the basic well control operations there are will be standard drilling ahead, tripping pipe, tripping BHA, running casing, and pipe out of the hole/open hole scenarios that will be defined by procedures below. Initial Shut In Pressure can be taken against the Uppermost BOPE component the 5M Annular, pressure control can be transferred from the lesser 5M Annular to the 10M Upper Pipe Rams if needed. Shut In Pressures may be equal to or less than the Rated Working Pressure but at no time will the pressure on the annular preventer exceed the Rated Working Pressure of the annular. The annular will be tested to 5,000 psi. This will be the Rated Working Pressure of the annular preventer. All scenarios will be written such as shut in will be performed by closing the 10,000 psi Upper Pipe Rams for faster Accumulator pressure recovery to allow safer reaction to controlling wellbore pressure.

Shutting In While Drilling

1. Sound alarm signaling well control event to Rig Crew
2. Space out drill string to allow FOSV installation
3. Shut down pumps
4. Shut in Upper Pipe Rams and open HCR against Open Chokes and Valves
Open to working pressure gauge
5. Install open, full open safety valve and close valve, Close Chokes
6. Verify well is shut-in and flow has stopped
7. Notify supervisory personnel
8. Record data (SIDP, SICP, Pit Gain, and Time)
9. Hold pre-job safety meeting and discuss kill procedure

Shutting In While Tripping

1. Sound alarm signaling well control event to Rig Crew
2. Space out drill string to allow FOSV installation
3. Shut in Upper Pipe Rams and open HCR against Open Chokes and Valves
Open to working pressure gauge
4. Install open, full open safety valve and close valve, Close Chokes
5. Verify well is shut-in and flow has stopped
6. Notify supervisory personnel
7. Record data (SIDP, SICP, Pit Gain, and Time)
8. Hold pre-job safety meeting and discuss kill procedure

Shutting In While Running Casing

1. Sound alarm signaling well control event to Rig Crew
2. Space out casing to allow circulating swedge installation
3. Shut in Upper Pipe Rams and open HCR against Open Chokes and Valves
Open to working pressure gauge
4. Install circulating swedge, Close high pressure, low torque valves, Close Chokes
5. Verify well is shut-in and flow has stopped
6. Notify supervisory personnel
7. Record data (SIDP, SICP, Pit Gain, and Time)
8. Hold Pre-job safety meeting and discuss kill procedure

Shutting In while out of hole

1. Sound alarm signaling well control event to Rig Crew
2. Shut-in well: close blind rams and open HCR against Open Chokes and Valves
Open to working pressure gauge
3. Close Chokes, Verify well is shut-in and monitor pressures
4. Notify supervisory personnel
5. Record data (SIDP, SICP, Pit Gain, and Time)
6. Hold Pre-job safety meeting and discuss kill procedure

Shutting In prior to pulling BHA through stack

Prior to pulling last joint of drill pipe thru the stack space out and check flow
If flowing see steps below.

1. Sound alarm signaling well control event to Rig Crew
2. Shut in upper pipe ram and open HCR against Open Chokes and Valves Open
to working pressure gauge
3. Install open, full open safety valve and close valve, Close Chokes
4. Verify well is shut-in and flow has stopped
5. Notify supervisory personnel
6. Record data (SIDP, SICP, Pit Gain, and Time)
7. Hold pre-job safety meeting and discuss kill procedure

Shutting in while BHA is in the stack and ram preventer and combo immediately available

1. Sound alarm signaling well control event to Rig Crew
2. Space out BHA with upset just beneath the compatible pipe ram
3. Shut in upper compatible pipe ram and open HCR against Open Chokes and Valves Open to working pressure gauge
4. Install open, full open safety valve and close valve, Close Chokes
5. Verify well is shut-in and flow has stopped
6. Notify supervisory personnel
7. Record data (SIDP, SICP, Pit Gain, and Time)
8. Hold pre-job safety meeting and discuss kill procedure

*FOSV will be on rig floor in open position with operating handle for each type of connection utilized and tested to 10,000 psi

Shutting in while BHA is in the stack and no ram preventer or combo immediately available

1. Sound alarm signaling well control event to Rig Crew
2. If possible pick up high enough, to pull string clear and follow "Open Hole" scenario

If not possible to pick up high enough:

3. Stab Crossover, make up one joint/stand of drill pipe, and install open, full open safety valve (Leave Open)
4. Space out drill string with upset just beneath the compatible pipe ram.
5. Shut in upper compatible pipe ram and open HCR against Open Chokes and Valves Open to working pressure gauge
6. Close FOSV, Close Chokes, Verify well is shut-in and flow has stopped
7. Notify supervisory personnel
8. Record data (SIDP, SICP, Pit Gain, and Time)
9. Hold pre-job safety meeting and discuss kill procedure


Pressure Control Plan

Pressure Control Equipment

- Following setting of 13-3/8" Surface Casing Ameredev will install 13-5/8 MB4 Multi Bowl Casing Head by welding on a 13-5/8 SOW x 13-5/8" 5M in combination with 13-5/8 5M x 13-5/8 10M B-Sec to Land Intm #1 and a 13-5/8 10M x 13-5/8 10M shouldered to land C-Sec to Land Intm #2 (Installation procedure witnessed and verified by a manufacturer's representative).
- Casing will be tested to 1500 psi or .22 psi/ft whichever is greater for 30 minutes with <10% leak off, but will not exceed 70% of the burst rating per Onshore Order No. 2.
- Ameredev will install a 5M System Blowout Preventer (BOPE) with a 5M Annular Preventer and related equipment (BOPE). Full testing will be performed utilizing a full isolation test plug and limited to 5,000 psi MOP of MB4 Multi Bowl Casing Head. Pressure will be held for 10 min or until provisions of test are met on all valves and rams. The 5M Annular Preventer will be tested to 50% of approved working pressure (2,500 psi). Casing will be tested to 1500 psi or .22 psi/ft whichever is greater for 30 minutes with <10% leak off, but will not exceed 70% of the burst rating per Onshore Order No. 2.
- Setting of 9-5/8" Intermediate will be done by landing a wellhead hanger in the 13-5/8" 5M Bowl, Cementing and setting Well Head Packing seals and testing same. (Installation procedure witnessed and verified by a manufacturer's representative) Casing will be tested to 1500 psi or .22 psi/ft whichever is greater for 30 minutes with <10% leak off, but will not exceed 70% of the burst rating per Onshore Order No. 2.
- Full testing will be performed utilizing a full isolation test plug to 10,000 psi MOP of MB4 Multi Bowl B-Section. Pressure will be held for 10 min or until provisions of test are met on all valves and rams. The 5M Annular Preventer will be tested to 100% of approved working pressure (5,000 psi).
- Before drilling >20ft of new formation under the 9-5/8" Casing Shoe a pressure integrity test of the Casing Shoe will be performed to minimum of the MWE anticipated to control formation pressure to the next casing depth.
- Following setting of 5-1/2" Production Casing and adequate WOC time Ameredev will break 10M System Blowout Preventer (BOP) from 10M DOL-2 Casing Head, install annulus casing slips and test same (Installation procedure witnessed and verified by a manufacturer's representative) and install 11" 10M x 5-1/8" 15M Tubing Head (Installation procedure witnessed and verified by a manufacturer's representative). Ameredev will test head to 70% casing design and install Dry Hole cap with needle valve and pressure gauge to monitor well awaiting completion.

Pressure Control Plan

- Slow pump speeds will be taken daily by each crew and recorded on Daily Drilling Report after mudding up.
- A choke manifold and accumulator with floor and remote operating stations will be functional and in place after installation of BOPE, as well as full functioning mud gas separator.
- Weekly BOPE pit level drills will be conducted by each crew and recorded on Daily Drilling Report.
- BOP will be fully operated when out of hole and will be documented on the daily drilling log.
- All B.O.P.s and associated equipment will be tested in accordance with Onshore Order #2
- All B.O.P. testing will be done by an independent service company.
- The B.O.P. will be tested within 21 days of the original test if drilling takes more time than planned.
- Ameredev requests a variance to connect the B.O.P. choke outlet to the choke manifold using a co-flex hose with a 10,000 psi working pressure that has been tested to 15,000psi and is built to API Spec 16C. Once the flex line is installed it will be tied down with safety clamps. (certifications will be sent to Carlsbad BLM Office prior to install)
- Ameredev requests a variance to install a 5M Annular Preventer on the 10M System to drill the Production Hole below the 9-5/8" Intermediate Section. 5M Annular will be tested to 100% working pressure (5,000 psi). A full well control procedure will be included to isolate well bore.



Quotation		Downing Wellhead Equipment		Oklahoma City, Oklahoma - USA	
Reference Data: 16925 AMEREDEV		Proprietary and Confidential The information contained in this drawing is the sole property of Downing Wellhead Equipment, any reproduction in part or in whole without the written permission of Downing Wellhead Equipment is prohibited.		TITLE: AMEREDEV	
DRAWN		CHECKED		SIZE A	DWG. NO.
APPROVED		Scale:		Weight:	REV. Sheet:

AMEREDEV

AMERDEV LLC

Wellbore Schematic

Well: Juniper Fed Com 25-36-34 091H
 SHL: Sec. 03 26S-36E 230' FNL & 270' FWL
 BHL: Sec. 27 25S-36E 50' FNL & 200' FWL
 Lea, NM
 Wellhead: A - 13-5/8" 10M x 13-5/8" SOW
 B - 13-5/8" 10M x 13-5/8" 10M
 C - 13-5/8" 10M x 13-5/8" 10M
 Tubing Spool - 5-1/8" 15M x 13-3/8" 10M
 Xmas Tree: 2-9/16" 10M
 Tubing: 2-7/8" L-80 6.5# 8rd EUE

Co. Well ID: xxxxxx
 AFE No.: xxxx-xxx
 API No.: xxxxxxxxxxxx
 GL: 2,992'
 Field: Delaware
 Objective: 3rd Bone Spg
 TVD: 11,280'
 MD: 22,233'
 Rig: TBD KB: 27'
 E-Mail: Wellsite2@amereDEV.com

Hole Size	Formation Tops	Logs Cement	Mud Weight
17.5"	Rustler 1,763'	1,165 Sacks TOC 0' 100% Excess	8.4-8.6 ppg WBM
	13.375" 54.5# J-55 BTC 1,888'		
12.25"	Salado 1,985'	886 Sacks TOC 0' 50% Excess	8.5 - 9.4 ppg Diesel Brine Emulsion
	Tansill 3,262'		
	Capitan Reef 3,807'		
	Lamar 4,963'		
	DV Tool 5,013'		
	Bell Canyon 5,159'		
	Brushy Canyon 6,704'		
8.5"	Bone Spring Lime 7,688'	1,723 Sacks TOC 0' 50% Excess	8.5 - 9.4 ppg Diesel Brine Emulsion
	First Bone Spring 9,300'		
	Second Bone Spring 9,885'		
	Third Bone Spring Upper 10,545'		
	9.625" 40# L-80HC BTC 10,796'		
12° Build @ 10,796' MD thru 11,826' MD	Third Bone Spring 11,140'	4,747 Sacks TOC 0' 25% Excess	10.5 - 14 ppg OBM
	5.5" 20# P-110CYHP BTC 22,233'		
Target 3rd Bone Spg 11280 TVD // 22233 MD			

Casing Design and Safety Factor Check

Casing Specifications						
Segment	Hole ID	Depth	OD	Weight	Grade	Coupling
Surface	17.5	1,888'	13.375	54.5	J-55	BTC
Intermediate	12.25	10,796'	9.625	40	HCL-80	BTC
Prod Segment A	8.5	10,796'	5.5	20	CYHP-110	BTC
Prod Segment B	8.5	22,233'	5.5	20	CYHP-110	BTC

Check Surface Casing				
OD Cplg	Body	Joint	Collapse	Burst
<i>inches</i>	<i>1000 lbs</i>	<i>1000 lbs</i>	<i>psi</i>	<i>psi</i>
14.375	853	915	4,100	2,730
Safety Factors				
1.56	8.29	8.89	4.86	0.52
Check Intermediate Casing				
OD Cplg	Body	Joint	Collapse	Burst
<i>inches</i>	<i>1000 lbs</i>	<i>1000 lbs</i>	<i>psi</i>	<i>psi</i>
7.625	940	558	6700	9460
Safety Factors				
2.31	2.18	2.22	1.27	1.15
Check Prod Casing, Segment A				
OD Cplg	Body	Joint	Collapse	Burst
<i>inches</i>	<i>1000 lbs</i>	<i>1000 lbs</i>	<i>psi</i>	<i>psi</i>
5.777	728	655	12780	14360
Safety Factors				
1.36	3.23	2.90	1.63	1.75
Check Prod Casing, Segment B				
OD Cplg	Body	Joint	Collapse	Burst
<i>inches</i>	<i>1000 lbs</i>	<i>1000 lbs</i>	<i>psi</i>	<i>psi</i>
5.777	728	655	12780	14360
Safety Factors				
1.36	75.21	67.67	1.56	1.75

U.S. Steel Tubular Products
Product Information
5.5 in. 20 lb/ft (0.361 in. wall) P-110 HC Casing
STAR SEAL - CDC™

Grade(s)	P-110 HC		
MECHANICAL PROPERTIES			
	Yield Strength		
	Minimum	110	ksi
	Maximum	140	ksi
	Tensile Strength		
	Minimum	125	ksi
PIPE PROPERTIES			
Dimensions, Nominal	Pipe Outside Diameter	5.500	in.
	Wall	0.361	in.
	Pipe Inside Diameter	4.778	in.
	Pipe Drift		
	API	4.653	in.
	Special (If Applicable)	N/A	in.
	Weight, T&C	20.00	lbs/ft
	Weight, Plain End	19.83	lbs/ft
	Pipe Cross Sectional Area	5.828	sq. in.
Performance Properties	Minimum Pipe Body Yield Strength	641	1,000 lbs
	Minimum Collapse Pressure	12,200	psi
	Minimum Internal Yield Pressure	12,640	psi
CONNECTION PROPERTIES			
Dimensions, Nominal	Connection Outside Diameter	6.050	in.
	Connection Inside Diameter	4.778	in.
	Connection Drift		
	API	4.653	in.
	Special (If Applicable)	N/A	in.
	Makeup Loss	4.63	in.
	Critical Area	5.828	in.
	Joint Efficiency	100	%
Performance Properties	Joint Strength	667	1,000 lbs
	Compression Rating	400	1,000 lbs
	API Collapse Pressure Rating	12,200	psi
	API Internal Pressure Resistance	12,360	psi
	Maximum Uniaxial Bend Rating	57.2	deg/100 ft
Recommended Torque Values	Minimum Shoulder Torque	5,000	ft-lbs
	Maximum Shoulder Torque	7,500	ft-lbs
	Connection Yield Torque	16,100	ft-lbs

* STAR SEAL - CDC (Casing Drilling Connection) is a Modified API Buttress threaded and coupled connection designed for field proven in drilling with casing applications. Star Seal is a registered trademark of U. S. Steel Corporation. All material contained in this publication is for general information only. This material should not therefore, be used or relied upon for any specific application without independent competent professional examination and verification of its accuracy, suitability and applicability. Anyone making use of this material does so at their own risk and assumes any and all liability resulting from such use. U. S. Steel disclaims any and all expressed or implied warranties of fitness for any general or particular application.



U.S. Steel Tubular Products, Inc.
600 Grant Street
Pittsburgh, PA 15219

SeAH

9.625"

40#

.395"

SEAH-80 HIGH COLLAPSE

(SEAH-80 IS A NON HEAT TREATED PRODUCT)

Dimensions (Nominal)

Outside Diameter	9.625	in.
Wall	0.395	in.
Inside Diameter	8.835	in.
Drift	8.750	in.
Weight, T&C	40.000	lbs./ft.
Weight, PE	38.970	lbs./ft.

Performance Properties

Collapse	4100	psi
Internal Yield Pressure at Minimum Yield		
PE	5750	psi
LTC	5750	psi
BTC	5750	psi
Yield Strength, Pipe Body	916	1000 lbs.
Joint Strength		
LTC	717	1000 lbs.
BTC	915	1000 lbs.

Note: SeAH Steel has produced this specification sheet for general information only. SeAH does not assume liability or responsibility for any loss or injury resulting from the use of information or data contained herein. All applications for the material described are at the customer's own risk and responsibility.

SeAH

13-3/8" 54.50# .380 J-55

Dimensions (Nominal)

Outside Diameter	13.375	in.
Wall	0.380	in.
Inside Diameter	12.615	in.
Drift	12.459	in.
Weight, T&C	54.500	lbs/ft
Weight, PE	52.790	lbs/ft

Performance Ratings, Minimum

Collapse, PE	1130	psi
Internal Yields Pressure		
PE	2730	psi
STC	2730	PSI
BTC	2730	psi
Yield Strength, Pipe Body	853	1000 lbs
Joint Strength, STC	514	1000 lbs
Joint Strength, BTC	909	1000 lbs

Note: SeAH Steel has produced this specification sheet for general information only. SeAH does not assume liability or responsibility for any loss or injury resulting from the use of information or data contained herein. All applications for the material described are at the customer's own risk and responsibility.

H₂S Drilling Operation Plan

1. **All Company and Contract personnel admitted on location must be trained by a qualified H₂S safety instructor to the following:**
 - a. Characteristics of H₂S
 - b. Physical effects and hazards
 - c. Principal and operation of H₂S detectors, warning system and briefing areas
 - d. Evacuation procedure, routes and first aid
 - e. Proper use of safety equipment and life support systems
 - f. Essential personnel meeting Medical Evaluation criteria will receive additional training on the proper use of 30 minute pressure demand air packs.

2. **Briefing Area:**
 - a. Two perpendicular areas will be designated by signs and readily accessible.
 - b. Upon location entry there will be a designated area to establish all safety compliance criteria (1.) has been met.

3. **H₂S Detection and Alarm Systems:**
 - a. H₂S sensors/detectors shall be located on the drilling rig floor, in the base of the sub structure/cellar area, and on the mud pits in the shale shaker area. Additional H₂S detectors may be placed as deemed necessary. All detectors will be set to initiate visual alarm at 10 ppm and visual with audible at 14 ppm and all equipment will be calibrated every 30 days or as needed.
 - b. An audio alarm will be installed on the derrick floor and in the top doghouse.

4. **Protective Equipment for Essential Personnel:**
 - a. **Breathing Apparatus:**
 - i. Rescue Packs (SCBA) - 1 Unit shall be placed at each briefing area.
 - ii. Two (SCBA) Units will be stored in safety trailer on location.
 - iii. Work/Escapes packs - 1 Unit will be available on rig floor in doghouse for emergency evacuation for driller.
 - b. **Auxiliary Rescue Equipment:**
 - i. Stretcher
 - ii. 2 - OSHA full body harnesses
 - iii. 100 ft. 5/8" OSHA approved rope
 - iv. 1 - 20# class ABC fire extinguisher

5. **Windsock and/or Wind Streamers:**
 - a. Windsock at mud pit area should be high enough to be visible.
 - b. Windsock on the rig floor should be high enough to be visible.

6. **Communication:**
 - a. While working under mask scripting boards will be used for communication where applicable.
 - b. Hand signals will be used when script boards are not applicable.

H₂S Drilling Operation Plan

- c. Two way radios will be used to communicate off location in case of emergency help is required. In most cases cellular telephones will be available at Drilling Foreman's Office.

7. **Drill Stem Testing:** - No Planned DST at this time.

8. **Mud program:**

- a. If H₂S is encountered, mud system will be altered if necessary to maintain control of formation. A mud gas separator will be brought into service along with H₂S scavengers if necessary.

9. **Metallurgy:**

- a. All drill strings, casing, tubing, wellhead, blowout preventer, drilling spool, kill lines, choke manifold and lines, and valves shall be suitable for H₂S service.
- b. Drilling Contractor supervisor will be required to be familiar with the effect H₂S has on tubular goods and other mechanical equipment provided through contractor.



H₂S Contingency Plan

Emergency Procedures

In the event of a release of H₂S, the first responder(s) must:

- Isolate the area and prevent entry by other persons into the 100 ppm ROE.
- Evacuate any public places encompassed by the 100 ppm ROE.
- Be equipped with H₂S monitors and air packs in order to control the release.
- Use the "buddy system" to ensure no injuries occur during the response.
- Take precautions to avoid personal injury during this operation.
- Contact Operator and/or local officials the aid in operation. See list of phone numbers attached.
- Have received training in the:
 - Detection of H₂S and
 - Measures for protection against the gas,
 - Equipment used for protection and emergency response.

Ignition of Gas Source

Should control of the well be considered lost and ignition considered, take care to protect against exposure to Sulfur Dioxide (SO₂). Intentional ignition must be coordinated with the NMOCD and local officials. Additionally, the NM State Police may become involved. NM State Police shall be the Incident Command on scene of any major release. Take care to protect downwind whenever there is an ignition of the gas.

Characteristics of H₂S and SO₂

Common Name	Chemical Formula	Specific Gravity	Threshold Limit	Hazardous Limit	Lethal Concentration
Hydrogen Sulfide	H ₂ S	1.189 Air=1	10 ppm	100 ppm/hr	600 ppm
Sulfur Dioxide	SO ₂	2.21 Air=1	2 ppm	N/A	1000 ppm

Contacting Authorities

Ameredev Operating LLC personnel must liaise with local and state agencies to ensure a proper response to a major release. Additionally, the OCD must be notified of the release as soon as possible but no later than 4 hours. Agencies will ask for information such as type and volume of release, wind direction, location of release, etc. Be prepared with all information available including direction to site. The following call list of essential and potential responders has been prepared for use during a release. Ameredev Operating LLC's response must be in coordination with the State of New Mexico's "Hazardous Materials Emergency Response Plan" (HMER)



Amerdev Operating LLC

H₂S Contingency Plan

Amerdev Operating LLC – Emergency Phone 737-300-4799

Key Personnel:

Name	Title	Office	Mobile
Floyd Hammond	Chief Operating officer	737-300-4724	512-783-6810
Zachary Boyd	Operations Superintendent	737-300-4725	432-385-6996
Blake Estrada	Construction Foreman		432-385-5831

Artesia

Ambulance	911
State Police	575-746-2703
City Police	575-746-2703
Sheriff's Office	575-746-9888
Fire Department	575-746-2701
Local Emergency Planning Committee	575-746-2122
New Mexico Oil Conservation Division	575-748-1283

Carlsbad

Ambulance	911
State Police	575-885-3137
City Police	575-885-2111
Sheriff's Office	575-887-7551
Fire Department	575-887-3798
Local Emergency Planning Committee	575-887-6544
US Bureau of Land Management	575-887-6544

Santa Fe

New Mexico Emergency Response Commission (Santa Fe)	505-476-9600
New Mexico Emergency Response Commission (Santa Fe) 24 Hrs	505-827-9126
New Mexico State Emergency Operations Center	505-476-9635

National

National Emergency Response Center (Washington, D.C.)	800-424-8802
---	--------------

Medical

Flight for Life - 4000 24th St.; Lubbock, TX	806-743-9911
Aerocare - R3, Box 49F; Lubbock, TX	806-747-8923
Med Flight Air Amb - 2301 Yale Blvd S.E., #D3; Albuquerque, NM	505-842-4433
'SB Air Med Service - 2505 Clark Carr Loop S.E.; Albuquerque, NM	505-842-4949

AMEREDEV

Ameredev Operating, LLC.

JUN/PIM

JUN/PIM #1S

Juniper 091H

Wellbore #1

Plan: Design #1

Standard Planning Report

14 January, 2019

Database:	EDM5000	Local Co-ordinate Reference:	Well Juniper 091H
Company:	Ameredev Operating, LLC.	TVD Reference:	KB @ 3019.0usft
Project:	JUN/PIM	MD Reference:	KB @ 3019.0usft
Site:	JUN/PIM #1S	North Reference:	Grid
Well:	Juniper 091H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Design #1		

Project	JUN/PIM		
Map System:	US State Plane 1983	System Datum:	Mean Sea Level
Geo Datum:	North American Datum 1983		
Map Zone:	New Mexico Eastern Zone		

Site	JUN/PIM #1S				
Site Position:		Northing:	394,110.55 usft	Latitude:	32° 4' 44.214 N
From:	Lat/Long	Easting:	873,588.15 usft	Longitude:	103° 15' 38.243 W
Position Uncertainty:	0.0 usft	Slot Radius:	13-3/16"	Grid Convergence:	0.57°

Well	Juniper 091H					
Well Position	+N/-S	-0.2 usft	Northing:	394,110.39 usft	Latitude:	32° 4' 44.215 N
	+E/-W	-20.0 usft	Easting:	873,568.17 usft	Longitude:	103° 15' 38.475 W
Position Uncertainty		0.0 usft	Wellhead Elevation:		Ground Level:	2,992.0 usft

Wellbore	Wellbore #1				
Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	IGRF2015	1/11/2019	6.63	59.96	47,725.91111583

Design	Design #1				
Audit Notes:					
Version:	Phase:	PROTOTYPE	Tie On Depth:	0.0	
Vertical Section:	Depth From (TVD) (usft)	+N/-S (usft)	+E/-W (usft)	Direction (°)	
	0.0	0.0	0.0	359.05	

Plan Survey Tool Program	Date	1/14/2019			
Depth From (usft)	Depth To (usft)	Survey (Wellbore)	Tool Name	Remarks	
1	0.0	22,233.3 Design #1 (Wellbore #1)	MWD OWSG MWD - Standard		

Database:	EDM5000	Local Co-ordinate Reference:	Well Juniper 091H
Company:	Ameredev Operating, LLC.	TVD Reference:	KB @ 3019.0usft
Project:	JUN/PIM	MD Reference:	KB @ 3019.0usft
Site:	JUN/PIM #1S	North Reference:	Grid
Well:	Juniper 091H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Design #1		

Plan Sections

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	TFO (°)	Target
0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.00	0.00	
2,000.0	0.00	0.00	2,000.0	0.0	0.0	0.00	0.00	0.00	0.00	
2,300.0	6.00	175.00	2,299.5	-15.6	1.4	2.00	2.00	0.00	175.00	
6,020.9	6.00	175.00	6,000.0	-403.1	35.3	0.00	0.00	0.00	0.00	
6,320.9	0.00	0.00	6,299.5	-418.7	36.6	2.00	-2.00	0.00	180.00	
10,796.5	0.00	0.00	10,775.0	-418.7	36.6	0.00	0.00	0.00	0.00	
11,496.4	83.99	351.17	11,249.8	3.7	-29.0	12.00	12.00	0.00	351.17	
11,741.8	83.99	351.17	11,275.5	244.9	-66.4	0.00	0.00	0.00	0.00	
11,826.8	90.00	359.43	11,280.0	329.3	-73.4	12.00	7.07	9.71	54.18	Jun091 FTP
22,233.3	90.00	359.43	11,280.0	10,735.3	-177.6	0.00	0.00	0.00	0.00	Jun091 BHL

Database:	EDM5000	Local Co-ordinate Reference:	Well Juniper 091H
Company:	Ameredev Operating, LLC.	TVD Reference:	KB @ 3019.0usft
Project:	JUN/PIM	MD Reference:	KB @ 3019.0usft
Site:	JUN/PIM #1S	North Reference:	Grid
Well:	Juniper 091H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Design #1		

Planned Survey										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	
0.0	0.00	0.00	0.0	0.0	0.0	0.0	0.00	0.00	0.00	
100.0	0.00	0.00	100.0	0.0	0.0	0.0	0.00	0.00	0.00	
200.0	0.00	0.00	200.0	0.0	0.0	0.0	0.00	0.00	0.00	
300.0	0.00	0.00	300.0	0.0	0.0	0.0	0.00	0.00	0.00	
400.0	0.00	0.00	400.0	0.0	0.0	0.0	0.00	0.00	0.00	
500.0	0.00	0.00	500.0	0.0	0.0	0.0	0.00	0.00	0.00	
600.0	0.00	0.00	600.0	0.0	0.0	0.0	0.00	0.00	0.00	
700.0	0.00	0.00	700.0	0.0	0.0	0.0	0.00	0.00	0.00	
800.0	0.00	0.00	800.0	0.0	0.0	0.0	0.00	0.00	0.00	
900.0	0.00	0.00	900.0	0.0	0.0	0.0	0.00	0.00	0.00	
1,000.0	0.00	0.00	1,000.0	0.0	0.0	0.0	0.00	0.00	0.00	
1,100.0	0.00	0.00	1,100.0	0.0	0.0	0.0	0.00	0.00	0.00	
1,200.0	0.00	0.00	1,200.0	0.0	0.0	0.0	0.00	0.00	0.00	
1,300.0	0.00	0.00	1,300.0	0.0	0.0	0.0	0.00	0.00	0.00	
1,400.0	0.00	0.00	1,400.0	0.0	0.0	0.0	0.00	0.00	0.00	
1,500.0	0.00	0.00	1,500.0	0.0	0.0	0.0	0.00	0.00	0.00	
1,600.0	0.00	0.00	1,600.0	0.0	0.0	0.0	0.00	0.00	0.00	
1,700.0	0.00	0.00	1,700.0	0.0	0.0	0.0	0.00	0.00	0.00	
1,800.0	0.00	0.00	1,800.0	0.0	0.0	0.0	0.00	0.00	0.00	
1,900.0	0.00	0.00	1,900.0	0.0	0.0	0.0	0.00	0.00	0.00	
2,000.0	0.00	0.00	2,000.0	0.0	0.0	0.0	0.00	0.00	0.00	
2,100.0	2.00	175.00	2,100.0	-1.7	0.2	-1.7	2.00	2.00	0.00	
2,200.0	4.00	175.00	2,199.8	-7.0	0.6	-7.0	2.00	2.00	0.00	
2,300.0	6.00	175.00	2,299.5	-15.6	1.4	-15.7	2.00	2.00	0.00	
2,400.0	6.00	175.00	2,398.9	-26.0	2.3	-26.1	0.00	0.00	0.00	
2,500.0	6.00	175.00	2,498.4	-36.5	3.2	-36.5	0.00	0.00	0.00	
2,600.0	6.00	175.00	2,597.8	-46.9	4.1	-46.9	0.00	0.00	0.00	
2,700.0	6.00	175.00	2,697.3	-57.3	5.0	-57.4	0.00	0.00	0.00	
2,800.0	6.00	175.00	2,796.7	-67.7	5.9	-67.8	0.00	0.00	0.00	
2,900.0	6.00	175.00	2,896.2	-78.1	6.8	-78.2	0.00	0.00	0.00	
3,000.0	6.00	175.00	2,995.6	-88.5	7.7	-88.6	0.00	0.00	0.00	
3,100.0	6.00	175.00	3,095.1	-98.9	8.7	-99.1	0.00	0.00	0.00	
3,200.0	6.00	175.00	3,194.5	-109.4	9.6	-109.5	0.00	0.00	0.00	
3,300.0	6.00	175.00	3,294.0	-119.8	10.5	-119.9	0.00	0.00	0.00	
3,400.0	6.00	175.00	3,393.4	-130.2	11.4	-130.3	0.00	0.00	0.00	
3,500.0	6.00	175.00	3,492.9	-140.6	12.3	-140.8	0.00	0.00	0.00	
3,600.0	6.00	175.00	3,592.3	-151.0	13.2	-151.2	0.00	0.00	0.00	
3,700.0	6.00	175.00	3,691.8	-161.4	14.1	-161.6	0.00	0.00	0.00	
3,800.0	6.00	175.00	3,791.2	-171.8	15.0	-172.1	0.00	0.00	0.00	
3,900.0	6.00	175.00	3,890.7	-182.2	15.9	-182.5	0.00	0.00	0.00	
4,000.0	6.00	175.00	3,990.1	-192.7	16.9	-192.9	0.00	0.00	0.00	
4,100.0	6.00	175.00	4,089.6	-203.1	17.8	-203.3	0.00	0.00	0.00	
4,200.0	6.00	175.00	4,189.0	-213.5	18.7	-213.8	0.00	0.00	0.00	
4,300.0	6.00	175.00	4,288.5	-223.9	19.6	-224.2	0.00	0.00	0.00	
4,400.0	6.00	175.00	4,387.9	-234.3	20.5	-234.6	0.00	0.00	0.00	
4,500.0	6.00	175.00	4,487.4	-244.7	21.4	-245.0	0.00	0.00	0.00	
4,600.0	6.00	175.00	4,586.9	-255.1	22.3	-255.5	0.00	0.00	0.00	
4,700.0	6.00	175.00	4,686.3	-265.5	23.2	-265.9	0.00	0.00	0.00	
4,800.0	6.00	175.00	4,785.8	-276.0	24.1	-276.3	0.00	0.00	0.00	
4,900.0	6.00	175.00	4,885.2	-286.4	25.1	-286.7	0.00	0.00	0.00	
5,000.0	6.00	175.00	4,984.7	-296.8	26.0	-297.2	0.00	0.00	0.00	
5,100.0	6.00	175.00	5,084.1	-307.2	26.9	-307.6	0.00	0.00	0.00	
5,200.0	6.00	175.00	5,183.6	-317.6	27.8	-318.0	0.00	0.00	0.00	
5,300.0	6.00	175.00	5,283.0	-328.0	28.7	-328.5	0.00	0.00	0.00	

Database: EDM5000
Company: Ameredev Operating, LLC.
Project: JUN/PIM
Site: JUN/PIM #1S
Well: Juniper 091H
Wellbore: Wellbore #1
Design: Design #1

Local Co-ordinate Reference: Well Juniper 091H
TVD Reference: KB @ 3019.0usft
MD Reference: KB @ 3019.0usft
North Reference: Grid
Survey Calculation Method: Minimum Curvature

Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
5,400.0	6.00	175.00	5,382.5	-338.4	29.6	-338.9	0.00	0.00	0.00
5,500.0	6.00	175.00	5,481.9	-348.9	30.5	-349.3	0.00	0.00	0.00
5,600.0	6.00	175.00	5,581.4	-359.3	31.4	-359.7	0.00	0.00	0.00
5,700.0	6.00	175.00	5,680.8	-369.7	32.3	-370.2	0.00	0.00	0.00
5,800.0	6.00	175.00	5,780.3	-380.1	33.3	-380.6	0.00	0.00	0.00
5,900.0	6.00	175.00	5,879.7	-390.5	34.2	-391.0	0.00	0.00	0.00
6,000.0	6.00	175.00	5,979.2	-400.9	35.1	-401.4	0.00	0.00	0.00
6,020.9	6.00	175.00	6,000.0	-403.1	35.3	-403.6	0.00	0.00	0.00
6,100.0	4.42	175.00	6,078.7	-410.2	35.9	-410.8	2.00	-2.00	0.00
6,200.0	2.42	175.00	6,178.6	-416.2	36.4	-416.7	2.00	-2.00	0.00
6,300.0	0.42	175.00	6,278.5	-418.7	36.6	-419.2	2.00	-2.00	0.00
6,320.9	0.00	0.00	6,299.5	-418.7	36.6	-419.3	2.00	-2.00	0.00
6,400.0	0.00	0.00	6,378.5	-418.7	36.6	-419.3	0.00	0.00	0.00
6,500.0	0.00	0.00	6,478.5	-418.7	36.6	-419.3	0.00	0.00	0.00
6,600.0	0.00	0.00	6,578.5	-418.7	36.6	-419.3	0.00	0.00	0.00
6,700.0	0.00	0.00	6,678.5	-418.7	36.6	-419.3	0.00	0.00	0.00
6,800.0	0.00	0.00	6,778.5	-418.7	36.6	-419.3	0.00	0.00	0.00
6,900.0	0.00	0.00	6,878.5	-418.7	36.6	-419.3	0.00	0.00	0.00
7,000.0	0.00	0.00	6,978.5	-418.7	36.6	-419.3	0.00	0.00	0.00
7,100.0	0.00	0.00	7,078.5	-418.7	36.6	-419.3	0.00	0.00	0.00
7,200.0	0.00	0.00	7,178.5	-418.7	36.6	-419.3	0.00	0.00	0.00
7,300.0	0.00	0.00	7,278.5	-418.7	36.6	-419.3	0.00	0.00	0.00
7,400.0	0.00	0.00	7,378.5	-418.7	36.6	-419.3	0.00	0.00	0.00
7,500.0	0.00	0.00	7,478.5	-418.7	36.6	-419.3	0.00	0.00	0.00
7,600.0	0.00	0.00	7,578.5	-418.7	36.6	-419.3	0.00	0.00	0.00
7,700.0	0.00	0.00	7,678.5	-418.7	36.6	-419.3	0.00	0.00	0.00
7,800.0	0.00	0.00	7,778.5	-418.7	36.6	-419.3	0.00	0.00	0.00
7,900.0	0.00	0.00	7,878.5	-418.7	36.6	-419.3	0.00	0.00	0.00
8,000.0	0.00	0.00	7,978.5	-418.7	36.6	-419.3	0.00	0.00	0.00
8,100.0	0.00	0.00	8,078.5	-418.7	36.6	-419.3	0.00	0.00	0.00
8,200.0	0.00	0.00	8,178.5	-418.7	36.6	-419.3	0.00	0.00	0.00
8,300.0	0.00	0.00	8,278.5	-418.7	36.6	-419.3	0.00	0.00	0.00
8,400.0	0.00	0.00	8,378.5	-418.7	36.6	-419.3	0.00	0.00	0.00
8,500.0	0.00	0.00	8,478.5	-418.7	36.6	-419.3	0.00	0.00	0.00
8,600.0	0.00	0.00	8,578.5	-418.7	36.6	-419.3	0.00	0.00	0.00
8,700.0	0.00	0.00	8,678.5	-418.7	36.6	-419.3	0.00	0.00	0.00
8,800.0	0.00	0.00	8,778.5	-418.7	36.6	-419.3	0.00	0.00	0.00
8,900.0	0.00	0.00	8,878.5	-418.7	36.6	-419.3	0.00	0.00	0.00
9,000.0	0.00	0.00	8,978.5	-418.7	36.6	-419.3	0.00	0.00	0.00
9,100.0	0.00	0.00	9,078.5	-418.7	36.6	-419.3	0.00	0.00	0.00
9,200.0	0.00	0.00	9,178.5	-418.7	36.6	-419.3	0.00	0.00	0.00
9,300.0	0.00	0.00	9,278.5	-418.7	36.6	-419.3	0.00	0.00	0.00
9,400.0	0.00	0.00	9,378.5	-418.7	36.6	-419.3	0.00	0.00	0.00
9,500.0	0.00	0.00	9,478.5	-418.7	36.6	-419.3	0.00	0.00	0.00
9,600.0	0.00	0.00	9,578.5	-418.7	36.6	-419.3	0.00	0.00	0.00
9,700.0	0.00	0.00	9,678.5	-418.7	36.6	-419.3	0.00	0.00	0.00
9,800.0	0.00	0.00	9,778.5	-418.7	36.6	-419.3	0.00	0.00	0.00
9,900.0	0.00	0.00	9,878.5	-418.7	36.6	-419.3	0.00	0.00	0.00
10,000.0	0.00	0.00	9,978.5	-418.7	36.6	-419.3	0.00	0.00	0.00
10,100.0	0.00	0.00	10,078.5	-418.7	36.6	-419.3	0.00	0.00	0.00
10,200.0	0.00	0.00	10,178.5	-418.7	36.6	-419.3	0.00	0.00	0.00
10,300.0	0.00	0.00	10,278.5	-418.7	36.6	-419.3	0.00	0.00	0.00
10,400.0	0.00	0.00	10,378.5	-418.7	36.6	-419.3	0.00	0.00	0.00
10,500.0	0.00	0.00	10,478.5	-418.7	36.6	-419.3	0.00	0.00	0.00

Database:	EDM5000	Local Co-ordinate Reference:	Well Juniper 091H
Company:	Ameredev Operating, LLC.	TVD Reference:	KB @ 3019.0usft
Project:	JUN/PIM	MD Reference:	KB @ 3019.0usft
Site:	JUN/PIM #1S	North Reference:	Grid
Well:	Juniper 091H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Design #1		

Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	
10,600.0	0.00	0.00	10,578.5	-418.7	36.6	-419.3	0.00	0.00	0.00	
10,700.0	0.00	0.00	10,678.5	-418.7	36.6	-419.3	0.00	0.00	0.00	
10,796.5	0.00	0.00	10,775.0	-418.7	36.6	-419.3	0.00	0.00	0.00	
Jun091 KOP										
10,800.0	0.42	351.17	10,778.5	-418.7	36.6	-419.3	12.00	12.00	0.00	
10,900.0	12.42	351.17	10,877.7	-407.7	34.9	-408.2	12.00	12.00	0.00	
Sec 03										
11,000.0	24.42	351.17	10,972.4	-376.5	30.1	-377.0	12.00	12.00	0.00	
11,100.0	36.42	351.17	11,058.5	-326.6	22.3	-326.9	12.00	12.00	0.00	
11,200.0	48.42	351.17	11,132.2	-260.0	12.0	-260.2	12.00	12.00	0.00	
11,300.0	60.42	351.17	11,190.2	-179.8	-0.5	-179.8	12.00	12.00	0.00	
11,400.0	72.42	351.17	11,230.2	-89.4	-14.5	-89.2	12.00	12.00	0.00	
11,496.4	83.99	351.17	11,249.8	3.7	-29.0	4.2	12.00	12.00	0.00	
11,500.0	83.99	351.17	11,250.2	7.2	-29.5	7.7	0.00	0.00	0.00	
11,600.0	83.99	351.17	11,260.7	105.5	-44.8	106.2	0.00	0.00	0.00	
11,700.0	83.99	351.17	11,271.2	203.8	-60.1	204.7	0.00	0.00	0.00	
11,741.8	83.99	351.17	11,275.5	244.9	-66.4	245.9	0.00	0.00	0.00	
11,759.5	85.23	352.89	11,277.2	262.2	-68.9	263.4	12.00	7.04	9.76	
Sec 34										
11,800.0	88.10	356.83	11,279.6	302.5	-72.5	303.7	12.00	7.07	9.71	
11,826.8	90.00	359.43	11,280.0	329.3	-73.4	330.5	12.00	7.09	9.68	
Jun091 FTP										
11,900.0	90.00	359.43	11,280.0	402.5	-74.1	403.7	0.00	0.00	0.00	
12,000.0	90.00	359.43	11,280.0	502.5	-75.1	503.7	0.00	0.00	0.00	
12,100.0	90.00	359.43	11,280.0	602.5	-76.1	603.7	0.00	0.00	0.00	
12,200.0	90.00	359.43	11,280.0	702.5	-77.1	703.7	0.00	0.00	0.00	
12,300.0	90.00	359.43	11,280.0	802.5	-78.1	803.7	0.00	0.00	0.00	
12,400.0	90.00	359.43	11,280.0	902.5	-79.1	903.7	0.00	0.00	0.00	
12,500.0	90.00	359.43	11,280.0	1,002.5	-80.1	1,003.7	0.00	0.00	0.00	
12,600.0	90.00	359.43	11,280.0	1,102.5	-81.1	1,103.7	0.00	0.00	0.00	
12,700.0	90.00	359.43	11,280.0	1,202.5	-82.1	1,203.7	0.00	0.00	0.00	
12,800.0	90.00	359.43	11,280.0	1,302.5	-83.1	1,303.7	0.00	0.00	0.00	
12,900.0	90.00	359.43	11,280.0	1,402.5	-84.1	1,403.7	0.00	0.00	0.00	
13,000.0	90.00	359.43	11,280.0	1,502.5	-85.1	1,503.7	0.00	0.00	0.00	
13,100.0	90.00	359.43	11,280.0	1,602.5	-86.1	1,603.7	0.00	0.00	0.00	
13,200.0	90.00	359.43	11,280.0	1,702.5	-87.1	1,703.7	0.00	0.00	0.00	
13,300.0	90.00	359.43	11,280.0	1,802.5	-88.1	1,803.7	0.00	0.00	0.00	
13,400.0	90.00	359.43	11,280.0	1,902.4	-89.1	1,903.7	0.00	0.00	0.00	
13,500.0	90.00	359.43	11,280.0	2,002.4	-90.1	2,003.7	0.00	0.00	0.00	
13,600.0	90.00	359.43	11,280.0	2,102.4	-91.1	2,103.7	0.00	0.00	0.00	
13,700.0	90.00	359.43	11,280.0	2,202.4	-92.1	2,203.7	0.00	0.00	0.00	
13,800.0	90.00	359.43	11,280.0	2,302.4	-93.1	2,303.7	0.00	0.00	0.00	
13,900.0	90.00	359.43	11,280.0	2,402.4	-94.1	2,403.6	0.00	0.00	0.00	
14,000.0	90.00	359.43	11,280.0	2,502.4	-95.1	2,503.6	0.00	0.00	0.00	
14,100.0	90.00	359.43	11,280.0	2,602.4	-96.1	2,603.6	0.00	0.00	0.00	
14,200.0	90.00	359.43	11,280.0	2,702.4	-97.2	2,703.6	0.00	0.00	0.00	
14,300.0	90.00	359.43	11,280.0	2,802.4	-98.2	2,803.6	0.00	0.00	0.00	
14,400.0	90.00	359.43	11,280.0	2,902.4	-99.2	2,903.6	0.00	0.00	0.00	
14,500.0	90.00	359.43	11,280.0	3,002.4	-100.2	3,003.6	0.00	0.00	0.00	
14,600.0	90.00	359.43	11,280.0	3,102.4	-101.2	3,103.6	0.00	0.00	0.00	
14,700.0	90.00	359.43	11,280.0	3,202.4	-102.2	3,203.6	0.00	0.00	0.00	
14,800.0	90.00	359.43	11,280.0	3,302.4	-103.2	3,303.6	0.00	0.00	0.00	
14,900.0	90.00	359.43	11,280.0	3,402.4	-104.2	3,403.6	0.00	0.00	0.00	

Database: EDM5000
Company: Ameredev Operating, LLC.
Project: JUN/PIM
Site: JUN/PIM #1S
Well: Juniper 091H
Wellbore: Wellbore #1
Design: Design #1

Local Co-ordinate Reference: Well Juniper 091H
TVD Reference: KB @ 3019.0usft
MD Reference: KB @ 3019.0usft
North Reference: Grid
Survey Calculation Method: Minimum Curvature

Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
15,000.0	90.00	359.43	11,280.0	3,502.4	-105.2	3,503.6	0.00	0.00	0.00
15,100.0	90.00	359.43	11,280.0	3,602.4	-106.2	3,603.6	0.00	0.00	0.00
15,200.0	90.00	359.43	11,280.0	3,702.4	-107.2	3,703.6	0.00	0.00	0.00
15,300.0	90.00	359.43	11,280.0	3,802.4	-108.2	3,803.6	0.00	0.00	0.00
15,400.0	90.00	359.43	11,280.0	3,902.3	-109.2	3,903.6	0.00	0.00	0.00
15,500.0	90.00	359.43	11,280.0	4,002.3	-110.2	4,003.6	0.00	0.00	0.00
15,600.0	90.00	359.43	11,280.0	4,102.3	-111.2	4,103.6	0.00	0.00	0.00
15,700.0	90.00	359.43	11,280.0	4,202.3	-112.2	4,203.6	0.00	0.00	0.00
15,800.0	90.00	359.43	11,280.0	4,302.3	-113.2	4,303.6	0.00	0.00	0.00
15,900.0	90.00	359.43	11,280.0	4,402.3	-114.2	4,403.6	0.00	0.00	0.00
16,000.0	90.00	359.43	11,280.0	4,502.3	-115.2	4,503.6	0.00	0.00	0.00
16,100.0	90.00	359.43	11,280.0	4,602.3	-116.2	4,603.6	0.00	0.00	0.00
16,200.0	90.00	359.43	11,280.0	4,702.3	-117.2	4,703.6	0.00	0.00	0.00
16,300.0	90.00	359.43	11,280.0	4,802.3	-118.2	4,803.6	0.00	0.00	0.00
16,400.0	90.00	359.43	11,280.0	4,902.3	-119.2	4,903.6	0.00	0.00	0.00
16,500.0	90.00	359.43	11,280.0	5,002.3	-120.2	5,003.6	0.00	0.00	0.00
16,600.0	90.00	359.43	11,280.0	5,102.3	-121.2	5,103.6	0.00	0.00	0.00
16,700.0	90.00	359.43	11,280.0	5,202.3	-122.2	5,203.6	0.00	0.00	0.00
16,800.0	90.00	359.43	11,280.0	5,302.3	-123.2	5,303.6	0.00	0.00	0.00
16,900.0	90.00	359.43	11,280.0	5,402.3	-124.2	5,403.6	0.00	0.00	0.00
17,000.0	90.00	359.43	11,280.0	5,502.3	-125.2	5,503.6	0.00	0.00	0.00
17,005.2	90.00	359.43	11,280.0	5,507.4	-125.3	5,508.7	0.00	0.00	0.00
Sec 27									
17,100.0	90.00	359.43	11,280.0	5,602.3	-126.2	5,603.6	0.00	0.00	0.00
17,200.0	90.00	359.43	11,280.0	5,702.3	-127.2	5,703.6	0.00	0.00	0.00
17,300.0	90.00	359.43	11,280.0	5,802.3	-128.2	5,803.6	0.00	0.00	0.00
17,400.0	90.00	359.43	11,280.0	5,902.2	-129.2	5,903.6	0.00	0.00	0.00
17,500.0	90.00	359.43	11,280.0	6,002.2	-130.2	6,003.6	0.00	0.00	0.00
17,600.0	90.00	359.43	11,280.0	6,102.2	-131.2	6,103.6	0.00	0.00	0.00
17,700.0	90.00	359.43	11,280.0	6,202.2	-132.2	6,203.6	0.00	0.00	0.00
17,800.0	90.00	359.43	11,280.0	6,302.2	-133.2	6,303.6	0.00	0.00	0.00
17,900.0	90.00	359.43	11,280.0	6,402.2	-134.2	6,403.6	0.00	0.00	0.00
18,000.0	90.00	359.43	11,280.0	6,502.2	-135.2	6,503.6	0.00	0.00	0.00
18,100.0	90.00	359.43	11,280.0	6,602.2	-136.2	6,603.6	0.00	0.00	0.00
18,200.0	90.00	359.43	11,280.0	6,702.2	-137.2	6,703.6	0.00	0.00	0.00
18,300.0	90.00	359.43	11,280.0	6,802.2	-138.2	6,803.6	0.00	0.00	0.00
18,400.0	90.00	359.43	11,280.0	6,902.2	-139.2	6,903.6	0.00	0.00	0.00
18,500.0	90.00	359.43	11,280.0	7,002.2	-140.2	7,003.6	0.00	0.00	0.00
18,600.0	90.00	359.43	11,280.0	7,102.2	-141.2	7,103.5	0.00	0.00	0.00
18,700.0	90.00	359.43	11,280.0	7,202.2	-142.2	7,203.5	0.00	0.00	0.00
18,800.0	90.00	359.43	11,280.0	7,302.2	-143.2	7,303.5	0.00	0.00	0.00
18,900.0	90.00	359.43	11,280.0	7,402.2	-144.2	7,403.5	0.00	0.00	0.00
19,000.0	90.00	359.43	11,280.0	7,502.2	-145.2	7,503.5	0.00	0.00	0.00
19,100.0	90.00	359.43	11,280.0	7,602.2	-146.2	7,603.5	0.00	0.00	0.00
19,200.0	90.00	359.43	11,280.0	7,702.2	-147.2	7,703.5	0.00	0.00	0.00
19,300.0	90.00	359.43	11,280.0	7,802.2	-148.2	7,803.5	0.00	0.00	0.00
19,400.0	90.00	359.43	11,280.0	7,902.1	-149.2	7,903.5	0.00	0.00	0.00
19,500.0	90.00	359.43	11,280.0	8,002.1	-150.2	8,003.5	0.00	0.00	0.00
19,600.0	90.00	359.43	11,280.0	8,102.1	-151.2	8,103.5	0.00	0.00	0.00
19,700.0	90.00	359.43	11,280.0	8,202.1	-152.2	8,203.5	0.00	0.00	0.00
19,800.0	90.00	359.43	11,280.0	8,302.1	-153.3	8,303.5	0.00	0.00	0.00
19,900.0	90.00	359.43	11,280.0	8,402.1	-154.3	8,403.5	0.00	0.00	0.00
20,000.0	90.00	359.43	11,280.0	8,502.1	-155.3	8,503.5	0.00	0.00	0.00
20,100.0	90.00	359.43	11,280.0	8,602.1	-156.3	8,603.5	0.00	0.00	0.00

Database:	EDM5000	Local Co-ordinate Reference:	Well Juniper 091H
Company:	Ameredev Operating, LLC.	TVD Reference:	KB @ 3019.0usft
Project:	JUN/PIM	MD Reference:	KB @ 3019.0usft
Site:	JUN/PIM #1S	North Reference:	Grid
Well:	Juniper 091H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Design #1		

Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
20,200.0	90.00	359.43	11,280.0	8,702.1	-157.3	8,703.5	0.00	0.00	0.00
20,300.0	90.00	359.43	11,280.0	8,802.1	-158.3	8,803.5	0.00	0.00	0.00
20,400.0	90.00	359.43	11,280.0	8,902.1	-159.3	8,903.5	0.00	0.00	0.00
20,500.0	90.00	359.43	11,280.0	9,002.1	-160.3	9,003.5	0.00	0.00	0.00
20,600.0	90.00	359.43	11,280.0	9,102.1	-161.3	9,103.5	0.00	0.00	0.00
20,700.0	90.00	359.43	11,280.0	9,202.1	-162.3	9,203.5	0.00	0.00	0.00
20,800.0	90.00	359.43	11,280.0	9,302.1	-163.3	9,303.5	0.00	0.00	0.00
20,900.0	90.00	359.43	11,280.0	9,402.1	-164.3	9,403.5	0.00	0.00	0.00
21,000.0	90.00	359.43	11,280.0	9,502.1	-165.3	9,503.5	0.00	0.00	0.00
21,100.0	90.00	359.43	11,280.0	9,602.1	-166.3	9,603.5	0.00	0.00	0.00
21,200.0	90.00	359.43	11,280.0	9,702.1	-167.3	9,703.5	0.00	0.00	0.00
21,300.0	90.00	359.43	11,280.0	9,802.0	-168.3	9,803.5	0.00	0.00	0.00
21,400.0	90.00	359.43	11,280.0	9,902.0	-169.3	9,903.5	0.00	0.00	0.00
21,500.0	90.00	359.43	11,280.0	10,002.0	-170.3	10,003.5	0.00	0.00	0.00
21,600.0	90.00	359.43	11,280.0	10,102.0	-171.3	10,103.5	0.00	0.00	0.00
21,700.0	90.00	359.43	11,280.0	10,202.0	-172.3	10,203.5	0.00	0.00	0.00
21,800.0	90.00	359.43	11,280.0	10,302.0	-173.3	10,303.5	0.00	0.00	0.00
21,900.0	90.00	359.43	11,280.0	10,402.0	-174.3	10,403.5	0.00	0.00	0.00
22,000.0	90.00	359.43	11,280.0	10,502.0	-175.3	10,503.5	0.00	0.00	0.00
22,100.0	90.00	359.43	11,280.0	10,602.0	-176.3	10,603.5	0.00	0.00	0.00
22,183.3	90.00	359.43	11,280.0	10,685.3	-177.1	10,686.7	0.00	0.00	0.00
Jun091 LTP									
22,200.0	90.00	359.43	11,280.0	10,702.0	-177.3	10,703.5	0.00	0.00	0.00
22,233.3	90.00	359.43	11,280.0	10,735.3	-177.6	10,736.7	0.00	0.00	0.00
Jun091 BHL									

Database:	EDM5000	Local Co-ordinate Reference:	Well Juniper 091H
Company:	Ameredev Operating, LLC.	TVD Reference:	KB @ 3019.0usft
Project:	JUN/PIM	MD Reference:	KB @ 3019.0usft
Site:	JUN/PIM #1S	North Reference:	Grid
Well:	Juniper 091H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Design #1		

Design Targets

Target Name - hit/miss target - Shape	Dip Angle (°)	Dip Dir. (°)	TVD (usft)	+N/-S (usft)	+E/-W (usft)	Northing (usft)	Easting (usft)	Latitude	Longitude
Jun091 KOP - plan hits target center - Point	0.00	0.00	10,775.0	-418.7	36.6	393,691.66	873,604.81	32° 4' 40.068 N	103° 15' 38.098 W
Jun091 BHL - plan misses target center by 0.1usft at 22233.3usft MD (11280.0 TVD, 10735.3 N, -177.6 E) - Point	0.00	0.00	11,280.0	10,735.3	-177.7	404,845.65	873,390.50	32° 6' 30.452 N	103° 15' 39.299 W
Jun091 LTP - plan misses target center by 0.1usft at 22183.3usft MD (11280.0 TVD, 10685.3 N, -177.1 E) - Point	0.00	0.00	11,280.0	10,685.3	-177.2	404,795.66	873,390.96	32° 6' 29.958 N	103° 15' 39.300 W
Jun091 FTP - plan hits target center - Point	0.00	0.00	11,280.0	329.3	-73.4	394,439.73	873,494.80	32° 4' 47.481 N	103° 15' 39.290 W
Sec 03 - plan misses target center by 4690.7usft at 10900.0usft MD (10877.7 TVD, -407.7 N, 34.9 E) - Polygon	0.00	0.00	11,471.0	-5,053.8	-219.0	389,056.56	873,349.16	32° 3' 54.231 N	103° 15' 41.604 W
Point 1			11,471.0	0.0	0.0	389,056.56	873,349.16		
Point 2			11,471.0	5,281.2	-53.3	394,337.76	873,295.86		
Point 3			11,471.0	5,330.6	5,227.9	394,387.16	878,577.06		
Point 4			11,471.0	47.9	5,279.4	389,104.46	878,628.56		
Sec 34 - plan misses target center by 283.1usft at 11759.5usft MD (11277.2 TVD, 262.2 N, -68.9 E) - Polygon	0.00	0.00	11,471.0	227.4	-272.3	394,337.79	873,295.83	32° 4' 46.491 N	103° 15' 41.614 W
Point 1			11,471.0	0.0	0.0	394,337.79	873,295.83		
Point 2			11,471.0	5,278.0	-53.8	399,615.79	873,242.03		
Point 3			11,471.0	5,326.9	5,230.6	399,664.69	878,526.43		
Point 4			11,471.0	49.4	5,281.3	394,387.19	878,577.13		
Sec 27 - plan misses target center by 329.4usft at 17005.2usft MD (11280.0 TVD, 5507.4 N, -125.3 E) - Polygon	0.00	0.00	11,541.0	5,505.4	-326.2	399,615.80	873,242.02	32° 5' 38.720 N	103° 15' 41.630 W
Point 1			11,541.0	0.0	0.0	399,615.80	873,242.02		
Point 2			11,541.0	5,278.0	-52.0	404,893.80	873,190.02		
Point 3			11,541.0	5,328.3	5,215.5	404,944.10	878,457.52		
Point 4			11,541.0	48.8	5,284.4	399,664.60	878,528.42		

AMEREDEV

Ameredev Operating, LLC.

JUN/PIM

JUN/PIM #1S

Juniper 091H

Wellbore #1

Plan: Design #1

Lease Penetration Section Line Footages

14 January, 2019

Company: Ameredev Operating, LLC.	Local Co-ordinate Reference: Well Juniper 091H
Project: JUN/PIM	TVD Reference: KB @ 3019.0usft
Site: JUN/PIM #1S	MD Reference: KB @ 3019.0usft
Well: Juniper 091H	North Reference: Grid
Wellbore: Wellbore #1	Survey Calculation Method: Minimum Curvature
Design: Design #1	Database: EDM5000

Project JUN/PIM	
Map System: US State Plane 1983	System Datum: Mean Sea Level
Geo Datum: North American Datum 1983	
Map Zone: New Mexico Eastern Zone	

Site JUN/PIM #1S		
Site Position:	Northing: 394,110.55 usft	Latitude: 32° 4' 44.214 N
From: Lat/Long	Easting: 873,588.15 usft	Longitude: 103° 15' 38.243 W
Position Uncertainty: 0.0 usft	Slot Radius: 13-3/16 "	Grid Convergence: 0.57 °

Well Juniper 091H		
Well Position +N/-S 0.0 usft	Northing: 394,110.39 usft	Latitude: 32° 4' 44.215 N
+E/-W 0.0 usft	Easting: 873,568.17 usft	Longitude: 103° 15' 38.475 W
Position Uncertainty 0.0 usft	Wellhead Elevation: usft	Ground Level: 2,992.0 usft

Wellbore Wellbore #1					
Magnetics	Model Name	Sample Date	Declination	Dip Angle	Field Strength
			(°)	(°)	(nT)
	IGRF2015	1/11/2019	6.63	59.96	47,725.911111583

Design Design #1				
Audit Notes:				
Version:	Phase: PROTOTYPE	Tie On Depth: 0.0		
Vertical Section:	Depth From (TVD)	+N/-S	+E/-W	Direction
	(usft)	(usft)	(usft)	(°)
	0.0	0.0	0.0	359.05

Survey Tool Program	Date 1/14/2019			
From	To	Survey (Wellbore)	Tool Name	Description
(usft)	(usft)			
0.0	22,233.3	Design #1 (Wellbore #1)	MWD	OWSG MWD - Standard

Company: Ameredev Operating, LLC.
Project: JUN/PIM
Site: JUN/PIM #1S
Well: Juniper 091H
Wellbore: Wellbore #1
Design: Design #1

Local Co-ordinate Reference: Well Juniper 091H
TVD Reference: KB @ 3019.0usft
MD Reference: KB @ 3019.0usft
North Reference: Grid
Survey Calculation Method: Minimum Curvature
Database: EDM5000

Planned Survey

MD (usft)	Inc (°)	Azi (azimuth) (°)	TVD (usft)	+FSL/-FNL (usft)	+FWL/-FEL (usft)	V. Sec (usft)	DLeg (°/100usft)	Build (°/100usft)	Turn (°/100usft)
0.0	0.00	0.00	0.0	-230.2	270.0	0.0	0.00	0.00	0.00
100.0	0.00	0.00	100.0	-230.2	270.0	0.0	0.00	0.00	0.00
200.0	0.00	0.00	200.0	-230.2	270.0	0.0	0.00	0.00	0.00
300.0	0.00	0.00	300.0	-230.2	270.0	0.0	0.00	0.00	0.00
400.0	0.00	0.00	400.0	-230.2	270.0	0.0	0.00	0.00	0.00
500.0	0.00	0.00	500.0	-230.2	270.0	0.0	0.00	0.00	0.00
600.0	0.00	0.00	600.0	-230.2	270.0	0.0	0.00	0.00	0.00
700.0	0.00	0.00	700.0	-230.2	270.0	0.0	0.00	0.00	0.00
800.0	0.00	0.00	800.0	-230.2	270.0	0.0	0.00	0.00	0.00
900.0	0.00	0.00	900.0	-230.2	270.0	0.0	0.00	0.00	0.00
1,000.0	0.00	0.00	1,000.0	-230.2	270.0	0.0	0.00	0.00	0.00
1,100.0	0.00	0.00	1,100.0	-230.2	270.0	0.0	0.00	0.00	0.00
1,200.0	0.00	0.00	1,200.0	-230.2	270.0	0.0	0.00	0.00	0.00
1,300.0	0.00	0.00	1,300.0	-230.2	270.0	0.0	0.00	0.00	0.00
1,400.0	0.00	0.00	1,400.0	-230.2	270.0	0.0	0.00	0.00	0.00
1,500.0	0.00	0.00	1,500.0	-230.2	270.0	0.0	0.00	0.00	0.00
1,600.0	0.00	0.00	1,600.0	-230.2	270.0	0.0	0.00	0.00	0.00
1,700.0	0.00	0.00	1,700.0	-230.2	270.0	0.0	0.00	0.00	0.00
1,800.0	0.00	0.00	1,800.0	-230.2	270.0	0.0	0.00	0.00	0.00
1,900.0	0.00	0.00	1,900.0	-230.2	270.0	0.0	0.00	0.00	0.00
2,000.0	0.00	0.00	2,000.0	-230.2	270.0	0.0	0.00	0.00	0.00
2,100.0	2.00	175.00	2,100.0	-231.9	270.2	-1.7	2.00	2.00	0.00
2,200.0	4.00	175.00	2,199.8	-237.1	270.6	-7.0	2.00	2.00	0.00
2,300.0	6.00	175.00	2,299.5	-245.8	271.4	-15.7	2.00	2.00	0.00
2,400.0	6.00	175.00	2,398.9	-256.2	272.3	-26.1	0.00	0.00	0.00
2,500.0	6.00	175.00	2,498.4	-266.6	273.2	-36.5	0.00	0.00	0.00
2,600.0	6.00	175.00	2,597.8	-277.0	274.1	-46.9	0.00	0.00	0.00

Company: Ameredev Operating, LLC.
Project: JUN/PIM
Site: JUN/PIM #1S
Well: Juniper 091H
Wellbore: Wellbore #1
Design: Design #1

Local Co-ordinate Reference: Well Juniper 091H
TVD Reference: KB @ 3019.0usft
MD Reference: KB @ 3019.0usft
North Reference: Grid
Survey Calculation Method: Minimum Curvature
Database: EDM5000

Planned Survey

MD (usft)	Inc (°)	Azi (azimuth) (°)	TVD (usft)	+FSL/-FNL (usft)	+FWL/-FEL (usft)	V. Sec (usft)	DLeg (°/100usft)	Build (°/100usft)	Turn (°/100usft)
2,700.0	6.00	175.00	2,697.3	-287.4	275.0	-57.4	0.00	0.00	0.00
2,800.0	6.00	175.00	2,796.7	-297.9	275.9	-67.8	0.00	0.00	0.00
2,900.0	6.00	175.00	2,896.2	-308.3	276.9	-78.2	0.00	0.00	0.00
3,000.0	6.00	175.00	2,995.6	-318.7	277.8	-88.6	0.00	0.00	0.00
3,100.0	6.00	175.00	3,095.1	-329.1	278.7	-99.1	0.00	0.00	0.00
3,200.0	6.00	175.00	3,194.5	-339.5	279.6	-109.5	0.00	0.00	0.00
3,300.0	6.00	175.00	3,294.0	-349.9	280.5	-119.9	0.00	0.00	0.00
3,400.0	6.00	175.00	3,393.4	-360.3	281.4	-130.3	0.00	0.00	0.00
3,500.0	6.00	175.00	3,492.9	-370.8	282.3	-140.8	0.00	0.00	0.00
3,600.0	6.00	175.00	3,592.3	-381.2	283.2	-151.2	0.00	0.00	0.00
3,700.0	6.00	175.00	3,691.8	-391.6	284.1	-161.6	0.00	0.00	0.00
3,800.0	6.00	175.00	3,791.2	-402.0	285.1	-172.1	0.00	0.00	0.00
3,900.0	6.00	175.00	3,890.7	-412.4	286.0	-182.5	0.00	0.00	0.00
4,000.0	6.00	175.00	3,990.1	-422.8	286.9	-192.9	0.00	0.00	0.00
4,100.0	6.00	175.00	4,089.6	-433.2	287.8	-203.3	0.00	0.00	0.00
4,200.0	6.00	175.00	4,189.0	-443.6	288.7	-213.8	0.00	0.00	0.00
4,300.0	6.00	175.00	4,288.5	-454.1	289.6	-224.2	0.00	0.00	0.00
4,400.0	6.00	175.00	4,387.9	-464.5	290.5	-234.6	0.00	0.00	0.00
4,500.0	6.00	175.00	4,487.4	-474.9	291.4	-245.0	0.00	0.00	0.00
4,600.0	6.00	175.00	4,586.9	-485.3	292.3	-255.5	0.00	0.00	0.00
4,700.0	6.00	175.00	4,686.3	-495.7	293.3	-265.9	0.00	0.00	0.00
4,800.0	6.00	175.00	4,785.8	-506.1	294.2	-276.3	0.00	0.00	0.00
4,900.0	6.00	175.00	4,885.2	-516.5	295.1	-286.7	0.00	0.00	0.00
5,000.0	6.00	175.00	4,984.7	-526.9	296.0	-297.2	0.00	0.00	0.00
5,100.0	6.00	175.00	5,084.1	-537.4	296.9	-307.6	0.00	0.00	0.00
5,200.0	6.00	175.00	5,183.6	-547.8	297.8	-318.0	0.00	0.00	0.00
5,300.0	6.00	175.00	5,283.0	-558.2	298.7	-328.5	0.00	0.00	0.00

Company: Ameredev Operating, LLC.
Project: JUN/PIM
Site: JUN/PIM #1S
Well: Juniper 091H
Wellbore: Wellbore #1
Design: Design #1

Local Co-ordinate Reference: Well Juniper 091H
TVD Reference: KB @ 3019.0usft
MD Reference: KB @ 3019.0usft
North Reference: Grid
Survey Calculation Method: Minimum Curvature
Database: EDM5000

Planned Survey

MD (usft)	Inc (°)	Azi (azimuth) (°)	TVD (usft)	+FSL/-FNL (usft)	+FWL/-FEL (usft)	V. Sec (usft)	DLeg (°/100usft)	Build (°/100usft)	Turn (°/100usft)
5,400.0	6.00	175.00	5,382.5	-568.6	299.6	-338.9	0.00	0.00	0.00
5,500.0	6.00	175.00	5,481.9	-579.0	300.5	-349.3	0.00	0.00	0.00
5,600.0	6.00	175.00	5,581.4	-589.4	301.5	-359.7	0.00	0.00	0.00
5,700.0	6.00	175.00	5,680.8	-599.8	302.4	-370.2	0.00	0.00	0.00
5,800.0	6.00	175.00	5,780.3	-610.3	303.3	-380.6	0.00	0.00	0.00
5,900.0	6.00	175.00	5,879.7	-620.7	304.2	-391.0	0.00	0.00	0.00
6,000.0	6.00	175.00	5,979.2	-631.1	305.1	-401.4	0.00	0.00	0.00
6,020.9	6.00	175.00	6,000.0	-633.3	305.3	-403.6	0.00	0.00	0.00
6,100.0	4.42	175.00	6,078.7	-640.4	305.9	-410.8	2.00	-2.00	0.00
6,200.0	2.42	175.00	6,178.6	-646.4	306.4	-416.7	2.00	-2.00	0.00
6,300.0	0.42	175.00	6,278.5	-648.8	306.6	-419.2	2.00	-2.00	0.00
6,320.9	0.00	0.00	6,299.5	-648.9	306.7	-419.3	2.00	-2.00	0.00
6,400.0	0.00	0.00	6,378.5	-648.9	306.7	-419.3	0.00	0.00	0.00
6,500.0	0.00	0.00	6,478.5	-648.9	306.7	-419.3	0.00	0.00	0.00
6,600.0	0.00	0.00	6,578.5	-648.9	306.7	-419.3	0.00	0.00	0.00
6,700.0	0.00	0.00	6,678.5	-648.9	306.7	-419.3	0.00	0.00	0.00
6,800.0	0.00	0.00	6,778.5	-648.9	306.7	-419.3	0.00	0.00	0.00
6,900.0	0.00	0.00	6,878.5	-648.9	306.7	-419.3	0.00	0.00	0.00
7,000.0	0.00	0.00	6,978.5	-648.9	306.7	-419.3	0.00	0.00	0.00
7,100.0	0.00	0.00	7,078.5	-648.9	306.7	-419.3	0.00	0.00	0.00
7,200.0	0.00	0.00	7,178.5	-648.9	306.7	-419.3	0.00	0.00	0.00
7,300.0	0.00	0.00	7,278.5	-648.9	306.7	-419.3	0.00	0.00	0.00
7,400.0	0.00	0.00	7,378.5	-648.9	306.7	-419.3	0.00	0.00	0.00
7,500.0	0.00	0.00	7,478.5	-648.9	306.7	-419.3	0.00	0.00	0.00
7,600.0	0.00	0.00	7,578.5	-648.9	306.7	-419.3	0.00	0.00	0.00
7,700.0	0.00	0.00	7,678.5	-648.9	306.7	-419.3	0.00	0.00	0.00
7,800.0	0.00	0.00	7,778.5	-648.9	306.7	-419.3	0.00	0.00	0.00

Company: Ameredev Operating, LLC.
Project: JUN/PIM
Site: JUN/PIM #1S
Well: Juniper 091H
Wellbore: Wellbore #1
Design: Design #1

Local Co-ordinate Reference: Well Juniper 091H
TVD Reference: KB @ 3019.0usft
MD Reference: KB @ 3019.0usft
North Reference: Grid
Survey Calculation Method: Minimum Curvature
Database: EDM5000

Planned Survey

MD (usft)	Inc (°)	Azi (azimuth) (°)	TVD (usft)	+FSL-FNL (usft)	+FWL-FEL (usft)	V. Sec (usft)	DLeg (°/100usft)	Build (°/100usft)	Turn (°/100usft)
7,900.0	0.00	0.00	7,878.5	-648.9	306.7	-419.3	0.00	0.00	0.00
8,000.0	0.00	0.00	7,978.5	-648.9	306.7	-419.3	0.00	0.00	0.00
8,100.0	0.00	0.00	8,078.5	-648.9	306.7	-419.3	0.00	0.00	0.00
8,200.0	0.00	0.00	8,178.5	-648.9	306.7	-419.3	0.00	0.00	0.00
8,300.0	0.00	0.00	8,278.5	-648.9	306.7	-419.3	0.00	0.00	0.00
8,400.0	0.00	0.00	8,378.5	-648.9	306.7	-419.3	0.00	0.00	0.00
8,500.0	0.00	0.00	8,478.5	-648.9	306.7	-419.3	0.00	0.00	0.00
8,600.0	0.00	0.00	8,578.5	-648.9	306.7	-419.3	0.00	0.00	0.00
8,700.0	0.00	0.00	8,678.5	-648.9	306.7	-419.3	0.00	0.00	0.00
8,800.0	0.00	0.00	8,778.5	-648.9	306.7	-419.3	0.00	0.00	0.00
8,900.0	0.00	0.00	8,878.5	-648.9	306.7	-419.3	0.00	0.00	0.00
9,000.0	0.00	0.00	8,978.5	-648.9	306.7	-419.3	0.00	0.00	0.00
9,100.0	0.00	0.00	9,078.5	-648.9	306.7	-419.3	0.00	0.00	0.00
9,200.0	0.00	0.00	9,178.5	-648.9	306.7	-419.3	0.00	0.00	0.00
9,300.0	0.00	0.00	9,278.5	-648.9	306.7	-419.3	0.00	0.00	0.00
9,400.0	0.00	0.00	9,378.5	-648.9	306.7	-419.3	0.00	0.00	0.00
9,500.0	0.00	0.00	9,478.5	-648.9	306.7	-419.3	0.00	0.00	0.00
9,600.0	0.00	0.00	9,578.5	-648.9	306.7	-419.3	0.00	0.00	0.00
9,700.0	0.00	0.00	9,678.5	-648.9	306.7	-419.3	0.00	0.00	0.00
9,800.0	0.00	0.00	9,778.5	-648.9	306.7	-419.3	0.00	0.00	0.00
9,900.0	0.00	0.00	9,878.5	-648.9	306.7	-419.3	0.00	0.00	0.00
10,000.0	0.00	0.00	9,978.5	-648.9	306.7	-419.3	0.00	0.00	0.00
10,100.0	0.00	0.00	10,078.5	-648.9	306.7	-419.3	0.00	0.00	0.00
10,200.0	0.00	0.00	10,178.5	-648.9	306.7	-419.3	0.00	0.00	0.00
10,300.0	0.00	0.00	10,278.5	-648.9	306.7	-419.3	0.00	0.00	0.00
10,400.0	0.00	0.00	10,378.5	-648.9	306.7	-419.3	0.00	0.00	0.00
10,500.0	0.00	0.00	10,478.5	-648.9	306.7	-419.3	0.00	0.00	0.00

Company: Ameredev Operating, LLC.
Project: JUN/PIM
Site: JUN/PIM #1S
Well: Juniper 091H
Wellbore: Wellbore #1
Design: Design #1

Local Co-ordinate Reference: Well Juniper 091H
TVD Reference: KB @ 3019.0usft
MD Reference: KB @ 3019.0usft
North Reference: Grid
Survey Calculation Method: Minimum Curvature
Database: EDM5000

Planned Survey

MD (usft)	Inc (°)	Azi (azimuth) (°)	TVD (usft)	+FSL-FNL (usft)	+FWL-FEL (usft)	V. Sec (usft)	DLeg (°/100usft)	Build (°/100usft)	Turn (°/100usft)	
10,600.0	0.00	0.00	10,578.5	-648.9	306.7	-419.3	0.00	0.00	0.00	
10,700.0	0.00	0.00	10,678.5	-648.9	306.7	-419.3	0.00	0.00	0.00	
10,796.5	0.00	0.00	10,775.0	-648.9	306.7	-419.3	0.00	0.00	0.00	
Jun091 KOP										
10,800.0	0.42	351.17	10,778.5	-648.9	306.7	-419.3	12.00	12.00	0.00	
10,900.0	12.42	351.17	10,877.7	-637.8	304.9	-408.2	12.00	12.00	0.00	
Sec 03										
11,000.0	24.42	351.17	10,972.4	-606.7	300.1	-377.0	12.00	12.00	0.00	
11,100.0	36.42	351.17	11,058.5	-556.7	292.3	-326.9	12.00	12.00	0.00	
11,200.0	48.42	351.17	11,132.2	-490.2	282.0	-260.2	12.00	12.00	0.00	
11,300.0	60.42	351.17	11,190.2	-410.0	269.5	-179.8	12.00	12.00	0.00	
11,400.0	72.42	351.17	11,230.2	-319.6	255.5	-89.2	12.00	12.00	0.00	
11,496.4	83.99	351.17	11,249.8	-226.5	241.0	4.2	12.00	12.00	0.00	
11,500.0	83.99	351.17	11,250.2	-222.9	240.5	7.7	0.00	0.00	0.00	
11,600.0	83.99	351.17	11,260.7	-124.7	225.2	106.2	0.00	0.00	0.00	
11,700.0	83.99	351.17	11,271.2	-26.4	210.0	204.7	0.00	0.00	0.00	
11,741.8	83.99	351.17	11,275.5	14.7	203.6	245.9	0.00	0.00	0.00	
11,759.5	85.23	352.89	11,277.2	32.1	201.1	263.4	12.00	7.04	9.76	
Sec 34										
11,800.0	88.10	356.83	11,279.6	72.4	197.5	303.7	12.00	7.07	9.71	
11,826.8	90.00	359.43	11,280.0	99.2	196.6	330.5	12.00	7.09	9.68	
Jun091 FTP										
11,900.0	90.00	359.43	11,280.0	172.4	195.9	403.7	0.00	0.00	0.00	
12,000.0	90.00	359.43	11,280.0	272.4	194.9	503.7	0.00	0.00	0.00	
12,100.0	90.00	359.43	11,280.0	372.3	193.9	603.7	0.00	0.00	0.00	
12,200.0	90.00	359.43	11,280.0	472.3	192.9	703.7	0.00	0.00	0.00	
12,300.0	90.00	359.43	11,280.0	572.3	191.9	803.7	0.00	0.00	0.00	

Company: Ameredev Operating, LLC.
Project: JUN/PIM
Site: JUN/PIM #1S
Well: Juniper 091H
Wellbore: Wellbore #1
Design: Design #1

Local Co-ordinate Reference: Well Juniper 091H
TVD Reference: KB @ 3019.0usft
MD Reference: KB @ 3019.0usft
North Reference: Grid
Survey Calculation Method: Minimum Curvature
Database: EDM5000

Planned Survey

MD (usft)	Inc (°)	Azi (azimuth) (°)	TVD (usft)	+FSL-FNL (usft)	+FWL-FEL (usft)	V. Sec (usft)	DLeg (°/100usft)	Build (°/100usft)	Turn (°/100usft)
12,400.0	90.00	359.43	11,280.0	672.3	190.9	903.7	0.00	0.00	0.00
12,500.0	90.00	359.43	11,280.0	772.3	189.9	1,003.7	0.00	0.00	0.00
12,600.0	90.00	359.43	11,280.0	872.3	188.9	1,103.7	0.00	0.00	0.00
12,700.0	90.00	359.43	11,280.0	972.3	187.9	1,203.7	0.00	0.00	0.00
12,800.0	90.00	359.43	11,280.0	1,072.3	186.9	1,303.7	0.00	0.00	0.00
12,900.0	90.00	359.43	11,280.0	1,172.3	185.9	1,403.7	0.00	0.00	0.00
13,000.0	90.00	359.43	11,280.0	1,272.3	184.9	1,503.7	0.00	0.00	0.00
13,100.0	90.00	359.43	11,280.0	1,372.3	183.9	1,603.7	0.00	0.00	0.00
13,200.0	90.00	359.43	11,280.0	1,472.3	182.9	1,703.7	0.00	0.00	0.00
13,300.0	90.00	359.43	11,280.0	1,572.3	181.9	1,803.7	0.00	0.00	0.00
13,400.0	90.00	359.43	11,280.0	1,672.3	180.9	1,903.7	0.00	0.00	0.00
13,500.0	90.00	359.43	11,280.0	1,772.3	179.9	2,003.7	0.00	0.00	0.00
13,600.0	90.00	359.43	11,280.0	1,872.3	178.9	2,103.7	0.00	0.00	0.00
13,700.0	90.00	359.43	11,280.0	1,972.3	177.9	2,203.7	0.00	0.00	0.00
13,800.0	90.00	359.43	11,280.0	2,072.3	176.9	2,303.7	0.00	0.00	0.00
13,900.0	90.00	359.43	11,280.0	2,172.3	175.9	2,403.6	0.00	0.00	0.00
14,000.0	90.00	359.43	11,280.0	2,272.3	174.9	2,503.6	0.00	0.00	0.00
14,100.0	90.00	359.43	11,280.0	2,372.2	173.9	2,603.6	0.00	0.00	0.00
14,200.0	90.00	359.43	11,280.0	2,472.2	172.9	2,703.6	0.00	0.00	0.00
14,300.0	90.00	359.43	11,280.0	2,572.2	171.9	2,803.6	0.00	0.00	0.00
14,400.0	90.00	359.43	11,280.0	2,672.2	170.9	2,903.6	0.00	0.00	0.00
14,500.0	90.00	359.43	11,280.0	2,772.2	169.9	3,003.6	0.00	0.00	0.00
14,600.0	90.00	359.43	11,280.0	2,872.2	168.9	3,103.6	0.00	0.00	0.00
14,700.0	90.00	359.43	11,280.0	2,972.2	167.9	3,203.6	0.00	0.00	0.00
14,800.0	90.00	359.43	11,280.0	3,072.2	166.9	3,303.6	0.00	0.00	0.00
14,900.0	90.00	359.43	11,280.0	3,172.2	165.9	3,403.6	0.00	0.00	0.00
15,000.0	90.00	359.43	11,280.0	3,272.2	164.9	3,503.6	0.00	0.00	0.00

Company: Ameredev Operating, LLC.
Project: JUN/PIM
Site: JUN/PIM #1S
Well: Juniper 091H
Wellbore: Wellbore #1
Design: Design #1

Local Co-ordinate Reference: Well Juniper 091H
TVD Reference: KB @ 3019.0usft
MD Reference: KB @ 3019.0usft
North Reference: Grid
Survey Calculation Method: Minimum Curvature
Database: EDM5000

Planned Survey

MD (usft)	Inc (°)	Azi (azimuth) (°)	TVD (usft)	+FSL-FNL (usft)	+FWL-FEL (usft)	V. Sec (usft)	DLeg (°/100usft)	Build (°/100usft)	Turn (°/100usft)	
15,100.0	90.00	359.43	11,280.0	3,372.2	163.9	3,603.6	0.00	0.00	0.00	
15,200.0	90.00	359.43	11,280.0	3,472.2	162.9	3,703.6	0.00	0.00	0.00	
15,300.0	90.00	359.43	11,280.0	3,572.2	161.9	3,803.6	0.00	0.00	0.00	
15,400.0	90.00	359.43	11,280.0	3,672.2	160.8	3,903.6	0.00	0.00	0.00	
15,500.0	90.00	359.43	11,280.0	3,772.2	159.8	4,003.6	0.00	0.00	0.00	
15,600.0	90.00	359.43	11,280.0	3,872.2	158.8	4,103.6	0.00	0.00	0.00	
15,700.0	90.00	359.43	11,280.0	3,972.2	157.8	4,203.6	0.00	0.00	0.00	
15,800.0	90.00	359.43	11,280.0	4,072.2	156.8	4,303.6	0.00	0.00	0.00	
15,900.0	90.00	359.43	11,280.0	4,172.2	155.8	4,403.6	0.00	0.00	0.00	
16,000.0	90.00	359.43	11,280.0	4,272.2	154.8	4,503.6	0.00	0.00	0.00	
16,100.0	90.00	359.43	11,280.0	4,372.1	153.8	4,603.6	0.00	0.00	0.00	
16,200.0	90.00	359.43	11,280.0	4,472.1	152.8	4,703.6	0.00	0.00	0.00	
16,300.0	90.00	359.43	11,280.0	4,572.1	151.8	4,803.6	0.00	0.00	0.00	
16,400.0	90.00	359.43	11,280.0	4,672.1	150.8	4,903.6	0.00	0.00	0.00	
16,500.0	90.00	359.43	11,280.0	4,772.1	149.8	5,003.6	0.00	0.00	0.00	
16,600.0	90.00	359.43	11,280.0	4,872.1	148.8	5,103.6	0.00	0.00	0.00	
16,700.0	90.00	359.43	11,280.0	4,972.1	147.8	5,203.6	0.00	0.00	0.00	
16,800.0	90.00	359.43	11,280.0	5,072.1	146.8	5,303.6	0.00	0.00	0.00	
16,900.0	90.00	359.43	11,280.0	5,172.1	145.8	5,403.6	0.00	0.00	0.00	
17,000.0	90.00	359.43	11,280.0	5,272.1	144.8	5,503.6	0.00	0.00	0.00	
17,005.2	90.00	359.43	11,280.0	5,277.3	144.8	5,508.7	0.00	0.00	0.00	
Sec 27										
17,100.0	90.00	359.43	11,280.0	5,372.1	143.8	5,603.6	0.00	0.00	0.00	
17,200.0	90.00	359.43	11,280.0	5,472.1	142.8	5,703.6	0.00	0.00	0.00	
17,300.0	90.00	359.43	11,280.0	5,572.1	141.8	5,803.6	0.00	0.00	0.00	
17,400.0	90.00	359.43	11,280.0	5,672.1	140.8	5,903.6	0.00	0.00	0.00	
17,500.0	90.00	359.43	11,280.0	5,772.1	139.8	6,003.6	0.00	0.00	0.00	

Company: Ameredev Operating, LLC.
Project: JUN/PIM
Site: JUN/PIM #1S
Well: Juniper 091H
Wellbore: Wellbore #1
Design: Design #1

Local Co-ordinate Reference: Well Juniper 091H
TVD Reference: KB @ 3019.0usft
MD Reference: KB @ 3019.0usft
North Reference: Grid
Survey Calculation Method: Minimum Curvature
Database: EDM5000

Planned Survey

MD (usft)	Inc (°)	Azi (azimuth) (°)	TVD (usft)	+FSL-FNL (usft)	+FWL-FEL (usft)	V. Sec (usft)	DLeg (°/100usft)	Build (°/100usft)	Turn (°/100usft)
17,600.0	90.00	359.43	11,280.0	5,872.1	138.8	6,103.6	0.00	0.00	0.00
17,700.0	90.00	359.43	11,280.0	5,972.1	137.8	6,203.6	0.00	0.00	0.00
17,800.0	90.00	359.43	11,280.0	6,072.1	136.8	6,303.6	0.00	0.00	0.00
17,900.0	90.00	359.43	11,280.0	6,172.1	135.8	6,403.6	0.00	0.00	0.00
18,000.0	90.00	359.43	11,280.0	6,272.1	134.8	6,503.6	0.00	0.00	0.00
18,100.0	90.00	359.43	11,280.0	6,372.0	133.8	6,603.6	0.00	0.00	0.00
18,200.0	90.00	359.43	11,280.0	6,472.0	132.8	6,703.6	0.00	0.00	0.00
18,300.0	90.00	359.43	11,280.0	6,572.0	131.8	6,803.6	0.00	0.00	0.00
18,400.0	90.00	359.43	11,280.0	6,672.0	130.8	6,903.6	0.00	0.00	0.00
18,500.0	90.00	359.43	11,280.0	6,772.0	129.8	7,003.6	0.00	0.00	0.00
18,600.0	90.00	359.43	11,280.0	6,872.0	128.8	7,103.5	0.00	0.00	0.00
18,700.0	90.00	359.43	11,280.0	6,972.0	127.8	7,203.5	0.00	0.00	0.00
18,800.0	90.00	359.43	11,280.0	7,072.0	126.8	7,303.5	0.00	0.00	0.00
18,900.0	90.00	359.43	11,280.0	7,172.0	125.8	7,403.5	0.00	0.00	0.00
19,000.0	90.00	359.43	11,280.0	7,272.0	124.8	7,503.5	0.00	0.00	0.00
19,100.0	90.00	359.43	11,280.0	7,372.0	123.8	7,603.5	0.00	0.00	0.00
19,200.0	90.00	359.43	11,280.0	7,472.0	122.8	7,703.5	0.00	0.00	0.00
19,300.0	90.00	359.43	11,280.0	7,572.0	121.8	7,803.5	0.00	0.00	0.00
19,400.0	90.00	359.43	11,280.0	7,672.0	120.8	7,903.5	0.00	0.00	0.00
19,500.0	90.00	359.43	11,280.0	7,772.0	119.8	8,003.5	0.00	0.00	0.00
19,600.0	90.00	359.43	11,280.0	7,872.0	118.8	8,103.5	0.00	0.00	0.00
19,700.0	90.00	359.43	11,280.0	7,972.0	117.8	8,203.5	0.00	0.00	0.00
19,800.0	90.00	359.43	11,280.0	8,072.0	116.8	8,303.5	0.00	0.00	0.00
19,900.0	90.00	359.43	11,280.0	8,172.0	115.8	8,403.5	0.00	0.00	0.00
20,000.0	90.00	359.43	11,280.0	8,272.0	114.8	8,503.5	0.00	0.00	0.00
20,100.0	90.00	359.43	11,280.0	8,371.9	113.8	8,603.5	0.00	0.00	0.00
20,200.0	90.00	359.43	11,280.0	8,471.9	112.8	8,703.5	0.00	0.00	0.00

Ameredev Operating, LLC Lease Penetration Section Line Footages

Company: Ameredev Operating, LLC.
Project: JUN/PIM
Site: JUN/PIM #1S
Well: Juniper 091H
Wellbore: Wellbore #1
Design: Design #1

Local Co-ordinate Reference: Well Juniper 091H
TVD Reference: KB @ 3019.0usft
MD Reference: KB @ 3019.0usft
North Reference: Grid
Survey Calculation Method: Minimum Curvature
Database: EDM5000

Planned Survey

MD (usft)	Inc (°)	Azi (azimuth) (°)	TVD (usft)	+FSL-FNL (usft)	+FWL-FEL (usft)	V. Sec (usft)	DLeg (°/100usft)	Build (°/100usft)	Turn (°/100usft)
20,300.0	90.00	359.43	11,280.0	8,571.9	111.8	8,803.5	0.00	0.00	0.00
20,400.0	90.00	359.43	11,280.0	8,671.9	110.8	8,903.5	0.00	0.00	0.00
20,500.0	90.00	359.43	11,280.0	8,771.9	109.8	9,003.5	0.00	0.00	0.00
20,600.0	90.00	359.43	11,280.0	8,871.9	108.8	9,103.5	0.00	0.00	0.00
20,700.0	90.00	359.43	11,280.0	8,971.9	107.8	9,203.5	0.00	0.00	0.00
20,800.0	90.00	359.43	11,280.0	9,071.9	106.8	9,303.5	0.00	0.00	0.00
20,900.0	90.00	359.43	11,280.0	9,171.9	105.8	9,403.5	0.00	0.00	0.00
21,000.0	90.00	359.43	11,280.0	9,271.9	104.7	9,503.5	0.00	0.00	0.00
21,100.0	90.00	359.43	11,280.0	9,371.9	103.7	9,603.5	0.00	0.00	0.00
21,200.0	90.00	359.43	11,280.0	9,471.9	102.7	9,703.5	0.00	0.00	0.00
21,300.0	90.00	359.43	11,280.0	9,571.9	101.7	9,803.5	0.00	0.00	0.00
21,400.0	90.00	359.43	11,280.0	9,671.9	100.7	9,903.5	0.00	0.00	0.00
21,500.0	90.00	359.43	11,280.0	9,771.9	99.7	10,003.5	0.00	0.00	0.00
21,600.0	90.00	359.43	11,280.0	9,871.9	98.7	10,103.5	0.00	0.00	0.00
21,700.0	90.00	359.43	11,280.0	9,971.9	97.7	10,203.5	0.00	0.00	0.00
21,800.0	90.00	359.43	11,280.0	10,071.9	96.7	10,303.5	0.00	0.00	0.00
21,900.0	90.00	359.43	11,280.0	10,171.9	95.7	10,403.5	0.00	0.00	0.00
22,000.0	90.00	359.43	11,280.0	10,271.9	94.7	10,503.5	0.00	0.00	0.00
22,100.0	90.00	359.43	11,280.0	10,371.8	93.7	10,603.5	0.00	0.00	0.00
22,183.3	90.00	359.43	11,280.0	10,455.1	92.9	10,686.7	0.00	0.00	0.00
Jun091 LTP									
22,200.0	90.00	359.43	-11,280.0	10,471.8	92.7	10,703.5	0.00	0.00	0.00
22,233.3	90.00	359.43	11,280.0	10,505.1	92.4	10,736.7	0.00	0.00	0.00
Jun091 BHL									

5M Annular Preventer Variance Request and Well Control Procedures

Note: A copy of the Well Control Plan must be available at multiple locations on the rig for review by rig personnel, as well as review by the BLM PET/PE, and a copy must be maintained on the rig floor.

Dual Isolation Design for 5M Annular Exception

Ameredev will utilize 13-5/8" 10M (5M Annular) BOPE System consisting of:

- 13-5/8" 5M Annular
- 13-5/8" 10M Upper Pipe Rams
 - 3-1/2" – 5-1/2" Variable Bore Ram
- 13-5/8" 10M Blind Rams
- 13-5/8" 10M Drilling Spool /w 2 - 4" 10M Outlets Double 10M Isolation Valves
- 13-5/8" 10M Lower Blind Rams
 - 3-1/2" – 5-1/2" Variable Bore Ram

All drilling components and casing associated to exposure > 5000 psi BHP requiring a 10M system will have a double isolation (secondary barrier) below the 5M Annular that would provide a barrier to flow. The mud system will always be primary barrier, it will be maintained by adjusting values based on tourly mud tests and monitoring a PVT System to maintain static wellbore conditions, displacement procedures will be followed and recorded on daily drilling reports during tripping operations. Surge and swab pressure values will be calculated and maintained and static flow check will be monitored at previous casing shoe and verified static well conditions prior to tripping out of hole and again prior to pulling last joint of drill pipe through BOPE. The below table, documents that two barriers to flow can be maintained at all times, independent of the rating of the annular preventer.

Drill Components	Size	Primary Barrier	Secondary Barrier	Third Barrier
Drillpipe	3-1/2"-5-1/2"	Drilling Fluid	Upper Pipe Rams	Lower Pipe Rams
HWDP Drillpipe	3-1/2"-5-1/2"	Drilling Fluid	Upper Pipe Rams	Lower Pipe Rams
Drill Collars	3-1/2"-5-1/2"	Drilling Fluid	Upper Pipe Rams	Lower Pipe Rams
Production Casing	3-1/2"-5-1/2"	Drilling Fluid	Upper Pipe Rams	Lower Pipe Rams
Open Hole	13-5/8	Drilling Fluid	Blind Rams	

All Drilling Components in 10M Environment will have OD that will allow full Operational RATED WORKING PRESSURE for system design. Kill line with minimum 2" ID will be available outside substructure with 10M Check Valve for OOH Kill Operations

Well Control Procedures

Proper well control procedures are dependent to differentiating well conditions, to cover the basic well control operations there are will be standard drilling ahead, tripping pipe, tripping BHA, running casing, and pipe out of the hole/open hole scenarios that will be defined by procedures below. Initial Shut In Pressure can be taken against the Uppermost BOPE component the 5M Annular, pressure control can be transferred from the lesser 5M Annular to the 10M Upper Pipe Rams if needed. Shut In Pressures may be equal to or less than the Rated Working Pressure but at no time will the pressure on the annular preventer exceed the Rated Working Pressure of the annular. The annular will be tested to 5,000 psi. This will be the Rated Working Pressure of the annular preventer. All scenarios will be written such as shut in will be performed by closing the 10,000 psi Upper Pipe Rams for faster Accumulator pressure recovery to allow safer reaction to controlling wellbore pressure.

Shutting In While Drilling

1. Sound alarm signaling well control event to Rig Crew
2. Space out drill string to allow FOSV installation
3. Shut down pumps
4. Shut in Upper Pipe Rams and open HCR against Open Chokes and Valves
Open to working pressure gauge
5. Install open, full open safety valve and close valve, Close Chokes
6. Verify well is shut-in and flow has stopped
7. Notify supervisory personnel
8. Record data (SIDP, SICP, Pit Gain, and Time)
9. Hold pre-job safety meeting and discuss kill procedure

Shutting In While Tripping

1. Sound alarm signaling well control event to Rig Crew
2. Space out drill string to allow FOSV installation
3. Shut in Upper Pipe Rams and open HCR against Open Chokes and Valves
Open to working pressure gauge
4. Install open, full open safety valve and close valve, Close Chokes
5. Verify well is shut-in and flow has stopped
6. Notify supervisory personnel
7. Record data (SIDP, SICP, Pit Gain, and Time)
8. Hold pre-job safety meeting and discuss kill procedure

Shutting In While Running Casing

1. Sound alarm signaling well control event to Rig Crew
2. Space out casing to allow circulating swedge installation
3. Shut in Upper Pipe Rams and open HCR against Open Chokes and Valves
Open to working pressure gauge
4. Install circulating swedge, Close high pressure, low torque valves, Close Chokes
5. Verify well is shut-in and flow has stopped
6. Notify supervisory personnel
7. Record data (SIDP, SICP, Pit Gain, and Time)
8. Hold Pre-job safety meeting and discuss kill procedure

Shutting in while out of hole

1. Sound alarm signaling well control event to Rig Crew
2. Shut-in well: close blind rams and open HCR against Open Chokes and Valves
Open to working pressure gauge
3. Close Chokes, Verify well is shut-in and monitor pressures
4. Notify supervisory personnel
5. Record data (SIDP, SICP, Pit Gain, and Time)
6. Hold Pre-job safety meeting and discuss kill procedure

Shutting in prior to pulling BHA through stack

Prior to pulling last joint of drill pipe thru the stack space out and check flow
If flowing see steps below.

1. Sound alarm signaling well control event to Rig Crew
2. Shut in upper pipe ram and open HCR against Open Chokes and Valves Open
to working pressure gauge
3. Install open, full open safety valve and close valve, Close Chokes
4. Verify well is shut-in and flow has stopped
5. Notify supervisory personnel
6. Record data (SIDP, SICP, Pit Gain, and Time)
7. Hold pre-job safety meeting and discuss kill procedure

Shutting in while BHA is in the stack and ram preventer and combo immediately available

1. Sound alarm signaling well control event to Rig Crew
2. Space out BHA with upset just beneath the compatible pipe ram
3. Shut in upper compatible pipe ram and open HCR against Open Chokes and Valves Open to working pressure gauge
4. Install open, full open safety valve and close valve, Close Chokes
5. Verify well is shut-in and flow has stopped
6. Notify supervisory personnel
7. Record data (SIDP, SICP, Pit Gain, and Time)
8. Hold pre-job safety meeting and discuss kill procedure

*FOSV will be on rig floor in open position with operating handle for each type of connection utilized and tested to 10,000 psi

Shutting in while BHA is in the stack and no ram preventer or combo immediately available

1. Sound alarm signaling well control event to Rig Crew
2. If possible pick up high enough, to pull string clear and follow "Open Hole" scenario

If not possible to pick up high enough:

3. Stab Crossover, make up one joint/stand of drill pipe, and install open, full open safety valve (Leave Open)
4. Space out drill string with upset just beneath the compatible pipe ram.
5. Shut in upper compatible pipe ram and open HCR against Open Chokes and Valves Open to working pressure gauge
6. Close FOSV, Close Chokes, Verify well is shut-in and flow has stopped
7. Notify supervisory personnel
8. Record data (SIDP, SICP, Pit Gain, and Time)
9. Hold pre-job safety meeting and discuss kill procedure

Pressure Control Plan

Pressure Control Equipment

- Following setting of 13-3/8" Surface Casing Ameredev will install 13-5/8 MB4 Multi Bowl Casing Head by welding on a 13-5/8 SOW x 13-5/8" 5M in combination with 13-5/8 5M x 13-5/8 10M B-Sec to Land Intm #1 and a 13-5/8 10M x 13-5/8 10M shouldered to land C-Sec to Land Intm #2 (Installation procedure witnessed and verified by a manufacturer's representative).
- Casing will be tested to 1500 psi or .22 psi/ft whichever is greater for 30 minutes with <10% leak off, but will not exceed 70% of the burst rating per Onshore Order No. 2.
- Ameredev will install a 5M System Blowout Preventer (BOPE) with a 5M Annular Preventer and related equipment (BOPE). Full testing will be performed utilizing a full isolation test plug and limited to 5,000 psi MOP of MB4 Multi Bowl Casing Head. Pressure will be held for 10 min or until provisions of test are met on all valves and rams. The 5M Annular Preventer will be tested to 50% of approved working pressure (2,500 psi). Casing will be tested to 1500 psi or .22 psi/ft whichever is greater for 30 minutes with <10% leak off, but will not exceed 70% of the burst rating per Onshore Order No. 2.
- Setting of 9-5/8" Intermediate will be done by landing a wellhead hanger in the 13-5/8" 5M Bowl, Cementing and setting Well Head Packing seals and testing same. (Installation procedure witnessed and verified by a manufacturer's representative) Casing will be tested to 1500 psi or .22 psi/ft whichever is greater for 30 minutes with <10% leak off, but will not exceed 70% of the burst rating per Onshore Order No. 2.
- Full testing will be performed utilizing a full isolation test plug to 10,000 psi MOP of MB4 Multi Bowl B-Section. Pressure will be held for 10 min or until provisions of test are met on all valves and rams. The 5M Annular Preventer will be tested to 100% of approved working pressure (5,000 psi).
- Before drilling >20ft of new formation under the 9-5/8" Casing Shoe a pressure integrity test of the Casing Shoe will be performed to minimum of the MWE anticipated to control formation pressure to the next casing depth.
- Following setting of 5-1/2" Production Casing and adequate WOC time Ameredev will break 10M System Blowout Preventer (BOP) from 10M DOL-2 Casing Head, install annulus casing slips and test same (Installation procedure witnessed and verified by a manufacturer's representative) and install 11" 10M x 5-1/8" 15M Tubing Head (Installation procedure witnessed and verified by a manufacturer's representative). Ameredev will test head to 70% casing design and install Dry Hole cap with needle valve and pressure gauge to monitor well awaiting completion.

Pressure Control Plan

- Slow pump speeds will be taken daily by each crew and recorded on Daily Drilling Report after mudding up.
- A choke manifold and accumulator with floor and remote operating stations will be functional and in place after installation of BOPE, as well as full functioning mud gas separator.
- Weekly BOPE pit level drills will be conducted by each crew and recorded on Daily Drilling Report.
- BOP will be fully operated when out of hole and will be documented on the daily drilling log.
- All B.O.P.s and associated equipment will be tested in accordance with Onshore Order #2
- All B.O.P. testing will be done by an independent service company.
- The B.O.P. will be tested within 21 days of the original test if drilling takes more time than planned.
- Ameredev requests a variance to connect the B.O.P. choke outlet to the choke manifold using a co-flex hose with a 10,000 psi working pressure that has been tested to 15,000psi and is built to API Spec 16C. Once the flex line is installed it will be tied down with safety clamps. (certifications will be sent to Carlsbad BLM Office prior to install)
- Ameredev requests a variance to install a 5M Annular Preventer on the 10M System to drill the Production Hole below the 9-5/8" Intermediate Section. 5M Annular will be tested to 100% working pressure (5,000 psi). A full well control procedure will be included to isolate well bore.

QUALITY CONTROL	No.: QC-DB- 651 / 2013
	Page : 1 / 44
Hose No.: 66551, 66552, 66553, 66554	Revision : 0
	Date: 14. November 2013.
	Prepared by : <i>Szabolcs Linder</i>
	Appr. by: <i>Szabolcs Linder</i>

CHOKER AND KILL HOSES

id.: 3" 69 MPa x 35 ft (10,67 m)

DATA BOOK

Purchaser: H&P STOCK

Purchaser Order No.:


ContiTech Rubber Order No.: 537587

ContiTech Oil & Marine Corp. Order No.:
4500370505

NOT DESIGNED FOR WELL TESTING

CONTENT

		<u>Page</u>
1.	API QMS Certificate (No.: 0760)	3.
2.	American Petroleum Institute Certificate of Authority To Use the Official API Monogram (No.: 16C-0004)	4.
3.	Quality Control Inspection and Test Certificates (No.: 1905, 1906, 1907, 1908)	5-8.
4.	Hose Data Sheet	9.
5.	Metal Parts	
5.1.	Raw Material Quality Certificates (No.: TR070687, EUR-265844, 86989/13-0)	10-13.
5.2.	Hardness Test Reports (No.: 561/13, 562/13)	14-15.
5.3.	Ultrasonic Test Reports (No.: 513/13, 514/13, 515/13)	16-18.
5.4.	NDT Examiner Certificate (Name: Tóth Ákos József)	19-20.
5.5.	Welding Procedure Specification (No.: 140-71)	21-24.
5.6.	Welding Procedure Qualification Record (No.: BUD 0700002/1)	25-26.
5.7.	Welder's Approval Test Certificate (No.: RK1825997.R1)	27-28.
5.8.	Welding Log Sheet (No.: 2013/2898)	29.
5.9.	Visual Examination Record (No.: 813/13)	30.
5.10.	NDT Examiner Certificate (Name: Kis Gábor Balázs)	31-32.
5.11.	Radiographic Test Certificates (No.: 2431/13, 2430/13)	33-34.
5.12.	NDT Examiner Certificate (Name: Ménesi István)	35-36.
5.13.	MP Examination Record (No.: 1222/13)	37.
5.14.	NDT Examiner Certificate (Name: Oravec Gábor)	38-39.
6.	Steel Cord	
6.1.	Inspection Certificate (No.: 4046181212)	40.
7.	Outside Stripwound Tube	
7.1.	Inspection Certificate (No.: 63892/2012)	41.
8.	Certificate of Calibration (Manometer Serial No.: 1518086)	42-44.



ContiTech Rubber
Industrial Kft.
Quality Control Dept.
(1)



Certificate of Registration

APIQR REGISTRATION NUMBER

0760

This certifies that the quality management system of

CONTITECH RUBBER INDUSTRIAL LTD.
Budapesti ut 10
Szeged
Hungary

has been assessed by the American Petroleum Institute Quality Registrar (APIQR®) and found it to be in conformance with the following standard:

ISO 9001:2008

The scope of this registration and the approved quality management system applies to the
Design and Manufacture of High Pressure Hoses

APIQR® approves the organization's justification for excluding:
No Exclusions Identified as Applicable

Effective Date: October 15, 2013
Expiration Date: October 15, 2016
Registered Since: October 15, 2007

W. Don Whittaker
Manager of Operations, APIQR

Accredited by Member of
the International
Accreditation Forum
Multilateral Recognition
Arrangement for Quality
Management Systems



This certificate is valid for the period specified herein. The registered organization must continually meet all requirements of APIQR's Registration Program and the requirements of the Registration Agreement. Registration is established and regularly monitored through annual full system audits. Further clarifications regarding the scope of this certificate and the applicability of ISO 9001 standard requirements may be obtained by consulting the registered organization. This certificate has been issued from APIQR offices located at 1120 I Street, N.W., Washington, D.C. 20005-4031, U.S.A. It is the property of APIQR, and must be returned upon request. To verify the authenticity of this certificate, go to www.api.org/computerlink.





**American
Petroleum
Institute**



2011 123

Certificate of Authority to use the Official API Monogram

License Number: **16C-0084**

ORIGINAL

The American Petroleum Institute hereby grants to

**CONTITECH RUBBER INDUSTRIAL LTD.
Budapesti ut 10
Szeged
Hungary**

the right to use the Official API Monogram® on manufactured products under the conditions in the official publications of the American Petroleum Institute entitled API Spec Q1® and **API Spec 16C** and in accordance with the provisions of the License Agreement.

In all cases where the Official API Monogram is applied, the API Monogram should be used in conjunction with this certificate number: **16C-0084**

The American Petroleum Institute reserves the right to revoke this authorization to use the Official API Monogram for any reason satisfactory to the Board of Directors of the American Petroleum Institute.

The scope of this license includes the following product: **Flexible Choke and Kill Lines**

QMS Exclusions: **No Exclusions Identified as Applicable**

American Petroleum Institute

Director of Global Industry Services

Effective Date: OCTOBER 15, 2013

Expiration Date: OCTOBER 15, 2016



To verify the authenticity of this license, go to www.api.org/compositelist.

CONTITECH RUBBER
Industrial Kft.

No: OC-DB- 651 /2013
Page: 4 / 44

QUALITY CONTROL INSPECTION AND TEST CERTIFICATE				CERT. N°: 1905			
PURCHASER: ContiTech Oil & Marine Corp.			P.O. N°: 4500370505				
CONTITECH RUBBER order N°: 537587		HOSE TYPE: 3" ID		Choke and Kill Hose			
HOSE SERIAL N°: 66551		NOMINAL / ACTUAL LENGTH: 10,67 m / 10,75 m					
W.P. 68,9 MPa 10000 psi		T.P. 103,4 MPa 15000 psi		Duration: 60 min.			
<p>Pressure test with water at ambient temperature</p> <p style="text-align: center;">See attachment. (1 page)</p> <p>↑ 10 mm = 10 Min. → 10 mm = 25 MPa</p>							
COUPLINGS Type		Serial N°		Quality		Heat N°	
3" coupling with		8084 8083		AISI 4130		24613	
4 1/16" 10K API Flange end				AISI 4130		034939	
NOT DESIGNED FOR WELL TESTING				API Spec 16 C			
				Temperature rate:"B"			
All metal parts are flawless							
WE CERTIFY THAT THE ABOVE HOSE HAS BEEN MANUFACTURED IN ACCORDANCE WITH THE TERMS OF THE ORDER INSPECTED AND PRESSURE TESTED AS ABOVE WITH SATISFACTORY RESULT.							
STATEMENT OF CONFORMITY: We hereby certify that the above items/equipment supplied by us are in conformity with the terms, conditions and specifications of the above Purchaser Order and that these items/equipment were fabricated inspected and tested in accordance with the referenced standards, codes and specifications and meet the relevant acceptance criteria and design requirements.							
COUNTRY OF ORIGIN HUNGARY/EU							
Date:		Inspector		Quality Control			
13. November 2013.				ContiTech Rubber Industrial Kft. Quality Control Dept. 			

QUALITY CONTROL INSPECTION AND TEST CERTIFICATE		CERT. N°:	1906
PURCHASER: ContiTech Oil & Marine Corp.		P.O. N°:	4500370505
CONTITECH RUBBER order N°: 537587	HOSE TYPE: 3" ID	Choke and Kill Hose	
HOSE SERIAL N°: 66552	NOMINAL / ACTUAL LENGTH: 10,67 m / 10,73 m		
W.P. 68,9 MPa 10000 psi	T.P. 103,4 MPa 15000 psi	Duration:	60 min.
Pressure test with water at ambient temperature			
See attachment. (1 page)			
↑ 10 mm = 10 Min. → 10 mm = 25 MPa			
COUPLINGS Type	Serial N°	Quality	Heat N°
3" coupling with	8088 8085	AISI 4130	24613
4 1/16" 10K API Flange end		AISI 4130	034939
NOT DESIGNED FOR WELL TESTING		API Spec 16 C	
Temperature rate:"B"			
All metal parts are flawless			
WE CERTIFY THAT THE ABOVE HOSE HAS BEEN MANUFACTURED IN ACCORDANCE WITH THE TERMS OF THE ORDER INSPECTED AND PRESSURE TESTED AS ABOVE WITH SATISFACTORY RESULT.			
STATEMENT OF CONFORMITY: We hereby certify that the above items/equipment supplied by us are in conformity with the terms, conditions and specifications of the above Purchaser Order and that these items/equipment were fabricated inspected and tested in accordance with the referenced standards, codes and specifications and meet the relevant acceptance criteria and design requirements.			
COUNTRY OF ORIGIN HUNGARY/EU			
Date:	Inspector	Quality Control	
13. November 2013.		ContiTech Rubber Industrial Kft. Quality Control Dept. <i>János Gy...</i>	

QUALITY CONTROL INSPECTION AND TEST CERTIFICATE				CERT. N°: 1907			
PURCHASER: ContiTech Oil & Marine Corp.			P.O. N°: 4500370505				
CONTITECH RUBBER order N°: 537587		HOSE TYPE: 3" ID		Choke and Kill Hose			
HOSE SERIAL N°: 66553		NOMINAL / ACTUAL LENGTH: 10,67 m / 10,745 m					
W.P. 68,9 MPa 10000 psi		T.P. 103,4 MPa 15000 psi		Duration: 60 min.			
<p>Pressure test with water at ambient temperature</p> <p style="text-align: center;">See attachment. (1 page)</p> <p>↑ 10 mm = 10 Min. → 10 mm = 25 MPa</p>							
COUPLINGS Type		Serial N°		Quality		Heat N°	
3" coupling with		8089 8087		AISI 4130		23171 24613	
4 1/16" 10K API Flange end				AISI 4130		034939	
NOT DESIGNED FOR WELL TESTING				API Spec 16 C			
				Temperature rate:"B"			
All metal parts are flawless							
WE CERTIFY THAT THE ABOVE HOSE HAS BEEN MANUFACTURED IN ACCORDANCE WITH THE TERMS OF THE ORDER INSPECTED AND PRESSURE TESTED AS ABOVE WITH SATISFACTORY RESULT.							
STATEMENT OF CONFORMITY: We hereby certify that the above items/equipment supplied by us are in conformity with the terms, conditions and specifications of the above Purchaser Order and that these items/equipment were fabricated inspected and tested in accordance with the referenced standards, codes and specifications and meet the relevant acceptance criteria and design requirements.							
COUNTRY OF ORIGIN HUNGARY/EU							
Date: 13. November 2013.		Inspector		Quality Control <div style="text-align: center;">   ContiTech Rubber Industrial Kft. Quality Control Dept. </div>			

QUALITY CONTROL INSPECTION AND TEST CERTIFICATE		CERT. N°:	1908
PURCHASER: ContiTech Oil & Marine Corp.		P.O. N°:	4500370505
CONTITECH RUBBER order N°: 537587	HOSE TYPE: 3" ID	Choke and Kill Hose	
HOSE SERIAL N°: 66554	NOMINAL / ACTUAL LENGTH: 10,67 m / 10,71 m		
W.P. 68,9 MPa 10000 psi	T.P. 103,4 MPa 15000 psi	Duration:	60 min.
Pressure test with water at ambient temperature <p style="text-align: center;">See attachment. (1 page)</p>			
↑ 10 mm = 10 Min. → 10 mm = 25 MPa			
COUPLINGS Type	Serial N°	Quality	Heat N°
3" coupling with 4 1/16" 10K API Flange end	8090	AISI 4130	23171 24613
	8086	AISI 4130	034939
NOT DESIGNED FOR WELL TESTING		API Spec 16 C	
Temperature rate:"B"			
All metal parts are flawless			
WE CERTIFY THAT THE ABOVE HOSE HAS BEEN MANUFACTURED IN ACCORDANCE WITH THE TERMS OF THE ORDER INSPECTED AND PRESSURE TESTED AS ABOVE WITH SATISFACTORY RESULT.			
STATEMENT OF CONFORMITY: We hereby certify that the above items/equipment supplied by us are in conformity with the terms, conditions and specifications of the above Purchaser Order and that these items/equipment were fabricated inspected and tested in accordance with the referenced standards, codes and specifications and meet the relevant acceptance criteria and design requirements.			
COUNTRY OF ORIGIN HUNGARY/EU			
Date:	Inspector	Quality Control	
13. November 2013.		ContiTech Rubber Industrial Kft. Quality Control Dept. 	



Hose Data Sheet

CRI Order No.	537587
Customer	ContiTech Oil & Marine Corp.
Customer Order No	4500370505
Item No.	1
Hose Type	Flexible Hose
Standard	API SPEC 16 C
Inside dia in inches	3
Length	35 ft
Type of coupling one end	FLANGE 4.1/16" 10KPSI API SPEC 6A TYPE 6BX FLANGE C/W BX155STANDARD RING GROOVE
Type of coupling other end	FLANGE 4.1/16" 10KPSI API SPEC 6A TYPE 6BX FLANGE C/W BX155 STANDARD RING GROOVE
H2S service NACE MR0175	Yes
Working Pressure	10 000 psi
Design Pressure	10 000 psi
Test Pressure	15 000 psi
Safety Factor	2,25
Marking	USUAL PHOENIX
Cover	NOT FIRE RESISTANT
Outside protection	St. steel outer wrap
Internal stripwound tube	No
Lining	OIL RESISTANT
Safety clamp	No
Lifting collar	No
Element C	No
Safety chain	No
Safety wire rope	No
Max. design temperature [°C]	100
Min. design temperature [°C]	-20
Min. Bend Radius operating [m]	0,90
Min. Bend Radius storage [m]	0,90
Electrical continuity	The Hose is electrically continuous
Type of packing	WOODEN CRATE ISPM-15

Body

Customer: ContiTech Rubber Industrial Kft
 Order Number: 32258500
 Part Number: 4205160045
 Our Ref: SO84201
 Date: 11th February 2013
 Certificate Number: TR070687 (Rev. 18/06/2013)
 Approved Signatories:
 R M Greaves A Cocking J Jarvis A Pears S Selman

8083-8088



2451-2466

42 0516 0045

Description	CERTIFICATE OF CONFORMITY	Heat Treatment
AISI4130 BLACK ROLLED BAR, HEAT TREATED & TESTED TO 197-238 BHN, 655MPA MIN TENSILE, 517MPA MIN YIELD, 18% MIN ELONGATION, CHARTY IMPACT TESTING 27J MIN @ -30C (OR COLDER) LATERAL EXPANSION 0.38 MIN. ROLLING REDUCTION 3:1 MIN, NI 1% MAX & CE 0.82 MAX. TESTS MAY BE TAKEN FROM A 4" SQR QTC AS PER API 8A/PSL 3 QTC SIZE. MECHANICAL TEST SPECIMEN TO ASTM A370 NACE MR0175/ISO15168 APPLIES APPROX 20 TONNES 210 MM DIA CERTS TO EN10204 3.1	HARDENED FROM 880°C FOR 5:30 HOURS (WATER QUENCH) TEMPERED AT 670°C FOR 10 HOURS (AIR COOL) WATER TEMPERATURE BEFORE QUENCH, 28°C, AFTER, 35°C. TEMP. MEASUREMENT, FURNACE ATMOSPHERE THERMOCOUPLE COMPONENT HARDNESS E10 - 211 HBW10/3000 TEST COUPON - 4" SQ X 8" LONG, TESTED AT 1/4 T LOCATION REDUCTION RATIO - 6.2 REDUCTION RATIO & HT APPLY TO BOTH JOB & TEST PIECE FURNACE CALIBRATION: API8A 20th ed, annex M C/E = 0.693	

CAST 24613

C	Si	Mn	S	P	Ni	Cr	Mo	Al	Cu	Sn	Nb
0.3200	0.2590	0.5680	0.0090	0.0100	0.1660	1.0560	0.2350	0.0200	0.1420	0.0070	0.0010
V	Ta	Ti	Nb+Ta	Co	N	B	W	Ce	Fe	As	Sb
0.0010		0.0010			0.0079	0.0001					
Pb	Ca	H (ppm)	CEV								
		1.20	0.69								

TEST SPECIFICATION 517 N/mm2 MIN YIELD

Temperature	Re	Rp 0.2	Rm	A %	Z %	Impact	Temp.	Hardness
RT		517.000						
	N/mm2	N/mm2	N/mm2	%	%			

TEST RESULTS

Test Number	Dir./Temp.	Re	Rp	Rm	A %	Z %	Joules	Charpy Direction
ST22561N	20.0°C		524.000	698.000	27.80	87.70	KCV -48°C 80 50 78	LONG
Specimen Ø 12.500mm							KCV -60°C 50 50 46	LONG
							% Shear Surface	
							62.0% 52.0% 80.0%	
							Lateral Expansion (mm)	
							0.840 0.740 1.020	LONG

For and on Behalf of TM Steels Ltd.

A Cocking

ContiTech Rubber Industrial Kft. CERTIFICATE ACCEPTABLE
 OC INSPECTOR
 DATE: 18.06.21.

TM Steels Ltd
 Foxwood Way
 Foxwood Road
 Chesterton
 S41 9RA

Steel for the Oil and Engineering Industries
 Machining and Boring Facilities

Tel +44 (0)1248 268312
 Sales Fax +44 (0)1248 268313
 Production Fax +44 (0)1248 268841
 email sales@tmsteels.co.uk
 Co Reg No: 3523526 Vat No: GB 706 2614 57



Carbrook Street
Sheffield S9 2JN
Telephone: +44 114 244 6711
Facsimile: +44 114 244 7469




Cert No. 55293

Results quoted only refer to the items tested.

Body
8089-8090

Test Certificate

To:	CONTITECH RUBBER INDUSTRIAL KFT H-8728, SZEGED, BUDAPESTI UT 10, K.1562-K.1575 HUNGARY	Customer Order Number	32252183 - 01	Test Number	402483
	420516 0045	Customer Order Date	27Feb12	Part Number	4205160045
		Sales Order Number	EUR-352087-1	Cast Number	23171
		Report Date	25Sep12	Cert Number	EUR-265844
		Quantity	14 Pcs 17402 Kgs 210 mm Dia		
Description AISI 4130 76KSI .2% PS API QTC				Steel Type	ALLOY 4130

Material Specification	AISI4130		Test Spec	517N/MM2MIN.YLD		Test Spec				
Heat Treatment Spec	197-237BHN		Production Method	FORGED						
Melt Practice	EFVD		Charge Ref.							
Heat Treatment	Temp(°C)	Soak	Coolant	Init	Max(°C)	Batch	Temp recorded using			
HARDEN	860	3 HRS	WATER QUENCH	20	30	0912091308	CONTACT THERMOCOUPLE			
TEMPER	650	4 HRS	TABLE COOL			1012091319	Nature of T/P Separate			
							Qto size 4Inch SQ X 6Inch LONG			
							Req. Min/Max			
							Achieved			
							Hardness on T/P			
							197 237 HBW 228 229 HBW			
							Hardness on Material			
							197 237 HBW 218 235 HBW			
Tensile -				Impacts -						
Location	Direction	Rp 0.20%	Rm	A%	Z%	Location	Direction	CVN	Lat. Exp. (mm)	% Shear
1/4T	LONGITUDINAL	517 Min	655 to 800	18 Min (4d)	0 Min	1/4T	LONGITUDINAL	27 Min Ave	0.380 Min	0
Results (N/mm2)		580	785	25 (50.0mm)	64.0 (12.56mm)	Results (Joules)	-30 Centigrade	106 104 102	1.44 1.42 1.4	40 40 40
Results						Results				
Corrosion		Pitting Resistance		Fertile		Microstructure				
Carbon Equivalent		.871		Grain Size		Min 6 Max 6				
C	Si	Mn	P	S	Cr	Mo	Ni	Cu		
0.2940	0.2820	0.5370	0.0110	0.0050	1.0620	0.2290	0.1860	0.2430		
Certs to BSEN10204.2004 3.1 NACE MR-01-75 FE = BAL REDUCTION RATIO 6.5:1						 QC INSPECTOR DATE: 12.12.04		All furnace Calibration conforms to API6A 20th Edition ANNEX M. Hardness load/penetration depth - HBW 10 diameter (mm)/3000 kgf test force per ASTM E10.		
Names of Approved Signatories : S.Maxted G.Smith S.Suter P.Rogers M.Brown This report is not to be reproduced without written approval.						Third party inspection :		Signature 		

CONTITECH RUBBER
 Industrial Kft.
 No:QC-DB-651/2013
 Page: 11 / 44

HAMOR zrt.

Flange

FORGING, MACHINING, HEAT-TREATING

8083-8090 3386
4205140284

ÉMI-TÜV
ISO9001

H-3531 Miskolc, Kiss Ernő u. 17. Phone: 36/46/401-033 Fax: 36/46/379-199

INSPECTION CERTIFICATE

ACCEPTANCE ACCORDING EN 10204-05/3.1 | Certificate No.: **86989/13-0**

Date of issue: 2013.03.27 | Hámor No.: 98-39B5263 | Order No.: 32259784/13/2

Customer: Contitech Rubber Industrial Kft.
6728 Szeged Budapesti út 10

Quality: AISI 4130/CONTI Spec.No.: API 6A PSL3 325/151 x 182
Dimension: MSO-100597-002/A/H mm
Final dim.:MSO-100597-002/A(4 1/16") Heat-treatment:Quenched & tempered

Quantity: 30 pcs | Weight: 73.0 kg/pc | Total weight: 2190.00 kg

nomination of product: Forged,machined disc

Chemical analysis %

Heat No.: **034939**

Steelmaker: CELSA Hutaostrowiec POLA

Test No.	Spec. value Min. Max.	C	MN	SI	P	S	CR	MO	V	Ce
		0.45	1.80	1.00	0.025	0.025	2.75	1.500	0.300	0.82
	Result	0.28	0.56	0.20	0.006	0.003	0.99	0.170	0.003	0.62

Mechanical properties:

Test No.	Spec. value Min. Max.	HB	Rp0.2 MPa	Rm MPa	A5 %	KV-J -30°C
		197 238	517	655	18	27
L13314	Result	235 238	525	662	19.50	35 52 82

Contitech Rubber
Industrial Kft.
CERTIFICATE
ACCEPTABLE
QC INSPECTOR
DATE: 1.03.29

Test bar from product.
Dimensional and visual control: passed
Ultrasonic test acc. to SEP 1921-84 spec. is satisfactory C/c
Steel making (melting) process: UHP-ASEA vacuum-treated.
NACE MR 0175/ISO 15156+API 17K + API 6A PSL3.
HB-E10, Mechanika: ASTM A370 acc.
Grade Of forging: 9.81 30 pc/series.

Executive

Hámor zrt.
minőség ellenőrzé-
Osztály

Expért

MU-4-10/1/86
HÁMOR zrt.
FIALKA ÉRKEZ




MISKOLC Kiss Ernő u. 17. sz. H-3531 tel:36/46/401-033 fax:36/46/379-199 e-mail: hamor@t-online.hu

PROTOCOL NUMMER: 98-39B5263

HEAT-TREATMENT PROTOCOL		
BUYER: CONTITECH RUBBER INDUSTRIAL Kft. Szeged Budapesti út 10. sz.	Order No. of Buyer: 32259784/13/2	
	Work No. of Buyer:	
PRODUCT: forged	QUANTITY: PIECE 30	No. of drawing: MSO-100597-002/A/H
MATERIAL QUALITY: AISI 4130 CONTI API 6A PSL3	Charge No.: 34939	Test No.:
<u>HEAT-TREATMENT:</u> quenching and tempering		
Typ of furnace: electric furnace Hardening medium: water		

PROCESS OF HEAT-TREATMENT



Miskolc, Hámor ZRt. 2013-03-26.


Kandó'
head of heat-treatment

Hámor ZRt.
minőség ellenőrzés
osztály

Felado : 61344

gamma kontroll kft

19/10/13 12:54 Lap: 2



HARDNESS TEST REPORT

Report No: 561/13.

CLIENT: JE-ZO KFT. SZEGED, KÜLTERÜLET, 01408/22.
TEST EQUIPMENT: TH 160-D Hardness tester
PROCEDURE: QCP-45-R1
DESCRIPTION OF COUPLING: coupling(s) after PWHT
DRAWING NUMBER: MT-3121-3000
SERIAL NUMBER: 8083; 8084; 8085; 8086

BRINELL HARDNESS REQUIREMENT	SERIAL NO OF COUPLING	PART OF THE COUPLING	ACTUAL HARDNESS RESULT (HB)
Min HB 197 Max HB 238	✓ 8083	body	224
		weld	222
		flange	236
		connection face	238
	✓ 8084	body	213
		weld	208
		flange	220
		connection face	238
	✓ 8085	body	214
		weld	214
		flange	219
		connection face	222
	✓ 8086	body	232
		weld	237
		flange	238
		connection face	197

The coupling(s) conform to API Spec 6A requirements.

DATE:
2013. október 30.

PREPARED:

Ménési István

APPROVED:
GAMMA-CONTROL KFT.
6750 Algyő, Kálterület 0189/14. hrsz.
Add: +36 028 47 420
www.gamma-control.hu

Felado : 61344

gamma controll kft

19/10/13 12:54 Lap: 3



**HARDNESS TEST
REPORT**

Report No: 562/13.

CLIENT: JE-ZO KFT. SZEGED, KÜLTERÜLET, 01408/22.

TEST EQUIPMENT: TH 160-D Hardness tester

PROCEDURE: QCP-45-R1

DESCRIPTION OF COUPLING: coupling(s) after PWHT

DRAWING NUMBER: MT-3121-3000

SERIAL NUMBER: 8087; 8088; 8089; 8090

BRINELL HARDNESS REQUIREMENT	SERIAL NO OF COUPLING	PART OF THE COUPLING	ACTUAL HARDNESS RESULT (HB)
Min HB 197 Max HB 238	✓ 8087	body	213
		weld	216
		flange	220
		connection face	225
	✓ 8088	body	229
		weld	212
		flange	223
		connection face	213
	✓ 8089	body	219
		weld	229
		flange	231
		connection face	238
	✓ 8090	body	207
		weld	210
		flange	226
		connection face	234

The coupling(s) conform to API Spec 6A requirements.


DATE:
2013. október 30.

PREPARED:


.....
Ménési István

APPROVED: GAMMA-CONTROL KFT.
6750 Algyő, Kőhertület 0148/14. hrsz.
Adószám: 11094014-0-06
www.gamma-control.hu
Varga Mihály

 <p>GAMMA-CONTROLL www.gamma-controll.hu 6750 Algyő, költőutca 01804/14. hrsz. Tel./Fax.: +36 62/617-400 / 61344 ANKT által NKI-1-114/2018 sz.útván előírt vizsgálati laboratóriumnak</p>	<p>ULTRAHANG VIZSGÁLATI JEGYZŐKÖNYV</p> <p>ULTRASONIC EXAMINATION REPORT</p>	<p>Vizsgálati szám: Report No.:</p> <p style="text-align: center;">513/13</p>


Vizsgálat tárgya / Object of test		Coupling (Body)	
Gyártó Manufacturer	Megrendelő Customer	JE-ZO Kft. Szeged	
Gyáriszám Serial-No.	Rendelési szám Order-No.	---	
Azonosító jel Identification	Követelmény Requirement	8083-8088 ASTM A388	
Geometriai kialakítás / Rajzszám Geometric configuration / Drawing-No.	Vizsgálati hőkezelés Test heat treatment	MT-3121-3000 ø200xø70x491 előtt prior	
Anyagminőség Material	Letapogatási irányok Direction of scanning	AISI 4130 / axiális és radiális	
Adagszám Heat-No.	Vizsgálati terület állapota Surface condition	24813 / forgácsolt machined	
Vizsgálati darabszám Testing pieces	Vizsgálati terjedelem Exted of Test	6 db 100%	
Vizsgálati adatok / Examination data			
Készülék típusa Type of US-equipment	Készülék gyári száma Serial-No. Of US-equipment	USM25 7875f	
Vizsgálófej(ek) Searc unit(s)	Frekvencia(k) Frequency(ies)	SEB-2, SEB4H 2 MHz 4 MHz MHz MHz	
Kalibrációs blokk Calibration standard identification	Erősítés(ek) Gain	ET1,ET2 axiálisan 18 dB dB dB radiálisan 6 dB	
Csatoló közeg Couplant	Hanggyengülés Attenuation	olaj oil dB/m	
Értékelés / észlelt kijelzések / Evaluation / recordable indications			
Értékelés Evaluation	X	megfelelő satisfactory	nem megfelelő / not acceptable
Megjegyzés(ek) Remark(s)			
Hely / kelt Place / date	 Vizsgálatot végezte Tested by Tóth Ákos UT20103090307		GAMMA CONTROLL KFT. 6750 Algyő, költőutca 01804/14. hrsz. Adószám: 11094614-2-06..... www.gamma-controll.hu Tel.: 06-30-218-2640 Approved by Benkő Péter - Felelős vezetőh.

 <p>www.gamma-controll.hu 6750 Algyó, külterület 01894/14. hrsz. Tel./Fax.: +36 82/517-400 / 81344 A NAT által NAT-1-1140/2010 sz.úttal előírtak szerinti vizsgálóhelyzetben</p>	<p>ULTRAHANG VIZSGÁLATI JEGYZŐKÖNYV</p> <p>ULTRASONIC EXAMINATION REPORT</p>	<p>Vizsgáló szám: Report No.:</p> <p style="text-align: center;">514/13</p>

Vizsgálat tárgya / Object of test		Coupling (Body)	
Gyártó Manufacturer		Megrendelő Customer	JE-ZO Kft. Szeged
Gyárísza Serial-No.		Rendelési szám Order-No.	---
Azonosító jel Identification	8089-8090	Követelmény Requirement	ASTM A388
Geometria kialakítás / Rajzszám Geometric configuration / Drawing-No.	MT-3121-3000 ø200xø70x491	Vizsgáló hőkezelés Test heat treatment	előtt prior
Anyagminőség Material	AISI 4130 /	Letapogatási irányok Direction of scanning	axiális és radiális
Adagszám Heat-No.	23171 /	Vizsgáló terjedeleme Exted of Test	100%
Vizsgáló felület állapota Surface condition	forgácsolt machined	Vizsgáló darabszám Testing pieces	2 db
Vizsgáló adatok / Examination data			
Készülék típusa Type of US-equipment	USM25	Készülék gyári száma Serial-No. Of US-equipment	7875f
Vizsgálófeje(ek) Searc unit(s)	SEB-2, SEB4H	Frekvencia(k) Frequency(ies)	2 MHz 4 MHz MHz MHz
Kalibrációs blokk Calibration standard identification	ET1,ET2	Erősítés(ek) Gain	axiálisan 18 dB dB dB radiálisan 6 dB
Csatoló közeg Couplant	olaj oil	Hanggyengülés Attenuation	dB/m
Értékelés / észlelt kijelzések / Evaluation / recordable indications			
Értékelés Evaluation	X	megfelelő satisfactory	nem megfelelő / not acceptable
Megjegyzés(ek) Remark(s)			
Hely / kelt Place / date	Gamma-Controll Kft. Algyó, 2013.10.17	 Vizsgáló végzte Tested by Tóth Ákos UT20103090307	GAMMA - CONTROLL KFT. 6750 Algyó, külterület 01894/14. hrsz. Adószám: 2094614-2-06 www.gamma-controll.hu Tel.: 06 82 517 400-2640 Approved by Bankó Péter - Felelős vezető.

Ez a jegyzőkönyv részleteiben nem másolható! / Copying details is prohibited!

 GAMMA-CONTROL <small>www.gamma-control.hu 0750 Algyő központi ÜTEB474 kassza Tel./Fax.: +36 02517-400 / 81964 ANKY 624 BK-1-114920-03 szellemi tulajdonú vizsgálatberendezés</small>	ULTRAHANG VIZSGÁLATI JEGYZŐKÖNYV ULTRASONIC EXAMINATION REPORT	Vizsgálati szám: Report No.: 516/13
--	---	--

Vizsgálat tárgya / Object of test		Flange	
Gyártó Manufacturer	Megrendelő Customer	JE-ZO Kft. Szeged	
Gyáriszám Serial-No.	Rendelési szám Order-No.	---	
Azonosító jel Identification	Követelmény Requirement	8093-8090 ASTM A388	
Geometria leírása / Rajzsám Geometric configuration / Drawing-No.	Vizsgáló hőkezelés Test heat treatment	e315x85x190x94x70 előtér prior	
Anyagminőség Material	Letapogatási irányok Direction of scanning	AISI 4130 / axiális és radiális	
Adagszám Heat-No.	Vizsgálati terjedelem Extent of Test	034939 / 100%	
Vizsgálati felület állapota Surface condition	Vizsgálati darabszám Testing pieces	forgácsolt machined 8 db	
Vizsgálati adatok / Examination data			
Készülék típusa Type of US-equipment	Készülék gyári száma Serial-No. Of US-equipment	USM25 7875f	
Vizsgálófeje(ek) Search unit(s)	Frekvencia(k) Frequency(ies)	SEB-2, SEB4H 2 MHz 4 MHz MHz kHz	
Kalibrációs blokk Calibration standard identification	Erősítés(ek) Gain	ET1,ET2 axiálisan 6 dB 0dB dB radiálisan 6 dB	
Csatoló közege Couplant	Hanggyengülés Attenuation	olaj oil dB/m	
Értékelés / észlelt kijelzések / Evaluation / recordable indications			
Értékelés Evaluation	X	megfelelő satisfactory	nem megfelelő / not acceptable
Megjegyzés(ek) Remark(s)			
Hely / dátum Place / date	 Vizsgálatot végezte Tested by Tóth Ákos UT20103090307		GAMMA-CONTROL KFT. 0750 Algyő központi ÜTEB474 kassza Adószám: 1122614-2-06 www.gamma-control.hu JAVASOLÓ Benkő Péter - Felelős vezető

Ez a jegyzőkönyv részleteiben nem másolható! / Copying details is prohibited!



MAGYAR HEGESZTÉSTECHNIKAI ÉS ANYAGVIZSGÁLATI EGYESÜLÉS
(HUNGARIAN ASSOCIATION OF WELDING TECHNOLOGY AND MATERIAL TESTING)
(Certification Body)

RONCSOLÁSMENTES ANYAGVIZSGÁLÓ TANÚSÍTVÁNY
(Certificate of NDT personnel)

Azonosító szám: **UT20103090307**
(Identification No.)

A tanúsított neve:
(The name and forename of
the certificated individual):
Születési hely/ide:
(Place and date of birth):

Tóth Ákos József
Hódmezővásárhely, 1987. 09.
19.

A tanúsított személy aláírása
(The signature of the certificated individual)

Vizsgálati eljárás(ok):
(The NDT method(s)):

Ultraszagos anyagvizsgálat
(Ultrasonic testing)

Ipari terület:
(Industrial sector):

Készülékek, berendezések, létesítmények vizsgálata EM
(Pre and in-service testing of equipment, plant and structure)

Termék terület(ek):
(Product sector(s)):

(c)+Fv, (w)+Fv, (wp)+Fv, (f)+Fv

A minősítés fokozata:
(The level of certification):

UT2

A tanúsítás és kiadásának időpontja:
(The date of certification and its issue):

Budapest, 2009. 12. 07.

A tanúsítás érvényes:
(The date upon which certification expires):

2014. 12. 06.

Tanúsító Testület nevében
(On behalf of certifying body)

Az ipari és/vagy termék terület érvényesség kiterjesztve:
(The industrial and/or product sector has been expanded to):

9/2001 GM, 97/23 EC

Dátum (Date):

2009. 12. 07.

A tanúsítás érvényessége
(Renewed the validity of the certification until (MSZ EN 473 9.):

-ig megújítva (MSZ EN 473 9.):

Dátum (Date):

Tanúsító Testület nevében
(On behalf of certification body)



A Magyar Hegesztéstechnikai és Anyagvizsgáló Egyesülés, mint a Nemzeti Akkreditáló Testület által a NAT-S-0013/2006 számon akkreditált tanúsító testület az MSZ EN 473 számú szabvány szerint eredményes vizsgája alapján a nevezett személyt tanúsítja a fentiek szerint:
(The Hungarian Association of Welding Technology and Material Testing as an accredited by the National Accreditation Board (under No. NAT-S-0013/2006) certification body, on the basis of his/her successful examination under the standard MSZ EN 473, hereby certifies the named individual according to the above.)

* c - öntvények (castings); f - kovácsolt termékek (forgings); w - hegesztett kötések-termékek (welded products); t - csövek (tubes); wp - alakított termékek (wrought products); p - műanyag termékek (plastics products); k - kompozitok (composites products).

UT20103090307



MAGYAR HEGESZTÉSTECHNIKAI ÉS ANYAGVIZSGÁLATI EGYESÜLÉS
(HUNGARIAN ASSOCIATION OF WELDING TECHNOLOGY AND MATERIAL TESTING)
(Certification Body)

Meghatálazzuk a tanúsítvány tulajdonosát, hogy vizsgálatokat végezzen és azok eredményéért felelősséget vállaljon.
(MSZ EN 473 3.21)

(The holder of this certificate has been authorised to perform tests and take responsibility for the test results. (MSZ EN 473 3.21))

GAMMA - CONTROLL KFT
6722 Szeged, Gyertyános u. 12-16/A

Munkáltató aláírása: *[Handwritten signature]*
(Signature of the employer)
Adószám: 11024514-2-06
Céginformációk: 14738005-20406154
www.gamma-controll.hu
Tel.: 06 30 218-2640


Dátum: 2009.12.07
(Date)

Folyamatos munkavégzés igazolása (MSZ EN 473 9.)
(Evidence of continued work activity (MSZ EN 473 9.))

Sorsz.:	Munkáltató aláírása (Signature of the employer)	GAMMA-CONTROLL (Stamp)	Dátum (Date)
1.	<i>[Handwritten signature]</i>	Műanyagellenőrzés Kft.	2010.01.04.
2.		GAMMA-CONTROLL	2011.01.06.
3.		Műanyagellenőrzés Kft.	2012.01.09.
4.		GAMMA-CONTROLL	2013.01.09.
5.		Műanyagellenőrzés Kft.	
6.			
7.			
8.			
9.			
10.			


Kiegészítések:
(Additional remarks)

* A tanúsítvány a munkáltató aláírásával érvényes
(This certificate is valid with the signature of the employer.)

		TECHNICAL DATA SHEET		TDS	Page
PHOENIX RUBBER INDUSTRIAL LTD.		WELDING PROCEDURE SPECIFICATION		WPS	N° 1 of 2
CLIENT		THIS SPECIFICATION IS BASED ON ASME CODE SECTION IX		WPS N° 140-71 REV 4	
IDENTITY CODE				SUPPORTING PQR N° BUD 0700002/1	
ITEM	Qty	WELDING PROCESS: GTAW-SMAW		PERFORMED BY:	
DATA FOR ACCEPTANCE		TYPES: MANUAL		WELDER'S STAMP	
JOINTS (QW-402)					
JOINT DESIGN			BACKING: YES/NO		
BASE METALS (QW-403)			WELD SEQUENCE		
DRW N°			PART „A”		PART „B”
GRADE:			WNo.:1.7220		
CARBON EQUIVALENT			max. C _e ~		
MECHANICAL PROPERTIES:			ASTM A 322-91: AISI 4130 / 34CrMo4 (MSZ EN 10083-1) *		
TENSILE STRENGTH			N/mm ² min.		
DUCTILITY			% min.		
HARDNESS			HB max.		
IMPACT TEST -30°C			J Average		
THICKNESS:			t = 5-38 mm		
			OUTSIDE DIAMETER : ØD = 60-280 mm		
FILLER METALS (QW-404)					
WELD MATERIAL	DIAMETER	BRAND	STANDARD	SUPPLIER	
Rod	2.4 mm	EML 5	AWS A5.18-01: ER70S-3	Böhler	
Electrode	3.2; 4.0	T-PUT NiMo 100**	AWS A 5.5-96: E 10018-D2 (mod.)	Böhler	
LAPSE BETWEEN OF PASSES MIN./min					
POSITIONS (QW-405)			PREHEAT (QW-406)		
POSITIONS: 1G Rotated (horizontal)			PREHEAT TEMP.: 300-330 °C		
WELDING PROGRESSION: Weld flat at or near to the top			INTERPASS TEMP.: max. 350 °C		
POSITION OF FILLET			PREHEAT MAINTENANCE: Till the beginning of postweld heat treating		
OTHER			METHOD OF PREHEATING: Furnace		





CONTINUATION OF WPS N° 140-71 Rev.4							Page N° 2 of 2		
POSTWELD HEAT TREATMENT (QW-407)					GAS (QW-408)				
HOLDING TEMP. RANG		620 +20 / -0 C°			SHIELDING GAS		Argon for root		
HOLDING TEMP. TIME		4 HR			PERCENTAGE COMPOSITION (MIXTURE)				
HEATING RATE MAX.:					99.995 %				
COOLING RATE MAX.:		80 °C/HR			FLOW RATE		10-12 LITRES/min.		
LOCATION OF THERMOCOUPLE					GAS BACKING: Argon (for 1st and 2nd passes)				
FURNACE ATMOSPHERE		Air			FLOW RATE		7-9 Litres/min		
TYPE:					TRAILING SHIELDING GAS COMP.				
ELECTRICAL CHARACTERISTICS (QW-409)					1st		pass: -		
CURRENT		DC			ELECTRODE POLARITY :		2nd-28th passes: +		
TUNGSTEN ELEKTRODE SIZE/TYPE: Ø3.2 mm thoriated tungsten									
MODE OF TRANSFER FOR GMAW									
ELECTRODE / WIRE FEED SPEED RANGE									
WELD LAYERS	PROCESS	FILLER METAL		CURRENT		VOLT RANGE	HEAT INPUT (KJ/cm)		
		CLASS	DIAMETER	TYPE POLAR.	AMP. RANGE				
1	GTAW	EML 5	2.4 mm	-	110-130	11-12	5-8.4		
2-3	SMAW	T-PUT NiMo 100	3.2 mm	+	120-140	24-26	12-19.6		
4-28	SMAW	T-PUT NiMo 100	4.0 mm	+	150-170	26-30	16.2-27.5		
TRAVEL SPEED RANGE		100-130 mm/min							
TECHNIQUE (QW-410)									
STRING OR WEAVE BEAD					ORIFACE OR GAS CUP SIZE Ø9mm				
INITIAL/INTERPASS CLEANING: Brushing, Grinding									
EQUIPMENTS FOR WELDING:									
OTHER:									
EXAMINATION - Acc. to the acceptance instruction N° MIO-FB 2 Based on ASME IX.					REMARKS - * Formerly CMo3 (MSZ 61) - ** Ni content less than 1 % - Before welding bake electrodes for 2 hours at 350 °C				
		BY	DATE	TECHNICAL DATA SHEET					
Desig.	Bozok	14.06.2009		WELDING PROCEDURE SPECIFICATION				HOSE TECHNICAL	
Appr.	Bozok	14.06.2009		SUBJECT: Butt weld of hose coupling for H2S service;				DEPARTMENT	
Chek'd				Strenght 75K				WPS N° 140-71 Rev.4	

PHOENIX RUBBER Industrial Ltd. Hose Division	N°:	WPS 140-71 Addendum
	Revision:	4
ADDENDUM for the approved wall thickness range 5-38 mm Based on WPS 140-71 Rev.4, PQR No.: BUD 070002/1	Page N°:	1/2
	Date:	2007-06-12
	Designed:	<i>Bauer</i>
	Checked:	
	Approval:	<i>[Signature]</i>

No.	Wall thickness [mm]	Weld layers	Electrode Ø [mm]
1.	5-7	 1 2	3,2 3,2
2.	7-9	 1 2-3	3,2 3,2
3.	9-11	 1 2-3 4-5	3,2 3,2 4,0
4.	11-13	 1 2-3 4-6	3,2 3,2 4,0
5.	13-15	 1 2-3 4-8	3,2 3,2 4,0
6.	15-18	 1 2-3 4-10	3,2 3,2 4,0
7.	18-20	 1 2-3 4-11	3,2 3,2 4,0
8.	20-22,22	 1 2-3 4-15	3,2 3,2 4,0
9.	22,2-26	 1 2-3 4-19	3,2 3,2 4,0

Remarks: - Process for layer No1 GTAW with Ø3,2 mm thoriated tungsten electrode and Ø2,4 mm Rod EML 5;
for the others: SMAW with electrode T-PUT NiMo 100

PHOENIX RUBBER Industrial Ltd. ADDENDUM for the approved wall thickness range 5-38 mm Based on WPS 140-71Rev.4, PQR No.: BUD 0700002/1	N°:	WPS 140-71 Addendum
	Revision:	4
	Page N°:	2/2

No.	Wall thickness [mm]	Weld layers	Electrode Ø [mm]
10.	26-29		1 3,2 2-3 3,2 4-19 4,0
11.	29-32		1 3,2 2-3 3,2 4-23 4,0
12.	32-35		1 3,2 2-3 3,2 4-24 4,0
13.	35-38		1 3,2 2-3 3,2 4-28 4,0


Remarks: - Process for layer No1 GTAW with Ø3,2 mm thoriated tungsten electrode and Ø2,4 mm wire EML 5;
for the others: SMAW with electrode T-PUT NiMo 100

Certificate no: BUD 0700002/1
Page 1 of 2



Welding Procedure Qualification Record
(PQR) ASME IX
Energy and Transportation

Company Name: Phoenix Rubber Gumilpari Kft, SZEGED
 Procedure Qualification Record No. BUD 0700002/1
 WPS No. 140-71
 Welding Process(es) GTAW/SMAW
 Types (Manual, Automatic, Semi-Auto.) Manual
 Date 28 February 2007



Groove Design for Test Coupon
(For combination qualifications, the deposited weld metal thickness shall be recorded for each filler metal or process used.)

Base Metal (QW-403)
 Material Spec. ASTM A 322-91, AISI 4130
 Type or Grade AISI 4130
 P.No. AISI 4130 to P.No. AISI 4130
 Thickness of Test Coupon 19 mm
 Diameter of Test Coupon 72 mm

Postweld Heat Treatment (QW-407)
 Temperature 620 +20-0 °C
 Time 4 hours
 Other

Other
 Filler Metals (QW-404)
 SFA Specification ER 70S-3
 AWS Classification A5.18
 Filler Metal F-No. 6
 Weld Metal Analysis A-No. 1
 Size of Filler Metal 2.4 mm
 Other
 Weld Metal Thickness 3 mm
 Position (QW-405)
 Position of Groove 1G rotated
 Weld Progression (Uphill, Downhill)
 Other

Gas (QW-408)

	Shielding Gas	Backing Gas	Flow Rate
Shielding	Ar 99.95%		10-12 l/min
Backing	Ar 99.95%		7-9 l/min

Electrical Characteristics (QW-409)
 Current DC
 Polarity GTAW DCEN, SMAW DCEP
 Amps. Layer 1 120, Layer 2-3 127, Layer 4-12 136
 Tungsten Electrode Size 3.2 mm
 Other

Preheat (QW-416)
 Preheat Temp. 300-330 °C
 Interpass Temp. max 350 °C
 Other

Technique (QW-410)
 Travel Speed Layer 1-11 100-130 Layer 12 non/min
 String or Weave Bead Layer 1-11 String Layer 12 Weave

	GTAW	SMAW
Multipass or Single Pass (per side)	5	M
Single or Multiple Electrodes	5	M

 Heat Input Layer 1 6.0-6.6 kJ/cm, Layer 2-3 14.1-19.8 kJ/cm, Layer 4-12 18.7-28.1 kJ/cm

Lloyd's Register, its affiliates and subsidiaries and their respective officers, employees or agents are, individually and collectively, referred to in this clause as the 'Lloyd's Register Group'. The Lloyd's Register Group assumes no responsibility and shall not be liable to any person for any loss, damage or expense caused by reliance on the information or advice in this document or howsoever provided, unless that person has signed a contract with the relevant Lloyd's Register Group entity for the provision of this information or advice and in that case any responsibility or liability is exclusively on the terms and conditions set out in that contract.

Certificate no: **BUD 0700002/1**
 Page 2 of 2

Specimen No.	Width mm	Thickness mm	Area mm ²	Tensile Test (QW150)		Type of Failure & Location
				Ultimate Total Load kN	Ultimate Unit Stress MPa	
39/1	18.9	15.8			657	Base material
39/2	18.9	15.7			664	Base material

Guided Bend Test (QW160)
 Type and Figure No. **180° Bend roller dia: 36 mm 2+2 pcs.**
 Results **Satisfactory**

Specimen No.	Notch Location	Specimen Size mm	Test Temp. °C	Impact Value J	% Shear	M/s	Drop Weight Break (Y/N)
39	S	10x10x55	-30	49			
39	S	10x10x55	-30	41			
39	HAZ	10x10x55	-30	38			
39	HAZ	10x10x55	-30	97			
39	HAZ	10x10x55	-30	62			

Comments:


Flare Tests (QW18)
 Result - Satisfactory: Yes No Penetration Into Parent Metal: Yes No

Macro - Results
Other Tests
 Type of Test **Hardness test**
 Deposit Analysis
 Other **Macro - Satisfactory**
X-ray - Satisfactory
 Welder's Name **Tivadar Szabo DC-IL 378258** Clock No. **(BC 15)** Stamp No.
 Test Conducted By: **DKG EAST Anyagvizsgalati Labor.** Laboratory Test No: **TMO 007-7/07 VJK 1207/2007**

We certify that the statements in this record are correct and that the test welds were prepared, welded, and tested in accordance with the requirements of Section IX of the ASME Code.


Date Issued: **28 February 2007**

Manufacturer's Representative **László Bajusz**
 Manufacturer **Phoenix Rubber Gumipari Kft., SZEGED**



László Pénzes
 Surveyor to Lloyd's Register EMEA

A member of the Lloyd's Register Group



Fluid Technology

WELDER'S APPROVAL TEST CERTIFICATE - ASME CODE IX

Examiner or test body: ABS

Registration No.: RK1825997.R1

Designation ASME IX: GTAW / SMAW Pipe BW s19 1G

Welder's name: Tivadar Szabó (BC15)

Identification card No: 517278EA

Date and place of birth: 19. August 1949; SZEGED

		Weld test details	Range of approval	Photo (if required)
Welding process		GTAW/SMAW		
Filler metal	Type	Rod / Electrode		
	Designation	AWS 5.18: ER70S-3 AWS 5.5: E9018		
Parent metal group(s)		ASTM A 322-91; AISI 4130	ASTM A 322-91; AISI 4130	
Plate or pipe		Pipe	Pipe/Plate	
Welding position		1G	1G/Flat	
Outside diameter (mm)		72 mm	> 25 mm	Identification of test pieces:
Test piece thickness (mm)		19	Max to be welded	
Single/ both side welding		Single		WPS No.: 140-60 Rev.4
Gouging/ backing				
Joint type		Groove	Groove / Fillet	Testing standard: ASME IX
Shielding/ backing gas(es)		Argon (99,95%)		
Welding carried out, place: Szeged			Date: 29 April 2010	
			Welding Engineer: László Bajusz <i>Bajusz</i>	
Type of test	Performed and accepted	Not required	Place and date: Szeged, 18-Jun-2010 Surveyor: Péter Szabó Stamp and signature: 	
Visual	Accepted (Vjk-1739/10)			
Radiography	Accepted (Vjk-1739/10)			
Ultrasonic		+		
Magnetic particle		+		
Penetrant		+		
Macro		+		
Fracture		+		
Bend		+		
Additional tests		+		
See attached page(s) for prolongation by employer every 6 months				

JE-ZO KFT. 6728 Szeged, Kálterület 01408/22 hrsz. Adószám: 13341039-2-06 Bankszámlaszám: 12067001-00127077-00100001		WELDING LOG SHEET HEGESZTÉSI MUNKALAP		WLS N ^o Száma: 2013. / 2898.	
				PAGE /oldal 1/1	
CLIENT Megrendelő CONTITECH RUBBER Industrial Kft.			PURCH.ORDER N ^o Rendelészám 32261598		
CONTRACT N ^o Kötésszám		SPOOL/JOB N ^o Üzemi m.szám 2898 - 2905		WPS N ^o Heg.ut.szám 140-71 Rev. 4. / 7	
NAME OF WEDED PARTS Heg. alkatrész megnevezése Body + Flange			DRWG N ^o Rajzszám WT 3121-3000		
NAME/N ^o . OF WELDER Hegesztő neve és száma Szabó Tivador László. B.C. 15.			LOCATION/SHOP Munkavégzés helye Szeged. Tépé szüle G.		
DATE Dátum 2013. 10. 25		QUANTITY Darabszám 8		SERIAL NUMBERS Sorszámok 8083 - 8090	
1. MATERIAL CONTROL Anyag megfelelés azonosítása	SUBJECT 1 Tárgy 1 body	MATERIAL Anyag AlSi. 4130	CAST N ^o Adagszám 24665, 8083-8088		
	SUBJECT 2 Tárgy 2 Flange	MATERIAL Anyag AlSi. 4130	CAST N ^o Adagszám 034939		
2. FILLER METAL Elektroda minőség és méret	WELD LAYERS Varratszám	1.	2-3.	4-11.	
	TYPE Típus	EW. 5.	NIMD. 100.	NIMO. 100.	
	DIAMETER Átmérő	2.4.	3.2.	4.	
	FILLER CAST N ^o Elektr.adagszám	800303.	1124075	1127750.	
3. ELECTRICAL CHARACTERISTICS Elektromos adatok	TYPE POLAR Polaritás	-	+	+	
	VOLT (V)	12.	24.	26.	
	AMPERE (A)	180.	140.	180.	
4. PRE HEAT TREATMENT OF ELECTRODES Elektroda felhasználást megelőző hőkezelése		300.	°C	8.	Hours
5. APPLIED SHILDING GAS Alkalmazott védőgáz	TYPE Típus Argon.	Percentage Composition Tisztaság 99.95. %		Flow Rate Áramlási seb 8. l/min	
6. HEAT TREATMENT (pre-weld) Előmelegítés	300.	°C	7. POSITION Helyzet Forgatott.		
8. SPEED OF TRAVELS Hegesztési sebesség	100 ÷ 130. mm/min		9. LAPSE BETWEEN OF PASSES Varratfelrakási szünetek 8. min		
10. POSTWELD HEAT TREATMENT Utóhőkezelési adatok	Time Idő 240. min	Temperature Hőmérséklet 620. °C	Furnace atmosph. Hűtőközeg Levegő.	Cooling rate Hűlési sebesség 80. °C/H	
11. RADIOGRAPHIC TEST CERT. N ^o . Radiográfiai vizsg. biz. száma 2430/15, 2451/15					
REPAIR Javítás	YES/ Igen		X NO/ Nem		
	PLACE OF DEFECT Hiba helye		TYPE OF DEFECT Hiba típusa		
	METHOD OF REPAIR Javítási módszer				
VISUAL INSPECTION Szemrevételezés Megfelelő / Satisfactory.					
REMARKS Megjegyzés Fronius. Magic. Wave. 2600.					
Date, end of coling down time Dátum, kihűlés vége 2013. 10. 26. - 15. óra		WELDER HEGESZTŐ JE-ZO KFT. HEGESZTŐI TÁRSASÁG 6728 Szeged, Tépé szüle 6. Tel.: 6728 Szeged, Heller köz 1. Adószám: 13341039-2-06		INSPECTOR Ellenőr BC 15 DATE Dátum 2013 NOV 04	

 <p>www.gamma-control.hu 6750 Algyó, Kálvária út 113/A/14. fsz. Tel./Fax.: +36 82/517-400 / 01344 A NAT 483 NAT-1-11402/03 sz. szerinti szabvány szerinti vizsgálóhely</p>	SZEMREVÉTELEZÉSES VIZSGÁLATI JEGYZŐKÖNYV	Record No. Jegyzőkönyv száma:
	VISUAL EXAMINATION REPORT	813/13

Object Tárgy	Coupling welding Csatlakozó hegesztés	Serial No. Gyári szám	8083-8090
Customer Megrendel	JE-ZO Kft. Szeged	Drawing No. Rajzszám	MT-3121-3000
Job Nr. Munkaszám	002/13	Material/Dimension Anyagminőség/méret	AISI 4130 118/77
Quantity Mennyiség	8 db	Extent of examination Vizsgálat terjedelme	100%
Requirements Követelmények	ASME code VIII/1	Heat treatment Hőkezelés	after PWHT
Written Procedure No. Vizsgálati eljárás száma	QCP-09-1	Welder Hegesztő	BC15

Visual examination / Szemrevételezéses vizsgálat

Technique Módszer	Direct visual	-
Instrument Készülék	-	-
Visual aids Segédeszközök	3x magnifying lens	-

Measurement / Mérés

Equipment Készülék	-	-
Instrument Készülék	-	-
Surface temperature A felület hőmérséklete	20 °C	Lighting intensity Megvilágítás
Surface condition Felület Állapota	machined	1000lx

Test results Eredmények :	SATISFACTORY	
	megfelelő.....8	pc(s)/db
	not accepted	
	nem megfelelő.....0	pc(s)/db

Vizsgálat helye és ideje: Place and date of test:	Vizsgálatot végezte: Tested by:	Áttekintette és jóváhagyta: Reviewed and approved by:
Gamma-Controll Kft. Algyó, 2013.10.30. (10h)	Kis Gábor VT20103130102	GAMMA-CONTROL Kft. 6750 Algyó, Kálvária út 113/A/14. fsz. Adaszék 11004612-2-09 www.gamma-control.hu Tel. Fax: +36 82/517-400



MAGYAR HEGESZTÉSTECHNIKAI ÉS ANYAGVIZSGÁLATI EGYESÜLÉS
(HUNGARIAN ASSOCIATION OF WELDING TECHNOLOGY AND MATERIAL TESTING)
(Certification Body)

RONCSOLÁSMENTES ANYAGVIZSGÁLÓ TANÚSÍTVÁNY
(Certificate of NDT personnel)

A tanúsított neve:
(The name and forename of
the certificated individual):
Születési hely/ideje:
(Place and date of birth):

Kis Gábor Balázs
Szeged, 1980. 02. 29.

Azonosító szám:
(Identification No.): **VT20103130102**

A tanúsított személy aláírása
(The signature of the certificated individual)

Vizsgálati eljárás(ok):
(The NDT method(s)):

Szemrevételezéses anyagvizsgáló
(Visual testing)

Ipari terület:
(Industrial sector):

Készülékek, berendezések, létesítmények vizsgálata EM
(Pre and in-service testing of equipment, plant and structure)

Termék terület(ek):
(Product sector(s)):

(c), (w), (wp), (f)

A minősítés fokozata:
(The level of certification):

VT2

A tanúsítás és kiadásának időpontja:
(The date of certification and its issue):

Budapest, 2013. 02. 19.

A tanúsítás érvényes:
(The date upon which certification expires):

2018. 02. 18.

Tanúsító Testület nevében
(On behalf of certifying body)



Vizsgáló
(Examiner)

Az ipari és/vagy termék terület érvényesség kiterjesztve:
(The industrial and/or product sector has been expanded to):

Dátum (Date):

Tanúsító Testület nevében
(On behalf of certifying body)

A tanúsítás érvényessége
(Renewed the validity of the certification until (MSZ EN ISO 9712 10.):

-ig megújítva (MSZ EN ISO 9712 10.):

Dátum
(Date):

Tanúsító Testület nevében
(On behalf of certification body)

c - öntvények (castings); f - kovácsolt termékek (forgings); w - hegesztett és forrasztott termékek (welded products); t - csövek és csővezetékek (tubes); wp - alakított termékek (wrought products); k - kompozit anyagok (composites products).

VT20103130102



MAGYAR HÉGESZTÉSTECHNIKAI ÉS ANYAGVIZSGÁLATI EGYESÜLÉS
(HUNGARIAN ASSOCIATION OF WELDING TECHNOLOGY AND MATERIAL TESTING)
(Certification Body)

Meghatározzuk a tanúsítvány tulajdonosát, hogy vizsgálatokat végezzen és azok eredményéért felelősséget vállaljon.
 (MSZ EN ISO 9712 3.21)
 (The holder of this certificate is authorised to perform tests and take responsibility for the test results. (MSZ EN ISO 9712 3.21))

GAMMA CONTROLL KFT.
 0726 Szeged, Tüzok u. 8/A
 Adószám: 11704614-3-002
 Bank: 11335003-20100134
 www.gamma-control.hu
 Tel.: 06-30-216-0000

Dátum: 2013.01.01.
 (Date)

Folyamatos munkatevékenység igazolása (MSZ EN ISO 9712 10.)
 (Evidence of continued work activity (MSZ EN ISO 9712 10.))

Sorsz.	Munkáltató aláírása (Signature of the employer)	Fü "GAMMA CONTROLL" Anyagvizsgáló és Minőségellenőrző Kft.	Dátum (Date)
1.			2013.01.01.
2.			
3.			
4.			
5.			
6.			
7.			
8.			
9.			
10.			

Kiegészítések:
 (Additional remarks)

A tanúsítvány a munkáltató aláírásával érvényes
 (This certificate is valid with the signature of the employer.)

Feladó : 61344

gamma controll kft

19/10/13 12:54 Lap: 1

 <p>www.gamma-controll.hu 6750 Algyő, Kálterület 01884/II. hrsz. TEL/FAX: +36 63/617-400 / 61944 A KFT által KAT-1-1102010-10 alapján elővártott vizsgálatokhoz</p>	<p>RADIOGRÁFIAI VIZSGÁLATI JEGYZŐKÖNYV</p> <p>RADIOGRAPHIC EXAMINATION REPORT</p>	<p>Jegyzőkönyv szám: Report No.: 2431/13</p> <p>Kiállítás dátuma: Date of report: 2013.10.30</p>
--	---	--

Vizsgálat tárgya: Object:	Coupling	Megrendelő: Client:	JE-ZO Kft. Szeged
Munkaszám:	—	Rendelési szám: Order No.:	—
Job No.:	—	Anyagminőség: Material:	AISI 4130
Rajzsám: Drawing No.:	MT-3121-3000	Vizsgálat terjedelme: Extent of testing:	100%
Vizsgálati szabvány: Testing standard:	QCP-13-1	Hőkezelés: Heat treatment condition:	After PWHT
Árvételi követelmény: Acceptance criterion:	ASTM E94	Hegesztési jele: Welder stamp:	BC15
Kód: Code:	MSZ EN ISO 6520-1	Képmínőségjelző típusa: Type of IQ:	ASTM set B type
Berendezés típusa: Type of equipment:	GAMMAMAT	Képmínőségjelző helye: Placement of IQ:	F
Sugárforrás: Source:	Ir192	Előírt képmínőség: Required IQ:	2% (2-2T)
Sugárforrás mérete: Source size:	3x1,5mm	Film típusa: Film Type:	FOMA R5
Aktivitás: Activity:	0,4 TBq	Fóliafajta és vastagság: Screen type and thick:	Pb 0,027
Filmfeldolgozás módja: Film processing:	Kézi: Manual:	Automata: Automatic:	<input checked="" type="checkbox"/>

Megnevezés Designation	Méret Size	Férvetés száma: Number of radiograph	Ábrázolt anyagvastagság: Penetrated thickness	Sugárforrás film távolság: Source-to-film distance	Film táv. a tárgy sugárforrás közli közéle: Distance from source side of object to film	Férsűrűs: Density	Mégvilágítás idő: Expos. Time	Vizsgáló: Inspector	Eredmény: Result	Vizsgálati körülmények: Examined conditions	Hibák/Defects					
											Gáz Porosity A	Salak Slag B	Kötés Lack of fusion C	Gyök Lack of penetration D	Repedés Crack E	Felület Surface F
8083	115/77	4	19	96	19	2,4	0,5	A	10,30 10h							
8084	115/77	4	19	96	19	2,4	0,5	A	10,30 10h							
8085	115/77	4	19	96	19	2,4	0,5	A	10,30 10h							
8086	115/77	4	19	96	19	2,4	0,5	A	10,30 10h							
8087	115/77	4	19	96	19	2,4	0,5	A	10,30 10h							
8088	115/77	4	19	96	19	2,4	0,5	A	10,30 10h							

A filmszámok és varratszámok azonosak, beazonosításuk a megrendelőre terheli.
The numbers of the films and welds are identical, their identification is the task of the customer.

Vizsgálatot végezte:
Performed by: **Ménesi I. - Szabó T.**

Vizsgálat helye: Place of test: 6750 Algyő, Gamma-Controll Kft. Telephely	Értékelte: Evaluated by:  Ménesi István RT20101120107	Jóváhagyta: Approved by:  GAMMA - CONTROLL KFT 6750 Algyő, Kálterület 01884/II. hrsz. Adószám: 14946122-04 www.gamma-controll.hu Tel: +36 30 218 2640 Péter Vezsér
--	---	---

Ez a jegyzőkönyv részleteiben nem másolható / Copying details is prohibited

Feladó : 61344

gamma controll kft

19/10/13 12:48 Lap: 1

 GAMMA-CONTROLL <small>www.gamma-controll.hu 6750 Algyó, Kálváriaút 0189/14. hrsz. Tel./Fax: +36 02917-400 / 61344 A NYK által kiadott 1/19622/14 sz.útvál. alapján készült vizsgálati jelentés</small>	RADIOGRÁFIAI VIZSGÁLATI JEGYZŐKÖNYV RADIOGRAPHIC EXAMINATION REPORT	Jegyzőkönyv szám: Report No.: 2430/13 Kiállítás dátuma: Date of report: 2013.10.30
--	--	---

Vizsgálat tárgya: Object:	Coupling	Megrendelő: Client:	JE-ZO Kft. Szeged
Munkaszám: Job No.:	—	Rendelési szám: Order No.:	—
Rajzsám: Drawing No.:	MT-3121-3000	Anyagminőség: Material:	AISI 4130
Vizsgálati szabvány: Testing standard:	QCP-13-1	Vizsgálati terjedelmé: Extent of testing:	100%
Arvéri követelmény: Acceptance criteria:	ASTM E94	Hkezelés: Heat treatment condition:	After PWHT
Kód: Code:	MSZ EN ISO 6520-1	Hegesztő jelé: Welder stamp:	BC15
Berendezés típusa: Type of equipment:	GAMMAMAT	Képmínőségjelölő típusa: Type of IQI:	ASTM set B type
Sugárforrás: Source:	Ir192	Képmínőség jelző helye: Placement of IQI:	F
Sugárforrás mérete: Source size:	3x1,5mm	Elmírt képmínőség: Required IQI:	2% (2-2T)
Aktivitás: Activity:	0,4 TBq	Film típus: Film Type:	FOMA R5
Filmfeldolgozás módja: Film processing:	Kézi: Manual:	Automata: Automatic:	X
		Pólyaajtó és vastagság: Screen type and thick:	Pb 0,027

Megnevezés Designation	Méret Size	Férválók száma: Number of radiographs	Ásugárfilm vastagság: Processed thickness	Sugárfilm film vastagság: Source-to-film distance	Film táv. a tárgy széle felől: Distance from source edge of object to film	Férsűrűs: Density	Véghatár: Expos. Time	Munkaszám: NA-vevő engedély: Rész: Accession No. and access.	Vizsgáló dátuma: Date of test	Hibák/Defects					
										Cláz: Porosity	Salak Slag	Kötés Lack of fusion	Gyök Lack of penetration	Repedés Crack	Felület Surface
										A	B	C	D	E	F
8089	115/77	4	19	96	19	2,4	0,5	A	10.30.10h						
8090	115/77	4	19	96	19	2,4	0,5	A	10.30.10h						
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-

A filmszámok és varratszámok azonosak, beazonosításuk a megrendelőt terheli.
The numbers of the films and welds are identical, their identification is the task of the customer.

Vizsgálatot végezte: Performed by:	Ménesi I. - Szabó T.	
Vizsgálat helye: Place of test:	Értékelte: Evaluated by:	Jóváhagyta: Approved by:
6750 Algyó, Gamma-Controll Kft. Telephely	 Ménési István RT20101120107	GAMMA-CONTROLL KFT 6750 Algyó, Kálváriaút 0189/14. hrsz. Adószám: VEP-1614-2-#6 www.gamma-controll.hu Tel: +36 90 230 6640

Ez a jegyzőkönyv részleteiben nem másolható / Copying details is prohibited!



MAGYAR HEGESZTÉSTECHNIKAI ÉS ANYAGVIZSGÁLATI EGYESÜLÉS
(HUNGARIAN ASSOCIATION OF WELDING TECHNOLOGY AND MATERIAL TESTING)
(Certification Body)

RONCSOLÁSMENTES ANYAGVIZSGÁLÓ TANÚSÍTVÁNY
(Certificate of NDT personnel)

Azonosító szám: **RT20101120107**
(Identification No.):

A tanúsított neve:
(The name and forename of the certified individual):
Születési hely/idő:
(Place and date of birth):

Ménesi István
Szentes, 1988. 09. 06.

A tanúsított személy aláírása
(The signature of the certified individual)

Vizsgálati eljárás(ok):
(The NDT method(s)):

Radiográfiai anyagvizsgálat
(Radiographic testing)

Ipari terület:
(Industrial sector):

Készülékek, berendezések, létesítmények vizsgálata EM
(Pre and in-service testing of equipment, plant and structure)

Termék terület(ek):
(Product sector(s)):

(c), (w)

A minősítés fokozata:
(The level of certification):

RT2

A tanúsítás és kiadásának időpontja:
(The date of certification and its issue):

Budapest, 2012. 03. 28.

A tanúsítás érvényes:
(The date upon which certification expires):

2017. 03. 27.

Tanúsító Testület nevében
(On behalf of certifying body)

Vizsgáztató
(Examiner)

Az ipari és/vagy termék terület érvényesség kiterjesztve:
(The industrial and/or product sector has been expanded to):

Dátum (Date):

A tanúsítás érvényessége
(Renewed the validity of the certification until (MSZ EN 473 9.):

-ig megújítva (MSZ EN 473 9.):

Dátum (Date):

Tanúsító Testület nevében
(On behalf of certification body)

A Magyar Hegesztéstechnikai és Anyagvizsgáló Egyesülés, mint „a Nemzeti Akkreditáló Testület által a NAT-5-0013/2010 számon akkreditált személytanúsító szervezet” a fentebb nevezett személyt tanúsítja az MSZ EN 473 szerint eredményes vizsgálata alapján a fentiek szerint:
(The Hungarian Association of Welding Technology and Material Testing as an “accredited certification body for person as by National Accreditation Board (under No. NAT-5-013/2010”, on the basis of his/her successful examination under the standard MSZ EN 473, hereby certifies the named individual according to the above.)

* c - öntvények (castings); f - kovácsolt termékek (forgings); w - hegesztett kötések-termékek (welded products); t - csövek (tubes); wp - alakított termékek (wrought products); p - műanyag termékek (plastics products); k - kompozitok (composites products).

RTZ0101120107



MAGYAR HEGESZTÉSTECHNIKAI ÉS ANYAGVIZSGÁLATI EGYESÜLÉS
(HUNGARIAN ASSOCIATION OF WELDING TECHNOLOGY AND MATERIAL TESTING)
(Certification Body)

Meghatalmazzuk a tanúsítvány tulajdonosát, hogy vizsgálatokat végezzen és azok eredményéért felelősséget vállaljon.
 (MSZ EN 473 3.21)

(The holder of this certificate has been authorized to perform tests and take responsibility for the test results. (MSZ EN 473 3.21))

GAMMA-CONTROLL Kft.
 6126 Szeged, Tuzos
 Adószám: 11094614-2-06
 OTP Bank: 11735005-20406154
 www.gamma-control.hu
 Tel: 06-30-218-2640

Munkáltató aláírása:
 (Signature of the employer:)

Dátum:
 (Date: 2012.04.19.)

Folyamatos munkavégzés igazolása (MSZ EN 473 9.)
 (Evidence of continued work activity (MSZ EN 473 9.))

Sorsz.:	Munkáltató aláírása (Signature of the employer)	Ph "GAMMA-CONTROLL" Anyagvizsgáló és Kísérleti Kft. "GAMMA-CONTROLL" Anyagvizsgáló és Kísérleti Kft.	Dátum (Date)
1.			2012.04.19.
2.			2013.06.09.
3.			
4.			
5.			
6.			
7.			
8.			
9.			
10.			

Kiegészítések:
 (Additional remarks:)

ContiTech Rubber Industrial Kft. Szeged/Hungary		Examination record Vizsgálati jegyzőkönyv Liquid penetrant examination Festékdiffrúziós vizsgálat <input checked="" type="checkbox"/> Magnetic particle examination Mágneses repedésvizsgálat		Record No. Jegyzőkönyv száma : 1222/13
Manufacturer Gyártó	JE-ZO Kft.	Serial No. Gyári szám	8083-8090	
Customer Megrendelő	ContiTech Rubber Industrial Kft.	Drawing No. Rajzszám	MT 3121-3000	
Object Tárgy	coupling(s)	Material Anyagminőség	AISI 4130	
Quantity Mennyiség	8 pc(s)	Extent of examination Vizsgálat terjedelme	100 % outside	
Requirements Követelmények	ASTM E 709	Heat treatment Hőkezelés	yes	
Written Procedure No. Vizsgálati eljárás száma	QCP-11-1	Welder: Hegesztő:	Szabó T.	
Liquid penetrant examination /Folyadékbehatolásos vizsgálat				
Penetrant Behatóló anyag	Remover Tisztító	Developer Előhívó		
Dwell time Behatólási idő	Drying Szárítás	Developing time Előhívási idő		
Surface temperature A felület hőmérséklete	Surface condition Felület állapota	Lighting intensity Megvilágítás		
Magnetic particle examination/Mágnesezhető poros vizsgálat				
Equipment type Készülék típusa	TSW 1000	Testing material Vizsgáló anyag	MR 76F	Magnetizing current Mágnesező áram
Black light type UV-A lámpa típusa	Superlight C 10A-HE	Field strength checking Téroró mérő	Berthold disc	Field strength Téroró
Surface temperature A felület hőmérséklete	23 °C	Surface condition Felület állapota	machined	Lighting intensity Megvilágítás
Test results Eredmények :				
		satisfactory megfelelő.....8..... pc(s)/db		
		not accepted nem megfelelő.....-..... pc(s)/db		
Performed by NDE Level II. Vizsgálatot végezte <i>Oravec Gábor</i> Signature Aláírás Place/Date Kelt Szeged, 04.11.2013.		Revised by Q.C. manager Ellenőrizte – MEO vezető ContiTech Rubber Industrial Kft. QC 1 <i>Markó László</i> Signature Aláírás Place/Date Kelt Szeged, 04.11.2013.		

QCP-12-1-MPT/07



MAGYAR HEGESZTÉSTECHNIKAI ÉS ANYAGVIZSGÁLATI EGYESÜLÉS
(HUNGARIAN ASSOCIATION OF WELDING TECHNOLOGY AND MATERIAL TESTING)
(Certification Body)

RONCSOLÁSMENTES ANYAGVIZSGÁLÓ TANÚSÍTVÁNY
(Certificate of NDT personnel)

Azonosító szám: **MT20103010506Ú**
(Identification No.):

A tanúsított neve:
(The name and forename of the certified individual): **Oravecz Gábor**

Születési hely/ideje:
(Place and date of birth): **Szeged, 1958. 07. 07.**

A tanúsított személy aláírása
(The signature of the certified individual)

Vizsgálati eljárás(ok):
(The NDT method(s)): **Mágnesezhető poros anyagvizsgáló
(Magnetic particle testing)**

Ipari terület:
(Industrial sector): **Fémfeldolgozás MM
(Metal manufacturing)**

Termék terület(ek):
(Product sector(s)): **(c), (f), (w), (wp)**

A minősítés szintje:
(The level of certification): **MT2**

A tanúsítás és kiadásának időpontja:
(The date of certification and its issue): **Budapest, 2012. 02. 21.**

A tanúsítás érvényes:
(The date upon which certification expires): **2017. 02. 20.**

Tanúsító Testület nevében
(On behalf of certifying body)

Vizsgáztató
(Examiner)

Az ipari és/vagy termék terület érvényesség kiterjesztve:
(The industrial and/or product sector has been expanded to):

Dátum (Date): _____

Tanúsító Testület nevében
(On behalf of certifying body)

A tanúsítás érvényessége _____-ig megújítva (MSZ EN 473 9.):
(Renewed the validity of the certification until (MSZ EN 473 9.):)

Dátum (Date): _____

Tanúsító Testület nevében
(On behalf of certification body)

A Magyar Hegesztéstechnikai és Anyagvizsgáló Egyesület, mint „a Nemzeti Akkreditáló Testület által a NAT-5-0013/2010 számon akkreditált személytanúsító szervezet” a nevezett személyt tanúsítja az MSZ EN 473 szerint eredményes vizsgálja alapján a fentiek szerint:
(The Hungarian Association of Welding Technology and Material Testing as an “accredited certification body for person an by National Accreditation Board (under No. NAT-5-013/2010”, on the basis of his/her successful examination under the standard MSZ EN 473, hereby certifies the named individual according to the above:)

* c - öntvények (castings); f - kovácsolt termékek (forgings); w - hegesztett kötések-termékek (welded products); t - csövek (tubes); wp - alakított termékek (wrought products); p - műanyag termékek (plastics products); k - kompozitok (composites products).



MAGYAR HEGESZTÉSTECHNIKAI ÉS ANYAGVIZSGÁLATI EGYESÜLÉS
(HUNGARIAN ASSOCIATION OF WELDING TECHNOLOGY AND MATERIAL TESTING)
(Certification Body)

* Meghatalmazzuk a tanúsítvány tulajdonosát, hogy vizsgálatokat végezzen és azok eredményéért felelősséget vállaljon.
(MSZ EN 473 3.21)
(The holder of this certificate has been authorised to perform tests and take responsibility for the test results. (MSZ EN 473 3.21))

Munkáltató aláírása:
(Signature of the employer:)

[Handwritten signature]

Dátum:
(Date:)

2012. 02. 21.

Folyamatos munkavégzés igazolása (MSZ EN 473 9.) (Evidence of continued work activity (MSZ EN 473 9.))			
Sorsz.:	Munkáltató aláírása (Signature of the employer)	Ph. Contitech Rubber Industrial Kft. Quality Control Dept. (1)	Dátum (Date)
1.	<i>[Handwritten signature]</i>		2013. 01. 24.
2.			
3.			
4.			
5.			
6.			
7.			
8.			
9.			
10.			

Kiegészítések:
(Additional remarks:)

505760

Bekaert Hlohovec a.s.
 Mierová 2317
 82028 Hlohovec / Slovakia
 Tel.: 00421337363111
 Fax: 00421337422742

**STEELCORD
 MANUFACTURER : BKHL**

Page : 1 / 1

Certificate of Analysis
 Delivery No. : 4046181212

Contitech Rubber Industrial Kft.
 CONTITECH RUBBER IND SZEGED
 Budapesti út 10
 H-6728 SZEGED

Sales Order 3046058220/10
 Purchase Order 32260330
 Inspection lot 090000200665/000001
 Batch 3500245378
 Date produced 01.07.2013
 Date COA 09.08.2013
 Spools 32 delivered from a batch of 32 produced
 Units 16 delivered from a batch of 16 produced
 Delivery net Qty. 10517 KG
 Material Description Zinc coated steelcord 1X24DW/3.6 NT 20/36 ZZ B850
 5000 M
 Lay direction ZZ
 Lay length 20/36

Spec customer Contitech Rubber Industrial Kft.
 Your code 14-18-07/1
 Your spec REV.3 / 15.01.2002
 Our Spec H207297 / 26.10.2012

Tests			Specs		Results		
Test	Procedure	Unit	Alm	Min. Max.	Avg. N	Min ind Max ind	
Cord diameter	RA12-100	mm	3,6000	3,4200 3,7800	3,6845 6	3,6840 3,6930	
Linear density	RA30-110	g/m	65,000	61,700 68,300	66,632 6	65,300 65,870	
Cord breaking strength	RA30-203	N		17800,0	19337,0 6	19087,0 18584,0	
Cord elongation at break	RA30-203	%		2,50	2,98 6	2,80 3,15	
Zinc D1	RA40-741	g/m2		32,000	40,057 6	37,870 44,630	
Zinc D2	RA40-741	g/m2		44,000	48,788 6	45,350 55,100	
Residual torsions	RA30-160	Nt	0,000	-3,000 3,000	-0,250 6	-0,500 0,000	

Comments :
 D1: 0,54
 D2: 0,73
 Nominal Chemical composition of High Grade Oxysteel:
 %Carbon : 0.70-0.90
 %Manganese: 0.40-0.60
 %Silicon: <0.230
 %S: <0.011
 %P: <0.012

Microstructure/Texture: Metallurgically the texture is known as a highly drawn, fine ferritic structure.



Terminox S.p.A. con Unico Bocio
 Una società del gruppo ThyssenKrupp Acciai Speciali Len.
 C.V.A. 00012070558



Azienda con sistema di gestione certificato da IGO secondo ISO: 9001

PAG 1/1

Conforme a EN.10204/ 3.1

n°: **63892/2012**

Specifica/Specification:
EN 10088-2

Destinatario/Receiver:
ACCIAI VENDER S.P.A.
VIA A. NOBEL, 3/A
43100 PARMA

Cliente/Customer: ACCIAI VENDER S.P.A.
VIA A. NOBEL, 4/A Q.RE IND.LE S.P.I.P.
43100 PARMA
Acciaio/Steel: 304PS

25 mm

DDT/DEL. NOTE: 16753 DEL/OF: 24/05/2012 Ordine/order Terminox: P04249 Ord. Cliente/Customer:

Matricola Serial Number	Pos Item	Tipo Prodotto Product Type	Fin	Descrizione Description	Dimensioni(mm) Dimensions(mm)	Pezzi Pieces	Weight (Kg)	Rif. Cli. Cust. Ref.	Colata Heat	NIM
C47997 T-22882	22	COIL	2B		0.60 x 460.0	1	6040		0431359	310727
C54489 T-22887	27	NASTRI STRETTI	BA		0.79 x 264.7	1	1290		0431741	324612

IL MATERIALE SOPRA ELENCATO E' STATO DIMENSIONALMENTE E/O SUPERFICIALMENTE TRASFORMATO DA TERMINOX SENZA ALTERARNE LE CARATTERISTICHE MECCANICHE E CHIMICHE
 THE MATERIAL DESCRIBED ABOVE HAS BEEN DIMENSIONALLY AND/OR SUPERFICIALLY TRANSFORMED BY TERMINOX WITHOUT CHANGING THE MECHANICAL AND CHEMICAL FEATURES

Analisi di colata/Chemical Composition

Colata/Heat	C %	Si %	Mn %	P %	S %	Cr %	Ni %	Mo %	N %	Ti %	Cu %	Nb %	B %	Al %	Co %
0431359	0.045	0.300	1.290	0.027	0.001	18.000	9.040	0.260	0.024		0.310				
0431741	0.048	0.310	1.420	0.029	0.001	18.090	9.050	0.320	0.019		0.370				

Risultati delle prove/Test Result (1N/mm²=1 MPa)

NIM	P R O D O T T O	S E R V I Z I O N E	Caric. unit. snervamento Yield strenght		Caric. unit. Rottura Tensile strength		Allungamento a rottura Ultimate elongation (%)			Durezza Hardness	Piega a Bend To 180°	Trat. termico Ricott. di solub./ heat treatment of annealing for solubilit.	Resistenza alla corrosione intergranulare secondo / Resistance to corrosion intergranulare	Grano Grain
			Rp0.2% N/mm²	Rp1% N/mm²	Rm N/mm²	Lo =2"	Lo =80	Lo =A5						
			HRB											
310727	T	T	245	271	607				70.5	1050	EN ISO 3651-2			
	C	T	230	261	604			62.8	66.0					
324612	T	T	235	262	688			62.4	70.5	1050	EN ISO 3651-2			
	C	T	237	267	605			62.1	72.0					

I dati chimici e fisici sopra riportati sono tratti dal certificato di qualità del nostro fornitore qualificato il cui originale è in no. possesso e disponibile su richiesta.
 Chemical and physical data reported above are extracted from quality certificate emitted from our qualified supplier; the original document is in our possess and it is available upon your request.

Certificazioni che i prodotti sopra elencati sono conformi alle prescrizioni e standard. We certify that products listed above are compliant to order prescriptions.

(1) Bumping
T = Testa - Top
C = Coda - Bottom

(2) Sema
T = Trasversale - Transverse
L = Longitudinale - Longitudinal

3. ITAL INOX
 HUNGARIA KFT.
 118 Budapest, Laktanya út 42/A.
 Tel: 097-1050, 201-0239 Fax: 250-5067
 Addebi: 12141537-2-43
 BAE SA. 1000000-00000005-0130114

COMPLIES WITH ED 2000/53/EC

Certificato emesso automaticamente

Data/Date 24/05/2012

R. GOVONI

500/24
506320

OUTSIDE STRIPWOUND TURE

CONTITECH RUBBER
 Industrial Kft.
 No:QC-DB- 651 /2013
 Page: 41 / 44



MKEH

Metrológiai Hatóság/Metrology Authority
Mechanikai Mérések Osztály
Section of Mechanical Measurements
BUDAPEST XII., NÉMETVÖLGYI ÚT 37-39.
1535 Budapest, Pf. 919
Telefon: 458-5800
Telefax: 458-5927

Ügyiratszám / File No.:

MKEH-MH/00287-003/2013/NY

Bizonyítványszám / Certificate No.:

NYO - 0008/2013

Hivatkozási szám / Reference No.:

32259470

Page 1/3 oldal

Kiadva / Issued

Budapest, 2013. 01. 28. / 28 01 2013

KALIBRÁLÁSI BIZONYÍTVÁNY
CALIBRATION CERTIFICATE

A kalibrálás tárgya: villamos kimenőjelű nyomásmérő
Object of calibration: electrical-output manometer
Gyártó / Manufacturer: AFRISO-EURO-INDEX GmbH
Típus / Type: DMU03 HD
Azonosító szám / Serial No.: 1518086
Műszaki adatok / Technical data: (0...2500) bar méréstartomány / measuring range (0...2500) bar
(4...20) mA kimenőjel tartomány / output signal range (4...20) mA

Kalibrálásra bemutatta: ContiTech Rubber Industrial Kft.
Customer: 6728 Szeged, Budapesti út 10.

A kalibrálás helye és ideje: Magyar Kereskedelmi Engedélyezési Hivatal
Place and date of calibration: Hungarian Trade Licensing Office
Metrológiai Hatóság, Mechanikai Mérések Osztály
Metrology Authority, Section of Mechanical Measurements
Budapest, 2013.01.24.

A kalibrálást végezte:
Calibrated by: 
Szaulich Dénes
metrológus / metrologist

A kalibrálásnál alkalmazott etalonok:
Standards used for the calibration:

Megnevezés: <i>Designation:</i>	Gyártó: <i>Manufacturer:</i>	Típus: <i>Type:</i>	Gyártási szám: <i>Serial No.:</i>	Bizonyítvány szám: <i>Certificate No.:</i>
túlnyomás etalon / <i>pressure standard</i>	Budenberg	283	20603	NYO-0001/2013
digitális multiméter / <i>digital multimeter</i>	Keithley	2000	0597910	ELD-0014/2012
normál ellenállás / <i>resistance standard</i>	ZIP	P 331	117530	ELD-0021/2012
hőmérő / <i>temperature measuring instr.</i>	GANZ MM	DTH1	33656	Hőm-0296/2012

A mérési eredmények a nemzeti (nemzetközi) etalonra visszavezetettek.
The measuring results are traceable to national standards.

A kalibrálás módja:
Calibration method:

A kalibrálást a KE NYO-3-2002 számú kalibrálás eljárás alapján végeztük.
The calibration was done according to the calibration procedure No.: KE NYO-3-2002.



This certificate is consistent with Calibration and Measurement Capabilities (CMCs) that are included in Appendix C of the Mutual Recognition Arrangement (MRA) drawn up by the International Committee for Weights and Measures (CIPM). Under the MRA, all participating institutes recognize the validity of each other's calibration and measurement certificates for the quantities, ranges and measurement uncertainties specified in Appendix C (for details see <http://www.bipm.org>).

A bizonyítvány az MKEH írásbeli engedélye nélkül csak teljes formájában és terjedelmében másolható!
The calibration certificate shall not be reproduced except in full, without written approval of MKEH!



MKEH
Metrológiai Hatóság/Metrology Authority
Mechanikai Mérések Osztály
Section of Mechanical Measurements

Ügyiratszám / File No.:

MKEH-MH/00287-003/2013/NY

Bizonyítványszám / Certificate No.:

NYO - 0008/2013

Page 2/3 oldal

A kalibrálás körülményei:

Calibration conditions:

környezeti hőmérséklet / Ambient temperature

21,1 °C

a kalibrált eszköz helyzete / Position of the calibrated manometer

függőleges / vertical

a kalibrált eszköz tápfeszültsége / Supply voltage of the calibrated manometer

24V DC

nyomóközeg / Pressure transfer medium

olaj / oil

Mérési eredmények a (0...2500) bar nyomástartományban:

Results of the measurements in the pressure range of (0...2500) bar:

Nyomás, névleges érték <i>Pressure, nominal value</i> bar	Áram-kimenőjel, névleges érték <i>Current-Output, nominal value</i> mA	Áram-kimenőjel, mért eltérés a helyes értéktől <i>Current-Output, measured deviation from the reference value</i> mA	Nyomás, mért eltérés a helyes értéktől <i>Pressure, measured deviation from the reference value</i> bar	Eredő mérési bizonytalanság <i>Expanded uncertainty of the measurement</i> bar
0	4,0	-0,0042	-0,7	2,6
250	5,6	-0,0002	0,0	
500	7,2	0,0029	0,5	
750	8,8	0,0050	0,8	
1000	10,4	0,0063	1,0	
1250	12,0	0,0053	0,8	
1500	13,6	0,0033	0,5	
1750	15,2	-0,0003	-0,1	
2000	16,8	-0,0052	-0,8	
2250	18,4	-0,0117	-1,8	
2500	20,0	-0,0192	-3,0	

Mérési bizonytalanság: A mérési eredmény(ek) mellett közölve.

Uncertainty of measurement: See next to the results of the measurements.

A közölt kiterjesztett mérési bizonytalanság a standard bizonytalanságnak k kiterjesztési tényezővel szorzott értéke ($k = 2$), amely normális (Gauss) eloszlás feltételezésével közelítőleg 95%-os fedési valószínűségnek felel meg.

The reported expanded uncertainty of measurement is stated as the standard uncertainty of measurement multiplied by the coverage factor $k=2$, which for a normal distribution corresponds to coverage probability of approximately 95 %.

A mérési bizonytalanság tartalmazza az etalonból, a kalibrálás módszeréből, a környezeti feltételekből, a kalibrált mérőeszközből stb. eredő részbizonytalanságokat.

It contains the uncertainties of the standards, calibration method, environmental conditions, calibrated device etc.

A standard bizonytalanság meghatározása az EA-4/02 (Expression of the Uncertainty of Measurement in Calibration) kiadványnak megfelelően történt.

The standard uncertainty of measurement has been determined in accordance with the EA Publication EA 4/02 (Expression of the Uncertainty of Measurement in Calibration).

A bizonyítvány az MKEH írásbeli engedélye nélkül csak teljes formájában és terjedelmében másolható!
The calibration certificate shall not be reproduced except in full, without written approval of MKEH!



MKEH
Metrológiai Hatóság/Metrology Authority
Mechanikai Mérések Osztály
Section of Mechanical Measurements

Ügyiratszám / File No.:
MKEH-MH/00287-003/2013/NY
Bizonyítványszám / Certificate No.:
NYO - 0008/2013
Page 3/3 oldal

Bélyegzés:

Calibration mark:

A kalibrált mérőeszközön **K067662** azonosító számú kalibrálási bélyeget helyeztünk el.
We have placed a calibration stamp No.: K067662 on the calibrated instrument.

Megjegyzések:

Additional remarks:

Jelen bizonyítvány összhangban van a Nemzetközi Súly és Mértékügyi Bizottság (CIPM) Kölsönös Elismerési Megegyezése (MRA) C függeléke által tartalmazott kalibrálási és mérési képességekkel (CMCs). Az MRA minden aláíró intézete elismeri egymás kalibrálási és mérési bizonyítványait a C függelék szerinti mennyiségfajtákra, azok értéktartományaival és mérési bizonytalanságaival (közelebbit lásd: <http://www.bipm.org>)

This certificate is consistent with Calibration and Measurement Capabilities (CMCs) that are included in Appendix C of the Mutual Recognition Arrangement (MRA) drawn up by the International Committee for Weights and Measures (CIPM). Under the MRA, all participating institutes recognize the validity of each other's calibration and measurement certificates for the quantities, ranges and measurement uncertainties specified in Appendix C (for details see <http://www.bipm.org>)

A kalibrálási bizonyítványban megadott értékek a mérőeszköznek a kalibrálás idejére és körülményeire jellemző adatai.


The measurement results show the metrological properties of the device during the time of the calibration under the environmental conditions listed above.

Az újrakalibrálás időpontját a felhasználó dönti el a mérőeszköz használatának és állapotának függvényében.

The date of the next calibration is decided by the user. It depends on the usage and the condition of the device.

A bizonyítvány kiadható / Approved by:




Kálóczi László
osztályvezető / Head of Section

Requested Exceptions

- Variance is requested to connect the BOP choke outlet to the choke manifold using a co-flex line (instead of using a 4" OD steel line) with a 10,000 psi working pressure that has been tested to 15,000 psi and is built to API Spec 16C. Once the flex line is installed it will be tied down with safety clamps.
- Variance is requested to allow Option of rig not capable of reaching TD presetting Surface, Drilling Plan will be same using Fresh Water fluid system.
- Variance is requested to wave any centralizer requirements on the 5-1/2" casing. Ameredev will utilize cement expansion additives in the cement slurry to maximize cement bond and zonal isolation.
- Variance is requested to wave any centralizer requirements on the 9-5/8" casing. Ameredev will utilize cement expansion additives in the cement slurry to maximize cement bond and zonal isolation.
- Variance is requested to allow Temporary Postponement of Operations on well to skid to adjacent well if multiple wells on drilling pad are drilled.
- Variance is requested to allow use of Multi-Bowl Well Head System.
- Variance is requested to allow adjustment of Casing Design Safety Factor on conditions that Ameredev keeps minimum of 1/3 casing capacity filled with OMW drilling fluids.
- Variance is requested to allow 5M Annular Preventer on 10M BOPE System to drill Production Interval. (Supporting Documentation Attached)



APD ID: 10400031762

Submission Date: 08/02/2018



Operator Name: AMEREDEV OPERATING LLC

Well Name: JUNIPER FED COM 25 36 34

Well Number: 091H

[Show Final Text](#)

Well Type: OIL WELL

Well Work Type: Drill

Section 1 - Existing Roads

Will existing roads be used? YES

Existing Road Map:

JUNIPER_FED_COM_25_36_34_091H__WELL_PAD_ACCESS_MAP_REV_20190205121212.pdf

Existing Road Purpose: ACCESS

Row(s) Exist? NO

ROW ID(s)

ID:

Do the existing roads need to be improved? NO

Existing Road Improvement Description:

Existing Road Improvement Attachment:

Section 2 - New or Reconstructed Access Roads

Will new roads be needed? YES

New Road Map:

JUNIPER_FED_COM_25_36_34_091H__WELL_PAD_ACCESS_MAP_REV_20190205121341.pdf

Juniper_Pimento_Road_20190205121410.pdf

New road type: RESOURCE

Length: 4442

Feet

Width (ft.): 30

Max slope (%): 2

Max grade (%): 2

Army Corp of Engineers (ACOE) permit required? NO

ACOE Permit Number(s):

New road travel width: 20

New road access erosion control: Crowned and Ditched

New road access plan or profile prepared? NO

New road access plan attachment:

Operator Name: AMEREDEV OPERATING LLC

Well Name: JUNIPER FED COM 25 36 34

Well Number: 091H

Access road engineering design? NO

Access road engineering design attachment:

Access surfacing type: OTHER

Access topsoil source: ONSITE

Access surfacing type description: Caliche

Access onsite topsoil source depth: 6

Offsite topsoil source description:

Onsite topsoil removal process: Grader

Access other construction information: NM One Call (811) will be notified before construction starts.

Access miscellaneous information:

Number of access turnouts:

Access turnout map:

Drainage Control

New road drainage crossing: OTHER

Drainage Control comments: Crowned and Ditched

Road Drainage Control Structures (DCS) description: Crowned and Ditched

Road Drainage Control Structures (DCS) attachment:

Access Additional Attachments

Additional Attachment(s):

Section 3 - Location of Existing Wells

Existing Wells Map? YES

Attach Well map:

JUNIPER_FED_COM_25_36_34_091H__ONE_MI_RAD_EXIST_WELLS_20190205121714.pdf

Existing Wells description:

Section 4 - Location of Existing and/or Proposed Production Facilities

Submit or defer a Proposed Production Facilities plan? SUBMIT

Production Facilities description: A multiple well pad will be located on section 3, and will measure 400'x500'. The top 6" of soil and brush will be stockpiled south of the well pad. A buried 4" poly flowline (750 psi maximum) will be run approximately 570' from the Juniper Fed Com 25 36 34 091H to the Juniper/Pimento CTB north of the well pad. A 20' pipeline ROW containing three buried 12" poly water lines (200 psi maximum) will be run from the Juniper/Pimento CTB to tie into existing water lines at the Firethorn CTB. The overall length of disturbance for the new water lines will be approximately 4,857'. A power line will be run parallel to the water line and will connect into the power line at the Firethorn CTB. The power

Operator Name: AMEREDEV OPERATING LLC

Well Name: JUNIPER FED COM 25 36 34

Well Number: 091H

line will be approximately 4,857'. The Juniper/Pimento CTB will be 500'x525' and will include a separator, heat exchanger, VRU, VRT, meter run and a tank battery. The new production facility will have a secondary containment structure that is constructed to hold the capacity of 1-1/2 times the largest tank, plus freeboard to account for precipitation, unless more stringent protective requirements are deemed necessary.

Production Facilities map:

JUNIPER_FED_COM_25_36_34_091H__FACILITIES_MAP_REV_20190205121751.pdf

BO_JUNIPER_FED_COM_BATTERY_SITE_REV1_20190205121809.pdf

EP_JUN_PIM_1S_FLOWLINE_SEC_3_S_20190205121810.pdf

EP_JUN_PIM_1S_FLOWLINE_SEC_34_S_20190205121810.pdf

Juniper_CTB_Electric_20190205121811.pdf

Juniper_CTB_Water_20190205121813.pdf

Section 5 - Location and Types of Water Supply

Water Source Table

Water source use type: DUST CONTROL,
INTERMEDIATE/PRODUCTION CASING, STIMULATION, SURFACE
CASING

Water source type: GW WELL

Describe type:

Source longitude:

Source latitude:

Source datum:

Water source permit type: PRIVATE CONTRACT

Source land ownership: PRIVATE

Water source transport method: PIPELINE, TRUCKING

Source transportation land ownership: FEDERAL

Water source volume (barrels): 20000

Source volume (acre-feet): 2.577862

Source volume (gal): 840000

Water source and transportation map:

JUNIPER_FED_COM_25_36_34_091H__WATER_WELLS_LIST_20190205121909.pdf

JUNIPER_FED_COM_25_36_34_091H__WATER_WELLS_MAP_REV_20190205121910.pdf

Water source comments: Water will be trucked or surface piped from existing water wells on private land. See attached list of available wells.

New water well? NO

New Water Well Info

Well latitude:

Well Longitude:

Well datum:

Well target aquifer:

Est. depth to top of aquifer(ft):

Est thickness of aquifer:

Aquifer comments:

Aquifer documentation:

Operator Name: AMEREDEV OPERATING LLC

Well Name: JUNIPER FED COM 25 36 34

Well Number: 091H

Well depth (ft):

Well casing type:

Well casing outside diameter (in.):

Well casing inside diameter (in.):

New water well casing?

Used casing source:

Drilling method:

Drill material:

Grout material:

Grout depth:

Casing length (ft.):

Casing top depth (ft.):

Well Production type:

Completion Method:

Water well additional information:

State appropriation permit:

Additional information attachment:

Section 6 - Construction Materials

Construction Materials description: NM One Call (811) will be notified before construction start. Top 6" of soil and brush will be stockpiled south of the pad. V-door will face west. Closed loop drilling system will be used. Caliche will be hauled from an existing caliche pit on private (EOG) land in N2NE4 29-25S-36E or an existing caliche pit on private (Beckham) land in S2SW4 19-25S-36E or a proposed caliche pit on state land in S2SE4 11-26S-36E.

Construction Materials source location attachment:

JUNIPER_FED_COM_25_36_34_091H__CALICHE_MAP_REV_20190205121958.pdf

JUNIPER_FED_COM_25_36_34_091H__WELL_SITE_DIAGRAM_20190205122000.pdf

Section 7 - Methods for Handling Waste

Waste type: DRILLING

Waste content description: Drill cuttings, mud, salts, and other chemicals

Amount of waste: 2000 barrels

Waste disposal frequency : Daily

Safe containment description: Steel tanks

Safe containmant attachment:

Waste disposal type: HAUL TO COMMERCIAL FACILITY **Disposal location ownership:** COMMERCIAL

Disposal type description:

Disposal location description: R360's state approved (NM-01-0006) disposal site at Halfway, NM

Reserve Pit

Reserve Pit being used? NO

Temporary disposal of produced water into reserve pit?

Reserve pit length (ft.)

Reserve pit width (ft.)

Reserve pit depth (ft.)

Reserve pit volume (cu. yd.)

Operator Name: AMEREDEV OPERATING LLC

Well Name: JUNIPER FED COM 25 36 34

Well Number: 091H

Is at least 50% of the reserve pit in cut?

Reserve pit liner

Reserve pit liner specifications and installation description

Cuttings Area

Cuttings Area being used? NO

Are you storing cuttings on location? YES

Description of cuttings location Steel tanks on pad

Cuttings area length (ft.)

Cuttings area width (ft.)

Cuttings area depth (ft.)

Cuttings area volume (cu. yd.)

Is at least 50% of the cuttings area in cut?

WCuttings area liner

Cuttings area liner specifications and installation description

Section 8 - Ancillary Facilities

Are you requesting any Ancillary Facilities?: NO

Ancillary Facilities attachment:

Comments:

Section 9 - Well Site Layout

Well Site Layout Diagram:

JUNIPER_FED_COM_25_36_34_091H__WELL_SITE_DIAGRAM_20190205122118.pdf

Comments:

Section 10 - Plans for Surface Reclamation

Type of disturbance: New Surface Disturbance

Multiple Well Pad Name: JUNIPER

Multiple Well Pad Number: 091H

Recontouring attachment:

JUNIPER_FED_COM_25_36_34_091H__WELL_SITE_DIAGRAM_20190205122134.pdf

Drainage/Erosion control construction: Crowned and ditched

Drainage/Erosion control reclamation: Harrowed on the contour

Operator Name: AMEREDEV OPERATING LLC

Well Name: JUNIPER FED COM 25 36 34

Well Number: 091H

Well pad proposed disturbance (acres): 4.59
Road proposed disturbance (acres): 3.06
Powerline proposed disturbance (acres): 2.23
Pipeline proposed disturbance (acres): 0.39
Other proposed disturbance (acres): 6.03
Total proposed disturbance: 16.3

Well pad interim reclamation (acres): 0.79
Road interim reclamation (acres): 0
Powerline interim reclamation (acres): 0
Pipeline interim reclamation (acres): 0
Other interim reclamation (acres): 0
Total interim reclamation: 0.79

Well pad long term disturbance (acres): 3.8
Road long term disturbance (acres): 3.06
Powerline long term disturbance (acres): 2.23
Pipeline long term disturbance (acres): 0.39
Other long term disturbance (acres): 6.03
Total long term disturbance: 15.51

Disturbance Comments:

Reconstruction method: Interim reclamation will be completed within 6 months of completing the well. Interim reclamation will consist of shrinking the pad 17% (.79 acre) by removing caliche and reclaiming 40' wide swaths on the south and west sides of the pad. This will leave 3.8 acres for producing three wells, with tractor-trailer turn around. Disturbed areas will be contoured to match pre-construction grades. Soil and brush will be evenly spread over disturbed areas and harrowed on the contour. Disturbed areas will be seeded in accordance with the surface owner's requirements.

Topsoil redistribution: Enough stockpiled topsoil will be retained to cover the remainder of the pad when the well is plugged. New road will be similarly reclaimed within 6 months of plugging. Noxious weeds will be controlled.

Soil treatment: None

Existing Vegetation at the well pad:

Existing Vegetation at the well pad attachment:

Existing Vegetation Community at the road:

Existing Vegetation Community at the road attachment:

Existing Vegetation Community at the pipeline:

Existing Vegetation Community at the pipeline attachment:

Existing Vegetation Community at other disturbances:

Existing Vegetation Community at other disturbances attachment:

Non native seed used? NO

Non native seed description:

Seedling transplant description:

Will seedlings be transplanted for this project? NO

Seedling transplant description attachment:

Will seed be harvested for use in site reclamation? NO

Seed harvest description:

Seed harvest description attachment:

Operator Name: AMEREDEV OPERATING LLC

Well Name: JUNIPER FED COM 25 36 34

Well Number: 091H

Seed Management

Seed Table

Seed type:

Seed source:

Seed name:

Source name:

Source address:

Source phone:

Seed cultivar:

Seed use location:

PLS pounds per acre:

Proposed seeding season:

Seed Summary	
Seed Type	Pounds/Acre

Total pounds/Acre:

Seed reclamation attachment:

Operator Contact/Responsible Official Contact Info

First Name:

Last Name:

Phone:

Email:

Seedbed prep:

Seed BMP:

Seed method:

Existing invasive species? NO

Existing invasive species treatment description:

Existing invasive species treatment attachment:

Weed treatment plan description: To BLM standards

Weed treatment plan attachment:

Monitoring plan description: To BLM standards

Monitoring plan attachment:

Success standards: To BLM satisfaction

Pit closure description: No pit

Pit closure attachment:

Operator Name: AMEREDEV OPERATING LLC

Well Name: JUNIPER FED COM 25 36 34

Well Number: 091H

Section 11 - Surface Ownership

Disturbance type: NEW ACCESS ROAD

Describe:

Surface Owner: PRIVATE OWNERSHIP

Other surface owner description:

BIA Local Office:

BOR Local Office:

COE Local Office:

DOD Local Office:

NPS Local Office:

State Local Office:

Military Local Office:

USFWS Local Office:

Other Local Office:

USFS Region:

USFS Forest/Grassland:

USFS Ranger District:

Disturbance type: PIPELINE

Describe:

Surface Owner: PRIVATE OWNERSHIP

Other surface owner description:

BIA Local Office:

BOR Local Office:

COE Local Office:

DOD Local Office:

NPS Local Office:

State Local Office:

Military Local Office:

USFWS Local Office:

Other Local Office:

USFS Region:

Operator Name: AMEREDEV OPERATING LLC

Well Name: JUNIPER FED COM 25 36 34

Well Number: 091H

USFS Forest/Grassland:

USFS Ranger District:

Disturbance type: WELL PAD

Describe:

Surface Owner: PRIVATE OWNERSHIP

Other surface owner description:

BIA Local Office:

BOR Local Office:

COE Local Office:

DOD Local Office:

NPS Local Office:

State Local Office:

Military Local Office:

USFWS Local Office:

Other Local Office:

USFS Region:

USFS Forest/Grassland:

USFS Ranger District:

Disturbance type: OTHER

Describe: Powerline

Surface Owner: PRIVATE OWNERSHIP

Other surface owner description:

BIA Local Office:

BOR Local Office:

COE Local Office:

DOD Local Office:

NPS Local Office:

State Local Office:

Military Local Office:

Operator Name: AMEREDEV OPERATING LLC

Well Name: JUNIPER FED COM 25 36 34

Well Number: 091H

USFWS Local Office:

Other Local Office:

USFS Region:

USFS Forest/Grassland:

USFS Ranger District:

Section 12 - Other Information

Right of Way needed? NO

Use APD as ROW?

ROW Type(s):

ROW Applications

SUPO Additional Information:

Use a previously conducted onsite? YES

Previous Onsite information: On-site inspection was held with Jeff Robertson (BLM) on 11/28/17. Ameredev made a donation with the MOU fund in lieu of an archaeology report.


Other SUPO Attachment

Juniper_Fed_Com_25_36_34_091H__Owner_Agreement_Letter_20180629103011.pdf

JUNIPER_FED_COM_25_36_34_091H__SUPO_REV_20190204_20190205122345.pdf

SECTION 4, TOWNSHIP 26-S, RANGE 36-E, N.M.P.M.
LEA COUNTY, NEW MEXICO

SCALE: 1" = 1000'



P.O.B. LINE A
X=868011.75
Y=394270.01

P.O.E. LINE A
X=873295.98
Y=394322.79

E.O.L. LINE B
X=869937.59
Y=393834.12

B.O.L. LINE B
X=869934.10
Y=394289.10

CARTER BRAXTON
26 36 04 SWD 1

Being a proposed road easement being 30 feet in width, 15 feet left and right of the above platted centerline total line footage containing 6194.49 feet or 375.42 rods, containing 4.27 acres more or less.

AMEREDEV
AMEREDEV OPERATING, LLC

TOPOGRAPHIC
LOYALTY INNOVATION LEGACY
1400 EVERMAN PARKWAY, Ste. 146 • FT. WORTH, TEXAS 76140
TELEPHONE: (817) 744-7512 • FAX (817) 744-7554
2803 NORTH BIG SPRING • MIDLAND, TEXAS 79705
TELEPHONE: (432) 682-1653 OR (800) 787-1653 • FAX (432) 682-1743
WWW.TOPOGRAPHIC.COM

STAN W. LLOYD
NEW MEXICO
19642
PROFESSIONAL SURVEYOR

Stan W. Lloyd
Stan W. Lloyd, P.S. No. 19642
JULY 13, 2018

		REVISION:	
NORTH ROAD EASEMENT	MML	08/10/17	
	MEH	08/15/17	
DATE:	07/20/17	MML	11/03/17
FILE:	EP_NORTH_ROAD_EASEMENT_SEC_4_REV7	ACC	02/19/18
DRAWN BY:	MML	EAH	05/07/18
SHEET:	1 OF 1	BKG	07/13/18

- NOTES:**
1. ORIGINAL DOCUMENT SIZE: 8.5" X 11"
 2. ALL BEARINGS, DISTANCES, AND COORDINATE VALUES CONTAINED HEREIN ARE GRID BASED UPON THE NEW MEXICO COORDINATE SYSTEM OF 1883, EAST ZONE, U.S. SURVEY FEET.
 3. CERTIFICATION IS MADE ONLY TO THE LOCATION OF THIS EASEMENT, IN RELATION TO THE EVIDENCE FOUND DURING A FIELD SURVEY, MADE ON THE GROUND, UNDER MY SUPERVISION, AND USING DOCUMENTATION PROVIDED BY AMEREDEV OPERATING LLC. ONLY UTILITIES/EASEMENTS THAT WERE VISIBLE ON THE DATE OF THIS SURVEY, WITHIN/ADJOINING THIS EASEMENT, HAVE BEEN LOCATED AS SHOWN HEREON OF WHICH I HAVE KNOWLEDGE. THIS CERTIFICATION IS LIMITED TO THOSE PERSONS OR ENTITIES SHOWN ON THE FACE OF THIS PLAT AND IS NON-TRANSFERABLE, AND MADE FOR THIS TRANSACTION ONLY.
 5. B.O.L./P.O.B. = BEGINNING OF LINE/POINT OF BEGINNING
 6. E.O.L./P.O.E. = END OF LINE/POINT OF EXIT


SECTION 34, TOWNSHIP 25-S, RANGE 36-E, N.M.P.M.
LEA COUNTY, NEW MEXICO

SCALE: 1" = 1000'
0' 500' 1000'



LEGEND

- TOWNSHIP LINE
- SECTION LINE
- SURVEYED BASELINE
- TRACT BORDER
- EDGE OF EASEMENT
- EXISTING PIPELINE
- FENCE LINE
- MONUMENT



Being a proposed road easement being 30 feet in width, 15 feet left and right of the above platted centerline total line footage containing 540.00 feet or 32.73 rods, containing 0.37 acres more or less.



Stan W. Lloyd
Stan W. Lloyd, P.S. No. 19642

MAY 09, 2018

AMEREDEV
AMEREDEV OPERATING, LLC


TOPOGRAPHIC
LOYALTY INNOVATION LEGACY
1400 EVERMAN PARKWAY, Ste. 148 • FT. WORTH, TEXAS 76140
TELEPHONE: (817) 744-7512 • FAX: (817) 744-7554
2803 NORTH BIG SPRING • MIDLAND, TEXAS 79705
TELEPHONE: (432) 682-1853 OR (800) 787-1853 • FAX: (432) 682-1743
WWW.TOPOGRAPHIC.COM

REVISION:	
NORTH ROAD EASEMENT	IMU 05/09/2018
DATE:	05/07/18
FILE:	EP_NORTH_ROAD_EASEMENT_SEC_34_REV1
DRAWN BY:	EAH
SHEET:	1 OF 1

- NOTES:**
1. ORIGINAL DOCUMENT SIZE: 8.5" X 11"
 2. ALL BEARINGS, DISTANCES, AND COORDINATE VALUES CONTAINED HEREIN ARE GRID BASED UPON THE NEW MEXICO COORDINATE SYSTEM OF 1983, EAST ZONE, U.S. SURVEY FEET.
 3. CERTIFICATION IS MADE ONLY TO THE LOCATION OF THIS EASEMENT, IN RELATION TO THE EVIDENCE FOUND DURING A FIELD SURVEY, MADE ON THE GROUND, UNDER MY SUPERVISION, AND USING DOCUMENTATION PROVIDED BY AMEREDEV OPERATING LLC. ONLY UTILITIES/EASEMENTS THAT WERE VISIBLE ON THE DATE OF THIS SURVEY, WITHIN/ADJOINING THIS EASEMENT, HAVE BEEN LOCATED AS SHOWN HEREON OF WHICH I HAVE KNOWLEDGE. THIS CERTIFICATION IS LIMITED TO THOSE PERSONS OR ENTITIES SHOWN ON THE FACE OF THIS PLAT AND IS NON-TRANSFERABLE, AND MADE FOR THIS TRANSACTION ONLY.
 5. B.O.L./P.O.B. = BEGINNING OF LINE/POINT OF BEGINNING
 6. E.O.L./P.O.E. = END OF LINE/POINT OF EXIT

SECTION 3, TOWNSHIP 26-S, RANGE 36-E, N.M.P.M.
LEA COUNTY, NEW MEXICO

SCALE: 1" = 1000'
0' 500' 1000'



LEGEND

- BLOCK/TOWNSHIP LINE SURVEY/SECTION LINE
- SURVEYED BASELINE A
- SURVEYED BASELINE B
- EDGE OF EASEMENT
- CONTINUED BASELINE
- TRACT BORDER
- EXISTING PIPELINE
- WATER LINE
- MONUMENT
- POINT OF INTERSECTION

LINE TABLE A

LINE	BEARING	DISTANCE
A2	N 89°26'45" E	15.00'

LINE TABLE B

LINE	BEARING	DISTANCE

PRIVATE OWNERSHIP

NORTH ROAD EASEMENT

Being a proposed road easement being 30 feet in width, 15 feet left and right of the above platted centerline total line footage containing 555.00 feet or 33.64 rods, containing 0.38 acres more or less.

AMEREDEV
AMEREDEV OPERATING, LLC

TOPOGRAPHIC
LOYALTY INNOVATION LEGACY
1400 EVERMAN PARKWAY, Ste. 146 • FT. WORTH, TEXAS 76140
TELEPHONE: (817) 744-7512 • FAX: (817) 744-7548
2903 NORTH BIG SPRING • MIDLAND, TEXAS 79705
TELEPHONE: (432) 682-1653 OR (800) 767-1653 • FAX: (432) 682-1743
WWW.TOPOGRAPHIC.COM


STAN W. LLOYD
NEW MEXICO
19642
PROFESSORIAL SURVEYOR
Stan W. Lloyd
Stan W. Lloyd, P.S. No. 19642
JULY 12, 2018

NORTH ROAD EASEMENT	REVISION:	
	IMU	05/09/2018
	AMD	07/12/2018
DATE:	04/03/18	
FILE:	EP_NORTH_ROAD_EASEMENT_SEC_3_REV2	
DRAWN BY:	GJU	
SHEET:	1 OF 1	

- NOTES:**
1. ORIGINAL DOCUMENT SIZE: 8.5" X 11"
 2. ALL BEARINGS, DISTANCES, AND COORDINATE VALUES CONTAINED HEREIN ARE GRID BASED UPON THE NEW MEXICO COORDINATE SYSTEM OF 1983, EAST ZONE, U.S. SURVEY FEET.
 3. CERTIFICATION IS MADE ONLY TO THE LOCATION OF THIS EASEMENT, IN RELATION TO THE EVIDENCE FOUND DURING A FIELD SURVEY, MADE ON THE GROUND, UNDER MY SUPERVISION, AND USING DOCUMENTATION PROVIDED BY AMEREDEV OPERATING LLC. ONLY UTILITIES/EASEMENTS THAT WERE VISIBLE ON THE DATE OF THIS SURVEY, WITHIN/ADJOINING THIS EASEMENT, HAVE BEEN LOCATED AS SHOWN HEREON OF WHICH I HAVE KNOWLEDGE. THIS CERTIFICATION IS LIMITED TO THOSE PERSONS OR ENTITIES SHOWN ON THE FACE OF THIS PLAT AND IS NON-TRANSFERABLE, AND MADE FOR THIS TRANSACTION ONLY.
 4. P.O.B. = POINT OF BEGINNING
 5. E.O.L. = END OF LINE

SECTION 3, TOWNSHIP 26-S, RANGE 36-E, N.M.P.M.
LEA COUNTY, NEW MEXICO

SCALE: 1" = 1000'
0' 500' 1000'



LEGEND

- BLOCK/TOWNSHIP LINE
- SURVEY/SECTION LINE
- SURVEYED BASELINE
- EDGE OF EASEMENT
- CONTINUED BASELINE
- TRACT BORDER
- EXISTING PIPELINE
- WATER LINE
- MONUMENT

LINE TABLE

LINE	BEARING	DISTANCE

PRIVATE OWNERSHIP

**JUN/PIM #1S
FLOWLINE EASEMENT**

Being a proposed road easement being 30 feet in width, 15 feet left and right of the above plated centerline total line footage containing 30.00 feet or 1.82 rods, containing 0.02 acres more or less.

AMEREDEV
AMEREDEV OPERATING, LLC

TOPOGRAPHIC
LOYALTY INNOVATION LEGACY
1400 EVERMAN PARKWAY, Ste. 148 • FT. WORTH, TEXAS 76140
TELEPHONE: (817) 744-7512 • FAX (817) 744-7548
2903 NORTH BIG SPRING • MIDLAND, TEXAS 79705
TELEPHONE: (432) 682-1653 OR (800) 767-1653 • FAX (432) 682-1743
WWW.TOPOGRAPHIC.COM

MICHAEL B. BROWN
NEW MEXICO
18329
PROFESSIONAL SURVEYOR


Michael Blake Brown, R.P.L.S. No 18329
JANUARY 2, 2019

JUN/PIM #1S FLOWLINE EASEMENT	REVISION:	
	INT	DATE
DATE: 01/02/19		
FILE: EP_JUN_PIM_1S_FLOWLINE_SEC_3		
DRAWN BY: ACC		
SHEET: 1 OF 1		

- NOTES:**
1. ORIGINAL DOCUMENT SIZE: 8.5" X 11"
 2. ALL BEARINGS, DISTANCES, AND COORDINATE VALUES CONTAINED HEREIN ARE GRID BASED UPON THE NEW MEXICO COORDINATE SYSTEM OF 1983, EAST ZONE, U.S. SURVEY FEET.
 3. CERTIFICATION IS MADE ONLY TO THE LOCATION OF THIS EASEMENT, IN RELATION TO THE EVIDENCE FOUND DURING A FIELD SURVEY, MADE ON THE GROUND, UNDER MY SUPERVISION, AND USING DOCUMENTATION PROVIDED BY AMEREDEV OPERATING LLC. ONLY UTILITIES/EASEMENTS THAT WERE VISIBLE ON THE DATE OF THIS SURVEY, WITHIN/ADJOINING THIS EASEMENT, HAVE BEEN LOCATED AS SHOWN HEREON OF WHICH I HAVE KNOWLEDGE. THIS CERTIFICATION IS LIMITED TO THOSE PERSONS OR ENTITIES SHOWN ON THE FACE OF THIS PLAT AND IS NON-TRANSFERABLE, AND MADE FOR THIS TRANSACTION ONLY.
 4. P.O.B. = POINT OF BEGINNING
 5. E.O.L. = END OF LINE

SECTION 34, TOWNSHIP 25-S, RANGE 36-E, N.M.P.M.
LEA COUNTY, NEW MEXICO

SCALE: 1" = 1000'
0' 500' 1000'



LEGEND


- TOWNSHIP LINE
- SECTION LINE
- SURVEYED BASELINE
- TRACT BORDER
- EDGE OF EASEMENT
- EXISTING PIPELINE
- FENCE LINE
- MONUMENT

LINE TABLE

LINE	BEARING	DISTANCE
1		
2		
3		

**JUN/PIM #1S
FLOWLINE EASEMENT**

Being a proposed road easement being 30 feet in width, 15 feet left and right of the above platted centerline total line footage containing 540.00 feet or 32.73 rods, containing 0.37 acres more or less.



Michael Blake Brown, R.P.L.S. No 18329
JANUARY 2, 2019




TOPOGRAPHIC
LOYALTY INNOVATION LEGACY
1400 EVERMAN PARKWAY, Ste. 146 - FT. WORTH, TEXAS 76140
TELEPHONE: (817) 744-7512 - FAX (817) 744-7554
2803 NORTH BIG SPRING • MIDLAND, TEXAS 79705
TELEPHONE: (432) 682-1853 OR (800) 787-1853 - FAX (432) 682-1743
WWW.TOPOGRAPHIC.COM

JUN/PIM #1S FLOWLINE EASEMENT	REVISION:	
	INT	DATE
DATE: 01/02/19		
FILE: EP_JUN_PIM_1S_FLOWLINE_SEC_34		
DRAWN BY: ACC		
SHEET: 1 OF 1		

- NOTES:**
1. ORIGINAL DOCUMENT SIZE: 8.5" X 11"
 2. ALL BEARINGS, DISTANCES, AND COORDINATE VALUES CONTAINED HEREIN ARE GRID BASED UPON THE NEW MEXICO COORDINATE SYSTEM OF 1983, EAST ZONE, U.S. SURVEY FEET.
 3. CERTIFICATION IS MADE ONLY TO THE LOCATION OF THIS EASEMENT, IN RELATION TO THE EVIDENCE FOUND DURING A FIELD SURVEY, MADE ON THE GROUND, UNDER MY SUPERVISION, AND USING DOCUMENTATION PROVIDED BY AMEREDEV OPERATING LLC. ONLY UTILITIES/EASEMENTS THAT WERE VISIBLE ON THE DATE OF THIS SURVEY, WITHIN/ADJOINING THIS EASEMENT, HAVE BEEN LOCATED AS SHOWN HEREON OF WHICH I HAVE KNOWLEDGE. THIS CERTIFICATION IS LIMITED TO THOSE PERSONS OR ENTITIES SHOWN ON THE FACE OF THIS PLAT AND IS NON-TRANSFERABLE, AND MADE FOR THIS TRANSACTION ONLY.
 5. B.O.L./P.O.B. = BEGINNING OF LINE/POINT OF BEGINNING
 6. E.O.L./P.O.E. = END OF LINE/POINT OF EXIT

SECTION 4, TOWNSHIP 26-S, RANGE 36-E, N.M.P.M.
LEA COUNTY, NEW MEXICO

SCALE: 1" = 1000'
0' 500' 1000'




P.O.E.
X=868021.60
Y=393285.03

LEGEND

- TOWNSHIP LINE
- SECTION LINE
- SURVEYED BASELINE A
- SURVEYED BASELINE B
- CONTINUED BASELINE
- TRACT BORDER
- EDGE OF EASEMENT
- EXISTING PIPELINE
- FENCE LINE
- OHE OVERHEAD ELECTRIC
- W WATER LINE
- ROAD WAY
- POINT OF INTERSECTION
- MONUMENT
- IRON ROD FOUND

LINE TABLE

LINE	BEARING	DISTANCE
4	S 89°26'51" W	4806.28'
5	S 89°26'22" W	460.00'



DETAIL VIEW
SCALE: 1" = 30'

PRIVATE OWNERSHIP

NORTH ELECTRIC LINE

Being a proposed electric line easement being 20 feet in width, 10 feet left and right of the above platted centerline total line footage containing 2968.28 feet or 179.77 rods, containing 1.36 acres more or less.

AMEREDEV
AMEREDEV OPERATING, LLC

TOPOGRAPHIC
LOYALTY INNOVATION LEGACY
1400 EVERMAN PARKWAY, Ste. 148 - FT. WORTH, TEXAS 76140
TELEPHONE: (817) 744-7512 - FAX (817) 744-7554
2803 NORTH BIG SPRING - MIDLAND, TEXAS 79705
TELEPHONE: (432) 682-1653 OR (800) 787-1653 - FAX (432) 682-1743
WWW.TOPOGRAPHIC.COM


STAN W. LLOYD
NEW MEXICO
19642
PROFESSIONAL SURVEYOR
Stan W. Lloyd
Stan W. Lloyd, P.S. No. 19642
MAY 7, 2018

NORTH ELECTRIC LINE		REVISION:	
		MML	07/28/17
		MML	09/11/17
DATE:	07/20/17	AMD	11/03/17
FILE:	EP_NORTH_ELECTRIC_SEC_4_REVS	GJU	11/10/17
DRAWN BY:	MML	EAH	05/07/18
SHEET:	1 OF 1		

- NOTES:
1. ORIGINAL DOCUMENT SIZE: 8.5" X 11"
 2. ALL BEARINGS, DISTANCES, AND COORDINATE VALUES CONTAINED HEREIN ARE GRID BASED UPON THE NEW MEXICO COORDINATE SYSTEM OF 1883, EAST ZONE, U.S. SURVEY FEET.
 3. CERTIFICATION IS MADE ONLY TO THE LOCATION OF THIS EASEMENT, IN RELATION TO THE EVIDENCE FOUND DURING A FIELD SURVEY, MADE ON THE GROUND, UNDER MY SUPERVISION, AND USING DOCUMENTATION PROVIDED BY AMEREDEV OPERATING LLC. ONLY UTILITIES/EASEMENTS THAT WERE VISIBLE ON THE DATE OF THIS SURVEY, WITHIN/ADJOINING THIS EASEMENT, HAVE BEEN LOCATED AS SHOWN HEREON OF WHICH I HAVE KNOWLEDGE. THIS CERTIFICATION IS LIMITED TO THOSE PERSONS OR ENTITIES SHOWN ON THE FACE OF THIS PLAT AND IS NON-TRANSFERABLE, AND MADE FOR THIS TRANSACTION ONLY.
 5. B.O.L./P.O.B. = BEGINNING OF LINE/POINT OF BEGINNING
 6. E.O.L./P.O.E. = END OF LINE/POINT OF EXIT

SECTION 34, TOWNSHIP 25-S, RANGE 36-E, N.M.P.M.
LEA COUNTY, NEW MEXICO

SCALE: 1" = 1000'
0' 500' 1000'



Being a proposed electric line easement being 20 feet in width, 10 feet left and right of the above platted centerline total line footage containing 830.00 feet or 50.30 rods, containing 0.38 acres more or less.



TOPOGRAPHIC
LOYALTY INNOVATION LEGACY

1400 EVERMAN PARKWAY, Ste. 148 • FT. WORTH, TEXAS 78140
TELEPHONE: (817) 744-7512 • FAX (817) 744-7554
2903 NORTH BIG SPRING • MIDLAND, TEXAS 79705
TELEPHONE: (432) 682-1653 OR (800) 767-1853 • FAX (432) 682-1743
WWW.TOPOGRAPHIC.COM

STAN W. LLOYD
NEW MEXICO
19642
PROFESSIONAL SURVEYOR

Stan W. Lloyd


Stan W. Lloyd, P.S. No. 19642
MAY 7, 2018

NORTH ELECTRIC LINE	REVISION:	
	INT	DATE
DATE: 05/07/18		
FILE: EP_NORTH_ELECTRIC_SEC_34		
DRAWN BY: EAH		
SHEET: 1 OF 1		

- NOTES:**
1. ORIGINAL DOCUMENT SIZE: 8.5" X 11"
 2. ALL BEARINGS, DISTANCES, AND COORDINATE VALUES CONTAINED HEREIN ARE GRID BASED UPON THE NEW MEXICO COORDINATE SYSTEM OF 1983, EAST ZONE, U.S. SURVEY FEET.
 3. CERTIFICATION IS MADE ONLY TO THE LOCATION OF THIS EASEMENT, IN RELATION TO THE EVIDENCE FOUND DURING A FIELD SURVEY, MADE ON THE GROUND, UNDER MY SUPERVISION, AND USING DOCUMENTATION PROVIDED BY AMEREDEV OPERATING LLC. ONLY UTILITIES/EASEMENTS THAT WERE VISIBLE ON THE DATE OF THIS SURVEY, WITHIN/ADJOINING THIS EASEMENT, HAVE BEEN LOCATED AS SHOWN HEREON OF WHICH I HAVE KNOWLEDGE. THIS CERTIFICATION IS LIMITED TO THOSE PERSONS OR ENTITIES SHOWN ON THE FACE OF THIS PLAT AND IS NON-TRANSFERABLE, AND MADE FOR THIS TRANSACTION ONLY.
 5. B.O.L./P.O.B. = BEGINNING OF LINE/POINT OF BEGINNING
 6. E.O.L./P.O.E. = END OF LINE/POINT OF EXIT

SECTION 4, TOWNSHIP 26-S, RANGE 36-E, N.M.P.M.
LEA COUNTY, NEW MEXICO

SCALE: 1" = 1000'
0 500' 1000'




P.O.E.
X=868021.40
Y=393305.05

LEGEND

- TOWNSHIP LINE
- SECTION LINE
- SURVEYED BASELINE A
- SURVEYED BASELINE B
- CONTINUED BASELINE
- TRACT BORDER
- EDGE OF EASEMENT
- EXISTING PIPELINE
- x- FENCE LINE
- o- OVERHEAD ELECTRIC
- w- WATER LINE
- == ROAD WAY
- POINT OF INTERSECTION
- MONUMENT
- IRON ROD FOUND

LINE TABLE

LINE	BEARING	DISTANCE
4	S 89°26'54" W	4766.28'
6	S 89°26'54" W	480.00'



DETAIL VIEW
SCALE: 1" = 30'

PRIVATE OWNERSHIP

NORTH WATER LINE

Being a proposed water line easement being 20 feet in width, 10 feet left and right of the above platted centerline total line footage containing 2926.28 feet or 177.35 rods, containing 1.34 acres more or less.

AMEREDEV
AMEREDEV OPERATING, LLC

TOPOGRAPHIC
LOYALTY INNOVATION LEGACY
1400 EVERMAN PARKWAY, Ste. 148 • FT. WORTH, TEXAS 78140
TELEPHONE: (817) 744-7512 • FAX (817) 744-7554
2803 NORTH BIG SPRING • MIDLAND, TEXAS 79705
TELEPHONE: (432) 682-1853 OR (800) 787-1853 • FAX (432) 682-1743
WWW.TOPOGRAPHIC.COM

STAN W. LLOYD
NEW MEXICO
19642
PROFESSIONAL SURVEYOR
Stan W. Lloyd
Stan W. Lloyd, P.S. No. 19642
MAY 7, 2018

NORTH WATER LINE		REVISION:	
DATE:	07/20/17	MML	07/28/17
FILE:	EP_NORTH_WATER_SEC_4_REV5	MML	09/11/17
DRAWN BY:	MML	AMD	11/04/17
SHEET:	1 OF 1	GJU	11/10/17
		EAH	05/07/18

- NOTES:
1. ORIGINAL DOCUMENT SIZE: 8.5" X 11"
 2. ALL BEARINGS, DISTANCES, AND COORDINATE VALUES CONTAINED HEREIN ARE GRID BASED UPON THE NEW MEXICO COORDINATE SYSTEM OF 1983, EAST ZONE, U.S. SURVEY FEET.
 3. CERTIFICATION IS MADE ONLY TO THE LOCATION OF THIS EASEMENT, IN RELATION TO THE EVIDENCE FOUND DURING A FIELD SURVEY, MADE ON THE GROUND, UNDER MY SUPERVISION, AND USING DOCUMENTATION PROVIDED BY AMEREDEV OPERATING LLC. ONLY UTILITIES/EASEMENTS THAT WERE VISIBLE ON THE DATE OF THIS SURVEY, WITHIN/ADJOINING THIS EASEMENT, HAVE BEEN LOCATED AS SHOWN HEREON OF WHICH I HAVE KNOWLEDGE. THIS CERTIFICATION IS LIMITED TO THOSE PERSONS OR ENTITIES SHOWN ON THE FACE OF THIS PLAT AND IS NON-TRANSFERABLE, AND MADE FOR THIS TRANSACTION ONLY.
 5. B.O.L./P.O.B. = BEGINNING OF LINE/POINT OF BEGINNING
 6. E.O.L./P.O.E. = END OF LINE/POINT OF EXIT


SECTION 33, TOWNSHIP 25-S, RANGE 36-E, N.M.P.M.
LEA COUNTY, NEW MEXICO

SCALE: 1" = 1000'
0 500' 1000'




LEGEND

- TOWNSHIP LINE
- SECTION LINE
- SURVEYED BASELINE
- CONTINUED BASELINE
- TRACT BORDER
- EDGE OF EASEMENT
- EXISTING PIPELINE
- FENCE LINE
- ROAD WAY
- POINT OF INTERSECTION
- MONUMENT
- IRON ROD FOUND



LINE TABLE

LINE	BEARING	DISTANCE



Being a proposed water line easement being 20 feet in width, 10 feet left and right of the above platted centerline total line footage containing 3766.78 feet or 228.29 rods, containing 1.73 acres more or less.

AMEREDEV
AMEREDEV OPERATING, LLC

TOPOGRAPHIC
LOYALTY INNOVATION LEGACY
1400 EVERMAN PARKWAY, Ste. 146 • FT. WORTH, TEXAS 76140
TELEPHONE: (817) 744-7512 • FAX (817) 744-7554
2803 NORTH BIG SPRING • MIDLAND, TEXAS 79705
TELEPHONE: (432) 682-1653 OR (800) 787-1653 • FAX (432) 682-1743
WWW.TOPOGRAPHIC.COM


STAN W. LLOYD
NEW MEXICO
19642
PROFESSORIAL SURVEYOR
Stan W. Lloyd
Stan W. Lloyd, P.S. No. 19642
MAY 7, 2018

NORTH WATER LINE	REVISION:	
	INT	DATE
DATE: 05/07/18		
FILE:EP_NORTH_WATER_SEC_33		
DRAWN BY: EAH		
SHEET: 1 OF 1		

- NOTES:
1. ORIGINAL DOCUMENT SIZE: 8.5" X 11"
 2. ALL BEARINGS, DISTANCES, AND COORDINATE VALUES CONTAINED HEREIN ARE GRID BASED UPON THE NEW MEXICO COORDINATE SYSTEM OF 1983, EAST ZONE, U.S. SURVEY FEET.
 3. CERTIFICATION IS MADE ONLY TO THE LOCATION OF THIS EASEMENT, IN RELATION TO THE EVIDENCE FOUND DURING A FIELD SURVEY, MADE ON THE GROUND, UNDER MY SUPERVISION, AND USING DOCUMENTATION PROVIDED BY AMEREDEV OPERATING LLC. ONLY UTILITIES/EASEMENTS THAT WERE VISIBLE ON THE DATE OF THIS SURVEY, WITHIN/ADJOINING THIS EASEMENT, HAVE BEEN LOCATED AS SHOWN HEREON OF WHICH I HAVE KNOWLEDGE. THIS CERTIFICATION IS LIMITED TO THOSE PERSONS OR ENTITIES SHOWN ON THE FACE OF THIS PLAT AND IS NON-TRANSFERABLE, AND MADE FOR THIS TRANSACTION ONLY.
 5. B.O.L./P.O.B. = BEGINNING OF LINE/POINT OF BEGINNING
 6. E.O.L./P.O.E. = END OF LINE/POINT OF EXIT

SECTION 34, TOWNSHIP 25-S, RANGE 36-E, N.M.P.M.
LEA COUNTY, NEW MEXICO

SCALE: 1" = 1000'
0' 500' 1000'



Being a proposed water line easement being 20 feet in width, 10 feet left and right of the above platted centerline total line footage containing 770.00 feet or 46.67 rods, containing 0.35 acres more or less.

AMEREDEV
AMEREDEV OPERATING, LLC

TOPOGRAPHIC
LOYALTY INNOVATION LEGACY
1400 EVERMAN PARKWAY, Ste. 148 • FT. WORTH, TEXAS 76140
TELEPHONE: (817) 744-7512 • FAX (817) 744-7554
2903 NORTH BIG SPRING • MIDLAND, TEXAS 79705
TELEPHONE: (432) 682-1653 OR (800) 767-1653 • FAX (432) 682-1743
WWW.TOPOGRAPHIC.COM

STAN W. LLOYD
NEW MEXICO
19642
PROFESSIONAL SURVEYOR
Stan W. Lloyd
Stan W. Lloyd, P.S. No. 19642
MAY 7, 2018

NORTH WATER LINE	REVISION:	
	INT	DATE
DATE: 05/07/18		
FILE: EP_NORTH_WATER_SEC_34		
DRAWN BY: EAH		
SHEET: 1 OF 1		

NOTES:

- ORIGINAL DOCUMENT SIZE: 8.5" X 11"
- ALL BEARINGS, DISTANCES, AND COORDINATE VALUES CONTAINED HEREIN ARE GRID BASED UPON THE NEW MEXICO COORDINATE SYSTEM OF 1983, EAST ZONE, U.S. SURVEY FEET.
- CERTIFICATION IS MADE ONLY TO THE LOCATION OF THIS EASEMENT, IN RELATION TO THE EVIDENCE FOUND DURING A FIELD SURVEY, MADE ON THE GROUND, UNDER MY SUPERVISION, AND USING DOCUMENTATION PROVIDED BY AMEREDEV OPERATING LLC. ONLY UTILITIES/EASEMENTS THAT WERE VISIBLE ON THE DATE OF THIS SURVEY, WITHIN/ADJOINING THIS EASEMENT, HAVE BEEN LOCATED AS SHOWN HEREON OF WHICH I HAVE KNOWLEDGE. THIS CERTIFICATION IS LIMITED TO THOSE PERSONS OR ENTITIES SHOWN ON THE FACE OF THIS PLAT AND IS NON-TRANSFERABLE, AND MADE FOR THIS TRANSACTION ONLY.
- B.O.L./P.O.B. = BEGINNING OF LINE/POINT OF BEGINNING
- E.O.L./P.O.E. = END OF LINE/POINT OF EXIT

Ameredeve Operating, LLC
Juniper Fed Com 25 36 34 091H
Section 34, Township 25S, Range 36E
Lea County, New Mexico



<u>PERMIT #</u>	<u>WELL NAME</u>	<u>LOCATION (LAT/LON)</u>
CP 1049 POD 2	Bennett	32°04'14.32" N, 103°12'32.30" W
CP 1378	S. Eppenour	32°05'40.62" N, 103°13' 35.26" W
CP 1285	Sec. 5	32°03'56.50" N, 103°17'37.04" W
CP 857	Capped	32°04'39.70" N, 103°16'51.13" W
C 2287	#1	32°03'59.0" N, 103°33'16.8" W
C 2286	#2	32°03'59.2" N, 103°33'15.2" W
C 2290	#3	32°04'1.0" N, 103°33' 12.6" W
C 2285	#4	32°04'3.7" N, 103°33'9.7" W
C 2288	#5	32°04'0.5" N, 103°33'8.4" W
C 2294	Garden	32°03'3.2" N, 103°32'38.1" W
C 2293	House	32°03'2.3" N, 103°32'36.8" W
J-11-S-3	Farm Well #2	32°03'08.4" N, 103°16'35.2" W
J-11-S-2	Farm Well #3	32°03'11.5" N, 103°17'02.0" W
J-11-S	Farm Well #4	32°03'24.6" N, 103°17'02.1" W
CP 1170 POD 1	CB 1	32°03'57.2" N, 103°18'45.3" W
CP 1170 POD 5		32°07'17.1" N, 103°17'48.0" W
CP 1263 POD 5	CB 2	32°03'56.27" N, 103°18'27.4" W
CP 1263 POD 3	CB 3	32°03'54.90" N, 103°18'16.74" W
CP 1351 POD 1	CB 4	32°03'57.16" N, 103°17'45.13" W
CP 1351 POD 2	CB 5	32°03'30.70" N, 103°17'45.70" W
J 26	Ryan	32°01'20.41" N, 103°15'49.46" W
J 3		32°02'41.5" N, 103°18'55.8" W

Exhibit 4 – Water Wells



Surface Use Plan of Operations

Introduction

The following Surface Use Plan of Operations will be implemented by Ameredev Operating, LLC (Ameredev), after APD approval. No disturbance will be created other than those described in this surface use plan. If any additional surface disturbance becomes necessary after APD approval, the appropriate BLM approved sundry notice or right of way application will be acquired prior to such disturbance. This Surface Use Plan includes Ameredev's well pad, battery site, electrical, water and flow lines, and access roads.

Before any surface disturbance is created, stakes or flagging will be installed to mark boundaries of permitted areas of disturbance, including soil storage areas. As necessary, slope, grade, and other construction control stakes will be placed to ensure construction is in accordance with the surface use plan. All boundary markers will be maintained in place until final construction cleanup is completed. If disturbance boundary markers are displaced, they will be replaced before construction proceeds. Adjacent operators will be contacted before construction starts to mark adjacent pipelines.

Directions to proposed pad:

At the intersection of 3rd St/NM-205/Frying Pan Rd & NM-128, head south on 3rd St/NM-205/Frying Pan Road approximately 5.6 miles. Turn right on Anthony Road and proceed west approximately 3.4 miles. Continue North (right) on Anthony Road and proceed north approximately 0.3 miles. Turn right on Pipeline Road and proceed east approximately 0.3 miles. Turn left on lease road and proceed north approximately 1 mile. Turn right on unnamed lease road and proceed east for approximately 1.1 miles to the north side of the location.

See *Exhibit 1 – Well Pad Access* for a map of the route.





Exhibit 1 – Well Pad Access

Section 1 – Existing Roads

- A. The existing access road route to the proposed project is depicted on *Exhibit 1 – Well Pad Access*. Improvements to the driving surface will be done where necessary. No new surface disturbance will be done, unless otherwise noted in the New or Reconstructed Access Roads section of this surface use plan.
- B. Right-Of-Way will be acquired before construction begins.
- C. The operator will improve or maintain existing roads in a condition the same as or better than before operations begin. The operator will repair pot holes, clear ditches, repair the crown, etc. All existing structures on the entire access route such as cattle guards, other range improvement projects, culverts, etc. will be properly repaired or replaced if they are damaged or have deteriorated beyond practical use.
- D. Operator will prevent and abate fugitive dust as needed, whether created by vehicular traffic, equipment operations, or wind events. BLM written approval will be acquired before application of surfactants, binding agents, or other dust suppression chemicals on roadways.

Section 2 – New or Reconstructed Access Roads

- A. A section of new access road will be needed for this proposed project. See *Exhibit 1 – Well Pad Access*, for locations.
- B. The length of new access road needed to be constructed for this proposed project is approximately 4,442 feet.
- C. New access road will be constructed with 6 inches of compacted caliche.
- D. The maximum driving width of the access road will be 20 feet. The maximum width of surface disturbance when constructing the access road will not exceed 30 feet. All areas outside of the driving surface will be revegetated.
- E. When the road travels on fairly level ground, the road will be crowned and ditched with a maximum 2% slope from the tip of the road crown to the edge of the driving surface. Ditches will be constructed on each side of the road. The ditches will be 3 feet wide with 3:1 slopes. See road cross section diagram below:



- F. No turnouts will be constructed on the new portions of access road.
- G. No cattle guards will be installed on the new portions of access road.
- H. Right-Of-Way will be acquired before construction begins.
- I. No culverts or low water crossings will be constructed for the new portions of access road.
- J. Since the access road is on level ground, no lead-off ditches will be constructed for the new portions of access road.
- K. Any sharp turns in the in the new road will be rounded to facilitate turning by trucks.



- L. Newly constructed or reconstructed roads, on surface under the jurisdiction of the Bureau of Land Management, will be constructed as outlined in the BLM "Gold Book" and to meet the standards of the anticipated traffic flow and all anticipated weather requirements as needed. Construction will include ditching, draining, crowning and capping or sloping and dipping the roadbed as necessary to provide a well-constructed and safe road.
- M. All topsoil and fragmented rock removed in excavation will be used as directed in approved plan.

Section 3 – Location of Existing Wells

Exhibit 2 – One Mile Radius Existing Wells depicts all known wells within a one mile radius of the Juniper Fed Com 25 36 34 091H. See *Exhibit 2a – One Mile Radius Wells List* for a list of wells depicted.




Exhibit 2 – One Mile Radius Existing Wells

API	WELL NAME	STATUS	TD
30025208430000	SOUTHWEST JALIT-FED 1	PLUGGED	13505

Exhibit 2a – One Mile Radius Existing Wells List

Section 4 - Location of Existing and/or Proposed Production Facilities

- A. The multiple well pad will be located on Section 3, and will measure 400'x500'. Should any type of production facilities be located on the well pad, they will be strategically placed to allow for maximum interim reclamation, re-contouring, and revegetation of the well location.
- B. Production from the proposed well will be transported to a new production facility named Juniper/Pimento CTB, north of the well pad.
- C. A buried 4" poly flowline (750 psi maximum) will be run approximately 570' from the Juniper Fed Com 25 36 34 091H to the Juniper/Pimento CTB north of the well pad. A 20' pipeline ROW containing three buried 12" poly water lines (200 psi maximum) will be run from the Juniper/Pimento CTB to tie into existing water lines at the Firethorn CTB. The overall length of disturbance for the new water lines will be approximately 4,857'. A power line will be run parallel to the water line and will connect into the power line at the Firethorn CTB. The power line will be approximately 4,857'. The Juniper/Pimento CTB will be 500'x525' and will include a separator, heat exchanger, VRU, VRT, meter run and a tank battery. The new production facility will have a secondary containment structure that is constructed to hold the capacity of 1-1/2 times the largest tank, plus freeboard to account for precipitation, unless more stringent protective requirements are deemed necessary.
- D. All permanent (lasting more than six months) above ground structures including but not limited to pump jacks, storage tanks, barrels, pipeline risers, meter housing, etc., that are not subject to safety requirements will be painted a non-reflective paint color, Shale Green, from the BLM Standard Environmental Colors chart, unless another color is required in the APD Conditions of Approval.
- E. If any plans change regarding the production facility or other infrastructure (pipeline, electrical lines, etc.), Ameredev will submit a sundry notice or right-of-way (if applicable) prior to installation or construction.




Exhibit 3 – Well Site Diagram

Section 5 - Location and Types of Water Supply

- A. This location will be drilled using a combination of water and mud systems (outlined in the Drilling Program). The water will be obtained from preexisting water wells, by running a pump directly to the drilling rig. See *Exhibit 4 - Water Wells*, for a list of available water wells. In cases where a polyline is used to transport water for drilling or completion purposes, the existing and proposed roads into location will be utilized.

Ameredev Operating, LLC
 Juniper Fed Com 25 36 34 091H
 Section 34, Township 25S, Range 36E
 Lea County, New Mexico



<u>Permit #</u>	<u>Well Name</u>	<u>Location (Lat/Lon)</u>
CP 1049 POD 2	Bennett	32°04'14.32" N, 103°12'32.30" W
CP 1378	S. Eppenour	32°05'40.62" N, 103°13' 35.26" W
CP 1285	Sec. 5	32°03'56.50" N, 103°17'37.04" W
CP 857	Capped	32°04'39.70" N, 103°16'51.13" W
C 2287	#1	32°03'59.0" N, 103°33'16.8" W
C 2286	#2	32°03'59.2" N, 103°33'15.2" W
C 2290	#3	32°04'1.0" N, 103°33' 12.6" W
C 2285	#4	32°04'3.7" N, 103°33'9.7" W
C 2288	#5	32°04'0.5" N, 103°33'8.4" W
C 2294	Garden	32°03'3.2" N, 103°32'38.1" W
C 2293	House	32°03'2.3" N, 103°32'36.8" W
J-11-S-3	Farm Well #2	32°03'08.4" N, 103°16'35.2" W
J-11-S-2	Farm Well #3	32°03'11.5" N, 103°17'02.0" W
J-11-S	Farm Well #4	32°03'24.6" N, 103°17'02.1" W
CP 1170 POD 1	CB 1	32°03'57.2" N, 103°18'45.3" W
CP 1170 POD 5		32°07'17.1" N, 103°17'48.0" W
CP 1263 POD 5	CB 2	32°03'56.27" N, 103°18'27.4" W
CP 1263 POD 3	CB 3	32°03'54.90" N, 103°18'16.74" W
CP 1351 POD 1	CB 4	32°03'57.16" N, 103°17'45.13" W
CP 1351 POD 2	CB 5	32°03'30.70" N, 103°17'45.70" W
J 26	Ryan	32°01'20.41" N, 103°15'49.46" W
J 3		32°02'41.5" N, 103°18'55.8" W

Exhibit 4 – Water Wells



Section 6 – Construction/Construction Materials

- A. Caliche will be obtained from the caliche pit located at Lat: 32° 6'28.78"N, Long: 103°16'58.77"W or the caliche pit at Lat: 32° 6'33.14"N, Long: 103°18'44.16"W or the caliche pit at Lat: 32° 3'8.30"N, Long: 103°13'57.00"W.
- B. Caliche utilized for the drilling pad will be obtained either from the locations listed above, an existing approved mineral pit, or by benching into a hill, which will allow the pad to be level with existing caliche from the cut, or extracted by "flipping" the well location. A mineral material permit will be obtained from the BLM prior to excavating any caliche on Federal Lands. Amount will vary for each pad. The procedure for "flipping" a well location is as follows:
1. An adequate amount of topsoil/root zone (usually top 6 inches of soil) will be stripped from the proposed well location and stockpiled along the side of the well location as depicted on the *Exhibit 3 - Well Site Diagram*.
 2. An area will be used within the proposed well site dimensions to excavate caliche.
 3. Subsoil will be removed and stockpiled within the surveyed well pad dimensions.
 4. Once caliche/surfacing mineral is found, the mineral material will be excavated and stockpiled within the approved drilling pad dimensions.
 5. Subsoil will then be pushed back in the excavated hole and caliche will be spread accordingly across the entire well pad and road (if available).
 6. Neither caliche, nor subsoil will be stockpiled outside of the well pad dimensions. Topsoil will be stockpiled along the edge of the pad as depicted in *Exhibit 5 – Enlarged Well Site Diagram*.
 7. In the event that no caliche is found onsite, caliche will be hauled in from a BLM approved caliche pit or other established mineral pit. A BLM mineral material permit will be acquired prior to obtaining any mineral material from BLM pits or federal land.




Exhibit 5 – Enlarged Well Site Diagram

Section 7 - Methods of Handling Waste

- A. Drill cuttings, mud, salts and other chemicals will be properly disposed of into steel tanks on site and hauled to a State approved commercial disposal facility.
- B. Garbage and trash produced during drilling and completion operations will be collected in a portable metal trash container and disposed of properly at a state approved disposal facility. All trash on and around the well site will be collected for disposal.
- C. Human waste and grey water will be properly contained and disposed of properly at a state approved disposal facility.
- D. After drilling and completion operations, trash, chemicals, salts, frac sand and other waste material will be removed and disposed of properly at a state approved disposal facility.

Section 8 - Ancillary Facilities

- A. No ancillary facilities will be needed for the proposed project.

Section 9 - Well Site Layout

- A. See *Exhibit 3 - Well Site Diagram* and *Exhibit 5 – Enlarged Well Site Diagram*. The following information is presented:
 - 1. Reasonable scale
 - 2. Well pad dimensions/orientation
 - 3. Drilling rig components/layout
 - 4. Proposed access road
 - 5. Topsoil stockpile
- B. The proposed drilling pad was staked and surveyed by a professional surveyor. The attached survey plat of the well site depicts the drilling pad layout as staked.
- C. Topsoil salvaging
 - 1. Grass, forbs, and small woody vegetation such as mesquite will be excavated as the topsoil is removed. Large woody vegetation will be stripped and stored separately and re-spread evenly on the site following topsoil re-spreading. Topsoil depth is defined as the top layer of soil that contains 80% of the roots. In areas to be heavily disturbed, the top 6 inches of soil material will be stripped and stockpiled on the perimeter of the well location and along the perimeter of the access road to control run-on and run-off, to keep topsoil viable, and to make redistribution of topsoil more efficient during interim reclamation. Stockpiled topsoil should include vegetative material. Topsoil will be clearly segregated and stored separately from subsoils. Contaminated soil will not be stockpiled, but properly treated and handled prior to topsoil salvaging.

Section 10 - Plans for Final Surface Reclamation

Reclamation Objectives

- A. The objective of interim reclamation is to restore vegetative cover and a portion of the landform sufficient to maintain healthy, biologically active topsoil, to control erosion, and to minimize habitat and forage loss, visual impact, and weed infestation during the life of the well or facilities.
- B. The long-term objective of final reclamation is to return the land to a condition similar to what existed prior to disturbance. This includes restoration of the landform and natural vegetative community, hydrologic systems, visual resources, and wildlife habitats. To ensure that the long-term objective will be reached through human and natural processes, actions will be taken to ensure standards are met for site stability, visual quality, hydrological functioning, and vegetative productivity.

- C. The BLM will be notified at least 3 days prior to the commencement of any reclamation procedures.
- D. If circumstances allow, interim reclamation and/or final reclamation actions will be completed no later than 6 months from when the final well on location has been completed or plugged. Ameredev will gain written permission from the BLM if more time is needed.
- E. Interim reclamation will be performed on the well site after the well is drilled and completed. *Exhibit 3 – Well Site Diagram and Exhibit 5 – Enlarged Well Site Diagram* depict the location and dimension of the planned interim reclamation for the well site.

Interim Reclamation Procedures (if performed)

- A. Within 30 days of well completion, the well location and surrounding areas will be cleared of, and maintained free of, all materials, trash, and equipment not required for production.
- B. In areas planned for interim reclamation, all the surfacing material will be removed and returned to the original mineral pit or recycled to repair or build roads and well pads.
- C. The areas planned for interim reclamation will then be contoured to the original contour if feasible, or if not feasible, to an interim contour that blends with the surrounding topography as much as possible. Where applicable, the fill material of the well pad will be backfilled into the cut to bring the area back to the original contour. The interim cut and fill slopes prior to re-seeding will not be steeper than a 3:1 Ratio, unless the adjacent native topography is steeper. Note: Constructed slopes may be much steeper during drilling, but will be re-contoured to the above ratios during interim reclamation.
- D. Topsoil will be evenly re-spread and aggressively revegetated over the entire disturbed area not needed for all-weather operations, including cuts and fills. To seed the area, the proper BLM mixture, free of noxious weeds, will be used. Final seedbed preparation will consist of contour cultivating to a depth of 4 to 6 inches within 24 hours prior to seeding, dozer tracking, or other imprinting, in order to break the soil crust and create seed germination micro-sites.
- E. Proper erosion control methods will be used on the area to control erosion, runoff, and siltation of the surrounding area.
- F. The interim reclamation will be monitored periodically to ensure that vegetation has reestablished and that erosion is controlled.

Final Reclamation Procedures (well pad, buried pipelines, etc.)

- A. Prior to final reclamation procedures, the well pad, road, and surrounding area will be cleared of material, trash, and equipment.
- B. All surfacing material will be removed and returned to the original mineral pit or recycled to repair or build roads and well pads.
- C. All disturbed areas, including roads, pipelines, pads, production facilities, and interim reclaimed areas will be re-contoured to the contour existing prior to initial construction or a contour that blends indistinguishably with the surrounding landscape. Topsoil that was spread over the interim reclamation areas will be stockpiled prior to re-contouring. The topsoil will be redistributed evenly over the entire disturbed site to ensure successful revegetation.

Ameredev Operating, LLC
Juniper Fed Com 25 36 34 091H
Section 34, Township 25S, Range 36E
Lea County, New Mexico



- D. After all the disturbed areas have been properly prepared, the areas will be seeded with the proper BLM seed mixture, free of noxious weeds. Final seedbed preparation will consist of contour cultivating to a depth of 4 to 6 inches within 24 hours prior to seeding, dozer tracking, or other imprinting, in order to break the soil crust and create seed germination micro-sites.
- E. Proper erosion control methods will be used on the area to control erosion, runoff, and siltation of the surrounding area.
- F. All unused equipment and structures including pipelines, electric line poles, tanks, etc. that serviced the well will be removed.
- G. All reclaimed areas will be monitored periodically to ensure that revegetation occurs, that the area is not re-disturbed, and that erosion is controlled.

Section 11 - Surface Ownership

- A. EOG has surface ownership for proposed project area.

Section 12 - Other Information

- A. There are no dwellings within 1 mile of this location.
- B. An on-site meeting for the Juniper Fed Com 25 36 34 091H well was held on Nov. 28, 2017.
- C. The well pad described in this document - Juniper/Pimento (JUN/PIM #1S) - will contain 6 wells that produce into a central tank battery (CTB) located north of the well pad. The wells share a common pad access road, and the six total flowlines from the individual wells will share a common corridor that terminates into the CTB. The CTB will be tied into a shared pipeline and electrical corridor. The wells that share the pad are:
 - Juniper Fed Com 25 36 34 081H, APD ID# 10400031765
 - Juniper Fed Com 25 36 34 091H, APD ID# 10400031762
 - Juniper Fed Com 25 36 34 111H, APD ID# 10400031759
 - Juniper Fed Com 25 36 34 121H, APD ID# 10400031755
 - Pimento Fed Com 26 36 03 111H, APD ID# 10400031732
 - Pimento Fed Com 26 36 03 121H, APD ID# 10400031733

Ameredev field representative:

Zac Boyd, Operations Supervisor

Cell: (432) 385-6996

Email: zboyd@ameredev.com

Ameredev office contact:

Christie Hanna, Regulatory Coordinator

Direct: (737) 300-4723

Email: channa@ameredev.com

Ameredev Operating, LLC Address: 5707 Southwest Parkway Building 1, Suite 275 Austin, Texas 78735



Section 1 - General

Would you like to address long-term produced water disposal? NO

Section 2 - Lined Pits

Would you like to utilize Lined Pit PWD options? NO

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Lined pit PWD on or off channel:

Lined pit PWD discharge volume (bbl/day):

Lined pit specifications:

Pit liner description:

Pit liner manufacturers information:

Precipitated solids disposal:

Describe precipitated solids disposal:

Precipitated solids disposal permit:

Lined pit precipitated solids disposal schedule:

Lined pit precipitated solids disposal schedule attachment:

Lined pit reclamation description:

Lined pit reclamation attachment:

Leak detection system description:

Leak detection system attachment:

Lined pit Monitor description:

Lined pit Monitor attachment:

Lined pit: do you have a reclamation bond for the pit?

Is the reclamation bond a rider under the BLM bond?

Lined pit bond number:

Lined pit bond amount:

Additional bond information attachment:

Section 3 - Unlined Pits

Would you like to utilize Unlined Pit PWD options? NO

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Unlined pit PWD on or off channel:

Unlined pit PWD discharge volume (bbl/day):

Unlined pit specifications:

Precipitated solids disposal:

Describe precipitated solids disposal:

Precipitated solids disposal permit:

Unlined pit precipitated solids disposal schedule:

Unlined pit precipitated solids disposal schedule attachment:

Unlined pit reclamation description:

Unlined pit reclamation attachment:

Unlined pit Monitor description:

Unlined pit Monitor attachment:

Do you propose to put the produced water to beneficial use?

Beneficial use user confirmation:

Estimated depth of the shallowest aquifer (feet):

Does the produced water have an annual average Total Dissolved Solids (TDS) concentration equal to or less than that of the existing water to be protected?

TDS lab results:

Geologic and hydrologic evidence:

State authorization:

Unlined Produced Water Pit Estimated percolation:

Unlined pit: do you have a reclamation bond for the pit?

Is the reclamation bond a rider under the BLM bond?

Unlined pit bond number:

Unlined pit bond amount:

Additional bond information attachment:

Section 4 - Injection

Would you like to utilize Injection PWD options? NO

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Injection PWD discharge volume (bbl/day):

Injection well mineral owner:

Injection well type:

Injection well number:

Assigned injection well API number?

Injection well new surface disturbance (acres):

Minerals protection information:

Mineral protection attachment:

Underground Injection Control (UIC) Permit?

UIC Permit attachment:

Injection well name:

Injection well API number:

Section 5 - Surface Discharge

Would you like to utilize Surface Discharge PWD options? NO

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Surface discharge PWD discharge volume (bbl/day):

Surface Discharge NPDES Permit?

Surface Discharge NPDES Permit attachment:

Surface Discharge site facilities information:

Surface discharge site facilities map:

Section 6 - Other

Would you like to utilize Other PWD options? NO

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Other PWD discharge volume (bbl/day):

Other PWD type description:

Other PWD type attachment:

Have other regulatory requirements been met?

Other regulatory requirements attachment:



U.S. Department of the Interior
BUREAU OF LAND MANAGEMENT

Bond Info Data Report

03/25/2019

Bond Information

Federal/Indian APD: FED

BLM Bond number: NMB001478

BIA Bond number:

Do you have a reclamation bond? NO

Is the reclamation bond a rider under the BLM bond?

Is the reclamation bond BLM or Forest Service?

BLM reclamation bond number:

Forest Service reclamation bond number:

Forest Service reclamation bond attachment:

Reclamation bond number:

Reclamation bond amount:

Reclamation bond rider amount:

Additional reclamation bond information attachment: