

HOBBES OCD  
NOV 04 2019

RECEIVED

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

## APPLICATION FOR PERMIT TO DRILL OR REENTER

FORM APPROVED  
OMB No. 1004-0137  
Expires: January 31, 2018

1a. Type of work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER		5. Lease Serial No. NMNM0002889
1b. Type of Well: <input checked="" type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Other		6. If Indian, Allottee or Tribe Name
1c. Type of Completion: <input type="checkbox"/> Hydraulic Fracturing <input checked="" type="checkbox"/> Single Zone <input type="checkbox"/> Multiple Zone		7. If Unit or CA Agreement, Name and No.
2. Name of Operator CIMAREX ENERGY COMPANY (215099)		8. Lease Name and Well No. DOS EQUIS 12-13 FEDERAL COM 6H (726096)
3a. Address 600 N. Marienfeld St., Suite 600 Midland TX 79701	3b. Phone No. (include area code) (432)620-1936	9. API Well No. 30-025-46481
4. Location of Well (Report location clearly and in accordance with any State requirements. *) At surface NWNE / 360 FNL / 1410 FEL / LAT 32.23847 / LONG -103.624347 At proposed prod. zone SESE / 100 FSL / 330 FEL / LAT 32.210704 / LONG -103.620877		10. Field and Pool, or Exploratory (96603) TRISTE DRAW BONE SPRING TRISTE
14. Distance in miles and direction from nearest town or post office* 27 miles		11. Sec., T. R. M. or Blk. and Survey or Area SEC 12 / T24S / R32E / NMP
15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) 360 feet	16. No of acres in lease 680	17. Spacing Unit dedicated to this well 320
18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft. 20 feet	19. Proposed Depth 9600 feet / 19577 feet	20. BLM/BIA Bond No. in file FED: NMB001188
21. Elevations (Show whether DF, KDB, RT, GL, etc.) 3600 feet	22. Approximate date work will start* 09/10/2019	23. Estimated duration 30 days
24. Attachments		

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, and the Hydraulic Fracturing rule per 43 CFR 3162.3-3 (as applicable)

- |  |   |
|--|---|
| 1. Well plat certified by a registered surveyor.   | 4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above). |
| 2. A Drilling Plan.  | 5. Operator certification.  |
| 3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO must be filed with the appropriate Forest Service Office). | 6. Such other site specific information and/or plans as may be requested by the BLM.            |

25. Signature (Electronic Submission)	Name (Printed/Typed) Aricka Easterling / Ph: (918)560-7060	Date 01/08/2019
Title Regulatory Analyst		
Approved by (Signature) (Electronic Submission)	Name (Printed/Typed) Cody Layton / Ph: (575)234-5959	Date 10/24/2019
Title Assistant Field Manager Lands & Minerals		
Office CARLSBAD		

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.  
Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

ECP Rec 11/04/19

APPROVED WITH CONDITIONS

KZ  
11/07/19

# PECOS DISTRICT DRILLING CONDITIONS OF APPROVAL

<b>OPERATOR'S NAME:</b>	<b>CIMAREX ENERGY COMPANY</b>
<b>LEASE NO.:</b>	<b>NMNM0002889</b>
<b>LOCATION:</b>	<b>Section 12, T.24 S., R.32 E., NMPM</b>
<b>COUNTY:</b>	<b>Lea County, New Mexico</b>

<b>WELL NAME &amp; NO.:</b>	<b>Dos Equis 12-13 Federal COM 6H</b>
<b>SURFACE HOLE FOOTAGE:</b>	<b>360'/N &amp; 1410'/E</b>
<b>BOTTOM HOLE FOOTAGE:</b>	<b>100'/S &amp; 330'/E</b>

COA

H2S	<input type="radio"/> Yes	<input checked="" type="radio"/> No	
Potash	<input checked="" type="radio"/> None	<input type="radio"/> Secretary	<input type="radio"/> R-111-P
Cave/Karst Potential	<input checked="" type="radio"/> Low	<input type="radio"/> Medium	<input type="radio"/> High
Cave/Karst Potential	<input type="radio"/> Critical		
Variance	<input type="radio"/> None	<input checked="" type="radio"/> Flex Hose	<input type="radio"/> Other
Wellhead	<input type="radio"/> Conventional	<input checked="" type="radio"/> Multibowl	<input type="radio"/> Both
Other	<input type="checkbox"/> 4 String Area	<input type="checkbox"/> Capitan Reef	<input type="checkbox"/> WIPP
Other	<input checked="" type="checkbox"/> Fluid Filled	<input type="checkbox"/> Cement Squeeze	<input type="checkbox"/> Pilot Hole
Special Requirements	<input type="checkbox"/> Water Disposal	<input checked="" type="checkbox"/> COM	<input type="checkbox"/> Unit

## A. HYDROGEN SULFIDE

Hydrogen Sulfide (H2S) monitors shall be installed prior to drilling out the surface shoe. If H2S is detected in concentrations greater than 100 ppm, the Hydrogen Sulfide area shall meet Onshore Order 6 requirements, which includes equipment and personnel/public protection items. If Hydrogen Sulfide is encountered, provide measured values and formations to the BLM.

## B. CASING

1. The 13-3/8 inch surface casing shall be set at approximately **1,235 feet** (a minimum of **25 feet (Lea County)** into the Rustler Anhydrite and above the salt) and cemented to the surface.
  - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.

- b. Wait on cement (WOC) time for a primary cement job will be a minimum of **8 hours** or 500 pounds compressive strength, whichever is greater. (This is to include the lead cement)
- c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.
- d. If cement falls back, remedial cementing will be done prior to drilling out that string.

**Intermediate casing must be kept fluid filled to meet BLM minimum collapse requirement.**

- 2. The minimum required fill of cement behind the 9-5/8 inch intermediate casing is:
  - Cement to surface. If cement does not circulate see B.1.a, c-d above. **Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to cave/karst or potash.**
- 3. The minimum required fill of cement behind the 5-1/2 inch production casing is:
  - Cement should tie-back at least **200 feet** into previous casing string. Operator shall provide method of verification. **Excess cement calculates to 14%, additional cement might be required.**

### **C. PRESSURE CONTROL**

- 1. Variance approved to use flex line from BOP to choke manifold. Manufacturer's specification to be readily available. No external damage to flex line. Flex line to be installed as straight as possible (no hard bends).'
- 2. Operator has proposed a multi-bowl wellhead assembly. This assembly will only be tested when installed on the surface casing. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be **2000 (2M) psi**. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the intermediate casing shoe shall be **3000 (3M) psi**.
  - a. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
  - b. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
  - c. Manufacturer representative shall install the test plug for the initial BOP test.
  - d. If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.

- e. Whenever any seal subject to test pressure is broken, all the tests in OOGO2.III.A.2.i must be followed.

#### **D. SPECIAL REQUIREMENT (S)**

##### **Communitization Agreement**

- The operator will submit a Communitization Agreement to the Carlsbad Field Office, 620 E Greene St. Carlsbad, New Mexico 88220, at least 90 days before the anticipated date of first production from a well subject to a spacing order issued by the New Mexico Oil Conservation Division. The Communitization Agreement will include the signatures of all working interest owners in all Federal and Indian leases subject to the Communitization Agreement (i.e., operating rights owners and lessees of record), or certification that the operator has obtained the written signatures of all such owners and will make those signatures available to the BLM immediately upon request.
- If the operator does not comply with this condition of approval, the BLM may take enforcement actions that include, but are not limited to, those specified in 43 CFR 3163.1.
- In addition, the well sign shall include the surface and bottom hole lease numbers. When the Communitization Agreement number is known, it shall also be on the sign.

**JJP10222019**

### **GENERAL REQUIREMENTS**

The BLM is to be notified in advance for a representative to witness:

- a. Spudding well (minimum of 24 hours)
- b. Setting and/or Cementing of all casing strings (minimum of 4 hours)
- c. BOPE tests (minimum of 4 hours)

☒ Eddy County

Call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220,  
(575) 361-2822

☒ Lea County

Call the Hobbs Field Station, 414 West Taylor, Hobbs NM 88240, (575)  
393-3612

1. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval.

- a. In the event the operator has proposed to drill multiple wells utilizing a skid/walking rig. Operator shall secure the wellbore on the current well, after installing and testing the wellhead, by installing a blind flange of like pressure rating to the wellhead and a pressure gauge that can be monitored while drilling is performed on the other well(s).
  - b. When the operator proposes to set surface casing with Spudder Rig
    - Notify the BLM when moving in and removing the Spudder Rig.
    - Notify the BLM when moving in the 2<sup>nd</sup> Rig. Rig to be moved in within 90 days of notification that Spudder Rig has left the location.
    - BOP/BOPE test to be conducted per Onshore Oil and Gas Order No. 2 as soon as 2nd Rig is rigged up on well.
2. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works are located, this does not include the dog house or stairway area.
  3. The record of the drilling rate along with the GR/N well log run from TD to surface (horizontal well – vertical portion of hole) shall be submitted to the BLM office as well as all other logs run on the borehole 30 days from completion. If available, a digital copy of the logs is to be submitted in addition to the paper copies. The Rustler top and top and bottom of Salt are to be recorded on the Completion Report.

#### A. CASING

1. Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size or are Non-API. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.). The initial wellhead installed on the well will remain on the well with spools used as needed.
2. Wait on cement (WOC) for Potash Areas: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi for all cement blends, 2) until cement has been in place at least 24 hours. WOC time will be recorded in the driller's log. The casing integrity test can be done (prior to the cement setting up) immediately after bumping the plug.
3. Wait on cement (WOC) for Water Basin: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi at the shoe, 2) until cement has been in place at least 8 hours.

WOC time will be recorded in the driller's log. See individual casing strings for details regarding lead cement slurry requirements. The casing integrity test can be done (prior to the cement setting up) immediately after bumping the plug.

4. Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. Have well specific cement details onsite prior to pumping the cement for each casing string.
5. No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.
6. On that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Formation at the shoe shall be tested to a minimum of the mud weight equivalent anticipated to control the formation pressure to the next casing depth or at total depth of the well. This test shall be performed before drilling more than 20 feet of new hole.
7. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.
8. Whenever a casing string is cemented in the R-111-P potash area, the NMOCD requirements shall be followed.

**B. PRESSURE CONTROL**

1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in Onshore Oil and Gas Order No. 2 and API RP 53 Sec. 17.
2. If a variance is approved for a flexible hose to be installed from the BOP to the choke manifold, the following requirements apply: The flex line must meet the requirements of API 16C. Check condition of flexible line from BOP to choke manifold, replace if exterior is damaged or if line fails test. Line to be as straight as possible with no hard bends and is to be anchored according to Manufacturer's requirements. The flexible hose can be exchanged with a hose of equal size and equal or greater pressure rating. Anchor requirements, specification sheet and hydrostatic pressure test certification matching the hose in service, to be onsite for review. These documents shall be posted in the company man's trailer and on the rig floor.
3. 5M or higher system requires an HCR valve, remote kill line and annular to match. The remote kill line is to be installed prior to testing the system and tested to stack pressure.
4. If the operator has proposed a multi-bowl wellhead assembly in the APD. The following requirements must be met:

- a. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
  - b. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
  - c. Manufacturer representative shall install the test plug for the initial BOP test.
  - d. Whenever any seal subject to test pressure is broken, all the tests in OOGO2.III.A.2.i must be followed.
  - e. If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
5. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.
- a. In a water basin, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. The casing cut-off and BOP installation can be initiated four hours after installing the slips, which will be approximately six hours after bumping the plug. For those casing strings not using slips, the minimum wait time before cut-off is eight hours after bumping the plug. BOP/BOPE testing can begin after cut-off or once cement reaches 500 psi compressive strength (including lead when specified), whichever is greater. However, if the float does not hold, cut-off cannot be initiated until cement reaches 500 psi compressive strength (including lead when specified).
  - b. In potash areas, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. For all casing strings, casing cut-off and BOP installation can be initiated at twelve hours after bumping the plug. However, **no tests** shall commence until the cement has had a minimum of 24 hours setup time, except the casing pressure test can be initiated immediately after bumping the plug (only applies to single stage cement jobs).
  - c. The tests shall be done by an independent service company utilizing a test plug not a cup or J-packer. The operator also has the option of utilizing an independent tester to test without a plug (i.e. against the casing) pursuant to Onshore Order 2 with the pressure not to exceed 70% of the burst rating for the casing. Any test against the casing must meet the WOC time for water basin (8 hours) or potash (24 hours) or 500 pounds compressive strength, whichever is greater, prior to initiating the test (see casing segment as lead cement may be critical item).

- d. The test shall be run on a 5000 psi chart for a 2-3M BOP/BOP, on a 10000 psi chart for a 5M BOP/BOPE and on a 15000 psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one hour chart. A circular chart shall have a maximum 2 hour clock. If a twelve hour or twenty-four hour chart is used, tester shall make a notation that it is run with a two hour clock.
- e. The results of the test shall be reported to the appropriate BLM office.
- f. All tests are required to be recorded on a calibrated test chart. A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.
- g. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug. This test shall be performed prior to the test at full stack pressure.
- h. BOP/BOPE must be tested by an independent service company within 500 feet of the top of the Wolfcamp formation if the time between the setting of the intermediate casing and reaching this depth exceeds 20 days. This test does not exclude the test prior to drilling out the casing shoe as per Onshore Order No. 2.

#### C. DRILLING MUD

Mud system monitoring equipment, with derrick floor indicators and visual and audio alarms, shall be operating before drilling into the Wolfcamp formation, and shall be used until production casing is run and cemented.

#### D. WASTE MATERIAL AND FLUIDS

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area.

Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.





U.S. Department of the Interior  
BUREAU OF LAND MANAGEMENT

## Operator Certification Data Report

10/24/2019

### Operator Certification

*I hereby certify that I, or someone under my direct supervision, have inspected the drill site and access route proposed herein; that I am familiar with the conditions which currently exist; that I have full knowledge of state and Federal laws applicable to this operation; that the statements made in this APD package are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for the operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filing of false statements.*

**NAME:** Amithy Crawford

**Signed on:** 01/08/2019

**Title:** Regulatory Analyst

**Street Address:**

**City:**

**State:**

**Zip:**

**Phone:** (432)620-1909

**Email address:** acrawford@cimarex.com

### Field Representative

**Representative Name:**

**Street Address:**

**City:**

**State:**

**Zip:**

**Phone:**

**Email address:**



U.S. Department of the Interior  
BUREAU OF LAND MANAGEMENT

## Application Data Report

10/24/2019

APD ID: 10400037729

Submission Date: 01/08/2019

Operator Name: CIMAREX ENERGY COMPANY

Well Name: DOS EQUIS 12-13 FEDERAL COM

Well Number: 6H

Well Type: OIL WELL

Well Work Type: Drill

[Show Final Text](#)

### Section 1 - General

APD ID: 10400037729

Tie to previous NOS?

Submission Date: 01/08/2019

BLM Office: CARLSBAD

User: Amithy Crawford

Title: Regulatory Analyst

Federal/Indian APD: FED

Is the first lease penetrated for production Federal or Indian? FED

Lease number: NMNM0002889

Lease Acres: 680

Surface access agreement in place?

Allotted?

Reservation:

Agreement in place? NO

Federal or Indian agreement:

Agreement number:

Agreement name:

Keep application confidential? YES

Permitting Agent? NO

APD Operator: CIMAREX ENERGY COMPANY

Operator letter of designation:

### Operator Info

Operator Organization Name: CIMAREX ENERGY COMPANY

Operator Address: 600 N. Marienfeld St., Suite 600

Zip: 79701

Operator PO Box:

Operator City: Midland

State: TX

Operator Phone: (432)620-1936

Operator Internet Address: tstathem@cimarex.com

### Section 2 - Well Information

Well in Master Development Plan? NO

Master Development Plan name:

Well in Master SUPO? NO

Master SUPO name:

Well in Master Drilling Plan? NO

Master Drilling Plan name:

Well Name: DOS EQUIS 12-13 FEDERAL COM

Well Number: 6H

Well API Number:

Field/Pool or Exploratory? Field and Pool

Field Name: TRISTE DRAW  
BONE SPRING

Pool Name: TRISTE DRAW  
BONE SPRING

Is the proposed well in an area containing other mineral resources? USEABLE WATER

Operator Name: CIMAREX ENERGY COMPANY

Well Name: DOS EQUIS 12-13 FEDERAL COM

Well Number: 6H

Is the proposed well in an area containing other mineral resources? USEABLE WATER

Is the proposed well in a Helium production area? N Use Existing Well Pad? NO New surface disturbance?

Type of Well Pad: MULTIPLE WELL

Multiple Well Pad Name: DOS EQUIS 12-13 FEDERAL COM  
Number of Legs: 1

Number: W2E2 PAD 6

Well Class: HORIZONTAL

Well Work Type: Drill

Well Type: OIL WELL

Describe Well Type:

Well sub-Type: INFILL

Describe sub-type:

Distance to town: 27 Miles

Distance to nearest well: 20 FT

Distance to lease line: 360 FT

Reservoir well spacing assigned acres Measurement: 320 Acres

Well plat: Dos\_Equis\_12\_13\_Fed\_Com\_6H\_C102\_Plat\_20190108075232.pdf

Well work start Date: 09/10/2019

Duration: 30 DAYS

### Section 3 - Well Location Table

Survey Type: RECTANGULAR

Describe Survey Type:

Datum: NAD83

Vertical Datum: NAVD88

Survey number:

Reference Datum:

Wellbore	NS-Foot	NS Indicator	EW-Foot	EW Indicator	Twsp	Range	Section	Aliquot/Lot/Tract	Latitude	Longitude	County	State	Meridian	Lease Type	Lease Number	Elevation	MD	TVD	Will this well produce
SHL Leg #1	360	FNL	141 0	FEL	24S	32E	12	Aliquot NWNE	32.23847	- 103.6243 47	LEA	NEW MEXI CO	NEW MEXI CO	F	NMNM 000288 9	360 0	0	0	
KOP Leg #1	360	FNL	330	FEL	24S	32E	12	Aliquot NENE	32.23845	- 103.6208 556	LEA	NEW MEXI CO	NEW MEXI CO	F	NMNM 000288 9	- 552 3	921 0	912 3	
PPP Leg	0	FNL	330	FEL	24S	32E	13	Aliquot NENE	32.22493 33	- 103.6208	LEA	NEW MEXI	NEW MEXI	F	NMNM 055364	- 600	144 00	960 0	

Operator Name: CIMAREX ENERGY COMPANY

Well Name: DOS EQUIS 12-13 FEDERAL COM

Well Number: 6H

Wellbore	NS-Foot	NS Indicator	EW-Foot	EW Indicator	Twsp	Range	Section	Aliquot/Lot/Tract	Latitude	Longitude	County	State	Meridian	Lease Type	Lease Number	Elevation	MD	TVD	Will this well produce
PPP Leg #1	0	FNL	330	FEL	24S	32E	13	Aliquot NENE	32.22493 33	- 103.6208 667	LEA	NEW MEXI CO	NEW MEXI CO	F	NMNM 055364 2	- 600 0	144 00	960 0	
PPP Leg #1	0	FNL	330	FEL	24S	32E	13	Aliquot NENE	32.22493 33	- 103.6208 667	LEA	NEW MEXI CO	NEW MEXI CO	F	NMNM 055364 2	- 600 0	144 00	960 0	
PPP Leg #1	0	FNL	330	FEL	24S	32E	13	Aliquot NENE	32.22493 33	- 103.6208 667	LEA	NEW MEXI CO	NEW MEXI CO	F	NMNM 055364 2	- 600 0	144 00	960 0	
PPP Leg #1	0	FNL	330	FEL	24S	32E	13	Aliquot NENE	32.22493 33	- 103.6208 667	LEA	NEW MEXI CO	NEW MEXI CO	F	NMNM 055364 2	- 600 0	144 00	960 0	
PPP Leg #1	264 0	FSL	330	FEL	24S	32E	12	Aliquot NESE	32.23235 56	- 103.6208 583	LEA	NEW MEXI CO	NEW MEXI CO	F	NMNM 000191 7	- 600 0	117 00	960 0	
PPP Leg #1	264 0	FSL	330	FEL	24S	32E	12	Aliquot NESE	32.23235 56	- 103.6208 583	LEA	NEW MEXI CO	NEW MEXI CO	F	NMNM 000191 7	- 600 0	117 00	960 0	
PPP Leg #1	264 0	FSL	330	FEL	24S	32E	12	Aliquot NESE	32.23235 56	- 103.6208 583	LEA	NEW MEXI CO	NEW MEXI CO	F	NMNM 000191 7	- 600 0	117 00	960 0	
PPP Leg #1	264 0	FSL	330	FEL	24S	32E	12	Aliquot NESE	32.23235 56	- 103.6208 583	LEA	NEW MEXI CO	NEW MEXI CO	F	NMNM 000191 7	- 600 0	117 00	960 0	
PPP Leg #1	264 0	FSL	330	FEL	24S	32E	12	Aliquot NESE	32.23235 56	- 103.6208 583	LEA	NEW MEXI CO	NEW MEXI CO	F	NMNM 000191 7	- 600 0	117 00	960 0	
EXIT Leg #1	264 1	FNL	330	FEL	24S	32E	13	Aliquot SENE	32.21778 61	- 103.6208 722	LEA	NEW MEXI CO	NEW MEXI CO	F	NMNM 055364 2	- 600 0	170 00	960 0	
BHL Leg #1	100	FSL	330	FEL	24S	32E	13	Aliquot SESE	32.21070 4	- 103.6208 77	LEA	NEW MEXI CO	NEW MEXI CO	F	NMNM 055354 8	- 600 0	195 77	960 0	



U.S. Department of the Interior  
BUREAU OF LAND MANAGEMENT

## Drilling Plan Data Report

10/24/2019

APD ID: 10400037729

Submission Date: 01/08/2019

Operator Name: CIMAREX ENERGY COMPANY

Well Name: DOS EQUIS 12-13 FEDERAL COM

Well Number: 6H

Well Type: OIL WELL

Well Work Type: Drill

[Show Final Text](#)

### Section 1 - Geologic Formations

Formation ID	Formation Name	Elevation	True Vertical Depth	Measured Depth	Lithologies	Mineral Resources	Producing Formation
1							
2							
3							
4							
5							
6							
7							
8							
9							
10							
11							
12							

### Section 2 - Blowout Prevention

Pressure Rating (PSI): 2M

Rating Depth: 4900

**Equipment:** A BOP consisting of three rams, including one blind ram and two pipe rams and one annular preventer. An accumulator that meets the requirements in Onshore Order #2 for the pressure rating of the BOP stack. A rotating head may be installed as needed. A Kelly clock will be installed and maintained in operable condition and a drill string safety valve in the open position will be available on the rig floor.

**Requesting Variance?** YES

**Variance request:** Co-flex line between the BOP and choke manifold. Certification for proposed co-flex hose is attached.

Operator Name: CIMAREX ENERGY COMPANY

Well Name: DOS EQUIS 12-13 FEDERAL COM

Well Number: 6H

String Type	Lead/Tail	Stage Tool Depth	Top MD	Bottom MD	Quantity(sx)	Yield	Density	Cu Ft	Excess%	Cement type	Additives
SURFACE	Lead		0	1235	599	1.72	13.5	1029	50	Class C	Bentonite
SURFACE	Tail		0	1235	160	1.34	14.8	214	25	Class C	LCM
INTERMEDIATE	Lead		0	4900	919	1.88	12.9	1727	50	35:65 (Poz:C)	Salt, Bentonite
INTERMEDIATE	Tail		0	4900	286	1.34	14.8	383	25	Class C	LCM
PRODUCTION	Lead		0	9210	389	3.64	10.3	1414	25	Tuned Light	LCM
PRODUCTION	Tail		0	9210	2217	1.3	14.2	2881	10	50:50 (Poz:H)	Salt, Bentonite, Fluid Loss, Dispersant, SMS
PRODUCTION	Lead		9210	1957 7	389	3.64	10.3	1414	25	Tuned Light	LCM
PRODUCTION	Tail		9210	1957 7	2217	1.3	14.2	2881	10	50:50 (Poz:H)	Salt, Bentonite, Fluid Loss, Dispersant, SMS

### Section 5 - Circulating Medium

Mud System Type: Closed

Will an air or gas system be Used? NO

Description of the equipment for the circulating system in accordance with Onshore Order #2:

Diagram of the equipment for the circulating system in accordance with Onshore Order #2:

**Describe what will be on location to control well or mitigate other conditions:** Sufficient mud materials will be kept on location at all times in order to combat lost circulation or unexpected kicks. In order to run DSTs, open hole logs, and casing, the viscosity and water loss may have to be adjusted in order to meet these needs.

**Describe the mud monitoring system utilized:** PVT/Pason/Visual Monitoring

### Circulating Medium Table

Top Depth	Bottom Depth	Mud Type	Min Weight (lbs/gal)	Max Weight (lbs/gal)	Density (lbs/cu ft)	Gel Strength (lbs/100 sqft)	PH	Viscosity (CP)	Salinity (ppm)	Filtration (cc)	Additional Characteristics
0	1235	SPUD MUD	8.2	8.8							

**Operator Name:** CIMAREX ENERGY COMPANY

**Well Name:** DOS EQUIS 12-13 FEDERAL COM

**Well Number:** 6H

Top Depth	Bottom Depth	Mud Type	Min Weight (lbs/gal)	Max Weight (lbs/gal)	Density (lbs/cu ft)	Gel Strength (lbs/100 sqft)	PH	Viscosity (CP)	Salinity (ppm)	Filtration (cc)	Additional Characteristics
1235	4900	SALT SATURATED	9.7	10.2							
4900	1957 7	OTHER : FW/Cut Brine	8.5	9							

### Section 6 - Test, Logging, Coring

**List of production tests including testing procedures, equipment and safety measures:**

No DST Planned

**List of open and cased hole logs run in the well:**

CNL,DS,GR

**Coring operation description for the well:**

N/A

### Section 7 - Pressure

**Anticipated Bottom Hole Pressure:** 4492

**Anticipated Surface Pressure:** 2380

**Anticipated Bottom Hole Temperature(F):** 166

**Anticipated abnormal pressures, temperatures, or potential geologic hazards?** YES

**Describe:**

Lost circulation may be encountered in the Delaware mountain group. Abnormal pressure as well as hole stability issues may be encountered in the Wolfcamp.

**Contingency Plans geohazards description:**

Lost circulation material will be available, as well as additional drilling fluid along with the fluid volume in the drilling rig pit system. Drilling fluid can be mixed on location or mixed in vendor mud plant and trucked to location if needed. Sufficient barite will be available to maintain appropriate mud weight for the Wolfcamp interval.

**Contingency Plans geohazards attachment:**

**Hydrogen Sulfide drilling operations plan required?** YES

**Hydrogen sulfide drilling operations plan:**

Dos\_Equis\_12\_13\_Fed\_Com\_6H\_H2S\_Plan\_20190108123344.pdf

**Operator Name:** CIMAREX ENERGY COMPANY

**Well Name:** DOS EQUIS 12-13 FEDERAL COM

**Well Number:** 6H

## **Section 8 - Other Information**

**Proposed horizontal/directional/multi-lateral plan submission:**

Dos\_Equis\_12\_13\_Fed\_Com\_6H\_AC\_Report\_20190108123407.pdf

Dos\_Equis\_12\_13\_Fed\_Com\_6H\_Directional\_Plan\_20190108123408.pdf

**Other proposed operations facets description:**

**Other proposed operations facets attachment:**

Dos\_Equis\_12\_13\_Fed\_Com\_6H\_Drilling\_Plan\_20190108123420.pdf

Dos\_Equis\_12\_13\_Fed\_Com\_6H\_Flex\_Hose\_20190108123430.pdf

Dos\_Equis\_12\_13\_Fed\_Com\_6H\_Gas\_Capture\_Plan\_20190108123431.pdf


**Other Variance attachment:**

Dos\_Equis\_12\_13\_Fed\_Com\_6H\_Multibowl\_Procedure\_20190108123503.pdf

Dos\_Equis\_12\_13\_Fed\_Com\_6H\_Multibowl\_Wellhead\_20190108123505.pdf



Drilling 12-1/4" hole  
below 13 3/8" Casing



2000# BOP  
Dos Equis 12-13 Federal Com 6H  
Cimarex Energy Co.  
12-24S-32E  
Lea Co., NM

Drilling 8-3/4" hole  
below 9 5/8" Casing

Fill Line

Flowline

3000# (3M)  
BOP

Annular Preventer

SRR & A

Pipe Rams

Blind Rams

2" Minimum Kill Line

Kill Line

2 Valves Minimum  
(including 1 check valve)

Drilling  
Spool

3" minimum choke line

Choke Line

2 Valves Minimum

13-5/8" 3000 psi x 11" 5000 psi  
Wellhead Assembly

Wellhead  
Assembly

13-5/8" 3000# psi x 13-3/8" SOW Casing Head

3000# BOP  
Dos Equis 12-13 Federal Com 6H  
Cimarex Energy Co.  
12-24S-32E  
Lea Co., NM

Hydrogen Sulfide Drilling Operations Plan  
Dos Equis 12-13 Federal Com 6H  
Cimarex Energy Co.  
UL: B, Sec. 12, 24S, 32E  
Lea Co., NM

1 All Company and Contract personnel admitted on location must be trained by a qualified H<sub>2</sub>S safety instructor to the following:

- A. Characteristics of H<sub>2</sub>S
- B. Physical effects and hazards
- C. Principal and operation of H<sub>2</sub>S detectors, warning system and briefing areas.
- D. Evacuation procedure, routes and first aid.
- E. Proper use of safety equipment & life support systems
- F. Essential personnel meeting Medical Evaluation criteria will receive additional training on the proper use of 30 minute pressure demand air packs.

H<sub>2</sub>S Detection and Alarm Systems:

- A. H<sub>2</sub>S sensors/detectors to be located on the drilling rig floor, in the base of the sub structure/cellar area, on the mud pits in the shale shaker area. Additional H<sub>2</sub>S detectors may be placed as deemed necessary.
- B. An audio alarm system will be installed on the derrick floor and in the top doghouse.

3 Windsock and/or wind streamers:

- A. Windsock at mudpit area should be high enough to be visible.
- B. Windsock on the rig floor and / or top doghouse should be high enough to be visible.

4 Condition Flags and Signs

- A. Warning sign on access road to location.
- B. Flags to be displayed on sign at entrance to location. Green flag indicates normal safe condition. Yellow flag indicates potential pressure and danger. Red flag indicates danger (H<sub>2</sub>S present in dangerous concentration). Only H<sub>2</sub>S trained and certified personnel admitted to location.

5 Well control equipment:

- A. See exhibit "E-1"

6 Communication:

- A. While working under masks chalkboards will be used for communication.
- B. Hand signals will be used where chalk board is inappropriate.
- C. Two way radio will be used to communicate off location in case of emergency help is required. In most cases cellular telephones will be available at most drilling foreman's trailer or living quarters.

7 Drillstem Testing:

No DSTs or cores are planned at this time.

8 Drilling contractor supervisor will be required to be familiar with the effects H<sub>2</sub>S has on tubular goods and other mechanical equipment.

9 If H<sub>2</sub>S is encountered, mud system will be altered if necessary to maintain control of formation. A mud gas separator will be brought into service along with H<sub>2</sub>S scavengers if necessary.

H<sub>2</sub>S Contingency Plan  
Dos Equis 12-13 Federal Com 6H  
Cimarex Energy Co.  
UL: B, Sec. 12, 24S, 32E  
Lea Co., NM

**Emergency Procedures**

In the event of a release of gas containing H<sub>2</sub>S, the first responder(s) must:

- « Isolate the area and prevent entry by other persons into the 100 ppm ROE.
- « Evacuate any public places encompassed by the 100 ppm ROE.
- « Be equipped with H<sub>2</sub>S monitors and air packs in order to control the release.
- « Use the "buddy system" to ensure no injuries occur during the 432-620-1975
- « Take precautions to avoid personal injury during this operation.
- « Contact operator and/or local officials to aid in operation. See list of phone numbers attached.
- « Have received training in the:
  - Detection of H<sub>2</sub>S, and
  - Measures for protection against the gas,
  - Equipment used for protection and emergency response.

**Ignition of Gas Source**

Should control of the well be considered lost and ignition considered, take care to protect against exposure to Sulfur Dioxide (SO<sub>2</sub>). Intentional ignition must be coordinated with the NMOCD and local officials. Additionally, the NM State Police may become involved. NM State Police shall be the Incident Command on scene of any major release. Take care to protect downwind whenever there is an ignition of the gas.

**Characteristics of H<sub>2</sub>S and SO<sub>2</sub>**

Please see attached International Chemical Safety Cards.

**Contacting Authorities**

Cimarex Energy Co. of Colorado's personnel must liaise with local and state agencies to ensure a proper response to a major release. Additionally, the OCD must be notified of the release as soon as possible but no later than 4 hours. Agencies will ask for information such as type and volume of release, wind direction, location of release, etc. Be prepared with all information available including directions to site. The following call list of essential and potential responders has been prepared for use during a release. Cimarex Energy Co. of Colorado's response must be in coordination with the State of New Mexico's "Hazardous Materials Emergency Response Plan" (HMER).

H<sub>2</sub>S Contingency Plan Emergency Contacts  
**Dos Equis 12-13 Federal Com 6H**  
 Cimarex Energy Co.  
 UL: B, Sec. 12, 24S, 32E  
 Lea Co., NM

<b>Company Office</b>			
Cimarex Energy Co. of Colorado		800-969-4789	
Co. Office and After-Hours Menu			
<b>Key Personnel</b>			
<b>Name</b>	<b>Title</b>	<b>Office</b>	<b>Mobile</b>
Larry Seigrist	Drilling Manager	432-620-1934	580-243-8485
Charlie Pritchard	Drilling Superintendent	432-620-1975	432-238-7084
Roy Shirley	Construction Superintendent		432-634-2136
<b>Artesia</b>			
Ambulance		911	
State Police		575-746-2703	
City Police		575-746-2703	
Sheriff's Office		575-746-9888	
<b>Fire Department</b>		<b>575-746-2701</b>	
Local Emergency Planning Committee		575-746-2122	
New Mexico Oil Conservation Division		575-748-1283	
<b>Carlsbad</b>			
Ambulance		911	
State Police		575-885-3137	
City Police		575-885-2111	
Sheriff's Office		575-887-7551	
<b>Fire Department</b>		<b>575-887-3798</b>	
Local Emergency Planning Committee		575-887-6544	
US Bureau of Land Management		575-887-6544	
<b>Santa Fe</b>			
New Mexico Emergency Response Commission (Santa Fe)		505-476-9600	
New Mexico Emergency Response Commission (Santa Fe) 24 Hrs		505-827-9126	
New Mexico State Emergency Operations Center		505-476-9635	
<b>National</b>			
National Emergency Response Center (Washington, D.C.)		800-424-8802	
<b>Medical</b>			
Flight for Life - 4000 24th St.; Lubbock, TX		806-743-9911	
Aerocare - R3, Box 49F; Lubbock, TX		806-747-8923	
Med Flight Air Amb - 2301 Yale Blvd S.E., #D3; Albuquerque, NM		505-842-4433	
SB Air Med Service - 2505 Clark Carr Loop S.E.; Albuquerque, NM		505-842-4949	
<b>Other</b>			
Boots & Coots IWC		800-256-9688	or 281-931-8884
Cudd Pressure Control		432-699-0139	or 432-563-3356
Halliburton		575-746-2757	
B.J. Services		575-746-3569	

## Cimarex Dos Equis 12-13 Federal Com #6H - Rev0 RM 2Jan19 Anti-Collision Summary Report

Analysis Date-24hr Time: January 02, 2019 - 13:57  
 Client: Cimarex Energy  
 Field: NM Lea County (NAD 83)  
 Structure: Cimarex Dos Equis 12-13 Federal Com #6H  
 Slot: New Slot  
 Well: Dos Equis 12-13 Federal Com #6H  
 Borehole: Dos Equis 12-13 Federal Com #6H  
 Scan MD Range: 0.00ft ~ 19576.81ft

Analysis Method: 3D Least Distance  
 Reference Trajectory: Cimarex Dos Equis 12-13 Federal Com #6H - Rev0 RM 2Jan19 (Non-Def Plan)  
 Depth Interval: Every 10.00 Measured Depth (ft)  
 Rule Set: NAL Procedure: D&M AntiCollision Standard S002  
 Min Pts: All local minima indicated.  
 Version / Patch: 2.10.753.0  
 Database \ Project: US1153APP452.dir.slb.com\drilling-NM Lea County 2.10

**Trajectory Error Model:** ISCWSA0 3-D 95.000% Confidence 2.7955 sigma, for subject well. For offset wells, error model version is specified with each well respectively.

## Offset Trajectories Summary

## Offset Selection Criteria

Wellhead distance scan:  
 Selection filters:

Not performed!  
 Definitive Surveys - Definitive Plans - Definitive surveys exclude definitive plans  
 - All Non-Def Surveys when no Def-Survey is set in a borehole - All Non-Def Plans when no Def-Plan is set in a borehole

Offset Trajectory	Separation			Allow Dev. (ft)	Sep. Fact.	Controlling Rule	Reference Trajectory		Risk Level			Alert	Status
	Ct-Ct (ft)	MAS (ft)	EOU (ft)				MD (ft)	TVD (ft)	Alert	Minor	Major		

Results highlighted: Sep-Factor separation <= 1.50 ft

Cimarex Dos Equis 12-13  
 Federal Com #6H Rev0 RM  
 2Jan19 (Non-Def Plan)

Warning Alert

19.99	16.49	17.49	3.50	N/A	MAS = 5.03 (m)	0.00	0.00	CtCt<=15m<15.00	Enter Alert
19.99	16.49	17.49	3.50	N/A	MAS = 5.03 (m)	26.00	26.00		WRP
19.99	16.49	8.46	3.50	1.94	MAS = 5.03 (m)	1500.00	1500.00		MinPts
20.05	16.61	8.14	3.44	1.87	OSF1.50	1620.00	1619.96		MINPT-O-EQU
20.09	16.66	8.15	3.44	1.86	OSF1.50	1650.00	1649.93		MinPt-O-ADP
20.11	16.67	8.16	3.44	1.86	OSF1.50	1660.00	1659.92		MinPt-O-SF
163.93	50.94	129.13	112.99	5.00	OSF1.50	5810.00	5755.92	OSF>5.00	Exit Alert
261.79	76.00	210.29	185.79	5.29	OSF1.50	8590.00	8502.99		MinPt-O-SF
267.82	75.49	216.66	192.32	5.45	OSF1.50	9210.00	9122.99		MinPts
2700.00	322.63	2484.08	2377.37	12.64	OSF1.50	19576.81	9600.00		MinPts

Cimarex Dos Equis 12-13  
 Federal Com #5H Rev0 RM  
 2Jan19 (Non-Def Plan)

Pass

919.87	32.81	917.37	887.06	N/A	MAS = 10.00 (m)	0.00	0.00		Surface
919.87	32.81	917.36	887.06	117968.46	MAS = 10.00 (m)	26.00	26.00		WRP
914.96	32.81	902.96	882.15	96.08	MAS = 10.00 (m)	1790.00	1789.50		MinPts
1122.88	40.60	1094.98	1082.28	44.11	OSF1.50	5050.00	5006.20		MinPt-O-SF
1611.00	63.28	1567.98	1547.72	39.70	OSF1.50	8084.88	8000.00		MinPt-O-SF
1649.78	66.14	1604.85	1583.64	38.83	OSF1.50	9209.54	9122.54		MinPt-O-SF
1649.78	66.13	1604.85	1583.64	38.83	OSF1.50	9260.00	9172.90		MinPts
1649.78	64.82	1605.73	1584.95	39.65	OSF1.50	9550.00	9434.87		MinPt-CtCt
1649.78	326.05	1431.57	1323.72	7.64	OSF1.50	19576.81	9600.00		MinPts

Offset Trajectory	Separation			Allow Dev. (ft)	Sep. Fact.	Controlling Rule	Reference Trajectory		Risk Level			Alert	Status
	Ct-Ct (ft)	MAS (ft)	EOU (ft)				MD (ft)	TVD (ft)	Alert	Minor	Major		
Cimarex Dos Equis 12-13 Federal Com #73H Rev0 RM 2Jan19 (Non-Def Plan)													
													Pass
	939.87	32.81	937.37	907.06	N/A	MAS = 10.00 (m)	0.00	0.00					Surface
	939.87	32.81	937.36	907.06	117192.16	MAS = 10.00 (m)	26.00	26.00					WRP
	938.59	32.81	926.21	905.78	94.71	MAS = 10.00 (m)	1730.00	1729.75					MinPts
	938.60	32.81	926.19	905.79	94.46	MAS = 10.00 (m)	1740.00	1739.72					MINPT-O-EOU
	1312.97	53.38	1276.55	1259.59	38.64	OSF1.50	6060.00	6002.53					MinPt-O-SF
	1632.69	68.67	1586.08	1564.02	36.95	OSF1.50	8084.88	8000.00					MinPt-O-SF
	1671.02	72.42	1621.91	1598.60	35.80	OSF1.50	9220.00	9132.99					MinPts
	1676.05	72.97	1626.57	1603.08	35.62	OSF1.50	9380.00	9289.39					MinPt-O-SF
	3161.06	335.89	2936.30	2825.17	14.21	OSF1.50	19576.81	9600.00					MinPts
Cimarex Dos Equis 12-13 Federal Com #3H Rev0 smk 20Dec18 (Def Plan)													
													Pass
	2238.27	32.81	2235.77	2205.46	N/A	MAS = 10.00 (m)	0.00	0.00					Surface
	2238.27	32.81	2235.75	2205.46	129009.32	MAS = 10.00 (m)	26.00	26.00					WRP
	2229.07	32.81	2217.03	2196.26	233.32	MAS = 10.00 (m)	1750.00	1749.68					MinPts
	2921.47	63.58	2878.25	2857.89	71.68	OSF1.50	8100.00	8014.92					MinPt-O-SF
	2957.74	65.97	2912.93	2891.77	69.84	OSF1.50	9250.00	9162.94					MinPts
	2955.98	66.55	2910.78	2889.43	69.17	OSF1.50	9860.00	9589.66					MinPt-CtCt
	2957.67	476.39	2639.24	2481.28	9.35	OSF1.50	19576.81	9600.00					MinPts
Cimarex Dos Equis 12-13 Federal Com #47H Rev0 smk 20Dec18 (Def Plan)													
													Pass
	2258.24	32.81	2255.74	2225.44	N/A	MAS = 10.00 (m)	0.00	0.00					Surface
	2258.24	32.81	2255.73	2225.44	133587.50	MAS = 10.00 (m)	26.00	26.00					WRP
	2241.54	32.81	2228.58	2208.74	213.93	MAS = 10.00 (m)	1860.00	1859.05					MinPts
	2241.55	32.81	2228.56	2208.75	213.32	MAS = 10.00 (m)	1870.00	1868.97					MINPT-O-EOU
	2931.39	66.93	2885.94	2864.46	68.19	OSF1.50	8100.00	8014.92					MinPt-O-SF
	2967.64	70.74	2919.64	2896.89	65.17	OSF1.50	9230.00	9142.99					MinPts
	2983.75	71.86	2935.01	2911.89	64.47	OSF1.50	9590.00	9463.99					MinPt-O-SF
	2986.84	71.94	2938.05	2914.90	64.47	OSF1.50	9620.00	9484.27					MinPt-O-SF
	3999.60	424.00	3716.09	3575.59	14.22	OSF1.50	19576.81	9600.00					MinPts
Cimarex Dos Equis 12-13 Federal Com #11H Rev1 smk 20Dec18 (Def Plan)													
													Pass
	3485.77	32.81	3483.27	3452.97	N/A	MAS = 10.00 (m)	0.00	0.00					Surface
	3485.77	32.81	3483.26	3452.97	223964.50	MAS = 10.00 (m)	26.00	26.00					WRP
	3485.77	32.81	3474.22	3452.97	384.78	MAS = 10.00 (m)	1500.00	1500.00					MinPts
	3485.79	32.81	3474.19	3452.98	382.78	MAS = 10.00 (m)	1510.00	1510.00					MINPT-O-EOU
	4529.39	74.87	4478.65	4454.52	93.83	OSF1.50	8100.00	8014.92					MinPt-O-SF
	4565.73	79.66	4511.79	4486.07	88.71	OSF1.50	9200.00	9112.99					MinPts
	4565.74	79.67	4511.79	4486.07	88.70	OSF1.50	9209.54	9122.54					MinPt-O-SF
	4607.45	470.99	4292.62	4136.46	14.74	OSF1.50	19576.81	9600.00					MinPts
Cimarex Dos Equis 12-13 Federal Com #8H Rev0 smk 20Dec18 (Def Plan)													
													Pass
	3505.78	32.81	3503.28	3472.97	N/A	MAS = 10.00 (m)	0.00	0.00					Surface
	3505.78	32.81	3503.26	3472.97	222077.93	MAS = 10.00 (m)	26.00	26.00					WRP
	3505.78	32.81	3494.22	3472.97	386.98	MAS = 10.00 (m)	1500.00	1500.00					MinPts
	3505.79	32.81	3494.19	3472.98	384.96	MAS = 10.00 (m)	1510.00	1510.00					MINPT-O-EOU
	4569.82	74.84	4519.10	4494.99	94.71	OSF1.50	8100.00	8014.92					MinPt-O-SF

Offset Trajectory	Separation			Allow Dev. (ft)	Sep. Fact.	Controlling Rule	Reference Trajectory		Risk Level			Alert	Status
	Ct-Ct (ft)	MAS (ft)	EOU (ft)				MD (ft)	TVD (ft)	Alert	Minor	Major		
4608.37	76.30	4556.67	4532.07	93.62	OSF1.50	8660.00	8572.99					MINPT-O-EOU	
4610.62	79.74	4556.62	4530.88	89.49	OSF1.50	9209.54	9122.54					MINPT-O-EOU	
4610.67	79.80	4556.63	4530.87	89.43	OSF1.50	9220.00	9132.99					MinPt-O-ADP	
4635.26	81.60	4580.02	4553.65	87.85	OSF1.50	9750.00	9554.75					MinPt-O-SF	
5336.69	445.05	5039.15	4891.64	18.08	OSF1.50	19576.81	9600.00					MinPts	





**Cimarex Dos Equis 12-13 Federal Com #6H - Rev0 RM 2Jan19 Proposal**  
**Geodetic Report**  
(Non-Def Plan)



**Report Date:** January 02, 2019 - 01:56 PM  
**Client:** Cimarex Energy  
**Field:** NM Lea County (NAD 83)  
**Structure / Slot:** Cimarex Dos Equis 12-13 Federal Com #6H / New Slot  
**Well:** Dos Equis 12-13 Federal Com #6H  
**Borehole:** Dos Equis 12-13 Federal Com #6H  
**UWI / API#:** Unknown / Unknown  
**Survey Name:** Cimarex Dos Equis 12-13 Federal Com #6H - Rev0 RM 2Jan19  
**Survey Date:** January 02, 2019  
**Tort / AHD / DDI / ERD Ratio:** 108.876 ° / 11174.684 ft / 6.395 / 1.164  
**Coordinate Reference System:** NAD83 New Mexico State Plane, Eastern Zone, US Feet  
**Location Lat / Long:** N 32° 14' 18.49298", W 103° 37' 27.64812"  
**Location Grid N/E Y/X:** N 451212.550 ftUS, E 760546.590 ftUS  
**CRS Grid Convergence Angle:** 0.3782 °  
**Grid Scale Factor:** 0.99996413  
**Version / Patch:** 2.10.753.0

**Survey / DLS Computation:** Minimum Curvature / Lubinski  
**Vertical Section Azimuth:** 179.660 ° (Grid North)  
**Vertical Section Origin:** 0.000 ft, 0.000 ft  
**TVD Reference Datum:** RKB  
**TVD Reference Elevation:** 3626.400 ft above MSL  
**Seabed / Ground Elevation:** 3600.400 ft above MSL  
**Magnetic Declination:** 6.729 °  
**Total Gravity Field Strength:** 998.4390mgn (9.80665 Based)  
**Gravity Model:** GARM  
**Total Magnetic Field Strength:** 47964.239 nT  
**Magnetic Dip Angle:** 59.925 °  
**Declination Date:** January 02, 2019  
**Magnetic Declination Model:** HDGM 2019  
**North Reference:** Grid North  
**Grid Convergence Used:** 0.3782 °  
**Total Corr Mag North->Grid North:** 6.3504 °  
**Local Coord Referenced To:** Well Head

Comments	MD (ft)	Incl (°)	Azim Grid (°)	TVD (ft)	VSEC (ft)	NS (ft)	EW (ft)	DLS (°/100ft)	Northing (ftUS)	Easting (ftUS)	Latitude (N/S ° ' ")	Longitude (E/W ° ' ")
SHL [360° FNL, 1410° FEL]	0.00	0.00	173.56	0.00	0.00	0.00	0.00	N/A	451212.55	760546.59	N 32 14 18.49 W 103 37 27.65	
	100.00	0.00	90.00	100.00	0.00	0.00	0.00	0.00	451212.55	760546.59	N 32 14 18.49 W 103 37 27.65	
	200.00	0.00	90.00	200.00	0.00	0.00	0.00	0.00	451212.55	760546.59	N 32 14 18.49 W 103 37 27.65	
	300.00	0.00	90.00	300.00	0.00	0.00	0.00	0.00	451212.55	760546.59	N 32 14 18.49 W 103 37 27.65	
	400.00	0.00	90.00	400.00	0.00	0.00	0.00	0.00	451212.55	760546.59	N 32 14 18.49 W 103 37 27.65	
	500.00	0.00	90.00	500.00	0.00	0.00	0.00	0.00	451212.55	760546.59	N 32 14 18.49 W 103 37 27.65	
	600.00	0.00	90.00	600.00	0.00	0.00	0.00	0.00	451212.55	760546.59	N 32 14 18.49 W 103 37 27.65	
	700.00	0.00	90.00	700.00	0.00	0.00	0.00	0.00	451212.55	760546.59	N 32 14 18.49 W 103 37 27.65	
	800.00	0.00	90.00	800.00	0.00	0.00	0.00	0.00	451212.55	760546.59	N 32 14 18.49 W 103 37 27.65	
	900.00	0.00	90.00	900.00	0.00	0.00	0.00	0.00	451212.55	760546.59	N 32 14 18.49 W 103 37 27.65	
	1000.00	0.00	90.00	1000.00	0.00	0.00	0.00	0.00	451212.55	760546.59	N 32 14 18.49 W 103 37 27.65	
	1100.00	0.00	90.00	1100.00	0.00	0.00	0.00	0.00	451212.55	760546.59	N 32 14 18.49 W 103 37 27.65	
Rustler	1185.00	0.00	90.00	1185.00	0.00	0.00	0.00	0.00	451212.55	760546.59	N 32 14 18.49 W 103 37 27.65	
	1200.00	0.00	90.00	1200.00	0.00	0.00	0.00	0.00	451212.55	760546.59	N 32 14 18.49 W 103 37 27.65	
	1300.00	0.00	90.00	1300.00	0.00	0.00	0.00	0.00	451212.55	760546.59	N 32 14 18.49 W 103 37 27.65	
	1400.00	0.00	90.00	1400.00	0.00	0.00	0.00	0.00	451212.55	760546.59	N 32 14 18.49 W 103 37 27.65	
Salado (Top Salt) Nudge 2°/100' DLS	1500.00	0.00	90.00	1500.00	0.00	0.00	0.00	0.00	451212.55	760546.59	N 32 14 18.49 W 103 37 27.65	
	1600.00	2.00	90.00	1599.98	0.01	0.00	1.75	2.00	451212.55	760548.34	N 32 14 18.49 W 103 37 27.63	
	1700.00	4.00	90.00	1699.84	0.04	0.00	6.98	2.00	451212.55	760553.57	N 32 14 18.49 W 103 37 27.57	
	1800.00	6.00	90.00	1799.45	0.09	0.00	15.69	2.00	451212.55	760562.28	N 32 14 18.49 W 103 37 27.47	
	1900.00	8.00	90.00	1898.70	0.17	0.00	27.88	2.00	451212.55	760574.47	N 32 14 18.49 W 103 37 27.32	
Hold Nudge	1971.90	9.44	90.00	1969.76	0.23	0.00	38.78	2.00	451212.55	760585.37	N 32 14 18.49 W 103 37 27.20	
	2000.00	9.44	90.00	1997.49	0.26	0.00	43.39	0.00	451212.55	760589.98	N 32 14 18.49 W 103 37 27.14	
	2100.00	9.44	90.00	2096.13	0.35	0.00	59.78	0.00	451212.55	760606.37	N 32 14 18.49 W 103 37 26.95	
	2200.00	9.44	90.00	2194.78	0.45	0.00	76.18	0.00	451212.55	760622.77	N 32 14 18.49 W 103 37 26.76	

Comments	MD (ft)	Incl (°)	Azim Grid (°)	TVD (ft)	VSEC (ft)	NS (ft)	EW (ft)	DLS (°/100ft)	Northing (ftUS)	Easting (ftUS)	Latitude (N/S ° ' ")	Longitude (E/W ° ' ")
	2300.00	9.44	90.00	2293.43	0.55	0.00	92.58	0.00	451212.55	760639.17	N 32 14 18.49 W 103 37 26.57	
	2400.00	9.44	90.00	2392.07	0.65	0.00	108.98	0.00	451212.55	760655.56	N 32 14 18.49 W 103 37 26.38	
	2500.00	9.44	90.00	2490.72	0.74	0.00	125.38	0.00	451212.55	760671.96	N 32 14 18.48 W 103 37 26.19	
	2600.00	9.44	90.00	2589.37	0.84	0.00	141.77	0.00	451212.55	760688.36	N 32 14 18.48 W 103 37 26.00	
	2700.00	9.44	90.00	2688.01	0.94	0.00	158.17	0.00	451212.55	760704.76	N 32 14 18.48 W 103 37 25.81	
	2800.00	9.44	90.00	2786.66	1.04	0.00	174.57	0.00	451212.55	760721.15	N 32 14 18.48 W 103 37 25.62	
	2900.00	9.44	90.00	2885.31	1.13	0.00	190.97	0.00	451212.55	760737.55	N 32 14 18.48 W 103 37 25.42	
	3000.00	9.44	90.00	2983.95	1.23	0.00	207.37	0.00	451212.55	760753.95	N 32 14 18.48 W 103 37 25.23	
	3100.00	9.44	90.00	3082.60	1.33	0.00	223.76	0.00	451212.55	760770.34	N 32 14 18.48 W 103 37 25.04	
	3200.00	9.44	90.00	3181.25	1.43	0.00	240.16	0.00	451212.55	760786.74	N 32 14 18.48 W 103 37 24.85	
	3300.00	9.44	90.00	3279.89	1.52	0.00	256.56	0.00	451212.55	760803.14	N 32 14 18.48 W 103 37 24.66	
	3400.00	9.44	90.00	3378.54	1.62	0.00	272.96	0.00	451212.55	760819.54	N 32 14 18.48 W 103 37 24.47	
	3500.00	9.44	90.00	3477.18	1.72	0.00	289.35	0.00	451212.55	760835.93	N 32 14 18.47 W 103 37 24.28	
	3600.00	9.44	90.00	3575.83	1.81	0.00	305.75	0.00	451212.55	760852.33	N 32 14 18.47 W 103 37 24.09	
	3700.00	9.44	90.00	3674.48	1.91	0.00	322.15	0.00	451212.55	760868.73	N 32 14 18.47 W 103 37 23.90	
	3800.00	9.44	90.00	3773.12	2.01	0.00	338.55	0.00	451212.55	760885.13	N 32 14 18.47 W 103 37 23.71	
	3900.00	9.44	90.00	3871.77	2.11	0.00	354.95	0.00	451212.55	760901.52	N 32 14 18.47 W 103 37 23.52	
	4000.00	9.44	90.00	3970.42	2.20	0.00	371.34	0.00	451212.55	760917.92	N 32 14 18.47 W 103 37 23.32	
	4100.00	9.44	90.00	4069.06	2.30	0.00	387.74	0.00	451212.55	760934.32	N 32 14 18.47 W 103 37 23.13	
	4200.00	9.44	90.00	4167.71	2.40	0.00	404.14	0.00	451212.55	760950.71	N 32 14 18.47 W 103 37 22.94	
	4300.00	9.44	90.00	4266.36	2.50	0.00	420.54	0.00	451212.55	760967.11	N 32 14 18.47 W 103 37 22.75	
	4400.00	9.44	90.00	4365.00	2.59	0.00	436.94	0.00	451212.55	760983.51	N 32 14 18.46 W 103 37 22.56	
	4500.00	9.44	90.00	4463.65	2.69	0.00	453.33	0.00	451212.55	760999.91	N 32 14 18.46 W 103 37 22.37	
	4600.00	9.44	90.00	4562.29	2.79	0.00	469.73	0.00	451212.55	761016.30	N 32 14 18.46 W 103 37 22.18	
Base of Salt	4688.91	9.44	90.00	4650.00	2.87	0.00	484.31	0.00	451212.55	761030.88	N 32 14 18.46 W 103 37 22.01	
	4700.00	9.44	90.00	4660.94	2.88	0.00	486.13	0.00	451212.55	761032.70	N 32 14 18.46 W 103 37 21.99	
	4800.00	9.44	90.00	4759.59	2.98	0.00	502.53	0.00	451212.55	761049.10	N 32 14 18.46 W 103 37 21.80	
	4900.00	9.44	90.00	4858.23	3.08	0.00	518.92	0.00	451212.55	761065.49	N 32 14 18.46 W 103 37 21.61	
Delaware Sands	4962.61	9.44	90.00	4920.00	3.14	0.00	529.19	0.00	451212.55	761075.76	N 32 14 18.46 W 103 37 21.49	
	5000.00	9.44	90.00	4956.88	3.18	0.00	535.32	0.00	451212.55	761081.89	N 32 14 18.46 W 103 37 21.42	
	5100.00	9.44	90.00	5055.53	3.27	0.00	551.72	0.00	451212.55	761098.29	N 32 14 18.46 W 103 37 21.22	
	5200.00	9.44	90.00	5154.17	3.37	0.00	568.12	0.00	451212.55	761114.69	N 32 14 18.46 W 103 37 21.03	
	5300.00	9.44	90.00	5252.82	3.47	0.00	584.52	0.00	451212.55	761131.08	N 32 14 18.45 W 103 37 20.84	
	5400.00	9.44	90.00	5351.47	3.57	0.00	600.91	0.00	451212.55	761147.48	N 32 14 18.45 W 103 37 20.65	
	5500.00	9.44	90.00	5450.11	3.66	0.00	617.31	0.00	451212.55	761163.88	N 32 14 18.45 W 103 37 20.46	
	5600.00	9.44	90.00	5548.76	3.76	0.00	633.71	0.00	451212.55	761180.28	N 32 14 18.45 W 103 37 20.27	
	5700.00	9.44	90.00	5647.40	3.86	0.00	650.11	0.00	451212.55	761196.67	N 32 14 18.45 W 103 37 20.08	
	5800.00	9.44	90.00	5746.05	3.96	0.00	666.51	0.00	451212.55	761213.07	N 32 14 18.45 W 103 37 19.89	
	5900.00	9.44	90.00	5844.70	4.05	0.00	682.90	0.00	451212.55	761229.47	N 32 14 18.45 W 103 37 19.70	
	6000.00	9.44	90.00	5943.34	4.15	0.00	699.30	0.00	451212.55	761245.86	N 32 14 18.45 W 103 37 19.51	
	6100.00	9.44	90.00	6041.99	4.25	0.00	715.70	0.00	451212.55	761262.26	N 32 14 18.45 W 103 37 19.32	
	6200.00	9.44	90.00	6140.64	4.34	0.00	732.10	0.00	451212.55	761278.66	N 32 14 18.45 W 103 37 19.12	
	6300.00	9.44	90.00	6239.28	4.44	0.00	748.49	0.00	451212.55	761295.06	N 32 14 18.44 W 103 37 18.93	
	6400.00	9.44	90.00	6337.93	4.54	0.00	764.89	0.00	451212.55	761311.45	N 32 14 18.44 W 103 37 18.74	
	6500.00	9.44	90.00	6436.58	4.64	0.00	781.29	0.00	451212.55	761327.85	N 32 14 18.44 W 103 37 18.55	
	6600.00	9.44	90.00	6535.22	4.73	0.00	797.69	0.00	451212.55	761344.25	N 32 14 18.44 W 103 37 18.36	
	6700.00	9.44	90.00	6633.87	4.83	0.00	814.09	0.00	451212.55	761360.64	N 32 14 18.44 W 103 37 18.17	
	6800.00	9.44	90.00	6732.52	4.93	0.00	830.48	0.00	451212.55	761377.04	N 32 14 18.44 W 103 37 17.98	
	6900.00	9.44	90.00	6831.16	5.03	0.00	846.88	0.00	451212.55	761393.44	N 32 14 18.44 W 103 37 17.79	
	7000.00	9.44	90.00	6929.81	5.12	0.00	863.28	0.00	451212.55	761409.84	N 32 14 18.44 W 103 37 17.60	
	7100.00	9.44	90.00	7028.45	5.22	0.00	879.68	0.00	451212.55	761426.23	N 32 14 18.44 W 103 37 17.41	
	7200.00	9.44	90.00	7127.10	5.32	0.00	896.07	0.00	451212.55	761442.63	N 32 14 18.43 W 103 37 17.22	
	7300.00	9.44	90.00	7225.75	5.41	0.00	912.47	0.00	451212.55	761459.03	N 32 14 18.43 W 103 37 17.02	
	7400.00	9.44	90.00	7324.39	5.51	0.00	928.87	0.00	451212.55	761475.43	N 32 14 18.43 W 103 37 16.83	
	7500.00	9.44	90.00	7423.04	5.61	0.00	945.27	0.00	451212.55	761491.82	N 32 14 18.43 W 103 37 16.64	
	7600.00	9.44	90.00	7521.69	5.71	0.00	961.67	0.00	451212.55	761508.22	N 32 14 18.43 W 103 37 16.45	
	7700.00	9.44	90.00	7620.33	5.80	0.00	978.06	0.00	451212.55	761524.62	N 32 14 18.43 W 103 37 16.26	
	7800.00	9.44	90.00	7718.98	5.90	0.00	994.46	0.00	451212.55	761541.01	N 32 14 18.43 W 103 37 16.07	

Comments	MD (ft)	Incl (°)	Azim Grid (°)	TVD (ft)	VSEC (ft)	NS (ft)	EW (ft)	DLS (°/100ft)	Northing (ftUS)	Easting (ftUS)	Latitude (N/S ° ' ")	Longitude (E/W ° ' ")
	7900.00	9.44	90.00	7817.63	6.00	0.00	1010.86	0.00	451212.55	761557.41	N 32 14 18.43 W	103 37 15.88
	8000.00	9.44	90.00	7916.27	6.10	0.00	1027.26	0.00	451212.55	761573.81	N 32 14 18.43 W	103 37 15.69
Drop to Vertical 2°/100' DLS	8084.88	9.44	90.00	8000.00	6.18	0.00	1041.18	0.00	451212.55	761587.73	N 32 14 18.42 W	103 37 15.53
	8100.00	9.14	90.00	8014.92	6.19	0.00	1043.62	2.00	451212.55	761590.17	N 32 14 18.42 W	103 37 15.50
	8200.00	7.14	90.00	8113.91	6.28	0.00	1057.77	2.00	451212.55	761604.32	N 32 14 18.42 W	103 37 15.33
	8300.00	5.14	90.00	8213.34	6.34	0.00	1068.45	2.00	451212.55	761615.00	N 32 14 18.42 W	103 37 15.21
	8400.00	3.14	90.00	8313.07	6.38	0.00	1075.67	2.00	451212.55	761622.21	N 32 14 18.42 W	103 37 15.12
	8500.00	1.14	90.00	8413.00	6.41	0.00	1079.39	2.00	451212.55	761625.94	N 32 14 18.42 W	103 37 15.08
Hold Vertical	8556.77	0.00	90.00	8469.76	6.41	0.00	1079.95	2.00	451212.55	761626.50	N 32 14 18.42 W	103 37 15.08
	8600.00	0.00	90.00	8512.99	6.41	0.00	1079.95	0.00	451212.55	761626.50	N 32 14 18.42 W	103 37 15.08
	8700.00	0.00	90.00	8612.99	6.41	0.00	1079.95	0.00	451212.55	761626.50	N 32 14 18.42 W	103 37 15.08
	8800.00	0.00	90.00	8712.99	6.41	0.00	1079.95	0.00	451212.55	761626.50	N 32 14 18.42 W	103 37 15.08
	8900.00	0.00	90.00	8812.99	6.41	0.00	1079.95	0.00	451212.55	761626.50	N 32 14 18.42 W	103 37 15.08
Bone Spring	8902.01	0.00	90.00	8815.00	6.41	0.00	1079.95	0.00	451212.55	761626.50	N 32 14 18.42 W	103 37 15.08
	9000.00	0.00	90.00	8912.99	6.41	0.00	1079.95	0.00	451212.55	761626.50	N 32 14 18.42 W	103 37 15.08
	9100.00	0.00	90.00	9012.99	6.41	0.00	1079.95	0.00	451212.55	761626.50	N 32 14 18.42 W	103 37 15.08
	9200.00	0.00	90.00	9112.99	6.41	0.00	1079.95	0.00	451212.55	761626.50	N 32 14 18.42 W	103 37 15.08
KOP - Build 12°/100' DLS	9209.54	0.00	90.00	9122.54	6.41	0.00	1079.95	0.00	451212.55	761626.50	N 32 14 18.42 W	103 37 15.08
	9300.00	10.85	179.66	9212.45	14.95	-8.54	1080.00	12.00	451204.01	761626.55	N 32 14 18.34 W	103 37 15.08
	9400.00	22.85	179.66	9307.98	43.89	-37.48	1080.18	12.00	451175.07	761626.73	N 32 14 18.05 W	103 37 15.08
	9500.00	34.85	179.66	9395.41	92.06	-85.65	1080.46	12.00	451126.90	761627.01	N 32 14 17.57 W	103 37 15.08
	9600.00	46.85	179.66	9470.90	157.36	-150.95	1080.85	12.00	451061.61	761627.40	N 32 14 16.93 W	103 37 15.08
	9700.00	58.85	179.66	9531.18	236.92	-230.51	1081.32	12.00	450982.05	761627.87	N 32 14 16.14 W	103 37 15.08
	9800.00	70.85	179.66	9573.59	327.28	-320.87	1081.86	12.00	450891.69	761628.41	N 32 14 15.25 W	103 37 15.08
	9900.00	82.85	179.66	9596.29	424.48	-418.07	1082.43	12.00	450794.50	761628.98	N 32 14 14.29 W	103 37 15.08
Landing Point	9959.54	90.00	179.66	9600.00	483.87	-477.46	1082.79	12.00	450735.11	761629.34	N 32 14 13.70 W	103 37 15.08
	10000.00	90.00	179.66	9600.00	524.33	-517.91	1083.03	0.00	450694.66	761629.58	N 32 14 13.30 W	103 37 15.08
	10100.00	90.00	179.66	9600.00	624.33	-617.91	1083.62	0.00	450594.66	761630.17	N 32 14 12.31 W	103 37 15.08
	10200.00	90.00	179.66	9600.00	724.33	-717.91	1084.21	0.00	450494.67	761630.76	N 32 14 11.32 W	103 37 15.08
	10300.00	90.00	179.66	9600.00	824.33	-817.91	1084.81	0.00	450394.67	761631.36	N 32 14 10.33 W	103 37 15.08
	10400.00	90.00	179.66	9600.00	924.33	-917.91	1085.40	0.00	450294.68	761631.95	N 32 14 9.34 W	103 37 15.08
	10500.00	90.00	179.66	9600.00	1024.33	-1017.90	1085.99	0.00	450194.68	761632.54	N 32 14 8.35 W	103 37 15.08
	10600.00	90.00	179.66	9600.00	1124.33	-1117.90	1086.59	0.00	450094.69	761633.14	N 32 14 7.36 W	103 37 15.08
	10700.00	90.00	179.66	9600.00	1224.33	-1217.90	1087.18	0.00	449994.70	761633.73	N 32 14 6.37 W	103 37 15.08
	10800.00	90.00	179.66	9600.00	1324.33	-1317.90	1087.77	0.00	449894.70	761634.32	N 32 14 5.38 W	103 37 15.09
	10900.00	90.00	179.66	9600.00	1424.33	-1417.90	1088.37	0.00	449794.71	761634.92	N 32 14 4.39 W	103 37 15.09
	11000.00	90.00	179.66	9600.00	1524.33	-1517.89	1088.96	0.00	449694.71	761635.51	N 32 14 3.40 W	103 37 15.09
	11100.00	90.00	179.66	9600.00	1624.33	-1617.89	1089.55	0.00	449594.72	761636.10	N 32 14 2.41 W	103 37 15.09
	11200.00	90.00	179.66	9600.00	1724.33	-1717.89	1090.15	0.00	449494.72	761636.70	N 32 14 1.42 W	103 37 15.09
	11300.00	90.00	179.66	9600.00	1824.33	-1817.89	1090.74	0.00	449394.73	761637.29	N 32 14 0.43 W	103 37 15.09
	11400.00	90.00	179.66	9600.00	1924.33	-1917.89	1091.33	0.00	449294.73	761637.88	N 32 13 59.44 W	103 37 15.09
	11500.00	90.00	179.66	9600.00	2024.33	-2017.89	1091.93	0.00	449194.74	761638.48	N 32 13 58.45 W	103 37 15.09
	11600.00	90.00	179.66	9600.00	2124.33	-2117.88	1092.52	0.00	449094.75	761639.07	N 32 13 57.47 W	103 37 15.09
	11700.00	90.00	179.66	9600.00	2224.33	-2217.88	1093.11	0.00	448994.75	761639.66	N 32 13 56.48 W	103 37 15.09
	11800.00	90.00	179.66	9600.00	2324.33	-2317.88	1093.71	0.00	448894.76	761640.26	N 32 13 55.49 W	103 37 15.09
	11900.00	90.00	179.66	9600.00	2424.33	-2417.88	1094.30	0.00	448794.76	761640.85	N 32 13 54.50 W	103 37 15.09
	12000.00	90.00	179.66	9600.00	2524.33	-2517.88	1094.89	0.00	448694.77	761641.44	N 32 13 53.51 W	103 37 15.10
	12100.00	90.00	179.66	9600.00	2624.33	-2617.88	1095.49	0.00	448594.77	761642.04	N 32 13 52.52 W	103 37 15.10
	12200.00	90.00	179.66	9600.00	2724.33	-2717.87	1096.08	0.00	448494.78	761642.63	N 32 13 51.53 W	103 37 15.10
	12300.00	90.00	179.66	9600.00	2824.33	-2817.87	1096.67	0.00	448394.78	761643.22	N 32 13 50.54 W	103 37 15.10
	12400.00	90.00	179.66	9600.00	2924.33	-2917.87	1097.27	0.00	448294.79	761643.82	N 32 13 49.55 W	103 37 15.10
	12500.00	90.00	179.66	9600.00	3024.33	-3017.87	1097.86	0.00	448194.80	761644.41	N 32 13 48.56 W	103 37 15.10
	12600.00	90.00	179.66	9600.00	3124.33	-3117.87	1098.45	0.00	448094.80	761645.00	N 32 13 47.57 W	103 37 15.10
	12700.00	90.00	179.66	9600.00	3224.33	-3217.86	1099.05	0.00	447994.81	761645.60	N 32 13 46.58 W	103 37 15.10
	12800.00	90.00	179.66	9600.00	3324.33	-3317.86	1099.64	0.00	447894.81	761646.19	N 32 13 45.59 W	103 37 15.10
	12900.00	90.00	179.66	9600.00	3424.33	-3417.86	1100.23	0.00	447794.82	761646.78	N 32 13 44.60 W	103 37 15.10
	13000.00	90.00	179.66	9600.00	3524.33	-3517.86	1100.83	0.00	447694.82	761647.38	N 32 13 43.61 W	103 37 15.10

Comments	MD (ft)	Incl (°)	Azim Grid (°)	TVD (ft)	VSEC (ft)	NS (ft)	EW (ft)	DLS (°/100ft)	Northing (ftUS)	Easting (ftUS)	Latitude (N/S ° ' ")	Longitude (E/W ° ' ")
	13100.00	90.00	179.66	9600.00	3624.33	-3617.86	1101.42	0.00	447594.83	761647.97	N 32 13 42.62 W	103 37 15.10
	13200.00	90.00	179.66	9600.00	3724.33	-3717.86	1102.01	0.00	447494.83	761648.56	N 32 13 41.63 W	103 37 15.11
	13300.00	90.00	179.66	9600.00	3824.33	-3817.85	1102.61	0.00	447394.84	761649.16	N 32 13 40.64 W	103 37 15.11
	13400.00	90.00	179.66	9600.00	3924.33	-3917.85	1103.20	0.00	447294.85	761649.75	N 32 13 39.65 W	103 37 15.11
	13500.00	90.00	179.66	9600.00	4024.33	-4017.85	1103.80	0.00	447194.85	761650.34	N 32 13 38.66 W	103 37 15.11
	13600.00	90.00	179.66	9600.00	4124.33	-4117.85	1104.39	0.00	447094.86	761650.94	N 32 13 37.67 W	103 37 15.11
	13700.00	90.00	179.66	9600.00	4224.33	-4217.85	1104.98	0.00	446994.86	761651.53	N 32 13 36.69 W	103 37 15.11
	13800.00	90.00	179.66	9600.00	4324.33	-4317.85	1105.58	0.00	446894.87	761652.12	N 32 13 35.70 W	103 37 15.11
	13900.00	90.00	179.66	9600.00	4424.33	-4417.84	1106.17	0.00	446794.87	761652.72	N 32 13 34.71 W	103 37 15.11
	14000.00	90.00	179.66	9600.00	4524.33	-4517.84	1106.76	0.00	446694.88	761653.31	N 32 13 33.72 W	103 37 15.11
	14100.00	90.00	179.66	9600.00	4624.33	-4617.84	1107.36	0.00	446594.88	761653.90	N 32 13 32.73 W	103 37 15.11
	14200.00	90.00	179.66	9600.00	4724.33	-4717.84	1107.95	0.00	446494.89	761654.50	N 32 13 31.74 W	103 37 15.11
	14300.00	90.00	179.66	9600.00	4824.33	-4817.84	1108.54	0.00	446394.90	761655.09	N 32 13 30.75 W	103 37 15.11
	14400.00	90.00	179.66	9600.00	4924.33	-4917.83	1109.14	0.00	446294.90	761655.68	N 32 13 29.76 W	103 37 15.12
	14500.00	90.00	179.66	9600.00	5024.33	-5017.83	1109.73	0.00	446194.91	761656.28	N 32 13 28.77 W	103 37 15.12
	14600.00	90.00	179.66	9600.00	5124.33	-5117.83	1110.32	0.00	446094.91	761656.87	N 32 13 27.78 W	103 37 15.12
	14700.00	90.00	179.66	9600.00	5224.33	-5217.83	1110.92	0.00	445994.92	761657.46	N 32 13 26.79 W	103 37 15.12
	14800.00	90.00	179.66	9600.00	5324.33	-5317.83	1111.51	0.00	445894.92	761658.06	N 32 13 25.80 W	103 37 15.12
	14900.00	90.00	179.66	9600.00	5424.33	-5417.83	1112.10	0.00	445794.93	761658.65	N 32 13 24.81 W	103 37 15.12
	15000.00	90.00	179.66	9600.00	5524.33	-5517.82	1112.70	0.00	445694.93	761659.24	N 32 13 23.82 W	103 37 15.12
	15100.00	90.00	179.66	9600.00	5624.33	-5617.82	1113.29	0.00	445594.94	761659.84	N 32 13 22.83 W	103 37 15.12
	15200.00	90.00	179.66	9600.00	5724.33	-5717.82	1113.88	0.00	445494.95	761660.43	N 32 13 21.84 W	103 37 15.12
	15300.00	90.00	179.66	9600.00	5824.33	-5817.82	1114.48	0.00	445394.95	761661.02	N 32 13 20.85 W	103 37 15.12
	15400.00	90.00	179.66	9600.00	5924.33	-5917.82	1115.07	0.00	445294.96	761661.62	N 32 13 19.86 W	103 37 15.12
	15500.00	90.00	179.66	9600.00	6024.33	-6017.82	1115.66	0.00	445194.96	761662.21	N 32 13 18.87 W	103 37 15.12
	15600.00	90.00	179.66	9600.00	6124.33	-6117.81	1116.26	0.00	445094.97	761662.80	N 32 13 17.88 W	103 37 15.12
	15700.00	90.00	179.66	9600.00	6224.33	-6217.81	1116.85	0.00	444994.97	761663.40	N 32 13 16.90 W	103 37 15.13
	15800.00	90.00	179.66	9600.00	6324.33	-6317.81	1117.44	0.00	444894.98	761663.99	N 32 13 15.91 W	103 37 15.13
	15900.00	90.00	179.66	9600.00	6424.33	-6417.81	1118.04	0.00	444794.98	761664.58	N 32 13 14.92 W	103 37 15.13
	16000.00	90.00	179.66	9600.00	6524.33	-6517.81	1118.63	0.00	444694.99	761665.18	N 32 13 13.93 W	103 37 15.13
	16100.00	90.00	179.66	9600.00	6624.33	-6617.81	1119.22	0.00	444595.00	761665.77	N 32 13 12.94 W	103 37 15.13
	16200.00	90.00	179.66	9600.00	6724.33	-6717.80	1119.82	0.00	444495.00	761666.36	N 32 13 11.95 W	103 37 15.13
	16300.00	90.00	179.66	9600.00	6824.33	-6817.80	1120.41	0.00	444395.01	761666.96	N 32 13 10.96 W	103 37 15.13
	16400.00	90.00	179.66	9600.00	6924.33	-6917.80	1121.00	0.00	444295.01	761667.55	N 32 13 9.97 W	103 37 15.13
	16500.00	90.00	179.66	9600.00	7024.33	-7017.80	1121.60	0.00	444195.02	761668.14	N 32 13 8.98 W	103 37 15.13
	16600.00	90.00	179.66	9600.00	7124.33	-7117.80	1122.19	0.00	444095.02	761668.74	N 32 13 7.99 W	103 37 15.13
	16700.00	90.00	179.66	9600.00	7224.33	-7217.79	1122.78	0.00	443995.03	761669.33	N 32 13 7.00 W	103 37 15.13
	16800.00	90.00	179.66	9600.00	7324.33	-7317.79	1123.38	0.00	443895.03	761669.92	N 32 13 6.01 W	103 37 15.13
	16900.00	90.00	179.66	9600.00	7424.33	-7417.79	1123.97	0.00	443795.04	761670.52	N 32 13 5.02 W	103 37 15.14
	17000.00	90.00	179.66	9600.00	7524.33	-7517.79	1124.56	0.00	443695.05	761671.11	N 32 13 4.03 W	103 37 15.14
	17100.00	90.00	179.66	9600.00	7624.33	-7617.79	1125.16	0.00	443595.05	761671.70	N 32 13 3.04 W	103 37 15.14
	17200.00	90.00	179.66	9600.00	7724.33	-7717.79	1125.75	0.00	443495.06	761672.30	N 32 13 2.05 W	103 37 15.14
	17300.00	90.00	179.66	9600.00	7824.33	-7817.78	1126.34	0.00	443395.06	761672.89	N 32 13 1.06 W	103 37 15.14
	17400.00	90.00	179.66	9600.00	7924.33	-7917.78	1126.94	0.00	443295.07	761673.48	N 32 13 0.07 W	103 37 15.14
	17500.00	90.00	179.66	9600.00	8024.33	-8017.78	1127.53	0.00	443195.07	761674.08	N 32 12 59.08 W	103 37 15.14
	17600.00	90.00	179.66	9600.00	8124.33	-8117.78	1128.12	0.00	443095.08	761674.67	N 32 12 58.09 W	103 37 15.14
	17700.00	90.00	179.66	9600.00	8224.33	-8217.78	1128.72	0.00	442995.08	761675.26	N 32 12 57.10 W	103 37 15.14
	17800.00	90.00	179.66	9600.00	8324.33	-8317.78	1129.31	0.00	442895.09	761675.86	N 32 12 56.12 W	103 37 15.14
	17900.00	90.00	179.66	9600.00	8424.33	-8417.77	1129.90	0.00	442795.10	761676.45	N 32 12 55.13 W	103 37 15.14
	18000.00	90.00	179.66	9600.00	8524.33	-8517.77	1130.50	0.00	442695.10	761677.04	N 32 12 54.14 W	103 37 15.14
	18100.00	90.00	179.66	9600.00	8624.33	-8617.77	1131.09	0.00	442595.11	761677.64	N 32 12 53.15 W	103 37 15.15
	18200.00	90.00	179.66	9600.00	8724.33	-8717.77	1131.68	0.00	442495.11	761678.23	N 32 12 52.16 W	103 37 15.15
	18300.00	90.00	179.66	9600.00	8824.33	-8817.77	1132.28	0.00	442395.12	761678.82	N 32 12 51.17 W	103 37 15.15
	18400.00	90.00	179.66	9600.00	8924.33	-8917.76	1132.87	0.00	442295.12	761679.42	N 32 12 50.18 W	103 37 15.15
	18500.00	90.00	179.66	9600.00	9024.33	-9017.76	1133.46	0.00	442195.13	761680.01	N 32 12 49.19 W	103 37 15.15
	18600.00	90.00	179.66	9600.00	9124.33	-9117.76	1134.06	0.00	442095.13	761680.60	N 32 12 48.20 W	103 37 15.15
	18700.00	90.00	179.66	9600.00	9224.33	-9217.76	1134.65	0.00	441995.14	761681.20	N 32 12 47.21 W	103 37 15.15
	18800.00	90.00	179.66	9600.00	9324.33	-9317.76	1135.24	0.00	441895.15	761681.79	N 32 12 46.22 W	103 37 15.15
	18900.00	90.00	179.66	9600.00	9424.33	-9417.76	1135.84	0.00	441795.15	761682.38	N 32 12 45.23 W	103 37 15.15

Comments	MD (ft)	Incl (°)	Azim Grid (°)	TVD (ft)	VSEC (ft)	NS (ft)	EW (ft)	DLS (°/100ft)	Northing (ftUS)	Easting (ftUS)	Latitude (N/S ° ' ")	Longitude (E/W ° ' ")
	19000.00	90.00	179.66	9600.00	9524.33	-9517.75	1136.43	0.00	441695.16	761682.98	N 32 12 44.24 W 103 37 15.15	
	19100.00	90.00	179.66	9600.00	9624.33	-9617.75	1137.02	0.00	441595.16	761683.57	N 32 12 43.25 W 103 37 15.15	
	19200.00	90.00	179.66	9600.00	9724.33	-9717.75	1137.62	0.00	441495.17	761684.16	N 32 12 42.26 W 103 37 15.15	
	19300.00	90.00	179.66	9600.00	9824.33	-9817.75	1138.21	0.00	441395.17	761684.76	N 32 12 41.27 W 103 37 15.15	
	19400.00	90.00	179.66	9600.00	9924.33	-9917.75	1138.80	0.00	441295.18	761685.35	N 32 12 40.28 W 103 37 15.16	
	19500.00	90.00	179.66	9600.00	10024.33	-10017.75	1139.40	0.00	441195.18	761685.94	N 32 12 39.29 W 103 37 15.16	
Cimarex Dos Equis 12-13 Federal Com #6H - PBHL [100' FSL, 330' FEL]	19576.81	90.00	179.66	9600.00	10101.14	-10094.55	1139.85	0.00	441118.38	761686.40	N 32 12 38.53 W 103 37 15.16	

Survey Type: Non-Def Plan

Survey Error Model: ISCWSA Rev 0 \*\*\* 3-D 95.000% Confidence 2.7955 sigma

Survey Program:

Description	Part	MD From (ft)	MD To (ft)	EOU Freq (ft)	Hole Size (in)	Casing Diameter (in)	Expected Max Inclination (deg)	Survey Tool Type	Borehole / Survey
	1	0.000	26.000	1/100.000	30.000	30.000		NAL_MWD_IFR1+MS-Depth Only	Dos Equis 12-13 Federal Com #6H / Cimarex Dos Equis 12-13 Federal Com #6H - Rev0 RM
	1	26.000	19576.809	1/100.000	30.000	30.000		NAL_MWD_IFR1+MS	Dos Equis 12-13 Federal Com #6H / Cimarex Dos Equis 12-13

**1. Geological Formations**

TVD of target 9,600  
MD at TD 19,577

Pilot Hole TD N/A  
Deepest expected fresh water

Formation	Depth (TVD) from KB	Water/Mineral Bearing/Target Zone	Hazards
Rustler	1185	N/A	
Salado (Top Salt)	1500	N/A	
Base of Salt	4650	N/A	
Delaware Sands	4920	N/A	
Bone Spring	8815	Hydrocarbons	
Bone Spring Target	9600	Hydrocarbons	
1st Bone Spring Sand	9910	Hydrocarbons	
2nd Bone Spring Sand	10635	Hydrocarbons	
3rd Bone Spring	11835	Hydrocarbons	
Wolfcamp	12245	Hydrocarbons	

**2. Casing Program**

Hole Size	Casing Depth From	Casing Depth To	Setting Depth TVD	Casing Size	Weight (lb/ft)	Grade	Conn.	SF Collapse	SF Burst	SF Tension
17 1/2	0	1235	1235	13-3/8"	48.00	H-40/J-55 Hybrid	ST&C	1.31	3.06	5.43
12 1/4	0	4900	4900	9-5/8"	40.00	J-55	LT&C	1.51	1.52	2.65
8 3/4	0	9210	9210	5-1/2"	20.00	L-80	LT&C	2.05	2.13	2.17
8 3/4	9210	19577	9600	5-1/2"	20.00	L-80	BT&C	1.97	2.00	59.74
BLM Minimum Safety Factor								1.125	1	1.6 Dry 1.8 Wet

TVD was used on all calculations.

All casing strings will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.h

	Y or N
Is casing new? If used, attach certification as required in Onshore Order #1	Y
Does casing meet API specifications? If no, attach casing specification sheet.	Y
Is premium or uncommon casing planned? If yes attach casing specification sheet.	N
Does the above casing design meet or exceed BLM's minimum standards? If not provide justification (loading assumptions, casing design criteria).	Y
Will the intermediate pipe be kept at a minimum 1/3 fluid filled to avoid approaching the collapse pressure rating of the casing?	Y
Is well located within Capitan Reef?	N
If yes, does production casing cement tie back a minimum of 50' above the Reef?	N
Is well within the designated 4 string boundary.	N
Is well located in SOPA but not in R-111-P?	N
If yes, are the first 2 strings cemented to surface and 3rd string cement tied back 500' into previous casing?	N
Is well located in R-111-P and SOPA?	N
If yes, are the first three strings cemented to surface?	N
Is 2nd string set 100' to 600' below the base of salt?	N
Is well located in high Cave/Karst?	N
If yes, are there two strings cemented to surface?	N
(For 2 string wells) If yes, is there a contingency casing if lost circulation occurs?	N
Is well located in critical Cave/Karst?	N
If yes, are there three strings cemented to surface?	N
Is AC Report included?	N

**3. Cementing Program**

Casing	# Sk	Wt. lb/gal	Yld ft <sup>3</sup> /sack	H <sub>2</sub> O gal/sk	500# Comp. Strength (hours)	Slurry Description
Surface	599	13.50	1.72	9.15	15.5	Lead: Class C + Bentonite
	160	14.80	1.34	6.32	9.5	Tail: Class C + LCM
Intermediate	919	12.90	1.88	9.65	12	Lead: 35:65 (Poz:C) + Salt + Bentonite
	286	14.80	1.34	6.32	9.5	Tail: Class C + LCM
Production	389	10.30	3.64	22.18		Lead: Tuned Light + LCM
	2217	14.20	1.30	5.86	14:30	Tail: 50:50 (Poz:H) + Salt + Bentonite + Fluid Loss + Dispersant + SMS

Casing String	TOC	% Excess
Surface	0	45
Intermediate	0	51
Production	4700	14



**4. Pressure Control Equipment**

A variance is requested for the use of a diverter on the surface casing. See attached for schematic.					
BOP installed and tested before drilling which hole?	Size	Min Required WP	Type		Tested To
12 1/4	13 5/8	2M	Annular	X	50% of working pressure
			Blind Ram		2M
			Pipe Ram		
			Double Ram	X	
			Other		
8 3/4	13 5/8	3M	Annular	X	50% of working pressure
			Blind Ram		3M
			Pipe Ram		
			Double Ram	X	
			Other		

BOP/BOPE will be tested by an independent service company to 250 psi low and the high pressure indicated above per Onshore Order 2 requirements. The System may be upgraded to a higher pressure but still tested to the working pressure listed in the table above. If the system is upgraded all the components installed will be functional and tested.

Pipe rams will be operationally checked each 24 hour period. Blind rams will be operationally checked on each trip out of the hole. These checks will be noted on the daily tour sheets. Other accessories to the BOP equipment will include a Kelly cock and floor safety valve (inside BOP) and choke lines and choke manifold. See attached schematics.

	Formation integrity test will be performed per Onshore Order #2. On Exploratory wells or on that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.i.				
X	A variance is requested for the use of a flexible choke line from the BOP to Choke Manifold. See attached for specs and hydrostatic test chart.				
N	Are anchors required by manufacturer?				

**5. Mud Program**

Depth	Type	Weight (ppg)	Viscosity	Water Loss
0' to 1235'	FW Spud Mud	8.30 - 8.80	30-32	N/C
1235' to 4900'	Brine Water	9.70 - 10.20	30-32	N/C
4900' to 19577'	FW/Cut Brine	8.50 - 9.00	30-32	N/C

Sufficient mud materials to maintain mud properties and meet minimum lost circulation and weight increase requirements will be kept on location at all times.

What will be used to monitor the loss or gain of fluid?	PVT/Pason/Visual Monitoring
---	-----------------------------

**6. Logging and Testing Procedures**

Logging, Coring and Testing	
<input type="checkbox"/>	Will run GR/CNL from TD to surface (horizontal well – vertical portion of hole). Stated logs run will be in the Completion Report and submitted to the BLM.
<input type="checkbox"/>	No logs are planned based on well control or offset log information.
<input type="checkbox"/>	Drill stem test?
<input type="checkbox"/>	Coring?

Additional Logs Planned	Interval
-------------------------	----------

**7. Drilling Conditions**

Condition	
BH Pressure at deepest TVD	4492 psi
Abnormal Temperature	No

Hydrogen Sulfide (H<sub>2</sub>S) monitors will be installed prior to drilling out the surface shoe. If H<sub>2</sub>S is detected in concentrations greater than 100 ppm, the operator will comply with the provisions of Onshore Oil and Gas Order #6. If Hydrogen Sulfide is encountered, measured values and formations will be provided to the BLM.

<input checked="" type="checkbox"/>	H <sub>2</sub> S is present
<input checked="" type="checkbox"/>	H <sub>2</sub> S plan is attached

**8. Other Facets of Operation****9. Wellhead**

A multi-bowl wellhead system will be utilized.

After running the 13-3/8" surface casing, a 13 5/8" BOP/BOPE system with a minimum working pressure of 3000 psi will be installed on the wellhead system and will be pressure tested to 250 psi low followed by a 3000 psi test. Annular will be tested to 50% of working pressure. The pressure test will be repeated at least every 30 days, as per Onshore Order No. 2.

The multi-bowl wellhead will be installed by vendor's representative. A copy of the installation instructions has been sent to the BLM field office.

The wellhead will be installed by a third-party welder while being monitored by the wellhead vendor representative.

All BOP equipment will be tested utilizing a conventional test plug. Not a cup or J-packer type.

A solid steel body pack-off will be utilized after running and cementing the intermediate casing. After installation the pack-off and lower flange will be pressure tested to 3000 psi.

The surface casing string will be tested as per Onshore Order No. 2 to at least 0.22 psi/ft or 1500 psi, whichever is greater.

The casing string utilizing steel body pack-off will be tested to 70% of casing burst.

If well conditions dictate conventional slips will be set and BOPE will be tested to appropriate pressures based on permitted pressure requirements.



U.S. Department of the Interior  
BUREAU OF LAND MANAGEMENT

## PWD Data Report

10/24/2019

APD ID: 10400037729

Submission Date: 01/08/2019

Operator Name: CIMAREX ENERGY COMPANY

Well Name: DOS EQUIS 12-13 FEDERAL COM

Well Number: 6H

Well Type: OIL WELL

Well Work Type: Drill

### Section 1 - General

Would you like to address long-term produced water disposal? NO

### Section 2 - Lined Pits

Would you like to utilize Lined Pit PWD options? NO

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Lined pit PWD on or off channel:

Lined pit PWD discharge volume (bbl/day):

Lined pit specifications:

Pit liner description:

Pit liner manufacturers information:

Precipitated solids disposal:

Describe precipitated solids disposal:

Precipitated solids disposal permit:

Lined pit precipitated solids disposal schedule:

Lined pit precipitated solids disposal schedule attachment:

Lined pit reclamation description:

Lined pit reclamation attachment:

Leak detection system description:

Leak detection system attachment:

**Operator Name:** CIMAREX ENERGY COMPANY

**Well Name:** DOS EQUIS 12-13 FEDERAL COM

**Well Number:** 6H

**Lined pit Monitor description:**

**Lined pit Monitor attachment:**

**Lined pit: do you have a reclamation bond for the pit?**

**Is the reclamation bond a rider under the BLM bond?**

**Lined pit bond number:**

**Lined pit bond amount:**

**Additional bond information attachment:**

### **Section 3 - Unlined Pits**

**Would you like to utilize Unlined Pit PWD options?** NO

**Produced Water Disposal (PWD) Location:**

**PWD disturbance (acres):**

**PWD surface owner:**

**Unlined pit PWD on or off channel:**

**Unlined pit PWD discharge volume (bbl/day):**

**Unlined pit specifications:**

**Precipitated solids disposal:**

**Describe precipitated solids disposal:**

**Precipitated solids disposal permit:**

**Unlined pit precipitated solids disposal schedule:**

**Unlined pit precipitated solids disposal schedule attachment:**

**Unlined pit reclamation description:**

**Unlined pit reclamation attachment:**

**Unlined pit Monitor description:**

**Unlined pit Monitor attachment:**

**Do you propose to put the produced water to beneficial use?**

**Beneficial use user confirmation:**

**Estimated depth of the shallowest aquifer (feet):**

**Does the produced water have an annual average Total Dissolved Solids (TDS) concentration equal to or less than that of the existing water to be protected?**

**TDS lab results:**

**Geologic and hydrologic evidence:**

**State authorization:**

**Unlined Produced Water Pit Estimated percolation:**

**Unlined pit: do you have a reclamation bond for the pit?**

**Operator Name:** CIMAREX ENERGY COMPANY

**Well Name:** DOS EQUIS 12-13 FEDERAL COM

**Well Number:** 6H

**Is the reclamation bond a rider under the BLM bond?**

**Unlined pit bond number:**

**Unlined pit bond amount:**

**Additional bond information attachment:**

#### **Section 4 - Injection**

**Would you like to utilize Injection PWD options?** NO

**Produced Water Disposal (PWD) Location:**

**PWD surface owner:**

**PWD disturbance (acres):**

**Injection PWD discharge volume (bbl/day):**

**Injection well mineral owner:**

**Injection well type:**

**Injection well number:**

**Injection well name:**

**Assigned injection well API number?**

**Injection well API number:**

**Injection well new surface disturbance (acres):**

**Minerals protection information:**

**Mineral protection attachment:**

**Underground Injection Control (UIC) Permit?**

**UIC Permit attachment:**

#### **Section 5 - Surface Discharge**

**Would you like to utilize Surface Discharge PWD options?** NO

**Produced Water Disposal (PWD) Location:**

**PWD surface owner:**

**PWD disturbance (acres):**

**Surface discharge PWD discharge volume (bbl/day):**

**Surface Discharge NPDES Permit?**

**Surface Discharge NPDES Permit attachment:**

**Surface Discharge site facilities information:**

**Surface discharge site facilities map:**

#### **Section 6 - Other**

**Would you like to utilize Other PWD options?** NO

**Produced Water Disposal (PWD) Location:**

**PWD surface owner:**

**PWD disturbance (acres):**

**Operator Name:** CIMAREX ENERGY COMPANY

**Well Name:** DOS EQUIS 12-13 FEDERAL COM

**Well Number:** 6H

**Other PWD type description:**

**Other PWD type attachment:**

**Have other regulatory requirements been met?**

**Other regulatory requirements attachment:**



U.S. Department of the Interior  
BUREAU OF LAND MANAGEMENT

## Bond Info Data Report

10/24/2019

APD ID: 10400037729

Submission Date: 01/08/2019

Operator Name: CIMAREX ENERGY COMPANY

Well Name: DOS EQUIS 12-13 FEDERAL COM

Well Number: 6H

Well Type: OIL WELL

Well Work Type: Drill

highlighted data  
criteria for most  
recent changes

[Show Final Text](#)

### Bond Information

Federal/Indian APD: FED

BLM Bond number: NMB001188

BIA Bond number:

Do you have a reclamation bond? NO

Is the reclamation bond a rider under the BLM bond?

Is the reclamation bond BLM or Forest Service?

BLM reclamation bond number:

Forest Service reclamation bond number:

Forest Service reclamation bond attachment:

Reclamation bond number:

Reclamation bond amount:

Reclamation bond rider amount:

Additional reclamation bond information attachment: