

Submit 3 Copies To Appropriate District Office
District I
1625 N. French Dr., Hobbs, NM 88240
District II
1301 W. Grand Ave., Artesia, NM 88210
District III
1000 Rio Brazos Rd., Aztec, NM 87410
District IV
1220 S. St. Francis Dr., Santa Fe, NM 87505

State of New Mexico
Energy, Minerals and Natural Resources

Form C-103
May 27, 2004

OIL CONSERVATION DIVISION
1220 South St. Francis Dr.
Santa Fe, NM 87505

WELL API NO.
30-025-06913

5. Indicate Type of Lease
STATE ☐ FEE ☒

6. State Oil & Gas Lease No.
317230

7. Lease Name or Unit Agreement Name

Henderson, V.M.

8. Well Number: 7

9. OGRID Number

10. Pool name or Wildcat
Drinkard

SUNDRY NOTICES AND REPORTS ON WELLS

(DO NOT USE THIS FORM FOR PROPOSALS TO DRILL OR TO DEEPEN OR PLUG BACK TO A DIFFERENT RESERVOIR. USE "APPLICATION FOR PERMIT" (FORM C-101) FOR SUCH PROPOSALS.)

1. Type of Well: Oil Well ☒ Gas Well ☐ Other:

2. Name of Operator
Chevron USA Inc.

3. Address of Operator
P.O. Box 7139, Midland, Texas, 79708

4. Well Location

Unit Letter F : 1980 feet from the North line and 1980 feet from the West line
Section 30 Township 21S Range 37E NMPM County Lea

11. Elevation (Show whether DR, RKB, RT, GR, etc.)
3490' GL

Pit or Below-grade Tank Application ☐ or Closure ☐

Pit type STEEL Depth to Groundwater 65 Distance from nearest fresh water well over 1000 Distance from nearest surface water

Pit Liner Thickness: mil Below-Grade Tank: Volume bbls; Construction Material

12. Check Appropriate Box to Indicate Nature of Notice, Report or Other Data

NOTICE OF INTENTION TO:

PERFORM REMEDIAL WORK ☐ PLUG AND ABANDON ☒
TEMPORARILY ABANDON ☐ CHANGE PLANS ☐
PULL OR ALTER CASING ☐ MULTIPLE COMPL ☐

OTHER: ☐


SUBSEQUENT REPORT OF:

REMEDIAL WORK ☐ ALTERING CASING ☐
COMMENCE DRILLING OPNS. ☐ P AND A ☐
CASING/CEMENT JOB ☐

OTHER: ☐

13. Describe proposed or completed operations. (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work). SEE RULE 1103. For Multiple Completions: Attach wellbore diagram of proposed completion or recompletion.

1. Notify NMOCD 24 hrs. prior to MI&RU.
2. RIH in "Z" string and spot 65sx of cement from 6617'-2,700' (Drinkard, Tubbs, Glorieta, San Andres, Grayburg, Queen, 8 5/8" shoe). WOC Tag.
3. RIH in "X" string, tag PBTD of 3,812' and spot 20sx of cement from 3,812'-2,700' (Grayburg, Queen, 8 5/8" shoe). WOC Tag.
4. RIH in "Y" string and spot 40sx of cement from 5,172'-2,700' (Glorieta, San Andres, Grayburg, Queen, 8 5/8" shoe) WOC Tag.
5. Cut and pull "Z", "X" and "Y" string from 2,700' for a total of 8,100' of tubing.
6. Displace hole w/MLF, 9.5 ppg brine w/12.5 gel p/bbl.
7. Spot 110sx of cement from 2,700'-2,355' (B. salt).
8. Spot 60sx of cement from 1,460'-1,250' (T. salt).
9. Spot 115sx of cement from 410'-surface, WOC Tag (11-3/4" shoe, fresh water, surface).
10. Install dry hole marker.



I hereby certify that the information above is true and complete to the best of my knowledge and belief. I further certify that any pit or below-grade tank has been/will be constructed or closed according to NMOCD guidelines ☐, a general permit ☐ or an (attached) alternative OCD-approved plan ☐.

SIGNATURE M. Lee Roark TITLE Agent DATE 6/1/2006

Type or print name M. Lee Roark
For State Use Only

E-mail address:

Telephone No. (432) 561-8600

OCD FIELD REPRESENTATIVE II/STAFF MANAGER


APPROVED BY: Gayle W. Wink
Conditions of Approval (if any):

TITLE DATE JUN 06 2006

THE OIL CONSERVATION DIVISION MUST
BE NOTIFIED 24 HOURS PRIOR TO THE
BEGINNING OF PLUGGING OPERATIONS.

PLUGGING & ABANDONMENT WORKSHEET (2 STRING CSNG)OPERATOR Chevron USA Inc.LEASENAME V. M. HendersonWELL # 7SECT 30 TWN 215 RNG 37EFROM 1980' NWL 1980' NWLTD: 6,745 FORMATION @ TD Drinkard

PBDT: FORMATION @ PBDT



	SIZE	SET @	TOC	TOC DETERMINED BY
SURFACE	11 3/4"	300'	surface	circulated
INTMED 1	8 5/8"	2,990'	surface	calculated
Prod. 1-Z	2 3/8"	6,744'	2,750'	Temp. Svy.
PROD. 2-X	2 3/8"	6,744'	2,750'	Temp. Svy.
	SIZE	Set @	TOC	TOC DETERMINED BY
Prod 3-Y	2 3/8"	5,310	2,750'	Temp. Svy.
	CUT & PULL @		TOP - BOTTOM	
Prod. 1-2	2,700'	PERFE	-	-
Prod. 2-X	2,700'	OSERHOLE	-	-
PROD 3-Y	2,700'			


REQUIRED PLUGS DISTRICT I

SUTLER (ANYTS)	
VATES	
QUEEN	3,375'
GRAYBURG	3,650'
MAN ANDER	3,950'
CANTAN REEF	
DELAWARE	
BELL CANYON	
CHEERY CANYON	
BELMITY CANYON	
BONE SPRING	
CLORIETA	5,112'
GLINNEY	5,562'
TUBS	
DRINKARD	6,615'
ASO	
WC	
PENN	
STRAWN	
ATOKA	
MOORELOW	
MISS	
DEVONIAN	

PLUG	TYPE	SACKS	DEPTH
PLUG	PLUG	CNMT	
EXAMPLES			
PLUG #1	OH	35 SXS	6400'
PLUG #2	SHOE	50 SXS	3350'-5450'
PLUG #3	CIBP/35'		4800'
PLUG #4	CIBP	25 SXS	4800'
PLUG #5	STUB	50 SXS	3600'-3700'
PLUG #6	REINR SIZ	200 SXS	400'
PLUG #7	SURF	10 SXS	0-10'
PLUG #8	"Z" string		
PLUG #9	Drinkard	653x	6617'-2700'
PLUG #10	Tubbs	—	—
PLUG #11	Glorieta	—	—
PLUG #12	S. Andros	—	—
PLUG #13	Grayburg	—	—
PLUG #14	Queen	—	—
PLUG #15	8 5/8" shoe	—	—
PLUG #16	"X" string		
PLUG #17	Grayburg	20sx	3812'-2700'
PLUG #18	Queen	—	—
PLUG #19	8 5/8" shoe	—	—
PLUG #20	"Y" string		
	Glorieta	40sx	5172'-2700'
	S. Andros	—	—
	Grayburg	—	—
	Queen	—	—
	8 5/8" shoe	—	—
	"8 5/8" Casing"		
	B. Salt	110sx	27' 2355'
	T. Salt	40sx	1440'-1250'
	11 3/4" shoe	115sx	410'-surf.
	F. Wtr.	—	—
	Surf.	—	—

V.M. Henderson #7

Date: 8-29-83



Y Backhoe
X Remore Skd
Z Drinkard

log meas. from K.B. 85
G.L. 3990'

3 strings of 2 3/8" cas
ave plastic coating down to 1000'

1. 3 str. 2 3/8" 4.6" J-55 BR
2. 1050' top @
also by temp. survey

X string, radioactive collar

5 (2-62) 2688'-92', 2696'-762', 3706'-18'
3716'-18', 3756'-60', 3784'-42'
3776'-80', 3820'-22', 3824'-30'
1 (3-62) 3688'-830' w/ 75 sk MP 3000'
er 3 (3-62) 3688'-880' (2 J55P)

crossed Skelly

string, radioactive collar

5 (2-62) 5172'-180' w/ 2 J55P

addback

2 3/8" 4.60" J-55 set @ PBTD

CIBP

62) Rem. Trencher Survey
Sound comm.
(believe shot by accident)

2 3/8" 4.60" J-55 cas

1 1/4" spiral weld casg
cmt. w/ 200 sk
cmt. circulated
15" hole to 310'

8 5/8" 24" x 32", H+J casg set w/
1370 sk, circ. assuming 47% S.
11" hole to 3000'

(2-62) sqz through Otis sleeve
w/ 75 sk MP 4200' MP 500'

Wireline BP (PBTD)

(2-62) sqz through Otis sleeve
w/ 140 sk MP 2200' MP 400'

Z string, radioactive collar

sqz through Otis sleeve
w/ 30 sk MP 3900' MP 1200'
" " MP 4600' MP 100'

sqz through Otis sleeve
w/ 23 sk MP 4300' MP 1000'
w/ 3 sk " 4300' " 2000'

6200' Otis HD retrievable seating nipple

sqz through Otis sleeve
w/ 36 sk MP 4000' MP 2000'
w/ 30 sk " 4000' " 1700'
w/ 42 sk " 4300' " 500'
w/ 13 sk " 4000' " 500'
could not open sleeve on last try

Per 5 (2-62) 6617'-21', 6624'-24', 6636'-39',
6646'-48', 6654'-58', 6671'-73', 6676'-79',
6685'-45', 6699'-701', 6710'-12' (2 J55P)

Drinkard

PBTD 6734'
6744' 2 3/8" 4.60" J-55 casg

7 5/8" hole to TD @
6745'

API # 30-025-06913

New Mexico Office of the State Engineer
POD Reports and Downloads

Township: 21S Range: 37E Sections: 23

NAD27 X: Y: Zone: Search Radius:

County: LE Basin: Number: Suffix:

Owner Name: (First) (Last) Non-Domestic Domestic All

POD / Surface Data Report

Avg Depth to Water Report

Water Column Report

Clear Form

iWATERS Menu

Help

AVERAGE DEPTH OF WATER REPORT 06/01/2006

							(Depth Water in Feet)			
Bsn	Tws	Rng	Sec	Zone	X	Y	Wells	Min	Max	Avg
CP	21S	37E	23				1	65	65	65
CP	21S	37E	23		924000	6600000	1	65	65	65

Record Count: 2