# Form 3160-3

#### OCD-HOBBS

#### FORM APPROVED OMB No. 1004-0136 Expires November 30, 2000

UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT

5. Lease Serial No.

NMNM100	864
---------	-----

APPLICATION FOR PERMIT	TO DRILL OR REENTER	6. If Indian, Allottee or Tribe	e Name
Ta. Type of Work: ☑ DRILL ☐ REENTER		7. It Unit or CA Agreement,	Name and No.
1b. Type of Well: ☐ Oil Well    Gas Well ☐ Oth		8. Lease Name and Well No RIO BLANCO 33 FED 1	
2. Name of Operator Contact: DEVON ENERGY PRODUCTION CO LP	KAREN COTTOM E-Mail: karen.cottom@dvn.com	9. API WEII NO. 30-025-3	36359
3a. Address 20 NORTH BROADWAY, SUITE 1500 OKLAHOMA CITY, OK 73102	3b. Phone No. (include area code) Ph: 405.228.7512 Fx: 405.552.4621	WILDCAT, De U	ratory
4. Location of Well (Report location clearly and in accorded	ance with any State requirements 2)8	11. Sec., T., R., M., or Blk. a	and Survey or Area
OKLAHOMA CITY, OK 73102      Location of Well (Report location clearly and in accorded At surface SESW 1000FSL 1620FWL At proposed prod. zone SESW 1000FSL 1620FWL)	000 squent	Sec 33 T22S R34E N SME: BLM	fer NMP
14. Distance in miles and direction from nearest town or post 20 MILES WEST OF JAL, NEW MEXICO	othice* OF OF ONE ON OF OTHER STATE OTHER STATE OF OTHER STATE OTHER STATE OF OTHER STATE OTHER STATE OF OTHER STATE OTHER STATE OF OTHER STATE OTHER STATE OF OTHER STATE OF OTHER STATE OF OTHER STATE OF OTHER STATE OTHER STATE OF OTHER STATE OF OTHER STATE	12. County or Parish LEA	NM
<ol> <li>Distance from proposed location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any)</li> <li>1000'</li> </ol>	360.00 36	17. Spacing Unit dedicated t	o this well
18. Distance from proposed location to nearest well, drilling, completed, applied for, on this lease, ft.	19. Proposed Depth CE CL CL	20. BLM/BIA Bond No. on	file
21. Elevations (Show whether DF, KB, RT, GL, etc. 3407 GL	22. Approximate date work will start 07/15/2003	23. Estimated duration 90 DAYS	
	24. Attachments Capitan	Controlled Water Basi	n
The following, completed in accordance with the requirements	of Onshore Oil and Gas Order No. 1, shall be attached to	this form:	
<ol> <li>Well plat certified by a registered surveyor.</li> <li>A Drilling Plan.</li> <li>A Surface Use Plan (if the location is on National Forest Sys SUPO shall be filed with the appropriate Forest Service Of the Company of the Property of</li></ol>	tem Lands, the Item 20 above).	ons unless covered by an existir	
25. Signature (Electronic Submission)	Name (Printed/Typed) KAREN COTTOM		Date 06/05/2003
Title ENGINEERING TECHNICIAN			
Approved by (Signature)	Name (Printed/Typed)  James A. Ames		AUG. 0 7 200
Title	Office		

Application approval does not warrant or certify the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon. Conditions of approval, if any, are attached.

CARLSBAD FIELD OFFICE

APPROVAL FOR 1 YEAR

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

Additional Operator Remarks (see next page)

Electronic Submission #22728 verified by the BLM Well Information System For DEVON ENERGY PRODUCTION CO LP, sent to the Hobbs APPROVAL SUBJECT Committed to AFMSS for processing by Linda Askwig on 06/05/2003 (03LA0197AE) GENERAL REQUIREMENTS AND

SPECIAL STIPULATIONS ATTACHED

\*\* BLM REVISED \*\* BLM REVISED \*\* BLM REVISED

OPER. OGRID NO. 6/37 PROPERTY NO. 32682

POOL CODE V

EFF. DATE 8-11-03 API NO. 30-025-36359

# Additional Operator Remarks:

Devon Energy proposes to drill a Devonian well to TD 15,000' for commercial quantities of gas. If the well is deemed noncommercial, the well bore will be plugged and abandonded per Federal regulations. Programs to adhere to onshore oil and gas regulations are outlined in the following exhibits and

DISTRICT 1 1825 N. French Dr., Hobbs, NM 88240 DISTRICT II 811 South First, Artesia, NM 88210

#### State of New Mexico

Energy, Minerals and Natural Resources Department

Form C-102 Revised March 17, 1999

Submit to Appropriate District Office
State Lease - 4 Copies
Fee Lease - 3 Copies

DISTRICT III 1000 Nio Braxos Rd., Axtec, NM 87410

DISTRICT IV 2040 South Pacheco, Santa Fe, NM 87605

#### OIL CONSERVATION DIVISION

2040 South Pacheco


Santa Fe, New Mexico 87504-2088

☐ AMENDED REPORT


#### WELL LOCATION AND ACREAGE DEDICATION PLAT

30-0°	Number	36359	1	Pool Code		WILDCAT, Dev.			
Property C	ode				Property Nam	ne .		Well No	umber
13268	2 Z _			RIO B	LANCO "33"	FEDERAL		1	
OGRID No					Operator Nam	ie		Elevation	
6137			DEV	ON ENE	RGY PRODUC	CTION CO., L.I	P.	3407'	
	Surface Location								
UL or lot No.	Section	Township	Range	Lot ldn	Feet from the	North/South line	Feet from the	East/West line	County
N	33	22 S	34 E		1000	SOUTH	1620	WEST	LEA
			Bottom	Hole Loc	ation If Diffe	rent From Sur	face		
UL or lot No.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
Dedicated Acres   Joint or Infill   Consolidation Code   Order No.									
320	ł	- 1							

NO ALLOWABLE WILL BE ASSIGNED TO THIS COMPLETION UNTIL ALL INTERESTS HAVE BEEN CONSOLIDATED OR A NON-STANDARD UNIT HAS BEEN APPROVED BY THE DIVISION



# SECTION 33, TOWNSHIP 22 SOUTH, RANGE 34 EAST, N.M.P.M., LEA COUNTY, NEW MEXICO.



Directions to Location:

FROM THE JUNCTION OF CO. RD. E-21 AND STATE HWY 128, GO NORTH ON CO. RD. E-21 FOR APPROX. 8.0 MILES; THENCE EAST ON E-21 FOR APPROX. 1.5 MILES TO A LEASE ROAD; THENCE NORTH ON LEASE ROAD FOR APPROX. 1.2 MILE TO PROPOSED LEASE ROAD.

BASIN SURVEYS P.O. BOX 1786-HOBBS, NEW MEXICO

W.O. Number: 3090 | Drawn By: K. GOAD

Date: 03-11-2003 | Disk: KJG CD#4 - 3090A.DWG

## DEVON ENERGY PROD. CO., L.P.

THE RIO BLANCO "33" FED. No. 1 / Well Pad Topo


THE RIO BLANCO "33" FED. No. 1 LOCATED 1000' FROM

THE SOUTH LINE AND 1620' FROM THE WEST LINE OF

SECTION 33, TOWNSHIP 22 SOUTH, RANGE 34 EAST,

N.M.P.M., LEA COUNTY, NEW MEXICO.

Survey Date: 03-05-2003 Sheet 1 of 1 Sheets



RIO BLANCO "33" FEDERAL #1
Located at 1000' FSL and 1620' FWL
Section 33, Township 22 South, Range 34 East,
N.M.P.M., Lea County, New Mexico.

Date: 03-10-2003



P.O. Box 1786 1120 N. West County Rd. Hobbs, New Mexico 88241 (505) 393-7316 - Office (505) 392-3074 - Fax basinsurveys.com

W.O. Number:	3090AA - KJG CD#4
Survey Date:	03-05-2003
Scale: 1" = 20	000'

DEVON ENERGY PROD. CO., L.P.

#### **DRILLING PROGRAM**

Attached to Form 3160-3
Devon Energy Production Company, LP
RIO BLANCO 33 FEDERAL #1
(N) 1000' FSL & 1620' FWL, Section 33 T22S, R34E
Lea, County, New Mexico

# 1. Geologic Name of Surface Formation

Alluvium

#### 2. <u>Estimated Tops of Important Geologic Markers</u>

Rustler	1790'
Salado	2400'
Delaware	5000'
Bone Spring	8450'
Wolfcamp	10970'
Strawn	11900'
Atoka	12100'
Morrow	12700'
Devonian	14,450'
Total Depth	15,000'

#### 3. Estimated Depths of Anticipated Fresh Water, Oil or Gas

The estimated depths at which water, oil and gas will be encountered are as follows.

Water

None expected in area

Oil

Bone Spring @9100'

Gas

Upper Morrow @13,100'

Devonian @14,450'

#### 4. <u>Casing Program</u>

Hole Size	Interval	OD Csg	Weight	Collar	Grade
26"	0 800' 1820-3330	20"	94#	ST&C	H-40
17 ½"	0 - 3400 & 3400' - 5000' 5200	13 3/8"	68#	ST&C	J-55 & HCK- 55
12 ¼"	0' - 8,900' & 8,900' - 12,000'	9 5/8"	43.5# & 53.5#	LT&C	HCP-110
8 1/4"	11,700' – 14,400'	7 5/8"	39#	LT&C	HCP-110
6 1/2"	14,100' – 15,000'	5 ½"	17#	LT&C	HCP-110

#### 5. CASING CEMENTING & SETTING DEPTH:

20"	Surface	Run 20",94#, ppf H-40 ST&C casing. Cement w/1100 sx 35:65 poz w/6% gel & ¼ pps Cello-Flake followed by 350 sx Class C cement containing 2% CaCl2. Run centralizers on every other joint above the shoe. Apply thread lock to bottom two joints and guide shoe. Circulate cement to surface. WOC 12hrs
13-3/8"	Intermediate	Run 13-3/8" 68# J-55 & HCK-55, ST&C casing. Cement with 2000 sx50:50 Poz:Class C w/ 10% gel, 5% NaCl, ¼ pps Cello Flake followed by 500 sx 60:40 Poz:Class C w/ 5% NaCl & ¼ pps Cello Flake. Cement to surface.
9-5/8"	Intermediate	Run 9-5/8" 43.5# & 53.5#, HCP-110, LT&C casing. Cement Stage I w/ 329 sx 35:65 Poz:Class H w/ 6% gel, 5% NaCl, ¼ pps Cello Flake followed by 925 sx 15:61:11 Poz:Class C Cement:CSE w/ 2% KCl and ¼ pps Cello Flake. Cement Stage II w/ 385 sx 35:65 Poz:Class C w/ 6% gel, 5% NaCl & ¼ pps Cello Flake followed by 125 sx Class C. Cement back to 13-3/8" casing.
7 5/8	Drilling Liner	Run 7 5/8",39# HCP 110, LT&C liner. Cement with 400 sx Class H. Cement to top of Liner
5 ½"	Production Liner	Run 5 ½", 17# HCP-110 Cement with 225 sx Class H containing necessary additives. Cement to top of liner.

Note: Cement volumes may vary based on hole conditions and caliper information.

6. PRESSURE CONTROL EQUIPMENT: Exhibit "E". A Blow-out Preventer (5,000/10,000 PSI working pressure) consisting of double ram type preventer with bag type preventer. Units will be hydraulically operated. Exhibit E-1 Choke Manifold and Closing Unit. Blind rams on top, pipe rams on bottom to correspond with size of drill pipe in use. BOP will be tested as well as choke manifold. BOP will be worked at least once each day while drilling & blind ram will be worked on trips when no drill pipe is in hole. Full opening stabbing valve and upper Kelly cock will be utilized. Anticipated BHP 6300 PSI and 200° BHT.

#### 7. PROPOSED MUD CIRCULATION SYSTEM:

DEPTH	MUD. WT.	MUD VISC.	FLUID LOSS	TYPE MUD
0'-800'	8.4 – 8.8	29-36	NC	Fresh water spud mud use paper for seepage.
800' – 5000'	8.5 – 10	29-32	NC	Brine water, use ground paper for seepage control and lime for ph
5000' – 11,800'	8.4 – 9	29-34°	N/C	Cut Brine use paper for seepage control
11,800' – 14,400'	9-12.5	34-38	10cc for drilling Morrow	Cut Brine. Mud up at 12,000'
14,400' - 15,000'	8.4	28-30	N/C	Fresh Water

Sufficient mud materials to maintain mud properties, meet lost circulation and weight increase requirement will be kept at wellsite at all times. In order to run casing and log well viscosity may have to be raised and water loss may have to be lowered.

#### 8. Auxiliary Well Control and Monitoring Equipment

- A. A kelly cock will be in the drill string at all times.
- B. A full opening drill pipe stabbing valve having the appropriate connections will be on the rig floor at all times.
- C. Hydrogen Sulfide detection equipment (Compliance Package) will be in operations when drilling out the 13 3/8" casing shoe until the 5 ½" production liner is cemented.

#### 9. Logging, Testing and Coring Program

- A. Drill stem tests may be run on potential pay interval.
- B. The open hole electrical logging program will be as follows.
  - 1) TD to intermediate casing; Induction/ Gamma Ray/ Neutron/ Density Log.
  - 2) TD to surface: Neutron with Gamma Ray.
- C. No coring program is planned.
- D. Additional testing will be initiated subsequent to setting the 5 1/2" production liner. Specific intervals will be targeted based on log evaluation, geological sample shows and drill stem tests.

#### 11. Abnormal Pressures, Temperatures and Potential Hazards

Abnormally high pressured zones with a bottom hole pressure of approximately 7500 psi could possibly be encountered while drilling the Pennsylvanian interval. Sufficient barite will be on location to enable the weighting up to the estimated 11.5 ppg to control any high pressure zone encountered. Along with the above mentioned primary control, a Blow Out Preventer System as outlined in Exhibit B will be utilized should the need arise to shut the well in prior to running and cementing the drilling liner. The estimated bottom hole temperature is 200°F. Hydrogen Sulfide has been reported at this depth in this area. No major lost circulation zones have been reported in the offsetting wells.

#### 12. Anticipated Starting Date and Duration of Operations

Road and location preparation will not be undertaken until approval has been received from the BLM. If approved, this well will be drilled as part of a development project. The anticipated spud date for the project is in July 15, 2003. The drilling operation should require approximately 70 days. If the well is deemed productive, completion operations will require, at minimum, an additional 30 days of testing to ascertain whether permanent production facilities will be constructed.

#### **SURFACE USE AND OPERATING PLAN**

Attached to Form 3160-3

RIO BLANCO 4 FEDERAL #1

(N) 1000' FSL & 1620' FWL, Section 33 T22S, R34E

Lea, County, New Mexico

#### 1. Existing Roads

- A. The well site and elevation plat for the proposed well are reflected on Exhibit #2. This well was staked by Basin Surveys in Hobbs, NM.
- B. All roads into the location are depicted in Exhibit #3. New construction from the existing lease road will be used to access the location. New construction will conform to the specifications outlined in Item #2 below.
- C. Directions to location: From the junction of Co. Rd. E-21 and state Hwy 128, go north on Co. Rd. E-21 for approx. 8.0 miles; thence east on E-21 for approx. 1.5 miles to a lease road; thence north on lease road for approx 1.2 mile to proposed lease road

#### 2. Proposed Access Road

Exhibit #3 shows the existing lease road. Access to this location will require the construction of about 1409' of proposed access road. All new construction will adhere to the following.

- A. The maximum width of the road will be 15'. It will be crowned and made of 6" of rolled and compacted caliche. Water will be deflected, as necessary, to avoid accumulation and prevent surface erosion.
- B. Surface material will be native caliche. This material will be obtained from a BLM approved pit nearest in proximity to the location. The average grade will be approximately 1%.
- C. No cattle guards, grates or fence cuts will be required. No turnouts are planned.

#### 3. <u>Location of Existing and/or Proposed Facilities</u>

A. In the event the well is found productive, a tank battery would be constructed and the necessary production equipment will be installed at the well site.

1) If necessary, the well will be operated by means of an electric prime mover.

Electric power poles will be set along side of the access road.

Wife approval.

#### RIO BLANCO 33 FEDERAL #1 SURFACE USE AND OPERATING PLAN PAGE 2

- 2) The tank battery, all connections and all lines will adhere to API standards.
- B. If the well is productive, rehabilitation plans are as follows.
  - 1) The reserve pit will be back-filled after the contents of the pit are dry (within 120 days after completion, weather permitting).
  - 2) The original topsoil from the well site will be returned to the location. The drill site will then be contoured to the original natural state.

#### 4. Methods of Handling Water Disposal

- A. Drill cuttings will be disposed into the reserve pit.
- B. Drilling fluids will be contained in steel mud tanks. The reserve pit will contain excess drilling fluid or fluid from the well during drilling, cementing and completion operations. The reserve pit will be an earthen pit roughly 125' x 125' x 6', or smaller, in size.
- C. The reserve pit will be fenced on three sides throughout drilling operations and will be totally isolated upon removal of the rotary rig. The pit will be lined using a 5-7 mil plastic to minimize loss of drilling fluids and saturation of the ground with brine water used during drilling.
- D. Water produced from the well during completion operations will be disposed into a steel tank or reserve pit, if volumes prove excessive. After placing the well on production through the production facilities, all water will be collected in tanks. Produced oil will be separated into steel stock tanks until sold.
- E. A portable chemical toilet will be available on the location for human waste during the drilling operations.
- F. Garbage, trash and waste paper produced during drilling operations will be collected in a contained trailer and disposed at an approved landfill. All waste material will be contained to prevent scattering by the wind. All water, fluids, salt or other chemicals will be disposed into the reserve pit. No toxic waste or hazardous chemicals will be generated by this operation.
- G. All waste material will be removed within 30 days after the well is either completed or abandoned. The reserve pit will be completely fenced until it has dried. At the point the reserve pit is found sufficiently dry, it will be backfilled and reclaimed as

#### **RIO BLANCO 33 FEDERAL #1**

SURFACE USE AND OPERATING PLAN

PAGE 3

per BLM specifications. Only the portion of the drilling pad used by the production equipment (pumping unit and tank battery) will remain in use. If the well is deemed non-commercial only a dry hole marker will remain.

#### 5. Well Site Layout

- A. The drilling pad is shown on Exhibit #5. The pad, pits and general location of the rig equipment are displayed. Top soil will be stored adjacent to the pad until reclamation efforts are undertaken. Only modest cuts will be necessary to build the pad which will be covered with 6" of compacted caliche.
- B. No permanent living facilities are planned, but temporary trailers for the tool pusher, drilling foreman and mud logger may be on location throughout drilling operations.
- C. The reserve pit will be lined using plastic sheeting of 5-7 mil thickness.

#### 10. Plans for Restoration of Surface

- A. After concluding the drilling and/or completion operations, if the well is found non-commercial, the road will be reclaimed as directed by the BLM. The reserve pit area will be broken out and leveled after drying to a condition where these efforts are feasible. The original top soil will be returned to the pad and contoured, as close as possible, to the original topography.
- B. The pit lining will be buried or hauled away in order to return the location and road to their pristine nature. All pits will be filled and location leveled, weather permitting, within 120 days after abandonment.
- C. The location and road will be rehabilitated as recommended by the BLM.
- D. The reserve pit will be fenced on three sides throughout drilling operations. After the rotary rig is removed, the reserve pit will be fenced on the fourth side to preclude endangering wildlife. The fencing will be in place until the pit is reclaimed.
- E. If the well is deemed commercially productive, the reserve pit will be restored as described in 10 (A) within 120 days subsequent to the completion date. The original top soil will be returned to the area of the drilling pad not necessary to operate the well. These unused areas of the drilling pad will be contoured, as close as possible, to match the original topography.

#### 11. Surface Ownership

The well site is owned by the Bureau of Land Management.

The surface location will be restored as directed by the BLM.

#### **RIO BLANCO 33 FEDERAL #1**

#### SURFACE USE AND OPERATING PLAN

PAGE 4

#### 12. Other Information

- A. The wellsite and access route are located in a relatively flat area.
- B. The top soil at the wellsite and access route is sandy.
- C. The vegetation cover at the wellsite is moderately sparse, with prairie grasses, some mesquite bushes, and shinnery oak.
- D. No wildlife was observed but it is likely that deer, rabbits, coyotes and rodents traverse the area.
- E. A Cultural Resources Examination will be completed by Southern New Mexico Archaeological Services, Inc. and forwarded to the BLM office in Carlsbad, New Mexico.

#### 13. Lessee's and Operator's Representative

The Devon Energy Production Company, L.P. representatives responsible for ensuring compliance of the surface use plan are listed below.

Bill Greenlees Operations Engineer Advisor	Don Mayberry Superintendent
Devon Energy Production Company, L.P.	Devon Energy Production Company, L.P.
20 North Broadway, Suite 1500	Post Office Box 250
Oklahoma City, OK 73102-8260	Artesia, NM 88211-0250
(405) 552-8194 (office)	(505) 748-3371 (office)
(405) 203-7778 (Cellular)	(505) 746-4945 (home)

#### Certification

I hereby certify that I, or persons under my direct supervision, have inspected the proposed drill site and access road; that I am familiar with the conditions that presently exist; that the statements made in this plan are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed by Devon Energy Production Company, L.P. and its contractors and subcontractors in conformity with this plan and the terms and conditions under which it is approved.

Signed:	Bu Only	Date:	June 5, 2003
	Bill Greenlees		
	Operations Engineer Advisor		

# Attachment to Exhibit #1 NOTES REGARDING BLOWOUT PREVENTERS Devon Energy Production Company, LP Rio Blanco 33 federal #1 (N) 1000' FSL & 1620' FWL, Section 33 T22S, R34E Lea, County, New Mexico

- 1. Drilling nipple will be constructed so it can be removed mechanically without the aid of a welder. The minimum internal diameter will equal BOP bore.
- 2. Wear ring will be properly installed in head.
- 3. Blowout preventer and all associated fittings will be in operable condition to withstand a minimum 5000 psi working pressure.
- 4. All fittings will be flanged.
- 5. A full bore safety valve tested to a minimum 5000 psi WP with proper thread connections will be available on the rotary rig floor at all times.
- 6. All choke lines will be anchored to prevent movement.
- 7. All BOP equipment will be equal to or larger in bore than the internal diameter of the last casing string.
- 8. Will maintain a kelly cock attached to the kelly.
- 9. Hand wheels and wrenches will be properly installed and tested for safe operation.
- 10. All BOP equipment will meet API standards and include a minimum 40 gallon accumulator having two independent means of power to initiate closing operation.

### UNITED STATES DEPARTMENT OF THE INTERIOR


#### Bureau of Land Management Roswell Field Office 2909 West Second Street Roswell, New Mexico 88201-1287

#### Statement Accepting Responsibility for Operations

Operator Name: Street or Box: City, State: Zip Code:	Devon Energy Production Company, LP 20 North Broadway, Suite 1500 Oklahoma City, Oklahoma 73102-8260
	blicable terms, conditions, stipulations and restrictions d on the leased land or portion thereof, as described
Lease No.:	NM-92199
Legal Description of Land:	320 acres 33-T22S-R34E
Formation(s):	Morrow, Devonian
Bond Coverage:	Nationwide
BLM Bond File No.:	CO-1104
Authorized Signature:	Bill Greenlees
Title:	<b>Operations Engineering Advisor</b>
Date:	06/05/03

# Rio Blanco Prospect 2

**Casing Schematic** 



Rio Blanco Prospect

Operator:

Devon Energy Production Company, L.P.

String type:

Surface

Location:

Section 33-22S-34E, Lea Co, NM

Design parameters: <u>Collapse</u> Mud weight: 10.500 ppg  Design is based on evacuated pipe.		Minimum design factors: Collapse: Design factor 1.125		Environment: H2S considered? Surface temperature: Bottom hole temperature: Temperature gradient: Minimum section length:		No 75 °F 86 °F 1.40 °F/100ft 800 ft			
Burst				Burst: Design fac	ctor	1.00	William Se	cuon lengui.	600 H
Max	anticipated	surface							
Inter Calc	ressure: mal gradient culated BHP packup mud		470 psi 0.268 psi/ft 684 psi	Tension: 8 Round S 8 Round L Buttress: Premium:	TC:	1.80 (J) 1.80 (J) 1.60 (J) 1.50 (J)	Non-direction	onal string.	
				Body yield		1.60 (B)	Re subsea	uent strings:	
				,,				ting depth:	2,236 ft
				Tension is	based on air	weight.	Next mu	d weight:	9.200 ppg
	Neutral point: 675 ft Next setting BHP: Fracture mud wt: Fracture depth: Injection pressure		mud wt: depth:	1,069 psi 19.250 ppg 800 ft 800 psi					
Run	Segment		Nominal		End	True Vert	Measured	Drift	Est.
Seq	Length (ft)	Size (in)	Weight (lbs/ft)	Grade	Finish	Depth (ft)	Depth (ft)	Diameter (in)	Cost (\$)
1	800	`20	94.00	H-40	ST&C	800	800	18.999	19349
Run Seq 1	Collapse Load (psi) 436	Collapse Strength (psi) 520		Burst Load (psi) 684	Burst Strength (psi) 1530	Burst Design Factor 2.24	Tension Load (kips) 75.2	Tension Strength (kips) 581	Tension Design Factor 7.73 J

Devon Energy

Date: March 4,2003 Oklahoma City, Oklahoma

Remarks:

Collapse is based on a vertical depth of 800 ft, a mud weight of 10.5 ppg. The casing is considered to be evacuated for collapse purposes.

Collapse strength is based on the Westcott, Dunlop & Kernler method of biaxial correction for tension.

Rio Blanco 33 Fed # 1

Operator:

**Devon Energy Production Company, L.P.** 

String type:

SUFFECE INTERMEDIATE

Location:

Section 33-22S-34E, Lea Co, NM

Collaps Mud	n <b>parameter</b> i <u>e</u> weight: nal fluid densi		10.000 ppg 0.900 ppg	Minimum <u>Collapse:</u> Design fac	ı <b>design f</b> a	actors: 1.125	Temperatur	ered? perature: temperature	1.40 °F/100ft
Burst				<u>Burst:</u> Design fac	tor	1.00	Minimum Di		2.250 in
pr Interi Calci Gas	anticipated suressure: nal gradient: ulated BHP gravity: ular backup:	urface	3,133 psi 0.075 psi/ft 3,506 psi 0.60 10.10 ppg	Tension: 8 Round S 8 Round L Buttress: Premium:		1.80 (J) 1.80 (J) 1.60 (J) 1.50 (J)	Non-direction	onal string.	
				Body yield:	:	1.60 (B)		u <b>ent strings:</b> ting depth:	12.000 ft
				Tension is Neutral poi	based on a	air weight. 4,257 ft	Next mu	id weight: ting BHP:	9.800 ppg 6,109 psi
				, source po		,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,		mud wt:	13.500 ppg 5,000 ft
				Estimated	cost:	80,723 (\$)		pressure	3,506 psi
Run	Segment	·	Nominal		End	True Vert	Measured	Drift	Est.
Seq	Length	Size	Weight	Grade	Finish	Depth	Depth	Diameter	Cost
2	(ft) 3400	(in) 13.375	(lbs/ft) 68.00	J-55	ST&C	<b>(ft)</b> 3400	(ft) 3400	(in) 12.29	<b>(\$)</b> 49592

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Est. Cost (\$)
2	3400	13.375	68.00	J-55	ST&C	3400	3400	12.29	49592
1	1600	13.375	68.00	HCK-55	ST&C	5000	5000	12.29	31131
Run Seq	Collapse Load	Collapse Strength	Collapse Design	Burst Load	Burst Strength	Burst Design	Tension Load	Tension Strength	Tension Design
	(psi)	(psi)	Factor	(psi)	(psi)	Factor	(kips)	(kips)	Factor
2	1607	1893	1.18	3133	3450	1.10	340	675	1.99 J
1	2364	2850	1.21	1603	3450	2.15	108.8	905	8.32 J

**Devon Energy** 

Date: June 3,2003 Oklahoma City, Oklahoma

Remarks:

Collapse is based on a vertical depth of 5000 ft, a mud weight of 10 ppg. An internal gradient of .047 psi/ft was used for collapse from TD to Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

**Rio Blanco Prospect 2** 

Operator:

**Devon Energy Production Company, L.P.** 

String type:

Intermediate - DEEP

Location:

Section 33-22S-34E, Lea Co, NM

Collaps Mud	n paramete se weight: gn is based	10	0.000 ppg ed pipe.	Minimum Collapse: Design fact	design fac	tors: 1.125	Temperature	ered? perature: temperature:	1.40 °F/100ft
<u>Burst</u>	ace pressure		100 psi	Burst: Design fact	or	1.10		J	
	ressure:		,882 psi						
,	nal gradient		).267 psi/ft	Tension:			Non-direction	nal etrina	
	ulated BHP		),084 psi	8 Round ST 8 Round LT		1.80 (J) 1.80 (J)	Non-direction	mai sumg.	
Annı	ular backup:	1	0.00 ppg	Buttress:		1.60 (J)			
	•			Premium:		1.50 (J)			
				Body yield:		1.60 (B)	Re subsequ	uent strings:	
				•			Next set	ting depth:	14,400 ft
					based on air	weight.	Next mu	d weight:	13.000 ppg
				Neutral poi	nt: 10	),447 ft		ting BHP:	9,725 psi
								mud wt:	15.400 ppg
							Fracture	•	12,000 ft
				Estimated of	cost: 205	5,659 (\$)	Injection	pressure	9,600 psi
Run	Segment		Nominal		End	True Vert	Measured	Drift	Est.
Seq	Length	Size	Weight	Grade	Finish	Depth	Depth	Diameter	Cost
<b>00</b> 4	(ft)	(in)	(lbs/ft)	0.00		(ft)	(ft)	(in)	(\$)
2	8900	9.625	43.50	HCP-110	LT&C	8900	8900	8.625	143972
1	3100	9.625	53.50	HCP-110	LT&C	12000	12000	8.5	61687
•	3100	3.023	55.56	1101-110	LIGO	12000	12000	0.5	01007
Run	Collapse	Collapse	Collapse	Burst	Burst	Burst	Tension	Tension	Tension
Seq	Load	Strength	Design	Load	Strength	Design	Load	Strength	Design
•	(psi)	(psi)	Factor	(psi)	(psi)	Factor	(kips)	(kips)	Factor
2	4723	5395	1.14	5882	8700	1.48	553	1106	2.00 J
1	6334	8850	1.40	3634	10900	3.00	165.9	1422	8.57 J
									_

**Devon Energy** 

Date: May 21,2003 Oklahoma City, Oklahoma

Remarks:

Collapse is based on a vertical depth of 12000 ft, a mud weight of 10 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Rio Blanco Prospect 2

Operator:

**Devon Energy Production Company, L.P.** 

String type:

**Drilling Liner** 

Location:

Section 33-22S-34E, Lea Co, NM

Collaps Mud	n paramete se weight: ign is based	•	13.000 ppg ted pipe.	Minimum <u>Collapse:</u> Design fac	design fac	:tors: 1.125	Temperatur	ered? perature: temperature	0.80 °F/100ft
				Burst:			Minimum D		6.500 in
				Design fac	tor	1.00			***************************************
<b>Burst</b>				•					
Max	anticipated								
	ressure:		5,872 psi				Liner top:		11,700 ft
	nal gradient		0.268 psi/ft	Tension:			Non-direction	onal string.	
Calc	ulated BHP		9,725 psi	8 Round S		1.80 (J)			
No b	ackup mud	anacified		8 Round L <sup>-</sup> Buttress:	IC:	1.80 (J) 1.60 (J)			
NOL	ackup mud	specinea.		Premium:		1.50 (J) 1.50 (J)			
				Body yield:		1.60 (B)	Re subsec	uent strings	•
				Dody yiola.	•	1.55 (5)		lting depth:	15.000 ft
				Tension is	based on air	weight.		ıd weight:	8.900 ppg
				Neutral poi		3,877 ft		lting BHP:	6,935 psi
				•		•	Fracture	mud wt:	13.600 ppg
							Fracture	e depth:	14,400 ft
							Injection	pressure	10,174 psi
Run	Segment		Nominal		End	True Vert	Measured	Drift	Est.
Seq	Length	Size	Weight	Grade	Finish	Depth	Depth	Diameter	Cost
•	(ft)	(in)	(lbs/ft)			(ft)	(ft)	(in)	(\$)
1	2700	7.625	39.00	HCP-110	LT&C	14400	14400	6.5	41216
Run	Collapse	Collapse	•	Burst	Burst	Burst	Tension	Tension	Tension
Seq	Load	Strength		Load	Strength	Design	Load	Strength	Design
	(psi)	(psi)	Factor	(psi)	(psi)	Factor	(kips)	(kips)	Factor
1	9725	11080	1.14	9725	12620	1.30	105.3	1066	10.12 J

**Devon Energy** 

Date: May 21,2003 Oklahoma City, Oklahoma

Remarks:

For this liner string, the top is rounded to the nearest 100 ft. Collapse is based on a vertical depth of 14400 ft, a mud weight of 13 ppg The Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

**Rio Blanco Prospect 2** 

Operator:

**Devon Energy Production Company, L.P.** 

String type:

Liner: Production

Location:

Section 33-22S-34E, Lea Co, NM

Desi	ign	parameters:
- "		

Collapse

Mud weight: Design is based on evacuated pipe.

8.900 ppg

Minimum design factors:

Collapse: Design factor

**Burst:** Design factor

Tension: API - tubing: 1.125

1.00

1.50 (J)

1.80 (J)

1.60 (J) 1.50 (J) **Environment:** 

H2S considered? Surface temperature:

75 °F 195 °F 0.80 °F/100ft Bottom hole temperature:

No

Temperature gradient: Minimum section length: Minimum Drift:

800 ft 2.100 in

**Burst** 

Max anticipated surface

2,922 psi pressure: Internal gradient: 0.268 psi/ft Calculated BHP

No backup mud specified.

6,935 psi

**Buttress:** Premium: Body yield:

8 Round LTC:

1.60 (B) Tension is based on air weight. Neutral point: 14,879 ft

Liner top:

14,100 ft Non-directional string.

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Est. Cost (\$)
1 -	900	5.5	17.00	HCP-110	LT&C	15000	15000	4.767	5928
Run Seq	Collapse Load	Collapse Strength	Collapse Design	Burst Load	Burst Strength	Burst Design	Tension Load	Tension Strength	Tension Design
1	<b>(psi)</b> 6935	(psi) 8580	Factor 1.24	<b>(psi)</b> 6935	(psi) 10640	Factor 1.53	(kips) 15.3	(kips) 445	<b>Factor</b> 29.08 J

**Devon Energy** 


Date: May 21,2003 Oklahoma City, Oklahoma

Remarks:

For this liner string, the top is rounded to the nearest 100 ft. Collapse is based on a vertical depth of 15000 ft, a mud weight of 8.9 ppg. The Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.


Burst strength is not adjusted for tension.

Engineering responsibility for use of this design will be that of the purchaser.



# MINIMUM CHOKE MANIFOLD 3,000, 5,000 and 10,000 PSi Working Pressure

3 MWP - 5 MWP - 10 MWP




BEYOND SUBSTRUCTURE

			MINII	MUM REQU	PEMENTS	3					
	<u> </u>	1	3,000 MWP			5,000 MWP			10,000 MWF		
No.		1.D.	NOMINAL	RATING	I.D.	NOMINAL	RATING	I.D.	NOMINAL	RATING	
1	Line from drilling spool	<del></del>	3*	3,000		3*	5,000		3*	10,000	
	Cross 3"x3"x3"x2"	<del>                                     </del>		3,000		[	5,000				
2	Cross 3"x3"x3"x3"									10,000	
3	Valves(1) Gate □ Plug □(2)	3-1/8"		3,000	3-1/8"		5,000	3-1/8"		10,000	
4	Valve Gate □ Plug □(2)	1-13/16*		3,000	1-13/16*		5,000	1-13/16"		10,000	
48	Valves(1)	2-1/16"		3,000	2-1/16"	L	5,000	3-1/8"		10,000	
5	Pressure Gauge	7		3,000		<u> </u>	5,000	L		10,000	
6	Valves Gate □ (2)	3-1/8*		3,000	3-1/8*		5,000	3-1/8"		10,000	
7	Adjustable Choke(3)	2*	1	3,000	2*		5,000	2*		10,000	
8	Adjustable Choke	1"		3,000	1"		5,000	2"		10,000	
9	Line	-	3-	3,000		3*	5,000		3"	10,000	
10	Line		2"	3,000		2"	5,000	<u> </u>	3"	10,000	
11	Valves Gate □ (2)	3-1/8"		3,000	3-1/8"		5,000	3-1/8*		10,000	
12	Lines		3*	1,000		3″	1,000	<u> </u>	3°	2,000	
13	Lines		3*	1,000		3*	1,000		3"	2,000	
14	Remote reading compound standpipe pressure gauge			3,000			5,000	•		10,000	
15	Gas Separator		2'x5'			2'x5'			2'x5'		
16	Line		4*	1,000		4*	1.000		4*	2,000	
17	Valves Gate □ (2)	3-1/8"		3,000	3-1/8"		5,000	3-1/8"		10,000	

- (1) Only one required in Class 3M.
- (2) Gate valves only shall be used for Class 10M.
- (3) Remote operated hydraulic choke required on 5,000 psi and 10,000 psi for drilling.

#### **EQUIPMENT SPECIFICATIONS AND INSTALLATION INSTRUCTIONS**

- 1. All connections in choke manifold shall be welded, studded, flanged or Cameron clamp of comparable rating.
- 2. All flanges shall be API 6B or 6BX and ring gaskets shall be API RX or BX. Use only BX for 10 MWP.
- 3. All lines shall be securely anchored.
- 4. Chokes shall be equipped with tungsten carbide seats and needles, and replacements shall be available.
- 5. Choke manifold pressure and standpipe pressure gauges shall be available at the choke manifold to assist in regulating chokes. As an alternate with automatic chokes, a choke manifold pressure gauge shall be located on the rig floor in conjunction with the standpipe pressure gauge.
- Line from drilling spool to choke manifold should be as straight as possible. Lines downstream from chokes shall make turns by large bends or 90° bends using bull plugged tees.
- 7. Discharge lines from chokes, choke bypass and from top of gas separator should vent as far as practical from the well.



## PROPOSED 10-M BOPE AND CHOKE ARRANGEMENT EXHIBIT B (A) ROTATING HEAD Lea County, New Mexico **ANNULAR PREVENTER** REMOTELY OPERATED CHOKE PIPE TO PIT AND/OR MUDIGAS SEPARATOR **RAMS** - 4" NOMINAL **BLIND** RAMS CHECK VALVE REMOTELY OPERATED VALVE FROM DRILLING **ELEED LINE** DRILLING SPOOL FLUID PUMP 3" NOMINAL 3° NOMINAL SEQUENCE 4 NOMINA 4" NOMINAL PIPE RAMS TO PIT AND/OR MUD/GAS SEPARATOR 4" NOMINAL REMOTELY OPERATED CHOKE