

Submit 3 Copies To Appropriate District Office
District I
1625 N. French Dr., Hobbs, NM 88240
District II
1301 W. Grand Ave., Artesia, NM 88210
District III
1000 Rio Brazos Rd., Aztec, NM 87410
District IV
1220 S. St. Francis Dr., Santa Fe, NM 87505

State of New Mexico
Energy, Minerals and Natural Resources

Form C-103
May 27, 2004

OIL CONSERVATION DIVISION
1220 South St. Francis Dr.
Santa Fe, NM 87505

WELL API NO.	30-025-38540
5. Indicate Type of Lease STATE <input type="checkbox"/> FEE <input checked="" type="checkbox"/>	
6. State Oil & Gas Lease No.	
7. Lease Name or Unit Agreement Name Southland Royalty A	
8. Well Number	32
9. OGRID Number	00873
10. Pool name or Wildcat Eunice; Blinebry-Tubb-Drinkard, N	

11. Elevation (Show whether DR, RKB, RT, GR, etc.) 3,487' GR

Pit or Below-grade Tank Application <input type="checkbox"/> or Closure <input type="checkbox"/>
Pit type _____ Depth to Groundwater _____ Distance from nearest fresh water well _____ Distance from nearest surface water _____
Pit Liner Thickness: _____ mil Below-Grade Tank: Volume _____ bbls; Construction Material _____

12. Check Appropriate Box to Indicate Nature of Notice, Report or Other Data

NOTICE OF INTENTION TO:

PERFORM REMEDIAL WORK ☐ PLUG AND ABANDON ☐
TEMPORARILY ABANDON ☐ CHANGE PLANS ☐
PULL OR ALTER CASING ☐ MULTIPLE COMPL ☐

SUBSEQUENT REPORT OF:


REMEDIAL WORK ☐ ALTERING CASING ☐
COMMENCE DRILLING OPNS. ☐ P AND A ☐
CASING/CEMENT JOB ☐

OTHER: ☐

OTHER: Completion Procedure ☒

13. Describe proposed or completed operations. (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work). SEE RULE 1103. For Multiple Completions: Attach wellbore diagram of proposed completion or recompletion.

03/21/07 PERF DRINKARD @ 6611-15', 6726-30', 43-47', 74-78', 6808-12' 2 JSPF
03/21/07 ACID DRINKARD W/ 3000 GALS 15% HCl
03/22/07 FRAC DRINKARD W/ 39K GALS SS-35 AND 62K LBS 20/40 SLC
03/23/07 PERF TUBB @ 6200-04', 28-34', 6342-46', 60-64', 6412-18' 2 JSPF
03/26/07 SET RBP @ 6450'. ACID TUBB W/ 3000 GALS 15% HCl
03/27/07 FRAC TUBB W/ 36K GALS SS-25 AND 82K LBS 20/40 SLC
03/27/07 RETRIEVE RBP @ 6450' AND POH
03/28/07 PERF BLINEBRY @ 5682-86', 5736-42', 5816-20', 5892-98', 5970-76' 2 JSPF
03/29/07 SET RBP @ 6030'. ACID BLINEBRY W/ 3000 GALS 15% HCl
04/02/07 FRAC BLINEBRY W/ 36K GALS SS-25 AND 82K LBS 20/40 SLC
04/02/07 RETRIEVE RBP @ 6030' AND POH
04/03/07 RIH W/PUMP & RODS
04/04/07 SET 640 PUMPING UNIT. PUT ON PRODUCTION BLINEBRY/TUBB/DRINKARD.



I hereby certify that the information above is true and complete to the best of my knowledge and belief. I further certify that any pit or below-grade tank has been/will be constructed or closed according to NMOCD guidelines ☐, a general permit ☐ or an (attached) alternative OCD-approved plan ☐.

SIGNATURE Sophie Mackay TITLE Engineering Tech DATE 04/16/2007
Type or print name Sophie Mackay E-mail address: sophie.mackay@apachecorp.com Telephone No. (918)491-4864
For State Use Only

APPROVED BY: [Signature] TITLE _____ DATE APR 26 2007
Conditions of Approval (if any): _____