

Submit 3 Copies To Appropriate District
Office
District I
1625 N. French Dr., Hobbs, NM 87240
District II
811 South First, Artesia, NM 87210
District III
1000 Rio Brazos Rd., Aztec, NM 87410
District IV
2040 South Pacheco, Santa Fe, NM 87505

State of New Mexico
Energy, Minerals and Natural Resources

OIL CONSERVATION DIVISION
2040 South Pacheco
Santa Fe, NM 87505

Form C-103
Revised March 25, 1999

SUNDRY NOTICES AND REPORTS ON WELLS (DO NOT USE THIS FORM FOR PROPOSALS TO DRILL OR TO DEEPEN OR PLUG BACK TO A DIFFERENT RESERVOIR. USE "APPLICATION FOR PERMIT" (FORM C-101) FOR SUCH PROPOSALS.)		WELL API NO. 30-025-35855
1. Type of Well: Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other <input type="checkbox"/>		5. Indicate Type of Lease STATE <input checked="" type="checkbox"/> FEE <input type="checkbox"/>
2. Name of Operator BP AMERICA PRODUCTION COMPANY		6. State Oil & Gas Lease No.
3. Address of Operator 501 WESTLAKE PARK BLVD, ROOM 5.174, HOUSTON, TX 77079		7. Lease Name or Unit Agreement Name: MAE F. CURRY
4. Well Location Unit Letter B : 660 feet from the NORTH line and 1780 feet from the EAST line Section 7 Township 21S Range 37E NMPM County LEA		8. Well No. 5
10. Elevation (Show whether DR, RKB, RT, GR, etc.) 3509' GR		9. Pool name or Wildcat HARDY (TUBB-DRINKARD)

11. Check Appropriate Box to Indicate Nature of Notice, Report, or Other Data	
NOTICE OF INTENTION TO: PERFORM REMEDIAL WORK <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> TEMPORARILY ABANDON <input type="checkbox"/> CHANGE PLANS <input type="checkbox"/> PULL OR ALTER CASING <input type="checkbox"/> MULTIPLE COMPLETION <input type="checkbox"/> OTHER: <input type="checkbox"/>	SUBSEQUENT REPORT OF: REMEDIAL WORK <input type="checkbox"/> ALTERING CASING <input type="checkbox"/> COMMENCE DRILLING OPNS. <input type="checkbox"/> PLUG AND ABANDONMENT <input type="checkbox"/> CASING TEST AND CEMENT JOB <input type="checkbox"/> OTHER: New Well Completion <input checked="" type="checkbox"/>

12. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work). SEE RULE 1103. For Multiple Completions: Attach wellbore diagram of proposed completion or recompilation.

6/25- Spud Date

7/11 - Rig Release

7/16 - Drill DV Tool @ 2154. Float Collar @ 4640', cmt, float shoe @ 4680' & cmt to 4715.

7/20 - TOP CMT 4810' - Tagged @ 6924'

7/21 - Swabbing Well, recovered @ 36 bbls water, no oil/treated w/51.5 bbls water and 24 bbls acid

9/15/02 - TOPS

Perfs: 6485' - 6483' - w/4 SPF, 20 Holes - Frac w/42,000# Flexsand and 483 BBL Gel.

6811' - 6831' Frac w/39,000 gal 35# gel

Casing:

8-5/8" 24# 1332' 12-1/4" 635 sxs cmt

5-1/2" 14.4# 4679' 7-7/8" 1628 sxs cmt

Tubing: 2-3/8" @ 6317'

I hereby certify that the information above is true and complete to the best of my knowledge and belief.

SIGNATURE *Sandra J. Moore* TITLE Regulatory Compliance Assist. DATE 10/11/02

Type or print name SANDRA J. MOORE

Telephone No. 281-366-7183

(This space for State use)

APPROVED BY *[Signature]* TITLE PETROLEUM ENGINEER DATE OCT 02 2003

Conditions of approval, if any:

Mae F. Curry #5

Hardy (Tubb/Drinkard)

660' FNL & 1780' FEL, Sect 7

T-21-S, R-37E

Lea County, New Mexico


RKB 3519'

GL 3509'

Spud: 6/25/02

RR: 7/11/02

API # 30 025 35855



8 5/8", 24#, J-55, ST&C @ 1332'
Cmt w/ 635 sx to surface

DV Tool @ 2000'+/-
not used - shifted to closed position

5 1/2", 15.5#, J-55, LT&C @ 4679'
Cmt w/ 850 sxs of 35:65 POZ & 450 sxs of 50:50 POZ
circ. 328 sxs

Tubb perms 6415 to 6483'

Drinkard perms 6811 to 6831'

4 1/2", 11.6# J-55 FL-4S @ 7000'
Cmt w/ 200 sxs of 35:65 POZ & 240 sxs of 50:50 POZ
TOC @ 4810' by CBL

TD: 7000'
PBD: 6925'