

Submit 3 Copies To Appropriate District Office
District I
1625 N. French Dr., Hobbs, NM 88240
District II
1301 W. Grand Ave., Artesia, NM 88210
District III
1000 Rio Brazos Rd., Aztec, NM 87410
District IV
1220 S. St. Francis Dr., Santa Fe, NM 87505

State of New Mexico
Energy, Minerals and Natural Resources

Form C-103
Revised May 08, 2003

OIL CONSERVATION DIVISION
1220 South St. Francis Dr.
Santa Fe, NM 87505

WELL API NO.	30-025-03217
5. Indicate Type of Lease	STATE <input type="checkbox"/> FEE <input checked="" type="checkbox"/>
6. State Oil & Gas Lease No.	
7. Lease Name or Unit Agreement Name	East Pearl Queen Unit
8. Well Number	20
9. OGRID Number	025482
10. Pool name or Wildcat	Pearl Queen

SUNDRY NOTICES AND REPORTS ON WELLS
(DO NOT USE THIS FORM FOR PROPOSALS TO DRILL OR TO DEEPEN OR PLUG BACK TO A DIFFERENT RESERVOIR. USE "APPLICATION FOR PERMIT" (FORM C-101) FOR SUCH PROPOSALS.)

1. Type of Well:
Oil Well ☐ Gas Well ☒ Other ☐

Injection

2. Name of Operator
Xeric Oil & Gas Corporation

3. Address of Operator
P. O. Box 352, Midland, TX 79702


4. Well Location
Unit Letter D : 660 feet from the North line and 660 feet from the West line
Section 27 Township 19S Range 35E NMPM Lea County

11. Elevation (Show whether DR, RKB, RT, GR, etc.)

12. Check Appropriate Box to Indicate Nature of Notice, Report or Other Data	
NOTICE OF INTENTION TO:	SUBSEQUENT REPORT OF:
PERFORM REMEDIAL WORK <input type="checkbox"/> PLUG AND ABANDON <input checked="" type="checkbox"/>	REMEDIAL WORK <input type="checkbox"/> ALTERING CASING <input type="checkbox"/>
TEMPORARILY ABANDON <input type="checkbox"/> CHANGE PLANS <input type="checkbox"/>	COMMENCE DRILLING OPNS. <input type="checkbox"/> PLUG AND ABANDONMENT <input type="checkbox"/>
PULL OR ALTER CASING <input type="checkbox"/> MULTIPLE COMPLETION <input type="checkbox"/>	CASING TEST AND CEMENT JOB <input type="checkbox"/>
OTHER: <input type="checkbox"/>	OTHER: <input type="checkbox"/>

13. Describe proposed or completed operations. (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work). SEE RULE 1103. For Multiple Completions: Attach wellbore diagram of proposed completion or recompletion.

- 1) MIRU Pulling Unit.
- 2) Circulate hole w/+/- 60 bbls mud.
- 3) Spot 25 sx of Class C cement @ 4600' & tag.
- 4) Spot 25 sx of Class C cement @ 1700' & tag.
- 5) Spot 25 sx of Class C cement @ 300'.
- 6) Spot 10 sx plug @ 60'.
- 7) RD. Install dry hole marker & clean location.



I hereby certify that the information above is true and complete to the best of my knowledge and belief.

SIGNATURE Angie Crawford TITLE Production Analyst DATE 11/3/03

Type or print name Angie Crawford ACrawford@xericoil.com Telephone No. 432-683-3171

(This space for State use)

APPROVED BY Harry W. Wink FIELD REPRESENTATIVE II/STAFF MANAGER DATE NOV 21 0 2003

Conditions of approval, if any:

THE COMMISSION MUST BE NOTIFIED 24 HOURS PRIOR TO THE BEGINNING OF PLUGGING OPERATIONS FOR THE C-103 TO BE APPROVED.

XERIC OIL & GAS CORP.
WELLBORE DIAGRAM

WELL: East Pearl Queen #20

COUNTY: Lea

STATE: NM

HOLE SIZE: 11"
CASING: 8⁵/₈" @ 306
CEMENTED WITH: 300SX
CEMENT TOP: Surf.

TUBING: 2³/₈" @ 4597'

RODS: _____

PUMP: _____

PACKER: Permanent @
4700'

Model R @
4597'

HOLE SIZE: 7⁷/₈"

CASING: 5¹/₂" @ 4885

CEMENTED WITH: 700SX

CEMENT TOP: Surface

PERFS:

4656' - 70'

4856' - 70'

PBTD: 4880'

TD: 4885'