## RECEIVED

FORM APPROVED

OMB No 1004-0137 Expires March 31, 2007

OCD-HOBBS

JUN 26 2009

**HOBBSOCD** 

EA-09-167

Form 3160-3 (April 2004)

# UNITED STATES

DEPARTMENT OF .THE INTERIOR BUREAU OF LAND MANAGEMENT					).			<del></del>
APPLICATION FOR PERMIT TO D	6. If Indian, Allotee or Tribe Name N/A							
1a. Type of work: ✓ DRILL REENTER	<b>?</b>			7 If Unit or CA Ag	reement	,		
lb Type of Well: ✓ Oil Well Gas Well Other	<b>√</b> Si	ngle ZoneMulti	ple Zone	8 Lease Name and Southeast Lu				120)
Name of Operator  Edge Petroleum Operating Company	_ <	224400	>	9 API Well No. 30-02	5- :	394	156	,
3a Address 1301 Travis Suite 2000 Houston, TX 77002		o. (include area code) ( 5-9808		10 Field and Pool, or Lusk Bone S	,	,	<b>\u</b>	राष्ट्र
4 Location of Well (Report location clearly and in accordance with any At surface 1685' FSL & 990' FWL	State requirem	ients.*)		11. Sec., T. R. M or		-	or Area	
At proposed prod zone 1685' FSL & 990" FWL				Sec 27, T- 19	S, R- 3	2E		
<ol> <li>Distance in miles and direction from nearest town or post office*</li> <li>6 miles southwest direction from Malaga NM</li> </ol>				12. County or Parish Lea Co		13	State NN	<u>—</u> м
location to nearest property or lease line, ft (Also to nearest drig unit line, if any)	16. No. of a	cres in lease 20 acres		g Unit dedicated to this SW/4 of Sec 27	well			
18 Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft  743'	4			BIA Bond No on file				
21 Elevations (Show whether DF, KDB, RT, GL, etc.) 2 3572' GL	22 Approxin	nate date work will star 04/15/2009	rt*	23 Estimated duration 30 days	on			-
	24. Attac			,				_
<ol> <li>The following, completed in accordance with the requirements of Onshore (</li> <li>Well plat certified by a registered surveyor</li> <li>A Drilling Plan.</li> <li>A Surface Use Plan (if the location is on National Forest System La SUPO shall be filed with the appropriate Forest Service Office).</li> </ol>		4 Bond to cover the Item 20 above) 5. Operator certific	ne operation ation specific info	is form  Is unless covered by an armation and/or plans a				
25 Signapire Lingela Lighther		(Printed/Typed) Angela Lightner a	ngela@rkf	ord.com	Date 1	0/03/20	D8	
Title Consultant 432-682-0440 office								<del>-</del>
Approved by (Signature)  Wellen Markey		Printed/Typed) Light Me	chen	.2	Date	JUN	2 :	
Title STATE DIRECTOR	Office	NM	STAT	E OFFICE	1 <u></u>			<del></del>
Application approval does not warrant or certify that the applicant holds le	gal or equita	ble title to those right	s in the subj	ect lease which would e	ntitle th	e applica	int to	

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction

\*(Instructions on page 2)

conduct operations thereon.

CAPITAN CONTROLLED WATER BASIN

Conditions of approval, if any, are attached.

SEE ATTACHED FOR CONDITIONS OF APPROVAL

APPROVAL SUBJECT TO GENERAL REQUIREMENTS AND SPECIAL STIPULATIONS **ATTACHED** 

\* APPROVAL FOR TWO YEARS

#### United States Department of the Interior Bureau of Land Management Roswell Field Office 2909 Second Street Roswell, New Mexico 88201-1287

#### Statement Accepting Responsibility for Operations

Operator Name:

Edge Petroleum Operating Company, Inc.

Street or Box:

1301 Travis, Suite 2000

City, State:

Houston, Texas

Zip Code:

77002

The undersigned accepts all applicable terms, conditions, stipulations, and restrictions concerning operations conducted on the leased land or portion thereof, as described below:

Lease No:

NM 12412

Legal Description of Land:

Lea

Township 19 South, Range 32 East, Eddy, New Mexico

SE/4 SW/4 of Section 27

**Bond Coverage:** 

Statewide Oil and Gas Surety Bond, Edge Petroleum Operating Company, Inc.

**BLM Bond File No.:** 

NMB-000121

Angela Lightner,

Agent

October 3, 2008

### RECEIVED

State of New Mexico

DISTRICT I 1625 N. FRENCH DR. HOBBS, NM 88240

JUN 25 ZIIII3 Energy, Minerals and Natural Resources Department

DISTRICT II 1301 W. GRAND AVENUE, ARTESIA, NM 88210

DISTRICT IV

### HOBBSACCONSERVATION DIVISION Submit to Appropriate District Office State Leave = 4 Control 1220 SOUTH ST. FRANCIS DR.

RONALD J EIDSON 3239

DISTRICT III 1000 Rio Brazos Rd., Aztec, NM 87410

1220 S ST. FRANCIS DR., SANTA FE, NM 87505

Santa Fe, New Mexico 87505

WELL LOCATION AND ACREAGE DEDICATION PLAT

Revised October 12, 2005 State Lease - 4 Copies
Fee Lease - 3 Copies

☐ AMENDED REPORT

Form C-102

Property Name   SOUTHEAST LUSK 27 FEDERAL   SOUTHEAST NAME   SOUTHEAST NAME   SOUTHEAST NAME   SOUTHEAST LUSK 27 FEDERAL   SOUTHEAST LUSK 27	API Numb		4 1	Pool Code			Pool Name		LD REI O
SOUTHEAST LUSK 27 FEDERAL  SOUTHEAST LUSK 27 FEDERAL  SOUTHEAST LUSK 27 FEDERAL  SOUTH			460	Lu	sk Bone	Spring	South		
GEODE IN COCKED No. CO							Well Nu	ımber	
UL or lot No. Section Township Range Lot Ida Feet from the SOUTH 990 WEST LEA  ### Dotton Hole Location If Different From Surface  ### Dotton Hole Location If Different From Surface  ### Ut or lot No. Section Township Range Lot Ida Feet from the North/South line Feet from the East/West line County  ### Dotton Hole Location If Different From Surface  ### Ut or lot No. Section Township Range Lot Ida Feet from the North/South line Feet from the East/West line County  ### Dotton Hole Location If Different From Surface  ### Ut or lot No. Section Township Range Lot Ida Feet from the North/South line Feet from the East/West line County  ### Dotton Hole Location If Different From Surface  ### Ut or lot No. Section Township Range Lot Ida Feet from the North/South line Feet from the East/West line County  ### Dotton Hole Location In Different From Surface  ### Dotton Hole Location Feet from the North/South line Feet from the East/West line County  ### Dotton Hole Location Feet from the North/South line Feet from the East/West line County  ### Dotton Hole Location Feet from the North/South line Feet from the East/West line County  ### Dotton Hole Location Feet from the North/South line Feet from the East/West line County  ### Dotton Hole Location Feet from the North/South line Feet from the East/West line County  ### Dotton Hole Location Feet from the North/South line Feet from the East/West line County  ### Dotton Hole Location Feet from the North/South line Feet from the East/West line County  ### Dotton Hole Location Feet from the North/South line Feet from the Rest/West line County  ### Dotton Hole Location Feet from the North/South line Feet from the East/West line County  ### Dotton Hole Location Feet from the North/South line Feet from the Rest/West line County  ### Dotton Hole Location Feet from the North/South line Feet from the North/South line Feet from the Rest/West line County  ### Dotton Hole Location Feet from the North/South line Feet from the North/South line Feet from the Location Feet from the North/Sou	OGRID No	-	EL	OCE DET				ľ	
UL or lot No.   Section   19-5   32-E   Lot Idn   1685   SOUTH   990   WEST   LEA	199 4400		EL	GE FEI			•	357	2'
Bottom Hole Location If Different From Surface  UL or tot No. Section Township Reage Lot ton Feet from the North/South line Feet from the East/West line County  Dedicated Acres Joint or Infill Consolidation Code Order No.  NO ALLOWABLE WILL BE ASSIGNED TO THIS COMPLETION UNTIL ALL INTERESTS HAVE BEEN CONSOLIDATED  NO ALLOWABLE WILL BE ASSIGNED TO THIS COMPLETION UNTIL ALL INTERESTS HAVE BEEN CONSOLIDATED  OPERATOR CERTIFICATION  I beredy certify that the information for runlased mineral interest in the land or organization of their owns and complete to the best of organization of their owns and complete to the best of organization of the runlased mineral interest in the land to the first of the control	III. or lot No.   Section	ion Tamakin	P	1					
Bottom Hole Location If Different From Surface  UL or lot No. Section Township Range Lot Idn Feet from the North/South line Feet from the East/West line County  Dedicated Acres Joint or Infill Consolidation Code Order No.  NO ALLOWABLE WILL BE ASSIGNED TO THIS COMPLETION UNTIL ALL INTERESTS HAVE BEEN CONSOLIDATED OR A NON-STANDARD UNIT HAS BEEN APPROVED BY THE DIVISION  OPERATOR CERTIFICATION Interest for the design of the first state and complete to the best of organization of other owns a working interest or appeared mineral interest in the land complete to the best of the state of the first state and complete to the best of or bas a right to drill this well at this location pursuant to a countext with an expensive pointing order heretolere entered by the stream.  GEODETIC COORDINATES NAD 27 NME  Y=592882.3 N  X=676853.4 E  LAT = 32 628622 N  LONG = 103 758673 W  SURVEYOR CERTIFICATION  I hereby control that the well houston notes or solution stream and control that the well houston notes or solution stream and the the same to the solution of the post we pointed the solution of the post we post the post we post the solution of the post we post the post we post the solution of the solution of the solution of the solution of the post we post the post we post the post we post the solution of th	[		1	Lot Idn	i	1	ļ		1
UL or lot No. Section Township Range Lot Idn Feet from the North/South line Feet from the East/West line County  Dedicated Acres Lot or Infill Consolidation Code Order No.  NO ALLOWABLE WILL BE ASSIGNED TO THIS COMPLETION UNTIL ALL INTERESTS HAVE BEEN CONSOLIDATED OR A NON-STANDARD UNIT HAS BEEN APPROVED BY THE DIVISION  OPERATOR CERTIFICATION  I bereaty certify that the information in five and complete to the best of any knowledge and belief, and that this organization either own a working interest including the proposed bottom bate location in finding the proposed bottom bate location or be set and the first of a working interest of as working interest of as working interest or a working interest or a working interest or as			L	<u></u>	L	1	L	WEST	LEA
Dedicated Acres Joint or Infill Consolidation Code Order No.  NO ALLOWABLE WILL BE ASSIGNED TO THIS COMPLETION UNTIL ALL INTERESTS HAVE BEEN CONSOLIDATED OR A NON-STANDARD UNIT HAS BEEN APPROVED BY THE DIVISION  OPERATOR CERTIFICATION  I hereby certify that the information for instance of such united or unlessed mineral interest in the lead to the focation previous of such united or such distinction of such united or such	III or lot No Socti	on Township	T	T	r				
NO ALLOWABLE WILL BE ASSIGNED TO THIS COMPLETION UNTIL ALL INTERESTS HAVE BEEN CONSOLIDATED OR A NON-STANDARD UNIT HAS BEEN APPROVED BY THE DIVISION  OPERATOR CERTIFICATION  been brown or with the information or provide and complete to the best of my knowledge and complete to the best of my best was plotted from field motion of the my control of the m	or or lot No.   Secu	on Township	Kange	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
NO ALLOWABLE WILL BE ASSIGNED TO THIS COMPLETION UNTIL ALL INTERESTS HAVE BEEN CONSOLIDATED OR A NON-STANDARD UNIT HAS BEEN APPROVED BY THE DIVISION  OPERATOR CERTIFICATION  There is no being of certify that the information on phore in the land of the part o	Dedicated Acres Jo	int or Infill Co	ngolidation	Code On	dan No				
OPERATOR CERTIFICATION  I hereby certify that the information beroin is true and complete to the best of my knowledge and belief, and that this organization either owns working interest the best of my knowledge and belief, and that this organization either owns working interest the children the proposed bottom beloe location or has a right to drill this real at this location pursuant to a contract with an increase of the cont	40/		asonadan i	Louic Or o	der No.				
OPERATOR CERTIFICATION  I hereby certify that the information beroin is true and complete to the best of my knowledge and belief, and that this organization either owns working interest the best of my knowledge and belief, and that this organization either owns working interest the children the proposed bottom beloe location or has a right to drill this real at this location pursuant to a contract with an increase of the cont	NO ALLOWARI	F WILL DE AS	CCICNIED C	TO THE	COMPLEMENT				
OPERATOR CERTIFICATION  I breeky certify that the information herein is true and complete to the best of my knowledge and belief, and that this organization either owns a working interest or providing the proposed soft in the factor of best a right to drill this rest at this location pursuant to a contract with an own for a working interest or sorking interest or the strength of the proposed of the strength of	NO ALLOWADE	OR A N	ION-STAN	DARD UN	COMPLETION O IT HAS BEEN	NTIL ALL INTER APPROVED BY T	EESTS HAVE BE THE DIVISION	EEN CONSOLIDA	TED
See Detail   See				T			7		
Berein is true and complete to the best of my knowledge and belief, and that this will knowledge and belief, and that this or unlessed mineral the proposed bottom bole location or unlessed mineral the proposed bottom bole location or bas a right to drill this well at this location pursuant or a contract with an even of the proposed bottom pursuant or a contract with an even of the driving of t		1			!		OPERATO	R CERTIFICAT	ION
GEODETIC COORDINATES  NAD 27 NME  Y=592882.3 N X=676853.4 E  LAT = 32 628622 N LONG = 103 758879 W  SURVEYOR CERTIFICATION    hereby certify that the well location shows on this plat was plotted from field under my supervision, and that the some is true and correct to the best of my belief.  SEE DETAIL    DETAIL   3575 6' 3574 9'   DETAIL   OB			1	ļ			herein is true	and complete to the	best of
GEODETIC COORDINATES NAD 27 NME  Y=592882.3 N X=67685.3 t E LAT = 32 628622 N LONG = 103 758879' W  SIRVEYOR CERTIFICATION  1 hereby certify that the well location show on this plat was plotted from field under our action such such such such such such such such		1	i		·		organization eit	her owns a working	interest
GEODETIC COORDINATES NAD 27 NME  Y=592882.3 N X=676853.4 E  LAI = 32 628622 N LONG = 103 758879 W  SURVEYOR CERTIFICATION  I hereby certify that the well location shown on this plet was pletted from field notes of actual survey made by the did notes of actual survey made by the did notes of actual survey made by the did notes of actual survey made by the field no		1	1				including the p	roposed bottom hole to drill this well at	location
GEODETIC COORDINATES NAD 27 NME  Y=592882.3 N X=676853.4 E  LAT = 32 628622' N LONG = 103 758879' W  SURVEYOR CERTIFICATION  I hereby certify that the well location shown on this plot was plotted from field notes of actual under my supervision, and that the same is true and correct to the best of my belief.  SEE DETAIL  DETAIL  3575 6' 3574 9'  O 80  O		1	l		1		owner of such	mineral or working :	Interest
GEODETIC COORDINATES NAD 27 NME  Y=592882.3 N X=676853.4 E  LAT = 32 628622' N LONG = 103 758879' W  SURVEYOR CERTIFICATION  I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief.  SEE DETAIL  SEE DETAIL  DETAIL  3575 6' 3574 9'  O & O O O O O O O O O O O O O O O O O							compulsory poo	ling order heretofore	t or a entered
Y=592882.3 N X=676853.4 E  LAT = 32 628622' N LONG = 103 758879' W  SURVEYOR CERTIFICATION  I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief.  SEE DETAIL  SEE DETAIL  DETAIL  3575 6' 3574 9'  DETAIL  AMOUST 15, 2008  Date Surveyed: AR Signature & Seal of Professional Surveyor  AMOUST 15, 2008  Date Surveyed: AR  Signature & Seal of Professional Surveyor  AMOUST 15, 2008  Date Surveyed: AR  Signature & Seal of Professional Surveyor		GE			īs				
Y=592882.3 N X=676853.4 E  LAT = 32 628622: N LONG = 103 758879: W  SURVEYOR CERTIFICATION  I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief.  SEE DETAIL  990'  DETAIL  3575 6: 3574 9'  O O O O O O O O O O O O O O O O O O O		1	NAD 27	7 NME	!		1 2		
LAT = 32 628622' N LONG = 103 758879' W  SURVEYOR CERTIFICATION  I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief.  SEE DETAIL  SEE DETAIL  DETAIL  DETAIL  DETAIL  DETAIL  DETAIL  DETAIL  OB  OB  OB  OB  OB  OB  OB  OB  OB  O							Signature	Dat	e
SURVEYOR CERTIFICATION  I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief.  SEE DETAIL  SEE DETAIL  DETAIL  3575 6' 3574 9'  DETAIL  O BLOOK SURVEYOR CERTIFICATION  I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief.  ALGUST 15: 2008  Date Surveyed: AR  Signature & Seal of Professional Surveyor  O BLOOK SIGNATURE SI		ı	X=6/68.	53.4 E	· 1		Printed Name	la high!	MOTO
SURVEYOR CERTIFICATION  I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief.  SEE DETAIL  SEE DETAIL  OB  DETAIL  3575 6' 3574 9'		T .			4/				
SEE DETAIL  SEE DETAIL  SEE DETAIL  SEE DETAIL  SOURCE  ADGUST 15: 2008  Date Surveyed!  Signature & Seal of Professional Surveyor  3575 6' 3574 9'  DETAIL  SOURCE  AR  Signature & Seal of Professional Surveyor  AR  Signature & Seal of Professional Surveyor							SURVEYO	R CERTIFICATI	ON
SEE DETAIL  SEE DETAIL  SEE DETAIL  SEE DETAIL  SEE DETAIL  SOURCE  DETAIL  3575 6 3574 9'  DETAIL  Shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief.  AUGUST 15, 2008  Date Surveyed!  AR  Signature & Seal of Professional Surveyor  AR  Signature & Seal of Professional Surveyor		•			ļ		I hereby o	ertify that the well	location
SEE DETAIL  990'  Detail  3575 6'  3574 9'  Detail  O  O  O  O  O  O  O  O  O  O  O  O  O		į.					notes of actual	lat was plotted from surveys made by me	field
990'  Detail 3575 6' 3574 9'		7 12 12	İ		ŧ		true and correct	to the best of my	belief.
DETAIL  3575 6' 3574 9'  O OU	SEE DETA							- 1 5 5 Mg	
DETAIL   Signature & Seal of Professional Surveyor	990'	- -	Ì	*	ı		ĀUGÙ	ST 15, 2008	
DETAIL 3575 6' 3574 9'  O 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0			1				11		AR
6 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6		DETAIL							
- 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0		1	- 1		l				
	1685		i		1		Kowalk	En Dan Rho	7/00
and the second s		1 1 0	909		1		108	11.1.1.3285	100
3569 7' 3571 7' Certificate No GARY EIDSON 12641		1 600'	- J				Certificate No	GARY EIDSON	12641

#### **8 POINT DRILLING PROGRAM**

# EDGE PETROLEUM OPERATING COMPANY, INC. SOUTHEAST LUSK "27" FEDERAL #5

Section 27 T-19-S, R-32-E Lea County, New Mexico

The following items supplement Form 3160-3 in accordance with instructions contained in Onshore Oil and Gas Orders #1 and #2, and all other applicable federal and state regulations.

1.	ESTIMATED TOPS OF GE	EOLOGIC MARK	(ERS (TVD)
	Anhydrite	Water	890'
	Yates	Water	2,665'
	Capitan	Water	3,525'
	Delaware	Oil	4,240'
	Cherry Canyon	Oil	4,748'
	Brushy Canyon	Oil	5,877'
	Lwr Brushy Canyon	. Oil	7,174'
	1 <sup>st</sup> Bone Springs Lm	<sup>'</sup> Oil	7,424'
	Bone Springs Lm Pay	Oil	7,616'
	Total Depth		8.000'

2. PRESSURE CONTROL EQUIPMENT The blow out preventer equipment (BOP) shown in Exhibit #1 will consist of a 3000 psi double ram type preventer for drilling the 13-1/2" hole. The blowout preventer stack for the production 6-3/4" hole as shown on Exhibit #2 will consist of at least a double-ram blowout preventer and annular preventer rated to 5000 psi working pressure. A diagram of the BOPs and choke manifold is attached. All BOPs and accessory equipment will be tested according to Onshore Order #2 before drilling out.

#### 3. PROPOSED CASING PROGRAM

Hole	Sz Interval	Csg	<u>vvt</u>	<u>Grade, Joint</u>	Collapse	<u>Tension</u>	Burst
20"	0 – 40'	20"	52.8#	X-42, BPE			
18-1/	2" 0 – 890'	16"	65#	H-40, STC	1.65	4.03	8.76
<u>/13-1/2</u>				J-55, STC	1.28	2.19	6.73
				HPG-110, LTC		4.39	6.77
				P-110, Ultra FJ	2.72	3.29	3.38
All ca	sing for this pro	<u>ject is ne</u>	w casir	<u>ng</u>			

There will be a DV Tool above an External Casing Packer (ECP) which is to be set inside the 13-1/2" casing at 3000 +/-. Cement will be circulated to surface. Equivalent or adequate grades and weights of casing may be substituted at time casing is run, depending on availability. Changes will be relayed to BLM prior to running.

See COA

600 -

### 4. PROPOSED CEMENTING PROGRAM LE GEE COM

20" conductor cemented with ready mix to surface

16" surf. Lead Slurry – 385 sxs "C" cement + 4% D20 + 2% S1 + 3 pps

D42 slurry wt.- 13.5, yield - 1.75 ft<sup>3</sup>/sk

Tail Slurry - 155 sks "C" cement + 2% S1, slurry wt.- 14.8, yield -

1.34 ft<sup>3</sup>/sk, TOC - surface

10-3/4"1st inter. Lead Slurry - 1015 sxs 35:65 Poz: "C" cement + 5% D44 bwow +

6% D20 + 3 pps D42 + 0.25pps D29, slurry wt. - 12.4, yield- 2.17

ft³/sk

Tail Slurry - 375 sxs "C" cement + 1% S1, slurry wt.- 14.8, yield -

1.33 ft<sup>3</sup>/sk, TOC - surface.

7-5/8" 2<sup>nd</sup> inter. 1<sup>st</sup> stage Lead Slurry - 70 sxs 50:50 Poz: "C" cement + 6% D44

bwow + 10% D20 + 0.25 pps D29 + 3 pps D42, slurry wt.- 11.9,

yield - 2.51 ft<sup>3</sup>/sk

hee 7

1 stageTail Slurry - 105 sxs "C" cement + 0.25 pps D29, slurry

wt.-14.8, yield - 1.32 ft<sup>3</sup>/sk, TOC - 3,000'

2nd stage Lead Slurry- 300 sxs 50:50 Poz: "C" cement + 6% D44 bwow + 10% D20 + 0.25 pps D29 + 1 pps D42, slurry wt.- 11.9,

yield- 2.5 ft<sup>3</sup>/sk, TOC- surface

2nd stage Tail Slurry- 60 sxs "C" cement + 0.25 pps D29, slurry

wt.- 14.8, yield - 1.32 ft<sup>3</sup>/sk, TOC- surface

5-1/2" prod.

Lead Slurry- 485 sxs 50:50 Poz: "H" cement + 5% D44 bwow + 2% D20 + 0.125 pps D29 + 1 pps D42, slurry wt. - 14.2, yield -

1.36 ft<sup>3</sup>/sk; TOC- surface

her COM

#### PROPOSED MUD SYSTEM

	DEPTH	DESCRIPTION	MUD WEIGHT	VISCOSITY	WATER LOSS
	0 – 890'	Fresh water	8.4 – 9.4 ppg	32 – 34	NC
ور	890' – 3 <del>,08</del> 0'	Brine water	10.0 ppg	28	NC
	.3,080' - 4,270'	Fresh water	8.3 - 8.5  ppg	28	NC
	4,270' - 7,200'	Fresh water	8.4 – 8.5 ppg	28	NC
	7,200' - 8,000'	Fresh water	8.5 - 8.7 ppg	30 - 32	12cc

#### 6. TESTING, LOGGING AND CORING PROGRAM

Samples None are planned DST's None are planned

Logging Neutron/Density and Resistivity

Coring Possible sidewall core

Edge Petroleum Operating Company, Inc. Southeast Lusk "27" Federal #5 Driffing Program

#### 7. ABNORMAL PRESSURES AND TEMPERATURES

None anticipated. Maximum bottom hole pressure should not exceed 4,000 psi. Maximum bottom hole temperature should not exceed 117°. This area has a potential H<sub>2</sub>S hazard. An H<sub>2</sub>S drilling plan is attached and a contingency program has been done and on file with the BLM.

#### 8. ANTICIPATED STARTING DATE AND DURATION OF OPERATIONS

It is planned that operations will commence on or about April 15, 2009. Drilling should be completed within 30 days followed by completion operations.

### HYDROGEN SULFIDE DRILLING OPERATIONS PLAN

### **EDGE PETROLEUM OPERATING COMPANY, INC.**

Southeast Lusk "27" Federal #5

#### I. HYDROGEN SULFIDE TRAINING

- A. All regularly assigned personnel, contracted or employed by Edge Petroleum Corporation, will receive training from a qualified instructor in the following areas prior to commencing drilling potential hydrogen sulfide bearing formations in this well:
  - 1. The hazards and characteristics of hydrogen sulfide  $(H_2S)$ .
  - 2. The proper use and maintenance of personal protective equipment and life support systems.
  - 3. The proper use of H<sub>2</sub>S detectors, alarms, warning systems, briefing areas, evacuation procedures and prevailing winds.
  - **4.** The proper techniques for first aid and rescue procedures.
- **B.** In addition, supervisory personnel will be trained in the following areas:
  - 1. The effects of H<sub>2</sub>S on metal components. If high tensile tubulars are to be used, personnel will be trained in their special maintenance requirements.
  - Corrective action and shut-in procedures when drilling or reworking a well and blowout prevention and well control procedures.
  - 3. The contents and requirements of the H₂S Drilling Operations Plan.
- C. There will be an initial training session just prior to encountering a known or probable H<sub>2</sub>S zone (within 3 days or 500 feet) and weekly H<sub>2</sub>S and well control drills for all personnel in each crew. The initial training session shall include a review of the site specific H<sub>2</sub>S Drilling Operations Plan. This plan shall be available at the well site. All personnel will be required to carry documentation that they have received the proper training.

#### II. H<sub>2</sub>S SAFETY EQUIPMENT AND SYSTEMS

Note: All H<sub>2</sub>S safety equipment and systems will be installed, tested and operational when drilling reaches a depth of 500 feet above, or three days prior to penetrating the first zone containing or reasonably expected to contain H<sub>2</sub>S.

#### A. Well Control Equipment

- **1.** Flare line with continuous pilot.
- 2. Choke manifold with a minimum of one remote choke.
- 3. Blind rams and pipe rams to accommodate all pipe sizes with properly sized closing unit.
- **4.** Auxiliary equipment to include: annular preventer, mud-gas separator, rotating head and flare.
- B. Protective Equipment for Essential Personnel

Mark II Surviveair 30-minute units located in the doghouse and at briefing areas, as indicated on well site diagram.

- C. H<sub>2</sub>S Detection and Monitoring Equipment
  - 1. Two portable H<sub>2</sub>S monitors positioned on location for best coverage and response. These units have warning lights and audible sirens when H<sub>2</sub>S levels of 20 ppm are reached.
  - 2. One portable SO<sub>2</sub> monitor positioned near flare line.

#### D. Visual Warning Systems

- 1. Wind direction indicators are shown on well site diagram.
- 2. Caution/Danger signs shall be posted on roads providing direct access to location. Signs will be painted a high visibility yellow with black lettering of sufficient size to be readable at a reasonable distance form the immediate location. Bilingual signs will be used when appropriate. See example attached.

#### E. Mud Program

- 1. The Mud Program has been designed to minimize the volume of H<sub>2</sub>S circulated to the surface. Proper mud weights, safe drilling practices and the use of H<sub>2</sub>S scavengers will minimize hazards when penetrating H<sub>2</sub>S bearing zones.
- 2. A mud-gas separator will be utilized as needed.

#### F. Metallurgy

All drill strings, casing, tubing, wellhead, blowout preventers, drilling spool, kill lines, choke manifold and line and valves shall be suitable for H<sub>2</sub>S service.

#### G. Communication

Cellular telephone communications in company vehicles, rig floor and mud logging trailer.

#### H. Well Testing

Drill stem testing will be performed with a minimum number of personnel in the immediate vicinity, which are necessary to safely and adequately conduct the test. The drill stem testing and an H<sub>2</sub>S environment will be conducted during the daylight hours.

### **PRIMARY CEMENTING PROPOSAL**

#### **4 CASING STRINGS**

## Edge Petroleum

SE Lusk 27 Fed. 5

#### **Well Location**

County: Lea

State : New Mexico

Country: USA

Prepared for : Angela Service Point : HOBBS, NM

Business Phone: 505-393-6186

Date Prepared : 8-Sep-08 FAX No. : 505-393-2132

 Prepared by
 :
 Bear Bryant

 Phone
 :
 505-393-6186

 FAX
 :
 505-393-2132

E-Mail address : bryant8@hobbs.oilfield.slb.com

#### Disclaimer Notice

This information is presented in good faith, but no warranty is given and Dowell assumes no liability for advice or recommendations made concerning results to be obtained from the use of any product or service. Prices quoted are estimates only, and are good for 30 days from the date of issue. Adual charges may vary depending upon time, equipment, and material, ultimately required to perform these services. Freedom from infringement of patents of Dowell or others is not to be inferred.

Edge Petroleum SE Lusk 27 Fed 5 Lea County, New Mexico Page 2

#### Well Data: 13 3/8 in. Surface Casing

< Surface 890 ft. Depth

> 13 3/8 in., 54.5 lbs./ft. Casing Size

17 1/2 in. Open Hole Diameter **BHST** 80 °F **BHCT** 80.0 °F 100 % **Total Excess** 100.0 % Lead Excess (calculated O.H.)

Tail Excess 100 %

< Top of Cement

< Previous Csg ft.

#### Mud Wt./Type: 8.5 ppg Fresh Wtr. Based

#### **Calculations:**

#### **Volume Factors:**

Casing x Open Hole 0.6946 cu.ft./ft Casing (Internal) 0.8675 cu.ft./ft

Top of Lead Surface Top of Tail 720 ft.

#### **Lead System:**

Total Lead Fill  $(720 \times 0.6946 \times 2.0) / 1.75 = 570$  sks.

#### **Tail System:**

Open Hole Fill  $(170 \times 0.6946 \times 2.) / 1.34 = 176$  sks. **Casing Shoe Cement**  $(40 \times 0.8675) / 1.34 = 26$  sks.

Total Tail Cement = 202 sks.

Edge Petroleum SE Lusk 27 Fed 5 Lea County, New Mexico Page 3

### **Cementing Systems**

Lead System: 570 sks.

Class C + 4% D20 + 2% S1 + 3 pps D42

Mix Weight

13.5 PPG

Yield

1.75 cu.ft./sk.

Mix Water

8.95 gal./sk.

(Fresh Water)

Tail System: 200 sks.

Class C + 2% S1

Mix Weight

14.8 PPG

Yield

1.34 cu.ft./sk.

Mix Water

6.3 gal./sk.

(Fresh Water)

Notice

Performance parameters for coment systems recommended are typically taken from existing laboratory data. In some cases, data exist which duplicate the recommended systems and job environment, but when those data do not exist, extrapolations are made from data which most closely match the anticipated conditions. Sufficient lead-time should always be allowed, so that pilot samples/field blends can be run to verify system performance. parameters, before actually pumping the job

Edge Petroleum SE Lusk 27 Fed. 5 Lea County, New Mexico Page 5

#### Well Data: 10 3/4 in. Intermediate Casing

Depth 3,080 ft. < Surface

10 3/4 in., 45.5 lbs./ft. Casing Size

Open Hole Diameter 12 1/4 in. Previous Csg. Depth 890 ft.

Previous Csg. Size 13 3/8 in., 54.5 lbs./ft.

95 °F **BHST BHCT** 80.0 °F **Total Excess** 165 % 241.5 %

Lead Excess (calculated O.H.) < Top of Cement

50 % Tail Excess

Mud Wt./Type: 8.5 ppg Brine Based < Previous Csg. 890 ft.

#### **Calculations:**

#### **Volume Factors:**

0.1882 cu.ft./ft Casing x Open Hole Casing x Previous Casing 0.2372 cu.ft./ft Casing (Internal) 0.54 cu.ft./ft

Top of Lead **Surface** Top of Tail 2,205 ft.

#### **Lead System:**

Open Hole Fill  $(1,315 \times 0.1882 \times 3.42) / 2.17 = 390 \text{ sks.}$ Previous Casing Fill  $(890 \times 0.2372) / 2.17 = 98$  sks. Total Lead Cement = 487 sks.

**Tail System:** 

Open Hole Fill  $(875 \times 0.1882 \times 1.5) / 1.33 = 186 \text{ sks}.$ Casing Shoe Cement  $(40 \times 0.54) / 1.33 = 16$  sks.

Total Tail Cement = 202 sks.

Edge Petroleum SE Lusk 27 Fed 5 Lea County, New Mexico Page 6

### **Cementing Systems**

Lead System: 485 sks.

35:65 Poz:Class C + 5% D44 (bwow) + 6% D20 + 3 pps D42 + 0.25 pps D29

Mix Weight : 12.4 PPG

2.17 cu.ft./sk. Yield

Mix Water : 11.86 gal./sk. (Fresh Water)

Tail System: 200 sks.

Class C + 1% S1

Mix Weight : 14.8 PPG

 
 Yield
 :
 1.33 cu.ft./sk.

 Mix Water
 :
 6.3 gal./sk.
 (Fresh Water)

Edge Petroleum SE Lusk 27 Fed. 5 Lea County, New Mexico Page 8

#### Well Data: 7 5/8 in. 2Nd Intermediate - Stage 1

< Surface	Depth	4,270 ft.

Casing Size 7 5/8 in., 26 lbs./ft.

Open Hole Diameter 9 1/2 in. Previous Csg. Depth 3,080 ft.

Previous Csg. Size 10 3/4 in., 45.5 lbs./ft.

BHST 115 °F 80.0 °F Total Excess 50 % Lead Excess (calculated O.H.) 50.0 %

Lead Excess (calculated O.H.) 50.0 % Tail Excess 50 %

Stage Collar Depth 3,000 ft.

< Previous Csg. 3,080 ft.

< Top of Cement

#### Mud Wt./Type: 9.5 ppg Brine Based

#### Calculations:

#### **Volume Factors:**

Casing x Open Hole 0.1751 cu.ft./ft
Casing x Previous Casing 0.2229 cu.ft./ft
Casing (Internal) 0.2655 cu.ft./ft

Top of Lead 3,080 ft.
Top of Tail 3,770 ft.

#### **Lead System:**

Total Lead Fill  $(690 \times 0.1751 \times 1.5) / 2.51 = 72$  sks.

#### Tail System:

Open Hole Fill  $(500 \times 0.1751 \times 1.5) / 1.32 = 99 \text{ sks.}$ Casing Shoe Cement  $(40 \times 0.2655) / 1.32 = 8 \text{ sks.}$ Total Tail Cement = 107 sks.

Edge Petroleum SE Lusk 27 Fed. 5 Lea County, New Mexico Page 9

#### **Cementing Systems**

Lead System: 70 sks.

50:50 Poz:Class C + 6% D44 (bwow) + 10% D20 + 0.25 pps D29 + 3 pps D42

Mix Weight

11.9 PPG

Yield

2.51 cu.ft./sk.

Mix Water : 14.22 gal./sk.

(Fresh Water)

Tail System: 105 sks.

Class C + 0.25 pps D29

Mix Weight :

14.8 PPG

Yield : Mix Water :

1.32 cu.ft./sk.

6.3 gal./sk.

(Fresh Water)

Edge Petroleum SE Lusk 27 Fed. 5 Lea County, New Mexico Page 10

#### Well Data: 7 5/8 in. 2Nd Intermediate - Stage 2

< Surface Depth	4,270 ft.
-----------------	-----------

Casing Size 7 5/8 in., 26 lbs./ft.

Open Hole Diameter 9 1/2 in. Previous Csg. Depth 3,080 ft.

Previous Csg. Size 10 3/4 in., 45.5 lbs./ft.

**BHST** 115 °F внст 94.8 °F **Total Excess** 15 % Lead Excess (calculated O.H.) 0.0 % 50 %

< Top of Cement Tail Excess

Stage Collar Depth 3,000 ft.

< Previous Csg. 3,080 ft.

#### Mud Wt./Type: 9.5 ppg Fresh Wtr. Based

#### **Calculations:**

#### **Volume Factors:**

Casing x Open Hole 0.1751 cu.ft./ft Casing x Previous Casing 0.2229 cu.ft./ft Casing (Internal) 0.2655 cu.ft./ft

Top of Lead Surface Top of Tail 2,800 ft.

#### **Lead System:**

Previous Casing Fill  $(2,800 \times 0.2229 \times 1.15) / 2.5 = 287 \text{ sks.}$ 

#### **Tail System:**

Previous Casing Fill  $(200 \times 0.2229 \times 1.5) / 1.32 = 50 \text{ sks.}$ Casing Shoe Cement  $(40 \times 0.2655) / 1.32 = 8 \text{ sks}.$ 1Total Tail Cement = 58 sks.

Edge Petroleum SE Lusk 27 Fed. 5 Lea County, New Mexico Page 11

### **Cementing Systems**

Lead System: 285 sks.

50:50 Poz:Class C + 6% D44 (bwow) + 10% D20 + 0.25 pps D29 + 1 pps D42

Mix Weight : 11.9 PPG

Yield : 2.5 cu.ft./sk.

Mix Water : 14.28 gal./sk. (Fresh Water)

Tail System: 60 sks.

Class C + 0.25 pps D29

Mix Weight : 14.8 PPG Yield : 1.32 cu.ft./sk.

Mix Water : 6.3 gal./sk. (Fresh Water)

Edge Petroleum SE Lusk 27 Fed. 5 Lea County, New Mexico Page 13

#### Well Data: 5 1/2 in. Production Casing

< Surface

Depth 8,000 ft.

Casing Size 5 1/2 in., 17 lbs./ft.

Open Hole Diameter 6 1/2 in. Previous Csg. Depth 4,270 ft.

Previous Csg. Size 7 5/8 in., 26 lbs./ft.

 BHST
 120 °F

 BHCT
 80.0 °F

 Total Excess
 50 %

 Tail Excess
 100 %

< Top of Cement 4,000 ft.

< Previous Csg 4,270 ft.

#### Mud Wt./Type: 9.5 ppg Brine Based

#### **Calculations:**

#### **Volume Factors:**

Casing x Open Hole 0.0654 cu.ft./ft
Casing x Previous Casing 0.1005 cu.ft./ft
Casing (Internal) 0.1312 cu.ft./ft

**Top of Cement** 

4,000 ft.

#### **Cement System:**

Open Hole Fill  $(3,730 \times 0.0654 \times 2.) / 1.36 = 359 \text{ sks.}$ Previous Casing Fill  $(270 \times 0.1005) / 1.36 = 20 \text{ sks.}$ Casing Shoe Cement  $(40 \times 0.1312) / 1.36 = 4 \text{ sks.}$ Total Tail Cement = 383 sks.

< T D. - 8,000 ft

Edge Petroleum SE Lusk 27 Fed. 5 Lea County, New Mexico Page 14

### **Cementing Systems**

Spacer System: 20 bbls .

**CW-100 Chemical Wash** 

Cement System: 385 sks.

50:50 Poz:Class H + 5% D44 (bwow) + 2% D20 + 0.125 pps D29 + 1 pps D42

Mix Weight : 14.2 PPG

Yield: 1.36 cu.ft./sk.

Mix Water : 6.28 gal./sk. (Fresh Water)

Edge Petroleum SE Lusk 27 Fed. 5 Lea County, New Mexico Page 16

This quote is valid for a period of thirty days from the date submitted. These prices are estimates based on current price structure and will vary somewhat with the materials, equipment, and time actually required at the time of service. The discount shown will be applicable to the most current Dowell price book in effect at the time of service. Not included are the costs of fluid storage, oil, water, (or transportation thereof) except as listed. Dowell does not offer these services.


The cement slurry data presented are from systems previously tested in Dowell laboratories. Thickening time tests should be run when field mix water is available and final temperatures are known. Mud\Cement compatibility tests should be run when final mud systems are in use. These tests could cause quantity variations of the materials recommended, thereby affecting the price of the job.


In the interest of safety, a pre-job tailgate safety meeting will be held with your representative and other on-location personnel to familiarize everyone with existing hazards and safety procedures. During this meeting a designated wash-up area will be assigned for our cementing unit to dispose of our cement slurry and drilling mud displacement fluid.

Thank you for considering Dowell for this work. Please do not hesitate to call with any questions or concerns.

Bear Bryant Hobbs, New Mexico

### DRILLING RIG LAYOUT Edge Petroleum Operating Co., Inc. Southeast Lusk 27 Federal #5






600'

Exhibit D Surface Use & Operations Plan

#### BOP SCHEMATIC FOR 12 1/4" Hole



Edge Petroleum Southeast Lusk 27 Federal #5 Lea County, New Mexico


### BOP SCHEMATIC FOR 9 1/2 HOLE **ROT HEAD** FLOW LINE TO PITS 2" FILL-UP LINE ANNULAR 11" 5M 11" 5M PIPE RAMS 11" 5M BLIND RAMS **5M ADJUSTABLE CHOKE** NOM 2" LINE 5M MGV NOM 2 LINE 5M MGV (SEQUENCE OPT) 5M CKV 5M MGV 5M MGV 5M HCR **DRILLING** 5M MGV 5M MGV SPOOL NOM 3" LINE MIN 2" NOM 5M KILL LINE MIN 3" NOM 5M CHOKE LINE -5M MGV W/ PRES GAUGE ON TOP OF BLOCK NOM 2 LINE 5M MGV

NOM 2'

5M REMOTELY OPERATED CHOKE

Edge Petroleum Southeast Lusk 27 Federal #5 Lea County, New Mexico

## LOCATION VERIFICATION MAP



SCALE: 1" = 2000'

SEC. \_27 TWP. 19-S RGE. 32-E

SURVEY\_\_\_\_\_\_\_N.M P.M

COUNTY\_\_LEA \_\_STATE\_NEW\_MEXICO

DESCRIPTION\_1685'\_FSL\_&\_990'\_FWL

ELEVATION \_\_\_\_\_\_\_3572'

EDGE PETROLEUM OPERATOR OPERATING CO.

LEASE SOUTHEAST LUSK 27 FEDERAL

U.S.G.S. TOPOGRAPHIC MAP GREENWOOD LAKE, N.M.

CONTOUR INTERVAL:
WILLIAMS SINK, N.M. – 10'
LAGUNA GATUNA, N.M. – 10'
LAGUNA GATUNA NW, N.M. – 10'
GREENWOOD LAKE, N.M. – 10'



PROVIDING SURVEYING SERVICES
SINCE 1946
JOHN WEST SURVEYING COMPANY
412 N. DAL PASO
HOBBS, N.M. 88240
(505) 393-3117

## VICINITY MAP

				· · · · · · · · · · · · · · · · · · ·					<del></del>		<del>-</del>		
	R 32 18	17	16	15	14	13 %	8 18 18	17	16	15	14	13 525	
T 18 S	19 X	H26 50	21	22	23	24	19	50	21	55	23	24 £	R 34 E
	30	29	58	27	26	25	30	29	28	27	26	25	
COUNTY	31	32	33	34	35	36	31	32	33	34	35	36	
EDDY CC	6	5	4	3	2	1	6	5	4	3	2	l	
Œ	7	8	9	10	11	12	7	8	9	10	11	12	
19 S	18 RY LAKE	17	16	15	14	13	18	17	16	15	14	13 % 33 %	R 34 E
F	HIZE LUSK PI	ł	21	25	23	24	19	50	21	22	23	24	
	30	29	28	27	26	25	30	29	28	27	56	25	
	31	32	33	34	SOUTHE	AST LUSK	27 FED	ERAL #5	<b>]</b> 3	34	35	36	
	6 Q	5	4 LAGUNA PLATA	3	-u <sup>2</sup> a	1	6	5	4	3	2	PARCE	
7 20 S	MAL JAMAR	H126	, {	10		12 ▼10	7	в	9	10	11	12	
H	18	17	16 ST. 243	15	14	L AGUNA HSS TO	18	LAGUNA GATUNA 17	62-180	15	14	13	

SCALE: 1" = 2 MILES

SEC. <u>27</u> 1	WP <u>19-S</u> RGE. <u>32-E</u>
SURVEY	N M.P.M.
COUNTYL	EA STATE NEW MEXICO
DESCRIPTION	1685' FSL & 990' FWL
ELEVATION	3572'
OPERATOR	EDGE PETROLEUM OPERATING CO.
LEASE_SOUTH	HEAST LUSK 27 FEDERAL



PROVIDING SURVEYING SERVICES
SINCE 1946
JOHN WEST SURVEYING COMPANY
412 N DAL PASO
HOBBS, N.M. 88240
(505) 393-3117

Ethibit B



SECTION 27, TOWNSHIP 19 SOUTH, RANGE 32 EAST, N.M.P.M., LEA COUNTY. NEW MEXICO 3575.61 600' *3574.9* ' 150' NORTH OFFSET 3573.9 SOUTHEAST LUSK 27 FEDERAL #5 150' WEST 150' EAST OFFSET □ OFFSET 0 3572.4' 3573.1' ELEV. 3572.0' LAT. = 32.628622° N LONG.=103.758879° W 360' OF PROPOSED RD TO LUSK 27 FED. #4 150' SOUTH **OFFSET** 3571.7 3569.7' 600' 3571.7' DIRECTIONS TO LOCATION FROM THE INTERSECTION OF ST. HWY. #243 AND CO. RD. H126, GO NORTH ON CO. RD. H126 APPROX. 4.0 MILES. TURN RIGHT AND GO EAST APPROX. 1.1 MILE. TURN RIGHT AND GO SOUTH THEN SOUTHEAST 100 100 200 Feet APPROX. 0.5 MILES. BEND LEFT AND GO EAST APPROX. Scale: 1"= 100' 0.7 MILES. TURN LEFT AND GO NORTH APPROX. 0.2 MILES TO LUSK 34 FEDERAL #3 WELL PAD TO EDGE PETROLEUM OPERATING CO. PROPOSED ROAD SURVEY. FOLLOW ROAD SURVEY NORTHEAST APPROX. 544 FEET TO THE PROPOSED LUSK 27 FEDERAL #2 WELL PAD THEN NORTH APPROX. 1047 FEET TO THE SOUTHWEST CORNER OF THIS LOCATION. SOUTHEAST LUSK 27 FEDERAL #5 WELL LOCATED 1685 FEET FROM THE SOUTH LINE AND 990 FEET FROM THE WEST LINE OF SECTION 27, TOWNSHIP 19 SOUTH, RANGE 32 EAST, N.M.P.M., LEA COUNTY, NEW MEXICO. PROVIDING SURVEYING SERVICES SINCE 1946 JOHN WEST SURVEYING COMPANY 412 N. DAL PASO HOBBS, N.M. 88240 (505) 393-3117 Survey Date: 8/15/08 Sheet of Sheets W.O. Number: 08.11.1328 | Dr By: AR Rev 1:10/1/08 Date: 8/26/08 08111328 Scale: 1 "= 100

### PECOS DISTRICT CONDITIONS OF APPROVAL

OPERATOR'S NAME:
LEASE NO.:
WELL NAME & NO.:
SURFACE HOLE FOOTAGE:
BOTTOM HOLE FOOTAGE
LOCATION:
COUNTY:
LEage Petroleum Operating Company
NM12412
Southeast Lusk 27 Federal No 5
1685' FSL & 990' FWL
Same
Section 27, T. 19 S., R 32 E., NMPM
Lea County, New Mexico

#### **TABLE OF CONTENTS**

Standard Conditions of Approval (COA) apply to this APD. If any deviations to these standards exist or special COAs are required, the section with the deviation or requirement will be checked below.

General Provisions
Permit Expiration
Archaeology, Paleontology, and Historical Sites
☐ Noxious Weeds
Special Requirements
Lesser Prairie Chicken
Ground-level Abandoned Well Marker
<b>⊠</b> Construction
Notification
Topsoil
Closed Loop System
Federal Mineral Material Pits
Well Pads
Roads
<b>⊠</b> Road Section Diagram
<b>☑</b> Drilling
Secretary's Potash
<b>☐</b> Production (Post Drilling)
Well Structures & Facilities
Pipelines
<b>◯</b> Closed Loop System/Interim Reclamation
Final Abandonment/Reclamation

#### I. GENERAL PROVISIONS

The approval of the Application For Permit To Drill (APD) is in compliance with all applicable laws and regulations: 43 Code of Federal Regulations 3160, the lease terms, Onshore Oil and Gas Orders, Notices To Lessees, New Mexico Oil Conservation Division (NMOCD) Rules, National Historical Preservation Act As Amended, and instructions and orders of the Authorized Officer. Any request for a variance shall be submitted to the Authorized Officer on Form 3160-5, Sundry Notices and Report on Wells.

#### II. PERMIT EXPIRATION

If the permit terminates prior to drilling and drilling cannot be commenced within 60 days after expiration, an operator is required to submit Form 3160-5, Sundry Notices and Reports on Wells, requesting surface reclamation requirements for any surface disturbance. However, if the operator will be able to initiate drilling within 60 days after the expiration of the permit, the operator must have set the conductor pipe in order to allow for an extension of 60 days beyond the expiration date of the APD. (Filing of a Sundry Notice is required for this 60 day extension.)

#### III. ARCHAEOLOGICAL, PALEONTOLOGY & HISTORICAL SITES

Any cultural and/or paleontological resource discovered by the operator or by any person working on the operator's behalf shall immediately report such findings to the Authorized Officer. The operator is fully accountable for the actions of their contractors and subcontractors. The operator shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery shall be made by the Authorized Officer to determine the appropriate actions that shall be required to prevent the loss of significant cultural or scientific values of the discovery. The operator shall be held responsible for the cost of the proper mitigation measures that the Authorized Officer assesses after consultation with the operator on the evaluation and decisions of the discovery. Any unauthorized collection or disturbance of cultural or paleontological resources may result in a shutdown order by the Authorized Officer.

#### IV. NOXIOUS WEEDS

The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes the roads, pads, associated pipeline corridor, and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

#### V. SPECIAL REQUIREMENT(S)

- 1. Timing Limitation Stipulation/Condition of Approval for Lesser Prairie-Chicken: Oil and gas activities including 3-D geophysical exploration, and drilling will not be allowed in lesser prairie-chicken habitat during the period from March 1st through June 15th annually. During that period, other activities that produce noise or involve human activity, such as the maintenance of oil and gas facilities, geophysical exploration other than 3-D operations, and pipeline, road, and well pad construction, will be allowed except between 3:00 am and 9:00 am. The 3:00 am to 9:00 am restriction will not apply to normal, around-the-clock operations, such as venting, flaring, or pumping, which do not require a human presence during this period. Additionally, no new drilling will be allowed within up to 200 meters of leks known at the time of permitting. Normal vehicle use on existing roads will not be restricted. Exhaust noise from pump jack engines must be muffled or otherwise controlled so as not to exceed 75 db measured at 30 ft. from the source of the noise.
- 2. Ground-level Abandoned Well Marker to avoid raptor perching: Upon the plugging and subsequent abandonment of the well, the well marker will be installed at ground level on a plate containing the pertinent information for the plugged well. For more installation details, contact the Carlsbad Field Office at 575-234-5972.

Southeast Lusk 27 Federal # 5: Closed loop System; V- Door East

#### VI. CONSTRUCTION

#### A. NOTIFICATION

The BLM shall administer compliance and monitor construction of the access road and well pad. Notify the Carlsbad Field Office at (575) 234-5972 at least 3 working days prior to commencing construction of the access road and/or well pad.

When construction operations are being conducted on this well, the operator shall have the approved APD and Conditions of Approval (COA) on the well site and they shall be made available upon request by the Authorized Officer.

#### B. TOPSOIL

The operator shall stockpile the topsoil of the well pad. The topsoil shall not be used to backfill the reserve pit and will be used for interim and final reclamation.

#### C. Closed Loop System

Southeast Lusk 27 Federal # 5: Closed loop System; V- Door East

Tanks are required for drilling operations: No Pits.

The operator shall properly dispose of drilling contents at an authorized disposal site.

#### D. FEDERAL MINERAL MATERIALS PIT

If the operator elects to surface the access road and/or well pad, mineral materials extracted during construction of the reserve pit may be used for surfacing the well pad and access road and other facilities on the lease.

Payment shall be made to the BLM prior to removal of any additional federal mineral materials from any site other than the reserve pit. Call the Carlsbad Field Office at (575) 234-5972.

#### E. WELL PAD SURFACING

Surfacing of the well pad is not required.

If the operator elects to surface the well pad, the surfacing material may be required to be removed at the time of reclamation.

The well pad shall be constructed in a manner which creates the smallest possible surface disturbance, consistent with safety and operational needs.

#### F. ON LEASE ACCESS ROADS

#### Road Width

The access road shall have a driving surface that creates the smallest possible surface disturbance and does not exceed fourteen (14) feet in width. The maximum width of surface disturbance, when constructing the access road, shall not exceed thirty (30) feet.

#### **Surfacing**

Surfacing material is not required on the new access road driving surface. If the operator elects to surface the new access road or pad, the surfacing material may be required to be removed at the time of reclamation.

Where possible, no improvements should be made on the unsurfaced access road other than to remove vegetation as necessary, road irregularities, safety issues, or to fill low areas that may sustain standing water.

The Authorized Officer reserves the right to require surfacing of any portion of the access road at any time deemed necessary. Surfacing may be required in the event the road deteriorates, erodes, road traffic increases, or it is determined to be beneficial for future field development. The surfacing depth and type of material will be determined at the time of notification.

#### Crowning

Crowning shall be done on the access road driving surface. The road crown shall have a grade of approximately 2% (i.e., a 1" crown on a 14' wide road). The road shall conform to Figure 1; cross section and plans for typical road construction.


#### Ditching

Ditching shall be required on both sides of the road.

#### **Turnouts**

Vehicle turnouts shall be constructed on the road. Turnouts shall be intervisible with interval spacing distance less than 1000 feet. Turnouts shall be constructed on all blind curves. Turnouts shall conform to the following diagram:

#### Standard Turnout - Plan View




#### Drainage

Drainage control systems shall be constructed on the entire length of road (e.g. ditches, sidehill outsloping and insloping, lead-off ditches, culvert installation, and low water crossings).

Page 5 of 18

A typical lead-off ditch has a minimum depth of 1 foot below and a berm of 6 inches above natural ground level. The berm shall be on the down-slope side of the lead-off ditch.

#### Cross Section of a Typical Lead-off Ditch



All lead-off ditches shall be graded to drain water with a 1 percent minimum to 3 percent maximum ditch slope. The spacing interval are variable for lead-off ditches and shall be determined according to the formula for spacing intervals of lead-off ditches, but may be amended depending upon existing soil types and centerline road slope (in %);

#### Formula for Spacing Interval of Lead-off Ditches

Example - On a 4% road slope that is 400 feet long, the water flow shall drain water into a lead-off ditch. Spacing interval shall be determined by the following formula:

400 foot road with 4% road slope: 
$$\frac{400'}{4\%}$$
 + 100' = 200' lead-off ditch interval

#### **Culvert Installations**

Appropriately sized culvert(s) shall be installed at the deep waterway channel flow crossing.

#### Cattleguards

An appropriately sized cattleguard(s) sufficient to carry out the project shall be installed and maintained at fence crossing(s).

Any existing cattleguard(s) on the access road shall be repaired or replaced if they are damaged or have deteriorated beyond practical use. The operator shall be responsible for the condition of the existing cattleguard(s) that are in place and are utilized during lease operations.

A gate shall be constructed and fastened securely to H-braces.

#### **Fence Requirement**


Where entry is required across a fence line, the fence shall be braced and tied off on both sides of the passageway prior to cutting.

The operator shall notify the private surface landowner or the grazing allotment holder prior to crossing any fence(s).

#### **Public Access**

Public access on this road shall not be restricted by the operator without specific written approval granted by the Authorized Officer.

Figure 1 - Cross Sections and Plans For Typical Road Sections



#### VII. DRILLING

#### A. DRILLING OPERATIONS REQUIREMENTS

The BLM is to be notified a minimum of 4 hours in advance for a representative to witness:

- a. Spudding well
- b. Setting and/or Cementing of all casing strings
- c. BOPE tests

#### **Lea County**

Call the Hobbs Field Station, 414 West Taylor, Hobbs NM 88240, (575) 393-3612

- 1. A Hydrogen Sulfide (H2S) Drilling Plan should be activated 500 feet prior to drilling into the Yates formation. If Hydrogen Sulfide is encountered, please report measurements and formations to the BLM.
- 2. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval.
- 3. When floor controls are required, (3M or Greater) controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works are located, this does not include the dog house or stairway area.

#### B. CASING

Changes to the approved APD casing and cement program require submitting a sundry and receiving approval prior to work. Failure to obtain approval prior to work will result in an Incident of Non-Compliance being issued.

Centralizers required on surface casing per Onshore Order 2.III.B.1.f.

Wait on cement (WOC) time for a primary cement job will be a minimum 18 hours for a water basin, 24 hours in the potash area, or 500 pounds compressive strength, whichever is greater for all casing strings. Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. See individual casing strings for details regarding lead cement slurry requirements.

No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.

Possible lost circulation in the Artesia Group and the Capitan Reef. Possible water flows in the Artesia and Salado Groups.

- 1. The 16 inch surface casing shall be set a minimum of 25 feet into the Rustler Anhydrite and above the salt at approximately 890 feet and cemented to the surface.
  - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with a surface log readout will be used or a cement bond log shall be run to verify the top of the cement.
  - b. Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry.
  - c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.
  - d. If cement falls back, remedial action will be done prior to drilling out that string.
- 2. The minimum required fill of cement behind the 10-3/4 inch intermediate casing is:
  - Cement to surface. If cement does not circulate see B.1.a, c-d above. Casing to be set at approximately 2850 feet within the Seven Rivers formation and above the Bowers Member. Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to Secretary's Potash.
- 3. The minimum required fill of cement behind the 7-5/8 inch intermediate casing is:
  - a. First stage to DV tool, cement shall:
  - □ Cement to circulate. If cement does not circulate, contact the appropriate BLM office, before proceeding with second stage cement job. Casing to be set at approximately 4300 feet at the base of the Goat Seep Reef. Additional cement may be needed as excess cement calculates to 14%.

External Casing Packer and DV tool are to be set a minimum of 50 feet above the 10-3/4" casing shoe.

- b. Second stage above DV tool, cement shall:
- Cement to surface. If cement does not circulate, contact the appropriate BLM office. Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to protection for Capitan Reef.
- 4. The minimum required fill of cement behind the 5-1/2 inch production easing is:
  - Cement to surface. If cement does not circulate, contact the appropriate BLM office. Additional cement will be required to circulate as excess calculated to a negative 8%.
- 5. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.

#### C. PRESSURE CONTROL

- 1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in Onshore Oil and Gas Order No. 2 and API RP 53 Sec. 17.
- 2. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.
  - a. The tests shall be done by an independent service company.
  - b. The results of the test shall be reported to the appropriate BLM office.
  - c. All tests are required to be recorded on a calibrated test chart. A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.
  - d. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug.

#### D. DRILL STEM TEST

If drill stem tests are performed, Onshore Order 2.III.D shall be followed.

WWI 111708

#### VIII. PRODUCTION (POST DRILLING)

#### A. WELL STRUCTURES & FACILITIES

#### **Placement of Production Facilities**

Production facilities should be placed on the well pad to allow for maximum interim recontouring and revegetation of the well location.

#### **Containment Structures**

The containment structure shall be constructed to hold the capacity of the entire contents of the largest tank, plus 24 hour production, unless more stringent protective requirements are deemed necessary by the Authorized Officer.

#### **Painting Requirement**

All above-ground structures including meter housing that are not subject to safety requirements shall be painted a flat non-reflective paint color Shale Green, Munsell Soil Color Chart # 5Y 4/2

#### B. PIPELINES

BLM Serial Number: Company Reference: Well # & Name:

#### STANDARD STIPULATIONS FOR SURFACE INSTALLED PIPELINES

A copy of the APD and attachments, including stipulations, survey plat and/or map, will be on location during construction. BLM personnel may request to you a copy of your permit during construction to ensure compliance with all stipulations.

Holder agrees to comply with the following stipulations to the satisfaction of the Authorized Officer:

- 1. The holder shall indemnify the United States against any liability for damage to life or property arising from the occupancy or use of public lands under this grant.
- 2. The holder shall comply with all applicable Federal laws and regulations existing or hereafter enacted or promulgated. In any event, the holder shall comply with the Toxic Substances Control Act of 1976 as amended, 15 USC 2601 et seq. (1982) with regards to any toxic substances that are used, generated by or stored on the right-of-way or on facilities authorized under this right-of-way grant. (See 40 CFR, Part 702-799 and especially, provisions on polychlorinated biphenyls, 40 CFR 761.1-761.193.) Additionally, any release of toxic substances (leaks, spills, etc.) in excess of the reportable quantity established by 40 CFR, Part 117 shall be reported as required by the Comprehensive Environmental Response, Compensation, and Liability Act, section 102b. A copy of any report required or requested by any Federal agency or State government as a result of a reportable release or spill of any toxic substances shall be furnished to the

authorized officer concurrent with the filing of the reports to the involved Federal agency or State government.

- 3. The holder agrees to indemnify the United States against any liability arising from the release of any hazardous substance or hazardous waste (as these terms are defined in the Comprehensive Environmental Response, Compensation and Liability Act of 1980, 42 U.S.C. 9601, et seq. or the Resource Conservation and Recovery Act, 42 U.S.C. 6901, et seq.) on the Right-of-Way (unless the release or threatened release is wholly unrelated to activity of the Right-of-Way holder's activity on the Right-of-Way), or resulting from the activity of the Right-of-Way holder on the Right-of-Way. This agreement applies without regard to whether a release is caused by the holder, its agent, or unrelated third parties.
- 4. The holder shall be liable for damage or injury to the United States to the extent provided by 43 CFR Sec. 2883.1-4. The holder shall be held to a standard of strict liability for damage or injury to the United States resulting from pipe rupture, fire, or spills caused or substantially aggravated by any of the following within the right-of-way or permit area:
- a. Activities of the holder including, but not limited to construction, operation, maintenance, and termination of the facility.
- b. Activities of other parties including, but not limited to:
  - (1) Land clearing.
  - (2) Earth-disturbing and earth-moving work.
  - (3) Blasting.
  - (4) Vandalism and sabotage.
- c. Acts of God.

The maximum limitation for such strict liability damages shall not exceed one million dollars (\$1,000,000) for any one event, and any liability in excess of such amount shall be determined by the ordinary rules of negligence of the jurisdiction in which the damage or injury occurred.

This section shall not impose strict liability for damage or injury resulting primarily from an act of war or from the negligent acts or omissions of the United States.

5. If, during any phase of the construction, operation, maintenance, or termination of the pipeline, any oil, salt water, or other pollutant should be discharged from the pipeline system, impacting Federal lands, the control and total removal, disposal, and cleaning up of such oil, salt water, or other pollutant, wherever found, shall be the responsibility of the holder, regardless of fault. Upon failure of the holder to control, dispose of, or clean up such discharge on or affecting Federal lands, or to repair all damages resulting therefrom, on the Federal lands, the Authorized Officer may take such measures as he

deems necessary to control and clean up the discharge and restore the area, including, where appropriate, the aquatic environment and fish and wildlife habitats, at the full expense of the holder. Such action by the Authorized Officer shall not relieve the holder of any responsibility as provided herein.

6.	All construction	n and ma	aintenance activity	will be	confined to	the authorized	right-of-
wa	y width of	25	feet.				

- 7. No blading or clearing of any vegetation will be allowed unless approved in writing by the Authorized Officer.
- 8. The holder shall install the pipeline on the surface in such a manner that will minimize suspension of the pipeline across low areas in the terrain. In hummocky of duney areas, the pipeline will be "snaked" around hummocks and dunes rather then suspended across these features.
- 9. The pipeline shall be buried with a minimum of 24 inches under all roads, "two-tracks," and trails. Burial of the pipe will continue for 20 feet on each side of each crossing. The condition of the road, upon completion of construction, shall be returned to at least its former state with no bumps or dips remaining in the road surface.
- 10. The holder shall minimize disturbance to existing fences and other improvements on public lands. The holder is required to promptly repair improvements to at least their former state. Functional use of these improvements will be maintained at all times. The holder will contact the owner of any improvements prior to disturbing them. When necessary to pass through a fence line, the fence shall be braced on both sides of the passageway prior to cutting of the fence. No permanent gates will be allowed unless approved by the Authorized Officer.
- 11. In those areas where erosion control structures are required to stabilize soil conditions, the holder will install such structures as are suitable for the specific soil conditions being encountered and which are in accordance with sound resource management practices.
- 12. Excluding the pipe, all above-ground structures not subject to safety requirement shall be painted by the holder to blend with the natural color of the landscape. The paint used shall be a color which simulates "Standard Environmental Colors" **Shale Green**, Munsell Soil Color No. 5Y 4/2; designated by the Rocky Mountain Five State Interagency Committee.
- 13. The pipeline will be identified by signs at the point of origin and completion of the right-of-way and at all road crossings. At a minimum, signs will state the holder's name, BLM serial number, and the product being transported. Signs will be maintained in a legible condition for the life of the pipeline.
- 14. The holder shall not use the pipeline route as a road for purposes other than routine

maintenance as determined necessary by the Authorized Officer in consultation with the holder. The holder will take whatever steps are necessary to ensure that the pipeline route is not used as a roadway.

15. Any cultural and/or paleontological resource (historic or prehistoric site or object) discovered by the holder, or any person working on his hehalf, on public or Federal land shall be immediately reported to the authorized officer. Holder shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the authorized officer. An evaluation of the discovery will be made by the authorized officer to determine appropriate cultural or scientific values. The holder will be responsible for the cost of evaluation and any decision as to proper mitigation measures will be made by the authorized officer after consulting with the holder.

(March 1989)

#### IX. INTERIM RECLAMATION & RESERVE PIT CLOSURE

#### A. INTERIM RECLAMATION

If the well is a producer, interim reclamation shall be conducted on the well site in accordance with the orders of the Authorized Officer. The operator shall submit a Sundry Notices and Reports on Wells (Notice of Intent), Form 3160-5, prior to conducting interim reclamation.

During the life of the development, all disturbed areas not needed for active support of production operations should undergo interim reclamation in order to minimize the environmental impacts of development on other resources and uses.

The operators should work with BLM surface management specialists to devise the best strategies to reduce the size of the location. Any reductions should allow for remedial well operations, as well as safe and efficient removal of oil and gas.

During reclamation, the removal of caliche is important to increasing the success of revegetating the site. Removed caliche may be used for road repairs, fire walls or for building other roads and locations. In order to operate the well or complete workover operations, it may be necessary to drive, park and operate on restored interim vegetation within the previously disturbed area. Disturbing revegetated areas for production or workover operations will be allowed. If there is significant disturbance and loss of vegetation, the area will need to be revegetated. Communicate with the appropriate BLM office for any exceptions/exemptions if needed.

#### BLM Serial #: Company Reference: Well Name and Number:

#### Seed Mixture for LPC Sand/Shinnery Sites

The holder shall seed all disturbed areas with the seed mixture listed below. The seed mixture shall be planted in the amounts specified in pounds of pure live seed (PLS)\* per acre. There shall be <u>no</u> primary or secondary noxious weeds in the seed mixture. Seed will be tested and the viability testing of seed will be done in accordance with State law(s) and within nine (9) months prior to purchase. Commercial seed will be either certified or registered seed. The seed container will be tagged in accordance with State law(s) and available for inspection by the authorized officer.

Seed will be planted using a drill equipped with a depth regulator to ensure proper depth of planting where drilling is possible. The seed mixture will be evenly and uniformly planted over the disturbed area (smaller/heavier seeds have a tendency to drop the bottom of the drill and are planted first). The holder shall take appropriate measures to ensure this does not occur. Where drilling is not possible, seed will be broadcast and the area shall be raked or chained to cover the seed. When broadcasting the seed, the pounds per acre are to be doubled. The seeding will be repeated until a satisfactory stand is established as determined by the authorized officer. Evaluation of growth will not be made before completion of at least one full growing season after seeding.

Species to be planted in pounds of pure live seed\* per acre:

<u>Species</u>	<u>lb/acre</u>
Plains Bristlegrass	5lbs/A
Sand Bluestem	5lbs/A
Little Bluestem	3lbs/A
Big Bluestem	6lbs/A
Plains Coreopsis	2lbs/A
Sand Dropseed	1lbs/A

<sup>\*\*</sup>Four-winged Saltbush

5lbs/A

Pounds of seed x percent purity x percent germination = pounds pure live seed (Insert Seed Mixture Here)

<sup>\*</sup> This can be used around well pads and other areas where caliche cannot be removed.

<sup>\*</sup>Pounds of pure live seed:

### X. FINAL ABANDONMENT & REHABILITATION REQUIREMENTS

Upon abandonment of the well and/or when the access road is no longer in service the Authorized Officer shall issue instructions and/or orders for surface reclamation and restoration of all disturbed areas.

On private surface/federal mineral estate land the reclamation procedures on the road and well pad shall be accomplished in accordance with the private surface land owner agreement.